

TIGHT BINDING BOOK

UNIVERSAL
LIBRARY

OU_160759

UNIVERSAL
LIBRARY

McGRAW-HILL PUBLICATIONS IN THE
AGRICULTURAL AND BOTANICAL SCIENCES

EDMUND W. SINNOTT, CONSULTING EDITOR

PLANT PHYSIOLOGY

McGRAW-HILL PUBLICATIONS IN THE AGRICULTURAL AND BOTANICAL SCIENCES

EDMUND W. SINNOTT, CONSULTING EDITOR

- Adams*—Farm Management
- Babcock and Clausen*—Genetics in Relation to Agriculture
- Babcock and Collins*—Genetics Laboratory Manual
- Bellamy*—The Use of the Microscope
- Boyle*—Marketing of Agricultural Products
- Braun-Blanquet and Fuller and Conard*—Plant Sociology
- Brown*—Cotton
- Carrier*—Beginnings of Agriculture in America
- Cruess*—Commercial Fruit and Vegetable Products
- Cruess and Christie*—Laboratory Manual of Fruit and Vegetable Products
- Eames and MacDaniels*—Introduction to Plant Anatomy
- Eckles, Combs and Macy*—Milk and Milk Products
- Emerson*—Soil Characteristics
- Fawcett and Lee*—Citrus Diseases and Their Control
- Fitzpatrick*—The Lower Fungi—Phycomycetes
- Gardner, Bradford and Hooker*—Fundamentals of Fruit Production
- Gardner, Bradford and Hooker*—Orcharding
- Gäumann and Dodge*—Comparative Morphology of Fungi
- Hayes and Garber*—Breeding Crop Plants
- Heald*—Manual of Plant Diseases
- Horlacher*—Sheep Production
- Hutcheson and Wolfe*—Production of Field Crops
- Jones and Rosa*—Truck Crop Plants
- Loeb*—Regeneration
- Lohnis and Fred*—Textbook of Agricultural Bacteriology
- Lutman*—Microbiology
- Mazimon*—A Textbook of Plant Physiology
- Müller*—Plant Physiology
- Piper and Morse*—The Soybean
- Pool*—Flowers and Flowering Plants
- Rice*—The Breeding and Improvement of Farm Animals
- Sharp*—Introduction to Cytology
- Sinnott*—Botany: Principles and Problems
- Sinnott*—Laboratory Manual for Elementary Botany
- Sinnott and Dunn*—Principles of Genetics
- Swingle*—A Textbook of Systematic Botany
- Thatcher*—The Chemistry of Plant Life
- Thompson*—Vegetable Crops
- Waite*—Poultry Science and Practice
- Weaver*—Root Development of Field Crops
- Weaver and Bruner*—Root Development of Vegetable Crops
- Weaver and Clements*—Plant Ecology

There is also a series of McGraw-Hill Publications in the Zoological Sciences, of which A. Franklin Shull is Consulting Editor.

PLANT PHYSIOLOGY

With reference to the green plant

BY

EDWIN C. MILLER, PH. D.

*Professor of Plant Physiology, Kansas State Agricultural College, and
Plant Physiologist, Kansas Agricultural Experiment Station*

FIRST EDITION
SECOND IMPRESSION

McGRAW-HILL BOOK COMPANY, Inc.

NEW YORK AND LONDON

1931

COPYRIGHT, 1931, BY THE
MCGRAW-HILL BOOK COMPANY, INC.

PRINTED IN THE UNITED STATES OF AMERICA

*All rights reserved. This book, or
parts thereof, may not be reproduced
in any form without permission of
the publishers.*

THE MAPLE PRESS COMPANY, YORK, PA.

To my wife

DELLA SLYE MILLER

PREFACE

There has existed for some time a need for an advanced text in plant physiology. The various texts by European investigators and teachers, while summarizing the work that has been done on the continent, have failed to cover adequately the contributions of American and English plant physiologists. These contributions during the past two decades have been outstanding and dominate in many cases the work along certain lines. A summary of these contributions should be available to students, teachers, and investigators in the field of plant physiology.

It has been the intention of the author to bridge this gap in the literature and to summarize in this book the more important findings of English, American, and continental plant physiologists. The material has been assembled in such form as to be available as a text for upper classmen and graduate students and at the same time to be sufficiently comprehensive as a reference book for investigators in plant physiology.

The work has been confined entirely to the physiology of the green plant as it has been thought that the processes and phenomena of the fungi belong at present at least to the province of plant pathology and allied fields. The discussions and summaries of the various investigators have been used freely and in many cases their phraseology has been altered but little. The author has tried, however, in each instance to indicate the source of the information presented. Some topics are discussed more thoroughly than others. This, however, is to be expected as an author naturally is more familiar with those subjects which are in the field of his research.

With but few exceptions the references cited at the end of each chapter have been mentioned or discussed in the text. It is considered that these references will be of value to those who desire to familiarize themselves more thoroughly with any of the topics than they are herein discussed. The questions following each chapter cover all the topics discussed in that portion of the text. It has been the experience of the author that these are valuable to the student as an aid in guiding him to a mastery of the subject matter.

This text is the outgrowth of twenty years' experience as a teacher of plant physiology in the Kansas State Agricultural College and as plant physiologist of the Kansas Agricultural Experiment Station. The material included herein has been presented to classes composed for the most part of juniors, seniors, and graduate students. The favorable manner in which the subject matter and its method of presentation have

been received in the classroom has prompted the author to present this volume to the public.

I am indebted to many of my associates for assistance in the preparation of this text. Most of the drawings were made by Mr. S. Fred Prince, formerly biological artist at the Kansas State Agricultural College. I am indebted to Miss Nora E. Dalbey, associate professor of botany in the Kansas State Agricultural College, for certain drawings and for helpful suggestions in the arrangement of the illustrations. I wish to thank Dr. Frank M. Schertz of the U. S. Bureau of Chemistry and Soils, Dr. John W. Shive of the New Jersey Agricultural Experiment Station, Dr. W. E. Tottingham of the University of Wisconsin, Dr. F. F. Blackman of Botany School, Cambridge, England, and Professor W. E. Davis of the Kansas State Agricultural College for permission to use certain figures as indicated in the text.

I am grateful to Mr. J. C. Frazier, formerly of the Department of Botany and Plant Pathology, Kansas State Agricultural College, for helpful advice in the preparation of the manuscript and to Dr. R. P. White, formerly of the same department, for criticism and advice in the preparation of Chap. II. I wish to thank Dr. J. V. Cortelyou, professor of modern languages at Kansas State Agricultural College, and Miss Madge Wardell, instructor in French at the same institution, for checking respectively the German and French references. I wish also to acknowledge the most valuable aid and advice of Miss Nellie Jacobs, clerk in the Department of Botany and Plant Pathology, Kansas State Agricultural College, in the preparation of the manuscript.

I am especially indebted to the following of my colleagues in the Kansas State Agricultural College for their constructive criticism in the preparation of the text: S. C. Salmon, professor of farm crops; Dr. P. L. Gainey, professor of bacteriology; R. J. Barnett, professor of horticulture; Dr. H. H. Haymaker, professor of plant pathology; W. E. Davis, professor of plant physiology; Dr. F. C. Gates, professor of taxonomy and ecology; Dr. F. L. Duley, professor of soils; Dr. C. W. Colver, professor of organic chemistry; and Dr. E. L. Tague, associate professor of chemistry. The author alone, however, is responsible for the statements in the text.

EDWIN C. MILLER.

KANSAS STATE AGRICULTURAL COLLEGE,
March, 1931.

CONTENTS

	PAGE
PREFACE	vii

CHAPTER I

THE PLANT CELL	1
I. The cell wall	1
A. Origin	1
B. General physical and chemical properties	4
C. Chemical composition	5
1. Normal, typical or true celluloses	5
2. Hydrocelluloses and oxycelluloses	6
3. Hemicelluloses	7
4. Compound celluloses	8
5. Suberin and cutin	9
6. Pectic substances	17
a. Pectose	13
b. Pectin	14
c. Pectic acid	14
7. Other constituents of the cell wall	15
II. The protoplasm	15
A. The cytoplasm	18
B. The nucleus	1
C. The plastids	20
1. The chloroplasts	20
2. The chromoplasts	21
3. The leucoplasts	21
4. The origin of the plastids	22
D. The mitochondria or chondriosomes	24
III. The vacuole or cell sap	25
A. Formation	25
B. Composition	26
C. Concentration	27
1. Factors that influence the concentration of the cell sap	28
a. The habitat of the plant	28
b. The kind of plant	30
c. The portion of the plant	31
d. The age of the tissues	33
e. The time of sampling	33
2. Cell-sap concentration and growth	34
D. The acidity of the cell sap	34
1. Actual and total acidity	34
2. The relation of the environmental conditions to the acidity of the sap	34

CONTENTS

	PAGE
3. General observations	38
Questions	39
Bibliography	41

CHAPTER II

SOLUTIONS AND MEMBRANES IN RELATION TO THE PLANT CELL	50
I. Solutions	50
A. The nature	50
B. Concentration	51
C. Diffusion	52
II. Membranes	54
A. Nature	54
B. <u>Imbibition of water</u>	55
C. <u>Diffusion</u>	56
D. The membranes of the plant cell	59
1. The cell-wall or non-living membrane	59
a. Permeability to water	59
b. Permeability to solutes	62
2. The protoplasmic, cytoplasmic, or living membrane	65
a. Nature	65
b. Permeability	67
1. Osmotic relationships of the plant cell	68
(a) Osmotic concentration of the cell sap	68
(b) Osmotic concentration of the external solution	68
(c) The turgor pressure of the cell	71
(d) The suction pressure, suction force, absorbing power, or suction tension of the cell	72
2. <u>Permeability</u> and absorption	73
3. Methods of measuring the permeability of the protoplasmic membrane to solutes	74
(a) Indirect methods	74
(1) By chemical analysis	74
(2) By visible changes within the cell	75
(3) By plasmolytic methods	75
a) The determination of concentration necessary to produce plasmolysis	75
b) The determination of the time required to recover from plasmolysis	76
(4) By electrical conductivity of tissues or masses of cells	76
(5) By the diffusion method	77
(b) Direct methods	77
4. Methods of measuring the permeability of the protoplasmic membrane to water	78
5. Factors that may influence the permeability of the protoplasmic membrane	79
(a) Temperature	79
(1) Influence on the permeability of the protoplasmic membrane to water	79
(2) Influence on the permeability of the protoplasmic membrane to solutes	80

	PAGE
(b) Light	82
(c) The nature of the solutes	82
<i>E.</i> Theories of Membrane Action	85
1. The sieve theory	85
2. The solution theory	85
3. The chemical theory	86
4. Colloidal theories	88
Questions	89
Bibliography	91

CHAPTER III

THE ROOTS OF PLANTS	97
I. Influence of environment on roots	97
A. Influence of soil moisture on root development	97
1. Direction of root growth	97
2. Relative weight of roots and tops	98
B. Soil nutrients and root development	98
1. Direction of root growth	99
2. Number of roots	101
3. Relative weight of roots and tops	102
C. Oxygen supply and root development	103
D. Soil temperature and the response of roots	108
E. Soil texture and root development	109
F. The response of roots to light	110
II. The extent of root systems	110
A. Total number and combined length of roots	110
B. Extent of roots in the soil	110
1. Vertical penetration	112
2. Lateral extent	115
3. The depth to which roots absorb water and nutrients	116
III. Root hairs	118
A. Growth	119
B. Conditions that affect the formation of root hairs	122
C. The cell wall of root hairs	123
IV. Excretions of roots	124
A. Acids—carbonic acid	125
1. Relative amounts	125
2. Solvent action	126
B. Enzymes	128
C. Beneficial or toxic substances	129
1. The beneficial influence of one plant on another	129
2. The deleterious influence of one plant on another	130
a. The influence of the depletion of the nutrients in the soil on plant growth	132
b. The influence of the decomposition of roots in the soil on plant growth	133
c. The influence of the secretion of toxic substances by the roots of growing plants on plant growth	136

	PAGE
V. The weight of roots	138
Questions	138
Bibliography	141

CHAPTER IV

THE INTAKE OF WATER BY PLANTS	150
I. Sources of the plant's water supply	150
II. Wilting coefficient	152
A. Methods of determining the wilting coefficient	152
1. Direct method. The observed wilting coefficient	152
2. Indirect method	152
a. The calculated wilting coefficient	152
1. Relation to the moisture equivalent of the soil	153
2. Relation to the hygroscopic coefficient of the soil	153
3. Relation to the moisture-holding capacity of the soil	153
b. The index of transpiring power as an indicator of permanent wilting in plants	153
B. Factors influencing the wilting coefficient	154
1. Type of soil	154
2. The climatic conditions	154
3. Kind of plant	157
C. The water-supplying power of the soil at the time of wilting	160
III. Entrance of water into the root	164
A. The structure of the root	164
B. Modes of water entrance into the roots	166
1. Imbibition	166
2. Osmotic forces	167
3. Passive absorption	169
Questions	170
Bibliography	171

CHAPTER V

THE INTAKE OF SOLUTES BY THE PLANT	174
I. Mode of entrance of solutes	174
A. Passive or physical absorption	175
B. Active or physiological absorption	176
II. Factors that affect the absorption ratio	179
A. Light	179
B. Concentration of the exterior medium	180
III. The unequal absorption of ions	182
A. Mechanism	183
B. Reaction of the exterior solution	184
C. Interchange of ions from the plant to the exterior solution	186
D. Factors that influence the unequal absorption of ions	187
1. Concentration of the external solution	187
2. The influence of one ion upon another	188
3. Other factors	189
IV. Transpiration and the intake of salts	190

	PAGE
V. Nutrient solutions	193
A. Historical	194
B. Kinds	194
C. Technique	197
1. Renewal	198
2. Aeration	199
3. Preparation	200
4. The triangle system in the studies of nutrient solutions, sand cultures, and fertilizer experiments	203
D. Factors that may determine the relative value of nutrient solutions	206
1. Temperature and light	206
2. Concentration	207
3. Water <i>vs.</i> sand cultures	209
4. Physiological balance	209
✓ E. The hydrogen-ion relations in nutrient solutions	212
F. Criticism of the data of plant nutrition	216
VI. Antagonism and balanced solutions	218
Questions	221
Bibliography	223

CHAPTER VI

THE ELEMENTS ABSORBED BY THE PLANT	232
I. Number and kind	232
A. Influence of the plant	233
B. Influence of the elements of the soil	236
C. Distribution of the elements in the plant	238
II. Form	239
A. Inorganic compounds	239
B. Organic compounds	239
1. Carbohydrates	239
2. Organic acids	241
3. Organic nitrogenous compounds	242
III. Essential <i>vs.</i> unessential elements	242
IV. Occurrence and function	244
A. Carbon, hydrogen, oxygen, and nitrogen	244
✓ B. Phosphorus	244
1. Occurrence	244
2. Form	245
3. Physiological rôle	246
✓ C. Calcium	247
1. Occurrence	247
2. Function	247
a. Influence on the translocation of carbohydrates	248
b. As a component of plant structures and compounds and influence on the physiological availability of other ions	248
c. As an antidoting agent	251
3. General responses of plants to calcium	251
D. Magnesium	252

	PAGE
<i>E.</i> Potassium	254
1. Occurrence	254
2. Physiological rôle	255
<i>a.</i> Use in food manufacture	255
<i>b.</i> As a catalyst	256
3. General response of plants to potassium	256
<i>F.</i> Sulphur	257
1. Occurrence	257
2. Physiological rôle	258
3. Formative effects	259
4. As a fertilizer	259
<i>G.</i> Iron	260
1. Occurrence	260
2. Physiological rôle	261
3. Form and amount necessary for plant growth	261
4. Relation to hydrogen-ion concentration	264
5. Absorption from the soil	265
6. Immobility within the plant	265
<i>H.</i> Silicon	266
1. Occurrence	266
2. Physiological rôle	266
<i>I.</i> Boron	269
1. Occurrence	269
2. Influence	269
<i>J.</i> Manganese	272
1. Occurrence	272
2. Need	273
3. As a fertilizer	274
4. Physiological rôle	275
<i>K.</i> Chlorine: Its occurrence, function, and value as a fertilizer to the plant	276
<i>L.</i> Aluminum	279
1. Occurrence	279
2. Influence upon plant life	280
<i>a.</i> Growth and production	280
<i>b.</i> Relationship of the soil to the plant	280
<i>c.</i> Function in the cell	281
<i>M.</i> Sodium	282
<i>N.</i> Other elements	283
<i>V.</i> The elemental requirements and the age of the plant	284
Questions	289
Bibliography	292

CHAPTER VII

THE LOSS OF WATER FROM PLANTS	308
I. The general need of water by plants	308
II. The evaporation of water from plants. Transpiration	311
A. Transpiration during the day and night	311
B. Amount of water lost	312

	Page
C. Factors that influence the rate of transpiration	313
1. Leaf structure	313
a. <u>The stomata</u>	317
1. Number	318
2. Opening and closing	323
(a) The physiology of the guard cells	324
(1) Osmotic relations of the guard cells	325
(2) Changes in the cell contents	326
(b) Methods of measuring the changes of stomatal apertures	328
(c) Factors influencing opening and closing	329
(d) Daily movement	330
3. Capacity for the diffusion of gases	332
(a) The stomata as paths of gaseous exchange	332
(b) Diffusion of gases through small openings	333
(c) The stomata in relation to such diffusion	336
4. Regulation or control of water loss	337
(a) Stomatal movement and the water content of the leaf	338
(b) Number of stomata and transpiration	339
(c) Changes in stomatal openings	341
b. Hairy coverings	342
c. General structure and composition of the leaf	344
2. Incipient drying or incipient wilting	346
a. Leaf surface of the plant	348
b. Nature of the root system	349
3. Aerial and meteorological conditions	350
a. Evaporating power of solar radiation	350
b. Evaporating power of the air	352
1. Temperature	352
2. Relative humidity	353
3. Wind	353
4. Water content of the soil	354
5. Chemicals	356
a. Chemicals applied to the soil	357
b. Films from sprays	358
6. Fungous diseases	361
D. Temperature of the leaves	362
1. Methods of measuring	363
2. Temperature	364
a. Fluctuations in temperature of the air	364
b. Temperature of normal turgid leaves	365
c. Rate of transpiration and the temperature of the leaf	368
d. The thermal death point	370
E. Evaporation	370
1. Measurement	371
a. Value of data	371
b. Instruments for measuring evaporation	371
1. Atmometers with a free water surface	372
2. Atmometers with a moist porous surface	373
2. The ratio of transpiration to evaporation	374
F. Methods of measuring transpiration	376
1. The potometer	377
2. The weighing method	377

	PAGE
3. The cobalt chloride method	378
4. The Freeman method	380
G. The significance of transpiration	382
H. The water requirement of plants	383
1. Methods of determining	384
2. Factors affecting the water requirement	385
a. Climatic conditions	385
b. Soil fertility	386
c. Soil moisture	388
III. The loss of water from plants in the liquid form. Guttation	388
Questions	390
Bibliography	394

CHAPTER VIII

THE FORMATION OF CARBOHYDRATES BY THE GREEN PLANT	404
I. The synthetic power of the green plant	404
II. The carbohydrates of the green plant	404
A. The sugars	406
1. Physical and chemical reactions	406
a. Specific rotatory power	406
b. Reducing action	406
c. Formation of hydrazones and osazones	407
2. Kinds or types	407
a. The monosaccharoses	407
1. The pentoses	408
2. The hexoses	408
(a) Glucose, dextrose, or grape sugar	408
(b) Fructose, levulose, or fruit sugar	409
(c) Mannose	409
(d) Galactose	409
b. The disaccharoses	410
1. Sucrose, saccharose, or cane sugar	410
2. Maltose, or malt sugar	411
3. Other disaccharoses	411
c. The trisaccharoses	411
B. The non-sugars or polysaccharoses	411
1. The celluloses	412
2. The amyloses or starches	412
a. Starch or amyllum	412
1. The starch grain	413
2. General properties	417
b. Dextrins	419
c. Inulin	419
3. Mannosans and galactans	419
4. Pentosans	420
III. Photosynthesis	420
A. Nature	420
B. Pigments of the chloroplasts	421

CONTENTS

xvii

	PAGE
1. The chlorophyll pigments. Chlorophyll components <i>a</i> and <i>b</i>	422
<i>a</i> . The chemistry of chlorophyll.	422
× <i>b</i> . Optical properties.	423
× <i>c</i> . The state of chlorophyll in the chloroplasts.	425
<i>d</i> . Formation	426
✓ 2. The carotinoids	428
<i>a</i> . Carotin	428
<i>b</i> . Xanthophyll	428
<i>c</i> . Fucoxanthin	429
C. Historical.	429
D. Products	430
✓ 1. The evolution of oxygen	430
✓ 2. The production of carbohydrates in the leaf.	431
✓ <i>a</i> . Early observations	431
✓ <i>b</i> . Daily variations of the carbohydrates in the leaves	435
✓ <i>c</i> . Variations in different portions of the leaf	438
✓ <i>d</i> . The first sugar formed.	439
E. Chemistry.	441
1. The function of chlorophyll.	441
✓ 2. The absorption of carbon dioxide by the leaf	443
✓ 3. Theories concerning photosynthesis	444
✓ 4. Experimental evidence	445
✓ <i>a</i> . The reduction of carbon dioxide.	445
✓ <i>b</i> . The condensation of formaldehyde to sugar.	448
✓ <i>c</i> . The detection of intermediate products in the leaves.	449
<i>d</i> . Nutrition experiments with organic compounds.	450
<u>F</u> Factors which affect photosynthesis.	451
1. The carbon dioxide supply	453
<i>a</i> . Amount in the air.	453
<i>b</i> . Amount used by the plant	454
<i>c</i> . Concentration and the rate of photosynthesis.	455
<i>d</i> . Application in agricultural practice	458
✓ 2. Supply of light	459
✓ <i>a</i> . Intensity.	459
✓ <i>b</i> . Wave lengths of light	460
✓ 3. Temperature	463
✓ <i>a</i> . Coefficient	463
✓ <i>b</i> . Range.	463
✓ 4. Amount of chlorophyll	465
✓ <i>a</i> . Plants of different habitats and of different varieties.	465
✓ <i>b</i> . Etiolated plants.	466
✓ 5. Water supply	467
✓ 6. Protoplasmic factors.	468
G. The energy relations of photosynthesis	471
1. Methods of determining the rate of photosynthesis.	471
<i>a</i> . Liberation of oxygen.	472
1. The use of bacteria.	472
2. The use of oxygen-absorbing compounds.	472
3. Bubble counting	472
4. Gas-analytical methods	472
<i>b</i> . Absorption of carbon dioxide.	473
<i>c</i> . Increase in organic matter	473

	PAGE
1. Qualitative methods	473
2. Quantitative methods	474
(a) Weighing	474
(b) Saccharification	475
2. The rate of photosynthesis	475
3. The total incident radiation	476
4. The coefficient of absorption of radiant energy for leaves	477
5. The utilization of solar energy in the leaves	478
a. Determination of the energy used in photosynthesis	479
b. The energy used in photosynthesis	479
6. The economic importance of photosynthesis	481
Questions	482
Bibliography	487

CHAPTER IX

<u>THE NITROGEN METABOLISM OF THE GREEN PLANT</u>	500
I. Occurrence of nitrogen in the plant	500
II. Sources of nitrogen supply of plant	500
A. Absorption from the soil. <i>Dr</i>	501
1. Inorganic nitrogen	501
2. Organic nitrogen	503
B. Absorption from the air	506
1. Historical	506
2. Non-leguminous plants	507
a. The algae	508
b. The higher non-leguminous plants	508
III. The proteins of the green plant	509
A. Physical properties	511
B. Chemical properties	511
1. The amino acids	512
2. Qualitative reactions of the proteins	513
a. Precipitation	514
b. Color	514
3. Amphoteric nature of the proteins	515
C. Classification of plant proteins	516
1. Simple proteins	517
a. Albumins	517
b. Globulins	518
c. Glutelins	518
d. Prolamins	518
2. Conjugated proteins	518
3. Derived proteins	519
D. Synthesis of proteins by the green plant	520
1. Reduction of nitrates in the plant	520
a. Occurrence	521
b. Conditions under which nitrates are reduced	522
c. Nitrate-reducing substances	523
2. Protein metabolism of the green leaf	524
a. Extraction of proteins	524
1. Previous history of tissue and nature of nitrogenous extract	525

CONTENTS

xix

	PAGE
2. Separation of the proteins of the cell	526
b. Diurnal variation of the nitrogen in the leaves	527
1. Methods of determining	527
2. Total nitrogen of the leaves	528
3. Nitrogenous compounds of the leaves	531
c. Formation of protein in the leaves	532
3. Light and protein synthesis	533
4. Formation of protein in seeds	534
5. Factors which influence the percentage of protein in grains	537
a. Time of application of nitrogen	537
b. Soil moisture	538
6. Yellow berry in hard winter wheats	539
IV. Nitrogen bases in plants	540
A. Plant amines or natural bases	540
B. Alkaloids	541
C. The purine bases	541
V. Loss of nitrogen from plants	542
VI. Carbon/nitrogen ratio	543
A. Fruit-bud formation	545
B. Length of day	546
C. Different stages of growth	547
D. Variations of ratio in different organs of the plant	548
E. Effect on root and shoot growth	548
F. Significance in agricultural practice	550
Questions	551
Bibliography	552

CHAPTER X

FAT METABOLISM OF THE GREEN PLANT	564
I. Fatty substances in plants. Crude lipides	564
A. Lipides	564
1. Composition	565
a. Fatty acids	565
1. Saturated	566
2. Unsaturated	567
b. Glycerol and other alcohols	568
2. Classification	568
a. Simple	568
1. Fats and fatty oils	568
(a) Physical properties	568
(b) Chemical properties	568
(1) Hydrolysis	569
(2) Saponification	569
(3) Drying of oils	569
a) Non-drying	569
b) Drying	570
c) Semidrying	571

	PAGE
(4) Values for determining the character of fats and oils	572
a) Acid value	572
b) Hehner value	572
c) Saponification value	572
d) Iodine value	573
e) Acetyl value	573
2. The waxes	573
b. Compound lipides	574
1. Phospholipides	574
(a) Lecithin	574
(b) Kephalin	574
2. Galactolipides	575
c. Derived lipides	575
3. Distribution in the plant cell	575
4. Occurrence of fats and fatty oils in the plant	577
5. Occurrence of compound lipides in the plant	578
a. Distribution	579
b. Relation of the amount of phospholipides to the protein and oil content	580
c. Phospholipides in developing and germinating seeds	580
d. Function of compound lipides	581
6. Synthesis of lipides	582
a. Relation of the carbohydrates to the formation of fats and oils	582
b. Changes in the fats and oils during their formation	583
c. General observations	585
7. Changes in the fats and fatty oils during germination	587
a. Changes in the amount of oil	587
b. Chemical changes in the oily reserve	588
1. Fatty acids of the oil	589
(a) Fatty acids of the cotyledons	590
(b) Fatty acids of the roots and hypocotyls	591
2. Relation of carbohydrates to the disappearance of the fats and oils	591
B. Fatty substances not compounds of fatty acids	591
Questions	591
Bibliography	591

CHAPTER XI

E PROCESS OF DIGESTION IN THE GREEN PLANT	603
I. Foods of the green plant	603
A. Plant sources of animal foods	603
B. Value to the plant of its stored foods	604
II. Nature of digestion	605
D. <u>I. Enzymes</u>	606
A. General nature of catalysts	607
B. General nature of enzymes	607
C. General nature of <u>enzyme action</u>	609
D. Nomenclature	611
E. <u>Classification</u>	612

	PAGE
<i>F.</i> Occurrence	613
1. The carbohydrases of plants	614
<i>a.</i> The invertases, invertins, saccharases, or sucrases	614
1. Preparation and study of invertase	615
<i>(a)</i> Preparation from yeast	615
<i>(b)</i> Preparation from green plants	616
2. Nature of the action of invertase	616
3. Factors influencing the action	618
<i>b.</i> The diastases or amylases	620
1. Preparation of plant diastase	622
2. Study of diastatic activity	624
3. Factors influencing the action	625
<i>(a)</i> Chemicals	625
<i>(b)</i> Temperature	626
<i>(c)</i> Light	627
<i>c.</i> The inulases	628
<i>d.</i> The glucases or maltases	628
<i>e.</i> The cellulases or cytases	629
<i>f.</i> Other carbohydrases	631
2. The glucosidases of plants	631
<i>a.</i> Emulsin	632
<i>b.</i> Maltase, phytase, and rhamnase	632
<i>c.</i> Myrosin	632
3. The esterases or lipases of plants	633
<i>a.</i> Preparation and study of lipase	633
<i>b.</i> Factors influencing the action	634
4. The proteases of plants	637
<i>a.</i> Historical	638
<i>b.</i> Kinds	638
1. The pepsins or peptases	638
2. The trypsins or tryptases	639
<i>(a)</i> Papain	639
<i>(b)</i> Bromelin	642
<i>(c)</i> Other plant trypsins	644
3. The crepsins or ereptases	645
5. The coagulases of plants	645
<i>a.</i> The rennets or rennins	645
<i>b.</i> The pectases	646
<i>G.</i> The formation of enzymes in plants	647
IV. A comparison of digestion in plants and animals	652
Questions	653
Bibliography	656

CHAPTER XII

THE TRANSLOCATION OF MATERIALS IN PLANTS	669
I. Need of translocation	669
II. Tissues concerned	669
A. The xylem	670
B. The phloem	671

	PAGE
III. Movement of materials	672
A. Translocation of water	672
1. <u>Pathway of water movement</u>	672
2. <u>Water-conducting cells</u>	673
3. Ascent of water	675
a. Low evaporation	676
b. High evaporation	679
1. Vital theories	680
2. Physical theories	683
(a) Absence of living cells	683
(b) Imbibition and capillary theories	685
(c) <u>Cohesion theory</u>	686
4. <u>Downward movement of water</u>	689
5. Lateral movement of water	691
B. Translocation of inorganic compounds	692
1. Upward transfer	692
2. Lateral transfer	695
C. Injection experiments	696
D. <u>Translocation of organic compounds</u>	698
1. Storage of reserves	698
2. Utilization of reserves	702
3. Tissues concerned	704
a. The xylem	704
1. The physical unsuitability of the phloem	704
2. Composition and amount of organic compounds in tracheal sap	705
b. The phloem	707
4. Lateral translocation	709
5. Translocation of carbohydrates	710
6. Translocation of fats and oils	714
7. Translocation of proteins	717
Questions	719
Bibliography	721

CHAPTER XIII

THE PROCESS OF RESPIRATION IN PLANTS	729
I. Energy relations of the plant	729
II. Nature of respiration	730
III. <u>Organic materials used in respiration</u>	731
IV. Aerobic and anaerobic respiration	735
V. Relationship of anaerobic and aerobic respiration	736
VI. Aerobic respiration and photosynthesis contrasted	739
VII. Respiration and breathing	740
VIII. Methods of measuring the intensity of aerobic respiration	741
IX. The respiratory quotient	744
X. Respiration and the production of heat	747
XI. Factors affecting respiration	748
A. Temperature	748

	PAGE
<i>B.</i> Moisture	752
<i>C.</i> Injury	755
<i>D.</i> Kind and age of tissues	757
<i>E.</i> Anesthetics	760
<i>F.</i> Concentration of oxygen and carbon dioxide	762
<i>G.</i> Various salt solutions	764
<i>H.</i> Light and electricity	765
XII. Substances or enzymes concerned in or associated with oxidation in plants	766
<i>A.</i> The oxidases	767
1. Classification of oxidases	768
<i>a.</i> The laccases or phenolases	768
<i>b.</i> The tyrosinases	769
2. Methods of determining activity	770
<i>a.</i> Color methods	770
<i>b.</i> <u>Measurement of oxygen absorbed.</u>	772
3. Factors influencing oxidase activity	772
4. The relation of the oxidases to physiological functions	773
<i>B.</i> The peroxidases	775
<i>C.</i> The catalases	775
1. Preparation and study	776
2. General nature and behavior	777
3. Relation to physiological activity	779
<i>a.</i> Respiration	779
<i>b.</i> Vitality	781
Questions	783
Bibliography	785

CHAPTER XIV

THE PROCESS OF GROWTH IN PLANTS	797
I. Nature of growth	797
II. Stages in the growth of a plant cell	798
<i>A.</i> Embryonic or formative	798
<i>B.</i> Elongating	800
<i>C.</i> Differentiating	800
III. Growth of plant organs	801
IV. Nature of growth curves	802
V. Periodic elongation	806
VI. Growth-promoting and growth-inhibiting substances	807
<i>A.</i> Growth-promoting substances	808
<i>B.</i> Growth-inhibiting substances	810
VII. Dormant or resting periods	811
<i>A.</i> Causes of dormancy in plants and plant parts	811
<i>B.</i> Overcoming dormancy	813
1. Stems, tubers, and bulbs	813
2. Seeds	814
<i>C.</i> After-ripening	815


	PAGE
VIII. Factors affecting growth of plants	818
A. Internal factors	818
B. External factors	820
1. Temperature	820
a. Growth curve in relation to temperature.	820
b. Resistance of plants to low temperatures.	822
2. Light.	824
a. Rate of growth in light and darkness	825
b. Different rays.	827
c. Intensity of light	829
d. Length of exposure to light.	829
1. Reproduction	830
2. Development of storage organs.	832
3. Chemical changes.	832
4. Localization of response.	833
3. Electricity	834
4. H-ion concentration	836
5. Gases	837
6. Moisture and nutrients.	838
Questions	838
Bibliography.	840
AUTHOR INDEX.	851
SUBJECT INDEX	871

PLANT PHYSIOLOGY

CHAPTER I

THE PLANT CELL

The cell is not only the structural unit but also the functional unit of the plant and animal body. Since plant physiology is the study of the functions of plants, a general knowledge of the morphological parts of the plant cell is necessary for a clear understanding of the various life activities of the plant. In this chapter it is intended to discuss the parts of the plant cell only in a general way, since a consideration of the more minute details belongs to the province of plant histology. The parts of a living plant cell are generally classified as follows (Fink, 1925):



I. THE CELL WALL

A. ORIGIN

The protoplasm of plant cells is with but few exceptions enclosed by a more or less solid membrane which has been secreted by it. This membrane, which is called the "cell wall," is relatively very thin when it is first formed but increases in thickness through the deposition by the protoplasm of new particles upon those already present. The wall may increase in thickness but little over its original measurements, or it may become so much thickened that it almost fills the cell cavity. Thus, for example, the amount of thickening in the cell wall of the flax fiber may amount to as much as 90 per cent of the area of the cell in cross-section (Anderson, 1927). (See Fig. 2.) The cell wall in many cases is thickened irregularly, leaving thin places in it which are termed "pits," which facilitate the interchange of materials from one cell to another (Fig. 2*p*). The manner in which the original cell wall becomes thickened is little understood and may be different in different types of plant cells. Aldaba

(1927) observed in the case of the development of the cell walls of the bast fibers of *Boehmeria* and *Linum* that the cell wall is formed by a series of telescoping, open, tubular hyaline membranes which gradually become transformed into cell-wall lamellae. Each of these successively formed




FIG. 1.—Diagram of a green parenchyma cell of a leaf showing the parts of a plant cell. *w*, cell wall. *c*, cytoplasm. *n*, nucleus. *p*, plastids. *v*, vacuole.

membranes arises from the base of the previously formed one and grows upward toward the elongating tip of the fiber. The modified hyaline membranes resemble plasma membranes and react similarly towards stains and during plasmolysis. The unmodified hyaline membranes are in direct contact with the protoplasm, but the thickening and differentiating portions are separated from it by one or more subsequently formed layers. The mode of formation is suggestive of a process of transformations. It cannot be satisfactorily accounted for by the theories of apposition and intussusception. That portion of the cell wall that is laid down during the early life of the cell is different in optical, chemical, and staining properties from that part of the wall which is later deposited. This central layer or plate is readily seen in those cell walls that have been greatly thickened, but it can be observed after proper treatment in nearly all cell-wall membranes, even when they are quite young. This central portion of the cell wall is called the "middle lamella" and is generally defined as the cell wall that was originally deposited by the protoplasm, although there is considerable uncertainty as to the length of the period during which this portion of the wall was formed.

Allen (1901) studied the origin of the middle lamella in the cells of a considerable number of plants and concluded that the middle lamella consists of the layers first deposited by the protoplasm plus a certain amount of material subsequently in contact with these layers which is generally rich in pectic compounds as compared with the still later deposited strata. He considered that in the higher plants there is no doubt that the young cambium walls are included in and form the basis of

the middle lamella of the older tissues. The chemical nature of the middle lamella was first studied in detail by Mangin (1888 to 1891). He concluded that the partition wall formed in higher plants during cell division consists almost wholly of pectic substances either in the free state or in the combined state with calcium in which form it was considered the bulk of the middle lamella in mature cells. Ritter (1925) considered that in woody tissue the middle lamella is not pectic in nature but is strongly lignified. Harlow (1927) observed in the young cortex unlignified pith and cambium region that the middle lamella is composed of pectin in one or more of its forms, while in woody tissue this layer is heavily




FIG. 2.—Sections showing thickening of the cell wall. *A*, section through the endosperm of the asparagus seed. *B*, section through the endosperm of the date seed. *C*, cross-section of spruce wood. *m*, middle lamella. *s*, secondary thickenings of the cell wall. *p*, pits. *cc*, cell contents. *c*, canals. *e*, empty cells.

lignified. There are two explanations for these observed changes in the older cell walls: (1) that the pectins are metamorphosed to form part of the lignin of the mature cell wall and (2) that the initial pectic structure may be completely covered with lignin substances which render it inert to the action of the usual pectic stains and solvents. A combination of these two processes might also occur. The evidence indicates that, at least in the softer tissues of plants, the middle lamella is composed, for the most part, of pectic substances which may become lignified in woody tissues. (The middle lamella in most tissues dissolves readily under the action of potassium chlorate and nitric acid which do not affect the later deposited portions of the cell wall. It resists the action of strong sulphuric and other mineral acids which cause the other portions of the cell wall to swell and finally dissolve.)

Tupper-Carey and Priestley (1923) investigated the cell walls of the apical meristem of the stem and root and found the existence of cellulose in the walls of the meristem, although its presence is marked by associa-

tion with other substances. Protein closely linked to it is considered to be the factor which prevents its detection with iodine and sulphuric acid. Pectin is present, but the middle lamella in the meristem is never of calcium pectate but is probably a mixture of pectin and protein. Fat is present in the cell walls of the meristem closely linked to cellulose and probably is responsible for the failure of chloriodid of zinc to give the cellulose reaction. Wood (1924, 1926), however, considered that there is not enough protein present in the cell wall to interfere with the cellulose-pectin reaction, since according to his tests not more than 0.001 per cent protein occurs in the cellulose cell walls of any of the plants examined.

B. GENERAL PHYSICAL AND CHEMICAL PROPERTIES


The general structure of the plant cell wall has been determined by direct microscopical observations, by microchemical means by the aid of polarized light (Frey, 1926, 1927), and by X-ray analysis (Sponsler, 1928).

The chemical and physical structure of plant cell walls varies widely in different plant groups and in the same individuals. Thus the cell walls of root hairs, wood fibers, bast cells, cork cells, or epidermal cells have but few characteristics in common. All plant cell walls, however, have two general characteristics in common: (a) They are not chemically homogeneous but are composed of two or more chemically distinct substances. (b) They are not physically homogeneous but show stratification, striation, and other indications of structural variation. By means of X-ray diffraction patterns, Sponsler (1928) proved the existence of structural units in the cell wall of the bast fibers of ramie (*Boehmeria nivea*). He proved in this manner that these units have a regular arrangement in layers in the wall, that they are regularly spaced, and that some of the layers extend lengthwise and some crosswise at right angles. The structural unit was shown to be, with a very high degree of probability, a $C_6H_{10}O_5$ anhydrous-glucose residue. The evidence indicates that the units are attached in chains of indefinite length which extend lengthwise of the fiber and are very uniformly spaced (see also Sponsler, 1929). Anderson (1928) considers that the recent researches indicate that all cellulose cell walls as well as those containing cellulose in considerable amounts possess a submicroscopic structure of crystalline micellae which are embedded in an amorphous matrix the chemical nature of which varies in different walls and probably at different stages of development in the same wall. The orientation of the crystalline micellae is not constant in all cell walls but varies widely. The microscopic structure of the cell wall is a complex of several chemically different lamellae. A given lamella may consist of but one chemical substance and alternate with lamellae of other cell-wall constituents, or the various constituents may be present in the same lamellae. This whole structure is saturated with colloidal phospholipides which are in intimate union with the protoplasm

of the cell. The general colloidal nature of the cell wall will be considered when the cell wall is discussed as a membrane.

C. CHEMICAL COMPOSITION

The chemical nature of the cell wall is but little understood. The substances that compose it are complex and their constitution is in most cases not definitely known. Furthermore, in many cases it is not known whether the cell wall is composed of a mixture of substances or these substances are chemically combined with each other. Any discussion of the chemical composition of the cell wall must, therefore, be rather meager and superficial. In general, however, it may be stated that the cell wall of the plant cell is composed of a mixture of celluloses, together with certain other compounds depending upon the nature of the cells in question. The following diagram shows the substances that may enter into the composition of the cell wall:



1. Normal, Typical, or True Celluloses.—Normal cellulose is a compound whose properties are fairly well established. It is a white hygroscopic substance that absorbs about 6 to 12 per cent of water which it loses in heating to 100°C. When heated with water under pressure to 260°C., it dissolves completely without disintegrating. Normal cellulose has the general formula $(C_6H_{10}O_5)_n$, so that it is chemically like, but not identical with, starch. Concentrated sulphuric acid dissolves cellulose gradually, converting it into dextrin and then into glucose. If the solution, as soon as made, is diluted with water, a gelatinous precipitate is formed which gives a blue color with iodine. The same substance is formed by the action of chlorzinc iodine which stains the compound at first a rose red and later a violet color. When cellulose is hydrolyzed

under the influence of the enzyme *cytase* secreted by bacteria and various fungi, but not by animals, it breaks down first into cellobiose, $C_{12}H_{20}O_{11}$, an isomer of maltose, and then into glucose. [Cellobiose stands in the same relation to cellulose as does maltose to starch.] Since cellulose and starch yield different saccharides on hydrolysis, it would appear that these two substances are fundamentally different. Cellulose is insoluble in all ordinary solvents but will dissolve in any one of the three following salt solutions: (a) Zinc chloride in twice its weight of concentrated hydrochloric acid dissolves cellulose in the cold. (b) It is dissolved by ammoniacal cupric oxide (Schweitzer's reagent); and (c) it goes into solution upon heating 1 part cellulose in a solution of 6 parts zinc chloride in 10 parts of water. Cotton fiber is the best example of almost pure normal cellulose occurring in nature. An analysis of American cotton fiber showed it to be composed of 91 per cent normal cellulose, 8 per cent water, and only 1 per cent of other materials, principally waxes, gums, minerals, and pectose derivatives. The cell walls of the younger plant cells are composed, for the most part, of normal cellulose or some of its derivatives. Wood (1924) studied the nature of the cellulose constituents of the cell wall of the cells of the young root tips of *Vicia faba* and *Helianthus annuus* as well as the parenchymatous tissues of the stems of these plants. He found that the cellulose constituents of the cell wall consist of normal cellulose, oxycellulose, and hydrocellulose, the proportion of each constituent varying with the age and kind of cell. The compounds termed "normal celluloses" are composed, in many cases at least, of three different types or forms of cellulose which have been designated as α , β , and γ celluloses. These differ from each other especially in regard to the action of alkalis and possess different degrees of dispersion, dehydration, and corresponding polymerization.

2. Hydrocelluloses and Oxycelluloses.—These celluloses are degradation products which are frequently found associated with normal celluloses in the cell wall. Hydrocellulose is apparently produced by partial hydrolysis and is a compound which possesses active carbonyl groups and shows a very strong absorptive power for different organic dyes. It may be prepared, according to Mehta (1925), by soaking cotton with as small a quantity as possible of cold 72 per cent sulphuric acid and treating almost immediately with 95 per cent alcohol. The hydrocellulose thus formed is washed free from acid and dried in the air. It has the formula $C_{12}H_{22}O_{11}$ but retains the fibrous structure of the original cellulose, can be rubbed into a powder, and stains blue with iodine. Oxycelluloses are mentioned by many authors to designate various compounds of an indefinite character which are produced by the action of various oxydizing agents on cellulose. The compounds of this type possess acidic properties, contain active carbonyl groups, and reduce Fehling's solution.

3. Hemicelluloses.—The term “hemicellulose” was first used by E. Schulze in 1892 to denote a substance in the cell wall that is somewhat similar in character to cellulose but which is easily hydrolyzed by weak acids. The term now loosely includes a heterogeneous collection of substances in the cell wall which are not soluble in water but are soluble in weak alkalies and which yield on hydrolysis principally the sugars galactose, mannose, and pentose, so that they are generally considered the anhydrides of these sugars. Hemicelluloses are found in the seed coats of beans, peas, and other legumes. They occur in the cell walls of the seeds of coffee, soybean, nasturtium, white lupine, date, onion, asparagus, vegetable ivory palm, as well as many others. They are found also in the pods of legumes, the shells of nuts and stony fruits, and to some extent in the cell wall of the xylem elements of woody stems. In many of the cases mentioned, hemicellulose undoubtedly functions as a reserve food which is utilized by the young seedling in its growth, since in the case of the seed of the date, vegetable ivory palm, and others, it is the only reserve carbohydrate present and disappears during the germination and development of the seedling. In many other cases, due to its location in the seed coats, hulls, or pods, it is difficult to see how it could be utilized by the plant for food. The results obtained by some of the investigators of hemicelluloses are worthy of consideration. Schulze (1893) examined cell walls of the seed coats of corn and white lupine. The cell walls of the seed coat of corn yielded, on hydrolysis, xylose and a small amount of galactose, while the pentosan content of the coat was estimated at 43 per cent. The cell wall of the seeds of blue lupine produced on hydrolysis galactose and pentose. He considered that pentosan and galactan are hemicelluloses that are widespread in their distribution in plants, since he also observed them in the seed coats of rye and barley. Grüss (1897) by the digestion of the cell wall of the date obtained mannose as one of the end products. Castoro (1906 to 1907) found a high hemicellulose content in the seeds of *Ruscus aculeatus* which yielded on hydrolysis mannose and some arabinose. He considered that this hemicellulose in this seed functions as a reserve food in the germination of the seed. The seed coats of *Lupinus angustifolius* and *Lupinus albus* contain a hemicellulose which yielded galactose, but Castoro considered that these do not function as reserve foods. The hemicellulose in the seed coats of the seeds of *Cucurbita pepo* yielded on hydrolysis principally xylose and some galactose. Schulze and Pfenniger (1910) found that the pods of *Pisum sativum* and *Phaseolus vulgaris* are rich in hemicellulose and that the amount increases as maturity takes place, the ripe pods yielding as much as 48.6 per cent. This hemicellulose yielded galactose and arabinose on hydrolysis. Tottingham, Roberts, and Lepkovsky (1921) observed that the wood from fruiting branches of apple twigs shows a high content of hemicellulose which yields xylose and glucose with a little galactose.

They considered that hemicellulose forms a reserve source of carbohydrate in the metabolism of the apple tree. Murneek (1929) also emphasizes the importance of hemicellulose as a reserve carbohydrate in the apple tree. In the case of the new growth of the fruit-bearing spur, the starch constituted 1 to 4 per cent of the total dry matter, while hemicellulose represented 17 to 22 per cent. Similar proportions of these two groups of substances were found also in leaves, flowers, and fruits. Hemicellulose also seems to be formed in relatively large quantities in the developing fruits and is apparently later hydrolyzed to form some of the sugar content of the ripening fruit. Cake and Bartlett (1922) found that the hemicelluloses which compose the reserve carbohydrate in the asparagus seed yield mannose, glucose, fructose, and galactose upon hydrolysis. Schryver and Thomas (1923) isolated from certain starches a hemicellulose which yielded on hydrolysis only glucose. O'Dwyer (1923) found that the chief product of hydrolysis of the hemicellulose of American white oak is 1-xylose with arabinose second in amount. The amount of xylose yielded by the hemicellulose of this wood was approximately 51.5 per cent and the arabinose 18.5 per cent. It has been estimated that xylan with a little araban makes up from 15 to 20 per cent of the dry matter of deciduous trees. She also observed (1928) that the nature of the hemicellulose in timber depends upon the age of the wood. Thus from beech 80 years old 80 per cent of the hemicellulose could be acetylated but only 20 per cent of the same substance from an older tree responded to the same treatment.

4. **Compound Celluloses.**—This is a general term that includes those compounds of the cell wall which consists of some form of cellulose combined or closely associated with a non-cellulose constituent. The most common and widespread compound cellulose in the plant kingdom is lignocellulose. Lignocellulose is the chief constituent of wood, jute, and cereal grasses and straw. (It is generally considered to consist of cellulose chemically combined with lignin, but some authorities are of the opinion that the lignin is simply an encrusting substance and consider its combination with the cellulose to be only a physical one.) The lignocelluloses cannot be crystallized without decomposition and cannot be obtained in the form of true solutions, although colloidal solutions are possible. They are among the most inert plant compounds and probably have no rôle other than that of adding stiffness to the plant tissues. The formation of lignocellulose seems to be a gradual infiltration process. In the younger plant cells the cell walls consist of practically pure cellulose, but as the cells become older lignin appears to be absorbed, or is infiltrated, into the cellulose fiber and lignocellulose results so that in the case of the cell walls of wood the proportion of cellulose in the tissue is only 50 to 60 per cent. Mehta (1925) considered that lignocellulose is not an adsorption compound but appears to consist of a chemical combination of lignin

with cellulose and related polysaccharides as an aromatic glucoside. This investigator found that the lignin content of the buds of Oregon pine and spruce was relatively high, a fact which indicated that lignification commences at a very early age simultaneously with the thickening of the cell walls. Ritter (1925) considered that the greater percentage of lignocellulose in wood is located in the middle lamella of the cell wall. According to Harlow (1928) the secondary cell walls of soft wood are appreciably lignified, while those of the hard woods with but few exceptions contain practically no lignin. The lignin of the secondary cell wall may be removed by mild chlorination without affecting to any great extent the lignin that comprises the middle lamella. Lignocellulose is resolved completely into its constituents by heating with 4 per cent sodium hydroxide at 10 atmospheres for one hour without any decomposition of the lignin constituents, which can be precipitated by acidifying the alkaline liquid and isolated in the pure condition quantitatively by extraction with alcohol. Lignin as isolated from wood by the above method is a brown, amorphous, faintly acidic substance with an aromatic odor and melting at 170°. It is insoluble in water at ordinary pressure but partially soluble under pressure and soluble in dilute alkalis and alcohol and is more readily attacked by oxidizing agents than cellulose. The lignins contain methyl, methoxyl, formyl, and acetyl groups and consequently have a higher carbon content than cellulose.

Pringsheim and Magnus (1919) have shown that when wood or straw is treated with sodium hydrate in the cold, boiled with it under pressure or otherwise, most of the acetic acid liberated is derived from the lignins. Klason (1910) has assigned to lignin the formula $C_{40}H_{42}O_{11}$. Since the reactions of lignin and coniferyl alcohol are analogous in many respects, he assumed that the lignin is derived from coniferyl alcohol, $C_{10}H_{12}O_3$, by condensation and oxidation of four molecules of the alcohol.

Dorée and Barton-Wright (1927) by the action of 4 per cent sodium hydroxide at 10 atmospheres pressure for an hour on purified wood obtained a new type of lignin which they designated "metalignin." This has the formula $C_{20}H_{20}O_6$ and a molecular weight of 356. The preparation of derivatives indicated the presence of one hydroxyl, two methoxyl, and two carbonyl groups, while two double linkages are apparently present.]

5. Suberin and Cutin.—These terms are used to designate those substances which render certain cell walls of the plant more or less impermeable to water. These two substances have frequently been called "adipo-" or "cutocelluloses" and were classified as compound celluloses, since it was assumed that they consisted of a cellulose base chemically combined or closely associated with compounds of a fatty or waxlike nature. The work of Gilson (1890), Wisselingh (1888 to 1892), Schmidt (1903 to 1910), and Priestley and his coworkers (1921 to 1925), however,

seems to show conclusively that suberin and cutin are not combined with a cellulose nucleus but are a collection of distinct compounds, although in some cases they may infiltrate a cellulose matrix.]

The general properties of suberin and cutin may be stated as insolubility in and impermeability to water, considerable insolubility in fatty solvents, great resistance to concentrated sulphuric acid, but readily oxidized by nitric or chromic acid and readily soluble in warm alkali. They are stained by fat stains such as Sudan III or scarlet red.

a. Suberin.—This is the substance which renders the cell walls of cork cells impervious to water, and on chemical grounds it may be regarded as an aggregate of variously modified forms (condensation products or anhydrides) of the suberogenic acids of which phellonic, suberic, and phloionic are representatives. Phellonic acid gives color reactions with iodine reagents, and this fact may account for the impression that cellulose is present in the suberin lamella. According to Priestley (1921) and Rhodes (1925), the distribution of suberin in the wall of the cork cell is as follows: Within each cell there is formed an inner layer which possesses fat-storing properties and which is called the "suberin lamella." Similarly, fatty substances impregnate the middle lamella of the cell wall. The continuous suberin lamella within the cell is laid down simultaneously in all parts of the cell and is undoubtedly formed from the contents of the cell itself which have accumulated at the surface of the protoplast. Between this suberin lamella and the protoplasm is located a layer of cellulose impregnated to some extent with fat but quite recognizable when all fat bodies are removed. The fatty substances in the walls of cork cells are thus not in a continuous sheet but are for the most part concentrated within a series of isolated lamellae lining individual cells and to some extent diffused throughout a carbohydrate basis of cellulose or of pectates. Rhodes (1925) found that neutral fat solvents remove only a small portion of the fatty substances of the cork cells of the potato and that of the fats so extracted only a small portion were glycerides. He removed the remainder of the fatty substances from the residual material by saponification with 3 per cent alcoholic sodium hydroxide. The fatty material thus removed is regarded as consisting, in the main, of the salts of various organic acids, many of which have the characteristics of hydroxy-fatty acids. It seems evident that suberin owes its peculiar properties to the presence of normal and hydroxy-fatty acids in a state of combination and condensation and that the hydroxy acids are derived from the normal acids by some process of oxidation. Rhodes found that the chloroform-soluble material in the cork cells of the potato remained constant as the thickness of the cork cells increased, and he considered that this chloroform-soluble material is responsible for the staining of the cork tissue with Sudan III.

Priestley and Woffenden (1923) investigated the formation of cork cells in the healing of the cut surfaces of potato tubers which had been cut for planting. They found that the first process in the healing of the tuber is the deposit of a fatty "suberin" layer formed by the oxidation and condensation of fatty substances deposited from the sap drying up in the tissues at the cut surface. A supply of oxygen is essential for the formation of this layer, and if the cut surface is exposed in a moist atmosphere, the layer is continuous, but it may not be so in a dry atmosphere in sunlight. This outer layer of suberin is formed within 24 to 48 hr. A few days later cork is formed below this suberin deposit as the result of cell divisions in an actually dividing cork phellogen.

From these observations on the process of the healing of the cut surface of the potato tubers, two practical conclusions can be drawn: (1) Cut potatoes should not be left in sunlight or too dry a place, and (2) the practice of liming potato sets does not appear to be of any importance so far as its use in aiding the healing of the cut surface is concerned. According to Weimer and Harter (1921), the production of a cork layer in a wound of the sweet potato is preceded by the formation of a layer of starch-free cells usually 3 to 10 cells deep, beneath the injured surface. Cross-walls begin to appear from the second to the third day, and by the fourth to the sixth day a distinct layer of cork cells forms a covering over the wound. Temperature and humidity are important factors in regulating the formation of cork in the sweet potato. This in their experiments took place from 20 to 33°C. A relative humidity of from 95 to 100 was favorable for cork production. No well-developed cork layer was produced over wounds under conditions existing in the storage house.

b. Cutin.—Cutin is a substance which is more or less impervious to water and is found in a continuous external layer or lamella on the outer cellulose wall of the epidermal cells of leaves and stems. Lee and Priestley (1924) have shown that in some cases there may be a cellulose cutinized lamella impregnated with fatty deposits beneath this external layer of cutin or cuticle. These authors consider that the cuticle is thickened by fatty substances migrating along the walls from interior tissues and that the mobility of the fatty substances in the walls may be modified by external conditions which thus affect the thickness of the developing cuticle.

Lee (1925) made a detailed macrochemical study of the cuticle of the petals of chrysanthemum and rose and of the petioles of rhubarb leaves. From her work it appears that cutin is a complex mixture of fatty substances, consisting of free fatty acids and condensation products of fatty acids, fatty acid combined with alcohol, soaps, unsaponifiable material, and resinous substances. A large amount of the fatty acids present are of the hydroxy-fatty type. These hydroxy-fatty acids are less soluble in chloroform than the normal fatty acids and are extracted from the

cuticle only after a lengthy saponification. In the petals of chrysanthemum the chloroform extract of the cuticle contains 45 per cent of normal fatty acids and 16 per cent of hydroxy-fatty acids, while the saponified extract contains 5 per cent of the normal fatty acids and 80 per cent of hydroxy-fatty acids. This author considers that the preponderance of the hydroxy-fatty acids is the result of oxidation processes taking place during the deposition of the cuticle. Since no glycerol has been identified, it seems that the fatty constituents of the cuticle have the characteristics of waxes rather than fats and have as their base monohydric alcohols rather than the trihydric alcohol glycerine. Legg and Wheeler (1925) extracted the cuticle of *Agave americana* and obtained four classes of compounds with the solvents used: (1) water-soluble material; (2) waxy material soluble in alcohol, benzene, or chloroform; (3) cellulose soluble in cuprammonia; and (4) the residue insoluble in the solvents used. This residue was considered as the characteristic constituent of the cuticle and was termed "cutin" by these investigators. More than 90 per cent of this cutin dissolved in alcoholic potash. The residue consisted for the most part of two semiliquid organic acids not hitherto reported as occurring in nature. One of these was termed "cutic acid," $C_{26}H_{50}O_6$, and the other "cutinic acid," $C_{13}H_{22}O_3$. The main distinction between cutin and suberin that is now definitely known is the absence from the cutin of phellonic acid and glycerine.

6. Pectic Substances.—There are present in the cell wall—especially the middle lamella of the parenchymatous tissue of fruit, as pears, apples, currents, leaf stem of rhubarb, and fleshy roots, as carrots, beets, and turnips as well as many others—a group of compounds that have the property of forming gels under certain conditions. These substances play an important part in the jam- and fruit-preserving processes, and it is to their peculiar properties that the "setting" of jams and jellies is due. It was formerly supposed that these substances consisted of a chemical combination of cellulose and certain mucilaginous compounds, so that they were classified as compound celluloses under the name of "pecto-celluloses." It is now fairly well established, however, that these substances are not chemically combined with cellulose, although they are closely associated with it, so that they are classified under the general name of the "pectic compounds" or "pectins."

The literature concerning the pectic substances is voluminous and contradictory. Over no other constituent of the cell wall is there such lack of agreement among investigators in regard to terminology as over this aggregation of pectic compounds, so that it is impossible to summarize the literature on the pectic substances with any degree of satisfaction. The different terms applied to these compounds have been tabulated by Ahmann and Hooker (1925). The lack of agreement of the various investigators on this subject can probably be traced to two causes. In

the first place, the term "pectins" includes, no doubt, a large aggregation of compounds rather than a few substances, so that the reactions obtained by one individual may be due to one substance and those by another individual to another substance. In the second place, the existence of many pectic compounds, which have been described by numerous investigators, must be regarded as uncertain. These pectic compounds are undoubtedly of a complex colloidal nature, and changes of physical properties and state of aggregation may occur without any definite change of chemical composition. On that account, solubility, the loss of solubility, or gelatinization—the tests that have so frequently been applied as determiners of pectic compounds—cannot be regarded as evidence in themselves of chemical change.

The real foundation of our knowledge of the pectic substances was laid by the researches of Fremy (1840 to 1848), and his general classification of these compounds is the one that has been in general use until the present time.

A study of the general properties of the pectic substances indicates that there are three distinct types of compounds as shown in the following outline:

Pectic substances	{	Pectic acid	{	Soluble in water	{	Potassium pectate
		Salts of pectic acid or pectates		Insoluble in water		Sodium pectate
						Calcium pectate
						Magnesium pectate
		Esters of pectic acid	{	Insoluble in water	{	Pectose
				Soluble in water		Pectin

a. Pectose.—The term "pectose" has been generally used since the time of Fremy to denote an insoluble pectic substance which occurs in the cell walls of green fruits and other immature plant parts and which is considered to be the parent substance of pectin. The terms "protopectin" and "pectinogen" have been used by Fellenberg (1918) and Clayson, Norris, and Schryver (1921), respectively, to denote pectose. It has been claimed by the majority of investigators that during the ripening of the fruit, pectose decomposes into a soluble compound generally known as "pectin," which consequently appears in increasing amounts in the expressed cell sap as the fruit matures. Tutin (1923) concluded from his investigations with the apple that pectose or protopectin does not exist and that pectin is present in the green fruits as well as the ripe ones, but it has not previously been extracted, since the tissues are extremely hard to reduce to a fine powder and also because certain insoluble compounds by their presence prevent the pectin from going through the filter. He claimed that he could with certain precautions obtain pectin from the green fruit. Tutin's work has been severely criticised by Carre (1925) who introduces evidence to show that his conclusions are in error.

b. Pectin.—The compound or aggregate of compounds termed “pectin” has the following characteristics: It is soluble in water and may be precipitated from this solution by alcohol. It cannot be crystallized and its only known method of purification is treatment in aqueous solution with animal charcoal and reprecipitation with alcohol. The chemical composition of pectin has not been determined with any certainty. Fellenberg (1918) established the fact that pectin is the methyl ester of pectic acid. Tutin (1921) considered pectin to be the dimethyl isopropenyl ester of pectic acid. Schryver and Haynes (1916) considered from the analysis of pectin from turnip, apple, strawberry, and rhubarb stems that it has the formula $C_{17}H_{24}O_{16}$ with strong evidence that it contained one pentose group.

Pectin undergoes changes in boiling, and Fremy (1840 to 1848) recognized two varieties: parapectin, which is precipitated by neutral lead acetate, and metapectin, which is produced by boiling pectin or parapectin with acids and is precipitated by barium chlorid. Fremy also discovered the action of the enzyme pectase on pectin. This enzyme causes a solution of pectin to set to a stiff gel and this change occurs more readily in the presence of chalk. The production of the gel has been considered to be due to the formation of calcium pectate. Tutin (1921) found that the action of cold dilute alkali and of pectase on pectin are essentially identical. In both cases a salt of pectic acid is formed and methyl alcohol and acetone are eliminated. Kopaczewski (1925) found that when pectin from carrots and pectase from alfalfa leaves which had been purified by long dialysis were mixed, coagulation of the pectin no longer occurs. Coagulation, however, occurs upon the addition of salts of Ca, Ba, Sr, Mg, Fe, or Cu to the mixture. All these salts show power to coagulate pectin in the absence of pectase. According to this author, a neutral medium gives the best results from the action of pectase. He concludes that any purely chemical explanation of the coagulation of pectin is at present impossible.

c. Pectic Acid.—This compound is only slightly soluble in water even in the presence of a considerable amount of electrolytes. Pectic acid forms soluble pectates with alkalis and insoluble ones with metals of the alkaline earth of which calcium pectate is the most widely distributed. Pectic acid is found especially in overripe and decaying fruits. The chemical constitution of pectic acid is not definitely known. Ahmann and Hooker (1925) after a study of the decomposition products of pectin proposed as a nucleus for pectic acid a dibasic acid galacturonic-galactonic acid and considered that at least six of these nuclei are linked together to form pectic acid. Conrad (1926) has described a method for the simultaneous removal and quantitative separation and determination of protopectin and pectic acid and its salts. Protopectin or its hydrolytic product pectin was found in all the tissues studied, but pectic acid or

pectates were found only in radishes. He considers that the many cases of pectates reported in plant tissue are probably the results of enzyme action during the preparation of the material for analysis.

All *pectic compounds* stain red with ruthenium red, as was first demonstrated by Mangin (1889 to 1892). With methylene blue (1:1,000) all the pectic substances stain violet; while the other cell-wall constituents stain blue or green. The membranes composed of pectic substances do not exhibit double refraction—they are isotropic—while cellulose membranes exhibit double refraction or are anisotropic.

7. Other Constituents of the Cell Wall.—The cell walls of the plant cell have infiltrations more or less of resins, gums, tannins, carbohydrates, fats, oils, dyes, ethereal oils, proteins, phospholipides, and the various inorganic salts of which potassium, sodium, silicon, and calcium are the more prominent. The kind and amount of these substances will depend upon the kind of plant and the conditions under which it was grown. The presence of phospholipides in the cell wall has been especially emphasized by Hansteen-Cranner (1914 to 1926). He considered that the plasma membrane bordering the cell wall is largely composed of these substances and that they are in direct and intimate connection with the phospholipides of the cell wall. The plasma membrane is thus considered not sharply delimited from the cell wall but is continuous with the phospholipides that saturate it. This, however, has been little considered by workers on the subject of plasmolysis, absorption, and general cell response. The occurrence of phospholipides in plants will be discussed in detail in Chap. X.

II. THE PROTOPLASM

The protoplasm is the name given to that aggregate of matter in the cell which displays those series of phenomena which we term "life." Its perceptible characters show that it has a viscous slimy consistency, that it is neither a true solid nor a true liquid, and that it possesses considerable power of cohesion. It is heavier than water and shows no tendency to mix with the same when placed therein. Its viscosity ranges from a degree slightly more than that of water to the firmness of a fairly rigid gel (Seifriz, 1920). While a certain degree of viscosity may characterize the protoplasm as a whole, it is always divided into regions more or less definite, as, for example, the plasma membrane, nucleus, or plastids which differ in viscosity from its general mass. The present known facts seem to support the view that protoplasm is essentially a colloidal solution of the emulsion type. It consists of a water phase containing dissolved minerals, a fat phase, a protein phase, and numerous minor phases, so that protoplasm can be considered as a polyphase colloidal system. The colloidal nature of protoplasm is manifested in its power of adsorption, in its staining properties, and in the changes in its physical state

under varied external conditions. Although much of the behavior of protoplasm cannot be explained on the basis of our present knowledge of colloidal solutions, "in the idea of protoplasm as a complex colloidal emulsion, we have the best hypothesis yet offered as a basis for the interpretation of the behavior of living substances" (Sharp, 1921).

Concerning the chemical constitution of living protoplasm but little is known. Strictly speaking, living protoplasts cannot be analyzed, since under any known method of chemical analysis the protoplasm is killed and only matter in the dead condition is being analyzed. The chemical analysis of protoplasm shows that it consists of from 80 to 90 per cent of water. The residue that remains after driving off the water consists of both inorganic and organic compounds. The inorganic substances make up from 5 to 7 per cent of the dry weight and consist chiefly of the chlorides, phosphates, sulphates, and carbonates of Mg, K, Na, Ca, and Fe. The organic constituents are chiefly protein, carbohydrates, and fatty substances. The nitrogenous compounds make up from 40 to 50 per cent and the carbohydrates and fats each from 12 to 14 per cent of the dry weight of the protoplasm. The principal component part of protoplasm thus consists of proteids and of fats and phospholipides collectively termed "lipoids" (Lepeschkin, 1928). The carbohydrates and decomposition products of protein substances are considered only as admixtures because in some cases they are absent. The various salts, however, are always present, although in some cases in very small amounts. The compounds that enter into the composition of protoplasm are thus no different from those found elsewhere and which are always considered as non-living material. Since protoplasm does not lose weight when it is killed, it is inferred that no elements or compounds escape from it at death and that it is the manner in which these various compounds are combined that gives the protoplasm the outstanding characteristics which distinguish it from matter in the dead condition. Death of living matter seems to be due to disorganization. It is of interest at this point to note the age that the living cells of plants may attain. MacDougal (1926), MacDougal and Long (1927), MacDougal and Smith (1928), MacDougal and Brown (1928), and Faul (1928) have made observations along this line. Living cells were observed in the medulla and cortex of the tree cactus (*Carnegiea*) and in the massive cactus *Ferocactus wislizenii* which had an age of at least 100 years. Ray cells of *Sequoia sempervirens* were found in the heartwood that was over 100 years of age, while living ray cells and tracheids 250 years old were observed in *Parkinsonia microphylla*. It was observed that the pentosans or mucilages which are abundant in the young cells of the cacti decrease with age. The glucose content increases, while the lipid and protein content undergoes the least change.




FIG. 3.—Stages in the development of the vacuole and protoplasmic membrane as shown by the cells of the growing region of a root of corn. *A*, an embryonic cell. *D*, a cell that has reached its full growth in length and in which the vacuole is fully formed, the protoplasm being in a thin membrane along the cell wall. *B* and *C*, intermediate stages in the enlargement of the cell, showing the formation of numerous vacuoles which finally coalesce to form a single large central one.

The physical and chemical consistency of the protoplasm is a variable one and it may not be the same for any two cells and may be different in different regions of the same cell and different for the same cell under different conditions. The protoplasm is in the most intimate exchange with its environment so that its general constituency as well as its position in the cell may vary according to the conditions under which it is found.

The protoplasm in embryonic plant cells completely fills the entire cavity within the cell wall, but as the cells increase in size the protoplasmic content is altered by the appearance within the protoplasm of cavities filled with cell sap and called "vacuoles." These vacuoles are in most cases ultimately combined to form a single large sap cavity so that the protoplasm is spread out in a thin film along the cell wall (Fig. 3).

Although it is possible to recognize within the protoplasm a number of well-differentiated parts that perform certain definite functions, the search for some ultramicroscopic structure of the protoplasm as such has so far been of no avail. The parts of the protoplasm of plant cells that are at this time definitely recognized are the cytoplasm, nucleus, plastids, and chondriosomes.

A. THE CYTOPLASM

The cytoplasm may be considered as the less specialized portion of the protoplasm of the cell, since its functions are not so clearly defined as those of the other parts of the living substance. The cytoplasm makes up the general groundwork of the protoplasm and the greater portion of its bulk. Its physical and chemical characteristics are practically the same as those that have been mentioned in the discussion of the protoplasm. In general, the cytoplasm is the more fluid portion of the protoplasm in which the more highly differentiated morphological portions of the protoplasm are embedded and is thus that portion of the protoplasm that comes into the most intimate relationship with the environment of the cell. The surfaces of the cytoplasm which border on the cell wall and on the vacuole are generally modified in a greater or less degree in texture and consistency from its general mass. These modifications seem to consist of special layers or membranes of non-granular hyaline cytoplasm. Whether these membranes are the result of inherent specialization of the cytoplasm or simply the resultant of the physical forces of surface tension is not definitely known. The outside membrane next to the cell wall is generally called the "ectoplast" and the inside membrane bordering the vacuole the "tonoplast," while the more granular turbid bulk of the cytoplasm lying between these two membranes has been termed the "endoplasm." Any matter that enters the vacuole from the exterior of the cell or passes from the vacuole to the outside must pass through the cytoplasmic layer. The ectoplast and the tonoplast have been called by some authors the "plasma membranes" and have been considered by some

authors to exercise a selective influence on the passage of materials into or out of the regions on which they border, but whether they are more specialized in this regard than the general mass of the cytoplasm has not been proved by any adequate experimental evidence. Concerning the physiological function of the cytoplasm but little is known. What little experimental work has been done seems to be in harmony with the hypothesis advanced almost 50 years ago by Bernard (1878) who maintained that the cytoplasm is the seat of destructive metabolism. If it is not thus involved, it would at least be safe to assume that it is a neutral region which translocates materials toward and away from the nucleus and plastids. It has been shown by Poirault (1893) and Gardiner and Hill (1901) that in many cases the cytoplasm of one cell is connected with that of the adjoining cell by delicate strands of cytoplasm which extend through the cell wall. These strands or fibrils are termed "plasmodesma" and lie in minute passageways through the cell wall. The plasmodesma are characteristic at least of those living cells which have cellulose or unglified walls. These strands are the largest in the cells of mosses and the smallest in the cells of seed plants. They have been observed in the thick-walled cells of endosperms, in storage tissue, phloem, meristem, and in the medullary rays. The plasmodesma bear a close resemblance to the connecting strands of sieve tubes and these strands are considered by some to be merely enlarged plasmodesma. Although the plasmodesma have been little recognized in plant physiology, it seems probable that they may play an important rôle in the transmission of stimuli and in translocation of materials from cell to cell.

B. THE NUCLEUS

The nucleus is the most conspicuous organ of the protoplasm, and due largely to its behavior in the process of reproduction and cell division, cytologists have largely concentrated their attention upon it with the result that the nucleus is the best known body in the protoplasm in regard to its structure and morphology. A detailed discussion of the nucleus is beyond the scope of this work and it is the intention to make only a few general statements concerning its structure and function. It is generally a rounded or ellipsoidal portion of the protoplasm whose structural basis is essentially similar to that of the cytoplasm. In its physical nature, the nucleus consists in part at least of a gel of higher viscosity than the cytoplasm. It is bounded by a distinct membrane within which is the nuclear sap or karyolymph. This substance is generally highly transparent and homogeneous and may occur as either a sol or a gel. In the karyolymph is embedded a network or reticulum which may be relatively uniform throughout or only fragmentary. In its chemical properties the nucleus is distinguished from the cytoplasm by the abundance of nucleoprotein that it contains. The nucleoproteins under proper procedure can be split into

nucleic acid and a form of protein, the two existing in the nucleus in chemical combination. In its physiological functions the nucleus seems to be especially the center of the synthetic activities of the cell. The limited experimental evidence here again tallies with the opinion of Bernard (1878) that the nucleus is the organ of constructive metabolism.

C. THE PLASTIDS

The plastids are differentiated portions of the protoplasm of plant cells which perform certain physiological functions and are classed as protoplasmic organs on the same morphological and physiological plane as the nucleus of the cell. According to our present knowledge, the plastids or their primordia are present in every plant cell of the green plant and the number of them formed in any given cell and the degree or form of differentiation that they assume will depend upon varied internal and external factors. Since the time of Schimper (1885) the plastids have been classified into three more or less distinct groups: the chloroplasts, the chromoplasts, and the leucoplasts.

1. The Chloroplasts.—The chloroplasts are the green plastids and owe their characteristic color to the presence of the pigment chlorophyll. They occur for the most part in those cells of the plant that are exposed to the sunlight. They vary much in shape and size in the algae, but for the most part, in the bryophytes, pteridophytes, and spermatophytes, they are small round or discoid bodies which more or less completely fill the peripheral cytoplasm of the plant cell. According to Eyster (1929), Mobius, in the examination of 215 species of plants belonging to many families of the bryophytes, pteridophytes, and spermatophytes, found 105 to have chloroplasts 5μ , 70 to have chloroplasts ranging from 3 to 5μ , 31 to have chloroplasts ranging from 5 to 7μ , and 9 to have chloroplasts from 7 to 10μ in their longest dimensions. In certain genetic strains of corn Eyster (1929) found the chloroplasts in one strain to be only 3 to 4μ in length, while in other strains they ranged from 10 to 25μ in their longest dimensions, as compared with 6 to 8μ in most strains. He observed a direct correlation between the number and size of the chloroplasts in individual cells. The smaller the chloroplasts the greater the number in the cell. Our meager information concerning the internal structure of the chloroplast seems to indicate that it consists of a colorless protoplasmic groundwork in which are embedded the chlorophyll granules. Priestley and Irving (1907) considered that the chlorophyll is restricted to the peripheral ring of the chloroplast where it is held in the meshes of a network of protoplasm in two species of *Selaginella* examined by them. Zirkle (1926) examined the chloroplasts under normal conditions in a large number of higher plants in monochromatic light of a known wave length without any fixing or staining. He considers that the ground substance or stroma of the chloroplast is in the form of a hollow, flattened

prolate spheroid surrounding a large central "vacuole." The stroma has a granular appearance that is due to numerous pores which connect the central vacuole with the cytoplasm surrounding the chloroplast. The pigments of the chloroplast are intimately mixed and evenly distributed throughout the protein ground substance. The starch inclusions of the chloroplasts are contained within the central vacuole. Zirkle also observed that in many leaves, a constant differentiation of chloroplasts occurs. Some contain little starch and are mainly concerned in photosynthesis, while others contain much included starch and little green tissue and apparently function mainly as storage organs. It has not been adequately shown that the chloroplast or any of the other plastids have a specific membrane of their own like the plasma membrane, or that of the nucleus, although Zirkle (1926) determined that the chloroplast is surrounded by a more or less permanent sheath of non-granular cytoplasm. Harper (1919), however, considers that when the chlorophyll is dissolved from the chloroplast it has little to distinguish it from the adjacent cytoplasm. He considers that the plastid is to be regarded as a region of the protoplasmic complex rather than as a differentiated and definitely delineated body and that cytologically the function of the chloroplast is perhaps little more than an area of the cytoplasm impregnated or infiltrated with chlorophyll.

The chloroplasts in the cells of the higher plants increase in number by the process of simple fission which resembles the amitotic division of nuclei, but so far as is known, the structure of the chloroplast undergoes no change in the process. The outstanding function of the chloroplasts is the formation of carbohydrates from carbon dioxide and water in the presence of sunlight. It is thus due primarily to the presence of the chloroplasts in certain of their cells that enable plants to manufacture their own food, while the members of the animal kingdom in whose cells the chloroplasts do not occur are totally unable to do so.

2. The Chromoplasts.—The chromoplasts are plastids which contain red, yellow, or orange pigments. They occur principally in the petals of flowers and in ripe fruits and may originate from chloroplasts or leucoplasts, as will subsequently be described. They have no special physiological function so far as is now known.

3. The Leucoplasts.—The leucoplasts are the colorless plastids and occur for the most part in those regions of the plant where light does not penetrate. They are of a denser consistency than the chloroplasts and are generally spherical in shape, although they may be greatly modified by the inclusions of starch and other compounds. Although the leucoplasts are colorless, they have the inherent capacity of forming coloring matter under certain conditions and thus being transformed into chloroplasts or chromoplasts. The term "leucoplasts" is generally used in a broad sense and is made to include not only the colorless plastids in the fully

developed cells of the plant but also the colorless undifferentiated plastids of the embryonic cells which may eventually develop into chloroplasts or chromoplasts. The term also includes the colorless plastids of the epidermal cells and hairs which are apparently abortive chloroplasts. One of the chief functions performed by the leucoplasts, especially in the storage cells, is the formation of definite starch grains from the soluble carbohydrates that are present in the cell. The capacity for forming definite starch grains is thus possessed only by plant cells and does not occur at all in the animal kingdom, whose cells in no case possess leucoplasts. Mottier (1921) investigated the formation of the protein granules in the aleurone layer of the endosperm of corn and the formation of oil in the castor bean. He is of the opinion that leucoplasts may elaborate bodies other than starch grains and concludes from his cytological investigations that the protein and oil bodies found in the above storage cells owe their origin to plastids whose primordia are permanent organs of the cell.

The three different types of plastids seem to be homologous structures which in many cases display direct relationship. The primordia from which the chloroplasts and leucoplasts develop are identical, as far as our present knowledge goes, since they cannot be differentiated from each other by any staining or chemical reactions at present at our disposal. The more mature plastids under certain conditions change from one into the other. The leucoplasts of the potato, for example, become filled with chlorophyll and function as chloroplasts when the tuber is exposed to light. It was observed by Powell (1925) that chlorophyll was developed in the roots of 13 out of 16 species of flowering plants when grown with their roots exposed to the light of a 200-cp. electric lamp. The plastids of the tomato at a very early age may undoubtedly be classified as leucoplasts but soon develop into chloroplasts which upon the ripening of the fruit become the chromoplasts which give the fruit its characteristic color.

4. The Origin of the Plastids.—There are two prevalent opinions in regard to the origin of the plastids in the cell. One group of investigators, including Sachs (1875), Mikosch (1885), and Belzung (1887 to 1891), hold the view that the plastids originate directly from the cytoplasm of the cell. According to them, the cells of the embryo of the mature seed contain no plastids. Their opinion is that if any plastids were present in the young embryo, they lose their identity and disintegrate at the ripening of the seed and that at germination the cytoplasm in the cells gives rise to new plastids which function during the period of activity of the plant. The other group of investigators is inclined to the opinion first set forth by Meyer (1883), Schimper (1885), and Bredow (1890) that the protoplasm of the cell never gives rise to plastids but they have an individual existence in the cell and that they multiply by division and are handed down from generation to generation. They consider that the

fertilized egg contains plastids which have been derived from the parent plant. During the development of the egg into the embryo these plastids multiply and in this manner provide every cell of the embryo with plastids. These plastids go through the resting stage of the embryo intact and at germination increase in number and thus supply each cell of the new plant. In certain *Conjugatae*, *Chlorophyceae*, and *Arche-goniatae* the chloroplasts pass through the entire life cycle apparently unchanged. They are reproduced exclusively by the division of pre-existing plastids and are apparently permanent cell organs. In the higher plants, however, the life history of the chloroplasts is more difficult and different, since in certain stages of the cycle no chloroplasts apparently occur but later reappear. They must then have originated from the cytoplasm or have passed through the preceding stage in an inconspicuous form. Although plastids both in the undifferentiated and differentiated state have been observed in the spores and fertilized eggs of several species of plants, the number of cases observed have been small due to the difficulty encountered in proper differentiation by staining, so that due to this lack of evidence in this link of the theory, it must remain more or less hypothetical. The work of later investigators has tended to strengthen this theory rather than to weaken it. Miller (1910) repeated the work of Famintzin (1893) on the origin of the chloroplasts in the cotyledons of the sunflower (*Helianthus annuus*) and showed that the plastids are present in their usual place in the cells of the seed but are very minute and that as the seed begins to germinate these plastids increase in size and divide by simple fission and develop into the chloroplasts of the green cotyledons of the seedling.

Mottier (1919) investigated the young tissues of *Pisum sativum*, *Zea mays*, and *Elodea canadensis* among others and concluded that the primordia of the leucoplasts and chloroplasts are permanent organs of the cell and that the egg and sperm have sufficient cytoplasm to carry these over into the new individual. Twiss (1919) traced in the root-tip cells of *Zea mays* from the embryonic cells backward an unbroken series of bodies varying in size from the most minute forms to plastids. She did not consider, however, that the observation of a series of gradations in size from mitochondria to the differentiated or mature chloroplasts is sufficient evidence that the mitochondria are the rudimentary plastids, since there is no way of showing that the rudimentary plastids are actually mitochondria and not young plastids. Randolph (1922) made a cytological study of various chlorophyll types of maize in order to determine the status of the plastids in the cells of these strains. All the chlorophyll types examined were found to contain the same initial, minute primordia of plastids (protoplastids) of the same size and general appearance. In normal green plants the protoplastid first appears in the cell as a minute granule at the limit of visibility, gradually enlarging and developing

chlorophyll until it becomes a mature chloroplast. In plants of the white virescent and other inheritance strains the unusual characters of the plants are due to the failure of the primordia initially present to develop into plastids with the normal size, color, or both. Randolph thinks that the behavior of the primordia of the chloroplasts may in part at least be under the control of the nucleus of the cell. In the case of *Coleus*, which has variegated leaves, Stout (1915) observed that plastids are present in both green and yellow cells but that in yellow cells they are fewer in number, smaller in size, and somewhat distorted in shape and, further, that in extreme cases of yellow development nearly all the cells fail in the production of chlorophyll. Hein (1926) cut sections of the leaves of certain variegated plants so that they included both normal green and abnormal white and yellow areas and the marginal cells lying between. He found in the leaves of *Dieffenbachia seguine* (Schott) in going from the normal green cells through the critical zone to the pure white areas that the plastids decrease in number, size, and color until the cells showing no green were reached and that in these cells no evidence of chlorophyll bodies could be observed. In contrast to this, the nuclei of the various cells showed no modification in shape, size, or appearance. In the leaves of *Dracaena godseffiana* (Sanders) a more abrupt change from the normal green tissue to the colorless tissue was shown than in *Dieffenbachia*, but it is not absolutely sharp and definite, since the marginal cells show both normal and abnormal chloroplasts.

Zirkle (1927) studied the origin of the plastids in the apical meristem of *Elodea canadensis*, *Lunularia vulgaris*, and *Zea mays*. He considered that the plastids develop from primordia in the meristematic tissue and that they are not reproduced *de novo* but reproduce by division, the division occurring in one plane only. The primordia are rod shaped, frequently found in strands end to end, and are often grouped around the nucleus. These enlarge, become green, and develop into chloroplasts. The immature plastids frequently contain starch inclusions. In the case of corn, Zirkle found that in the vascular tissue, epidermal cells, and tips of the prop roots, the primordia do not develop into plastids.

D. THE MITOCHONDRIA OR CHONDRIOSOMES

In the cytoplasm of the cells of many plants representing all the great groups of the plant kingdom there have been described by numerous investigators small rod-shaped or granular bodies under the name of "chondriosomes" or "mitochondria." These minute bodies can seldom be observed in living fresh tissue and are, in general, not preserved by the usual methods of fixation, so that they are not detected by the ordinary methods of staining. It is due to these facts that their discovery was not made until comparatively recent times in botanical history. A complete and thorough review of the literature on chondriosomes is given by Cavers

(1914). The literature on the chondriosomes is very confusing. Many of the investigators do not distinguish between the chondriosomes and the primordia of the plastids, and some (Guilliermond, 1911; Lewitsky, 1910; and others) consider that the bodies which they call chondriosomes give rise to the leucoplasts and chloroplasts. Rudolph (1912), Schmidt (1912), Mottier (1919), and others consider that the chondriosomes and the primordia of the plastids are entirely different structures and that in no case are chondriosomes changed into plastids. The evidence seems to indicate that there are present in the cytoplasm of plant cells certain definite minute bodies other than the primordia of the plastids. Guilliermond (1911 *et seq.*) and Mottier (1919) assign to these bodies the same morphological rank as the nucleus of the cell. The latter considers that they are permanent organs of the cell and are transmitted from individual to individual through the cytoplasm of the sperm and egg. The mitochondria are considered by physiologists (Politis, 1921; Marston, 1923; Cowdry, 1926; and Horning and Petrie, 1927) to be the seat of both synthetic and hydrolytic degradation processes in plants. The phase boundary of the mitochondria and the surrounding cytoplasm is regarded as the seat of these processes. Marston (1923) from the reaction of the mitochondria to azine dyes concluded that they contain proteolytic enzymes and developed the theory that the mitochondria are the seat of enzymatic protein synthesis in the cell. He considered that the "water-poor" phases which exist at the surface of the lipoidal constituents of the mitochondria provide suitable conditions for synthetic activity. He considered that not only protein but also other foods and complex compounds may be synthesized in the same regions of the mitochondria. The function of the mitochondria in hydrolytic processes has been studied by Horning and Petrie (1927) in the germination of corn, wheat, and barley. During germination the mitochondria become more numerous apparently by simple fission in the scutellum and are secreted in large numbers from the epithelial cells into the adjacent starch-containing cells of the endosperm. These secreted mitochondria then aggregate around the starch grains prior to their corrosion. Their behavior appears to lend considerable support to the enzymotic conception of mitochondrial activity, that the starch-splitting enzyme is located within them or at their surfaces and is liberated therefrom when the bodies have reached the surface of the starch grains.

III. THE VACUOLE OR CELL SAP

A. FORMATION

As an embryonic plant cell begins to increase in size, the protoplasm soon develops cavities of varying sizes which become filled with water and materials in solution and suspension. These cavities with their

contents are termed "vacuoles," and as the cell increases in size, these vacuoles usually coalesce to form a single large vacuole or cell cavity. The formation of the vacuole is apparently a much more complicated procedure than had formerly been considered. According to Guilliermond (1929), the vacuoles in the meristematic cells of flowering plants, as a result of the hydration and swelling of numerous and tiny mitochondria-like bodies, contain a thick colloidal solution. As the cell differentiates, these bodies swell into small, round vacuoles which fuse into one single large vacuole, making the bulk of the cell. The large liquid vacuoles originating from the mitochondria-like bodies by hydration of their contents ultimately contain a very dilute colloidal solution which stains faintly as a whole. The whole system of vacuoles in any given cell at any stage is termed the "vacuome." The colloidal substances in the vacuoles of flowering plants differ widely in different cases. According to Guilliermond, the vacuolar contents are most often composed of alcohol-soluble protein mixed with phenol compounds of the tannin group and closely related anthocyanin compounds all of which absorb intravivam dyes.

The vacuome is considered to be always present in any cell, and it may appear in two altogether different aspects according to the age of the cell: (a) It may be distributed throughout the cytoplasm as numerous tiny thick bodies composed of a concentrated solution of colloids and showing as mitochondria-like grains or threads. (b) It may be in the form of one or a few large liquid vacuoles, where colloids are in weak solution, these vacuoles developing from the small, mitochondria-like bodies by hydration and coalescence. Either of these aspects may be converted into the other. The vacuoles may be made to give up water when the cell is dehydrated. They shrink and break down into thread-like thick drops, as is shown when a seed begins to lose water preparatory to maturing and as can be experimentally induced by plasmolyzing cells.

B. COMPOSITION

The vacuole or cell sap may contain the following materials:

1. **Water.**—As much as 98 per cent of the cell sap may consist of water.
2. **Inorganic Salts.**—Any of the inorganic salts that are absorbed by the plant from the soil may be found in the cell sap, but those which occur in the greatest abundance are the salts of Na, K, Mg, and Ca.
3. **Carbohydrates.**—The carbohydrates that are generally found in the cell sap include cane sugar, maltose, glucose, fructose, dextrans, and inulin.
4. **Nitrogenous Compounds.**—The principal nitrogenous compounds are proteins, amino acids, amides, proteoses, and peptones.
5. **Soluble Alkaloids and Glucosides.**—These products which appear to be waste products of the cell include the tannins, amygdalin, anthocyanin, and the mustard-oil glucosides.

6. Enzymes.—The principal enzymes that may be found in the cell sap are diastase, invertase, lipase, inulase, and proteolytic enzymes.

7. Organic Acids.—These compounds are present either as acids or in combination with mineral bases. The principal organic acids present in the vacuole are oxalic, malic, citric, tartaric, tannic, acetic, and formic. The last two seem to be very widespread in their distribution and are probably present in every living cell. According to their origin, the materials found in the vacuole fall into three general groups: (a) those materials which have been absorbed by the cell from its exterior, (b) the materials which have been synthesized by the protoplasm, and (c) the waste products or excretions which arise in the protoplasm as a result of its life functions. It is evident, therefore, that the composition of the vacuole will be an extremely variable one, since the functions which give rise to the materials therein are dependent upon and influenced by a great many factors. Priestley and Wormald (1924, 1925) studied the composition of the sap exuded by root pressure from the cut vines of the grape. While these data are more applicable to the subject of translocation in plants, they are presented here as an example of the contents of the specialized conducting cells. The following table shows the relative amount and concentration of the various constituents of the sap:

Constituents	Grams per liter of sap	Constituents	Grams per liter of sap
Ash.....	0.56	Fructose.....	0.04
Total solid.....	1.56	Cane sugar.....	0.008
P ₂ O ₅	0.032	Inorganic nitrogen.....	0.023
Reducing sugars.....	0.33	Organic acids, oxalic, tartaric, malic, and succinic..	0.56
Glucose.....	0.29		

About one-third of the total solid was composed of inorganic matter and the rest organic. The organic constituents were chiefly sugar and organic acids. The sugars present were glucose, fructose, and a small amount of cane sugar. The organic acids present were oxalic, tartaric, malic, and succinic, and the total quantity of those exceeded that of the sugars present. The mineral salts present were the chlorides, sulphates, nitrites, silicates, and phosphates of Na, Ca, Fe, Mg, and, to a lesser extent, manganese and aluminum. Diastase, peroxidase, and a small amount of catalase were the only enzymes that could be detected under the conditions of the experiment.

C. CONCENTRATION

The concentration of the cell sap is generally expressed in terms of osmotic pressure. By the osmotic pressure of the cell sap is meant the pressure that the water in the vacuole would be capable of exerting upon

the protoplasm and the cell wall if the cell were placed in pure water. This definition of osmotic pressure is based on the assumption that the cell wall is absolutely rigid and that the protoplasm will allow water freely to enter and that neither will allow dissolved materials to escape from the vacuole. The osmotic pressure of the cell sap can also be defined by stating that it is the pull that the cell sap is capable of exerting upon pure water if it were separated from it by a perfectly semipermeable membrane. The magnitude of the osmotic pressure of the cell sap is commonly expressed in terms of atmospheric pressure. The osmotic pressure or pull of the cell sap varies directly with its concentration and is due to certain relationships of membranes and solutions which will subsequently be discussed in Chap. II.

1. Factors That Influence the Concentration of the Cell Sap.—The factors which influence the concentration of the cell sap are (a) the habitat of the plant, (b) the kind of plant, (c) the portion of the plant, (d) the age of the tissues, (e) the time of sampling, *i.e.*, season, day or night.

a. The Habitat of the Plant.—Considerable experimental work has been done on the effect of environment upon the concentration of the cell sap. Stange (1892) found that the osmotic pressure of the cell sap of both roots and stem could be raised by increasing the concentration of the medium in which the plants were grown. Thus the cell sap of the cells of wheat, beans, and peas grown in ordinary soil or weak solutions had an osmotic pressure equivalent to 0.25 *M* KNO_3 , but this pressure could readily be increased to 0.6 *M* KNO_3 by increasing the concentration of the medium in which the plants were grown. Hill (1908) worked with root hairs of *Salicornia* and *Suaeda*—plants which grow in salt marshes—and showed that the osmotic pressure of their cell sap was not constant. The osmotic pressure of the cell sap of these root hairs in their natural habitat was equivalent to 6.7 per cent NaCl. After being in fresh water for 5 hr. their osmotic equivalent was 2.4 per cent NaCl and after 12 hr. more it was only 1.9 per cent NaCl. The cells of roots which were grown in fresh water sod were placed in 3.5 per cent NaCl. The cells all plasmolyzed, but after standing all night in the solution, 81 per cent were apparently normal and 19 per cent were only slightly plasmolyzed. These experiments show that the root hairs can accommodate their osmotic pressure or concentration to that of the soil solution. Ohga (1926) noted when wheat and buckwheat seedlings were placed in a sugar solution of higher molecular concentration than that necessary to plasmolyze the cells that they wilted at first but recovered in time and continued to live. The maximum increase in osmotic pressure in the roots due to placing them in sucrose solution was about 0.8 *M* or 18.7 atmospheres. Drabble and Drabble (1907) examined 50 species of plants growing under various conditions of water supply and found the osmotic pressure of the cells varied from 4 to 20 atmospheres. Their conclusions concerning the relation between environment and the osmotic pressure of the cell sap of plants have been verified by other investigators and can now be stated under the general law, that "In plants of the same species growing under the same conditions of water supply the osmotic strength of the cell sap is generally the same and that in any area the osmotic strength of the cell sap varies indirectly with the physiological scarcity of water." Korstian (1924) states that the osmotic pressure in plants is more rapidly changed by fluctuations in the moisture conditions of the site than by any other environmental factors. During the growing season the lowest sap densities occur in the forest types which are well supplied with available moisture, whose

plants are best adapted to secure it and in which the complex of conditions is more favorable to plant growth. The highest densities of cell sap occur on the most adverse sites for a moisture supply which is due either to the absence of water or to a high salinity of the soil. Eaton (1927) grew wheat and salt brush on soils of different salinity for the purpose of comparing the extent to which they take up salts and increase their cell sap concentrations. He obtained evidence that plants do differ materially in this respect. The sap of the wheat plant in this experiment was 98 per cent more concentrated on the soil with the higher salt content than on the non-saline soil, while a corresponding difference of but 42 per cent was shown for the salt brush.

Fitting (1911) has given us the most complete record of the osmotic pressures in the cell sap of desert plants. He worked in the Sahara desert and examined 46 species of plants growing in oases, saline soils, rocky wastes, and sand dunes. His observations may be summarized briefly as follows:

Number of plants	Per cent of total	Osmotic pressure	
		Salt equivalent	Atmospheres
10	21	3.0 N (KNO ₃) or above	100 or above
16	35	1.5 N (KNO ₃) or above	53 or above
24	52	1.0 N (KNO ₃) or above	34 or above
5	11	0.3 to 0.6 N (KNO ₃) or above	10 to 20 or above

The highest osmotic pressures were found in the plants growing in dry soil and no extremely high pressures were met with in moist non-saline soil. The work of Fitting has been verified by Ilin and Nazarova (1915) and by Keller (1920) working in Russia. They observed a close connection between the degree of osmotic pressure and the amount of moisture in the soil. The higher the moisture content of the soil the lower is the osmotic pressure in the roots. Harrington and Hibbard (1916) found in the case of corn plants grown in soils with varying degrees of moisture that the osmotic pressure of the cell sap of the root cells was highest in those roots growing in the soil with the lowest moisture content.

Harris, Lawrence, and Gortner (1915 to 1921) have studied the concentration of the cell sap of a large number of different plants growing under a wide range of conditions. Their investigations include not only plants growing in widely distributed geographical areas of North America but also those growing in different habitats of the same area. In an investigation of the spring flora of the mesophytic region of Cold Spring Harbor, N. Y., and that of the desert region of Tucson, Ariz., they reported the following: At Cold Spring Harbor 50 per cent of the pressures were equal to 10.5 atmospheres or lower, while at Tucson in the desert 50 per cent of the pressures equalled 15.7 atmospheres or above. At Cold Spring Harbor only 3 per cent of the plants exceeded a pressure of 20 atmospheres, while at Tucson 30 per cent of the pressures exceeded this figure. The maximum pressure observed at the former location was 30 atmospheres, while the highest pressure at the latter station was 65 atmospheres. The average pressure of plants growing at Cold Spring Harbor was 14.4 atmospheres as compared to an average pressure of 38.8 atmospheres of those growing on the coastal slopes of Jamaica. Certain marine mangroves which grow in salt marshes showed a concentration equivalent to 50 atmospheres or more, while others which grow in nearly fresh water showed a concentration only one-half as great. For plants growing in the same general region but under widely different habitats, the investigations in Jamaica can be used as an example. The average

osmotic pressure of the plants growing in certain ravines or on certain slopes that were favorable to a water supply was 8.9 atmospheres, while those growing on slopes that were more arid had an average pressure of 12.07 atmospheres. The plants of the most xerophytic of the habitats had a concentration of cell sap of from 30 to 35 per cent higher than that of the most favorable areas of water supply. Roberts (1916) showed that the concentration of the cell sap of the root hairs of alfalfa, corn, cabbage, radish, pea, and sunflower grown in moist air was equivalent to 5.1 to 7.7 atmospheres so that under this condition there was a minimum difference of 4 atmospheres upon the inside and outside of the root-hair cell. By growing the roots of radish in a series of increasing concentrations of cane sugar from 0.02 *M* to 0.65 *M*, she showed that the cell sap of the root hairs increased directly with the concentration of the external medium and maintained an osmotic pressure of from 4 to 6 atmospheres above it.

McCool and Millar (1917) found that the osmotic pressure in the roots and tops of Canada pea and wheat and corn seedlings is indicative but not directly proportional to the density of the solution in which they are grown. The concentration of the soil solution was varied by adding solutions of $\text{Ca}(\text{NO}_3)_2$, MgSO_4 , and K_3PO_4 . The following figures show the variation of the osmotic pressure of the soil solution and the osmotic pressure of the corn roots growing therein:

Osmotic pressure of the soil solution, atmospheres	Osmotic pressure of sap of root cells, atmospheres
1.21	4.59
1.99	5.48
3.38	6.61
4.96	7.51
7.22	8.19

The application of the various mineral nutrients to the soil as fertilizers generally results in increased concentration of these elements in the cell sap (McCool and Weldon, 1928). It appears, however, that unless there is considerable contrast between two environments the osmotic value of the expressed sap cannot be taken as a safe criterion of the type of environment (Meyer, 1927).

Magistad and Truog (1925) found that the application of fertilizer in the hill increases the osmotic pressure of the sap of corn plants which in turn lowers the freezing temperature of the plants from one to two degrees centigrade. This is often sufficient to prevent plants from being frozen by late spring frosts if they are not too severe. The greatest benefits in this regard would be derived from the application of fertilizers to peat, muck, or other soils of low-soluble salt content.

b. The Kind of Plant.—Fitting (1911) observed that the concentration of the cell sap is highest in trees and shrubs and lowest in the annuals. Harris and Lawrence (1916) in their work at Tucson, Ariz., reported the following average determinations of the cell-sap concentration:

Kind of plants	Osmotic pressure of cell sap, atmospheres
Trees and shrubs.....	28.10
Dwarfs and half shrubs.....	21.45
Perennial herbs.....	16.35
Winter annuals.....	14.73

The osmotic pressure of the sap of trees and shrubs growing at Tucson, Ariz., Jamaica, and Cold Spring Harbor, N. Y., was found by Harris and

others (1921) to be 30.5 per cent higher than that of the herbaceous plants growing in the same region. Harris (1918) observed that the cell sap of epiphytic plants is only one-third to two-thirds as concentrated as that of the terrestrial plants. It was observed by him and is considered a general biological law that the conductivity of the sap of herbaceous plants is distinctly higher than in woody species. The concentration of ionized electrolytes is thus lower in woody forms than in herbaceous forms, although the reverse is true in regard to the total solutes. It was also observed by Korstian (1924) that the concentration of the cell sap of woody species is much higher than that of herbaceous species.

The leaves of herbs have a sap that has a lower osmotic pressure, lower solid matter content, and lower colloidal content than sap expressed from the leaves of trees and shrubs growing in central Ohio (Meyer, 1927).

The shrubs, in general, showed values for these physical properties intermediate between those for trees and herbs.

Harris and Lawrence (1916) studied the osmotic pressure of the cell sap of the mistletoes growing on 20 different hosts. They found the average pressure for the parasites to be 14.43 atmospheres and that of the hosts to be 13.59 atmospheres. The osmotic pressure of the leafless species of mistletoe is distinctly lower than that of the leafy species.

Harris and others (1925) found that the sulphate content of the leaves of the upland varieties of cotton is higher than that of the Egyptian variety, the differences ranging from 3 to 4 g. per liter. This is just the opposite from the chloride content, the Egyptian types taking up larger quantities of chlorides than the upland types. All of the Egyptian varieties considered have a higher osmotic pressure than the upland varieties.

c. *The Portion of the Plant.*—Hannig (1912) determined the relative concentration of the cell sap in leaves and roots of a large number of different plants. His observations are expressed as follows:

Percentage of plants examined	Ratio of the concentration of the sap of the leaves to that of the roots
14	1
51	1.25
12	1.5
23	2

Dixon and Atkins (1916) found that the osmotic strength of the cell sap of the leaves was greater than that of the roots. The concentration of the sap of the leaves of *Ilex aquifolium* varied from 13 to 15 atmospheres, while that of the roots varied from 7 to 10 atmospheres. The leaves of *Iris* had a pressure of 13 atmospheres and the roots a pressure of 9 atmospheres. Lutman (1919) made an extended study of the osmotic pressures in the cells of the various organs of the potato at various

stages of growth. He also observed the osmotic pressures in several plants closely related to the potato or closely resembling it in the manner of storing food. He found that the normal pressure in the seed tubers as they are taken from storage is between 7 and 10.3 atmospheres and that the sprouts which come from these tubers not in the soil exhibit a pressure slightly in excess of that of the tubers themselves. He found that the juice of the leaves of the young plant showed a higher osmotic pressure than that of the stalk and that the tubers as they develop maintain an almost constant pressure until maturity. The osmotic pressure of the sap of the growing tubers is always intermediate between that of the sap of the stalks and the roots whose osmotic pressure is always the least of any of the organs of the potato plant. Garden beets examined on Sept. 28 showed a pressure in the leaf sap of 8.83 atmospheres and a pressure in the root sap of 11.81 atmospheres. The sugar beets examined at the same time showed a pressure of 12.21 atmospheres for the sap of the leaves and of 17.18 atmospheres for the roots. According to Chandler (1914), the molecular concentration of the leaves of fruit trees is generally considerably greater than that of the fruit except in the case of some ripe fruits. The concentration of the cell sap of the leaves at different heights of insertion on the stem has been studied by Dixon (1914), Harris, Gortner, and Lawrence (1917), Korstian (1924), and Hurd-Karrer (1925). Dixon found that the leaves of wistaria at a height of 3 ft. above the ground had a concentration of 5.25 atmospheres, while the leaves at a height of 27 ft. had a sap concentration of 6.61 atmospheres. The leaves of the elm 1 ft. from the ground showed a sap concentration of 9.2 atmospheres, while those at a height of 10 ft. showed a pressure of 12.4 and 18.6 atmospheres in the shade and sun, respectively. Harris and others (1917) made determinations of the osmotic concentration of the leaf sap at different levels on 26 trees belonging to 12 species and concluded that the concentration of the leaves as measured by the freezing-point lowering method increases from lower to higher levels almost without exception. The following are the results that they obtained with *Betula lutea* and *Fagus grandifolia*:

Name of plant	Date	Height of leaves, feet	Osmotic pressure of cell sap, atmospheres
<i>Betula lutea</i>	July, 1914	11	12.6
<i>Betula lutea</i>	July, 1914	25	14.1
<i>Betula lutea</i>	July, 1914	39	15.1
<i>Betula lutea</i>	July, 1914	52	16.1
<i>Betula lutea</i>	July, 1914	66	15.6
<i>Fagus grandifolia</i>	August, 1913	19	17.33
<i>Fagus grandifolia</i>	August, 1913	64	21.92

Korstian also (1924) demonstrated an osmotic gradient in the cells of plants. In the case of the yellow pine the 2-year-old needles at the base of the leaves had a sap concentration equivalent to 17.3 atmospheres while at the top the osmotic pressure was equivalent to 18.5 atmospheres. Hurd-Karrer (1925) determined the concentration gradient in the juice of corn stalks as measured by the specific gravity of the expressed sap. The plants used were from 8 to 11 ft. high with large, but immature, ears. The sap from each internode showed a gradual gradation upward, the specific gravity of the sap of the first internode being 1.0347, while that of the thirteenth and fourteenth internode had a value of 1.0497.

The electrical conductivity is always less at the higher levels than at the lower ones, which indicates that the greater concentration of the uppermost leaves is due to the increase of non-electrolytes as sugar.

d. The Age of the Tissues.—Dixon (1912) worked with *Hedera helix* and *Ilex aquifolium*—two evergreen plants—and determined the osmotic pressure of the younger and older leaves. The following will serve as an example of his results:

Date	Plant	Kind of leaves	Concentration of the cell sap, atmospheres
Sept. 23....	<i>Ilex aquifolium</i>	Young	8.57
Sept. 23....	<i>Ilex aquifolium</i>	Mature	9.82
Oct. 25....	<i>Ilex aquifolium</i>	Mature leaves, ultimate growth	9.16
Oct. 25....	<i>Ilex aquifolium</i>	Mature leaves, penultimate growth	10.38
June 7.....	<i>Hedera helix</i>	Young mature leaves	5.12
June 7.....	<i>Hedera helix</i>	Old mature leaves	9.09

Korstian (1924) in the case of the pine found that there was a difference of from 1 to 5 atmospheres in the osmotic pressure of the young and old leaves, the young having the lower concentration. The conductivity of the sap of the older leaves was higher than that of the younger leaves and indicates that their greater concentration is due to the accumulation of electrolytes.

e. The Time of Sampling.—Since the sugars contribute to the solutes in the cell sap, the conditions that would affect their formation would modify its concentration. Shedd (1915) states large differences in the composition of the sap of the wild grape were found when it was collected at the same point on the vine at different times during the same season. The mineral constituents were generally higher during the day and the sap had a more uniform condition during the night. Harris, Hoffman,

and Lawrence (1925) noted an increase in the magnitude of the chloride concentration in Egyptian cotton plants as the season advanced. McCool and Millar (1917) found that the osmotic pressure of corn tops was lowest in the morning at sunrise and greatest at 1 p.m. The concentration of the cell sap of the leaves at sunrise was 6.06 atmospheres and at 1 p.m. it was 7.52. The osmotic pressure decreased after that period so that at 10 p.m. it amounted to only 6.72 atmospheres. The roots showed an osmotic pressure of 4.52 atmospheres at sunrise and a pressure of 6.05 atmospheres at 1 p.m. and then a decrease to 4.33 atmospheres at 10 p.m. These maximum pressures observed correspond in a general way to the maximum point of sugar production, and this fact apparently accounts for the increase in the osmotic pressures. Korstian (1924) observed that the density of the cell sap changes during the day, increasing as the day advances and decreasing toward evening. The daily minimum occurs in the early morning, indicating a relationship between concentration and photosynthesis. The same fact apparently accounts for the differences observed by Dixon and Atkins (1912) on the concentration of the cells of leaves of a north exposure and those of a south exposure. In *Hedera helix* they found that the concentration of leaves of a north exposure averaged 8.7 atmospheres while that of a south exposure averaged 9.3 atmospheres. They also observed that shaded or covered leaves always had a lower concentration than the ones exposed to the sunlight. This fact has also been observed by Lutman (1919) for the stem and leaves of potato.

2. Cell-sap Concentration and Growth.—The relationship of cell-sap concentration and the rate of growth has received considerable attention. It was observed by Chandler (1914) that the molecular concentration of the cortex sap is the lowest during the period of rapid growth and that the molecular concentration of the cortex sap is not so great during early summer with trees that have been forced into vigorous growth by heavy pruning as with trees not so pruned.

Reed (1921) investigated the relationship of growth and cell-sap concentration in the young trees of walnuts, apricot, and orange. The weekly increment in concentration, including the leaves, was determined. The more important facts observed by him are as follows: The rate of growth and sap concentration have a tendency to vary in opposite directions so that rapid growth is associated with a generally lower concentration of sap in the shoot while slower growth is accompanied by higher concentration of sap. There was a gradual increase in sap concentration as the season advanced. In the apricot tree the concentration of the sap continued to increase for some time after active growth had ceased. The average concentration of the cell sap of the apricot expressed in atmospheres by months was as follows: May, 11.84; June, 13.66; July, 14.34; August, 15.04; September, 15.18; and October, 16.48. Of several

environmental factors measured, soil moisture was the only one having an obvious effect upon sap concentration. The addition of water to the soil usually diminished the concentration of the plant sap. A concentration gradient appears to exist in the shoot. The concentration of the sap in the apical portion of the stem was greater than that in the basal region. The sap concentration of shoots in trees heavily pruned was lower than that of shoots on trees not pruned because of the more rapid growth of the former. In the case of the lemon, however, Reed and Halma (1926) found that neither severe nor moderate pruning affects the sap concentration of leaves and shoots of lemon trees for more than a few weeks after the operation. In view of these results, these authors concluded that there is something about the lemon tree which operates to maintain osmotic pressure in the face of a growth rate undergoing extreme fluctuations.

D. THE ACIDITY OF THE CELL SAP

1. Actual and Total Acidity.—The cell sap is as a rule acid and only rarely is it alkaline and then only slightly so. A P_H value on the alkaline of 7 to 8 has been observed, while on the acid side the highest acid value so far observed was 0.9 or a value equivalent to about tenth-normal sulphuric acid. The total acidity, however, is much higher than the actual acidity, as is shown from the work of Haas (1917), Atkins (1922), Smith and Quirk (1926), and Martin, Rea, and Small (1926).

Haas, who examined the more acid fruits, found the following values of acidity for the cell sap.

Plant	Actual acidity P_H value estimate in normality	Total acidity by titration
Cranberry.....	0.004 <i>N</i> *	0.917 <i>N</i>
Grapefruit.....	0.001 <i>N</i>	0.192 <i>N</i>
Apple.....	0.0004 <i>N</i>	0.071 <i>N</i>
Rhubarb (leaf stalk).....	0.0006 <i>N</i>	0.157 <i>N</i>
Orange.....	0.00016 <i>N</i>	0.094 <i>N</i>
Pineapple.....	0.000035 <i>N</i>	0.137 <i>N</i>

* This means that a 0.004*N* acid if completely dissociated would give a P_H reading equivalent to that observed.

Atkins (1922) examined the juices of various plants growing in India and reported the following results for the more common plants:

Plant	Part or tissue	P _H value	Plant	Part or tissue	P _H value
Wheat.....	{ Leaf	5.4	Cotton.....	{ Leaf	4.8
	{ Root	6.8		{ Stem	4.6
Oats.....	{ Leaf	5.4	Tobacco.....	{ Leaf	5.4
	{ Root	6.8	Sugar cane (<i>Saccharum officinarum</i>)	{ Leaf	4.8
Rice.....	{ Leaf	4.8	<i>Andropogon sorghum</i>	{ Leaf	4.8
	{ Stem	5.0		{ Spikelet	4.8
	{ Root	6.8	<i>Musa sapientum</i> (Banana).....	{ Fruit unripe	4.6 to 4.8
Castor plant....	{ Leaf	4.8		{ Leaf	4.9
	{ Flower	4.8	Tree (sp.).....	{ Berry	1.4
	{ Pith	4.6			

Smith and Quirk (1926) determined the acidity of the cell sap of the shoots and leaves of *Begonia lucerna*. This plant is the most acid on record, the leaves being the most acid and the acidity decreasing from top to base. The juice of the leaves was twice as acid as lemon juice and practically as acid as *N*/10 HCl. A considerable part of the acid is oxalic acid, although other acids are present. The hydrogen-ion concentration and total acidity of the sap of this plant ranged as follows: P_H 0.9 to 1.36, 1.22 to 2.23, and 3.30 to 3.42 for the leaves, top, and base of shoots, respectively. The total acidity (undissociated salts) for the leaves, top, and base of shoots was estimated at +250 to 263, +99 to 140, and +41 to 56, respectively. The total acidity as here expressed in terms of Fuller's scale denotes the number of cubic centimeters of *N*/1 NaOH required per liter of juice to bring it from the given P_H to P_H 8.2 (phenolphthalein neutrality). Smith and Quirk also determined the acidity of the sap of other plants according to the following table:

Plant	Tissues	P _H value	Total acidity	Plant	Tissues	P _H value	Total acidity
Oxalis.....	Leaves	1.70	+224	Sugar cane.....	Soft top	4.88	+ 37
Rumex crispus.....	Leaves	3.53	+ 66	Bananas.....	Young petiole of midrib	4.74	+ 12
Wandering Jew.....	Leaves	5.47	+ 10	White garlic....	Bulbs	3.46	+165
Pineapple.....	Leaves	4.72	+ 40	Olives.....	Young shoots	5.22	+ 52
Boston fern.....	Leaves	5.20	+ 38	Onions.....	Leaves	4.33	+ 30

Martin, Rea, and Small (1926) made a survey of 166 species of plants with especial regard to the young flowering stems and noted that the tissue reaction varied, in general, between P_H 6.0 and 4.0. The tissue of the xylem and epidermis tended to be more acid than the others. Their work indicates that some tissues may remain constant in their reaction while the reaction of others varies with the age of the plant.

Gustafson (1924) showed that in *Zea mays*, *Cucurbita maxima*, *Helianthus* sp., and *Bryophyllum calycinum* the total acid of the plant juice is not responsible for the H-ion concentration gradient found in plants and that there is no constant relation between total and actual acidity in these plants. The juice from young parts of plants requires more NaOH to neutralize it than does juice from older parts of the same plant, even when the former is nearer to the neutral point at the beginning than the latter.

2. The Relation of the Environmental Conditions to the Acidity of the Cell Sap.—The effect of the changes in the soil solution upon the acidity of the cell sap is not yet definitely known, since the data which have been presented are very conflicting. Thus Truog and Meacham (1919) grew alfalfa, clover, lupine, sorghum, buckwheat, corn, and rape on unlimed acid soil and on limed acid soil. In 12 of the 16 cases the plant juices are more acid on the unlimed soils than on the limed ones and in the opposite cases the differences are quite small. Some of their data are shown in the following table:

Plant	P_H value of juice from plants grown on	
	Unlimed soil	Limed soil
Alfalfa.....	5.78	6.03
Clover (<i>Trifolium pratense</i>).....	5.69	5.83
Soybean.....	5.81	5.94
Corn.....	5.21	5.31
Buckwheat.....	4.02	4.05

Haas (1920) found that in most cases the effect of the limed soil on the sap of the tops of alfalfa, barley, garden beans, alsike clover, mustard, timothy, and wheat was to decrease the actual acidity. He considered that his data is in favor of the suggestion of Truog (1919) that the main specific harmful influence of soil acidity on certain plants is due to its influence in preventing the plant from securing rapidly enough the bases that are needed to neutralize and precipitate acids within the plant. Clevenger (1919), however, found that the acidity of the tops of oats, buckwheat, soybeans, and cowpeas grown in limed and unlimed acid sand was higher in those plants grown in the former medium, and his conclusions are the opposite of those obtained by Truog and Meacham (1919) and Haas (1920). Miyake and Masashi (1924) in the case of oats and flax found that either phosphoric acid or potassium applied to the soil tends to raise the H-ion concentration of the cell sap while nitrogen tends to lower it. In the case of the tomato, more acid materials as determined by electro-dialysis were found in plants grown on acid soil and more basic materials in plants grown in alkaline soils.

Hoagland and Davis (1925) found that the hydrogen-ion concentration of the cell sap of normal cells remained at a practically constant P_H value of 5.2 when the cells were immersed in solutions of widely different reactions. They consider that the preservation of a definite reaction in the vacuolar sap may be essential to the normal functioning of the cell. Different types of cells may have different reactions so that the reactions of the cell sap expressed from a mass of tissue may not represent

the reactions of any particular cell. The reaction of the cell sap and that of the protoplasm are not necessarily identical. This agrees with the observations of Crozier (1919) on the acidity of the cell sap of *Valonia macrophysa*. The cell sap of this alga had a P_H of 5.0 to 6.7, the average being about 6.0, while the P_H value of the sea water in which the plant grew ranged from 8.2 to 8.3. The acidity of the sap remaining constant for a range of temperatures from 18 to 28°C. during different times of the year. Masoni (1920) observed that juices of plants maintained an acid reaction several days after contact with calcareous soil or when in contact with an excess of pure calcium carbonate.

3. General Observations.—Truog and Meacham (1919) found the juice of the alfalfa plant to be more acid in the morning than that of plants examined later in the day. In one case at 6 a.m. the P_H value of the juice was 5.97 and at 2 p.m. 6.06. In another case at 8 a.m. the P_H reading was 6.04 and at 2:30 p.m. it amounted to 6.11.

Clevenger (1919) followed the diurnal changes in the acidities of the leaves, stems, and roots of the cowpea during a 24-hr. period. The acidity of the leaves and stems was found to be highest in the morning and decreased during the day, while the acidity of the roots was found to be highest during the day.

According to Reed and Halma (1926), the H-ion concentration of both lemon and orange trees shows a rather small amount of seasonal fluctuation. There is some increase in acidity, however, during the period of rapid vegetative growth when presumably carbohydrates are being extensively oxidized.

Gustafson (1924) showed that there was an H-ion concentration gradient in corn, squash, pole bean, pumpkin, and sunflower plants. This gradient is not always in the same direction in different species or in the leaves and stems of the same species. In corn, squash, and pole bean the older leaves had a higher H-ion concentration than the younger leaves, while in pumpkin and sunflower the reverse was the case. The bases of the stems of corn, sunflower, and pumpkin had a lower H-ion concentration than the tops.

Gray and Ryan (1921) observed that the acidity of both navel and Valencia oranges was greatly reduced when a spray composed of soap, Na_2CO_3 , lead arsenate, and sulphur was applied to trees even for one season. This reduction in acidity amounted to more than 50 per cent in some cases and the arsenic compound seemed to be chiefly responsible for the effect, but the facts do not correlate the reduction of acidity with the local absorption of the spray by the fruit. The action of the spray is thought to be systemic, affecting the whole tree.

Hurd (1923) investigated the acidity of corn and its relation to vegetative vigor. She found that the concentration of titratable acid was always higher in the juice of the leaves than in that of the stalk regardless of the plant's vigor. The H-ion concentration was higher in the leaves than in the stalk in the vigorous plants only; in the stunted plants, it was greater in the stalks than in the leaves. The H-ion concentration of the tops of corn plants ranged from P_H 5.0 to P_H 5.6 and was inversely correlated with the degree of vegetative vigor induced by the environmental conditions affecting the different plots. The titratable acidity of these tops varied in the same manner, the values ranging from an average of 10 cc. of $N/20$ NaOH solution required to neutralize 10 cc. of juice from plants of the most stunted plot to 5 cc. required to neutralize the same quantity of juice from the most rapidly growing plants. The same author (1924) studied the course of the acidity changes in the cell sap of the wheat plant during different stages of growth. The acidity determinations were made on the sap at frequent intervals from the time the plants were three inches high

until they were in the flowering stage at the age of about 6 months. The titratable acidity of the juice decreases progressively sometimes to one-half the initial concentration between the ages of 2 and 6 weeks. This period is followed by one of relatively low acidity extending up to the visible approach of maturity when the acid concentration rises. The final acidity at maturity may be twice the highest seedling concentration and almost three times that of the least acid stage.

The H-ion concentration of the juice of the wheat plant does not decrease to any extent between the ages of 2 and 6 weeks. It is greatly increased during the pre-ripening period and reaches a relatively high value at the flowering stage and later. This increasing acid concentration during the final stages of growth seems to be correlated primarily with the rate of drying rather than with head formation or kernel development.

Hurd (1928) observed that the electrometric titration curve of juice expressed from wheat plants changes progressively during the seedling stage and during the maturation period. Only minor changes, correlated with environmental factors, occur during the tillering stage and most of the shooting stage. The difference in the form of the titration curve for juice of seedlings in successive stages of development indicates differences in composition associated with increasing photosynthetic activity. The end of this period of change in the curve may be interpreted as the end of the seedling stage. The specific gravity increases regularly during the maturation period and is closely correlated with the corresponding titratable acid values. Heat-coagulable proteins play a very small part in the buffer system of the wheat plant, since their removal by boiling reduces the buffer action of the juice only slightly.

Questions

1. What is a cell? Name the parts of a plant cell. Show by a diagram the location of these parts in the cell.
2. What is the cell wall? What is its origin? How does it vary in thickness? What is a pit? What is the apparent origin of the cell-wall lamellae in the bast fibers of *Linum*?
3. What is the middle lamella? When was it formed? How does it differ from the part of the wall later deposited? What is the chemical nature of the middle lamella? What is known concerning the chemical nature of the cell walls of the apical meristem?
4. By what means has the general structure of the cell wall been studied? What two characteristics do all cell walls have in common?
5. What do X-ray refraction patterns show in regard to the structural units in the cell wall? What appears to be the submicroscopic structure of the cell wall? The microscopic structure?
6. Enumerate and classify the compounds that may enter into the composition of the cell wall.
7. What is normal or typical cellulose? Name its general properties. In what cell walls is it most abundant? Name three solutions in which it will dissolve.
8. What is oxycellulose? Hydrocellulose?
9. What are hemicelluloses? Where do they occur? Of what use are they to plants?
10. What are compound celluloses? What is lignin? Name some of its properties. How is it obtained? What is lignocellulose? Where does it occur? What purpose does it serve?
11. What are suberin and cutin? Name the general characteristics of these substances. Where does each of these substances occur in the plant? In the cell wall?

12. What are the main distinctions between suberin and cutin? Where and when is suberin formed in cut potatoes? Of what importance is this formation?

13. What are the pectic substances? In what plant parts are they abundant? Where do they occur in the cell wall?

14. Why is there so much confusion in regard to their classification? Enumerate and classify the various pectic substances.

15. What is pectose? Where does it occur? By what other names is it called? What is pectin? Name its general properties. What is pectase? What salts will produce the same effect as pectase?

16. What are pectates? Pectic acid? Name three tests that can be used to distinguish the pectic substances from the rest of the cell-wall constituents.

17. Name eight or more infiltration compounds of the cell wall. What appears to be the relation of the phospholipides in the cell wall to the protoplasm of the cell?

18. What is protoplasm? Where is it located in an embryonic plant cell? In a mature plant cell? Name the general physical characteristics of the protoplasm.

19. What is its chemical composition? To what are its outstanding properties apparently due? What type of solution is the protoplasm? What three facts suggest this?

20. What is the greatest age of living plant cells that have been observed? Where? In what plants?

21. What is the cytoplasm? The ectoplast? The tonoplast? The endoplasm?

22. What function does the cytoplasm perform? What are plasmodesma? What function may they perform?

23. What is the nucleus? State some facts in regard to its general structure. What functions does it perform?

24. What are the plastids? Where do they occur?

25. What are the chloroplasts? How do they vary in shape and size? How do they increase in number? What is known concerning their structure? What function do they perform?

26. What are the leucoplasts? Where do they occur? What functions can they perform? What are the chromoplasts?

27. Why are the three types of plastids termed "homologous" structures? What are the two theories in regard to the origin of the plastids in the cell? What do variegated or white leaves show in regard to chloroplasts?

28. What are mitochondria or chondriosomes? What functions have been attributed to them?

29. What is the vacuole or cell sap? In what manner does it originate? What is the vacuome?

30. Name and classify the materials that make up the cell sap. What is the origin of these materials?

31. How is the concentration of the cell sap commonly expressed? What is meant by the osmotic pressure of the cell sap?

32. Name five factors that may influence the concentration of the cell sap. State a general law in regard to the availability of water and the concentration of the cell sap.

33. Under what conditions or in what regions do the highest concentrations of the cell sap occur? How does the concentration of the cell sap of the root hairs correspond to the medium in which they grow?

34. How does the application of mineral nutrients to the soil affect the concentration of the cell sap? Of what value may this be to the plant?

35. Under the same conditions, what plants have the highest concentration of cell sap? Which the lowest? How does the concentration of the cell sap of the roots compare with that of the top? Give examples.

36. How does the concentration of the cell sap of the lower leaves compare with that of the upper leaves? Give some specific data in this regard.

37. How does the conductivity of the cell sap from the upper portion of a plant compare with that of the lower part? What does this suggest? How does the conductivity of the cell sap of young and old tissues compare? Cause?

38. How does the concentration of the cell sap of young and old tissues compare? At what time of the day would you expect to find the highest concentration of the cell sap of stem and leaves? The lowest? Why? How does shading affect the concentration of the cell sap of leaves? Why?

39. What relationship is there between growth and cell sap concentration? Cause?

40. How do the total acidity and actual acidity of the cell sap compare? What is the general range of the actual acidity of the cell sap? The total acidity?

41. How do the conditions of the soil affect the acidity of the cell sap? Give some specific examples. How does the acidity change during the day?

42. What is known concerning the gradient of the P_H value of the cell sap of plants? How does vigor affect the H-ion concentration of the cell sap? The total acidity? How does the age of tissue affect the H-ion concentration of the cell sap? The total acidity?

Bibliography

- AHMANN, C. F., and H. D. HOOKER, 1925: The estimation of pectin and a study of the constitution of pectin, *Univ. Mo. Agr. Expt. Sta. Res. Bull.* 77.
- ALDABA, V. C., 1927: The structure and development of the cell wall in plants. I, Bast fibers of *Boehmeria* and *Linum*, *Amer. Jour. Bot.*, **14**: 16-24.
- ALLEN, C. E., 1901: On the origin and nature of the middle lamella, *Bot. Gaz.*, **32**: 1-34.
- ALVARADO, S., 1923: Die Entstehung der Plastiden aus Chondriosomen in den Paraphysen von *Mnium cuspidatum*, *Ber. d. d. bot. Ges.*, **41**: 85-96.
- ANDERSON, D. B., 1927: A microchemical study of the structure and development of flax fibers, *Amer. Jour. Bot.*, **14**: 187-212.
- , 1928: Some recent work on the structure of the plant cell wall, *Ohio Jour. Sci.*, **28**: 299-314.
- ASTRUC, A., 1903: Recherches sur l'acidité végétale, *Ann. Sci. Nat. Bot.*, **17**: 1-64.
- ATKINS, W. R. G., 1922: The H-ion concentration of plant cells, *Roy. Dublin Soc. Sci. Proc.*, n. s., **16**: 414-426.
- , 1922: The hydrogen ion concentrations of some Indian soils and plant juices, *Agr. Res. Inst. Pusa. Bull.* **136**: 1-12.
- BEER, RUDOLF, 1904: The present position of cell wall research, *New Phytol.*, **3**: 159-164.
- BELZUNG, E., 1887: Recherches morphologiques et physiologiques sur l'amidon et les grains de chlorophylle, *Ann. Sci. Nat. Bot.*, VII, **5-6**: 179-311.
- , 1891: Nouvelles recherches sur l'origine des grains d'amidon et des grains chlorophylliens, *Ann. Sci. Nat. Bot.*, VII, **13**: 1-22.
- BERNARD, CLAUDE, 1878: "Leçons sur les phénomènes de la vie," 1st ed., 1878; 2d ed., 1885, Paris.
- BRANNON, M. A., 1913: Osmotic pressure in potatoes, *Bot. Gaz.*, **56**: 433-439.
- BREDOW, HANS, 1890: Beiträge zur Kenntniss der Chromatophoren, *Jahrb. f. wiss. Bot.*, **22**: 349-414.
- CAKE, W. E., and H. H. BARTLETT, 1922: The carbohydrate content of the seed of *Asparagus officinalis*, *Jour. Biol. Chem.*, **51**: 93-102.
- CARRE, M. H., and D. HAYNES, 1922: The estimation of pectin as calcium pectate and the application of this method to the determination of the soluble pectin in apples, *Biochem. Jour.*, **16**: 60-70.

- CARRE, M. H., 1925: Chemical studies in the physiology of apples, IV; Investigations on the pectic constituents of apples, *Ann. Bot.*, **39**: 811-839.
- , 1925: The relation of pectose and pectin in apple tissue, *Biochem. Jour.*, **19**: 257-266.
- CASSTRO, N., 1906: Beiträge zur Kenntnis der Hemicellulosen, *Zeits. f. physiol. Chem.*, **49**: 96-107.
- , 1907: Ueber die in den Samenschalen von *Cucurbita pepo* enthaltenen Hemicellulosen, *Zeits. f. physiol. Chem.*, **52**: 521-525.
- CAVERS, F., 1914: Chondriosomes (mitochondria) and their significance, *New Phytol.*, **13**: 96-106, 170-180.
- CHANDLER, W. H., 1914: Sap studies with horticultural plants, *Mo. Agr. Expt. Sta. Res. Bull.* 14.
- CLAYSON, D. H. F., F. W. NORRIS, and S. B. SCHRYVER, 1921: The pectic substances of plants, Part II; A preliminary investigation of the chemistry of the cell walls of plants, *Biochem. Jour.*, **15**: 643-654.
- , and S. B. SCHRYVER, 1923: The hemicelluloses. I, The hemicellulose of wheat flour, *Biochem. Jour.*, **17**: 493-496.
- CLEVINGER, C. B., 1919: Hydrogen-ion concentration of plant juices. I, The accurate determination of the hydrogen-ion concentration of plant juices by means of the hydrogen electrode, *Soil Sci.*, **8**: 217-226.
- , 1919: Hydrogen-ion concentration of plant juices. II, Factors affecting the acidity or hydrogen-ion concentration of plant juices, *Soil Sci.*, **8**: 227-242.
- CONRAD, C. M., 1926: A biochemical study of the insoluble pectic substances in vegetables, *Amer. Jour. Bot.*, **13**: 531-548.
- COWDRY, E. V. (ed.), 1924: "General Cytology," University of Chicago Press.
- , 1926: Surface film theory of the function of mitochondria, *Amer. Nat.*, **60**: 157-165.
- CROSS, C. F., and CHARLES DORÉE, 1923: "Researches on cellulose," Longmans, Green and Co.
- CROZIER, W. J., 1919: Intracellular acidity in *Valonia*, *Jour. Gen. Physiol.*, **1**: 581-585.
- DIXON, H. H., and W. R. G. ATKINS, 1910: On osmotic pressure in plants, and on a thermo-electric method of determining freezing points, *Roy. Dublin Soc. Sci. Proc.*, n. s., **12**: 275-311.
- and ———, 1912: Changes in the osmotic pressure of the sap of the developing leaves of *Syringa vulgaris*, *Notes Bot. School Trinity Coll. Dublin*, **2**: 99-102.
- and ———, 1912: Variations in the osmotic pressure of the leaves of *Hedera helix*, *Notes Bot. School Trinity Coll. Dublin*, **2**: 103-110.
- and ———, 1912: Variations in the osmotic pressure of the sap of *Ilex aquifolium*, *Notes Bot. School Trinity Coll. Dublin*, **2**: 111-120.
- and ———, 1913: Osmotic pressures in plants. I, Methods of extracting sap from plant organs, *Notes Bot. School Trinity Coll. Dublin*, **2**: 154-165.
- and ———, 1913: Osmotic pressures in plants. II, Cryoscopic and conductivity measurements on some vegetable saps, *Notes Bot. School Trinity Coll. Dublin*, **2**: 166-172.
- and ———, 1916: Osmotic pressure in plants. VI, On the composition of the sap in the conducting tracts of trees at different levels and at different seasons of the year, *Roy. Dublin Soc. Sci. Proc.*, **15**: 51-62.
- DORÉ, W. S., 1924: Recent progress in the chemistry of pectin and its industrial applications, *Jour. Ind. Eng. Chem.*, **16**: 1042-1044.
- DORÉE, CHARLES, and E. C. BARTON-WRIGHT, 1927: Contributions to the study of lignin. I, Meta lignin a new type of alkali lignin, *Biochem. Jour.*, **21**: 290-300.
- DRABBLE, E., and HILDA LAKE, 1905: The osmotic strength of cell sap in plants growing under different conditions, *New Phytol.*, **4**: 189-192.

- DRABBLE, E., and HILDA DRABBLE, 1907: The relation between the osmotic strength of cell sap in plants and their physical environment, *Biochem. Jour.*, **2**: 117-132.
- EATON, F. M., 1927: The water requirement and cell sap concentration of Australian salt brush and wheat as related to the salinity of the soil, *Amer. Jour. Bot.*, **14**: 212-226.
- ESSELEN, G. J., 1923: A few high spots in the chemistry of cellulose, *Jour. Ind. Eng. Chem.*, **15**: 306-308.
- EYSTER, W. H., 1929: Variation in the size of plastids in genetic strains of *Zea mays*, *Science*, n. s., **69**: 48.
- FABER, O., and B. TOLLENS, 1899: Untersuchungen über die Oxycellulose, *Ber. d. d. chem. Ges.*, **32**: 2589-2601.
- FAMINTZIN, A., 1893: Sur les grains de chlorophylle dans les graines et les plantes germeantes, *Bul. de l'Acad. imp. de Sciences de St. Petersbourg*, n. s., IV, **36**: 75-85.
- FAUL, J. H., 1928: Living cells in heartwood of trees, *Science*, n. s., **67**: 296.
- FELLENBERG, T. VON, 1918: Über die Konstitution der Pektinkörper, *Biochem. Zeits.*, **85**: 118-161.
- FINK, BRUCE, 1925: Some considerations of protoplasm, *Ohio Jour. Sci.*, **25**: 99-113.
- FITTING, HANS, 1911: Die Wasserversorgung und die osmotischen Druckverhältnisse der Wüstenpflanzen, *Zeits. f. Bot.*, **3**: 209-275.
- FREMY, M. E., 1840: Recherches sur la pectine et l'acide pectique, *Jour. de Pharmacie*, **26**: 368-393.
- , 1859: Recherches chimiques sur la composition des cellules végétales, *Ann. d. Sci. Nat.*, IV, t. 12.
- FREY, A., 1926: Der heutige Stand der Micellartheorie, *Ber. d. d. bot. Ges.*, **44**: 564-570.
- , 1926: Die submikroskopische Struktur der Zellmembranen, *Jahrb. f. wiss. Bot.*, **65**: 195-223.
- , 1927: Der submikroskopische Feinbau der Zellmembran, *Die Natur. Wiss.*, **15**: 760-765.
- GARDNER, W., and A. W. HILL, 1901: II, The histology of the cell wall with special reference to the mode of connection of cells, *Phil. Trans. Roy. Soc.*, B, **194**: 83-125.
- GILSON, E., 1890: La suberine et les cellules du liège, *La Cellule*, **6**: 63.
- , 1892: La cristallisation de la cellulose et la composition chimique de la membrane cellulaire végétale, *La Cellule*, **9**: 397-441.
- GRAY, G. P., and H. J. RYAN, 1921: Reduced acidity in oranges caused by certain sprays, *Month. Bull. Dept. Agr. Calif.*, **10**: 11-33.
- GRÜSS, J., 1897: Studien über Reservecellulose, *Bot. Centrbl.*, **70**: 242-261.
- GUILLIERMOND, A., 1911: Sur la formation des chloroleucites aux dépens des mitochondries, *Compt. Rend. Acad. Sci. Paris*, **153**: 290-292.
- , 1911: Sur les mitochondries des cellules végétales, *Compt. Rend. Acad. Sci. Paris*, **153**: 199-202.
- , 1911: Sur l'origine des leucoplastes et sur le processus cytologique de l'élaboration de l'amidon dans le tubercule de la pomme de terre, *Compt. Rend. Acad. Sci. Paris*, **153**: 1492-1494.
- , 1912: Sur les différentes modes de la formation des leucoplastes, *Compt. Rend. Soc. Biol. Paris*, **73**: 110-112.
- , 1914: Bemerkungen über die Mitochondrien der vegetativen Zellen und ihre Verwandlung in Plastiden. Eine Antwort auf einige Einwürfe, *Ber. d. d. bot. Ges.*, **32**: 282-301.
- , 1929: The recent development of our idea of the vacuome of plant cells, *Amer. Jour. Bot.*, **16**: 1-23.
- GUSTAFSON, F. G., 1922: Studies of the hydrogen-ion concentration of plant juices, *Mich. Acad. Sci.*, **1922**: 49-53.

- GUSTAFSON, F. G., 1924: Hydrogen-ion concentration gradient in plants, *Amer. Jour. Bot.*, **11**: 1-6.
- , 1924: Total acidity compared with actual acidity of plant juices, *Amer. Jour. Bot.*, **11**: 365-370.
- HAAAS, A. R., 1916: The acidity of plant cells as shown by natural indicators, *Jour. Biol. Chem.*, **27**: 233-241.
- , 1917: The reaction of plant protoplasm, *Bot. Gaz.*, **63**: 232-235.
- , 1920: Studies on the reaction of plant juices, *Soil Sci.*, **9**: 341-370.
- HABER, E. S., 1928: The influence of soil reaction on the ionizable constituents of the tomato as determined by electro-dialysis, *Jour. Agr. Res.*, **37**: 101-114.
- HABERLANDT, G., 1914: "Physiological Plant Anatomy," English Trans., 4th ed. Macmillan & Co., Ltd.
- HANSTEEN-CRANNER, B., 1914: Ueber das Verhalten der Kulturpflanzen zu den Bodensalzen, III; Beiträge zur Biochemie und Physiologie der Zellwand lebender Zellen, *Jahrb. f. wiss. Bot.*, **35**: 536-598.
- , 1919. Beiträge zur Biochemie und Physiologie der Zellwand und der plasmatischen Grenzschichten, *Ber. d. d. bot. Ges.*, **37**: 380-391.
- , 1922: "Zur Biochemie und Physiologie der Grenzschichten lebender Pflanzenzellen," Kristiana, 1922.
- , 1926: Untersuchungen über die Frage ob in der Zellwand lösliche Phosphatide vorkommen, *Planta Archiv. f. wiss. Bot.*, **2**: 438-445.
- HARLOW, W. M., 1927: The chemical nature of the middle lamella, *N. Y. State Coll. Forestry Syracuse Univ. Tech. Bull.* 21.
- 1928: Contributions to the chemistry of the plant cell wall. II, Lignification in the secondary and tertiary layers of the cell wall of wood, *N. Y. State Coll. Forestry Syracuse Univ. Tech. Bull.* 24.
- HARPER, R. A., 1919: The structure of protoplasm, *Amer. Jour. Bot.*, **6**: 273-301.
- HARRIS, J. A., J. V. LAWRENCE, and R. A. GORTNER, 1915: The osmotic pressure of the juices of desert plants, *Science*, n. s., **41**: 656-658.
- and W. POPENOE, 1916: Freezing point lowering of the leaf sap of the horticultural types of *Persea americana*, *Jour. Agr. Res.*, **7**: 261-269.
- and J. V. LAWRENCE, 1916: The cryoscopic constants of expressed vegetable saps as related to local environmental conditions in the Arizona deserts, *Physiol. Res.*, **2**: 1-49.
- and ———, 1916: On the osmotic pressure of the tissue fluids of Jamaican Loranthaceae parasitic on various hosts, *Amer. Jour. Bot.*, **3**: 438-455.
- and ———, 1917: Cryoscopic determinations on tissue fluids of plants of Jamaican coastal deserts, *Bot. Gaz.*, **64**: 285-305.
- and ———, 1917: The osmotic concentration of the sap of the leaves of mangrove trees, *Biol. Bull. Marine Biol. Lab. Woods Hole*, **32**: 202-211.
- and ———, 1917: The osmotic concentration of the tissue fluids of Jamaican montane rain forest vegetation, *Amer. Jour. Bot.*, **4**: 268-299.
- and ———, 1917: Vegetable saps, *Carnegie Inst. Wash. Yearbook* **16**: 131-132.
- , 1917: Osmotic concentration of tissue fluids in relation to geographical distribution, *Carnegie Inst. Wash. Yearbook* **16**: 88-89.
- , R. A. GORTNER, and J. V. LAWRENCE, 1917: The relationship between the osmotic concentration of leaf sap and height of leaf insertion in trees, *Bull. Torrey Bot. Club*, **44**: 267-286.
- , 1918: On the osmotic concentration of the tissue fluids of phanerogamic epiphytes, *Amer. Jour. Bot.*, **5**: 490-506.
- , R. A. GORTNER, and J. V. LAWRENCE, 1921: On the differentiation of the leaf tissue fluids of ligneous and herbaceous plants with respect to osmotic concentration and electrical conductivity, *Jour. Gen. Physiol.*, **3**: 343-347.

- HARRIS, J. A., J. V. LAWRENCE, and R. A. GORTNER, 1921: The osmotic concentration and electrical conductivity of the tissue fluids of lignocous and herbaceous plants, *Jour. Phys. Chem.*, **25**: 122-146.
- and ———, W. F. HOFFMAN, J. V. LAWRENCE, and A. T. VALENTINE, 1924: The osmotic concentration, specific electrical conductivity and chlorid content of the tissue fluids of the indicator plants of Tooele Valley, Utah, *Jour. Agr. Res.*, **27**: 893-925.
- , J. V. LAWRENCE, and Z. W. LAWRENCE, 1924: The chloride content of the leaf tissue fluids of Egyptian and upland cotton, *Jour. Agr. Res.*, **28**: 695-705.
- , 1925: The accumulation of chlorides in the leaf tissue fluids of Egyptian cotton with the march of the season, *Proc. Soc. Expt. Biol. Med.*, **22**: 415-417.
- , C. T. HOFFMAN, and W. F. HOFFMAN, 1925: Sulfate content of the leaf tissue fluids of Egyptian and upland cotton, *Jour. Agr. Res.*, **31**: 653-663.
- , W. F. HOFFMAN and others, 1925: The leaf tissue fluids of Egyptian cotton, *Jour. Agr. Res.*, **31**: 1027-1035.
- , 1926: The relationship between the concentration of the soil solution and the physico-chemical properties of the leaf tissue fluids of Egyptian and upland cotton, *Jour. Agr. Res.*, **32**: 605-649.
- HAYNES, DOROTHY, 1914: The gelatinisation of pectin in solutions of the alkalis and the alkaline earths, *Biochem. Jour.*, **8**: 553-583.
- HEIN, ILLO, 1926: Changes in plastids in variegated plants, *Bull. Torrey Bot. Club*, **53**: 411-419.
- HIBBARD, R. P., and O. E. HARRINGTON, 1916: The depression of the freezing point in triturated plant tissue and the magnitude of this depression as related to soil moisture, *Physiol. Res.*, **1**: 441-454.
- HILL, T. G., 1908: Observations on the osmotic properties of the root hairs of certain salt marsh plants, *New Phytol.*, **7**: 133-142.
- HOAGLAND, D. R., and A. R. DAVIS, 1925: Suggestions concerning the absorption of ions by plants, *New Phytol.*, **24**: 99-111.
- HORNING, E. S., and A. H. K. PETRIE, 1927: The enzymatic function of mitochondria in the germination of cereals, *Proc. Roy. Soc., B*, **102**: 188-206.
- HURD, A. M., 1923: Acidity of corn and its relation to vegetative vigor, *Jour. Agr. Res.*, **25**: 457-469.
- , 1924: The course of acidity changes during the growth period of wheat with special reference to stem rust resistance, *Jour. Agr. Res.*, **27**: 725-735.
- HURD-KARRER, A. M., 1925: A concentration gradient in corn stalks, *Jour. Gen. Physiol.*, **9**: 341-345.
- , 1928: Changes in the buffer system of the wheat plant during its development, *Plant Physiol.*, **3**: 131-153.
- , 1929: Relation of leaf acidity to vigor in wheat grown at different temperatures, *Jour. Agr. Res.*, **39**: 341-350.
- ILIN, V. S., and P. S. NAZAROVA, 1915: Osmotic pressure in roots and leaves of plants with respect to the moisture content of their habitats, *Bull. Acad. Imp. Sci. Petrograd.*, 6 ser., **9**: 749-768; *Expt. Sta. Rec.*, **36**: 733.
- KAMERLING, Z., 1897: Zur Biologie und Physiologie der Zellmembran, *Bot. Centrbl.*, **72**: 49-54, 85-91.
- KELLER, B. A., 1920: The osmotic pressure of the cell sap of plants of different ecological types and different habitats, *Proc. Russ. Bot. Soc.*, **5**: 84-92.
- KLASON, P., 1911: "Beiträge zur Kenntniss der chemischen Zusammensetzung des Fichtenholzes," Berlin.
- KOPACZEWSKI, W., 1925: Sur la coagulation de la pectine, *Bull. Soc. Chim. Biol.*, **7**: 419-428.

- KORSTIAN, C. F., 1924: Density of cell sap in relation to environmental conditions in the Wasatch Mountains of Utah, *Jour. Agr. Res.*, **28**: 845-909.
- KOZLOWSKI, A., 1922: Critique de l'hypothèse des chondriosomes, *Rev. Gén. Bot.*, **34**: 641-658.
- LEE, BEATRICE, and J. H. PRIESTLEY, 1924: The plant cuticle. I, Its structure, distribution and function, *Ann. Bot.*, **38**: 525-545.
- , 1925: The plant cuticle. II, A macrochemical study, *Ann. Bot.*, **39**: 755-768.
- LEGG, V. H., and R. V. WHEELER, 1925: Plant cuticles. I, Modern plant cuticles, *Jour. Chem. Soc.*, **127**: 1412-1421.
- LEPESCHKIN, W. W., 1928: The chemical and physical composition of protoplasm, *Science*, n. s., **68**: 45-48.
- LEWITSKY, G., 1910: Über die Chondriosomen in pflanzlichen Zellen, *Ber. d. d. bot. Ges.*, **28**: 538-546.
- , 1911: Die Chloroplastenanlagen in lebenden und fixierten Zellen von *Elodea canadensis*, *Ber. d. d. bot. Ges.*, **29**: 697-703.
- LUTMAN, B. F., 1919: Osmotic pressures in the potato plant at various stages of growth, *Amer. Jour. Bot.*, **6**: 181-202.
- MACDOUGAL, D. T., and H. A. SPOEHR, 1920: The components and colloidal behavior of plant protoplasm, *Proc. Amer. Phil. Soc.*, **59**: 150-170.
- , 1926: Growth and permeability of century old cells, *Amer. Nat.*, **60**: 393-415.
- and F. L. LONG, 1927: Character of cells attaining a great age, *Amer. Nat.*, **61**: 385-406.
- and J. G. BROWN, 1928: Living cells two and one half centuries old, *Science*, n. s., **67**: 447-448.
- and G. M. SMITH, 1927: Long lived cells of the redwood, *Science*, n. s., **66**: 456-457.
- MAGISTAD, O. C. and E. TRUOG, 1925: The influence of fertilizers in protecting corn against freezing, *Jour. Amer. Soc. Agron.*, **17**: 517-526.
- MAHOOD, S. A., and D. E. CABLE, 1922: The chemistry of wood. IV, The analysis of the wood of *Eucalyptus globulus* and *Pinus monticola*, *Jour. Ind. Eng. Chem.*, **14**: 933-935.
- and ———, 1922: Comparison of wood cellulose and cotton cellulose, *Jour. Ind. Eng. Chem.*, **14**: 727-731.
- MANGIN, M. L., 1888: Sur la constitution de la membrane de végétaux, *Compt. Rend. Acad. Sci. Paris*, **107**: 144-146.
- , 1889: Sur la présence des composés pectiques dans les végétaux, *Compt. Rend. Acad. Sci. Paris*, **109**, 579-582.
- , 1890: Sur la substance intercellulaire, *Compt. Rend. Acad. Sci. Paris*, **110**: 295-297.
- , 1890: Sur les réactifs colorants des substances fondamentales de la membrane, *Compt. Rend. Acad. Sci. Paris*, **111**: 120-123.
- , 1891: Observations sur la membrane cellulosique, *Compt. Rend. Acad. Sci. Paris*, **113**: 1069-1072.
- , 1893: Sur l'emploi du rouge de ruthénium en anatomie végétale, *Compt. Rend. Acad. Sci. Paris*, **116**: 653-656.
- MARSTON, H. R., 1923: The azine and azonium compounds of the proteolytic enzymes, *Biochem. Jour.*, **17**: 851-859.
- MASON, T. G., 1920: On some factors affecting the concentration of electrolytes in the leaf sap of *Syringa vulgaris*, *Notes Bot. School Trinity Coll. Dublin.*, **3**: 67-82.
- MASONI, G., 1920: Acidity of plant roots and soil lime, *Staz. Sper. Agr. Ital.*, **53**: 421-437, *Abst. Expt. Sta. Rec.*, **49**: 121.
- MARTIN, S. H., M. W. REA, and J. SMALL, 1926: The reaction of plant tissues, *British Assoc. Adv. Sci. Rept.* **94**: 410.

- McCool, M. M., and C. E. MILLAR, 1917: The water content of the soil and the composition and concentration of the soil solution as indicated by the freezing point lowerings of the roots and tops of plants, *Soil Sci.*, **3**: 113-138.
- and M. D. WELDON, 1928: The effect of soil type and fertilization on the composition of the expressed sap of plants, *Jour. Amer. Soc. Agron.*, **20**: 778-793.
- МЕХТА, M. M., 1925: Biochemical and histological studies of lignification. I, The nature of lignin: its physiological significance and its estimation in timbers, *Biochem. Jour.*, **19**: 958-978.
- , 1925: Biochemical and histological studies of lignification. II, Histological studies on the polysaccharides and aromatic constituents of the cell wall, *Biochem. Jour.*, **19**: 979-997.
- MEYER, B. S., 1927: Studies on the physical properties of leaves and leaf saps, *Ohio Jour. Sci.*, **27**: 263-288.
- MEYERS, A., 1883: "Das Chlorophyllkorn in chemischer, morphologischer und biologischer Beziehung," Leipzig.
- MIKOSCH, C., 1885: Über die Entstehung der Chlorophyllkörner, *Sitzungsber. d. k. Akad. d. Wiss. Wien*, **92**: 168.
- MILLER, E. C., 1911: The origin of the chloroplasts in the cotyledons of *Helianthus annuus*, *Bot. Gaz.*, **51**: 378-384.
- MIYAKE, K., and A. MASASHI, 1924: On the influence of three manurial ingredients upon the hydrogen-ion concentration of the cell sap of oats and flax, *Jour. Biochem. Tokyo*, **4**: 317-321.
- MOTTIER, D. M., 1918: Chondriosomes and the primordia of chloroplasts and leucoplasts, *Ann. Bot.*, **32**: 91-114.
- , 1921. On certain plastids with special reference to the protein bodies of *Zea*, *Ricinus* and *Conopholis*, *Ann. Bot.*, **35**: 349-365.
- MURNEEK, A. E., 1929: Hemicellulose as a storage carbohydrate in woody plants with special reference to the apple, *Plant Physiol.* **4**: 251-265.
- NORRIS, F. W., and S. B. SCHRYVER, 1925: The pectic substances of plants. III, The nature of pectinogen and its relation to pectic acid, *Biochem. Jour.*, **19**: 676-694.
- O'DWYER, MARGARET H., 1923: The hemicelluloses. III, The hemicellulose of American white oak, *Biochem. Jour.*, **17**: 501-509.
- , 1928: Preliminary investigations on the constitution of the hemicelluloses of timber, *Biochem. Jour.*, **22**: 381-390.
- OHGA, I., 1926: On changes of osmotic concentration in certain plants, *Bot. Mag. Tokyo*, **60**: 587-590.
- OSTEPHOUT, W. J. V., 1906: The resistance of certain marine algae to changes in osmotic pressure and temperature, *Univ. Calif. Publ.* **2**(8).
- , 1917: Tolerance of fresh water by marine plants and its relation to adaptation, *Bot. Gaz.*, **63**: 146-149.
- POIRAULT, G., 1893: Recherches anatomiques sur les cryptogames vasculaires, *Ann. Sci. Nat. Bot.*, 7 ser., **18**: 113-256.
- POLITIS, J., 1921: Du rôle du chondriome dans la formation des essences dans les plantes, *Compt. Rend. Acad. Sci. Paris*, **173**: 98-100.
- POWELL, D., 1925: The development and distribution of chlorophyll in roots of flowering plants grown in the light, *Ann. Bot.*, **39**: 503-515.
- PRIESTLEY, J. H., and ANNIE IRVING, 1907: The structure of the chloroplast considered in relation to its function, *Ann. Bot.*, **21**: 407-413.
- , 1921: Suberin and cutin, *New Phytol.*, **20**: 17-29.
- and L. M. WOFFENDEN, 1923: The healing of wounds in potato tubers and their propagation by cut sets, *Ann. Appl. Biol.*, **10**: 96-115.
- and A. WORMALL, 1925: On the solutes exuded by root pressure from vines, *New Phytol.*, **24**: 24-38.

- PRINGSHEIM, H., and A. MAGNUS VON MERKALZ, 1919: Fermentversuche an Zellulose-abbauprodukten, *Zeits. f. physiol. Chem.*, **105**: 173-178.
- and H. MAGNUS, 1919: Über den Acetylgehalt des Lignins, *Zeits. f. physiol. Chem.*, **105**: 179-186.
- RANDOLPH, L. F., 1922: Cytology of chlorophyll types of maize, *Bot. Gaz.*, **73**: 337-376.
- REED, H. S., 1921: Growth and sap concentration, *Jour. Agr. Res.*, **21**: 81-98.
- and F. F. HALMA, 1926: Further observations on the relations between growth and sap concentration in citrus trees, *Jour. Agr. Res.*, **32**: 1177-1195.
- RHODES, EDGAR, 1925: The chemical nature of the membrane of potato cork, *Biochem. Jour.*, **19**: 454-463.
- RITTER, G. J., and L. C. FLECK, 1917: Chemistry of wood. V, Result of the analysis of some American woods, *Jour. Ind. Eng. Chem.*, **14**: 1050-1055.
- , 1925: The distribution of lignin in wood, *Jour. Ind. Eng. Chem.*, **17**: 1194-1197.
- RUDOLPH, K., 1912: Chondriosomen und Chromatophoren, *Ber. d. d. bot. Ges.*, **30**: 605-627.
- SCHIMPER, A. F. W., 1885: Untersuchungen über die Chlorophyllkörper und die ihnen homologen Gebilde, *Jahrb. f. wiss. Bot.*, **16**: 1-246.
- SCHMIDT, E. W., 1912: Pflanzliche Mitochondrien, *Progr. rei. Bot.*, **4**: 163-181.
- SCHROGER, A. W., 1917: The chemistry of wood. I, Methods and results of analysis of some American species, *Jour. Ind. Eng. Chem.*, **9**: 556-561.
- , 1917: The chemistry of wood. II, Discussion of methods and results, *Jour. Ind. Eng. Chem.*, **9**: 561-566.
- , 1917: The chemistry of wood. III, Mannan content of the gymnosperms, *Jour. Ind. Eng. Chem.*, **9**: 748-750.
- SCHRYVER, S. B., and D. HAYNES, 1916: The pectic substances of plants, *Biochem. Jour.*, **10**: 539-547.
- and E. M. Thomas, 1923: The hemicelluloses. II, The hemicellulose content of starches, *Biochem. Jour.*, **17**: 497-500.
- SCHULZE, E., 1892: Zur Chemie der pflanzlichen Zellmembranen, II, *Zeits. f. physiol. Chem.*, **16**: 387-438.
- , 1893: Zur Chemie der pflanzlichen Zellmembranen, III, *Zeits. f. physiol. Chem.*, **19**: 38-69.
- and N. CASTORO, 1902: Beiträge zur Kenntniss der Hemicellulosen, *Zeits. f. physiol. Chem.*, **37**: 40-53.
- and ———, 1903: Beiträge zur Kenntniss der Hemicellulosen, II, *Zeits. f. physiol. Chem.*, **39**: 318-329.
- and U. PFENNIGER, 1910: Ueber das Vorkommen von Hemicellulosen in den Samenhülsen von *Pisum sativum* und von *Phaseolus vulgaris*, *Zeits. f. physiol. Chem.*, **68**: 93-108.
- SCHÜRHOFF, P. N., 1924: "Die Plastiden," pp. 225, Figs. 57, Berlin.
- SEIFRIZ, W., 1920: Viscosity values as determined by micro-dissection, *Bot. Gaz.*, **70**: 360-387.
- SHARP, L. W., 1921: "Introduction to Cytology," 582 pp., McGraw-Hill Book Company, Inc., New York.
- SHEDD, O. M., 1915: Variations in mineral composition of sap, leaves and stems of the wild grape vine and sugar-maple tree, *Jour. Agr. Res.*, **5**: 529-543.
- SINGH, L., 1922: A study of the relation of pectin and acidity in jelly making, *Jour. Ind. Eng. Chem.*, **14**: 710-712.
- SMITH, E. F. and A. J. QUIRK, 1926: A begonia immune to crown gall with observations on immune or semi-immune plants, *Phytopath.*, **16**: 491-509.
- SPONSLEER, O. L., 1928: The molecular structure of the cell wall of fibers. A summary of x-ray investigations, *Amer. Jour. Bot.*, **15**: 525-537.

- SPONSLER, O. L., 1929: Mechanism of cell wall formation, *Plant Physiol.*, **4**: 329-337.
- STANGE, B., 1892: Beziehungen zwischen Substratkonzentration, Turgor, und Wachstum bei einigen phanerogamen Pflanzen, *Bot. Zeitung.*, **50**: 253-259, 273-285.
- STERN, A. L., 1904: The so-called hydro-cellulose, *Jour. Chem. Soc. (London)*, **85**: 336-340.
- STOUT, A. B., 1915: The establishment of varieties in Coleus by the selection of somatic variations, *Carnegie Inst. Wash. Pub.* **218**: 1-80.
- THATCHER, R. W., 1922: The role of celluloses in plant life, abs. in *Science*, n. s., **55**: 80.
- TOTTINGHAM, W. E., R. H. ROBERTS, and S. LEPKOVSKY, 1921: Hemicellulose of apple wood, *Jour. Biol. Chem.*, **45**: 407-414.
- TRUOG, E., and M. R. MEACHAM, 1919: Soil acidity. II, Its relation to the acidity of the plant juice, *Soil Sci.*, **7**: 469-475.
- TUPPER-CAREY, R. M., and J. H. PRIESTLEY, 1923: The composition of the cell wall of the apical meristem of stem and root, *Proc. Roy. Soc., B*, **95**: 109-131.
- and ———, 1924: The cell wall in the radicle of *Vicia faba* and the shape of the meristematic cells, *New Phytol.*, **23**: 156-159.
- TUTIN, F., 1921: The behavior of pectin towards alkalis and pectase, *Biochem. Jour.*, **15**: 494-498.
- , 1923: A note on the hydrolysis of pectin, *Biochem. Jour.*, **17**: 83-84.
- , 1923: Pectin and its hypothetical precursor, protopectin, *Biochem. Jour.*, **17**: 510-514.
- TWISS, W. C., 1919: A study of plastids and mitochondria in *Preissia* and corn, *Amer. Jour. Bot.*, **6**: 217-235.
- VAN WISSELIINGH, C., 1888: Sur la paroi des cellules subéreuses, *Arch. Néerl. des Sc. Exp. Nat.*, **22**: 253.
- , 1892: Sur la lamelle subéreuse et la subérine, *Arch. Néerl. des Sc. Exp. Nat.*, **26**: 304-353.
- , 1894: Sur la cuticularisation et la cutine, *Arch. Néerl. des Sc. Exp. Nat.*, **28**: 373-410.
- VON SCHMIDT, M., 1903: Zur Kenntniss der Korksubstanz, *Sitzungsber. d. k. Akad. d. Wiss. Wien*, 112 abt., 11 b., *Bot. Centrbl.*, **96**: 318.
- , 1910: Zur Kenntniss der Korksubstanz, *Monatshefte f. Chem.*, **31**: 347.
- , 1910: Zur Kenntniss der Korksubstanz, III, *Sitzungsber. d. k. Akad. d. Wiss. Wien*, **119**: 233-242.
- WEIMER, J. L., and L. L. HARTER, 1921: Wound cork formation in the sweet potato, *Jour. Agr. Res.*, **21**: 637-647.
- WOOD, F. M., 1924: Contributions to an investigation of the chemical nature of the cellulose membrane, *Ann. Bot.*, **38**: 273-298.
- , 1926: Further investigations of the chemical nature of the cell wall membrane, *Ann. Bot.*, **40**: 547-571.
- WORMALL, ARTHUR, 1924: The constituents of the sap of the vine, *Biochem. Jour.*, **18**: 1187-1202.
- WURDACK, MARY E., 1923: Chemical composition of the walls of certain algae, *Ohio Jour. Sci.*, **23**: 181-192.
- ZIRKLE, CONWAY, 1926: The structure of the chloroplast in certain higher plants, I, II, *Amer. Jour. Bot.*, **13**: 301-342.
- , 1927: The growth and development of plastids in *Lunularia vulgaris*, *Elodea canadensis* and *Zea mays*, *Amer. Jour. Bot.*, **14**: 429-446.

CHAPTER II

SOLUTIONS AND MEMBRANES IN RELATION TO THE PLANT CELL

In considering the relation of solutions and membranes to the physiological functions of the plant, the student should keep the two following salient facts clearly in mind as a background for the discussion: (1) Owing to the structural nature of the plant cell, all materials that enter or leave a plant or that move from one cell to another must pass through membranes. (2) Through the cell walls, protoplasm, and vacuoles of the living cells that compose a green plant, water is continuous from the exterior walls of the root hairs which come in contact with the soil particles to the exterior surface of the outer cells of the leaves which are exposed to the air. On this account and because membranes must be penetrated, all materials that enter a plant, whether from the soil or from the air, or that migrate from one part of the plant to another must do so dissolved in water. The entrance of water and dissolved substances into a plant and their translocation after they have once entered depend thus upon certain behaviors and relationships of membranes and solutions. In order to understand how materials enter a plant or how they migrate in it, one must have a considerable knowledge of the behavior of membranes and solutions, and for that reason it is the intention here to discuss in a brief and elementary manner some of the more important facts in regard to them.

I. SOLUTIONS

A. THE NATURE

A solution may be defined as a homogeneous mixture of two or more substances having the same physical and chemical properties throughout, the proportion of whose components may be altered continuously within certain limits without producing any abrupt change in any property of the mixture. The term "true solution" is now frequently used to designate a mixture of the nature above described to distinguish it from a colloidal solution which is a heterogeneous mixture occupying an intermediate position between a true solution on the one hand and the more pronounced heterogeneous mixtures called "suspensoids" on the other. The most important difference between a true solution and a colloidal solution is the difference in the degree of subdivision or dispersion of the dissolved substances. In a true solution the dissolved substance or substances are

generally in the ionic or molecular condition and the magnitude of the particles is $1\mu\mu^1$ or less in diameter, while in a colloidal solution the degree of dispersion is not so great and the particles vary from $1\mu\mu$ to $\frac{1}{10}\mu$ in diameter. True solutions may be of three general types, gaseous, liquid, or solid; but in plant physiology we are concerned wholly with liquid solutions, and it is to this type that our attention will be devoted.

In a solution, that component which is present in the larger proportion is called the "solvent" while the component or components which are present in smaller amounts are termed the "solute" or "solutes." It is generally stated that the solute is dissolved in the solvent, but it should be remembered that this method of designation is purely arbitrary and does not necessarily imply that one component possesses greater solvent powers than the other. The case of a solution of two liquids that are miscible in all proportions, as alcohol and water, is illuminating in discussing this relation of solvent and solute. If we are considering a 1 per cent solution of alcohol in water, we say that the alcohol is dissolved in water, although it would be just as correct to say that the water is dissolved in the alcohol. If the concentration of alcohol is 51 per cent, it is spoken of as the solvent and the water is termed the solute. If there is a 50 per cent solution of alcohol in water, however, either liquid may be called the solvent and either the solute. Water is practically the only solvent that functions in plants, but the solutes concerned are numerous and include all the soluble inorganic salts which may be present in the soil, as well as oxygen, carbon dioxide, sugars, organic acids, and various other soluble organic compounds.

B. CONCENTRATION

There are numerous ways in which the concentration and of a solution may be expressed, but the four following are t generally used.

1. In Terms of Percentage.—This method does not sh number of molecules of the solute that are present in the many of the physical reactions of solutions are resultat number of molecules present in the solvent, the percei stating the concentration of solutions is not a very desira

2. In Terms of Gram-molecular Weight or Formula Liter of Solution.—A solution made up after this manner "molar," "formal," "molecular," "gram-molecular," or normal" solution. It is made by dissolving as many grams of a s as there are units in its molecular weight so as to make 1 l. of sc Thus, in the case of sulphuric acid (H_2SO_4), the molecular weight of w is 98.08, a molecular solution would contain 98.08 g. of H_2SO_4 in 1 l. .

$$1\mu = \frac{1}{1,000} \text{ mm.} \quad 1\mu\mu = \frac{1}{1,000,000} \text{ mm. or } \frac{1}{1,000} \mu.$$

solution. In the case of hydrochloric acid, the molecular weight of which is 36.46, a molecular solution would contain 36.46 g. of HCl in 1 l. of solution.

3. **In Terms of Equivalent Weight per Liter of Solution.**—An equivalent solution is one which contains 1 g. atomic weight of hydrogen or its equivalent per liter. A solution made up after this manner is also termed an "equivalent normal solution." In the case of monovalent compounds, a molecular solution and equivalent solution are one and the same. In the case of bivalent compounds, however, an equivalent solution contains only one-half the molecular weight of the substance in grams dissolved in water so as to make 1 l. of solution. An equivalent solution of H_2SO_4 would thus contain 49.04 g. of this acid in 1 l. of solution. All equivalent solutions, regardless of the substances which compose them, thus contain the same number of hydrogen ions or their equivalent.

4. **In Terms of Osmotic Pressure.**—In biological work the concentration of a solution is frequently stated in terms of the osmotic pressure which would be produced if the solution were separated from pure water by a perfectly semipermeable membrane. The value of this osmotic pressure is commonly expressed in units of atmospheric pressure.

C. DIFFUSION

One of the distinct characteristics of a solution is the property of diffusion or the ability of the molecules or ions of the solvent and solute to move more or less freely throughout it. For a clear understanding of the entrance and translocation of materials in plants, the following simple pertinent facts in regard to the behavior of solvent and solutes in a solution must be remembered: (1) The molecules or ions of the solutes move or diffuse constantly throughout the solution. (2) The molecules or ions of the solute and solvent move in the solution in contact with each other. (3) When more than one solute is present the molecules or ions of each solute move independently of each other. (4) More molecules or ions of a given solute move from the higher toward the lower concentration of the solute in the opposite direction. (5) More molecules of the solvent move from the higher toward the lower concentration of the solute than in the opposite direction. These properties of diffusion bring about a uniform distribution of the solute or solutes throughout any given volume of solution. These facts in regard to the diffusion of the solute and the solvent can best be understood by considering a hypothetical case as diagrammed in Fig. 4. Let us assume that we have two solutions A and B in which water is the solvent and NaCl and KNO_3 the solutes. Solution A has a concentration $N/10$ NaCl and $3N/10$ KNO_3 , which makes a total concentration of four-tenths normal.

Solution *B* has a concentration of $N/10$ KNO_3 and $2N/10$ $NaCl$, making a total concentration of three-tenths normal. Now let solution *A* be placed in compartment *A* of a vessel and solution *B* in compartment *B* of the same vessel and the partition separating the two solutions be removed without disturbing them, thus allowing them to come in direct contact with each other. Let us now consider the behavior of the solutes and solvent when the two solutions thus come in contact.¹




FIG. 4.—Diagrams showing the direction of diffusion of solutes. L

Let us consider first the behavior of the molecules of $NaCl$ moving from *A* to *B* and the number moving from *B* to *A*, since the concentration of $NaCl$ in *B* is greater than in *A*. For the same reason the number of molecules of KNO_3 moving from *B* in a unit of time is greater than the number moving from *A* to *B*. The total number of molecules moving from *A* to *B* is less than the number moving from *B* to *A*, since the concentration of solutes in *A* (four-tenths normal) is higher than in *B* (three-tenths normal). Let us now consider the diffusion of the solvent. Since the total concentration

¹ For simplicity the two salts are considered as non-ionizing. The concentration, and the fact of their ionization

is equal to four-tenths normal and that in solution *B* to three-tenths normal, the concentration of the solvent in solution *A* is lower than the concentration of the solvent in solution *B*. The number of molecules of the solvent moving from *A* to *B* in a unit of time is therefore smaller than the number moving from *B* to *A*. These inequalities in the rates of diffusion of the solutes and solvent become less and less until the concentration of the two solutes becomes equally distributed throughout the solution. The independent rate of diffusion of the solutes and solvent of this solution can perhaps be better understood by considering the diagrams in Fig. 4, which represent the diffusion gradient or difference in concentration of each of the constituents. These diagrams show that the greater the difference in concentration of any component between two points or the steeper the diffusion gradient the more rapid the rate of movement or diffusion. Figure 4 also illustrates the rate of diffusion of the solutes and solvent between any two points in the solution after equilibrium has been reached.

IVES]

used in relation to solutions of an artificial origin. The term *membrane* and includes on the one hand the tubes, scales of bulbs, or the like, and on the other hand only the parts of the cell wall or even only the surface films of the cell wall. The consistency of a membrane may range from a liquid to a solid and ranges from a membrane which can be observed only with the microscope to a membrane whose thickness can easily be measured. The performance of experiments to determine the permeability of artificial membranes of collodion, gelatin, etc. are frequently used, since it has been found that natural membranes show in many cases a definite permeability toward solutions.

The capacity for allowing substances to pass through a membrane is said to be permeable to a substance if the substance is able to pass through and impermeable if it is not. A membrane which will allow the passage of water but not the solute is called a "semipermeable membrane" or a membrane for allowing substances to pass through with a certain permeability." Membranes differ not only in their permeability to a given substance but also in that their permeability is affected by general environmental factors, so that

a membrane may have as many degrees of permeability toward a given substance as there are environmental conditions under which it may be placed. In speaking of the permeability of a membrane, therefore, it is necessary to define the system with which it is in contact.

None of the artificial membranes that have been made is perfectly semipermeable, although some of them prevent all but a trace of the solute from passing through. The nearest approach to a perfect semipermeable membrane is one of copper ferrocyanide in its relation to a solution of cane sugar in water. This membrane allows the water to diffuse through it readily but prevents almost completely the passage of the sugar. The cytoplasmic layer in plant cells behaves frequently as a more or less perfectly semipermeable membrane to various water solutions, although it is now considered that it does not function to nearly so great a degree in that regard as formerly was supposed. There are some cases also where the cell walls behave as semipermeable membranes, as will be discussed later.

B. IMBIBITION OF WATER

The term "imbibition" as here used means the attraction of substances for water, a phenomenon which is especially characteristic of colloidal material in the gel condition. This process is best illustrated




FIG. 5.—Diagram to illustrate that water is continuous from the vacuole of one cell through the protoplasm and cell wall to the vacuole of the adjoining cell. Description in the text.

by the intake of water by dry wood, gelatin, starch grains, and dry seeds. Each particle of such substances has an attraction or affinity for water and will take it up from the surrounding medium against enormous pressures which vary with the nature of the imbibing material and its water content. The water so attracted arranges itself around the particles in the form of films so that as the amount of water imbibed increases, the thickness of the watery films increases and thus the particles that compose the substance are crowded farther and farther apart. The limit to the distance that these particles may be separated from each other by the water thus taken up will depend upon the cohesive force of the particles of that substance. Thus in the case of wood the limit of separation is soon reached, while in the case of gelatin and similar substances the particles may go into colloidal solution. This phenomenon of imbibition of water is closely related to the behavior of membranes to watery solu-

tions, since before there can be any passage of water, or of the solutes dissolved in it, across a membrane, the membrane must imbibe at least a certain amount of water. It is due to this characteristic imbibition of water by the protoplasm and the cell wall that water is continuous from the vacuole of one living cell to that of another. From the observed facts of the structure of the cell wall and the protoplasm and of the intake of water and of the migration of substances through them, we can crudely consider that these membranes are composed of a mixture of water and numerous and varied other substances. We can thus conceive that continuous waterways are provided along which the water-soluble substances may travel from cell to cell (Fig. 5).

C. DIFFUSION

When solutions are separated from each other or from the pure solvent by a membrane that is permeable to both the solvent and the solute or only to the solvent, certain phenomena occur which are not observable in the process of diffusion in solution when the membrane is not present.




FIG. 6.—Diagram to aid in the discussion of osmosis and osmotic pressure. Description in the text.

A discussion of this topic is necessary if we are to understand, in part at least, the intake, outgo, and translocation of materials in plants, since these processes are apparently concerned primarily with the diffusion through membranes. It is the intention here to discuss the process of diffusion through membranes only in a very elementary and brief manner, since a more elaborate and theoretical discussion belongs to the province of physical chemistry and not to plant physiology. Let us consider first the behavior of the solvent and solute where the solution is separated from the pure solvent by a semipermeable membrane. In Fig. 6 let us consider that a half-normal solution of cane sugar completely fills a container *B*, the wall of which, or some portion of it, behaves as a semipermeable membrane to the sugar solution (in case only a portion of the wall is semipermeable, it is here assumed that the remaining portion is impermeable to both the solvent and the solute). Let us further suppose that a fine capillary tube be connected with the container in such a manner as to function as a manometer and that the vessel containing

this sugar solution is immersed in distilled water in a larger container *A*. The solute will tend to diffuse very rapidly from *B* to *A* just as if no membrane intervened, for the diffusion gradient is steep, but the egress of the sugar from the vessel is prohibited, since the membrane is impermeable to it and equilibrium of concentration of the solute on both sides of the membrane cannot occur. Since the membrane is permeable to the solvent, water will readily move across it, diffusing more rapidly from *A* to *B* than it will from *B* to *A*, since the concentration of the solvent in *A* is higher than it is in *B*. The behavior of the solvent is thus similar to that which attains when two solutions of unequal concentration are brought together without the intervention of a membrane, but with this difference, that the solute cannot diffuse into the pure solvent exterior to the membrane, so that the concentration of the solvent in *A* will always remain higher than it is in *B*.

Since water enters *B* more rapidly than it leaves, a hydrostatic pressure will be set up in *B* as indicated by the rise of the column of mercury in the manometer. Water will continue to move from *A* into *B* with a corresponding increase in the hydrostatic pressure until this pressure equals the force with which water tends to enter *B*. In the case of the half-normal solution of cane sugar, the hydrostatic pressure thus set up in *B* at 0°C. and 760 mm. of mercury will be approximately 11.2 atmospheres if the conditions are ideal and the membranes and walls of *B* are capable of sustaining such a pressure.

This discussion now brings us to the consideration of osmosis and osmotic pressure. The term "osmosis" has been used with such a variety of meanings by workers in biology that one is in doubt many times as to what it really signifies (Stark, 1928). The physicist and the physical chemist always consider an ideal condition for the illustration of this process similar to that just mentioned in the preceding discussion in which the solution is separated from the pure solvent by a perfectly semipermeable membrane. They would thus define osmosis as the passage of a solvent from one side of a semipermeable membrane to the other when the escaping tendency (or free energy) of the solvent on the two sides is unequal. The osmotic pressure would then be defined as the pressure difference which must be established upon the solution and pure solvent, respectively, in order to make the escaping tendency of the solvent the same for both of them. Osmotic pressure can be defined also as the equivalent of the hydrostatic pressure produced when solution and solvent are separated by a perfectly semipermeable membrane. It may likewise be expressed as the equivalent of the excess pressure which must be imposed on a solution to prevent the passage into it of the solvent through a perfectly semipermeable membrane (Findlay, 1913). Beck (1928) defines osmotic pressure as the difference of pressure on solution and solvent which produces a condition of equilibrium such that there is no

tendency of the solvent to flow in either direction. Osmotic pressure should not be confused, however, with diffusion pressure, which is defined as the partial pressure which the solute molecules in any solution exert against a membrane permeable only to the solvent.)

Let us now consider a case of diffusion through a membrane in which such ideal conditions do not prevail, since in plants a solution may be separated not only from the pure solvent but also from another solution not by a perfectly semipermeable membrane but by one that is permeable to both the solvent and solutes. This condition prevails in the cells of plants to as great extent as or greater than does semipermeability of membranes. For an illustration of the phenomena which occur under these conditions, let us assume (Fig. 6) that an apparatus *B* similar to that just described, but with a membrane permeable to both the solute and solvent, is filled with a two-fifths normal solution of cane sugar in water and immersed in a larger vessel *A* containing a fifth-normal solution of cane sugar in water. The solute under this condition will diffuse more rapidly from *B* to *A* than it will from *A* to *B* and thus tend to equalize the concentration of the solute on each side of the membrane just as it would act if the two solutions were in contact without the intervention of the membrane. The water diffuses more rapidly from *A* to *B* than it does from *B* to *A*, since the concentration of the solvent in *B* is lower than in *A*. The behavior of the solvent is thus similar to that which would occur if the two solutions were placed in contact without the intervening membranes, but with this difference that water as a general rule diffuses through a membrane at a more rapid rate than the solutes so that a hydrostatic pressure will be set up in *B* as indicated by the rise of the mercury in the manometer. This hydrostatic pressure, however, is only temporary, for as the concentration of the solute in *A* and *B* becomes more nearly equal, the solvent on both sides of the membrane more nearly reaches equilibrium and the hydrostatic pressure in *B* is diminished accordingly. When the concentration of the solute and solvent have become, respectively, the same in *A* and *B*, the rate of diffusion of the solvent from *A* to *B* is the same as it is from *B* to *A* and as a result the hydrostatic pressure on the inside of *B* is reduced to zero.)

(It is evident from the above example that the phenomenon of osmosis and osmotic pressure may be exhibited when the membrane is not semipermeable. It would thus appear that osmosis should not be defined only in terms of semipermeable membranes but in terms of permeable membranes as well. Osmosis could thus be defined as the passage of the solvent from one side of a membrane to another where the escaping tendency of the solvent on the two sides is unequal. Stark (1928) proposes that osmosis be defined as diffusion through a membrane, the direction of the major movement being from a region of high concentration to a region of low concentration of the thing diffusing.)

If the fifth-normal solution of cane sugar were placed in *B* and the two-fifths normal solution in *A*, the rate of water movement from *B* to *A* would be greater than from *A* to *B* and as a result water would be withdrawn from *B*. Under such a condition the walls of *B* would contract or collapse unless they were strong enough to sustain the negative pressure developed therein. This phenomenon frequently prevails in plant cells under certain conditions, and their behavior under these conditions will be discussed in detail when the subject of plasmolysis is considered. The term "endosmosis" is used to designate the flow of either solute or solvent through the membranes of the plant cell into the vacuole, while the term "exosmosis" is used to designate the flow of solvent or solute outward from the cell vacuole. The connection of the phenomenon of osmosis with the water relations of the plant cell will be discussed in detail under the heading, Osmotic Relationship of the Plant Cell.)

D. THE MEMBRANES OF THE PLANT CELL

With but few exceptions there are in each fully developed living plant cell two well-defined membranes through which materials must pass in moving from the vacuole or vacuoles of one cell to those of another or in entering the vacuoles of the external cells of the plant body from the medium in which the plant is growing. These two membranes are the cell wall and the cytoplasmic layer.

1. The Cell-wall or Non-living Membrane.—With the exception of certain zoospores, sperms, unfertilized eggs, and in a few other cases, the protoplasm of plant cells is always enclosed by a definite compact solid membrane called the "cell wall." This membrane is frequently termed the "non-living" membrane of the plant cell. The constituents which may enter into the composition of the cell wall have been named and described in considerable detail in Chap. I, so it is the intention here to discuss only the general relationship of the cell wall to watery solutions.

a. Permeability to Water.—(The cell wall is, for the most part, composed of an aggregation of colloidal particles in the gel condition and like other gels it exhibits the power of imbibition and absorbs water when placed in contact with it. The amount of water thus absorbed before imbibitional saturation is reached varies greatly according to the constituents of the cell wall. Thus in the case of cutin and suberin the amount of water imbibed is very small, while in the case of the pectic substances the amount absorbed may be so great as practically to throw these substances into colloidal solution. Since all cell walls exhibit the power of imbibing water, it follows that none of them is absolutely impermeable to water. The suberized and cutinized cell walls are the least permeable to water, while the cell walls of embryonic tissue, root hairs, and parenchyma cells apparently offer the minimum retardation to water of any of the cell walls.) The cell walls that are the most permeable to

water, however, offer some resistance to water flow and water never diffuses so readily across a cell-wall membrane as it would were there no membrane present. (The principal factors that influence the rate of water movement across cell-wall membranes are the same as those that influence the behavior of practically all membranes. These main factors are the constitution of the membrane, the direction of flow, the concentration of the solutions in contact with it, and the temperature.) The differences in the degree of permeability of the cell walls of different species of plants to water is shown by the work of Denny (1917) with the seed coats of seeds and with the outer bulb scale of the onion. These membranes consist entirely of dead cells, so that with the possible exception of some non-living material within the cavities of the cells, the behavior of the membranes toward the diffusion of water through them is due entirely to the nature of the walls of the cells composing them. The amount of water passing through equal areas (19.63 sq. mm.) of these membranes in a unit of time, when the external solution consisted of a saturated solution of NaCl with an osmotic pressure of approximately 375 atmospheres, is shown in the following table:

Membrane	Number of observations	Average amount of water passing per hour, milligram
Seed coat of grapefruit.....	3	0
Seed coat of <i>Cucurbita pepo</i>	4	4.0
Seed coat of <i>Cucurbita maxima</i>	5	9.3
Seed coat of cocklebur.....	4	18.2
Outer bulb scale of onion.....	6	24.0
Seed coat of almond.....	7	88.5
Seed coat of peanut.....	7	565.1

Denny investigated the nature of the constituents of these cell walls in order to determine if possible the cause of their differential permeability to water. His method consisted in determining the rate of flow of water through a given membrane and then after treating it with a given solvent to measure again the rate of water flow across it. (The heating of the membranes in boiling water for 5 min. increased the permeability of the peanut and almond membranes but not that of the seed coats of the grapefruit or squash. The increase in permeability of the peanut coat averaged approximately 168 per cent, while the increase in permeability of the almond amounted to as much as 500 per cent. (The treatment of these membranes by hot alcohol, hot acetone, and hot ether, which are solvents of fatty substances, increased greatly the permeability) of the peanut, almond, squash, and cocklebur coats but not the grapefruit seed coats. The maximum increase in permeability of these membranes was

871, 242, 452, and 138 per cent, respectively, for the squash, peanut, almond, and cocklebur. After some of the membranes had been extracted with the fat solvents, they were immersed in the extract and exposed to evaporation so that they would again contain the materials that had been removed from them. Although the permeability of these membranes was reduced by this infiltration, it did not reach the low point exhibited by the membranes before their extraction. This fact indicates that the extracted materials which influenced the permeability of these membranes to water are distributed in an organized manner throughout the cell walls. This assumption is also strengthened by the fact that the permeability of some of these membranes is increased by simply heating them. (Denny considered that the substances in the cell walls of the membranes mentioned above which are factors in determining their permeability to water are fatty substances, tannins, and pectic substances.) There was no evidence from his experiments that suberin plays any part in determining the permeability of these membranes. The squash seed coat, for example, is very resistant to the passage of water yet it has no distinctly suberized layers. Denny considered that the resistance of the seed coats of grapefruit to the passage of water is due to the presence in certain portions of the membranes of a large amount of fatty substances surrounded by thick pectinized walls. Denny made certain observations which showed that some of these membranes under consideration are more permeable to water in one direction than in another. Thus, for example, when the membrane of the almond was placed in an osmometer so that the water passed through the membrane, as it naturally would in entering the seed from the outside, the rate of flow was 48.5 mg. per hour. If the position of the membrane was reversed so that the water entered, as it would in passing from the seed to the external medium, the rate of flow was only 42.6 mg. per hour. In the case of the peanut membrane, the maximum percentage decrease of water flow from the "in" to the "out" amounted to 56 per cent. No difference in the rate of penetration of water in opposite directions could be observed in the case of the outer bulb scale of the onion and the seed coat of *Dioon edule*. This difference in the behavior of membranes is apparently correlated with their structure. The peanut and almond coats are composed of distinct layers and have surfaces of different physical and chemical natures, while the onion scale and *Cycad* membranes are apparently uniform in structure. A difference in the rate of water flow through membranes is characteristic of many living and non-living animal membranes as well as many artificial ones. (The behavior of "double" membranes may have an important influence on the movement of water into and out of the plant cell) and Denny asks the important question: "If this difference in the rate of diffusion is due to the presence of double membranes of different nature, or to the difference in surface on opposite sides, may not the plant cell

itself show a difference in permeability in opposite directions, since such a system of double membranes is represented by the cell wall and ectoplast?"

Denny further made the very important observation in regard to the membranes with which he worked that when solutions of varying concentrations are placed on opposite sides of a membrane the relation between the rate of water movement and concentration difference is complex and that, in general, equal osmotic differences do not necessarily produce equal rates so that no mathematical relation can be noted between the concentration on opposite sides and the rate of water movement through the membranes.

b. Permeability to Solutes.—It has generally been supposed that if the cell wall were permeable to water, it would also be permeable to any solute dissolved in water. (Comparatively recent work, however, has shown that there are numerous cell walls that are impermeable to various solutes) and that this fact must be taken into consideration in studying the permeability of the plant cell. Brown (1907, 1909, 1915) studied especially the semipermeability of the covering of the barley grain. His first observation in this regard was that the blue pigment in the cells of the aleurone layer did not change in color even after the grains were soaked for several days in 1 per cent H_2SO_4 but that if the covering of the grain were punctured or otherwise injured, the pigment turned red at once, showing that the H_2SO_4 had passed through the membrane. He further found that the seeds which had been soaked in the 1 per cent H_2SO_4 absorbed water, swelled, and sprouted just as they did in distilled water, although as soon as the sprout ruptured the seed integument, the acid entered and turned the pigment red. It was further found that when these seeds were placed in 4.9, 7.6, 9, 18, or even 36 per cent H_2SO_4 no acid entered after 44 hr. and that these same seeds upon being washed and planted grew vigorously. The permeability of this membrane was studied in regard to $CuSO_4$, $FeSO_4$, K_2CrO_4 , $AgNO_3$, and $K_4Fe(CN)_6$ in a 5 per cent water solution. The covering was found to be semipermeable to all of these, taking up water but as far as could be observed preventing the entrance of these solutes into the seed. (The membrane was found to be permeable to mercuric chloride, acetic, formic, propionic, and butyric acids, ammonia, ethyl alcohol, and ethyl acetate among others. The degree of permeability to these substances, however, varied greatly. Ethyl alcohol, for example, entered at the same rate approximately as water, while acetic acid entered more rapidly, and ethyl acetate entered the most rapidly of the three. The seeds were subjected to boiling water for an hour period, but the results observed after this process were practically identical with those mentioned above, a fact which shows that this property of semipermeability lies in the cell walls of the covering of the grain and not in the protoplasm, since the latter was undoubtedly

killed by this treatment. Brown from these experiments concluded that this power of semipermeability is confined to the cell wall of the testa of the seed and probably to that portion which is derived from the epidermis of the nucellus during the germination of the seed. Brown also studied the rate of movement of various phenols across this seed membrane and concluded that when the osmotic pressures, vapor pressures, and viscosities of this series of solutions of soluble solutes are equal, their rate of diffusion across this membrane are inversely proportional to their surface tensions. The earlier work of Brown was followed by that of Schröder (1912), who found that the wheat grain possesses the same type of selective permeable coat as the barley grain, and by Tjebbes (1912), who observed that a part of the inner coat of the seed of the sugar beet shows the power of selective permeability. Becquerel (1909) showed that the dried seed coats of numerous plants are impermeable to various gases and to such penetrating substances as chloroform, absolute alcohol, and ether.

(Shull (1913) extended the field of observation in regard to the permeability of seed coats and found that those of cocklebur, numerous grains, peach, apple, bean, and sunflower act as semipermeable membranes.) His observations, however, were confined chiefly to the behavior of the seed coat of the cocklebur. This coat, he found, is composed of three rather definite layers, the outer of which does not function as a semipermeable membrane, the middle of which is several cells thick, and the inner of which is composed of a single row of cells. Both the middle and inner layers have osmotic properties, but neither functions so well separately as when they are together. The property of semipermeability in the case of the cocklebur coat is not dependent upon the protoplasmic membrane of the cells which compose it, since the same results are obtained after boiling the seeds or the membrane after it has been separated therefrom.

Shull tried the effect of soaking the dry cocklebur seeds in ether, chloroform, acetone, and absolute alcohol and found that no detectable amount of these substances penetrated through the seed coat and that the viability of the seed was not injured by this treatment. Thus, for example, seeds soaked in ether for 2 to 36 days and then dried and soaked in water and placed under germinative conditions after the testas were removed showed 87 per cent germination and the plants resulting were as vigorous as the controls. Shull investigated the permeability of this seed coat to approximately 40 different salts and found that NaCl, CuSO₄, K₂CrO₄, Na₂S₂O₃, glycerol, HCl, sugars, and tartaric acid were excluded while all the other compounds including AgNO₃, NaNO₃, KNO₃, KCl, FeSO₄, KOH, NaOH, H₂SO₄, HNO₃, acetic, lactic, and citric acid were allowed to pass through, although the degree of permeability to these substances varied with the substance.

Experiments with a large number of seed types in 1.5 per cent solutions of KNO_3 and MnSO_4 showed that when the seed coverings were intact any salts absorbed by the seeds were held superficially so that heavy losses in the amount of these salts resulted when the seeds were washed for one minute in water. When the seed coats were injured, a large amount of salts was absorbed but only a slight amount could be recovered by washing. Whitten (1914) found that the membranes of the corn seed are very impermeable to kerosene oils. Thus the grain may be immersed in kerosene for periods of 10 to 20 days without injury to the embryo.

The results obtained by Brown, Shull, Schröder, and others explain those reported by Giglioli (1895), who obtained a 20 per cent germination of alfalfa seed that had been in a saturated solution of HgCl_2 in absolute alcohol for 16 years.

Comparatively recently, Collins (1918) has reported his extensive experiments concerning the structure of the integument of the barley grain in relation to water absorption. His observations are in considerable contrast to those of Brown, since he considers that only a small part of the water absorbed by the grain of barley enters by the general surface of the grain which he considers to be invested by cells with cuticularized cell walls. He considered that most of the water and solutes enter the micropyle or germinal region of the grain and it is here that the structure which is the seat of permeability must be sought, since he found that the solutes which have been recorded as penetrating the covering of the grain scarcely pass at all through its general surface but enter like water through the restricted region at the germinal end. Should this work of Collins be substantiated, our present conception concerning the permeability of seed coats would need to be greatly modified.

Lavison (1910, 1911) studied the entrance of salts through the cell walls of the endodermis of the root. He found that the young cellulose periclinal walls of the endodermis are impermeable to the salts of Fe, Pb, Cu, Ni, and Hg among others and that they behave in this regard like the protoplasm itself. We thus have a case in one of the most active translocation regions of the plant where the cell walls act in a semipermeable manner. Brooks (1917) found that the exterior cell wall of the epidermis of the inner surface of the bulb scale of the onion behaves as a semipermeable membrane toward a watery solution of CaCl_2 , NaCl , AlCl_3 , NaOH , Bordeaux red, and eosin but that it allows a slight diffusion of HCl through it. It is a striking fact that semipermeability to these substances is confined only to the exterior wall of the epidermal cell, while the other walls of the cell are permeable to them. The work that has thus far been done in studying the permeability of the cell-wall membrane makes it very evident that it is necessary to consider its influence in the interpretation of the permeability of plant tissues.

2. The Protoplasmic, Cytoplasmic, or Living Membrane.—One of the outstanding differences between the plant cell and the animal cell is the amount and distribution of the protoplasm within these units. An animal cell is composed almost entirely of protoplasm and the growth of the cell simply means an increase in the amount of the living matter which thus increases concurrently with the size of the cell. In the embryonic plant cell, the protoplasm occupies the whole space enclosed by the cell wall, but as the cell enlarges the protoplasm does not increase in amount proportionately but spreads out in a thin film around the inside of the cell wall and the outside of the vacuole which is developed under these conditions. A plant cell may increase in volume as much as five hundred times or more and yet contain little more protoplasm than it did before it began to enlarge. This thin film of protoplasm thus forms a membrane through which materials entering or leaving the vacuole must pass and has been termed the “living membrane,” the “protoplasmic membrane,” or the “cytoplasmic membrane,” the last term being used because the cytoplasm composes the greater portion of it.

a. Nature.—The protoplasmic membrane has more of the characteristics of a liquid than of a solid and evidently consists of a colloidal suspension and a true solution of numerous substances. It possesses considerable power of cohesion, is more or less elastic, and is stretched or held in its position by the pressure of the cell sap, as is evidenced by its rapid contraction inwardly as soon as the pressure within the vacuole is sufficiently reduced. Since the protoplasmic membrane is more or less liquid in its nature, it has been assumed that it exhibits certain surface phenomena which must here be discussed.

The surface of a liquid differs in physical properties from its general mass due to the fact that the molecules at the surface are not attracted equally on all sides. Any molecule throughout the general mass of the liquid is attracted equally in all directions by the molecules distributed around it and this mutual attraction results in keeping the pressure on any particular molecule uniform in every direction. A molecule at the surface of a liquid, however, is subjected to the attraction of the molecules in the interior and those adjoining it on the surface, but there is no attractive force at the exterior to balance this. As a result of this the surface layers of molecules are subjected to an inwardly directed attraction or pull at right angles to the surface. This phenomenon is called “surface tension” and due to it the surface of a liquid differs from its general mass in its behavior as a thin film or skin. Since the protoplasmic membrane is more or less of a liquid, it is generally assumed that its surfaces bordering on the cell wall and vacuole, respectively, exhibit characteristic surface-tension phenomena and also a difference in the degree of permeability compared with the general mass of protoplasm.

The existence and nature of the surface layers of protoplasm have evinced much discussion, and probably no other topic in biophysics has been the subject of so much controversy. Some workers question its very existence, while others positively assert that an actual morphological and physiological definite surface layer can be clearly demonstrated. De Vries (1884, 1885) claimed that it has a morphological entity, Kite (1915) calls it a "hypothetical structure," while Fischer (1915) named it a "figment of the imagination," but Seifriz (1921) considers that the direct evidence from microdissection indicates a definite membrane on the surface of all protoplasm and considers that its thickness is about 0.1μ . The names used to designate this portion of the protoplasm are no less varied and numerous than the controversies concerning its existence. It has been called "surface layer," "surface film," "ectoplast," "phase boundary," "ectosarc," "hyaloplasm," and "plasma membrane." The term "plasma membrane" has been the one most commonly used. It was first used by Pfeffer (1877, 1900) to denote a surface layer or film of protoplasm which he considered to behave in regard to permeability differently from the general mass of the protoplasmic membrane. The term as it has been used by many authors and investigators is very loosely defined. In some cases it is employed only in the sense of a surface-tension film, in others it means a differentiated surface layer of the protoplasm of considerable depth, and by some it has been used to include the entire protoplasmic membrane. De Vries (1884) used the term "ectoplast" to denote the surface film of cytoplasm in contact with the cell wall and the term "tonoplast" to denote the surface bordering on the vacuole. Stiles (1925) suggests that the limiting surface of the protoplasm next to the cell wall be called the "external plasma membrane" and the surface bounding the vacuole the "internal plasma membrane." To the writer it appears that the attempts to prove the existence of a definite plasma membrane by direct observation and by various indirect methods have failed to establish definitely its identity, and it seems that the best evidence of such a membrane must rest wholly on the theoretical evidence from the physical laws governing the surfaces of liquids. If the plasma membrane is the result of these laws, then we must conclude (Seifriz, 1921, and Stiles, 1925) that the surface of the protoplasmic membrane is not an invariable structure but that it will vary with the change in composition of the protoplasm and the external medium. The limiting surface of the protoplasmic membrane thus cannot be separated from the rest of the protoplasm, for it depends for its existence on and is closely related to the media which it separates and passes over into the phases on either side of it, sometimes abruptly and sometimes gradually, depending upon the environmental conditions and the composition of the mass of the cytoplasm and the surrounding medium.

Osterhout, Damon, and Jacques (1927), and Osterhout and Harris (1928) studied the protoplasmic membrane of *Valonia macrophysa* and *Nitella* by the measurement of potential differences in order to determine whether there is any difference between the outer and inner surfaces of this membrane. The results indicate that they do differ, since when both surfaces are in contact with the same solution (cell sap) there is an electromotive force of about 14.5 and 15.9 millivolts, respectively, for *Valonia* and *Nitella*, the inner being positive to the outer (*i.e.*, the current tends to flow from the inner surface through the electrometer to the outer surface).

Brooks and Gelfan (1928) measured the potential differences between a microelectrode in the protoplasm of *Nitella* and one just outside the cell. The potential difference was found to increase with the increase in size of the cells studied in tap water and in 0.001 *M* NaCl from 15 millivolts for a cell when of about 0.5 mm.³ to about 40 millivolts for cells 3 mm.³ in volume. The potential differences for cells immersed in artificial *Nitella* sap was 7 millivolts. These potential differences increased with each dilution of the artificial sap until they approached those obtained in tap water or 0.001 *M* NaCl.

Whether or not the surface layers of the protoplasmic membrane differ in permeability from the greater portion of its bulk is of comparatively little moment. Many of the phenomena of diffusion which occur in plants due to the separation of solutions by the protoplasmic membrane can be explained, partially at least, by assuming that as a unit it behaves as a permeable or impermeable membrane, as the case may be, without considering whether its qualities of permeability reside in its surface layers or in its general mass.

b. Permeability.—From our knowledge of the nature of protoplasm and its remarkable capacity to respond and adjust itself to its environment, we should suspect that as a membrane it would exhibit marked variations of permeability. It does, and so responsive is it to environmental conditions (only a few of which we at present comprehend) that the permeability of this membrane to a given substance may be strikingly different not only in adjoining cells but also in different parts of the same cell. Any statements, therefore, regarding the permeability of the protoplasmic membrane must be only relative to the given cell or portion of it and on that account any discussion of its permeability to water or its solutes is inseparable from a discussion of the factors that influence permeability and the method of determining the same.

The protoplasmic membrane imbibes a large amount of water (Seifriz, 1921) and as a general statement it can be said that it is readily permeable to water, but under certain conditions it is more so than under others. The greatest variations in permeability, however, prevail in the behavior of the protoplasmic membrane toward solutes, the gradations ranging

from those cases where the protoplasm offers but little retardation to their passage on the one hand to practically absolute impermeability on the other. The degree of permeability depends primarily upon the environmental conditions, and these will be considered in detail when the factors influencing permeability are considered.

1. *Osmotic Relationships of the Plant Cell.*—In order to understand something of the factors which enter into the alteration of the permeability of the protoplasmic membrane as well as to comprehend the methods used in detecting these changes in permeability, it is necessary to have clearly in mind certain phenomena which occur in connection with the water relations of the plant cell. In a consideration of the osmotic relationships of a typically vacuolated plant cell with an elastic cell wall to the adjoining cells, or to the medium exterior to the plant, the following factors, quantities, or forces are considered the most important:

(a) *Osmotic Concentration of the Cell Sap.*—By the osmotic concentration of the cell sap is meant the concentration of the osmotically active substances therein under the conditions which occur in a normal cell. This concentration is generally stated in terms of the osmotic pressure expressed in atmospheres that the cell sap would be capable of producing if it were separated from pure water by a perfectly semipermeable membrane. The concentration of the cell sap thus expressed has been called by Ursprung and Blum (1916) the “osmotic value” of the cell sap. It might also be appropriately named the “potential” or “latent osmotic pressure” of the vacuole contents, since it does not express the value of the osmotic pressure being exerted within the vacuole but rather that which such a solution would be capable of developing if it were placed under the ideal conditions mentioned above. The osmotic value of the cell sap has frequently been measured under that condition of the cell designated as incipient plasmolysis. Under such conditions the osmotic concentration of the cell sap is higher than that which prevails under the normal conditions of the plant cell, as will be seen later. The osmotic value of the cell sap is the highest at incipient plasmolysis and the lowest when the cell is in equilibrium with distilled water.

(b) *Osmotic Concentration of the External Solution.*—The term “external solution” as here used may refer to the cell sap of the cells adjoining the one under consideration or that which may attain in the medium exterior to the plant. This external solution exerts an osmotic pressure which counterbalances to a greater or lesser degree that of the solution in the vacuole of the cell in question. If the osmotic concentration of the cell sap is higher than that of the external solution, water will be drawn into the cell with a force equal to the difference between the osmotic pressure of the cell sap and that of the external solution, provided that the cell wall and protoplasmic membrane exerts no inward pressure

upon the solution in the vacuole. If the osmotic value of the external solution is higher than that of the vacuole of the cell being considered, water will be withdrawn from the cell with a force equal to the difference between the osmotic pressure of the vacuole and the external medium, if the external medium is not subjected to any inwardly directed pressure.

This latter behavior can be observed in the laboratory by placing plant tissue in a solution the concentration of which is higher than that of the cell sap of the cells which compose the tissue. Let us consider the phenomena which would prevail under these conditions if the protoplasmic membrane were (1) impermeable to the solutes of the exterior solution and those of the cell sap and (2) permeable to the solutes of the exterior solution but impermeable to those of the cell sap. It is assumed in both cases that the concentration of the solutes in the external solution is not of such a nature nor of sufficient strength to be directly injurious to the protoplasm.




FIG. 7.—Plasmolysis. *A*, section of a plant cell showing the position of the protoplasm at incipient plasmolysis. *B*, position of the protoplasm after evident plasmolysis.

Let us now assume that a plant cell is placed in a solution whose osmotic value is higher than that of the cell sap and that the protoplasmic membrane is impermeable to the solutes of the exterior solution and of the cell sap (Fig. 7*A*). Under these conditions no diffusion of solutes across this membrane tending toward an equilibrium in their concentration could occur. Since the concentration of solutes in the exterior solution is higher than that in the vacuole of the cell, it follows that the concentration of solvent is lower in the former than it is in the latter and that as a result water will diffuse outwardly from the vacuole into the exterior solution more rapidly than it will move in the opposite direction. Hence water will be drawn from the vacuole of the cell and the hydrostatic

pressure that is normally exerted against the protoplasm and the cell wall is lowered and as a result these membranes contract inwardly. Since the cell wall is only slightly elastic, the limit of its contraction is soon reached, but this is not true of the protoplasmic membrane and it will continue further to contract inwardly and thus separate itself from the cell wall (Fig. 7B). This contraction of the protoplasm will continue until the osmotic concentration of the cell sap, due to the unequal diffusion of water outwardly and also perhaps to the formation of new osmotically active materials by the protoplasm, has become equal to that in the external solution. When this state of equilibrium prevails, further contraction of the protoplasm will not occur, and unless the protoplasm is capable of manufacturing osmotically active substances to increase further the osmotic concentration of the vacuole, the protoplasmic membrane will never regain its normal position and death will shortly ensue.

Let us now consider the phenomena which occur if the protoplasm is permeable to the solutes of the medium in which the cell is placed but impermeable to the solutes within the vacuole. Since the solutes in the external solution are higher in concentration than those in the cell sap, they will diffuse inwardly and this will tend to equalize the total concentration of the solutes in the vacuole with that of the external solution. The concentration of the solvent being lower in the external solution than in the cell sap, water will tend to diffuse outwardly. Since, however, the solvent moves more rapidly across membranes than do solutes, the water of the cell sap will diffuse outwardly more rapidly than the solutes move inwardly. As a result, the hydrostatic pressure against the cell wall and the protoplasm will be reduced and these membranes will contract in the same manner as described in the previous example. The protoplasm will recede from the cell wall and continue to contract until, due to the diffusion outwardly of water and the diffusion inwardly of the solutes, the cell sap is in osmotic equilibrium with the external solution.

Since, however, the protoplasmic membrane is permeable to the solutes of the external solution, they will diffuse inwardly until the concentration of each solute is the same in the cell sap as it is in the external solution. As a result of this, the osmotic value of the cell sap will increase and water will move inwardly so that a hydrostatic pressure will be gradually set up which will force the contracted protoplasmic membrane against the wall into its normal position. Thus eventually the hydrostatic pressure against the protoplasmic membrane and the cell wall will be the same as that which prevailed before the cell was immersed in the solution.

The contraction of the protoplasmic membrane from the cell wall, due to the release of the hydrostatic pressure of the cell sap against it,

is called "plasmolysis," a term which literally means "the loosening of the protoplasm."

The cell wall soon reaches its limit of contraction, but the protoplasmic membrane, which is more elastic, will continue to contract as water is withdrawn and thus will move inwardly from its normal position along the cell wall. That condition in a cell when the cell wall has reached its limit of contraction but when the protoplasm has not yet receded from the wall is termed "incipient plasmolysis." The deficiency of water in the vacuole which causes plasmolysis in plant cells is most generally due to the difference in concentration of the solution external to the cell and that of the cell sap or to the inability of the cell to replace the water which is being lost from it through evaporation.

A solution that has the same osmotic value as the cell sap is termed an "isotonic" solution and if a cell is placed in such a solution it will neither contract nor expand in volume. The term has also been frequently used to denote a solution which has the same osmotic value as the cell sap at incipient plasmolysis. A solution which has an osmotic value higher than that of the cell sap is called a "hypertonic" solution while the term "hypotonic" is applied to a solution whose osmotic value is less than that of the cell sap.

✓ (c) *The Turgor Pressure of the Cell.*—A normal living plant cell (regardless of whether it is vacuolated or non-vacuolated) under the ordinary conditions of plant life absorbs a sufficient amount of water to exert a hydrostatic pressure against the cell-wall membrane. This membrane is elastic and is stretched by the hydrostatic pressure, but its limit of extensibility is soon reached and at that point it exerts a pressure against any further increase in the volume of the cell. When the limit of extensibility of the cell wall has been reached, its resilience or inward pressure is equal to the force with which water is being drawn into the cell and hence no more water will enter. When this process of expansion is underway or has reached its limit, the cell is rigid and is said to be "turgid." This condition of rigidity is spoken of as the "turgidity" of the cell.

This inwardly directed pressure of the cell wall and protoplasm against the cell sap is termed the "turgor pressure" of the cell. It is less than the total osmotic pressure previous to the time that the limit in extensibility of the cell wall has been reached but is equal to the osmotic pressure of the cell sap when that condition prevails.

A theoretical example will illustrate this point. Let us assume that a vacuolated cell is at the point of incipient plasmolysis and that the osmotic value of the cell sap is 16 atmospheres. If a cell in this condition is placed in distilled water, water will enter the vacuole of the cell and increase its volume and thus lower the osmotic value of the cell sap. Let us assume that water will continue to enter until the osmotic value of the sap has been reduced to 14 atmospheres and that at this point the

limit of extensibility of the cell wall has been reached. At this point, its resilience or power of contraction is equal to the force with which the cell sap can attract or pull water into the cell and no more water will enter. The hydrostatic pressure that is now being exerted against the protoplasmic membrane and cell-wall membrane by the cell sap is equal to 14 atmospheres and is the value of the turgor pressure of the cell. Thus when a cell is in equilibrium with pure water the turgor pressure is at its highest possible value and is equal to the osmotic pressure of the cell sap. At incipient plasmolysis, the turgor pressure is zero. Between these limits, the turgor pressure possesses intermediate values depending upon the quantity of water present in the cell. It is generally assumed that within the limits of the elasticity of the cell wall, the tension of the wall increases proportionately to the volume of the water taken into the cell, although it appears that such a relation holds only approximately.

(d) *The Suction Pressure, Suction Force, Absorbing Power, or Suction Tension of the Cell.*—These terms are used to denote the pressure sending water into the cell. The term "suction pressure" may be designated as the net suction pressure sending water into the cell regardless of the external concentration, or it may be designated as the full suction when the external liquid is considered to be water. The net suction pressure is equal to the difference between the osmotic value of the external solution and the osmotic value of the cell sap less the turgor pressure. The full suction pressure is equal to the osmotic value of the cell sap less the turgor pressure. When a plant cell is in equilibrium with pure water, the suction force of the cell is zero, while at the point of incipient plasmolysis the suction force reaches its maximum value for any condition in which the protoplasm is in its normal position along the cell wall. The suction force of the plant cells under the conditions that generally prevail in the plant are somewhere intermediate between the two extremes just mentioned.

The osmotic concentration or value of the cell sap at incipient plasmolysis has been wrongly termed by many investigators as the suction force of the cell under the normal conditions of the plant. These investigators considered the concentration of the cell sap at incipient plasmolysis to be the same as that which normally prevails in the plant and did not take into consideration the shrinkage of the cell in volume and the attending increase in concentration of the cell sap. Ursprung (1903 to 1925), Ursprung and Blum (1916 to 1924), Molz (1926), and Beck (1928) have studied the force of the cell-sap suction in the various tissues of the plant and its variation under various external conditions. As an example of the different quantities concerned in the osmotic relationship of the plant cell, those determined for the cells of the root of *Vicia faba* are given (Molz, 1926).

OSMOTIC VALUE, SUCTION FORCE, AND TURGOR PRESSURE AS DETERMINED IN THE ROOT CELLS OF *Vicia faba*

Tissue examined	Distance from growing point, millimeters	Osmotic ¹ value of cell sap, atmospheres	Suction force of cells, atmospheres	Turgor pressure, atmospheres
Epidermis of cells of outer cortex	1.5	14.3	7.4	3.9
	3.0	14.0	7.7	4.0
	5.0	13.3	10.0	2.7
	8.0	12.7	0.4	9.4

¹ At incipient plasmolysis.

These investigators found in the absorption zone of the root of *Vicia faba* an increase in the suction force of the cells from the epidermis toward the endodermis and then a marked decrease in the endodermis and wood parenchyma. It was also observed that the suction force of the cells of the upper portion of the stem and its leaves was higher than the cells of the same parts lower down. An increase in suction force from the base to the apex was found in the mid- and lateral veins of the ivy leaf. The observation of the suction force of a row of palisade cells which extended from the midvein into a portion of the leaf free from larger veins was especially noteworthy. From a minimum of 12 atmospheres near the midvein, the suction force rose regularly to a maximum of 32.6 atmospheres, which was attained in the two hundred and tenth palisade cell, from which point it decreased. In contrast to this regular rise in suction force, the osmotic value in the same row of palisade cells showed no regularity.

Molz (1926) measured the osmotic value of the cell sap under the natural conditions of the plant. He did this by determining the concentration of cane sugar in which the cells kept their normal volume. He found that soil moisture and humidity of the air are the external factors which especially influence this value. A heavy rain, for example, after a drought may cause the osmotic value of the leaves to decrease 20 atmospheres or more. The lowest osmotic values are found in submerged aquatic plants and they increase with the dryness of the habitat of the plant.

2. Permeability and Absorption.—The diffusion of any solute into a plant cell will depend not only upon the degree of permeability of the cell membranes to the substance in question but also on how much the equilibrium of the solute on the outside and inside of the cell is disturbed. On that account, therefore, the rate at which a substance enters a cell cannot be taken as a measure of the permeability of the cell membranes to that substance. Let us consider a case in which the protoplasmic membrane is only slightly permeable to a given solute, but as soon as this solute enters the cell it is chemically combined, precipi-

tated, or adsorbed and thus rendered osmotically inactive. In that case, the concentration of this solute on the inside of the cell will always be lower than that on the outside and it will continue to enter, so that after a period of time a comparatively large amount of the substance has entered the cell even though the protoplasmic membrane is only slightly permeable to it. On the other hand, the protoplasmic membrane may be very permeable to a solute, but after its entrance into the cell, this solute may not be combined or adsorbed to any extent. In that case, equilibrium of concentration of this solute on the outside and inside of the cell will soon be reached and no more will enter. Thus after a period of time only a comparatively small amount of the solute has entered the cell, although the protoplasmic membrane is readily permeable to it. In discussing the methods used in determining the changes in the permeability of the protoplasmic membrane, the distinction between the degree of permeability of the membranes and the rate of absorption of a given solute must be kept clearly in mind. It should be remembered that these quantities have little to do with each other and that the rate of absorption is no criterion of permeability, although it has been so used by many investigators.

3. *Methods of Measuring the Permeability of the Protoplasmic Membrane to Solutes.*—The investigations of the changes in permeability of the protoplasmic membrane to solutes have shown marked differences in evidence secured by different methods and in the conclusions based thereon. These differences are in a large measure due to a lack of understanding of the limitations of the methods used and to assumptions which are unwarranted by the data obtained. A brief survey should thus be made of the methods that have been employed and their advantages and disadvantages mentioned so that the student may be able to judge better the value of the work that has been reported in this regard. The principal methods that have been used in the study of the permeability of the protoplasm are (a) chemical analysis of the tissue extracts or of the solutions external to the tissues; (b) observation of visible changes within the cells; (c) methods involving plasmolysis; (d) electrical conductivity of tissues or masses of cells; and (e) the diffusion method. These have been termed “indirect methods,” since the cell contents are examined only in an indirect manner or not at all. A direct method has lately been devised that is applicable in certain cases, whereby the cell sap may be withdrawn directly from the cells and a quantity of material obtained sufficient to make a qualitative and in some cases a quantitative chemical determination.

(a) *Indirect Methods.* (1) *By Chemical Analysis.*—This method has been used primarily to determine what substances may enter or leave the plant cell through the protoplasmic membrane rather than a measure of the changes in its permeability. The method is more applicable in considering the amount of materials absorbed by a

considerable portion of tissue or by the entire plant than to a consideration of a single cell or of a small amount of tissue. Two lines of procedure have been followed. One is to analyze the tissue or the tissue extract and the other is to analyze the solution bathing the tissues. The principal objection to analysis of tissue extracts is that it is extremely difficult to obtain a sample that is representative of the cell sap by any of the present means of extraction. The analysis of the tissue or tissue extract also does not take into consideration the presence of salts in the intercellular spaces or in the cell wall where they may be held in solution or by adsorption. The analysis of the solution in which the plant is grown in order to determine the intake or outgo of solutes has many sources of error. The results in many cases can be observed only after several hours and in many cases that have been reported only after several days. Under such conditions some of the external cells are undoubtedly killed or are separated from the roots, especially the root tip, and thus give off their cell sap into the solution. Any increase in the diffusion outward of the solutes may be due not to increased permeability but to increased production within the cells under the conditions of the experiment. Brooks (1917) criticises the method, since it in no way distinguishes between the rate of absorption and the degree of permeability of the protoplasmic membrane. Steward (1928) concluded from a consideration of the effects of various treatments upon exosmosis that protracted leaching does not necessarily result in loss of semipermeability. It is evident thus that under certain conditions the chemical method may be an indicator at least of the degree of permeability of the protoplasmic membrane but that its limitations must be kept in mind.

(2) *By Visible Changes within the Cell.*—This method of studying permeability is of importance in the investigation of the diffusion of substances into the cell which will form therein precipitates, stains, crystals, or other compounds that may be observed. These substances include certain alkaloids which form intracellular precipitates; acids and alkalis which cause color changes of pigments within the cell; dyes which form precipitates; stains; salts which form crystals after their entrance; and sugar and glycerol whose penetration into the cells is made manifest by the formation of starch. This method of determining permeability is necessarily limited in its application and it is also open to the objection that it is more a measure of the rate at which the substances are combined in the cell than a measure of the degree of permeability of the protoplasmic membrane to these substances.

(3) *By Plasmolytic Methods.*—Plasmolysis of a cell is caused by the inability of the solutes on the exterior of the cell to diffuse rapidly enough across the protoplasmic membrane to equalize the concentration of the cell sap with that of the exterior medium. This inequality of concentration may be due to the fact that the solutes are combined or rendered osmotically inactive after they have once entered the cell sap or that the protoplasmic membrane is not permeable to a sufficient degree to allow the solutes to enter rapidly enough. It is on the latter assumption that the plasmolytic methods for the studying of changes in permeability are based. Two methods have been the most generally used.

(a) *The Determination of Concentrations Necessary to Produce Plasmolysis.*—If the protoplasmic membrane is only slightly permeable to the solute in the external solution, the attaining of equilibrium between the cell sap and a hypertonic solution takes place slowly, so that an exterior solution, the concentration of which is only slightly above that of the cell sap, will almost immediately cause plasmolysis. If, on the other hand, the protoplasmic membrane is readily permeable to the solute under consideration, the solute will enter the cell and equilibrium between it and the cell sap will be quickly restored and plasmolysis will not result. The external concentration of the solute must therefore be increased to such an extent that even if the protoplasmic membrane is readily permeable to it, equilibrium will not be restored quickly enough to prevent plasmolysis. Thus if a cell or a portion of tissue under

condition *A* is plasmolyzed, for example, by a tenth-normal solution of NaCl and when placed under condition *B* it requires a fifth-normal solution of the same salt to produce plasmolysis, one may assume that the permeability of the protoplasmic membrane to NaCl is greater under condition *B* than it is under condition *A*.

b) *The Determination of the Time Required to Recover from Plasmolysis.*—If the formation of new osmotically active substances in the vacuole is not considered, the recovery of a cell from plasmolysis is due primarily to the diffusion of the solute of the exterior medium into the cell in sufficient amount to equalize the concentration of the cell sap and the exterior solution. Recovery from plasmolysis, therefore, will be more rapid if the protoplasmic membrane is readily permeable to the solute of the exterior solution than if it is only slightly permeable to it. Thus if a cell or the cells of a tissue are plasmolyzed by a hypertonic solution of NaCl and under condition *A* recovery from plasmolysis occurs in 30 min. while under condition *B* only 10 min. are required for recovery, it is considered that the permeability of the protoplasmic membrane to NaCl has increased under condition *B* as compared with what it was under condition *A*.

The main objection to the plasmolytic methods is that they do not take into consideration the possibility of the formation by the protoplasm of osmotically active substances in the cell sap, which if they were formed would have the same effect as solutes taken in from the external solution. The effect of ethyl alcohol on *Spirogyra* is of interest in this regard. Lepeschkin (1928) observed that the turgor pressure of this plant was decreased by a weak concentration of alcohol while a strong concentration of alcohol increased it to such an extent that the cells were torn to pieces. It is considered that the tannin in the cell sap is a colloidal solution in water, but in alcohol it becomes a molecular solution and thus increases the concentration of the cell sap. In a dilute solution of alcohol the permeability of the protoplasm is increased and the turgor pressure thus lessened.

(4) *By Electrical Conductivity of Tissues or Masses of Cells.*—“The conduction of an electrical current by a solution involves the passage through the solution of electrically charged ions of some substance. The rate at which the current will be conducted by the ions of a given salt will depend upon two factors, the potential gradient and the frictional or other resistance to the migration of the ions. If the potential gradient be kept constant we may follow fluctuations in the last factor by measurement of the current or by direct measurement of the electrical resistance. By the use of alternating currents of rather high frequencies, large effects due to the accumulation of ions at the surfaces impermeable to them is avoided” (Brooks, 1917). The electrical conductivity method of measuring the permeability of the protoplasmic membrane is based on the assumption that the electrical conductivity of a tissue is to be regarded as a measure of the permeability of the protoplasmic membrane. If the current is forced through the living protoplasmic membrane in a solution, the resistance offered by this membrane to the passage of ions is considered to vary inversely as the permeability. This electrical method was first used by Bugarsky and Tangl (1897) and Stewart (1897) but has been modified, elaborated, and extensively used by Osterhout (1912, 1918) and his pupils. Much of the work of Osterhout in measuring changes in permeability by the electrical conductivity method has been with the thallus of *Laminaria* after the following manner. One hundred to two hundred disks are cut from the fronds and packed together like a stack of coins. These form a cylinder 5 to 10 cm. high and about 1.3 cm. in diameter and are kept in position by means of glass rods. At each end of the cylinder and separated from it by a small amount of solution is a platinum electrode coated with platinum black and connected with an instrument for measuring the electrical conductivity. The general procedure is to immerse the stack of disks in a given solution and after drawing off the superfluous liquid to place the stack under the conditions mentioned above and measure the elec-

trical conductivity. There is sufficient solution between each of the disks to make the circuit, and experiments have shown that they are not injured even by prolonged treatment.

The manner in which the electrical conductivity method is used in determining changes in permeability can best be illustrated by a theoretical example. The resistance of a given column of disks after being immersed in a given solution *A* and then drained off, as has been previously mentioned, is 850 ohms. The same column after being immersed in solution *B*, which has the same conductivity as *A* but is of a different composition, and treated in the same manner has a resistance of 980 ohms. The assumption from this data is that the effect of solution *B* is to decrease the permeability of the protoplasmic membranes of the tissue under what it was in solution *A*. The question in dispute in regard to the reliability of this method is how far the electrical conductivity of tissue is a measure of the permeability of the protoplasmic membranes of the cells. Stiles and Jorgensen (1918) and Stiles (1924) have pointed out, however, that an increase in the conductivity of a tissue may be brought about in other ways than by an increase in the permeability of the protoplasmic membrane. They consider that changes in the content and nature of the electrolytes in the cell wall, protoplasm, and cell sap can have a marked influence on the alteration of the conductivity. Any factor such as diffusion which would bring about an increase in the amount of free electrolytes in the cell parts or the breaking down of large complex molecules to smaller ones, which are more mobile and undergo more ionization, would increase the conductivity of the tissues. These changes might increase the permeability of the protoplasmic membrane, but the increase in conductivity could be due, in part at least, to other factors.

(5) *By the Diffusion Method.*—This method was devised and used by Brooks (1917). His method of experimentation was as follows: Sections of glass tubing 18 mm. in diameter and respectively 2.5 and 4 cm. in length were cut, one end flared and ground flat. These pieces of tubing were combined in pairs each consisting of one long and one short piece of "cell." Disks of *Laminaria* were placed between the ground ends of each pair of cells and the joint made tight with a mixture of vaseline and beeswax. The lower piece of tubing or cell was closed at its unground end by a rubber tube and clip. The cell thus formed was filled with sea water or a pure salt solution of the same conductivity. The upper tube or cell contained a solution of half the concentration of that in the lower cell. The rate of increase of the electrical conductivity of the solution in the upper tube and the decrease in the conductivity of the solution in the lower tube was taken as a measure of the rate at which the salts in the lower cell passed through the tissue and thus a measure of the permeability of it. To eliminate the errors due to the diffusion of substances outwardly from the tissue and diffusion from the intercellular spaces, control experiments were made in which the more concentrated solution was contained in both upper and lower tubes, the average conductance of the solution in the upper tube of the controls at the end of the experiments being taken as the standard. Stiles (1924) considered that the principal objection to this method is "that there is no guarantee that the salt which diffuses into the tissue on the inner side is the same salt which diffuses out from the cells on the upper part of the cell wall and thus possible combinations between salts and cell constituents are avoided."

(b) *Direct Method.*—The reliability of the various indirect methods that have been used in determining permeability is open to question until they can be compared with results obtained by direct methods. In order to make direct determinations, it is necessary to extract the cell sap and then compare its composition with that of the solution extracts of the cells. The errors that are encountered in trying to analyze the cell sap have been enumerated above. The only known direct method is to extract the cells and to extract their cell sap without any contamination.

tion or change. Only a few cells, however, are large enough to give any satisfactory results by this method.

Wodehouse (1917) experimented with the marine alga *Valonia*, which has individual cells so large that the cell sap yields from 1 to 5 cc. of liquid. The cells were removed from the sea water, dried with filter paper, and then punctured with a needle. On pressing the cell wall, the cell sap exuded and was collected. Osterhout (1921) used the large multinucleate cells of a species of *Nitella* some of which reach a length of 6 in. and a diameter of $\frac{1}{32}$ in. Two methods were used for obtaining the cell sap. By one method the cell was placed on glue or filter paper and pierced with the point of a capillary tube which had been drawn out to a fine tip. The cell sap was by this means drawn up into the tube by capillary action and was not contaminated by the chloroplasts or protoplasm. The other method was to suspend the cell by the upper end, cut off the lower end, and bring it in contact with a glass slide and then to apply a slight pressure to the cell wall, beginning at the top. In this manner the cell sap flowed out on the slide, and by uniting the drops from several cells a sufficient quantity of material was obtained for examination. By this method Osterhout (1922, 1927) was able to compare direct observations of permeability behavior with that indicated by the electrical conductivity method and concluded that the conductivity method gives reliable information concerning permeability. The direct method of studying permeability has also been used by Irwin (1922) and Hoagland and Davis (1923). The results obtained by these various investigators will be discussed in full in Chap. V when the intake of solutes by the plant will be considered.

4. *Methods of Measuring the Permeability of the Protoplasmic Membrane to Water.*

The number of methods used in determining the permeability of the protoplasmic membrane to water are very few. Delf (1916) used the hollow leaves of the onion and the hollow scape of the dandelion for investigation. They lend themselves to this experiment because they present on their inside a natural surface of uncutinized thin-walled cells. An apparatus was employed by which a current of liquid could flow continuously through a cylinder 30 mm. in length of the tissue under investigation. It was so arranged that a solution of cane sugar could be immediately substituted for a water current, and *vice versa*, without altering the temperature of the tissue. The data on the passage of water across the protoplasmic membrane were obtained by observing the rate of shrinkage of the tissue under consideration when in contact with solutions that tended to plasmolyze them. An optical lever in connection with the tissue enabled alterations in length of 0.003 mm. or 1 part in 10,000 to be detected. An experiment of this nature cannot be carried out satisfactorily with strong plasmolyzing solutions because of the rapid shrinkage of the tissue. The solution must be sufficiently weak so that contraction will be comparatively slow and thus confine the experimentation to the strictly normal state of falling turgidity without the actual separation of the protoplasmic membrane from the cell wall. One of these is the rate of shrinkage of the tissue under these conditions is the resultant of two factors: the compressing force of the cell-wall action on the protoplasmic membrane which causes exudation of water, and the other is the permeability of the protoplasmic membrane for water. The influence of the permeability factor can be determined by comparing the tissues under consideration when the compressing force is equal. In the experiments of Delf, the points of 30, 50, and 70 per cent contraction were used, but the most acceptable series for the two kinds of tissue under consideration was the 50 per cent series.

The change-in-weight-and-volume method has been used (1917) to determine the rate of water intake by the tissue of carrot root. The intake of water was measured by immediate weighing and volume in water and weighing the tissue and volume at certain intervals. The change in weight under

and Jorgensen tuber and the rate of known increase in volume is attributed

uted to the amount of water taken up, since the weight of solutes that might diffuse outward during the experiment is considered negligible in comparison to the weight of water involved. The tissue in these experiments was cut in cylinders 1.8 cm. in diameter by means of a cork borer and then into disks 0.2 cm. in thickness by means of a hand microtome. Each experiment was run in triplicate or quadruplicate with a set of 20 disks.

5. *Factors That May Influence the Permeability of the Protoplasmic Membrane.* (a) *Temperature.* (1) *Influence on the Permeability of the Protoplasmic Membrane to Water.*—Rysselberghe (1901) studied the changes in the permeability by the plasmolytic methods and also by the rate of shrinkage of tissue in a 0.73 *N* solution of cane sugar. He observed especially the pith of the cells of the elder, *Spirogyra*, and the epidermal cells of *Tradescantia*. He found that the effect of temperature is significant from 0 to 20°C. but that from 20 to 30°C. the permeability of the protoplasmic membrane to water remains almost constant, as shown in the following table:

Temperature, degrees centigrade	Rate
0	1
6	1.9
12	4.5
16	6.3
20	7.1
25	7.5
30	8.0

Lepeschkin (1905) found that the volume of liquid extruded by hairs on the leaves of *Phaseolus multiflorus* increased from 0 to 20°C. and decreased from 20 to 35°C.

Delf (1916) found that the permeability of the protoplasmic membrane to water as measured by the rate of tissue shrinkage of the onion leaf and dandelion scape in a dilute sugar solution is increased continuously by temperature up to 42°C.—the highest temperature investigated. If the rate of permeability at 25°C. is taken as unity, the following relative values were established:

Temperature, degrees	Permeability	
	Onion	Dandelion
5	0.36	
10	0.44	0.22
15	0.50	0.30
20	0.66	0.50
25	1.0	1.0
30	1.7	1.9
35	2.9	3.0
40	5.0	5.0

Delf criticises the results of Rysselberghe in regard to the permeability remaining constant above 20°C. She considers that the sugar solution used by Rysselberghe was too concentrated for the best results, since a solution of that strength causes such a rapid contraction of the protoplasmic membrane that the cell wall cannot follow it. From her observations Delf considers that there is an upper limit to the rate at which the mechanical tissue system of the cell walls can collapse and shrink. If this assumption is correct, then no matter how rapidly the protoplasm contracts under the influence of the external solution, the cell wall cannot follow at a rate above a certain limit. In Rysselberghe's experiments that limit seemed to have been reached at 20°C. with a 0.73 *M* cane-sugar solution. Stiles and Jorgensen (1917) found that the temperature coefficients for the rate of swelling of the tissues of the potato tuber and root of carrot in distilled water were as follows:

Temperature, degrees centigrade	Temperature coefficients	
	Potato	Carrot
10 to 20	3.0	1.3
20 to 30	2.7	1.6

The rate of swelling, however, is dependent not only on the permeability of the protoplasmic membrane to water but on the elasticity of the cell wall and the permeability of the protoplasm to the dissolved materials in the cell sap. The previous history of the tissue under consideration also has a great influence on the results obtained.

The experimental evidence seems to indicate that the permeability of the protoplasmic membrane to water increases continuously from the lower to the higher temperatures so that if the other factors are the same the intake or outgo of water from the cells increases with a rise in temperature.

(2) *Influence on the Permeability of the Protoplasmic Membrane to Solutes.*—Rysselberghe (1901) found that the permeability of the protoplasmic membrane of the epidermal cells of *Tradescantia discolor* to glycerin, potassium nitrate, and urea increases from 0 to 30°C. Lepeschkin (1905) observed that the protoplasm of the leaves of *Phaseolus multiflorus* increased in permeability to the solutes of the cell sap from 0 to 20°C. and decreased from 20 to 35°. Eckerson (1914) investigated the influence of temperature on the permeability of the protoplasmic membranes of the cells of the roots of numerous plants. The results were obtained on the assumption that an increase in the concentration which is necessary to cause plasmolysis corresponds to an increase in the per-

meability of the protoplasm. Potassium nitrate was used, for the most part, as the plasmolyzing agent, and the tests for permeability were carried on under controlled temperatures. The permeability of the protoplasm of the cells of the radish root to KNO_3 was found to increase from 10 to 18°C. but did not change from 18 to 24°C., increased from 24 to 40°C., and then decreased. The permeability of these cells to glucose was observed to increase gradually from 10 to 40°C. and then decrease. The permeability to sucrose remained constant until temperatures above 42°C. were reached. *Helianthus annuus* showed no increase in permeability with increase in temperature but a decrease from 20 to 40°C. The primary roots of *Phaseolus multiflorus* exhibited no increase in permeability from 13 to 20°C., while the secondary ones increased in permeability from 6 to 25°C. Both types of roots decreased in permeability from 25 to 35°C.

The following table is a summary of the work of Eckerson on the relation of temperature to the changes in permeability to potassium nitrate:

PERMEABILITY VARIATIONS OF THE PROTOPLASMIC MEMBRANE TO KNO_3 AT DIFFERENT TEMPERATURES¹

Cells of the root of	Degrees centigrade			
	+	0	+	-
<i>Raphanus sativus</i>	10 to 14	18 to 24	24 to 40	40 to 50
<i>Pisum sativum</i>	6 to 15	15 to 35	35 to 45
<i>Sinapis alba</i>	10 to 30	30 to 45
<i>Helianthus annuus</i>	12 to 20	20 to 40
<i>Phaseolus multiflorus</i>
Primary roots.....	13 to 20	25 to 40
Secondary roots.....	6 to 25	25 to 40

¹ In the table a plus sign indicates increasing permeability; zero indicates no changes in permeability, while a minus sign indicates a decrease in permeability.

The work of Eckerson indicates that the changes in permeability due to changes in temperature vary with the species, with different temperatures, and with the plasmolyzing agent used.

Sen (1928) found that the permeability of the plasma membrane to ions increased with rising temperature from 20 to 30°C. in *Aloe* leaves and in *Bassella* stems. From 30 to 35°C. there was little or no increase, while beyond 35 or 40°C. and up to the lethal temperature, the permeability decreased but is reversible up to 40 or 45°C. At the lethal temperature, the plasma membrane becomes highly permeable, a change which is irreversible (see also Dixon, 1924).

(b) *Light*.—Lepeschkin (1908) observed that light increases and darkness decreases the permeability of the protoplasm of the pulvinal cells of the legumes. The increase in the permeability of the protoplasmic membrane of these cells results in a decrease of their volume, while a decrease in permeability brings about an increased turgor pressure and an increase in volume. Tröndle (1909, 1910, 1918) found that the protoplasm of the cells of the leaves of *Tilia europaea*, *Buxus sempervirens*, *Salix babylonica*, and *Acer platanoides* are more permeable to sodium chloride in light than in darkness. The permeability of the cells of the leaves of *Buxus* and *Tilia* was found to be 17.6 and 33 per cent, respectively, greater in sunlight than in cloudy weather. If the leaves were held at the same temperature, increasing illumination increased the rate at which sodium chloride passed into the cell up to a certain maximum of light intensity which varies with the kind of plant. Ruhland (1911) found that light was without any measurable influence on the permeability of the protoplasmic membrane of the cells of the sugar beet to sucrose, glucose, and fructose. Hoagland and Davis (1923) observed that the alga *Nitella* absorbed more solutes from the surrounding medium in light than in darkness. They considered that light in this case is of primary importance as a source of energy in the process of absorption. This assumption will be discussed in detail in Chap. V, when the absorption of solutes is considered.

(c) *The Nature of the Solutes*.—The influence of the various dissolved substances on the permeability of the protoplasm can best be understood by a summary of the results obtained by the various workers in that field. Osterhout (1911) found that a 0.2 *M* solution of CaCl_2 just plasmolyzed the cells of *Spirogyra* and that a 0.38 *M* NaCl solution did the same. The cells, however, were not plasmolyzed by a 0.195 *M* CaCl_2 solution or a 0.375 *M* NaCl solution. If, however, 10 cc. of a 0.195 *M* solution of CaCl_2 is mixed with 1,000 cc. of the 0.375 *M* NaCl solution and *Spirogyra* cells placed therein, prompt plasmolysis occurs. The addition of the CaCl_2 lowers the osmotic pressure of the solution, but in spite of that it plasmolyzes the cells. Thus by mixing two solutions, neither of which plasmolyzes, one is obtained that plasmolyzes very strongly. Osterhout (1915) used the electrical conductivity method to determine the effects of various salts on permeability. Tissue of *Laminaria saccharina* in sea water had a net resistance of 770 ohms or a net conductance of 0.00130 reciprocal ohm. When the tissue was transferred to a 0.52 *M* solution of NaCl having the same conductivity as sea water, the resistance dropped to 580 ohms in 5 min. or a net conductance of 0.001720 reciprocal ohm. The increase in permeability of the protoplasmic membrane thus amounted to 0.00042 reciprocal ohm or 32.3 per cent. This increase in conductance is not due to the increase in the number of ions of sodium chloride to which the protoplasmic mem-

brane might be considered to be normally more permeable than those of ordinary sea water. For example, in one case when the tissue was transferred from sea water to 0.52 *M* NaCl the conductance increased 25.2 per cent. The increase in sodium ions amounted to only 2 per cent, while the content of chlorine ions remained unchanged. Osterhout considers that this is evidence that there was a great increase in permeability of the protoplasm which was induced by the NaCl. The effect of CaCl₂ on the permeability of the protoplasm of *Laminaria* was found by the electrical conductivity method as follows: The net resistance of a portion of tissue in sea water was 770 ohms. After transferring it to a 0.278 *M* solution of CaCl₂ the net resistance rose within 10 min. to 1,260 ohms. This represents a decrease in permeability of 39.2 per cent. Osterhout found that KCl, LiCl, NH₄Cl, NaBr, NaI, NaNO₃, KNO₃, and Na₂SO₄ all act, in general, like NaCl in increasing the permeability. All the bivalent cations investigated, *viz.*, Mg, Ca, Ba, Sr, Mn, Co, Fe, Zn, Cd, and Sn, decreased permeability, and all the trivalent cations considered, *viz.*, La, Fe, Al, Ce, and Y, did the same. NaOH increased the permeability, while HCl produced a rapid decrease which was followed at once by a rapid increase that continued until the death point was reached. Hydrogen is the only monovalent cation that was found able to decrease the permeability of the protoplasm.

Raber (1920) investigated the effect of a series of anions on the permeability of *Laminaria agardhu* by means of the electrical conductivity method. He used sodium sulphocyanide, iodide, nitrate, bromide, chloride, acetate, sulphate, tartrate, phosphate, and citrate in solutions having the same conductivity as a 0.51 *M* solution of sodium iodide. Measurements of the conductivity were taken, for the most part, at the end of 5, 25, 45, 85, and 105 min. and the effect of these anions upon the increase in permeability at the end of the experiment stood in the following order: I > Br > SCN < Cl > NO₃ > acetate > SO₄ > tartrate > PO₄ > and citrate. From later work (1921) Raber considers that his results indicate that the effects upon permeability depend upon the valence of the anions regardless of whether the salts are organic or inorganic. He further found that bivalent and trivalent cations in combination with monovalent cations increase the electrical resistance of the protoplasm of *Laminaria*, but when combined with bivalent or trivalent anions the increase is less and may be entirely lacking. Chromium has a different initial effect upon the permeability of *Laminaria*, depending upon whether it occurs as the cation or the anion of the salt. If it is an anion, the first effect is a decrease in resistance, but if it is a cation, it increases the resistance. Osterhout (1913, 1916) observed that anesthetics, as ether and chloroform, increase or decrease permeability, depending upon the concentration used. Very low concentrations were found to produce little or no effect, but a point in concentration was soon reached in which a

decrease in permeability could be maintained for several hours. This change is reversible and produces no injury. A higher concentration causes for a very short time a decrease and then an increase in permeability which is not reversible and continues until death ensues.

Osterhout (1915) in experiments with *Laminaria saccharina* by the electrical conductivity method showed that it is possible to bring about extreme changes in the permeability of the protoplasmic membrane without injury. Experiments were conducted over a period of 15 days in which the tissue each day was transferred from sea water to 0.52 *M* NaCl for 5 to 10 min. and then transferred again to sea water where it always regained its original permeability. The increase in permeability in the NaCl solution over that in sea water amounted to 20.3 per cent. The tissue which underwent this daily alteration in permeability retained its normal resistance in sea water until the tenth day, when it began to fall off. The control, however, showed the same results, so that the fall in resistance was due to other causes than the effects of the sodium chloride. The permeability was decreased 23 per cent by transference from normal sea water to sea water containing 0.01 *M* lanthanum nitrate for 5 min. After being again placed in normal sea water it regained its original permeability. The procedure was followed each day for 5 days, being repeated three or four times daily. At the end of the fifth day this tissue was from all appearances in as good condition as the control and had a slightly higher resistance. In another series of experiments covering a period of 3 days, the tissue was transferred from sea water to a 0.278 *M* solution of CaCl₂, which has the same conductivity as sea water, and then to a 0.52 *M* NaCl and then again to sea water. The resistance of the tissue in sea water was 1,010 ohms; after 10 min. in the CaCl₂ solution, it had risen to 1,500 ohms; and after being removed from the CaCl₂ and transferred to the NaCl solution, it fell to 880 ohms. After 80 min. the tissue was again placed in sea water where it soon gained its normal resistance of 1,010 ohms. The permeability of the protoplasmic membrane in the CaCl₂ solution decreased 39.2 per cent below the normal permeability in sea water, while in the NaCl solution it increased 20 per cent above normal. Regardless of these wide alterations of permeability, the tissue at the end of the experiments was to all appearances absolutely normal.

Stiles and Jorgensen (1917) studied the action of various organic substances on the permeability of plant cells by estimating the exosmosis of electrolytes from potato tissue especially immersed in watery solution of the substances. The exosmosis was estimated by the change in conductivity of the solution. They found that equimolecular solutions of different substances do not bring about the same exosmosis. In the homologous series of the monohydric alcohols the more complex the molecule the greater the exosmosis produced by solutions of equimolecular

strength. They were unable to find a critical concentration of solution below which exosmosis of electrolytes will not take place. Bartlett and True (1915) found that when a plant like white lupine was grown in distilled water, leachings took place and that this exosmosis was increased in dilute solutions of NaCl and KCl. In dilute solutions of CaCl₂, however, leaching stopped and absorption took place. The inference is that the permeability of the protoplasmic membrane of the roots of the plant was increased by the NaCl and KCl and decreased by the CaCl₂.

E. THEORIES OF MEMBRANE ACTION

Numerous theories have been put forward to explain the differential permeability of membranes but most of them can be grouped under one of the following four headings.

1. Sieve or Ultrafiltration Theory.—This theory assumes that the membrane acts as a sort of ultra screen or sieve, so that molecules below a certain size pass through while those above a limiting size are held back. The theory was first put forward by Traube (1867) in order to explain the behavior of his precipitation membranes. Later it was proposed to explain the differential permeability of the protoplasm to various substances and has received considerable support from the work of Küster (1911, 1918) and Ruhland (1912, 1913, 1914) on the intake of dyes by certain plant cells. These investigators studied the behavior of the cells of *Vicia faba*, *Allium cepa*, *Spirogyra*, *Helianthus annuus*, and *Coleus hybridus* with respect to over 80 different acid and basic dyes.

Ruhland concluded that his work indicated that the entrance or non-entrance of a substance into the cell is related to the magnitude of its molecules or molecular aggregates and that the plasma membrane acts as an ultra filter. The behavior of the plasma membrane in the plant cells and of artificial parchment membranes toward dyes offers the strongest evidence for this theory, but there are numerous other cases where the observed facts are not in accord with the theory. Thus it has been shown that certain membranes are permeable to the large molecules of the alkaloids while they are impermeable to the relatively small molecules of the amino acids.

2. The Solution Theory.—This theory assumes that a membrane has definite solvent properties and that only those substances which are soluble in the membrane are capable of passing through it. The chief advocate of this theory in regard to the behavior of the protoplasmic membrane has been Overton (1895, 1896, 1899, 1900), who proposed the lipid theory. This investigator from his observations on the permeability of the protoplasm to certain dyes and other organic substances concluded that the penetration of different substances into the protoplasm depends upon the solubility of these substances in the lipoids which with the proteins form the plasma membrane. This theory has only a very

limited application and the chief objection to it arises from the behavior of the numerous inorganic salts which for the most part are insoluble in lipid substances, but which are known to enter the cells freely and in large amounts. MacDougal (1928) in experiments with an artificial cell showed that the presence of a phospholipid such as lecithin alone lessens permeability and allows the attainment of a high degree of turgidity. Artificial cells, including both cholesterol and lecithin, showed certain behaviors in balanced solutions of sodium and calcium concurrent with those of living cells. It was found that ions penetrate a lipoidal cell more rapidly from solutions at P_{H} 4.5 in contrast with the maximum for a lipid-free cell at P_{H} 5.4 of the solution. A lecithin-cholesterol suspension also stabilized the H-ion concentration of the cell content. This work of MacDougal indicates that certain lipoids in the protoplasm do influence the diffusion of organic and inorganic ions across it, but the exact manner in which they do so is not at present understood.

3. The Chemical Theory.—According to this theory the membrane is supposed to combine chemically with the substance to which it is permeable. This reaction is considered to be a reversible one, so that the diffusing substance is freed on the far side from its combination with the membrane. The chemical theory has received considerable support from numerous biological workers.

The temperature coefficient of permeability has been studied by numerous investigators in order to ascertain the nature of the absorption process through membranes. By the temperature coefficient of permeability is meant the increase in the permeability of the membrane for each 10°C. increase in temperature. The temperature coefficient for any reaction is commonly expressed by the symbol Q_{10} . That of chemical reactions is relatively high (2 to 3), while that of physical reactions is relatively low (1 to 1.5). Pfeffer (1877) measured the rate of water movement through the copper ferrocyanide membranes at different temperatures and found that from 7.1 to 17.6°C., $Q_{10} = 1.56$, and from 17.6 to 32.5°C., $Q_{10} = 1.27$. Krabbe (1896) observed that the temperature coefficient of permeability of the living pith cells of *Helianthus annuus* and of the roots of *Vicia faba*, from 0 to 20°C., was 2 to 2.5. He believed that this high coefficient indicated that purely physical forces were not operative but that the changes were due to the peculiar properties of the protoplasm. Rysselberghe (1901) studied the effect of temperature upon the permeability of the living protoplasm of the pith cells of *Sambucus nigra* and the epidermal cells of *Tradescantia* and found that from 0 to 30°C., Q_{10} averaged 2.0. Brown and Worley (1912) studied the rate of intake of water by the barley grains at different temperatures and obtained a temperature coefficient of 1.8 to 1.9. They considered that this indicated that chemical processes were involved in the penetra-

tion of water through the semipermeable seed coat of the barley grain. Shull (1920), however, found that the mean value of Q_{10} in *Xanthium* seeds was in one instance 1.55, in another 1.83, and in the case of split peas 1.6. He considered that his data do not support the theory of Brown and Worley but that the velocity of intake at any given moment in the seeds that were studied is approximately an inverse exponential function of the amount of water previously absorbed. He considers that his values do not indicate that absorption is conditioned by some single chemical change like simplifications of water to hydrone as the temperature rises but that absorption at different temperatures involves both physical and chemical changes.

Stiles and Jorgensen (1915) used 0.0011 *M* HCl in which they placed plant tissue to observe the penetration of the H ions at various temperatures. They found that $Q_{10} = 2.22$ from 0 to 10°C. and 2.17 from 10 to 20°C. They believed that the high temperature coefficient thus obtained indicated that the process of absorption is a chemical and not a physical reaction. Osterhout (1917) criticizes their conclusions on the ground that they, as many others, have not distinguished between permeability and absorption. The chemical process thus thought to have been observed might have been the union of the H ions with substances within the cell, and the permeability of the membranes thus might not have been considered. His experiments with the permeability of *Laminaria* gave a temperature coefficient of 1.3, which he considered suggested a physical reaction, although he was not positive. Denny (1917) measured the flow of water through the seed coat of *Arachis hypogaea* at temperatures ranging from 3.6 to 45°C. and found that Q_{10} ranged in value from 1.6 to 1.3, the coefficient being higher at the lower temperatures and lower at the higher temperatures, a fact which has been observed for a great many physical and chemical processes. The results obtained by Delf (1916), however, in measuring the temperature coefficient for increase of permeability for the onion leaf and the scape of the dandelion are in contrast to these. She found, for example, that the temperature coefficient between 10 and 20°C. was 1.5 and 2.3, respectively, for the onion leaf and dandelion scape, while from 20 to 30°C. it was 2.6 for the onion leaf and 3.8 for the dandelion scape. Denny (1917) makes the very important statement to the effect that the temperature effects on permeability thus observed may not be merely upon the membranes under consideration but also upon the cell contents. This latter effect may contribute to the total results so that the chemical reaction indicated by the relatively high temperature coefficient may have taken place in that part of the cell which is internal to the membrane under consideration. There seems thus to be no evidence that either physical or chemical processes are exclusively involved in the passage of materials through the membranes of the plant cell.

4. Colloidal Theories.—Since the protoplasmic membrane is regarded as an emulsoid polyphase colloidal system, numerous hypotheses have been proposed to explain its permeability upon the basis of changes in viscosity, phase inversion, or electrical reactions, which are common phenomena in colloidal suspensions or solutions. Spaeth (1916) suggested that the permeability of the protoplasmic membrane is determined by its viscosity which in itself is determined by the degree of dispersion of the colloids contained in it. Clowes (1916) supposed that changes in permeability are brought about by the continuous and discontinuous phases changing places. He used, as a support of his theory, data obtained in experiments on the effect of sodium hydroxide and calcium chloride in producing phase inversion in emulsion systems of olive oil and water.

Free (1918) and Lloyd (1915) considered that at least two of the liquid phases of protoplasm differ importantly only in the proportion of water which they contain. Changes in permeability are supposed to be due to changes in the distribution of water between the continuous and the discontinuous phase. When globules of the discontinuous phase are large, the spaces between them will be small; while if the globules of the discontinuous phase are small, the spaces between them will be large. A substance thus diffusing through the continuous phase will move faster or slower according to the dimensions of the spaces.

Kaho (1921) considers that the penetration of neutral salts into plant protoplasm is a physico-chemical process which depends upon the colloidal activity of the salts. The penetration of the salt depends upon the ability to change the colloidal condition of the plasma membrane in which the action of each salt is the additive effect of the oppositely acting ions. The cations have a coagulating effect which lowers the permeability for the salt. The anions have a peptizing or dissolving action on the plasma colloids which increases the permeability for the salt. The resulting action of a neutral salt is the algebraic sum of these opposite tendencies. He considers that the lipid materials in the surface layer of the cytoplasm play an important rôle in the entrance of neutral salts. These conclusions are supported by the observations of MacDougal (1923) with artificial cells. The main arguments against the various colloidal theories of permeability that have been proposed are that in many cases the phenomena suggested as influencing permeability have little or no effect in producing changes in the rate of diffusion of substances through colloidal systems and in other cases the data presented to explain the theory of permeability have been obtained under conditions that are definitely known not to occur in the plant.

No theory of membrane action has been proposed which will explain satisfactorily the behavior of the protoplasmic membrane. The passage of materials through it may occur to a certain extent after the manner proposed in the various theories that have herein been mentioned. When

one considers, however, the highly complex nature of protoplasm, its rapid adjustment to its environmental surroundings, its highly specialized nature for different individuals, tissues, and even for the different parts of the same cell, it would seem most unlikely that any one theory could be proposed that would cover its behavior under all conditions toward the various substances that diffuse across it.

Questions

43. Why are solutions and membranes studied in plant physiology?
44. What is a true solution? In what four ways may the concentration of a true solution be expressed? Which methods of expression are most frequently used in biological work? What is a colloidal solution?
45. What is the solvent? The solute? Give examples. What solvents are concerned in plant life? What solutes?
46. What is meant by diffusion? State five simple laws concerning the diffusion of solvent and solute in a solution. Illustrate by diagrams.
47. What is a membrane? What does the term include in plant physiology? What is meant by the permeability of a membrane? What factors influence the permeability of membranes?
48. Define permeable, impermeable, and semipermeable membranes. What is a natural membrane? An artificial membrane? Give examples.
49. Name the membranes of the plant cell. What one varies to the greatest extent in its degree of permeability?
50. What is imbibition? Cite examples. What determines the force of imbibition? Why is the imbibition of water considered in relation to membranes? How is water continuous from cell to cell?
51. How does the diffusion of the solvent and solute through membranes differ from diffusion through a solution?
52. Given a vessel with rigid walls but a portion of which, at least, is a semipermeable membrane to a solution of cane sugar. Describe in detail what would occur if this vessel were filled with a half-normal solution of cane sugar, sealed with the exception of a mercury manometer, and then immersed in distilled water.
53. Given a vessel similar to the above with the exception that a portion of the wall is a membrane permeable to a solution of cane sugar. Describe in detail what would occur if this vessel were filled with a two-fifths normal solution of cane sugar, sealed with the exception of a manometer, and then immersed in a fifth-normal solution of cane sugar.
54. What would occur if the above vessel were filled with a fifth-normal solution of cane sugar and then immersed in a two-fifths normal solution of this carbohydrate?
55. Define osmosis (*a*) when a perfectly semipermeable membrane is used and (*b*) when a membrane is used which is permeable to both the solvent and solute.
56. What is endosmosis? Exosmosis? Osmotic pressure?
57. How do cell walls vary in regard to their permeability to water? Give examples. What compounds in the cell wall retard the diffusion of water across it? How was it demonstrated that these compounds retard the passage of water?
58. Name some membranes through which the rate of water flow is greater in one direction than in another. Name some in which the flow is the same in either direction.
59. To what is this difference in the rate of flow due? How might this behavior of a double membrane be of importance in the water relations of the plant cell?

60. Name five cases in which the cell walls of seed coats behave as semipermeable membranes. Name some of the compounds to which these cell walls are semipermeable in solution. Of what importance is this property of the cell walls of the seed coats?

61. What cell walls of the endodermis show semipermeability? Of the onion-bulb scale? To what substances do they show semipermeability?

62. What is the protoplasmic membrane? What are its general characteristics? What is the origin of this membrane?

63. What is the plasma membrane? By what other name has it been called? What evidence is there that such membranes exist?

64. Are the plasma membranes constant in their organization? Why? How has it been shown that the two surfaces of the protoplasmic membrane are different?

65. How does the protoplasmic membrane vary in its permeability to solutes? To water? Why is the permeability of the protoplasm so variable?

66. What is an isotonic solution? A hypertonic solution? A hypotonic solution? What is incipient plasmolysis? Evident plasmolysis?

67. What is meant by the osmotic value of the cell sap? When is it the greatest? When the least?

68. What is the osmotic value of the external solution? How does it influence the osmotic pull of the cell sap?

69. What is the turgor pressure of the plant cell? When is it the greatest? When the least?

70. What is the suction pressure of the cell? When is it the greatest? When the least? Name some plant tissues in which a suction-pressure gradient has been shown to exist. Of what importance is this gradient?

71. Describe in detail what would occur if a turgid cell were placed in a relatively strong hypertonic solution if the protoplasmic membrane were (a) impermeable to the solute and (b) permeable to the solute—the protoplasmic membrane in both cases being impermeable to the solutes of the cell sap.

72. Explain why there may be no relationship between the degree of permeability of the cell membranes to a solute and the amount of solute which enters the cell.

73. Name and describe four indirect methods of determining changes in the permeability of the protoplasmic membrane to solutes. State the advantages and disadvantages of each method.

74. Under condition *A* the electrical resistance of a set of tissues is 850 ohms. Under condition *B* the resistance is 980 ohms. How does the permeability of the protoplasmic membrane to solutes compare under these two conditions? Why?

75. Under condition *X* the cells of a given tissue are just plasmolyzed with a fortieth-normal solution, while under condition *Y* it requires a twentieth-normal solution to plasmolyze the cells of the same tissue. How does the permeability of the protoplasmic membrane to the solute used compare under these two conditions? Why?

76. Under condition *C* a cell is plasmolyzed in a given solution but recovers from plasmolysis in 20 min. when left therein. Under condition *D* it is plasmolyzed by the same solution but requires 30 min. to recover from plasmolysis. Under which condition is the protoplasmic membrane the more permeable to the solute used? Why?

77. What direct method has been used for determining changes in the permeability of the protoplasmic membrane? What are its limitations?

78. In what two ways have the changes in the permeability of the protoplasmic membrane to water been studied?

79. How does temperature influence the permeability of the protoplasmic membrane to water? Discuss in detail the influence of temperature on the permeability of the protoplasmic membrane to solutes.

80. How does light influence the permeability of the protoplasmic membrane?

81. Name the cations that increase the permeability of the protoplasmic membrane. Name those that decrease it. How do anions affect the permeability of the protoplasm?

82. How do anesthetics affect the permeability of the protoplasmic membrane? State some cases in which extreme alterations of the protoplasmic membrane have been produced by solutes without injury to the cell.

83. Name and discuss four theories of membrane action. What is the temperature coefficient?

84. What evidence is there that diffusion is a chemical process? A physical process? What is the objection to considering the temperature coefficient as an index to the nature of permeability?

Bibliography

- BECK, W. A., 1928: Osmotic pressure, osmotic value and suction tension, *Plant Physiol.*, **3**: 413-441.
- BECQUEREL, PAUL, 1907: Recherche sur la vie latente des graines, *Ann. Sci. Nat. Bot.*, **IX**, **5**: 193-320.
- BROOKS, S. C., 1917: Permeability of the cell walls of *Allium*, *Bot. Gaz.*, **64**: 509-512.
- , 1917: Methods of studying permeability of protoplasm to salts, *Bot. Gaz.*, **64**: 230-249.
- , 1917: A new method of studying permeability, *Bot. Gaz.*, **64**: 306-317.
- , and S. GELFAN, 1928: Bioelectric potentials in *Nitella*, *Protoplasma*, **5**: 84-96.
- BROWN, A. J., 1907: On the existence of a semipermeable membrane enclosing the seeds of the *Gramineae*, *Ann. Bot.*, **21**: 79-87.
- , 1909: The selective permeability of the coverings of the seeds of *Hordeum vulgare*, *Proc. Roy. Soc. London*, **B**, **81**: 82-93.
- , and F. P. WORLEY, 1912: The influence of temperature on the absorption of water by seeds of *Hordeum vulgare* in relation to the temperature coefficient of chemical change. *Proc. Roy. Soc. London*, **B**, **85**: 546-553.
- , and F. TINKER, 1916: The rate of absorption of various phenolic solutions by seeds of *Hordeum vulgare* and the factors governing the rate of diffusion of aqueous solutions across semipermeable membranes, *Proc. Roy. Soc. London*, **B**, **89**: 119-135.
- and ———, 1916: Selective permeability: The absorption of phenol and other solutions by the seeds of *Hordeum vulgare*, *Proc. Roy. Soc. London*, **B**, **89**: 373-379.
- BUGARSKY, S., and F. TANGL, 1897: Eine Methode zur Bestimmung des relativen Volums der Blutkörperchen und des Plasmas, *Zentralbl. f. Physiol.*, **11**: 297.
- CLOWES, G. H. A., 1916: Protoplasmic equilibrium. I, Action of antagonistic electrolytes on emulsions and living cells, *Jour. Phys. Chem.*, **20**: 407-451.
- COLLINS, E. J., 1918: The structure of the integumentary system of the barley grain in relation to localized water absorption and semipermeability, *Ann. Bot.*, **32**: 381-414.
- CROZIER, W. J., 1919: Intracellular acidity in *Valonia*, *Jour. Gen. Physiol.*, **1**: 581-583.
- DELF, E. M., 1916: Studies of protoplasmic permeability by measurement of rate of shrinkage of turgid tissues. I, Influence of temperature on the permeability of protoplasm to water, *Ann. Bot.*, **30**: 283-310.
- DENNY, F. E., 1917: Permeability of certain plant membranes to water, *Bot. Gaz.*, **63**: 373-397.
- , 1917: Permeability of membranes as related to their composition, *Bot. Gaz.*, **63**: 468-485.
- DE VRIES, H., 1884: Eine Methode zur Analyse der Turgorkraft, *Jahrb. f. wiss. Bot.*, **14**: 427-601.

- DE VRIES, H., 1884: Zur plasmolytischen Methodik, *Bot. Zeitung*, **42**: 289-298.
- , 1885: Plasmolytische Studien über die Wand der Vacuolen, *Jahrb. f. wiss. Bot.*, **16**: 465-598.
- DIXON, H., 1924: Variations in the permeability of leaf cells, *Roy. Dublin Soc. Sci. Proc.*, **17**: 349-356.
- ECKERSON, SOPHIA, 1914: Thermotropism of roots, *Bot. Gaz.*, **58**: 254-263.
- FINDLAY, A., 1913: "Osmotic Pressure," 82 pp., Longmans, Green and Co.
- FISCHER, M. H., 1915: "Oedema and Nephritis: A Critical, Experimental and Clinical Study of the Physiology and Pathology of Water Absorption in the Living Organism," 2d ed., John Wiley & Sons, Inc., New York.
- FREE, E. E., 1918: A colloidal hypothesis of protoplasmic permeability, *Plant World*, **21**: 141-150.
- FUJITA, A., 1925: Untersuchungen über elektrische Erscheinungen und Ionendurchlässigkeit von Membranen. I, Die Potentialdifferenz an der Apfelschale, *Biochem. Zeits.*, **158**: 11-27.
- GIGLIOLI, ITALO, 1895: Latent vitality in seeds, *Nature*, **52**: 544-545.
- HOAGLAND, D. R. and A. R. DAVIS, 1923: The composition of the cell sap of the plant in relation to the absorption of ions, *Jour. Gen. Physiol.*, **5**: 629-647.
- and ———, 1923: Further experiments on the absorption of ions by plants, including observations on the effect of light, *Jour. Gen. Physiol.*, **6**: 47-62.
- IRWIN, M., 1922: Penetration of dyes into living cells, *Amer. Jour. Physiol.*, **59**: Proc. 458.
- , 1923: The permeability of living cells to dyes as affected by hydrogen ion concentration, *Jour. Gen. Physiol.*, **5**: 223-224.
- , 1923: The penetration of dyes as influenced by hydrogen ion concentration, *Jour. Gen. Physiol.*, **5**: 727-740.
- KAHO, H., 1921: Ein Beitrag zur Permeabilität des Pflanzenplasmas für die Neutral-salz, IV, *Biochem. Zeits.*, **123**: 284-303; *Rev. Bot. Gaz.*, **81**: 350-353 (1926).
- KITE, G. L., 1915: Studies on the permeability of the internal cytoplasm of animal and plant cells, *Amer. Jour. Physiol.*, **37**: 282-299.
- KOTOWSKI, F., 1927: Semipermeability of seed coverings and stimulation of seeds, *Plant Physiol.*, **2**: 177-186.
- KRABBE, G., 1896: Über den Einfluss der Temperatur auf die osmotischen Prozesse lebender Zellen, *Jahrb. f. wiss. Bot.*, **29**: 441-498.
- KÜSTER, E., 1911: Ueber die Aufnahme von Anilinfarben in lebende Pflanzenzellen, *Jahrb. f. wiss. Bot.*, **50**: 261-288.
- , 1918: Ueber Vitalfärbung der Pflanzenzellen, *Zeits. f. wiss. Mikroskopie*, **35**: 95-100.
- LAIVSON, JEAN, 1910: Du mode de pénétration de quelques sels dans la plante vivante; Role de l'endoderme, *Rev. Gen. Bot.*, **22**: 225-241.
- , 1911: Recherches sur la pénétration des sels dans le protoplasm et sur la nature de leur action toxique, *Ann. Sci. Nat. Bot.*, IX, **14**: 97-139.
- , 1911: Essai sur une théorie de la nutrition minérale des plantes vasculaires, *Rev. Gen. Bot.*, **23**: 177-211.
- LEPESCHKIN, W. W., 1906: Zur Kenntnis des Mechanismus der aktiven Wasserausscheidung der Pflanzen, *Beih. Bot. Centrbl.*, I, **19**: 409-452.
- , 1908: Über die osmotischen Eigenschaften und den Turgordruck der Blattgelenkzellen der Leguminosen, *Ber. d. d. bot. Ges.*, **26**: 231-237.
- , 1908: Zur Kenntnis des Mechanismus der Variationsbewegungen, *Ber. d. d. bot. Ges.*, **26**: 724-735.
- , 1909: Zur Kenntnis des Mechanismus des photonastischen Variationsbewegungen und der Einwirkung des Beleuchtungswechsels auf die Plasmamembran, *Beih. Bot. Centrbl.*, I, **24**: 308-356.

- LEPESCHKIN, W. W., 1928: The effect of ethyl alcohol on the turgor pressure of *Spirogyra*, *Amer. Jour. Bot.*, **15**: 422-424.
- LIVINGSTON, B. E., 1913: Osmotic pressure and related forces as environmental factors, *Plant World*, **16**: 165-176.
- LLOYD, F. E., 1915: The behavior of protoplasm as a colloidal complex, *Carnegie Inst. Wash. Yearbook*, **14**: 66-69.
- MACDOUGAL, D. T., 1923: Permeability and the increase of volume contents of living and artificial cells, *Proc. Amer. Phil. Soc.*, **62**: 1-26.
- , 1924: The arrangement and action of material in the plasmotic layers and cell walls of plants, *Amer. Phil. Soc. Proc.* **63**: 76-93.
- and V. MORAVEK, 1927: The activities of a constructed colloidal cell, *Protoplasma*, **2**: 161-188.
- , 1928: Substances regulating the passage of material into and out of plant cells: The lipoids, *Proc. Amer. Phil. Soc.*, **67**: 33-45.
- MICHAELIS, L., and A. FUJITA, 1925: Untersuchungen über elektrische Erscheinungen und Ionendurchlässigkeit von Membranen. II, Die Permeabilität von Apfelschale, *Biochem. Zeits.*, **158**: 28-37.
- MOLZ, F. J., 1926: A study of suction force by the simplified method. I, Effect of external factors, *Amer. Jour. Bot.*, **13**: 433-463.
- , 1926: A study of suction force by the simplified method. II, Periodic variations and the influence of habitat, *Amer. Jour. Bot.*, **13**: 465-502.
- OSTERHOUT, W. J. V., 1911: The permeability of living cells to salts in pure and balanced solutions, *Science*, n. s., **34**: 187-189.
- , 1912: Permeability of protoplasm to ions and the theory of antagonism, *Science*, n. s., **35**: 112-115.
- , 1912: Reversible changes in permeability produced by electrolytes, *Science*, n. s., **36**: 350-352.
- , 1913: Some quantitative researches on the permeability of the plant cell, *Plant World*, **16**: 129-144.
- , 1913: The effect of anesthetics upon permeability, *Science*, n. s., **37**: 111-112.
- , 1913: The organization of the cell with respect to permeability, *Science*, n. s., **38**: 408-409.
- , 1914: The effect of alkali on permeability, *Jour. Biol. Chem.*, **19**: 335-343.
- , 1914: The effect of acid on permeability, *Jour. Biol. Chem.*, **19**: 493-501.
- , 1915: Extreme alteration of permeability without injury, *Bot. Gaz.*, **59**: 242-253.
- , 1915: On the decrease of permeability due to certain bivalent kations, *Bot. Gaz.*, **59**: 317-330.
- , 1915: The effect of some trivalent and tetravalent kations on permeability, *Bot. Gaz.*, **59**: 464-473.
- , 1915: Normal and abnormal permeability, *Amer. Jour. Bot.*, **2**: 93-94.
- , 1916: The decrease of permeability produced by anesthetics, *Bot. Gaz.*, **61**: 148-158.
- , 1917: Similarity in the effects of potassium cyanide and of ether, *Bot. Gaz.*, **63**: 77-80.
- , 1917: Does the temperature coefficient of permeability indicate that it is chemical in nature? *Bot. Gaz.*, **63**: 317-320.
- , 1918: A method of measuring the electrical conductivity of living tissues, *Jour. Biol. Chem.*, **36**: 557-568.
- , 1919: A comparative study of permeability in plants, *Jour. Gen. Physiol.*, **1**: 299-305.
- , 1919: A comparison of permeability in plant and animal cells, *Jour. Gen. Physiol.*, **1**: 409-415.

- OSTERHOUT, W. J. V., 1918: Decrease of permeability and antagonistic effect caused by bile salts, *Jour. Gen. Physiol.*, **1**: 405-409.
- , 1921: Direct and indirect determinations of permeability, *Jour. Gen. Physiol.*, **4**: 275-283.
- , 1921: Conductivity and permeability, *Jour. Gen. Physiol.*, **4**: 1-9.
- , 1922: Some aspects of selective absorption, *Jour. Gen. Physiol.*, **5**: 225-231.
- , 1922: "Injury, Recovery, and Death in Relation to Conductivity and Permeability," 259 pp., J. B. Lippincott Company, Philadelphia and London.
- , 1927: Some aspects on bioelectrical phenomena, *Jour. Gen. Physiol.*, **11**: 83-99.
- , E. B. DAMON, and A. G. JACQUES, 1927: Dissimilarity of inner and outer protoplasmic surfaces in *Valonia*, *Jour. Gen. Physiol.*, **11**: 193-205.
- and E. S. HARRIS, 1928: Protoplasmic asymmetry in *Nitella* as shown by bioelectric measurements, *Jour. Gen. Physiol.*, **11**: 391-406.
- OVERTON, E., 1895: Über die osmotischen Eigenschaften der lebenden Pflanzen- und Tierzelle, *Vierteljahrsh. d. Nat. Ges. in Zürich*, **40**: 159-201.
- , 1897: Über die osmotischen Eigenschaften der Zelle in ihrer Bedeutung für die Toxikologie und Pharmakologie, *Vierteljahrsh. d. Nat. Ges. in Zürich*, **41**: 383-406.
- , 1899: Ueber die allgemeinen osmotischen Eigenschaften der Zelle, ihre vermuthlichen Ursachen und ihre Bedeutung für die Physiologie, *Vierteljahrsh. d. Nat. Ges. in Zürich*, **44**: 83-135.
- , 1900: Studien über die Aufnahme der Anilinfarben durch die lebende Zelle, *Jahrb. f. wiss. Bot.*, **34**: 669-701.
- PFEFFER, W., 1877: "Osmotische Untersuchungen: Studien zur Zell-mechanik," Leipzig.
- , 1890: Zur Kenntnis der Plasmahaut und der Vacuolen, *Abh. Sachs. Ges. Wiss.*, **16**: 187-343.
- RABER, O. L., 1920: A quantitative study of the effect of anions on the permeability of plant cells, *Jour. Gen. Physiol.*, **2**: 535-539.
- , 1920: The antagonistic action of anions, *Jour. Gen. Physiol.*, **2**: 541-544.
- , 1921: A quantitative study of the effect of anions on the permeability of plant cells, II, *Amer. Jour. Bot.*, **8**: 366-369.
- , 1921: The effect of permeability on polyvalent cations in combination with polyvalent anions, *Amer. Jour. Bot.*, **8**: 382-386.
- , 1921: The effect upon the permeability of (I) the same substance as a cation and anion and (II) changing the valency of the same ion, *Amer. Jour. Bot.*, **8**: 464-470.
- , 1923: Permeability of the cell to electrolytes, *Bot. Gaz.*, **75**: 298-308.
- RUHLAND, W., 1911: Untersuchungen über den Kohlenhydratstoffwechsel von *Beta vulgaris*, *Jahrb. f. wiss. Bot.*, **50**: 200-257.
- , 1912: Studien über die Aufnahme von Kolloiden durch die pflanzliche Plasmahaut, *Jahrb. f. wiss. Bot.*, **51**: 376-431.
- , 1912: Die Plasmahaut als Ultrafilter bei der Kolloidaufnahme, *Ber. d. d. bot. Ges.*, **30**: 139-141.
- , 1913: Zur Kritik der Lipoid- und der Ultrafiltertheorie der Plasmahaut nebst Beobachtungen über die Bedeutung der elektrischen Ladung der Kolloide für ihre Vitalaufnahme, *Biochem. Zeits.*, **54**: 59-77.
- , 1913: Zur Kenntnis der Rolle des elektrischen Ladungssinnes bei der Kolloidaufnahme durch die Plasmahaut, *Ber. d. d. bot. Ges.*, **31**: 304-310.
- , 1913: Zur chemischen Organisation der Zelle, *Biol. Centrbl.*, **33**: 337-351.
- , 1914: Weitere Beiträge zur Kolloidchemie und physikalischen Chemie der Zelle, *Jahrb. f. wiss. Bot.*, **54**: 391-447.

- RYSELBERGHE, FR. VAN, 1901: Influence de la température sur la perméabilité du protoplasme vivant pour l'eau et des substances dissoutes, *Bull. Acad. Roy. Belg. Cl. Sci.*, 173-221; *Rec. Inst. Bot. Univ. Bruxelles*, **5**: 209-248 (1902).
- SCHRÖDER, H., 1911: Über die selektiv permeable Hülle des Weizenkornes, *Flora*, **102**: 186-208.
- SEIFRIZ, WILLIAM, 1921: Observations on some physical properties of protoplasm by aid of micro-dissection, *Ann. Bot.*, **35**: 269-296.
- SEN, B., 1928: The effect of temperature on the permeability of the protoplasmic membrane, *Proc. Roy. Soc., B*, **103**: 272-288.
- SHULL, C. A., 1913: Semipermeability of seed coats, *Bot. Gaz.*, **56**: 169-199.
- , 1920: Temperature and the rate of moisture intake in seeds, *Bot. Gaz.*, **69**: 361-390.
- SPAETH, R. A., 1916: The vital equilibrium, *Science*, n. s., **43**: 502-509.
- STARK, O. K., 1928: What is osmosis? *Science*, n. s. **67**: 556-557.
- STEWART, F. C., 1928: The maintenance of semipermeability in the plant cell during leaching experiments, *Proc. Leeds, Phil. Soc.*, **1**: 258-270.
- STEWART, G. N., 1897: Elektrische Leitfähigkeit thierischer Flüssigkeiten, *Zentrbl. Physiol.*, **11**: 332-335.
- STILES, W., and I. JORGENSEN, 1915: Studies in permeability. II, The effect of temperature on the permeability of plant cells to the hydrogen ion, *Ann. Bot.*, **29**: 611-618.
- and ———, 1917: Studies in permeability. IV, The action of various organic substances on the permeability of the plant cell and its bearing on the Czapek's theory of plasma membrane, *Ann. Bot.*, **31**: 47-76.
- and ———, 1917: Studies in permeability. V, The swelling of plant tissue in water and its relation to the temperature and various dissolved substances, *Ann. Bot.*, **31**: 415-434.
- and ———, 1918: Quantitative measurements of permeability, *Bot. Gaz.*, **65**: 526-534.
- , 1922: The suction pressure of the plant cell. A note on nomenclature, *Biochem. Jour.*, **16**: 727-729.
- , 1924: "Permeability," 292 pp., Wheldon & Wesley, London.
- TJEBBES, K., 1912: Keimproeven met suikerbietenzaad, *Inaug. Diss. Amsterdam*.
- TRÖNDLE, A., 1909: Permeabilitätsänderung und osmotischer Druck in den assimilierenden Zellen des Laubblattes, *Ber. d. d. bot. Ges.*, **27**: 71-78.
- , 1910: Der Einfluss des Lichtes auf die Permeabilität der Plasmahaut, *Jahrb. f. wiss. Bot.*, **48**: 171-282.
- , 1918: Der Einfluss des Lichtes auf die Permeabilität der Plasmahaut und die Methode der Permeabilitäts-Koeffizienten, *Vierteljahrshchr. d. Nat. Ges. in Zürich*, **63**: 187-213.
- URSPRUNG, A., and G. BLUM, 1916: Über die Verteilung des osmotischen Wertes in der Pflanze, *Ber. d. d. bot. Ges.*, **34**: 88-104.
- and ———, 1916: Über die periodischen Schwankungen des osmotischen Wertes, *Ber. d. d. bot. Ges.*, **34**: 105-123.
- and ———, 1916: Über den Einfluss der Aussenbedingungen auf den osmotischen Wert, *Ber. d. d. bot. Ges.*, **34**: 123-142.
- and ———, 1916: Zur Methode der Saugkraftmessung, *Ber. d. d. bot. Ges.*, **34**: 525-539.
- and ———, 1916, 1918: Zur Kenntnis der Saugkraft, I, II, *Ber. d. d. bot. Ges.*, **34**: 539-554; **36**: 577-599.
- and ———, 1919: Zur Kenntnis der Saugkraft, III, *Ber. d. d. bot. Ges.*, **37**: 453-462.

- URSPRUNG, A., and G. BLUM, 1920: Dürfen wir die Ausdrücke osmotischer Wert, osmotischer Druck, Turgordruck, Saugkraft synonym gebrauchen? *Biol. Zentrbl.*, **40**: 193-216.
- and ———, 1921: Zur Kenntnis der Saugkraft. IV, Die Absorptionszone der Wurzel. Der Endodermisprung, *Ber. d. d. bot. Ges.*, **39**: 70-79.
- and ———, 1921: Zur Kenntnis der Saugkraft. V, Eine Methode zur Bestimmung des Widerstandes, den der Boden der Wasserabsorption durch die Wurzel entgegensetzt, *Ber. d. d. bot. Ges.*, **39**: 139-148.
- , 1923: Zur Kenntnis der Saugkraft. VII, Eine neue vereinfachte Methode zur Messung der Saugkraft, *Ber. d. d. bot. Ges.*, **41**: 338-343.
- and G. BLUM, 1924: Eine Methode zur Messung des Wand- und Turgordruckes der Zelle, nebst Anwendungen, *Jahrb. f. wiss. Bot.*, **63**: 1-110.
- , 1925: Einige Resultate der neuesten Saugkraftstudien, *Flora*, **118-119**: 566-599.
- WHITTEN, J. H., 1914: The effect of kerosene and other petroleum oils on the viability of growth of *Zea mais*, *Bull. Ill. State Lab. Nat. Hist.*, **10**: 245-273.
- WODEHOUSE, R. P., 1917: Direct determinations of permeability, *Jour. Biol. Chem.*, **29**: 453-458.

CHAPTER III

THE ROOTS OF PLANTS

The root system of a plant includes all of its roots considered collectively. The root systems are specific, that is, the root system of a given species, in its general appearance, can be distinguished from that of another type of plant. Weaver (1920) states that the general characters of the root systems of species are often as marked and distinctive as are those of the aerial vegetative parts and although these may be greatly modified when subjected to different environmental conditions, they still retains the characteristic impress of the species in its usual habitat. The root system of a given plant, therefore, may vary in its structure, extent, weight, number, and direction of its roots according to the conditions under which it is grown. The general behavior of roots in the soil is thus the resultant of the influence of many factors, the most important of which are moisture, nutrients, oxygen supply, temperature, physical texture of the soil, light, and gravity.

I. INFLUENCE OF ENVIRONMENT ON ROOTS

A. INFLUENCE OF SOIL MOISTURE ON ROOT DEVELOPMENT

The influence of varying amounts of moisture in the soil upon the roots has been studied along three general lines: (1) direction of root growth, (2) relative weight of roots and tops, and (3) lateral extent and depth of penetration into the soil. It is the purpose here to consider only the first two topics and to reserve the third for a later discussion under a separate heading.

1. Direction of Root Growth.—It is common knowledge that roots respond to the changes of moisture in the soil and that they are positive in their reaction as they turn from a lower to a higher water content. Some of the factors entering into this reaction were investigated by Hooker (1915) in working with the roots of *Lupinus albus*. He found that roots are positively hydrotropic in moist air and that they react only when the moisture of the air is between 80 and 100 per cent of saturation. He observed that the minimum, optimum, and maximum differences in moisture to which these roots reacted at 20°C. was a fall of 0.2, 0.4, and 0.5 per cent, respectively, per centimeter along a line at right angles to them. The best response of root reaction toward changes in moisture was thus obtained under conditions which would make a

difference of only 0.04 per cent moisture between the opposite sides of a root 1 mm. thick. Hooker also found that under optimum conditions 6 hr. elapsed before the hydrotropic reaction was visible in the roots and that the sensitiveness of roots to moisture is exhibited chiefly at the root tip and to a less extent by the cells behind the root tip. From these facts it is evident that roots will turn toward or follow moisture in the soil only when they are in direct contact with it or in very close proximity to it. In this connection it should be mentioned that roots cannot penetrate a layer of dry soil in order to reach a supply of moisture that might be beneath, since in a dry soil water would be extracted from the roots and they would perish as a result.

2. Relative Weight of Roots and Tops.—Tucker and Von Seelhorst (1898) grew oats in soil containing 42, 45, and 49 per cent of its moisture-holding capacity and found that the ratio of the dry weight of the tops to the dry weight of the roots was 6.6, 11.5, and 13.2, respectively, for each of these soils. They found (*a*) that the weight of the aerial parts increased in both grain and straw with the rising water content of the soil and (*b*) that with but one exception the greatest weight of roots was produced in the soil with the smallest amount of water.

Kiesselbach (1910) at the Nebraska Experiment Station grew corn plants in soil with a moisture content of 98, 80, 60, 40, and 20 per cent of saturation. The dry weight of the tops of these plants was, respectively, 8.6, 6.7, 7.2, and 5.2 times the weight of the roots. He concluded that root development varies inversely as the soil water content and that plants which have their early growth in a relatively dry soil may be able to withstand drought better on account of having a greater surface exposed to the soil particles. The observations of the above investigators have further been confirmed by Polle (1910) working with wheat and barley, by Harris (1914) and Miller and Duley (1925) working with corn, and by Conrad and Veihmeyer (1929) working with sorghum.

Weaver (1925) grew Nebraska White Prize corn for 5 weeks in fertile loess soil at water contents of 9 and 19 per cent, respectively, above the hygroscopic coefficient. In the wet soil the area of the tops (including the stem and counting both surfaces of the leaves) was 82 per cent of that of the roots, but in the drier soil the tops had only 46 per cent as great an area as the roots. The absorbing area of the roots (exclusive of root hairs) was 1.2 times as great as the area of tops in the wet soil and 2.2 times as great as the area of the tops of plants grown in the drier soil.

B. SOIL NUTRIENTS AND ROOT DEVELOPMENT

The effect of the kind and amount of nutrients in the soil, or other medium in which the plant is grown, upon root development has been studied along the three following lines: the influence (1) on the direction

taken by the roots, (2) on the number of roots, and (3) on the relative weight of roots and tops.

1. Direction of Root Growth.—The experimental evidence in regard to the response in direction of roots to nutrients is very limited. It is also difficult to interpret the data that have been obtained in this regard, since there is no way of knowing whether the observed curvatures of the roots are due to the direct physiological action of the nutrients in question or to the injury of portions of the root by them. The main work in this regard has been done by Newcombe and Rhodes (1904), Lilienfeldt (1905), and Porodko (1911 to 1914). Newcombe and Rhodes (1904) worked especially with the primary root of the seedlings of *Lupinus albus* and *Cucurbita pepo*. Blocks of gelatin in which were dissolved the nutrients or chemicals to be investigated were pressed gently, but closely, against the root on two sides and after a given period observations were made to determine whether the reaction of the root to the dissolved substances had been positive, negative, or neutral. In one experiment with a block on one side containing only distilled water, and the block on the other containing a 1.5 per cent solution of Na_2HPO_4 , all of the 10 roots of *Lupinus albus* under observation after 24 hr. had grown into the block containing the solution of phosphate where they quickly perished. In another case with distilled water on one side and a 0.01 per cent solution of copper acetate on the other, 13 of the 16 roots of *Lupinus albus* of the experiment had grown into the distilled water after a period of 24 hr. In the same manner the behavior of the roots was tested out when two unlike salts of equal osmotic pressure were brought at the same time against the opposite sides of the root. The chemicals used were $\text{Ca}(\text{NO}_3)_2$, KNO_3 , and MgSO_4 , and the following table shows the observed direction of growth for the roots of *Lupinus albus*:

	Neutral		
$\text{KNO}_3 \leftarrow$ 9	2	0	$\rightarrow \text{Ca}(\text{NO}_3)_2$
$\text{KNO}_3 \leftarrow$ 10	0	1	$\rightarrow \text{MgSO}_4$
$\text{Ca}(\text{NO}_3)_2 \leftarrow$ 0	4	10	$\rightarrow \text{MgSO}_4$

The roots of *Cucurbita pepo* under the same conditions as those of *Lupinus albus* did not behave in the same manner, which indicates that the response of roots to a given chemical will depend to some extent upon the nature of the plant. Lilienfeldt (1905) repeated the work of Newcombe and Rhodes, using their method and one of his own after the following manner: Small containers 12 cm. high were filled with 3 per cent of gelatin in distilled water. As soon as it was sufficiently hardened a hole of about 20 cc. capacity was dug out of the center and filled with a solution of the chemical to be tested. The seedlings of *Lupinus albus* were carefully planted without injury by pushing the roots into the soft gelatin and so placing them that they were at distances varying from 5 to

50 mm. from the cavity. These were left in the dark for varying periods of time and the effect of the chemical diffusing through the gelatin on their direction of growth was observed. He obtained identical results to those of Newcombe and Rhodes when he used their method and with his own method the results are the same, with the exception of the salts of Cu, Zn, Hg, and Pb. By the method of Newcombe and Rhodes the roots reacted in a positive manner to these chemicals, but by the method of Lilienfeldt they responded negatively to them. The difference in results is evidently due to the amount of the salt which reached the root. In the case of the method of Lilienfeldt, the amount of the poisonous salts that reach the roots by diffusing through the gelatin is much smaller than that which comes in contact with them when the salts are directly dissolved in the gelatin. A small amount of the poisonous salts stimulates growth on the contact side of the root and thus brings about a negative reaction in its behavior. A larger amount of the chemical would injure the cells of the root on the contact side and thus bring about a positive reaction in growth. Porodko (1911, 1914) worked with *Lupinus albus* and *Helianthus annuus* grown in the presence of various salts in agar as a diffusion medium and with solutions varying from one thousandth normal to tenth normal. He found in the reaction to chemicals that the upper and lower portions of the root remained straight and that the intermediate portion was concerned in the curvature. He considered that the region in which chemotropic sensitivity of the root may be exhibited is limited to about 1 to 2 mm. of the root tip. He found that the intensity of the curvature depended upon the intensity of the diffusing forces or stimuli and that this, in turn, varies with the nature of the salt or diffusion substance used, with the concentration, with the thickness of the agar, and with the length of time the diffusion current acts. In general, the reaction as to the direction of the curvature manifested itself by a check in the growth and a positive curvature of the roots. This effect was observed in all the substances tested, whether they were electrolytes or non-electrolytes.

In the case of electrolytic substances, there was observed a dominant direction curve which was positive in the case of acids, alkalies, sodium, and potassium carbonates and negative in the case of neutral salts. A strong positive curvature was generally observed in alkaline solutions, while acids produced slight positive curvatures. Although the experimental evidence is rather contradictory in regard to the response in direction of growth to chemicals in the soil, two facts seem to be definitely established. In the first place, positive and negative reactions occur only within limited concentrations of the substances that have been used. In the second place, the roots must come in contact with the chemicals before they can in any way react to them. Roots cannot detect a substance needed for their growth and development and grow toward it,

so that any nutrients that are applied to a soil must be so placed that they will come in contact with the roots in a solution of water if they are to be effective for the needs of the plant.

2. Number of Roots.—One of the classic experiments used to demonstrate the effects of fertilizers upon the development of roots was that performed by Nobbe (1862) with corn plants growing in an infertile clay soil contained in glass cylinders. The experiment was so arranged that the nutrient salts $(\text{NH}_4)_2\text{SO}_4$, $\text{Ca}(\text{NO}_3)_2$, and K_2HPO_4 were added only to definite regions of the soil contained in each of six cylinders. After a growing period of 4 months the plants were harvested and the root systems carefully isolated by a system of washing. The general form of the root systems remained normal and practically the same in all the experiments. The only difference that appeared was the local variation in the number of root branches. In the unfertilized portion of the soil the number of branches per unit of length of both primary and secondary roots remained small, while in the fertilized portions of the soil the number of branches of both primary and secondary roots was strikingly large. In the cylinder where the fertilizer was equally mixed throughout the soil mass the number of branches per unit length of both primary and secondary roots was the same in all parts of the vessel. Häveler (1892) grew corn and bean plants in vessels that contained alternate layers of sand and fertile soil rich in humus. He found that whenever the roots passed through the fertile soil a profuse branching of the several root orders occurred, but where the roots passed through the sand very little or no branching took place.

Frank (1893) grew corn and peas in such a manner that half of the roots of each plant grew in separate vessels. Each vessel contained the same amount of sand and was watered with the same nutrient solution, with the exception that to one vessel a portion of $\text{Ca}(\text{NO}_3)_2$ was added while the other received no nitrogen compounds. In the vessel containing the nitrogen-free medium, only a few small branch roots were formed, while the vessel containing the nitrogen compound was filled with a thrifty root growth. This same effect of nitrogen compounds on the secondary root formation of vetch, clover, corn, beans, and alfalfa was observed by Müller-Thurgau (1894).

Von Seelhorst (1902) carried on experiments to determine whether or not the use of fertilizers affected the number of roots of spring wheat, rye, peas, flax, beans, potatoes, beets, and barley. These plants were grown separately on two series of plots. One of these series had been fertilized annually for 25 years with fertilizers containing nitrogen, phosphorus, and potassium, although the amounts stated are not given, while the other series received no fertilizers during that period. The following table is a summary of the average number of roots found in an area of 314 cm.² at the various depths stated:

Soil	Number of roots at a depth in centimeters of				
	25	50	75	100	125
Fertilized.....	500	307	197	109	52
Unfertilized.....	459	206	158	92	43

Weaver, Jean, and Crist (1922) investigating the absorption of nitrates by roots found that where roots came in contact with a fertilized layer of soil they not only developed much more abundantly and branched more profusely but such a fertilized layer apparently retarded normal penetration into the soil below.

3. Relative Weight of Roots and Tops.—In general, it may be stated that the application of fertilizers increases the weight of the roots but that the weight of the tops generally increases more in proportion under such conditions than the roots so that the ratio of the dry weight of tops to the dry weight of the roots is generally higher in a fertile than in an infertile soil. Nitrogenous fertilizers especially increase the growth of tops as compared to the roots, while phosphorus as a rule increases the weight of the roots in a greater proportion than the tops. Harris (1914) found that the ratio of the weight of tops to the weight of roots of wheat seedlings was always greater with plants grown in concentrated than in dilute soil solutions. The concentrated soil solutions always produced more tops than the dilute, but the root growth was always greater in the dilute solution. The following table from the work of Harris (1914) shows that the proportion of roots and tops is affected more by a change in water content than by a change in the amount of nutrients:

DRY MATTER OF WHEAT TOPS AND ROOTS AT VARIOUS STAGES WHEN GROWN IN SOIL WITH DIFFERENT AMOUNTS OF FERTILIZER AND MOISTURE

Fertilizer	Per cent soil moisture	Boot stage, grams			Bloom stage, grams			Maturity, grams		
		Tops	Roots	T/R	Tops	Roots	T/R	Tops	Roots	T/R
None.....	30	35.3	15.8	2.2	50.5	10.7	4.7	74.9	9.3	8.1
None.....	15	15.2	10.0	1.5	19.3	8.8	2.2	29.2	9.5	3.1
Complete.....	30	45.4	22.8	2.0	76.2	14.3	5.3	102.0	11.7	8.7
Complete.....	15	27.8	20.7	1.3	39.9	12.4	3.2	52.3	13.2	4.0

Turner (1922) found that barley and corn showed significant increases in the ratio of tops to roots as the nitrate concentration of the solution was increased. The effect of the nitrates was shown to be independent of the concentration of the solution and the hydrogen-ion concentration. Flax

plants did not show this increased ratio even after a period of 40 days or more. He concludes that the increased ratio of tops to roots which results from increasing the amount of nitrate in the solution may be explained on the basis of the increased use of carbohydrates in the tops due to their combination with the nitrogen. This results in a decrease in the supply of the carbohydrates for the roots, which may bring about an absolute or relative reduction of root growth. It has been found that barley grown in the shade has a greater ratio of top weight to root weight than that grown in the unobstructed sunlight. Turner grew roots in pure cultures with a supply of sugar and found that nitrates do not check root growth directly but that they increased the growth of roots in all cases.

C. OXYGEN SUPPLY AND ROOT DEVELOPMENT

Numerous benefits are generally derived by crop plants through the cultivation of the soil previous to their planting and at intervals during their growing season. The main benefits thus derived are (1) the conservation of moisture by increasing its reception and retention, (2) the eradication of weeds, (3) the correction of the physical texture of the soil, and (4) the adequate aeration of the soil. The aeration of the soil is beneficial to the plants in an indirect way, since an adequate supply of oxygen is necessary for the proper functioning of the bacteria which elaborate the various materials of the soil into a form in which they can be absorbed and utilized by the plants. In a direct way the aeration of the soil benefits the plant by furnishing a supply of oxygen which is essential for the proper functioning of the protoplasm of the cells of the root. The general texture of the soil will determine to a great extent the benefits to be derived by increasing the oxygen supply by cultivation. Many soils are so light and porous that a deficiency of oxygen in them is not a limiting factor for growth, and it is a well-known fact that in many regions cultivation during the growing season is unnecessary for crop production provided the surface of the soil is kept free of weeds and is not too compact to absorb the rainfall. In very compact and in water-logged soils, special methods in addition to cultivation must be applied in order to insure the proper aeration for normal plant development.

Howard (1915, 1916, 1917, 1918) has reported that special methods are necessary to bring about the proper aeration of the soil in the Bihar region of India. The soils in this region are composed of fine particles, become very compact upon wetting, and do not crack when the surface dries, thus preventing natural aeration. This condition is corrected by manuring with straw, by subsoiling, by the application of fragments of tile and brick, and by the proper sequence of crops. *Cajanus indicus*, the pigeon pea, confers a great benefit on a crop following it, especially tobacco. The root system of the pigeon pea grows to a great depth and is extensive laterally. White ants eat out the roots and leave air

passages throughout the soil. In converting rough grassland into cultivated fields, sweet potatoes are planted as the first crop. They seem to thrive even if aeration is poor, while the swelling of the roots bursts open the soil and admits air, so that when the roots are removed, the numerous cavities furnish aeration for other crops which would not otherwise grow.

Two important observations have been made on the effect of soil aeration in the production of rice. As high as 20 per cent loss of the expected crop of rice has occurred due to a disease known as "straight head." In this trouble the flowers remain sterile and the panicles do not droop. Tisdale and Jenkins (1921) found that this condition of the plants was brought about mainly by the lack of proper soil aeration. Normal plants have few large roots and many branches and root hairs, while the plants affected with the disease show numerous large roots and very few branches and root hairs. For the control of this disease they recommended the irrigation of the plants ten days after they emerge or when they are 6 to 8 in. tall. The water should be allowed to drain off gradually, and if the soil is not free from water in 5 to 6 weeks after irrigation, it should be drained off and the land allowed to remain dry for 2 to 3 weeks. If the soil becomes dry enough to crack and the plants turn yellow, the results will be better. Water should then be turned on and allowed to remain until the end of the season. In the growing of swamp rice at Coimbatore, India, Harrison (1913) presents evidence to show that the surface film of algae and other organisms on these soils plays the leading part in the formation of the oxygen required by the roots of the rice. He believes that the aeration of these soils by the atmospheric oxygen is not so effective in promoting root aeration as is the aeration secured by the water which percolates through this surface film of algae. When certain rains fail to fall in the Bihar region, even if the soil is moist the rice crop is poor. This result is considered to be due to the failure of water to filter through the film algae and aerate the roots.

Arker (1901) and Hall, Brenchley, and Underwood (1914) have found that the rate of root growth and top growth in both soil and water cultures may be increased by pulling a stream of air through the medium. The following table is a brief summary of the results obtained by Hall, Brenchley, and Underwood with barley and lupine plants grown in water cultures:

Plant	Treatment	Average dry weight, grams
Barley	{ Not aerated	1.31
	{ Aerated continually	2.12
Lupine	{ Not aerated	0.83
	{ Aerated continually	1.53

It has been shown by Cannon (1915 to 1925), Livingston and Free (1917), and Bergman (1920) that different species of plants vary widely in their response to the variations in the amount of oxygen in the soil and that these differences in responses are quite as significant as the responses to temperature and to available water. Cannon found that *Prosopis*—the mesquite—and *Opuntia*—a cactus—have roots that are unlike in their response to the oxygen supply in the soil. His experiments showed that if pure CO₂ filled the air space of the soil, growth ceased in the roots of both plants. The reduction of the oxygen to 12 to 15 per cent did not stop growth in the roots of *Prosopis* but did so in the roots of *Opuntia*. The roots of *Prosopis* continued to grow when only 2 per cent of oxygen was contained in the soil air. Livingston and Free (1917) found that the roots of the willow (*Salix nigra*) could endure successfully the almost complete exclusion of oxygen from the soil. Coleus and heliotrope were injured in a short time, so that within 12 to 24 hr. the absorption of water by the roots ceased. Bergman found by growing plants in soil in pots which were submerged in water that *Impatiens*, *Pelargonium*, and *Coleus* were sensitive to a scarcity of oxygen. If, however, the water surrounding these pots was aerated the plants would grow normally. The following experiment is worthy of note: Two plants of *Impatiens* were potted in soil and the pots submerged in water. Several plants of *Philotria*, an aquatic plant, were placed in the water surrounding one of the pots but not in that surrounding the other. The evolution of oxygen from the photosynthetic activity of these aquatic plants aerated the surrounding water, and thus the water of the soil in the submerged pots, sufficiently to provide for the oxygen needs of the roots of the plants growing therein. As a result this plant was in good vegetative condition after two months, while the other plant whose roots were not thus aerated wilted after three days and shortly thereafter perished.

Interference with the process of respiration is apparently the cause of the injury and eventual death of the roots due to the exclusion or depletion of the oxygen supply of the soil. The first visible effects of the lack of oxygen to the roots are the wilting of the plant and a lowering of the rate of transpiration. These effects are apparently due to the fact that the protoplasm does not function properly as an absorbing membrane. Hunter and Rich (1925) found that the rate of transpiration and the intensity of respiratory activity of the shoot of *Impatiens balsamina* are increased by the aeration of the soil about the root system. They considered that the increased activity of these processes is due to the removal of carbon dioxide from the region of the root. The local concentration of carbon dioxide around an actively growing root is probably very high. The inner cells of the roots and those of the stem and leaves would be affected by the fluctuations of the activities of the epidermal

cells of the root. Cannon (1923 to 1925) has observed that the minimum oxygen supply is not a fixed amount but that it varies directly with temperature change. If the roots of *Potentilla anserina*, which inhabits swampy ground, are placed in a soil whose atmosphere consists of 1.2 per cent oxygen and the balance nitrogen gas, growth of the roots does not take place at 27 and 30°C., but at 18°C. it is about one-fourth normal for that temperature. In soils whose atmosphere contains 2 per cent oxygen, the growth rate is about one-fourth normal at 30°C., one-third normal at 27°C., and normal at 18°C. In the case of corn with the roots in soils containing 3 per cent oxygen, the rate of growth at 30°C. is about one-sixteenth normal, at 20°C. about one-fifth normal, and at 18°C. about one-third normal. When the percentage of oxygen is increased to 3.6, the rate of growth at 30°C. is about one-third the expected rate under normal conditions of aeration, while at 18°C., it is about two-thirds normal. These examples show that

. . . there comes a point in the diminution of the oxygen content of the soil atmosphere when the growth of the root ceases because there is no longer a sufficient amount of this gas to supply the demands for energy correlated with physiological activities of higher temperatures.

On this account it can be inferred, for instance in the case of corn, that to attain a fair rate of growth at a time of high soil temperatures the aeration of the soil must be good, otherwise the rate of growth would be considerably cut down. A sensitive and practicable method for comparing the oxygen-supplying powers of the soil atmosphere under different environmental conditions has been devised by Hutchins (1926). This method is based essentially on a colorimetric determination of the time required to produce a standard color change in an alkaline aqueous solution of pyrogallol by the absorption of oxygen. This oxygen is brought to the indicator in a continuous stream, having been absorbed from the environment in question by a very thin-walled, water-impregnated, porous porcelain conical-shaped absorber. The absorber has the capacity for absorbing oxygen and delivering it at least as rapidly as that element is supplied to the absorbing surface of the medium in which it is placed. The numerical results are termed "indices" of the environmental oxygen-supplying power and are expressed as milligrams of oxygen supplied per hour through a square meter of absorbing area exposed to the environment under consideration.

By this method it was found that the oxygen-supplying power of the soil is higher the less its depth, the dryer, and the more loosely it is packed. With a very wet loamy garden soil the index value for a depth of 40 cm. is only about 0.7 per cent as great as that for a depth of 15 cm. The oxygen-supplying power varies also with the kind of soil and with the prevalence of aerobic organisms and readily oxidizable materials

in the soil surrounding the absorber. Soil temperature and barometric pressure may also have an influence.

Cannon (1917) has observed that an increased air supply to the roots of certain desert plants favored root branching. Miller (1916) and Weaver (1919) have noticed in isolating root systems in the field that a root upon passing through a cavity in the soil branches profusely so that in many cases it fills the entire cavity. This behavior of the roots is apparently due to the combined effects of moisture and the oxygen supply. The clogging of tile drains by roots is probably due to the same causes. The superiority of the roots of soybeans grown in aerated nutrient solutions over those in unaerated solutions was found by Allison and Shive (1923) to be due not to the higher dry weight of the substance produced but to the development of a more efficient absorbing system. The main roots in the aerated cultures were long and slender and thickly beset with well-developed laterals almost to the very tips.

The evidence in regard to the growth of roots toward an oxygen supply is mostly indirect. Many of the main roots of corn and sorghum plants growing in the field under ordinary agricultural conditions extend horizontally if there is sufficient moisture in the uppermost portion of the soil. The laterals arising from these horizontal roots have been observed by Miller (1916) to extend vertically upward to within one-half inch of the soil surface. This behavior is considered to be due to the influence of the supply of oxygen in the upper part of the soil. The same explanation is given to the behavior of roots which after being forced to grow downward to a considerable depth through a vertical tile have turned directly upward upon emerging from it. Ewart (1894) found that the roots of peas, hemp, and wheat grown over water deprived of oxygen either turned slightly upward or grew along the water surface, while if the water were aerated they grew directly downward into it.

Clements (1921) found in experiments with sunflowers growing in sealed pots which were glazed, with the exception of certain small, square surfaces, that in all cases the roots showed right-angled curvatures toward the unglazed squares.

Bennett (1904) worked with corn, squash, radish, peas, and lupine to determine whether any response could be obtained to oxygen and carbon dioxide from the roots of these plants. In general, the experiment consisted in allowing the gases to diffuse directly upon the roots growing in soil or water as a medium. Three hundred and sixty-two reactions were observed upon the roots of corn, radish, and squash growing in water upon which either carbon dioxide or oxygen was allowed to diffuse from one side only. Of this number 84 were positive, 72 were negative, and 206 were neutral. In an experiment in which carbon dioxide diffused

against one side of the root and oxygen against the other, 166 observations were made of which 37 were positive in their reaction to oxygen, 22 were positive to carbon dioxide, and 107 were neutral to both gases. In the experiment in which plants growing in the soil were so arranged that oxygen could diffuse on one side of the primary root and carbon dioxide upon the other, the results showed no more than those mentioned above, since of the 221 observations made, 45 reacted in a positive manner toward the oxygen, 48 in a negative way, and 128 in a neutral manner. The evidence in these three experiments refutes the idea that roots exhibit aerotropism.

D. SOIL TEMPERATURES AND THE RESPONSE OF ROOTS

It is the intention here to discuss more particularly the response of roots as shown by curvatures induced by the changes in the temperature of the medium in which they are growing and to reserve for a subsequent chapter the effect of temperature changes upon the rate of root growth. Until 1914 our knowledge of the thermotropic curvature of roots was very confusing. The experimental results demonstrated that different plants exhibit little uniformity in behavior, since some roots were positive in their reaction at a given temperature, while others at the same temperature gave a negative or neutral reaction.

Eckerson (1914) investigated the response of roots when exposed to unequal temperatures on their two sides and arrived at results which cleared up the apparent discrepancies and contradictions in the results obtained by earlier investigators. In these experiments, Eckerson grew or placed the seedlings in sphagnum moss in a Ganong differential thermostat which furnished a gradation in temperatures from 5 to 58°C. If the roots curved toward a region of higher temperature, they were considered to have responded positively, while a curvature away from higher-temperature areas was listed as a negative response. After the roots of the radish had been in the thermostat two hours, they showed the following reactions in curvatures: 7 to 15° positive, 16 to 23° no curvatures, 24 to 36° positive, and 38 to 51° negative (see also Treitel, 1924). A study of the permeability of the cells of the roots of these plants at different temperatures by means of the plasmolytic method with KNO_3 solutions showed that it increased from 10 to 18°, did not change from 18 to 24°, increased from 24 to 40°, and then decreased. A comparison of the changes in permeability and the response in curvatures at the different temperatures show that in every case where the temperature induced an increased permeability there was a positive curvature, where no change in permeability occurred no curvatures resulted, while at temperatures causing a decrease in permeability, negative curvatures resulted. These observations show that with unequal temperatures on opposite sides of a root a curvature is produced only when the cells of the root are more

permeable at one of the temperatures than the other. Those cells subjected to a temperature at which they are more permeable to dissolved substances are consequently less turgid, and this results in a shrinking of the tissue on that side of the root and a consequent mechanical curvature, and in all cases the more permeable side of the root becomes concave. Eckerson also studied the changes in the permeability of the cells of the roots of the various species of plants that had been investigated by Wortmann (1885) and by Klercker (1891) and found that the increase or decrease in the permeability at the various temperatures paralleled the positive or negative curvatures that had been observed by these investigators. She summed up her observations in the following statement: (1) Thermotropic curvatures of roots vary with the temperature and with the species. (2) The permeability of the cells of the roots to dissolved substances varies with the same factors, and wherever the thermotropic reaction of the root changes the permeability also changes. (3) Heat does not act as a stimulus but by affecting permeability is a direct factor in producing curvature, so that thermotropism is not to be considered a tropism but a turgor movement.

E. SOIL TEXTURE AND ROOT DEVELOPMENT

A hard, compact soil limits the extent of root systems to a marked degree, and Weaver (1919, 1920) observed that in a compact soil the roots are more or less contorted or kinked, while the branching is decidedly less than in a soil of loose texture.

Carlson (1925) in studying the effect of soil structure on the character of alfalfa root systems found that in compact soils all varieties and strains develop branch roots, while in open soil the taproots predominate. He also found that the different strains of alfalfa have inherent root characteristics which as a rule do not develop until after 3 or 4 months of normal growth. McCool (1928) observed the development of the roots of alfalfa, sweet clover, and red clover in three different types of soil. The results obtained showed that there were marked differences in the nature and extent of the roots of these plants. Thus the average length of alfalfa roots in one soil was 40 in. and in another soil only 8 in. Sweet-clover roots attained a length of 43 in. in one soil, 13 in. in another, and but 10 in. in a third soil.

Weaver and Crist (1922) made some observations on the relation of hardpan to root penetration. This soil layer, in general, delimits the depth of penetration of the roots of crop plants, but under exceptional moisture conditions they may penetrate the hardpan and extend 2 to 3 ft. beneath it. No modifications in root habits were apparent in the hardpan layer. Since roots will not grow into dry soil, the conclusion is that water penetrated the hardpan and the soil beneath.

F. THE RESPONSE OF ROOTS TO LIGHT

Some roots show a marked reaction in response to light. This is especially true of some members of the mustard family. The roots of these plants are those that are so frequently pictured in textbooks as examples of the negative action of roots to the stimulus of light. Many roots, however, show little or no response to light.

II. THE EXTENT OF ROOT SYSTEMS

This general subject can be conveniently discussed under two general headings: (a) the total number and combined length of the roots of a given plant, and (b) the extent of roots in the soil.

A. TOTAL NUMBER AND COMBINED LENGTH OF ROOTS

Nobbe (1869) measured and counted the roots of winter wheat and rye and found that the roots of the first, second, third, and fourth order of 55-day-old plants growing in the soil numbered 16,000 for rye and 10,700 for wheat. The combined length of the roots of the rye plant measured 492 ft.; and that of the wheat plant, 283 ft. A mature wheat plant grown in the soil was found to possess 67,200 roots of the first four orders and to have a combined length of 1,730 ft.

Clark (1874) examined the roots of a squash plant growing in the greenhouse at the Massachusetts Agricultural College and estimated the total length of these roots at 15 miles. This estimate included not only the root system proper but also the roots with all their branches originating from the 70 nodes of the plant. In 1912 Gibson repeated this work with a closely related variety and found the combined length of both the main and nodal root systems to measure only 281 ft. at the time of full vegetative development. Hellriegel (1883) estimated the total length of the root systems of mature barley and oat plants grown in a fertile soil to be 134 and 168 ft., respectively. Weaver (1925) found that the root system of a single corn plant in the eighth leaf stage has from 8,000 to 10,000 laterals arising from 15 to 23 main roots. The area of the root system of winter wheat measured at various intervals from Sept. 30 to Nov. 29 exceeded the area of the aerial parts by 10 to 35 per cent, as shown by the following table:

Date	Total area of roots exclusive of root hairs, centimeters ²	Total area of tops, centimeters ²
Sept. 30.....	9.6	7.6
Oct. 10.....	31.4	22.5
Oct. 20.....	61.5	50.5
Oct. 30.....	105.1	89.0
Nov. 14.....	237.5	215.3
Nov. 29.....	309.7	280.0

B. EXTENT OF ROOTS IN THE SOIL

From 1880 to the present time, work has been done by Goff and Beckwith (1883 to 1888), Hays (1888 to 1892), King (1892 to 1893),

Headden (1896), Georgeson and Payne (1897), Ten Eyck (1899, 1900, 1904), Cottrell (1902), Shepperd (1905), Schulze (1906), Rotmistrov (1907 to 1909), Miller (1916), Weaver (1915 to 1924), Collings and Warner (1927), Lee (1926), Arny and Johnson (1928), Gursky (1929), and Krassovsky (1929) in studying the general distribution of the roots of cultivated plants in the soil and in perfecting methods for their isolation under field conditions. The general observations of these investigators

EXTENT OF ROOT SYSTEMS OF CULTIVATED PLANTS

Investigator, location, and date	Plants	Extent, inches		Remarks
		Vertical	Lateral	
Goff and Beckwith, New York (1883-1888)	18 garden plants	10 to 34	10 to 120	Clay loam 6 to 10 in. deep. Tenacious subsoil
Hays, Minnesota (1888)	Red clover	68	20	5-month-old plants. Soil fertile, 6 ft. deep
	Alfalfa	80	12	
	Mammoth clover	57	12	
King, Wisconsin (1892-1893)	Clover, oats, barley	48	Plants all mature. Clay-loam soil. Stiff subsoil
	Winter wheat, corn	48	24	
Headden, Colorado (1896)	Alfalfa	150	6	Plants 6 years old. Stiff clay soil
Georgeson and Payne, Kansas (1897)	White milo	72	In hills 8 ft. apart. Black loam soil 8 in. deep. Stiff clay subsoil
	White kafir	48	48 to 70	
	Corn	48	
Ten Eyck, North Dakota (1899-1900)	Spring wheat, oats	48	9	Soil a fertile loam 4 ft. deep. Oats and wheat in rows 18 in. apart
	Corn	42	42	
	Potatoes	18	24	
	Sugar beets	40	24	
Cottrell, Kansas (1902)	Alfalfa	120	Stiff subsoil. Did not find end of root
				Red clover 2 years old. Alfalfa 3 years old
Shepperd, North Dakota (1905)	Rye	36	
	Spring wheat	48		
	Barley and oats	38		
	Red clover	48		
	Alfalfa	60		
	Rye	70		
Schulze, Germany (1906)	Wheat	74		
	Barley	70		
	Oats	90		
	Vetch	86		
	Potato	97		
	Corn	45	53	
	Potato	24	40	
	Yellow sorghum	42	44	
Rotmistrov, Russia (1907-1909)	Cucumber	42	33	
	Cotton	38	41	
	Rye	47	24	
	Wheat	41	37	
	Beet	58	44	
	Corn, kafir, milo	72	36 to 48	
	Miller, Kansas (1916)			
Weaver, Kansas, Colorado, South Dakota, Nebraska (1920-1921)	Rye	41	12	Mixed prairie
	Oats	41	9	
	Wheat	32	4 to 8	
	Rye	58	12	
	Oats	50	9	
	Wheat	53	4 to 8	
	Rye	64	12	
	Oats	53	9	
	Wheat	65	4 to 8	
	Alfalfa	60	12 to 18	
Ten Eyck, Kansas (1904)	Red clover	52	12	Grown on flood plain. Plants 116 days old. Eastern Nebraska. Upland silt-loam subsoil loose loess. Eastern Nebraska
	Sweet clover	64	12	
	Wheat, Durum	88	14	
	Wheat, Marquis	76	15	
	Barley	75	15	
	Corn	98	48	
	Potato	46	26	
	Corn	48 to 60	
	Kafir	42	36 to 42	
	Winter wheat	48		
	Oats and barley	52		

and a brief summary of the conditions under which they worked are recorded in the following table. The investigations of the distribution of the roots in the soil have been undertaken for two main purposes: (1) to determine the effects of cultivation upon roots and (2) to obtain information concerning the relations of the roots to the water supply of the soil. Most of the investigations have been made with the latter point in view, and a study of the table below shows that most of the work has been conducted in more or less semiarid regions where rainfall is the limiting factor in crop production.

1. Vertical Penetration.—Cannon (1911) made a study of the root systems of over 50 annual and perennial plants growing in the desert region of Tucson, Ariz. He found that the root systems of the annuals rarely penetrated the soil more than 8 in. and that the greatest root development took place in the upper 2 to 3 in. of soil. He observed that the depth of root penetration depended upon the depth to which the rains moistened the soils. The cacti have two specialized root systems—a vertical one serving as an anchorage for the plant and a horizontal one which functions mainly in absorption. Most of the horizontal roots of cacti were found in the upper 4 in. of soil. Cannon (1913) also found a similar distribution of the roots of plants growing in the Algerian Sahara. Weaver (1919) found that the roots of *Yucca glauca* or Spanish bayonet, a plant very common in the semiarid regions of the Western plains of the United States, penetrated the soil to a depth of 18 in. only, while the horizontal roots extended to a distance of 30 ft. or more.

Weaver (1920) made an extensive study of the distribution in the soil of the roots of both cultivated and wild plants growing in the grassland formation which extends from the Missouri River to the foothills of the Rocky Mountains. Due primarily to variations in rainfall and evaporation, three more or less distinct plant associations are to be recognized in this area and have been classified by Clements (1920) as (a) the true prairie, (b) the short-grass plains, and (c) the mixed prairie. The true prairies occur in regions of sufficiently favorable soil- and air-moisture conditions to permit the growth of large numbers of dominant tall grasses with which are intermixed a great number of other herbs, the whole forming a luxuriant vegetation. The plants in this region grow under a mean annual precipitation of 28 in. or over, of which 20 in. comes during the growing season. The short-grass plains are characterized by a few short, sod-forming grasses, especially *Bulbils dactyloides* (Buffalo grass) and *Bouteloua gracilis* (grama grass). This short-grass association extends from southwestern Nebraska and the western half of Kansas through eastern Colorado into northwestern Texas, northern New Mexico, and Arizona. In these regions the evaporating power of the air is high and the rainfall is limited, averaging usually 20 in. or less. The mixed prairie occupies a region of greater precipitation and more favorable conditions for plant growth than the short-grass plains, and one of the distinctive features of this association is the intimate mixing of the tall with the shorter grasses.

From his 1,500 observations of the root systems of 180 species of plants growing under varied conditions of this grassland formation in 25 stations

in Kansas, Colorado, South Dakota, and Nebraska, Weaver concludes that the longest and most deeply penetrating roots are found where there is considerable rainfall, where much of this rainfall penetrates into the soil, and where the water table is relatively low. He emphasizes the fact that the maximum depth to which a few roots will penetrate is not of so much importance in the water relations of the plant as is the working or average depth to which the majority of the roots penetrate. It is also not so much a question of the depth to which roots penetrate as what proportion of the root system is functioning in absorption. Weaver found that 65 per cent of the species in the true prairie reached depths greater than 5 ft.; 42 per cent in the mixed prairie and only 13 per cent of the species examined in the short-grass plains reached beyond that depth.

Most of the species of the plains area were characterized by a fine system of wide-spreading laterals. This type of growth is evidently a response to the moisture in the upper portions of the soil resulting from summer showers. Practically all the deep-rooted plants in the short-

HEIGHT OF TOPS, WORKING DEPTH, AND MAXIMUM DEPTH OF ROOT PENETRATION OF RYE, OATS, AND WHEAT IN THE THREE REGIONS OF THE GRASSLAND FORMATION

Station and crop	Height of tops, feet	Working depth of roots, feet	Maximum depth of roots, feet	Remarks
Winter rye:				
Short-grass plains: 5 stations, Colorado and Kansas	2.7	2.8	3.4	Silt-loam soil
Mixed prairie: 3 stations, Colorado and Kansas	3.3	3.7	4.8	Sandy loam and silt loam
True prairie: 3 stations, eastern Nebraska	4.9	4.0	5.3	Mostly silt-loam soil
Oats:				
Short-grass plains: 3 stations, Colorado and Kansas	2.4	2.7	3.4	Silt-loam soil
Mixed prairie: 4 stations, Colorado, Kansas, and S. Dakota	2.7	3.4	4.2	Silt and sandy loam
True prairie: 5 stations, eastern Nebraska	2.8	3.4	4.4	Silt and clay loam
Wheat (turkey red):				
Short-grass plains: 7 stations, Colorado and Kansas	2.1	2.3	2.7	Silt loam
Mixed prairie: 4 stations, Colorado, Kansas, and S. Dakota	2.8	3.6	4.4	Silt and sandy loam
True prairie: 6 stations, eastern Nebraska	3.3	3.8	5.4	Silt loam

grass plains area are well adapted to absorb moisture from the upper portion of the soil. Of the 45 species examined by Weaver (1920) in this region the lateral extent of the roots ranged from $\frac{1}{2}$ to $3\frac{1}{2}$ ft. This contrasts markedly with plants growing in the true prairie region where the lateral spread of roots ranges from 1 to 4 in. The working depth of the roots of the majority of plants in the short-grass plains region was found to be from 1 to 5 ft. Weaver concluded that the root habit of a species is usually altered greatly when plants are grown under distinctly different conditions and that, in general, the distribution of roots conforms strikingly with that of the soil moisture, although a few species are found which show little or no variation to a change in habitat. The effect of the moisture supply on the depth of root penetration can be illustrated by quoting the data obtained by Weaver (1920) in his examination of the root systems of oats, winter wheat, and winter rye growing in the three regions of the grassland formation, (see table page 113).

The mean annual precipitation was 16.7 in. for the short-grass plains, 18.4 for the mixed prairie, and 28.8 in. for the true prairie.

The relative development of the roots and tops of plants growing in the short-grass plains and mixed prairie as compared to those growing in the true prairie region is shown in the following table:

RELATIVE DEVELOPMENT OF CEREAL CROP PLANTS AND RELATIVE PRECIPITATION IN THE GRASSLAND AREA

Plant	Short-grass plain	Mixed prairie	True prairie
Rye:			
Height of tops.....	56	66	100
Working depth of roots.....	69	92	100
Maximum depth of roots.....	65	90	
Oats:			
Height of tops.....	85	94	100
Working depth of roots.....	79	95	100
Maximum depth of roots.....	77	94	100
Wheat:			
Height of tops.....	64	85	100
Working depth of roots.....	61	93	100
Maximum depth of roots.....	51	80	100
Mean annual precipitation.....	58	64	100
Precipitation July, 1918 to July, 1919.....	73	77	100
Precipitation January, 1919 to July, 1919.....	50	53	100

If the proper conditions of soil texture, moisture, oxygen, and temperature prevail, there is nothing apparently to limit the growth of plant roots

downward except the time limit in the length of the life of the plant. The roots of cultivated perennials plants as a rule extend more deeply than those of annuals. The maximum depth of penetration of the roots of corn, sorghums, and the small grains that have been investigated is between 5 and 8 ft. The roots of alfalfa have been observed to grow downward to depths of from 6 to 14 ft. depending upon the age of the plant and the nature of the soil in which they were grown. Cottrell (1902) states that the roots of alfalfa in a good soil grow to a depth of 30 ft., but he gives no experimental evidence to support his statement. Kiesselbach, Russel, and Anderson (1929) found under the conditions existing in eastern Nebraska that 6-year-old alfalfa drew upon the moisture of the subsoil to a depth of 33 ft., indicating that some of the roots had penetrated to that depth. Duley (1929) at the Kansas Agricultural Experiment Station observed that alfalfa used the moisture of the subsoil to a depth of from 10 to 25 ft., depending upon the age of the plants. Coburn (1907) in his book on alfalfa mentions an instance in which the roots of alfalfa grew downward through the soil into a mining tunnel 129 ft. beneath. This great length was possible in this case, since the roots followed the crevices which were present in the soil and rock overlying the tunnel. The major portion of the root systems of the cultivated plants, however, is found in the upper 4 ft. of soil, while in many cases most of the roots are in the uppermost 2 to 3 ft. of soil. In the case of alfalfa, where the maximum depth of root penetration has been observed to be 16 ft. or more, the major portion of the root system was in the upper 6 ft. of soil. In observations on the roots of sugar cane growing in the Hawaiian Islands, Lee (1926) found that more than 58 per cent of the roots of the plants growing in furrows were above the 8-in. level of the soil and that more than 85 per cent of the roots were in the uppermost 2 ft. of soil. On the other hand, the few roots which extend downward into the maximum depth undoubtedly do absorb considerable moisture and in periods of severe drought may be a very important factor in furnishing sufficient moisture to prevent the death of the plant.

2. Lateral Extent.—The lateral extent of the roots of plants will depend upon two main factors: (*a*) the amount of rainfall and (*b*) the thickness of the stand. The difference in the lateral extent of roots of plants growing in the more arid regions as compared with those growing where rainfall is more abundant has been discussed under the heading of the vertical depth of root penetration, but it should be repeated here that the lateral extent of roots is greater the less the rainfall. The thickness of the stand is an important factor in determining the lateral extent of roots. A plant growing by itself in the open will extend its roots farther laterally than one that is closely surrounded by other plants. Miller (1916) found that the roots of corn and sorghum which were grown

in rows 44 in. apart extended from one row to the other and then turned downward. The roots of a single plant of corn or sorghum under such conditions thus extends through a cylinder of soil 7 ft. in diameter and 6 ft. deep and are distributed through a volume of soil that totals 230 cu. ft. The longest roots observed in this experiment were 10 ft. in length. They were those that extended laterally until they reached the opposite row and then turned downward. From the table on the extent of roots it can be observed that the lateral extent of the roots of the smaller cereals is only 4 to 12 in., due to the fact that the plants are in very close rows. The long lateral extent of the roots of corn and sorghum which were investigated by Georgeson and Payne (1897) was due to the fact that these plants were grown in hills 8 ft. apart.

3. The Depth to Which Roots Absorb Water and Nutrients.—The question concerning the depth to which the roots of plants absorb is a very important one from the standpoint of practical agriculture. The extensive investigations concerning the depth of root penetration have shown that a large proportion of the roots of the cultivated plants extend to 3 or 4 ft., a depth much greater than that to which absorption was supposed to occur. This had led certain investigators to doubt the accuracy of statements that are found in the literature on soils concerning the depth to which plants absorb. Russel (1917) states that "only the upper 6 or 8 in. of the soil is suited to plant life and the subsoil plays only an indirect part in plant nutrition." There seems to be considerable indirect evidence to refute the above statement, especially from observations of plant life growing in the Great Plains area. In the first place, the number of roots found in any given area of soil is no indication of their activity. It is a common observation that the first roots formed in the upper portion of the soil become suberized or cutinized so that they are totally incapable of absorbing even if that portion of the soil is moist. It has also been frequently observed that during periods of drought the upper foot of soil has been depleted of its moisture below the wilting coefficient so that little or no absorption occurs there, yet the plant remains turgid and functions normally if there is moisture at the lower depths.

Miller (1916) found in growing corn and sorghums on fall-irrigated land under seasonal conditions in which the rainfall penetrated the surface mulch little or not at all that the moisture content of the soil became depleted as the roots penetrated downward. When the corn was tasseling and the sorghums heading, the moisture content of the upper two feet of soil was below the wilting coefficient, yet the plants remained perfectly normal and matured a crop of grain. Determinations at this time showed that the roots had drawn heavily on the moisture supply of the soil to a depth of 6 ft., as shown in the following table:

SOIL-MOISTURE CONTENT AND DEPTH OF ROOT PENETRATION OF CORN, KAFIR, AND MILO IN 1914 AT GARDEN CITY, KAN.

Date	Percentage of moisture at depth in feet of										Greatest depth of roots, feet		
	1	2	3	4	5	6	7	8	9	10	Corn	Kafir	Milo
June 5.....	22.9	22.5	22.1	22.7	23.5	21.2	16.1	17.0	16.4	14.5			
July 2.....	14.6	20.2	21.2	22.8	22.1	21.8	1	1.5	1.5
July 10.....	11.8	17.1	19.5	23.6	24.6	21.4			
July 21.....	10.6	13.3	14.5	19.4	22.8	21.7	3	2.75	3
July 29.....	8.7	13.1	13.5	16.8	21.4	21.0	4	4	4
Aug. 9.....	9.4	13.5	13.2	14.5	20.3	19.5			
Aug. 22.....	8.4	13.4	12.4	14.4	19.2	19.7	6	6	6
Sept. 6.....	7.7	12.2	11.4	12.9	15.6	19.1	6	6	6
Wilting coefficient ..	12.7	14.5	14.5	16.3	17.1	16.1	18.2	18.9	16.7	13.0			

Weaver, Jean, and Crist (1922) reported control experiments in which they determined the depth to which certain crop plants could absorb water and nitrates from the soil. They grew the plants in large containers. The soil was tamped firmly in layers separated from each other by wax seals 2 to 3 cm. in thickness, which were composed of a mixture of 85 per cent paraffin and 15 per cent petrolatum. These seals permitted the penetration of the roots as they pushed downward, but they prevented the upward ascent of water and nutrients from the lower portions of the soil to the depleted portions above. Each layer of soil could be analyzed for moisture and nutrients at the close of the experiment, and the depth to which absorption took place could thus be determined. These investigators found that oats absorbed water to a depth of 2.5 ft. and barley to a depth of 3.5 ft. before the blossoming stage. Corn absorbed large quantities of water from the third and fourth foot and some from the fifth foot. Potatoes absorbed water to a depth of 2.5 ft. Barley at the age of 54 days removed 168 to 145 ppm. of nitrates from 1- to 1.5- and 1.5- to 2-ft. levels, respectively. When in blossom at the age of 73 days, it had removed 168 ppm. from the 2- to 2.5-ft. level and at maturity 186 ppm. from the 2.5- to 3-ft. level. Corn removed 203, 140, and 118 ppm. at depths of 3, 4, and 5 ft., respectively.

Crist and Weaver (1924) found that barley plants under controlled conditions absorbed nutrients in large amounts at every level to 30 in. The absorption of nutrients at levels below the surface foot materially affects the quantity and quality of the yield, and the additive effect of a nutrient salt present in the lower levels is not lost, even when the surface foot is abundantly supplied with the same nutrients. The effects of the nutritive salts are most marked on the quantity and quality of yield at an

early and late period in the development of the plant, that is, when absorption is effected largely from the first foot of soil as the crop is tillering and again when the younger portions of the longer roots are absorbing from the deeper levels at the time of heading. Millar (1925) studied the relative growth of oats and inoculated sweet clover on the different horizons of Fox sandy loam and Miami silt loam and found indications that different crops may have quite markedly different feeding powers on the various soil horizons.

From the experimental evidence at hand we must conclude that the deeper soils are not only suited to plant life but also play an exceedingly important part in it and deserve a careful consideration in the study of plant production.

III. ROOT HAIRS

The tissue of the root which functions in the absorption of materials from the soil is limited to the single outer layer of epidermal cells. Absorption, however, is not carried on over the whole surface of the root




FIG. 8.—Enlarged portion of the epidermis of a root of lupine showing the origin and development of the root hairs. *a, b, c, d, e*, successive stages in the development of root hairs from the younger portion of the root backward. *oc.*, ordinary epidermal cell.

system, since after varying periods of time the older portions of the roots become so modified by the deposition of cutin or the formation of cork cells that absorption through them can in no way take place. In most cases, then, the absorption area of the root is confined to a definite zone which begins at or near the growing tip and extends backward for varying distances, depending upon the species of plant and the conditions under which it is growing. In most plants a varying number of the epi-

dermal cells of the root undergo a modification which greatly increases their surface of absorption. This modification consists of a tubular outgrowth of the exterior wall of the epidermal cell and is termed a "root hair." The root hair is in no sense a root and it should not be confused with the term "hair roots," which is used to a considerable extent in agricultural literature to denote the small fibrous roots. The formation of root hairs in most cases begins at a distance of one to three millimeters back of the growing tip, but in the case of the sedges, their formation begins at the tips of the roots. New root hairs arise in acropetal succession and new ones are apparently only very rarely interpolated between the preexisting ones (Fig. 8).

Root hairs increase the absorbing surface of the epidermal cells. Schwarz (1883) calculated that the absorbing surface of the roots was increased six times in corn and twelve times in peas by the root hairs which developed on these roots in moist air. In most plants, each cell of the root epidermis is capable of forming a root hair, although under average conditions many do not so develop. It should be remembered, however, that even though an epidermal cell does not develop a root hair, it is still an effective organ for absorbing materials from the soil. This fact has been proved not only for the ordinary epidermal cells in the root-hair region but also for the epidermal cells which border the root tip.

A. GROWTH

Haberlandt (1914) observed the manner of the longitudinal growth of the root hairs of *Cucurbita pepo*, *Pisum sativum*, and *Helianthus annuus* by dusting the hairs with rice powder. He found that the longitudinal growth is confined strictly to the dome-shaped tip of the hair. Haberlandt considered that this manner of growth greatly facilitates the power of the root hair to push itself between the solid particles of the soil.

Jeffs (1922) studied the rate of growth of root hairs in moist chambers in the dark at a temperature of approximately 22°C. He found that root hairs grow slowly at first, gradually increasing their rate of growth up to the time root elongation ceases, and that there is a definite relationship between the elongation of the root hair and the parent root. About the time root elongation ceases, the rate of growth of the root hairs in that region becomes stabilized and there are only slight variations in their rate of growth until about 2 hr. before their growth ceases. The average rate of growth of root hairs of corn, each of which was on a different root, showed an initial rate of 6.5μ per 15-min. interval. This increased to 16.1μ per 15-min. interval at the end of the first hour and 33.6μ per 15-min. interval at the end of the third hour. After this there was no further root elongation in this region and the root hairs grew at the average rate of 35μ per 15-min. period for the next 3 hr., after which they were studied no longer. It has been demonstrated that the rate of

growth of a root hair diminishes very rapidly as it approaches maturity. The approximate length of five root hairs of the radish was $1,824\mu$ 2 hr. before growth ceased, at which time they were elongating at the rate of 44.5μ per 15-min. interval. At 1 hr. before growth ceased they were elongating at the rate of 36μ per interval, while at 15 min. before growth ceased their rate of elongation was only 15μ per $\frac{1}{4}$ -hr. period. Growth ceased on an average of 2 hr. after the retardation in their growth rate could be observed.

Jeffs (1925) investigated the influence of light and temperature on the rate of elongation of root hairs and found that those of *Raphanus sativa* and *Sinapis alba* showed no noticeable growth reactions in the light intensities used. The root hairs of these two species grown under a constant temperature within the limits of 17 and 27°C . showed a decided reaction to temperature changes of from 1 to 6° produced within a period of from 5 to 15 min. A drop in temperature resulted in a decrease in the growth rate and sometimes even in a contraction of the root hair. A rise in temperature of 2.5 to 3° within the 5- to 15-min. period resulted in a temporarily increased growth rate, but this soon returned to that which characterized the root hair before the temperature was raised. Jeffs concluded that the effect of temperature upon the rate of growth of tissues is, in part at least, an effect upon the osmotic pressure and imbibition of the cell colloids, rather than simply an effect upon the rate of chemical reactions within the tissues.

Farr (1925) compared the rate of growth of the root hairs of *Tradescantia fluminensis* in tap water and in Knop's solution. The average growth per minute in tap water was 0.916μ , while that in Knop's solution was 0.437μ . The fastest growth recorded in tap water during any 10-min. period was 24μ as compared with 10.8μ in Knop's solution. The average growth per hour for any series in tap water was 91.8μ ; while in Knop's solution it was 32.9μ . Farr's experiment shows that substances in solution may modify not only the form of root hairs but also their rate of elongation. Farr (1927 to 1928), in a series of the most extensive experiments yet undertaken on the growth of root hairs in solution, found that the root hairs of the Georgia collards (*Brassica oleracea*) do not grow at all during a period of 13 to 16 hr. after immersion in distilled water. They grow, however, at a rate of 60μ per hour in tap water and about 50μ per hour in Knop's solution. They also do not grow at all during the period of 13 to 16 hr. after immersion in concentrations of $\text{Ca}(\text{NO}_3)_2$ below $0.002 M$. Their maximum growth rate of 61μ per hour in $0.012 M \text{Ca}(\text{NO}_3)_2$ is more or less closely approached when growing in concentrations between 0.007 and 0.012 , but it drops abruptly at higher concentrations to 40μ at $0.013 M$. Farr also observed that the graph representing the effects of varying concentrations of CaCl_2 upon the growth rate of root hairs is almost identical with that for calcium nitrate

in form and in the location of the optimum molar concentration. The importance of calcium in the root hair and in root growth is attributed largely to its being the only constituent of the cell wall which is of direct external origin, although it must be recognized that calcium also plays a part in antagonism, H-ion concentration, and permeability. In a study of the effect of the H-ion concentration in calcium solutions upon root-hair growth it was found that the maximum elongation of the root hairs of the Georgia collards was 109.8μ per hour in $0.020 M$ CaCl_2 at P_{11} 6.9. The H-ion concentration range for root-hair elongation was from 3.4 to 11.9, varying with the concentration of the solution. It was also concluded that the entire root responds to changes in the H-ion concentration in much the same way as do the root hairs. Farr states that in producing root hairs, roots exhibit the power of adaptation to a wider range of H-ion concentration than any other organ, organism, or physiological process which has thus far been studied, although enzymes have been found to tolerate a still wider range.

The length of life of root hairs depends on the species of the plant and upon the moisture conditions of the soil. Root hairs of some species live for only a few days or weeks, while those of others exist for several years, although they do not apparently function in absorption for a period that long.

McDougall (1921) observed that the root hairs of *Gleditsia triacanthos* became thick walled and brown in color and that they persist as long as the root epidermis, which may be for several months. The older root hairs examined by him had a cell-wall thickness of 2μ , which is approximately four times the thickness of the cell wall of the root hairs of this plant when they are first formed. These hairs are only about 0.4 mm. in length and are stiff and rigid and do not shrivel upon exposure to the air even after several months. McDougall found that the root hairs of *Gymnocladus dioica* and *Cercis canadensis* sometimes become thick walled and brown but that this is not nearly so characteristic of these as it is of *Gleditsia triacanthos*. Whitaker (1923) confirmed the work of McDougall and found that the root hairs in certain species of the compositae persist for as long as 3 years. Weaver (1925) found in the case of wheat growing in the soil under field conditions that the root hairs did not begin to slough off from the oldest parts of the primary root until 7 weeks after planting and that at the end of 10 weeks more than 99 per cent of the root area still possessed functioning root hairs. In this case the soil was in excellent condition for their retention, but under conditions of a low water supply in the upper portion of the soil not only the older root hairs but also many of the more delicate branch roots would also perish. Root hairs range in length from a fraction of a millimeter to 10 mm., but their length and general shape depend to a great extent upon the medium in which they are grown. In its passage through the soil

the surface of the root hair retains the irregularity in the outlines of the objects to which it adheres. The changes in the shape of the root hair due to the various obstructive particles of the soil bring about a retardation of its general growth so that it often reaches only a small fraction of the length that it would attain if it could develop in moist air. The diameter of root hairs is about 10μ and their growth in length during the first few hours is less than 2 mm.

B. CONDITIONS THAT AFFECT THE FORMATION OF ROOT HAIRS

The number of root hairs that develop will depend primarily on the environmental conditions. Snow (1904, 1905) observed that high temperature with sufficient moisture tends to decrease the number of root hairs per unit of area by increasing the elongation of the epidermal cells. She also observed that the slower the growth the more root hairs were developed per unit area and that not only lower temperatures aided this effect but obstructions in the pathway of the root produced the same results. Schwarz (1883) estimated the density of the root hairs on the roots of corn growing in moist air as 425 per square millimeter, while the number on the roots of the pea under the same conditions was 232 per square millimeter. Snow also found that saturated soil tends to suppress root-hair production. Roots of corn and wheat grown in garden soil kept moist were found well covered with hairs after 7 days. Other roots growing in a saturated soil for the same period of time showed few or no root hairs, but after this same soil was allowed to dry root hairs appeared as numerously as in the moistened soil.

Spalding (1904) found better and more root-hair development in the creosote bush growing in a soil comparatively dry than when growing in a soil well supplied with water. Bardell (1915) grew corn, wheat, squash, beans, and peas in water and found that root hairs were produced under these conditions. She found that light conditions have no effect upon root-hair production and that curves and swellings are favorable to their formation. The hairs are most abundant on the concave side of the root. The average length of the cells producing hairs whether grown in air, water, or fractional solutions of normal KNO_3 is less than that of hairless epidermal cells and of cortical cells, showing that relative elongation of the epidermal and cortical cells is an important factor in root-hair production.

In this connection it should be mentioned that the roots of *Lemna minor*, *Nymphaea alba*, *Hippurus vulgaris*, and others do not develop root hairs, while *Scirpus sylvaticus* and *Carex paludosa* growing under similar conditions produce them fairly abundantly. The roots of *Elodea canadensis*, *Acorus calamus*, *Nuphar luteum*, and others produce no root hairs so long as they are immersed in water but develop them abundantly upon entering the soil.

The effect of bog water on the production of root hairs of the cuttings of *Tradescantia* was investigated by Rigg (1913). He found that practically no root hairs were produced normally by this plant when grown in bog water from Puget Sound. Of the specimens examined, 18 per cent produced no root hairs, 66 per cent produced hairs that were much stunted, while 16 per cent were only slightly stunted. He also found that effects on root-hair formation similar to those produced by bog water occurred in each of the following solutions: sea water diluted three times, carbolic acid 0.001 per cent, formalin 0.001 per cent, weak tea, and coffee. The root hairs developed normally in the filtered bog water and fairly well in the diluted bog water. Riggs believed that many plants are excluded from bogs on account of their inability to produce root hairs under those conditions and thus have a too limited absorbing surface. Addoms (1923) concluded that the abnormal root development and decreased growth of plants grown in nutrient solutions containing relatively large amounts of potassium-dihydrogen phosphate are due to the coagulation of the protoplasm of the root hairs. This coagulation, which is accompanied with flocculation, was found to be induced by the hydrogen ions formed by dissociation of the phosphate. The hydrogen-ion concentration of the nutrient solutions used varied from P 3.94 to 3.47.

C. THE CELL WALL OF ROOT HAIRS

Schwarz (1883) found that the cell wall of the root hair of *Taxus baccata* or yew is of two parts—an inner layer which stains blue with chlorzinc iodide and an outer layer which stains yellow brown. He concluded that the contact between the root hairs and the soil particles is rendered more permanent and intimate by the gelatinization of the outermost layers of the root membrane. Hesse (1904) found that the thickness of the cell wall of the root hair of any plant varied with the medium in which it was grown. Ridgway (1913) observed the occurrence of callose in the cell wall of certain root hairs. Roberts (1916) found in a majority of the forms investigated that the walls of root hairs growing in moist air are made up of two parts—an inner membrane which gave the cellulose reaction with 75 per cent sulphuric acid and the potassium-iodide iodine solution and an outer membrane which stained red with Ruthenium red denoting pectic compounds. That this membrane is calcium pectate was shown by the fact that on the addition of ammonium oxalate the membrane broke down and calcium-oxalate crystals were formed. Callose was observed at the tip of the root hairs in mustard, pea, and *Tradescantia* amongst others. The relative amount of the cellulose and pectin found in the cell walls of various root hairs is shown in the following table:

Plant	Nature of the cell wall of the root hair	
	Inner layer	Outer layer
Alfalfa.....	Thin cellulose	Thick pectin
Barley.....	Thin cellulose	Thick pectin
Corn.....	Thick cellulose	No pectin
Cabbage.....	Thin cellulose	Thin pectin
Pea.....	Thick cellulose	Thick pectin
Tobacco.....	Thin cellulose	Thin pectin
Mustard.....	Thin cellulose	Thin pectin

The calcium-pectate membrane on the outer wall of the epidermal cell and the root hair is a continuation of the middle lamella of the other walls of the cell. There is thus a secretion of calcium pectate around the entire cell, but the layer on the external wall is thicker than that on the other walls of the cell. The layer of pectic material is thinner toward the tip than it is at the base of the root hair. The high efficiency of the root hair as an absorbing organ is thus due to the fact that the soil particles are held to it by this pectic substance.

Howe (1921) examined the root hairs of 20 economic plants growing in sand and in loam soil. Some of the plants examined were beans, cabbage, corn, cucumber, radish, peas, squash, tomatoes, and watermelons. He found no cellulose in the cell wall of the root hairs grown under these conditions. The wall of the root hair contained a layer of pectic material on the outside and on the inside a layer of callose which varied in thickness for different plants, but in all cases it was a little thicker at the tips than in the lateral walls. As the wall of the epidermal cell bulges to form the root hairs, the inner layer, which is composed of cellulose, apparently stretches to its capacity and breaks and no more cellulose is formed. The outer pectic layer of the wall, however, is not ruptured but is extended out to form the root hair. Howe found that the root hairs formed either in loam or in sand gave an acid reaction in all cases, but the root hairs produced in loam soil were usually somewhat the more acid. The P_{H} values of the root hairs ranged from 6.0 to 6.8 in most cases. Whether the acidity of the root hair can be ascribed to the presence of pectic materials or to some other cause was not determined.

IV. EXCRETIONS OF ROOTS

From the discussions in Chap. II concerning the factors affecting the permeability of the cell membranes, it can readily be conceived that numerous conditions, both internal and external, might arise under which the outward diffusion of the cell contents of the roots into the soil

might occur. It is not the intention here to consider the possible loss of the inorganic salts from the roots but to discuss more particularly the excretion of those compounds that are waste products or synthetic substances of the protoplasm. The subject will be considered especially from the standpoint of the beneficial or detrimental effect that certain of these products are supposed to exert upon the plant which produced them or upon the plants growing in close proximity to it or upon the plants which follow it. The three topics to be considered are (a) the excretion of acids, (b) the excretion of enzymes, and (c) the production of beneficial or toxic substances by the roots.

A. ACIDS—CARBONIC ACID

Liebig (1858) first observed the dissolving action of roots on limestone, and his observations were verified by Sachs in 1860. Sachs advanced two theories as to the cause of this dissolving action. He considered that it was brought about either by the liberation of carbon dioxide or by the formation of acid due to the decomposition of the cell walls of the cells of the root. Czapek (1896) studied the excretion of acids from roots by the use of plates made with mixtures of aluminum phosphate and plaster of Paris. Plates of this composition are soluble in HCl, HNO₃, H₂SO₄, H₃PO₄, formic, oxalic, succinic, lactic, malic, citric, and tartaric acids but are insoluble in carbonic, acetic, propionic, and butyric acids. These plates showed no signs of etching when the roots of various plants came in contact with them, from which it was considered that none of these acids was excreted by the roots under the conditions of the experiment. Plants were grown in Congo red which becomes brownish red when acted upon by carbon dioxide and bright blue through the action of acetic and propionic acids. The results showed that carbon dioxide alone was excreted by the roots. Kunze (1906) also observed that free mineral acids are not excreted from the roots of higher plants, while Haas (1916) showed that CO₂ was the only acid excreted by the roots of sweet corn. Stocklase and Ernest (1908) found that if the roots of plants have a normal oxygen supply no acids either organic or inorganic except carbonic acid are excreted. If, however, the oxygen supply is cut off or is limited, organic acids only are produced. They found that the roots of buckwheat and barley under limited supplies of oxygen produced formic and acetic acids while the roots of oats and maize under like conditions excreted formic acid and the roots of beets, oxalic acid. These organic acids arise from incomplete oxidation and under normal conditions of aeration would be oxidized to carbon dioxide and water.

1. Relative Amounts.—The evidence indicates that under normal conditions carbonic acid is the only acid liberated by the living cells of the roots. Coupin (1918) considered that this was excreted more particularly by the superficial cells of the rootlet between the root hairs and the

root tip and by that portion from which the root hairs have disappeared. Carbon dioxide is an end product of respiration, a process which is going on continuously in every living cell, so that the amount of carbon dioxide thus formed will depend, then, upon the environmental conditions and upon the nature of the plant. Since the intensity of respiration varies directly with the intensity of metabolic activity, it would also be expected that the amount of carbon dioxide excreted by the roots would vary during the growing season of that plant.

Kossowitch (1904) found that the roots of mustard in pots and water cultures produced increasing amounts of carbon dioxide up to the time of blooming, while Barakov (1910) showed that the carbon dioxide content of the soil was insignificant at the beginning of vegetative growth but increased rapidly and reached its maximum at the blooming period and declined rapidly to the minimum at the ripening period. He observed that the greater the plant growth the more carbon dioxide there was in the soil. Most of this came from the respiration within the roots and varied with different crops and different stages of growth. With lupines the maximum was reached at the blooming stage and with oats about 2 weeks before blooming. The maximum production of carbon dioxide by the roots of potatoes was reached after blooming, while its excretion by sugar beets reached its highest point at the period of maximum growth. Lau (1906) observed that potatoes and legumes gave off more carbon dioxide than other crops, while Stocklasa and Ernest (1905) found that red clover, beet, and oat roots produced more carbon dioxide in the order named than the other plants considered. Turpin (1920) found that the oat crop increased the production of carbon dioxide in the soil. This increase became marked from the first month after seeding and increased to a maximum just previous to or after these plants had headed, following which decline took place. Millet produced about the same amount of carbon dioxide as oats. A cropped soil after harvest maintained a higher carbon dioxide content than bare soil, and it was considered that this was due to the decomposition of roots. Turpin considered that plants at their most active period of growth produce many times as much carbon dioxide as is produced by soil organisms and that the excess of carbon dioxide in the soil of growing crops is due to the respiratory activity of the roots of the plants rather than to the decay of root particles from the crop. According to Newton (1924), there is good evidence to prove that the quantity of CO_2 produced in soils by the decomposition of organic matter is greater than the quantity given off by the respiration of the roots of the growing crop.

2. Solvent Action.—The solvent power of the carbonic acid excreted by the roots upon the minerals of the soil is a matter of question. Hall (1906) considered that carbonic acid is the only acid excreted by the plant roots and that it is capable of dissolving everything needed by

the plant. Aberson (1910) considered that the mucilaginous covering of the root hairs contains a saturated solution of carbon dioxide sufficient to bring into solution the insoluble soil constituents with which it comes in contact, especially the phosphates. Pfeiffer and Blanck (1912), however, showed that in soils treated with phosphates the carbon dioxide given off by the roots of the plant does not form a solvent sufficiently powerful to account for all the mineral nutrients obtained by the plant from the soil. Russell and Appleyard (1917) observed a considerable increase in the production of CO_2 in the soil during the period of rapid growth of the crop and another and larger increase at the time of ripening. Bizzell and Lyon found the greatest apparent production of CO_2 by oats to be at the time of blooming, after which a marked decrease occurred. Fred and Haas (1919) studied the etching power of the roots of Canada field peas upon polished marble in sterile soil which had been inoculated with various bacterial cultures other than those of the nitrifying bacteria. It was found that in every case the marble slabs that had the greatest degree of etching were those in the soil which had been inoculated. They considered that the greater etching power of these roots in the presence of bacteria can be attributed to the normal carbon dioxide excretions of the living cells together with the carbon dioxide and acids set free from dead or dying root cells whose decomposition is accelerated by the presence of bacteria. Parker (1924) is of the opinion that the carbon dioxide excreted by the roots is more effective in bringing plant food into solution within reach of the plant than a unit of CO_2 produced in the soil by the decomposition of organic matter. He, however, could find no relation between the carbon dioxide production of roots and the feeding power of the plants for Ca, Mg, P, and K in a poor sandy soil. More carbon dioxide was excreted by the roots of cowpeas than by those of any other plant, while buckwheat roots gave off very little carbon dioxide but had the greatest feeding power of any of the plants used. For each gram of carbon dioxide excreted by the roots, buckwheat absorbed 41.5 mg. of Ca, while sorghum, cowpeas, and soybeans, respectively, absorbed 5.0, 12.7, and 21.2 mg. of this element for each gram of carbon dioxide excreted by the roots. It has long been recognized that species of plants differ widely in their ability to grow on infertile soils. It is well known that beans, rye, and buckwheat can grow apparently to good advantage on poor land, while pennyroyal, sassafras, poverty grass, and others are indicators of impoverished soil upon which plants like corn, barley, wheat, blue grass, and others grow poorly or do not thrive at all. Dustman (1925) studied the rate of excretion of carbon dioxide from the roots of these two types of plants. He found in his experiments that the production of carbon dioxide whether estimated from the standpoint of dry matter of roots or unit area of root system was greater for buckwheat and rye than for corn and barley.

He is of the opinion that the output of carbon dioxide in connection with the relative size and area of root systems is an important factor in aiding certain kinds of plants to secure the essential elements from the soil. Metzger (1925) also considered that the carbon dioxide excreted by roots exerts a measurable solvent action on soil nutrients. He used the concentration of bicarbonates as a means for determining the action of the carbon dioxide excreted by the roots. In 66 determinations with corn, kafir, wheat, and other plants 53 showed higher concentration of bicarbonate in samples from around roots, 4 showed equal, and 9 lower concentrations than in samples taken at short distances from the root.

B. ENZYMES

The question of the excretion by the roots of substances that are capable of oxidizing, reducing, or digesting materials in the soil has been investigated and is worthy of note. Molisch (1887) first demonstrated the oxidizing power of intact roots. He showed that there was considerable active secretion on the surface of grown roots and considered that this secretion had definite powers to effect changes in organic substances. Raciborski (1905) found that all the roots of the phanerogams examined by him had the property of extracellular oxidation. Schreiner and Reed (1909) considered that plant roots are able to carry on active extracellular oxidation chiefly by means of enzymes which they secrete. These investigators used wheat plants of the varieties Harvest Queen and Chul and found that their roots were able to oxidize organic substances such as chromogens at a fairly rapid rate. When the roots were grown in solutions containing alpha-naphthylamine, benzidine, vanillin, vanillic acid, or esculin, insoluble colored oxidation compounds were yielded which were deposited mainly upon the surface of the roots. Color changes that indicated oxidation were also observed when plants were grown in solutions containing phenolphthalein, aloin, and leucorosolic acid. The oxidizing power appeared to be most energetic in the region of the root where the root hairs are found and increasingly less active as that portion of the root becomes older. Schreiner and Reed found that the roots had greater oxidizing power in extracts of productive soil than in those of unproductive soil and that the presence of toxic organic substances in solution was extremely deleterious to the oxidizing power of the roots. Schreiner and Sullivan (1911) found that the roots carry on oxidation and reduction concurrently. The oxidation processes are weak in the young seedling but increase in strength as the seedling grows. The reduction processes are predominant in the early stages of the seedling growth but are less manifest at a later stage. Reduction is mostly intracellular, while oxidation, which seems to be the more prominent of these two properties of the roots, is mostly extracellular. The reducing power of the roots of grasses has also been observed by Sani (1919), and

the oxidizing power of roots upon ammonium ferrosulphate has been observed by Borowski (1919). He also considers that this oxidizing ability is located in the region of the root hairs and at the growing tips. He found that the oxidizing ability of the roots of different plants varies. In his experiments the roots of *Sinapis* showed the weakest, while *Phaseolus* showed the greatest power of oxidation. Lyon and Wilson (1921) working with nutrient solutions in which corn, oats, peas, and vetch were growing could detect reducing substances by some tests but not by others. They were not able, however, to show to their satisfaction that oxidizing substances were present in these solutions. Neller (1922), on the other hand, found in all his experiments with soybeans, field peas, and buckwheat, that these plants had a beneficial influence upon the oxidation activities in the substrata in which the plants were grown and suggested a symbiotic relationship between the soil oxidizing organisms and the roots of these growing plants.

The ability of the plant to absorb from the soil more or less complex organic compounds makes the excretion of digestive enzymes by the roots an interesting question. This subject has been investigated by Knudson and Smith (1919) and by Knudson (1920). They found that neither corn nor Canada field peas are capable of utilizing soluble starch directly or indirectly, nor is there any appreciable excretion of diastase by the roots of these plants under the conditions of the experiments. When these plants were grown in the presence of sucrose there was an increase in the amount of reducing sugars in the cultural solution, but incubation experiments gave negative results with respect to the presence of invertase. Knudson considers that the increase in reducing sugars in his experiments was due to their excretion from the roots into the solution rather than to the secretion of invertase with a consequent digestion of non-reducing sugars.

C. BENEFICIAL OR TOXIC SUBSTANCES

It has been known from the earliest times that one species of plant may have a detrimental or beneficial influence upon other plants of the same or different species that are growing in close proximity to it or that follow it in succession. Let us consider first the beneficial influence of one plant upon another.

1. The Beneficial Influence of One Plant on Another.—It has been known for several thousand years that grapes grow well in association with the elm tree and that certain grains produce better when grown in combination than when they are grown separately. Dandeno (1908, 1909) grew squash and corn seedlings together and separately and found that the growth when grown together was greater than when grown separately. He also found that the growing of Canada thistle with oats, wheat, and barley was beneficial to them. Zavitz (1922) grew oats,

barley, spring wheat, and peas separately and in various combinations for the production of grain for six years. Six mixtures having two classes of grain in each mixture, four having three classes of grain in each mixture, and one having all four classes of grain in combination were used each year and varieties were selected which matured uniformly. It was found with but one exception in the 11 mixtures that the grains grown in combination gave a greater yield per acre than the average production of the same grains when grown separately. The yield of straw was the highest in every instance in the case of the mixed grains. The different classes of grains exerted an influence on the productiveness of the mixtures in the following order: oats, barley, peas, and wheat—oats having the greatest effect and wheat least. It was found after 15 years of experimentation that the greatest yield of grain per acre in the case of barley and oats was produced by using a mixture of 48 lb. of barley and 34 lb. of oats per acre. The use of mixtures of different varieties of the same grain showed no beneficial results over the grains when grown by themselves.

The yields of grain and straw of the different mixtures and when grown separately are shown in the following table:

Varieties of grain grown in mixtures	Yield per acre			
	Straw, tons		Grain, pounds	
	Grown separately	Grown in mixture	Grown separately	Grown in mixture
Barley and oats.....	1.56	1.74	1,935	2,261
Barley, peas, and oats.....	1.47	1.67	1,489	2,101
Barley, wheat, and oats.....	1.47	1.72	1,683	2,067
Peas and oats.....	1.52	1.77	1,873	1,988
Barley, peas, wheat, and oats.....	1.43	1.71	1,682	1,955
Wheat and oats.....	1.52	1.68	1,624	1,921
Peas, wheat, and oats.....	1.44	1.73	1,642	1,860
Barley and peas.....	1.33	1.56	1,740	1,760
Barley, peas, and wheat.....	1.32	1.57	1,553	1,665
Wheat and barley.....	1.33	1.41	1,491	1,558
Peas and wheat.....	1.29	1.37	1,429	1,322

Army, Stoa, McKee, and Dillman (1929) under certain conditions and in some regions thought that mixtures of flax with wheat, oats, or barley, was beneficial in producing a greater yield but that under other conditions it was of no advantage.

2. The Deleterious Influence of One Plant on Another.—It has long been a matter of common observation that the soil becomes more and more unproductive for a given crop that is grown continuously upon it and also that the preceding crop may have a detrimental effect upon the

succeeding one of a different species. Finally, it has also been observed, especially in comparatively recent years, that plants growing in close relationships may have a detrimental influence on each other that cannot be wholly attributed to the competition of these plants for the raw materials of the soil and air or for the supply of sunlight.

Pickering (1903, 1917) and Bedford and Pickering (1914, 1919) reported their observations dating from 1898 upon the deleterious effects of one plant upon another. They considered that it is established with a reasonable amount of certainty that the detrimental effect of one growing plant upon another is of general occurrence. They developed a method for growing two plants in a single pot in order to study the influence of one upon the other. One of the plants was grown in a layer of soil contained in a tray which was superimposed on the soil in which the other plant was growing. The water was applied to the tray so that the lower soil received the drainage from the upper one. They found that pears, plums, apples, cherries, certain forest trees, mustard, tobacco, tomatoes, barley, clover, and some grasses are susceptible to this detrimental effect which may be exerted by apple seedlings, mustard, tobacco, tomatoes, clover, and 16 varieties of grasses. This deleterious effect varies greatly but is especially manifest in the reduction of growth which varies from 6 to 97 per cent. Fruit trees which are affected by the harmful products of certain grasses not only show reduced growth but also exhibit alterations in the coloring of the bark, leaves, and fruit which are unlike those attending other forms of ill treatment. These investigators found the above results so manifest that expert fruit growers were unable to name correctly the varieties thus affected. Pickering (1917) considered that different individual plants of the same species when grown together exert a deleterious effect upon one another. For example, it has frequently been observed that when the seeds of a given plant are sown and then three or four days later more seeds of the same kind are sown among those already in the ground, the plants resulting from the seeds first sown outdistance those from the later-sown seeds in their general vigor and rate of growth out of all proportion to their respective ages. In the case of mustard, a difference in the date of planting of only four days showed three months later a difference of 60 to 70 per cent inferiority in growth of the plants from the seeds sown later. In one case, a difference in germination of four days of one half of the mustard seeds in a given plot showed a reduction in yield by weight of 20 per cent.

Hedrick (1905) found that young peach trees were hindered in their development when grown in the same pot cultures with oats, potatoes, tomatoes, mustard, and rape even though the optimum conditions of moisture, aeration, and food supply were maintained. Dandeno (1908, 1909) observed that the growth of buckwheat was considerably deterred by Canada thistles when the two plants were grown together. He also

observed that poplars and oaks were injurious to the growth of corn. The injurious effects extended to some distance from the trees, a fact which showed that shade and moisture were not the deciding factors. It has also been observed by Jones and Morse (1902), Cook (1921), Massey (1925), and Schneiderhan (1926) that walnut trees have a detrimental effect upon the growth and vigor of various plants. These trees prevent the growth of cinquefoil (*Potentilla fruticosa*) within a large area surrounding them and cause the wilting, stunting, and frequently the death of corn, tomatoes, potatoes, alfalfa, and apple trees when their roots come in contact or close proximity to those of the walnut. It is a common observation in the Great Plains area of the United States (Sewell, 1923) that wheat planted in the fall after the various types of sorghums (*Andropogon sorghum*) does not yield so well as wheat planted after corn. At the Kansas Agricultural Experiment Station, winter wheat grown after a kafir yielded three bushels less per acre per year over a period of six years than when grown after corn.

The probable causes for the detrimental influence of one plant or crop on another has been attributed to three general factors: (a) the depletion of the nutrients in the soil so that there is not a sufficient supply for the plants which follow; (b) the production in the soil of compounds by the decomposition of roots, stems, leaves, and the cells which are lost from the growing root that are deleterious to the roots of the plants with which they come in contact; (c) The excretion of toxic substances by the roots of the plant which are injurious to the roots of the plants growing nearby or which follow in succession. Let us now consider the evidence for these three general theories.

a. *The Influence of the Depletion of the Nutrients in the Soil on Plant Growth.*—It was noted by Livingston, Schreiner, Skinner, and Reed (1905 to 1912) that, in many cases at least, there is no correlation between the mineral composition of soils and their crop-producing power, since the amount of nutrients removed from a given soil by a crop is not sufficient to account for the diminished yield of the following crop.

Hartwell and his workers (1918, 1919) have reported extensive work in regard to the influence of certain crops on those that follow. The general plan of their experiment was to grow 16 different crops on that number of parallel plots for two successive seasons and then every third year to grow one of these crops over the entire area. The plants which were grown were onion, potato, mangel beet, rutabaga, cabbage, buckwheat, corn, millet, oats, rye, carrot, redtop, timothy, alsike clover, and red clover. The crops that were grown uniformly over all the plots were onions in 1910, buckwheat in 1913, and alsike clover in 1916. The yield of onions following the various crops will serve as an example of the general facts observed. This was from 13 to 17 bu. per acre following cabbage, mangel beets, rutabaga, turnips, and buckwheat; 35 to 87 bu.

following rye and potatoes; 131 to 178 bu. following corn, millet, onions, oats, and red clover; 240 to 314 bu. following squash, timothy, and alsike clover; and 406 to 412 bu. following mixed timothy and redtop and redtop alone. These field experiments were checked by pot experiments in the greenhouse, and the following conclusions drawn:

The divergent effect of crops on those which follow seems not to be attributable at least principally to differences in the amount of nutrients removed by the crops grown previously. That is, the smallest yields may not occur after the crop which removed the largest amount of even the most needed nutrient.

They also found that the soil acidity was affected differently by the crops under consideration and that in the case of the onion, a plant which is sensitive to acid conditions, the best yields followed the crops giving rise to the least acidity. It was also found that the divergent effect of crops on those that follow was less if the soil acidity was corrected by liming. Garner (1925) and his workers from extensive studies on tobacco culture consider that the tobacco plant is particularly sensitive to the effects of preceding crops. It may be seriously retarded as a result of the effects of preceding crops of tobacco itself or of various other plants. Under intensive methods of production, when tobacco follows tobacco, reduced yields are not due, proportionately, to a reduction in the general productiveness of the soil. It is now generally accepted, in many cases at least, that the detrimental effect of a crop on the succeeding one is not due to the exhaustion of the nutrients of the soil by the preceding crop.

b. The Influence of the Decomposition of Roots in the Soil on Plant Growth.—It is now universally accepted that the productivity of the soil may be decreased by reason of more or less complex organic substances that may be produced in it. Livingston, Britton, and Reid (1905) and Livingston (1907) found that the unproductive soils which they examined contained soluble organic substances that were toxic to wheat plants. They observed that these soils were greatly benefited without any alteration of the nutrient conditions by the use of practically insoluble bodies such as ferric hydrate and carbon black which apparently rendered the harmful substances inactive. Tannic acid and pyrogallol also benefited these soils. This beneficial action they considered due to the chemical combination of these compounds with the toxic substances which so altered them that they became non-injurious to the plants. They considered that the beneficial effects derived from the use of stable manures on unproductive soils are due more to the addition of organic matter which alters the toxic substances of the soil than to the increased amount of salts added to the soil. Breazeale (1906) showed that the extracts of certain soils were injurious to wheat plants when grown in water cultures and that this toxicity could be overcome wholly or in part by

the treatment of the extract with carbon black, calcium carbonate, ferric hydroxide, and other solids.

Schreiner, Skinner, Shorey, Reed, and their coworkers (1907 to 1912) in some of the outstanding work of the century in organic chemistry have studied the effects and nature of the organic compounds of the soil. They developed means of extraction and identification of many of these substances. The following are some of the compounds of the soil that have been isolated and identified: dihydroxy stearic acid, picoline carboxylic acid, agroceric acid, hydroxy fatty acids, paraffinic acid, lignoceric acid, resin, glycerides of fatty acids, phytosterol, pentosan, pentose, histidine, arginine, pyrimidine, oxalic acid, succinic acid, purine nucleic acid, xanthine, choline, adenine, creatine, tyrosine, vanillin, cumarin, and others. Some of these compounds were found to be non-injurious and even beneficial to plant growth, while others were found to be injurious. Among those which were injurious were cumarin, vanillin, dihydroxy stearic acid, alanine, glycolol, neurine, quinone, pyridine compounds, and tyrosine, the degree of injury depending upon the nature and concentration of the substances under observation. These investigators found that when absorbing agents or certain fertilizers were used, the toxicity of the above-mentioned compounds was greatly reduced. The various fertilizer salts acted differently in overcoming the harmful effects of certain compounds. To neutralize cumarin, phosphate fertilizers were the most effective. In the case of vanillin, nitrogenous fertilizers were the most efficient antidoting agents, while potassium salts were most effective in overcoming the toxic action of quinone. The action of fertilizers on non-productive soils is not definitely known, but the results observed add weight to the evidence against the assumption that their effect is due altogether to the increase in plant nutrients that they add to the soil.

A glance at the list of the organic compounds that have been isolated from the soil shows that many of these substances are those which commonly result from the decomposition of animal and vegetable matter. The sources of the organic matter in the soil are the roots and stubbles of the plants which have previously grown in it and the cells which may be lost from the root tips of the plants growing therein. The kind of products that may arise from the decomposition of the organic matter in the soil will thus depend upon many and varied factors. Among these are the kind of plant that produced the organic matter, since each species of plant is made up of more or less specific compounds, and the age of the plants (Waksman and Tenney, 1928). The products produced will depend upon the amount of moisture in the soil, the thoroughness of aeration, the character of the microorganisms in the soil, and the mutual relation of the organic compounds and the mineral constituents. These factors which have just been mentioned are in turn influenced by cultural

practices, fertilizer, drainage, irrigation, and inoculation. Thus the resulting compounds from plant material in the process of decomposition may vary greatly so that the substances which may arise from a given type of plant material under one set of conditions may be very toxic to plants, while those which may arise under another set of conditions may not injure the following plants at all. The aeration of the soil is a very important factor in determining or overcoming the toxic properties of many organic compounds. Pickering (1917) found that if the soil leachings which were toxic to plants were exposed to the air for 24 hr. their toxic effect had entirely disappeared and that these leachings afterward became very beneficial. Schreiner and his coworkers (1906 to 1912) found that the detrimental influence of many of the organic compounds of the soil could be overcome by the addition of certain substances to oxidize more thoroughly the compounds in question and suggested that the beneficial effect of fertilizers upon plants might be due in part to their capacity as oxidizers.

The idea that the stubble and roots of certain plants may give rise to decomposition products which will be injurious to the crops which follow has been strengthened by the work of Sewell (1923), Breazeale (1924), Collison (1924), and Hawkins (1925). As has previously been mentioned, wheat does not yield so well when grown after a crop of sorghum as it does when grown after corn. In pot cultures where wheat received its moisture solely from water percolating through perforated trays (after the method of Pickering) in which corn and kafir were growing, the growth of the kafir plants inhibited the growth of the wheat. When kafir and corn were grown in these percolating trays, harvested, and then wheat planted so that it would receive the leaching from the trays, the kafir soil leachings depressed the growth of the wheat. From this Sewell concluded that there are decomposition products from the crop residue of kafir which have a retarding effect on the growth of wheat which follows. Breazeale (1924) by growing wheat in water cultures containing the chopped-up pieces of the stubble of kafir found that a toxic property was developed during the decomposition of the stubble that was injurious to the wheat plants. He observed that this toxic body or bodies were shortly either volatilized or decomposed into non-toxic substances. The decomposition of the stubble is hastened by an increase in temperature, and a good nutrient solution can be produced from finely chopped sorghum stubble in three or four weeks. From a mixture of water and stubble that was toxic to wheat plants, Breazeale distilled off a poisonous compound which would kill wheat plants within a few hours. Hawkins (1925) found that the stalk residues of the sorghums were more detrimental than those from the roots to plants that follow. He also observed that certain crop plants such as field peas do not use the upper stratum of soil as do the sorghum plants and are not depressed in growth following

a crop of sorghum so much as other crops such as vetch which have root systems more like sorghums. The detrimental effects of sorghum disappear in a few months after the crop has been harvested. It was found by Conrad (1927) that sorghum roots may contain as much as fifteen times the amount of sugar as the roots of corn. When this is liberated into the soil after harvesting, it stimulates the growth of certain microorganisms which thus compete with the following plants for nitrogen and probably for other elements. This released sugar may also retard the process of nitrification. He considers, then, that the immediate cause of the deleterious effects of sorghums on crops which follow may be due to one or more elements becoming a limiting factor. He believes that the result can be overcome to a great extent by a system of cultivation that would lead to the rapid decay of the roots. The work of Wilson and Wilson (1928) suggests that the injurious after effects of sorghum may be associated with the comparative ease with which the roots are oxidized in the soil. This process, which is accompanied by an increase in the number of soil organisms and an increase in the assimilation of nitrate nitrogen, would tend to deplete the soil of available nitrogen. Watery extracts of cereal straws, timothy residues, and alfalfa were found by Collison to be very toxic to plants grown in them, and he considers that there is no doubt but that these and other plant residues are important contributors to the soil of compounds toxic to plant growth. Whether the amounts of material thus contributed to the soil would ever become toxic to a crop in the field would depend upon the nature of the soil and the treatment that it receives. Collison further suggests that if these toxic compounds are present in the fresh sap they might serve as inhibiting agents against parasitic fungi.

c. The Influence of the Secretion of Toxic Substances by the Roots of Growing Plants on Plant Growth.—The theory that plant roots excrete or eliminate into the soil certain waste products which are especially injurious to other plants is an old one. De Candolle (1832) advocated a theory of crop rotation on the basis of root excretions in which he claimed that plants excreted from their roots substances which are harmful to succeeding crops of closely related plants. His theory was based partly on his own observations and partly on the statement of earlier writers. Experiments carried out according to his directions tended rather to disprove than to support his hypothesis. The subject of root excretions was given very little attention until about 1900, when the matter was investigated by Pickering in England and by the Bureau of Soils of the U. S. Department of Agriculture. The investigators in this department were at first inclined to favor the theory of root excretions to account for the deleterious substances which occur in soils. Later, however, it was considered that these detrimental substances might be caused by the decomposition of vegetable matter. In the case of growing plants,

especially, it is considered that the decomposition of the contents of the disintegrating epidermal cells and the cells of the root cap which are continually being lost into the soil might produce the toxic compounds which are toxic to other plants.

Fletcher (1912) grew corn and sesamum together under conditions where water and nutrients were not a limiting factor in their growth. He found that the plants of sesamum grown in rows between rows of corn were only one-third as large as those grown in rows in which a row of corn was on only one side. These plants were only one-sixth the size of the sesamin plants grown in the open with no corn plants near. Since water and light were not limiting factors and since the application of fertilizers did not have any effect, Fletcher concluded that the roots of the corn excreted toxic substances that are injurious to the sesamum plants. Prianischnikov (1914) considers that the hypothesis of root excretions^{is} not sufficiently demonstrated. He believes that the physical nature of the soil, decomposition of roots, and changes in the reaction of the soil might accomplish the same results as toxic excretions from roots. To substantiate his ideas, he presents the following data: When plants were grown in pure distilled water he found no decrease in size or the quality of the crops of second or third plantings either when wheat followed wheat or when wheat followed oats. In sand, however, there was a great decrease in the amount of the harvest of the second and third crops. Mukerji (1920) substantiated the work of Prianischnikov by growing wheat and other plants in Knop's solution. He found that the solutions which had previously grown a set of plants supported better growth than the fresh solution. Peralta and Estioko (1923) reported that cyperus and water lily (*Monochoria hastata*) are beneficial to the production of rice but that zocate (*Leersia hexandria*), the most common forage plant in the Philippines, is detrimental to the rice plants which follow it. Rice is also detrimental to the rice crop which follows. These investigators consider that the roots of these various plants excrete substances that are beneficial as well as detrimental to the crops that may follow. Davis (1928) in a search for the substances which might cause the toxic action of walnut trees upon plants growing near them succeeded in extracting from the hulls and roots of the walnut a substance that is apparently identical with juglone. This extract when purified and crystallized proved to be an exceedingly powerful toxin when injected into the stems of tomato and alfalfa plants. Whether this is the substance which exerts the toxic action by the roots in nature, however, is not known.

The problem of the toxic or beneficial effect of one plant on another is a complicated one and the causes are yet in doubt. A summary of this subject can best be stated in the words of Thatcher (1923):

There is yet no positive proof of the nature of the causative agent or agencies for either the beneficial or injurious effect of one plant on another. It may

vary widely in different cases and may be chemical or bacterial in character. Definite proof that observed injurious effects on a second crop are due to toxic chemical substances in the soil produced by or in association with the first crop has not been established.

V. THE WEIGHT OF ROOTS

The weight of the roots of some of the more common agricultural plants is here considered. It has been mentioned that the weight of the roots as compared to the weight of the tops will depend upon numerous factors, so that in discussing this subject any data given must be considered relative to the conditions under which the plants were grown. The data here presented were obtained by growing plants in large cans containing approximately 700 lb. of soil which was obtained from the surface foot of soil in the field. The soil was in good tilth and the water content was kept practically constant during the growing season. The quantity of soil was sufficient to produce plants comparable in every way to those growing in the field. The data were obtained at the Kansas Agricultural Experiment Station during the years 1923 to 1926.

Crop	Date	Number of plants per can	Number of observations	Dry weight of stem, leaves, and grain, grams	Dry weight of roots, grams	Weight of roots in comparison to tops, per cent
Corn, Kansas sunflower.	1923	1	4	810.5	66.5	8.2
Kafir, Blackhull.....	1924	1	3	385.4	19.8	5.1
Oats, Kanota.....	1925	6	5	236.3	17.9	7.6
Wheat, Kanred.....	1926	6	5	358.5	12.9	3.5
Alfalfa, common (2 years old).....	1926	3	3	242.0 ¹	36.1	15.0

¹ Total for three cuttings during the season.

If the number of corn plants per acre is taken as 8,000, the dry matter left in the soil by the roots would approximate 1,125 lb. per acre. This together with the weight of the crowns from which the roots originate would make approximately $\frac{3}{4}$ ton of dry matter left in the soil.

Questions

85. Enumerate the factors that may influence the weight, number, and extent of roots. What is a root system?

86. How does moisture influence the direction of roots? What are the maximum, minimum, and optimum differences in the moisture content to which roots will respond?

87. How does the moisture content of the soil affect the relative weight of roots and tops? Give examples.

88. In the case of young corn plants how do the relative areas of roots and leaves vary with the water content of the soil? Why are plants which have been growing in a relatively wet soil poorly fitted to endure a drought?

89. Describe the methods that have been used to determine the influence of chemicals on the direction of roots.

90. State the general facts that have been obtained in regard to the response in direction of roots to various compounds.

91. Why may roots respond negatively in direction to a chemical in one concentration and positively to the same chemical in another concentration?

92. How do nutrients influence the number of roots? By what methods has this been observed?

93. How do nutrients influence the relative weight of roots and top? Why does an abundant supply of nitrogen increase the weight of tops as compared to the roots? Why is the relative weight of tops as compared to the weight of roots greater in the shade than in sunlight?

94. How is the aeration of the soil beneficial to plants in an indirect and in a direct way? What special methods are used to aerate soils?

95. What is straight head of rice? Cause? How controlled?

96. What rôle do algae and other water plants play in the aeration of water-logged soils? Give some specific examples.

97. How do plants vary in regard to their need of oxygen in the soil? How does the lack of oxygen affect the roots? What is the first visible effect on the tops of a lack of oxygen in the soil?

98. It has been observed that the rate of transpiration and the intensity of respiration of the shoots have been increased by the aeration of the soil around the roots. What is the probable cause of this?

99. How does the minimum oxygen supply in the soil vary with the temperature? Give examples.

100. How has the oxygen-supplying power of the soil been determined? How is the supplying power expressed?

101. Enumerate the factors that may influence the oxygen-supplying power of the soil. How does the oxygen supply affect the branching of roots? Cite examples.

102. State the direct and indirect evidence in regard to the movement of roots toward an oxygen supply.

103. How does the response of roots to unequal temperatures on their two sides compare for different temperatures? For different plants? How are changes in permeability apparently associated with these responses?

104. What influence does the physical texture of the soil have on root development? Give examples.

105. Make some statements in regard to the total number and combined length of roots.

106. For what reasons have the root systems of plants in the field been studied? In what regions of the world have studies in this regard been made? Why?

107. State a general law in regard to the depth of root penetration. What is the working depth of roots?

108. State some facts concerning the climate and vegetation of the true prairie, the mixed prairie, and the short-grass plains of the general region south and west of the Missouri River and east of the Rocky Mountains.

109. How does the maximum depth of root penetration compare for these regions? The working depth?

110. What factors influence the lateral extent of roots? Illustrate by examples.

111. Make a general summary of the observations that have been made on the vertical and lateral extent of roots of the various agricultural plants.

112. To what depths do crop plants absorb water and solutes from the soil? By what means has this been observed?

113. What portion of a root is concerned in absorption? What are root hairs? Where do they occur? How long do they live?

114. Of what advantage are root hairs to plants? What is their length? What part of the root hair increases in length? How may this be shown?

115. How does the elongation of root hairs increase with time? With temperature? To what is this temperature effect probably due?

116. How does the growth of root hairs vary with different concentrations of different solutions? What is the H-ion range for the production of root hairs?

117. How do high temperatures affect the number of root hairs? How does the moisture content affect root hair production? Give examples.

118. What effect does bog water have on the development of root hairs? How may this toxic action be overcome? What other substances are detrimental to root-hair growths?

119. Of what is the cell wall of a root hair composed? Of what advantage is this in absorption? How does the composition of the root-hair cell wall seem to vary with the surrounding medium? How does the outer cell wall of the epidermis of a root differ in composition from that of the outer cell wall of the epidermis of a young stem?

120. What acids are excreted by roots? When? Why? By what methods have these facts been observed?

121. What is the origin of the CO_2 excreted by the roots? What portion of the root is concerned in this excretion? Why?

122. How does the amount of CO_2 excreted by the roots vary for different plants? For the same plants during the growing season? Why?

123. Discuss the experimental evidence in regard to the solvent action of the CO_2 excreted by the roots upon the minerals of the soil.

124. What evidence is there that roots excrete oxidizing enzymes? How has this been determined? What part of the root is concerned? How does this oxidizing power vary for different plants?

125. What evidence is there that roots have the power of reduction? Of what value to the plant is the oxidizing and reducing powers of the roots? Do roots excrete digestive enzymes?

126. Name three or four cases in which one plant has a beneficial influence upon the plant with which it is growing. What might be the cause of this?

127. Name 10 plants that exert a detrimental influence upon the plants with which they are growing or upon those which follow them. To what extent may this deleterious influence affect the growth of the plant? What evidence is there that different individual plants of the same species have a deleterious effect on each other?

128. To what three general factors has the detrimental influence of one plant on another been attributed?

129. Discuss the experimental evidence which tends to show that the detrimental influence of one crop upon those which follow is not due principally to the differences in the amount of nutrients removed by this preceding crop.

130. Enumerate 20 organic compounds that have been isolated from the soil. What is the origin of these compounds?

131. Name the general factors that will influence the type of decomposition products produced in the soil.

132. What agricultural practices have their effect upon the manner of the decomposition of plant material in the soil? Why?

133. Why do the decomposition products of different plants differ under the same conditions?

134. How do the numerous organic compounds of the soil affect the growth of plants? How has this been shown?

135. How may aeration of the soil reduce the toxicity of certain of the organic compounds? How has this been shown?

136. What effect does the application of commercial fertilizers have upon the toxicity of certain organic compounds of the soil? Why?

137. Discuss the experimental work that has been published in regard to the cause of the detrimental influence of the sorghum plants upon the plants which follow.

138. Discuss the data which have been presented to show that the injurious influence of one plant on another might be due to root excretions.

139. How does the weight of roots of some of the crop plants compare with the weight of the tops?

Bibliography

- ABERSON, J. H., 1910: Ein Beitrag zur Kenntnis der Natur der Wurzelabscheidungen, *Jahrb. f. wiss. Bot.*, **47**: 41-56.
- ADDOMS, R. M., 1923: The effect of the hydrogen ion on the protoplasm of the root hairs of wheat, *Amer. Jour. Bot.*, **10**: 211-220.
- ALLISON, R. V., and J. W. SHIVE, 1923: Studies on the relation of aeration and continuous renewal of nutrient solution on the growth of soybeans in artificial culture, *Amer. Jour. Bot.*, **10**: 554-567.
- ARKER, J., 1901: Die Beeinflussung des Wachstums der Wurzeln durch das umgebende Medium, *Bot. Centrbl.*, **87**: 433-434.
- ARNY, A. C. and I. J. JOHNSON, 1928: The roots of flax plants, *Jour. Amer. Soc. Agron.*, **20**: 373-381.
- , STOA, T. E., C. MCKEE, and A. C. DILLMAN, 1929: Flax cropping in mixture with wheat, oats and barley, *U. S. Dept. Agr. Tech., Bull.* 133.
- BARAKOV, P., 1910: The carbon dioxide content of soils during different stages of growth of plants, *Zhur. Opuitn. Agron. (Russ. Jour. Expt. Landw.)*, **11**: 321-343 (Russian); *Expt. Sta. Rec.*, **23**: 523 (1911).
- BARDELL, E. M., 1915: Production of root hairs in water, *Univ. Wash. Pub. Bot.*, **1**: 1-9.
- BECKWITH, M. H., 1885: Report of the assistant horticulturist, *N. Y. Expt. Sta. Rept.* 261-267.
- BENNETT, MARY E., 1904: Are roots aerotropic? *Bot. Gaz.*, **37**: 241-259.
- BERGMAN, H. F., 1920: The relation of aeration to the growth and activity of roots and its influence on the ecesis of plants in swamps, *Ann. Bot.*, **34**: 13-33.
- BIZZELL, J. A., and T. L. LYON, 1918: The effect of certain factors on the carbon dioxide content of soil air, *Jour. Amer. Soc. Agron.*, **10**: 97-113.
- BOROWSKI, R., 1919: Beitrag zur Kenntnis des Oxydationsvermögens der Wurzeln der höheren Pflanzen, *Landw. Versuchs-Stat.*, **94**: 265-284.
- BREAZEALE, J. F., 1906: Effect of certain solids upon the growth of seedlings in water cultures, *Bot. Gaz.*, **41**: 54-63.
- , 1924: The injurious after effects of sorghum, *Jour. Amer. Soc. Agron.*, **16**: 689-701.
- CANNON, W. A., 1911: Root habits of desert plants, *Carnegie Inst. Wash. Pub.* 131.
- , 1912: Physical relations of roots to soil factors, *Carnegie Inst. Wash. Yearbook* **11**: 61-62.
- , 1913: Botanical features of the Algerian Sahara, *Carnegie Inst. Wash. Pub.* 178.
- , 1915: On the relation of root growth and development to the temperature and aeration of the soil, *Amer. Jour. Bot.*, **2**: 211-224.
- , 1916: On the relation between the rate of root growth and the oxygen of the soil, *Carnegie Inst. Wash. Yearbook*, **15**: 74-75.

- CANNON, W. A., 1916: Distribution of the cacti with especial reference to the rôle played by the root response to soil temperature and soil moisture, *Amer. Nat.*, **60**: 435-442.
- , 1917: Root growth of *Prosopis velutina* and *Opuntia versicolor* under conditions of a small oxygen supply in the soil, *Carnegie Inst. Wash. Yearbook*, **16**: 82-83.
- and E. E. FREE, 1917: The ecological significance of soil aeration, *Science*, n. s., **45**: 178-180.
- , 1918: Root growth in desert plants and the oxygen supply of the soil, *Carnegie Inst. Wash. Yearbook*, **17**: 81-83.
- , 1923: The influence of the temperature of the soil on the relation of roots to oxygen, *Science*, n. s., **58**: 331-332.
- , 1924: A note on the relation of root growth in the soil to the oxygen supply: The growth ratio, *Ecology*, **5**: 319-322.
- , 1925: On the upper critical concentration of oxygen in root growth, *Science*, n. s., **61**: 118-120.
- , 1925: Physiological features of roots with especial reference to the relation of roots to the aeration of the soil, *Carnegie Inst. Wash. Pub.* 368.
- CARLSON, F. A., 1925: The effect of soil structure on the character of alfalfa root systems, *Jour. Amer. Soc. Agron.*, **17**: 336-345.
- CLARK, W. S., 1874: Observations upon the phenomena of plant life, 22d *Ann. Rept. Mass. State Board Agr.*, 204-312.
- CLEMENTS, F. E., 1920: Plant Indicators, *Carnegie Inst. Wash. Pub.* 290.
- , 1921: Aeration and air content. The role of oxygen in root activity, *Carnegie Inst. Wash. Pub.* 315.
- COLLINGS, G. H., and J. D. WARNER, 1927: Root development of cotton on Cecil sandy loam during 1926, *Jour. Amer. Soc. Agron.*, **19**: 839-842.
- COLLISON, R. C., 1924: The presence of certain organic compounds in plants and their relation to the growth of other plants, *Jour. Amer. Soc. Agron.*, **17**: 58-68.
- CONRAD, J. P., 1927: Some causes of the injurious after effects of sorghums and suggested remedies, *Jour. Amer. Soc. Agron.*, **19**: 1091-1111.
- , and F. J. VEIHMEYER, 1929: Root development and soil moisture, *Hilgardia*, **4**: 113-134.
- COOK, M. T., 1921: Wilting caused by walnut trees, *Phytopath.*, **11**: 346.
- COTTRELL, H. M., 1902: Growing alfalfa in Kansas, *Kans. State Expt. Sta. Bull.* **114**: 61-62.
- CRIST, J. W., and J. E. WEAVER, 1924: Absorption of nutrients from the subsoil in relation to crop yield, *Bot. Gaz.*, **77**: 121-149.
- and G. J. SROUT, 1929: Relation between top and root size in herbaceous plants, *Plant Physiol.*, **4**: 63-85.
- CZAPEK, F., 1896: Zur Lehre von den Wurzelauausscheidungen, *Jahrb. f. wiss. Bot.* **29**: 321-390.
- DANDENO, J. B., 1908, 1909: Mutual interaction of plant roots, *Rept. Mich. Acad. Sci.*, **10**: 32-36; **11**: 24-25.
- DAVIS, E. F., 1928: The toxic principle of *Juglans nigra* as identified with synthetic juglone, and its toxic effects on tomato and alfalfa plants, *Abs. Amer. Jour. Bot.*, **15**: 620.
- DE CANDOLLE, A. P., 1832: Physiologie vegetale, **1**: 248-251; **3**: 1474-1475, 1493-1520, Paris.
- DULEY, F. L., 1929: The effect of alfalfa on soil moisture, *Jour. Amer. Soc. Agron.*, **21**: 224-231.
- , 1929: Unpublished data, *Kans. Agr. Expt. Sta.*
- DUSTMAN, R. B., 1925: Inherent factors related to absorption of mineral elements by plants, *Bot. Gaz.*, **79**: 233-264.

- ECKERSON, SOPHIA, 1914: Thermotropism of roots, *Bot. Gaz.*, **58**: 254-263.
- EWART, A. J., 1894: Oxtropic irritability of roots, *Trans. Liverpool Biol. Soc.*, **8**: 238; **10**: 190.
- FARR, C. H., 1925: Root-hair elongation in Knop's solution and in tap water, *Amer. Jour. Bot.*, **12**: 372-383.
- , 1925: The formation of root hairs in water, *Proc. Iowa Acad. Sci.* **32**: 157-165.
- , 1927: Studies on the growth of root hairs in solutions. I, The problem, previous work, and procedure, *Amer. Jour. Bot.*, **14**: 446-457.
- , 1927: Studies on the growth of root hairs in solutions. II, The effects of the concentration of calcium nitrate, *Amer. Jour. Bot.*, **14**: 497-515.
- , 1927: Studies on the growth of root hairs in solutions. III, The effect of concentrations of CaCl_2 and $\text{Ca}(\text{OH})_2$, *Amer. Jour. Bot.*, **14**: 553-565.
- , 1928: Studies on the growth of root hairs in solutions. IV, The P_{H} -molar rate relations for collards in calcium chloride, *Amer. Jour. Bot.*, **15**: 6-32
- , 1928: Studies on the growth of root hairs in solutions. V, Root hair elongation as an index of root development, *Amer. Jour. Bot.*, **15**: 103-114.
- , 1928: Studies on the growth of root hairs in solutions. VI, Structural responses to toxic P_{H} and molar concentrations of calcium chloride, *Amer. Jour. Bot.*, **15**: 171-179.
- , 1928: Studies on the growth of root hairs in solutions. VII, Further investigations on collards in calcium hydroxide, *Bull. Torrey Bot. Club*, **55**: 223-247.
- , 1928: Studies on the growth of root hairs in solutions. VIII, Structural and intracellular features of collards in calcium nitrate, *Bull. Torrey Bot. Club*, **55**: 529-553.
- FLETCHER, F., 1912: Toxic excreta of plants, *Jour. Agr. Sci.*, **4**: 245-247.
- FRANK, B., 1893: Die Assimilation des freien Stickstoffs durch die Pflanzenwelt, *Bot. Zeitung*, **51**: 139-156.
- FRED, E. B., and A. R. C. HAAS, 1919: The etching of marble by roots in the presence and absence of bacteria, *Jour. Gen. Physiol.*, **1**: 631-639.
- FREE, E. E., and B. E. LIVINGSTON, 1917: The effect of deficient soil oxygen on the roots of higher plants, *Johns Hopkins Univ. Circ.*, n. s., **3**: 182-185.
- GARNER, W. W., W. M. LUNN and D. E. BROWN, 1925: Effects of crops on the yields of succeeding crops in the rotation with special reference to tobacco, *Jour. Agr. Res.*, **30**: 1095-1133.
- GEORGESON, C. C., and J. E. PAYNE 1897: Investigations of the root development of some forage plants, *Kans. Expt. Sta. Bul.* **75**: 212-222.
- GIBSON, R. G. H., 1912: The extent of the root system of *Cucumis sativus*, *Ann. Bot.*, **26**: 951-952.
- GOFF, E. S., 1883-1888: Report of the horticulturist, N. Y. State Exp. Agr. Sta. *2d Ann. Rept.* **219**; *3d Ann. Rept.*, 305-315 (1884); *5th Ann. Rept.* 159-168 (1886); *6th Ann. Rept.* 90-96 (1887); *7th Ann. Rept.* 171-178 (1888).
- GURSKY, A. V., 1928-1929: The root systems of *Fraxinus excelsior*, *Fraxinus Pennsylvanica* and *Acer Negundo* on the black soils of Kuban, *Bull. App. Genetics and Plant Breeding*, **21**: 145-181.
- HAAS, A. R. C., 1916: The excretion of acids by roots, *Science*, n. s., **44**: 685.
- , 1917: The excretion of acids by roots, *Proc. Nat. Acad. Sci.*, **2**: 561-566.
- HABERLANDT, G., 1914: "Physiological Plant Anatomy," Eng. transl., p. 222, Macmillan & Co., Ltd., London.
- HALL, A. D., 1906: The solvent action of roots upon the soil particles, *Sci. Prog. Twentieth Cent.*, **1**: 51-57.
- , W. E. BRENTCHLEY, and L. M. UNDERWOOD, 1914: The soil solution and the mineral constituents of the soil, *Jour. Agr. Sci.*, **6**: 278-301.

- HARRIS, F. S., 1914: The effect of soil moisture, plant food and age on the ratio of tops to roots in plants, *Jour. Amer. Soc. Agron.*, **6**: 65-75.
- HARRISON, W. H., and P. A. SUBRAMANIA AIYER, 1913: The gases of swamp rice soils; their composition and their relation to the crop, *Mem. Dept. Agr. in India, Chem. Ser.*, **3**: 65-106.
- HARTWELL, B. L., and S. C. DAMON, 1918: The influence of crop plants on those which follow, I, *R. I. Agr. Expt. Sta. Bull.* 175.
- , F. R. PEMBER, and G. E. MERKLE, 1919: The influence of crop plants on those which follow, II, *R. I. Agr. Expt. Sta. Bull.* 176.
- , J. B. SMITH, and S. C. DAMON, 1927: The influence of crop plants on those which follow, III, *R. I. Agr. Expt. Sta. Bull.* 210.
- HÄVELER, W., 1892: Ueber die Verwerthung des Humus bei der Ernährung der chlorophyllführenden Pflanzen, *Jahrb. wiss. Bot.*, **24**: 283-316.
- HAWKINS, R. S., 1925: The deleterious effect of sorghum on the soil and on the succeeding crops, *Jour. Amer. Soc. Agron.*, **17**: 91-92.
- HAYS, W. M., 1888: Roots of clovers, *5th Bien. Rept. Bd. Regents, Univ. Minn., Suppl. I, Dept. Agr. Expt. Sta.*, 188-198.
- , 1894: The roots of crops, *N. Dak. Bull.* **10**: 47-50.
- HEADDEN, W. P., 1896: Alfalfa, *Colo. Expt. Sta. Bull.* **35**: 47-59.
- HEDRICK, U. P., 1905: The relationship of plants in the orchard, *Proc. West N. Y. Hort. Soc.*, 50th ann. meet., 17-28.
- HELLRIEGEL, H., 1883: Wurzel und Bodenvolumen, *Beiträge zu den naturwiss. Grundlagen des Ackerbaus*, 119-280.
- HESSE, H., 1904: Beiträge zur Morphologie und Biologie der Wurzelhaare, *Inaug. Diss.*, Jena.
- HOLE, R. S., 1918: Recent investigations on soil aeration, *Indian Forester*, **1918**: 202.
- HOOKE, H. D., 1914: Thermotropism in roots, *Plant World*, **17**: 135-153.
- , 1915: Hydrotropism in roots of *Lupinus albus*, *Ann. Bot.*, **29**: 265-285.
- HOWARD, A. and G. L. C. HOWARD, 1915: Soil ventilation, *Agr. Res. Inst. Pusa Bull.* **52**: 1-35.
- , 1916: Soil aeration in agriculture, *Agr. Res. Inst. Pusa Bull.* **61**: 1-22.
- and G. L. C. HOWARD, 1917: The economic significance of the root development of agricultural crops, *Agr. Jour. India, Special Indian Sci. Congo No.*
- , 1918: Recent investigations on soil aeration, *Indian Forester*, **1918**: 187.
- HOWE, C. G., 1921: Pectic materials in root hairs, *Bot. Gaz.*, **72**: 313-320.
- HUNTER, C., 1912: Some observations on the effect of soil aeration on plant growth, *Proc. Phil. Soc. Univ. Durham*, **4**: 183.
- HUTCHINS, L. M., and B. E. LIVINGSTON, 1923: Oxygen-supplying power of the soil as indicated by color changes in alkaline pyrogallol solution, *Jour. Agr. Res.*, **25**: 133-140.
- , 1926: Studies on the oxygen-supplying power of the soil together with quantitative observations on the oxygen supplying power requisite for seed germination, *Plant Physiol.*, **1**: 95-150.
- JEAN, F. C., and J. E. WEAVER, 1924: Root behavior and crop yield under irrigation, *Carnegie Inst. Wash. Pub.* 357.
- JEFFS, R. E., 1922: The grand period of growth of root hairs, *Okla. Acad. Sci. Proc. (Okla. Univ.)* **2**: 53-56.
- , 1925: The elongation of root hairs as affected by light and temperature, *Amer. Jour. Bot.*, **12**: 577-606.
- JONES, L. R., and W. J. MORSE, 1902-1903: The shrubby cinquefoil as a weed, *16th Ann. Rept. Vt. Agr. Expt. Sta.*, 188-190.
- KIESSELBACH, T. A., 1910: Transpiration experiments with the corn plant, *Nebr. Expt. Sta. 24th Ann. Rept.*, 125-139.

- KIESSELBACH, T. A., J. C. RUSSEL, and A. ANDERSON, 1929: The significance of subsoil moisture in alfalfa production, *Jour. Amer. Soc. Agron.*, **21**: 241-268.
- KING, F. H., 1892-1893: Natural distribution of roots in field soils, *Wis. Agr. Expt. Sta. Rept.* 112-121; 160-167 (1893).
- KLERCKER, JOHN A., 1891: Über calorotropische Erscheinungen bei einigen Keimwurzeln, *Oefvers. Vetensk. Akad. Förhandl. Stockholm*, **48**: 765-790.
- KNIGHT, R. C., 1924: The response of plants in soil and in water culture to aeration of the roots, *Ann. Bot.*, **38**: 305-325.
- KNUDSON, L., and R. S. SMITH, 1919: Secretion of amylase by plant roots, *Bot. Gaz.*, **68**: 460-466.
- , 1920: The secretion of invertase by plant roots, *Amer. Jour. Bot.*, **7**: 371-379.
- KOSSOWITZ, P., 1904: The quantitative determination of carbon dioxide produced by the roots of plants during the period of their development (Russian), *Zhur. Opvutn. Agron.*, **5**: 482-493 (quoted by Turpin, 1920).
- KRASSOVSKY, IRENE, 1929: The root system of different varieties of flax, *Bull. Applied Bot. and Plant Breeding*, **22**: 43-100.
- KUNZE, G., 1906: Ueber Säureausscheidung bei Wurzeln und Pilzhyphen und ihre Bedeutung, *Jahrb. f. wiss. Bot.*, **42**: 357-393.
- LAU, E., 1906: Beiträge zur Kenntnis der Zusammensetzung der in Ackerboden befindlichen Luft, *Inaug. Diss.*, Rostock.
- LEE, H. A., 1926: The distribution of the roots of sugar cane in the soil in the Hawaiian Islands, *Plant Physiol.*, **1**: 363-378.
- LIEBIG, J., 1858: Ueber einige Eigenschaften der Ackerkrume, *Ann. Chem. Pharm.*, **105**: 109-144.
- LILIENFELD, M., 1905: Ueber den Chemotropismus der Wurzel, *Ber. d. d. bot. Ges.* **23**: 91-98.
- LIVINGSTON, B. E., J. C. BRITTON, and F. R. REID, 1905: Studies on the properties of an unproductive soil, *U. S. Dept. Agr. Bur. Soils Bull.* **28**.
- , C. A. JENSEN, J. F. BREAZEALE, F. R. PEMBER, and J. J. SKINNER, 1907: Further studies on the properties of unproductive soils, *U. S. Dept. Agr. Bur. Soils Bull.* 36.
- , 1909: An advance in root physiology, *Plant World*, **12**: 127-130.
- , 1923: Some physiological aspects of soil toxicity, *Jour. Amer. Soc. Agron.*, **15**: 313-323.
- LYON, T. L., and J. K. WILSON, 1921: Liberation of organic matter by roots of growing plants, *Cornell Agr. Expt. Sta. Mem.* 40.
- MARTIN, T. L., 1927: Decomposition studies of alfalfa and sweet clover roots and straw, *Soil Sci.*, **24**: 309-316.
- MASSEY, A. B., 1925: Antagonism of the walnuts (*Juglans nigra* L. and *J. cinerea* L.) in certain plant associations, *Phytopath.*, **15**: 773-785.
- MCDUGALL, W. B., 1921: Thick-walled root hairs of *Gleditsia* and related genera, *Amer. Jour. Bot.*, **8**: 171-176.
- METZGER, W. H., 1928: The effect of growing plants on solubility of soil nutrients, *Soil Sci.*, **25**: 273-281.
- MILLAR, C. E., 1925: The feeding power of plants in different soil horizons, *Jour. Amer. Soc. Agron.*, **17**: 150-157.
- MILLER, E. C., 1916: Comparative study of the root systems and leaf areas of corn and the sorghums, *Jour. Agr. Res.*, **6**: 311-333.
- , 1916: The root systems of agricultural plants, *Jour. Amer. Soc. Agron.*, **8**: 129-154.
- MILLER, M. F. and F. L. DULEY, 1925: The effect of varying moisture supply upon the development and composition of the maize plant at different periods of growth, *Mo. Agr. Expt. Sta. Tech. Bull.* 76.

- MOLISCH, H., 1885: Ueber die Ablenkung der Wurzeln von ihrer normalen Wachstumsrichtung durch Gase (Aerotropismus), *Sitzungsber. d. k. Akad. d. Wiss. Wien.*, **90**: 111.
- , 1887: Über Wurzelabscheidungen und deren Einwirkung auf organische Substanzen, *Sitzungsber. d. k. Akad. d. Wiss. Wien.*, **96**: 84–109.
- MOLLIARD, M., 1913: Sur la secretion par les racines de substances toxique pour la plante, *Soc. Bot. France Bull.* **60**: 442–446.
- MUKERJI, J. N., 1920: The excretion of toxins from the roots of plants, *Agr. Jour. India*, **15**: 502–507.
- MÜLLER-THURGAU, H., 1894: Einfluss des Stickstoffs auf die Wurzelbildung, *Jahrb. der Versuchs-Stat. in Wädensweil*, **4**: 48–52.
- NELLER, J. R., 1922: The influence of growing plants upon oxidation processes in the soil, *Soil Sci.*, **13**: 139–160.
- NEWCOMBE, F. C., and ANNA RHODES, 1904: Chemotropism of roots, *Bot. Gaz.*, **37**: 23–35.
- NEWTON, J. D., 1924: Measurement of carbon dioxide evolved from the roots of various crop plants, *Sci. Agr.*, **4**: 268–274.
- NOBBE, FRIEDRICH, 1862: Über die feinere Verästelung der Pflanzenwurzeln, *Landw. Versuchs-Stat.*, **4**: 212–224.
- , 1869: Die Pflanzencultur in Wasser, und ihre Bedeutung für die Landwirthschaft, *Landw. Versuchs-Stat.*, **11**: 106–120.
- PARKER, F. W., 1924: Carbon dioxide production of plant roots as a factor in the feeding power of plants, *Soil Sci.*, **17**: 229–249.
- , 1925: The carbon dioxide content of the soil air as a factor in the absorption of inorganic elements by plants, *Soil Sci.* **20**: 39–45.
- PERALTA, F. DE, and R. P. ESTIOKO, 1923: A tentative study of the effect of root excretion of common paddy weeds upon crop production of lowland rice, *Philippine Agr.*, **11**: 205–216.
- PERSECKE, K. 1877: Über die Formveränderungen der Wurzel in Wasser und Erde, *Diss. Leipzig*.
- PFEIFFER, F., and E. BLANCK, 1912: Die Säureabscheidung der Wurzeln und die Löslichkeit der Bodennährstoffe in kohlenstoffhaltigem Wasser, *Landw. Versuchs-Stat.*, **77**: 217–268.
- PICKERING, S. U., 1903: The effect of grass on apple trees, *Jour. Roy. Agr. Soc. England* **64**: 365–376.
- and DUKE OF BEDFORD, 1914: Effect of one crop upon another, *Jour. Agr. Sci.*, **6**: 136–151.
- , 1917: The effect of one plant on another, *Ann. Bot.*, **31**: 181–187.
- and DUKE OF BEDFORD, 1919: "Science and Fruit Growing," Chap. 28, pp. 291–312.
- POLLE, R., 1910: Über den Einfluss verschiedener hohen Wassergehalts, verschiedener Düngung und Festigkeit des Bodens auf die Wurzelentwicklung des Weizens und der Gerste im ersten Vegetationsstadium, *Jour. f. Landw.*, **58**: 297–345.
- POBODKO, T., 1911: Über den Chemotropismus der Pflanzenwurzeln, *Jahrb. f. wiss. Bot.*, **49**: 307–388.
- , 1912: Vergleichende Untersuchungen über die Tropismen. II, Mitt. Thermo- tropismus der Pflanzewurzeln, *Ber. d. d. bot. Ges.*, **30**: 305–313.
- , 1914: Vergleichende Untersuchungen über die Tropismen. VI, Der relative chemotrope Wirkungswert von Alkali- und Erdalkali-salzen für Keimwurzeln von *Lupinus albus*, *Ber. d. d. bot. Ges.*, **32**: 25–35.
- , 1914: Vergleichende Untersuchungen über die Tropismen. VII, Der relative chemotrope Wirkungswert von Schwermetallsalzen für Keimwurzeln von *Lupinus albus*, *Ber. d. d. bot. Ges.*, **32**: 271–275.

- PORODKO, T., 1914: Vergleichende Untersuchungen über die Tropismen. VIII, Bedingungen der chemotropen Krümmungsreaktion bei den Pflanzenwurzeln, *Ber. d. d. bot. Ges.*, **32**: 275-282.
- PRIANISCHNIKOV, D., 1914: Sur la question des excrétiens nuisibles des racines, *Rev. Gen. Bot.*, **25**: 563-582.
- RACIBORSKI, M. M., 1905: Oxydierende und reduzierende Eigenschaften der lebenden Zelle, *Bull. Acad. Sci. Cracovie*, **1905**: 338, 668, 693.
- RIDGWAY, C. S., 1913: The occurrence of callose in root hairs, *Plant World*, **16**: 116-122.
- RIGG, G. B., 1913: The effect of some Puget Sound bog waters on the root hairs of *Tradescantia*, *Bot. Gaz.*, **55**: 314-326.
- ROBERTS, E. A., 1916: The epidermal cells of roots, *Bot. Gaz.*, **62**: 488-506.
- ROTMISTROV, V., 1909: "Root Systems of Cultivated Plants of One Year's Growth," 57 pp., 22 pl., Odessa.
- RUSSELL, E. J., 1917: "Soil Conditions and Plant Growth," 190 pp., Longmans, Green and Co.
- and A. APPELYARD, 1917: The influence of soil conditions on the decomposition of organic matter in the soil, *Jour. Agr. Sci.*, **8**: 385-417.
- SACHS, J., 1860: Bericht über die physiologische Thätigkeit an der Versuchs-station in Tharandt, II. Wurzel-Studien, *Landw. Versuchs-Stat.*, **2**: 1-31.
- SCHNEIDERHAN, F. J., 1926: Apple disease studies in northern Virginia, *Va. Polytech. Inst. Va. Agr. Expt. Sta. Bull.* **245**: 29-30.
- SCHREINER, O., and H. S. REED, 1907: Some factors influencing soil fertility, *U. S. Dept. Agr. Bur. Soils Bull.* 40.
- and ———, and J. J. SKINNER, 1907: Certain organic constituents of soils in relation to soil fertility, *U. S. Dept. Agr. Bur. Soils Bull.* 47.
- and ———, 1907: The production of deleterious excretions by roots, *Bull. Torrey Bot. Club*, **34**: 279-303.
- and ———, 1908: The toxic action of certain organic plant constituents, *Bot. Gaz.*, **45**: 73-102.
- and ———, 1909: The role of oxidation in soil fertility, *U. S. Dept. Agr. Bur. Soils Bull.* 56.
- and ———, 1909: Studies on the oxidizing power of roots, *Bot. Gaz.*, **47**: 355-388.
- and E. C. SHOREY, 1909: The isolation of harmful organic substances from soils, *U. S. Dept. Agr. Bur. Soils Bull.* 53.
- and ———, 1910: Chemical nature of soil organic matter, *U. S. Dept. Agr. Bur. Soils Bull.* 74.
- and J. J. SKINNER, 1910: Some effects of a harmful organic soil constituent, *U. S. Dept. Agr. Bur. Soils Bull.* 70.
- and M. X. SULLIVAN, 1911: Reduction by roots, *Bot. Gaz.*, **51**: 121-130.
- and ———, 1911: Concurrent oxidation and reduction by roots, *Bot. Gaz.*, **51**: 273-285.
- and J. J. SKINNER, 1912: The toxic action of organic compounds as modified by fertilizer salts, *Bot. Gaz.*, **54**: 31-48.
- , 1923. Toxic organic soil constituents and the influence of oxidation, *Jour. Amer. Soc. Agron.*, **15**: 270-277.
- SCHULZE, B., 1906: Studien über die Bewurzelung unserer Kulturpflanzen, *Festschrift, 50 Jubiläum Agr. Chem. Vers. und Kontroll Stat.*, Breslau, 67-95.
- SCHWARZ, FR., 1883: Die Wurzelhaare der Pflanzen, *Untersuch Bot. Inst. Tübingen*, **1**: 135-188.
- SEELHORST, C. VON, 1902: Beobachtungen über die Zahl und den Tiefgang der Wurzeln verschiedener Pflanzen bei verschiedener Düngung des Bodens, *Jour. f. Landw.*, **50**: 91-104.

- SEWELL, M. C., 1923: Effect of *Andropogon sorghum* on succeeding crops of *Triticum sativum vulgare*, *Bot. Gaz.*, **75**: 1-26.
- SHEPPERD, J. H., 1905: Root systems of field crops, *N. Dak. Expt. Sta. Bull.* **64**: 529-535.
- SKINNER, J. J., 1913: Illustration of the effect of previous vegetation on a following crop: Cabbage after sesame, *Plant World*, **16**: 342-346.
- SNOW, L. M., 1904: The effects of external agents on the production of root hairs, *Bot. Gaz.*, **37**: 143-145.
- , 1905: Development of root hairs, *Bot. Gaz.*, **40**: 12-48.
- SPALDING, V. M., 1904: Biological relations of certain desert shrubs. I, The Creosote bush (*Covillea tridentata*) in its relation to water supply, *Bot. Gaz.*, **38**: 122-138.
- STEWART, G. R., and J. C. MARTIN, 1921: Effect of various crops upon the water extract of a typical silty clay loam soil, *Jour. Agr. Res.*, **20**: 663-668.
- STIELER, G., 1903: Ueber das Verhalten der Wurzelhärcen gegen Lösungen, *Diss. Kiel* (abs. *Bot. Centrbl.*, **96**: 541 (1904)).
- STOCKLASA, J., and A. ERNEST, 1905: Ueber den Ursprung, die Menge, und die Bedeutung der Kohlendioxyds im Boden, *Centrbl. Bakt.*, **2**: 14: 723-736.
- and ———, 1909: Beiträge zur Lösung der Frage der chemischen Natur des Wurzelsekretes, *Jahrb. f. wiss. Bot.*, **46**: 55-102.
- TEN EYCK, A. M., 1899: A study of the root systems of wheat, oats, flax, corn, potatoes, and sugar beets and of the soil in which they grew, *N. Dak. Agr. Exp. Sta. Bull.* **36**: 333-362.
- , 1900: A study of the root systems of cultivated plants grown as farm crops, *N. Dak. Agr. Expt. Sta. Bull.* **43**: 535-550.
- , 1904: The roots of plants, *Kans. Agr. Expt. Sta. Bull.* **127**: 199-252.
- THATCHER, R. W., 1923: The effect of one crop on another, *Jour. Amer. Soc. Agron.*, **15**: 331-338.
- TISDALE, W. H., and J. M. JENKINS, 1921: Straighthead of rice and its control, *U. S. Dept. Agr. Farmers' Bull.* 1212.
- TREITEL, O., 1924: Thermotropismus bei Wurzeln, *Bot. Archiv.*, **7**: 375-388.
- TUCKER, M., and C. VON SEELHORST, 1898: Der Einfluss, welchen der Wassergehalt und der Reichtum des Bodens auf die Ausbildung der Wurzeln und der oberirdischen Organe der Haferpflanze ausüben, *Jour. f. Landw.*, **46**: 52-63.
- TURNER, T. W., 1922: Studies of the mechanism of the physiological effects of certain mineral salts in altering the ratio of top growth to root growth in seed plants, *Amer. Jour. Bot.*, **9**: 415-446.
- TURPIN, H. W., 1920: The carbon dioxide of the soil air, *N. Y. Agr. Expt. Sta. Mem.* 32.
- WAKSMAN, S. A., and F. G. TENNEY, 1928: Composition of natural organic materials and their decomposition in the soil. III, The influence of nature of plant upon the rapidity of its decomposition, *Soil Sci.*, **26**: 155-171.
- WEAVER, J. E., 1915: A study of the root systems of prairie plants of southeastern Washington I, *Plant World*, **18**: 227-248.
- , 1919: The ecological relations of roots, *Carnegie Inst. Wash. Pub.* 286.
- , 1920: Root development in the grassland formation, *Carnegie Inst. Wash. Pub.* 292.
- and J. W. CRIST, 1922: Relation of hardpan to root penetration in the Great Plains, *Ecology*, **3**: 237-250.
- , F. C. JEAN, and J. W. CRIST, 1922: Development and activities of roots of crop plants, *Carnegie Inst. Wash. Pub.* 316.
- , J. KRAMER, and M. READ, 1924: Development of root and shoot of winter wheat under field environment, *Ecology*, **5**: 26-50.
- , 1925: Investigations on the root habits of plants, *Amer. Jour. Bot.*, **12**: 502-510.

- WEAVER, J. E., 1926: "Root Development of Field Crops," 290 pp., McGraw-Hill Book Company, Inc., New York.
- , and W. E. BRUNER, 1927: "Root Development of Vegetable Crops, 351 pp., McGraw-Hill Book Company, Inc., New York.
- WHITNEY, MILTON, and F. K. CAMERON, 1904: Investigations in soil fertility, *U. S. Dept. Agr. Bur. Soils Bull.* 23.
- WHITAKER, EDITH S., 1923: Root hairs and secondary thickening in the *Compositae*, *Bot. Gaz.*, **76**: 30-60.
- WILSON, B. D., and J. K. WILSON, 1928: Relation of sorghum roots to certain biological processes, *Jour. Amer. Soc. Agron.*, **20**: 747-754.
- WORTMANN, JULIUS, 1885: Über den Thermotropismus der Wurzeln, *Bot. Zeitung*, **43**: 193-200, 209-216, 225-235.
- ZAVITZ, C. A., 1922: Grains grown in combination for grain production, *Jour. Amer. Soc. Agron.*, **14**: 225-228.

CHAPTER IV

THE INTAKE OF WATER BY PLANTS

I. SOURCES OF THE PLANT'S WATER SUPPLY

It is an accepted fact that plants obtain through their roots from the soil the major portion of the water that is necessary for their needs. There is, however, considerable dispute in regard to the ability of plants to absorb water through their stem and leaves from the atmosphere, so it is intended here to review the experimental evidence. Ganong (1894) grew plants in soil in sealed containers and after allowing them to wilt badly placed them under conditions favorable for the absorption of water by their leaves. In one experiment the wilted leaves were covered with moist filter paper, in another they were sprayed with water, in a third case the wilted plants were immersed entirely or partially in water and left for a considerable period of time, while in the fourth experiment they were placed in a saturated atmosphere. In all these experiments the wilted leaves showed no signs of regaining their turgidity. This indicated that the amounts of water absorbed by the leaves were of little significance in the welfare of the plant. Spalding (1906) immersed the cut branches of various species of desert plants in water for three hours and found that some of these parts absorbed no water while in others the amount absorbed ranged from 2 to 6 per cent of their original weight. The stems and leaves that did absorb water, however, lost it all in a few minutes when exposed to the air. The absorption of water by the stem and leaves was shown most strikingly by those plants which showed marked mesophytic tendencies. Spalding also investigated the ability of these plants to obtain moisture from the atmosphere. A review of the data obtained shows that of the 12 species of desert perennials subjected to the experiment, all exhibited some slight capacity for the absorption of water vapor from the atmosphere, but in general the amounts absorbed were inconsiderable in comparison with that given off in corresponding periods in dry air. Spalding considers that as yet there is no evidence to indicate that the small quantities of water absorbed are utilized in the body of the plant, since the promptness with which the water thus absorbed is returned to the air suggests a process purely physical in its nature and of no physiological significance. Spalding states that the most important conclusion to be drawn from his experiments is the patent fact that the roots of desert plants constitute their only reliable active agent in providing a normal water supply no matter

how far some of these plants have departed from the habits of the present-day mesophytes. In Australia all members of the genus *Atriplex* and to a less extent species of *Kochia baosia* and *Rhagodia* absorb an appreciable amount of water from saturated atmospheres (Wood, 1925). The much greater absorption in the species *Atriplex* appears to be correlated with the high salt content of the leaves of these plants, the percentage of salt ranging from 12 to 30 per cent as compared with 2 to 7 per cent for the other leaves in question. Henslow (1908) concluded that the stems and leaves of various horticultural plants immersed in water could absorb some water under these conditions, since the loss by transpiration subsequent to was lower than it was previous to the immersion. His experiments on the absorption of dew by leaves is worthy of note. He used the leaves of 20 varieties of plants which were plucked in the evening between 4 and 5 p.m. and exposed to sunlight until nightfall, after which they were exposed to a heavy dew during the night. The specimens were dried with a cloth in the morning before the sunlight had had any effect and weighed. With but one exception these leaves showed a gain in weight of from 2 to 35 per cent over that of the previous evening. The conditions under which plants grow in the field would seem to eliminate, however, the absorption of any appreciable amount of moisture from the dew deposited on the surface of their leaves. Even when the moisture supply in the soil is extremely low and the plants are wilted badly during the day, the leaves rapidly regain their turgidity during the early evening so that loss of water from guttation frequently occurs during the night. It is thus difficult to conceive how the leaves could absorb any water of consequence through their surface under such conditions. In many semiarid regions where under extreme conditions the absorption of dew might be of some little benefit, the weather conditions are such that dew rarely if ever falls.

Wetzel (1924) found that the absorption of water by the leaves depends upon the permeability of the cuticle and its ability to be wetted. He found that a felt of hairs on the leaves greatly hinders the entrance of water. His experiments conducted in the open on rosette plants and plants with a felt of hairs indicate that absorption by aerial organs is without significance in a temperate climate.

{ There seems to be no question that leaves are capable under certain conditions of absorbing moisture from the air, but the amount is so insignificant, compared to that lost by transpiration that it is of little or no physiological importance. } The benefit to a plant of a light shower that does not penetrate to the roots or of a humid atmosphere is to reduce the evaporating power of the air so that the loss of water from the leaves is cut down to a rate that is lower than that of absorption by the roots, and as a result of this the cells of the leaves and stem become turgid and have the appearance of having absorbed water from the air.

✓ II. WILTING COEFFICIENT

A plant cannot remove all the moisture from the soil in which it grows, so that when a plant permanently wilts there will always be some moisture retained by the soil, regardless of how thoroughly roots may permeate it. A plant is said to be permanently wilted when its leaves have become so flaccid as a result of a deficiency in the soil moisture supply that they will not recover their normal turgidity when placed in an approximately saturated atmosphere without the addition of water to the soil. Briggs and Shantz (1912) first used the term "wilt coefficient" to denote the moisture content of the soil (expressed as percentage of the dry weight) at the time of the permanent wilting of the plants growing therein. These authors also found that the loss of moisture from the soil through the plant does not cease at permanent wilting but goes on to some extent even after the death of the plant—the plant during the drying stage acting simply as a medium for the transference of water from the soil to the air.

A. METHODS OF DETERMINING THE WILTING COEFFICIENT

1. Direct Method. The Observed Wilting Coefficient.—The wilting coefficient is determined directly by growing plants in sealed containers until they are so wilted that they will not revive when placed in a saturated atmosphere. The soil is then sampled and the percentage of moisture on a dry basis determined. The wilting coefficient obtained after this manner is termed the "observed wilting coefficient." The direct method of determining the wilting coefficient has been used, for the most part, for seedling plants in small containers but has not been used successfully for plants at a more advanced vegetative stage. In the case of more mature plants it is almost impossible to obtain a sharp end point for wilting, and in large containers the soil moisture is not evenly depleted throughout the soil mass.

2. Indirect Method. a. The Calculated Wilting Coefficient.—The determination of the wilting point especially with plants growing in the field is beset with many difficulties among which are the direct evaporation from the soil, local variation in soil texture, lack of uniformity in root development, and the lack of conditions to produce wilting. Briggs and Shantz, therefore, upon the assumption that the wilting coefficient is practically the same for a given soil for any plant under any climatic condition, formulated several indirect methods of determining the moisture content of the soil at the wilting point based upon the relationship of the wilting point to the moisture retentiveness of the soil as measured by certain physical methods. By these methods it is not necessary to work with the plants at all to determine the amount of moisture that would remain in the soil when they wilt permanently. By determining in the laboratory certain factors on the moisture retentiveness of a sample

of soil in which the plants are growing the wilting coefficient can be calculated and is then termed the "calculated wilting coefficient." Of the methods thus formulated by Briggs and Shantz, three which have been used to a considerable extent in ecological and agronomic work are here considered.

1. *Relation to the Moisture Equivalent of the Soil.*—The moisture equivalent of the soil is the percentage of water which it can retain in opposition to a centrifugal force one thousand times that of gravity. The ratio of the moisture equivalent to the wilting coefficient was found to be 1.84 ± 0.013 , or, expressed in another way, wilting coefficient = moisture equivalent.

$$\frac{1.84 \pm 0.013}{\dots}$$

2. *Relation to the Hygroscopic Coefficient of the Soil.*—When a dry soil is placed in a saturated atmosphere it will absorb water vapor until a condition of approximate equilibrium is attained. The moisture content of a soil under such conditions is known as the "hygroscopic coefficient" of that soil. This term should not be confused with the term hygroscopic water content of the soil, which is used in some plant physiological tests to signify the water content of "air-dry" soil. The mean ratio of the hygroscopic coefficient to the wilting coefficient was found by experiment to be 0.68 ± 0.012 , or the wilting coefficient = $\frac{\text{hygroscopic coefficient}}{0.68 \pm 0.012}$.

3. *Relation to the Moisture-holding Capacity of the Soil.*—The moisture-holding capacity of a soil is the percentage of water that it can retain in opposition to the force of gravity when free drainage is provided. The experiments of Briggs and Shantz showed that the wilting coefficient = $\frac{\text{moisture-holding capacity} - 21}{2.9 \pm 0.06}$.

b. *The Index of Transpiring Power as an Indicator of Permanent Wilting in Plants.*—It has been observed that the transpiration rate falls suddenly with wilting but rises thereafter to a considerable extent subsequent to a fall once more as desiccation occurs. This initial fall in the transpiration rate represents the increase in incipient drying within the leaves. During this initial decrease in transpiration the water columns in the conducting tissues remain intact. As the drying of the leaves continues, the strain on the columns of water increases so that the breaking point is eventually reached. When the water columns break, the tension is relieved and the transpiration rate is accelerated. When the water of the broken columns has been evaporated, the rate of transpiration will again fall. Bakke (1915) considered that the stage of permanent wilting represents the most intense wilting possible without the rupture of the water columns of the plant. He further considered (1918) that the transpiring power of plants as determined by standardized hygrometric paper gives an accurate knowledge of the internal water

relations of the plant and that the permanent wilting point of the plant corresponds to that point at which the transpiration rate indicates that the water columns of the stem have been ruptured.

B. FACTORS INFLUENCING THE WILTING COEFFICIENT

The amount of water that remains in the soil at the time of permanent wilting will depend upon various factors, the chief of which are (1) the type of soil, (2) the climatic conditions prevailing at the time of wilting, and (3) the kind of plant.

1. Type of Soil.—Sachs (1859) was the first to observe that the type of soil determined the amount of water that remained when the plants wilted permanently. He grew tobacco plants in three different soils—a vegetable mold, a loam, and a sand—and found that they wilted permanently while 12.3, 8.0, and 1.5 per cent of water, respectively, remained in the soil. The most extensive work on the relation of the water remaining in the soil at the time of permanent wilting of the plant and the type of soil has been done by Briggs and Shantz (1912). These investigators determined the wilting coefficient for 20 different types of soil ranging from a coarse sand to a clay loam. The following table has been compiled by selecting a few examples at random from their 1,300 observations:

Plant	Wilting coefficient of				
	Coarse sand	Fine sand	Sandy loam	Loam	Clay loam
Moisture equivalent.	1.55	5.5	12.0	18.9	27.4
Corn, Boone County, white.	1.07	3.1	6.5	9.9	15.5
Sorghum, Dwarf milo.	0.94	3.6	5.9	10.0	14.1
Wheat, Kubanka.	0.88	3.3	6.3	10.3	14.5
Oats, Kherson.	1.07	3.5	5.9	11.1	14.8
Pea, Canada field.	1.02	3.3	6.9	12.4	16.6
Tomato, Golden Queen.	1.11	3.3	6.9	11.7	15.3
Rice, Japan.	0.96	2.7	5.6	10.1	13.0

These data show that the finer the soil particles the greater is the amount of water remaining in the soil when the plant dies from the lack of a moisture supply.

2. The Climatic Conditions.—The extensive observations of Briggs and Shantz (1912) on the wilting coefficient of plants were made for the most part upon plants growing in the greenhouse where the temperature was about 70° F. and where the rate of loss of water from the plants was relatively low. These investigators, however, considered that their observations warranted the conclusion that the wilting coefficient for a

given soil would be a constant regardless of the nature of the climatic conditions prevailing at the time of wilting and, as will be mentioned in a subsequent heading, regardless of the type of plant under consideration.

Subsequent to the work of Briggs and Shantz, numerous investigators have studied the relation of the wilting coefficient to the climatic conditions prevailing at the time of wilting and the relationship of the observed wilting coefficient to the calculated one obtained from the formulae mentioned above. Brown (1912) placed potted plants of *Martynia* (Devil's Claw) in positions having varying degrees of evaporation and observed the moisture left in the soil when these plants wilted from lack of water. The following table gives an example of his results:

Position	Evaporation from atmometer. Rate per hour previous to wilting, cubic centimeters	Soil moisture at wilting, per cent
Open.....	7.2	15.4
Lath shelter.....	4.1	11.3
Room.....	2.8	6.8
Moist chamber.....	0.9	5.2

He showed thus that the rate of evaporation previous to the time of wilting determined the percentage of moisture that the plant cannot extract from the soil. Brown transferred plants which had wilted under a high rate of evaporation to a position where a lower rate of evaporation occurred. After this transfer the plants revived quickly without the addition of water to the soil and removed therefrom a greater quantity

	Hourly rate of evaporation from atmometer, cubic centimeters	Moisture remaining in the soil at the time of wilting, per cent
Plant 1:		
A ¹	4.2	11.3
B ²	0.3	5.9
Plant 2:		
A.....	7.5	17.5
B.....	1.6	6.6
Plant 3:		
A.....	3.2	10.5
B.....	0.9	5.2

¹ A represents the open.

² B represents the moist chamber.

of water. The case of three plants which were placed in the open, where evaporation was relatively high, and allowed to wilt badly after which they were transferred to a moist chamber, where the evaporation was very low, will serve as an illustration of the facts observed (see page 155).

Caldwell (1913) repeated some of the work of Brown and reached the following conclusions concerning the values of the observed and calculated wilting coefficients: When wilting of plants occurs in a partial shelter or in the open with relatively high evaporating rates, the ratio of the observed to the calculated wilting coefficient is always greater than unity. When wilting occurs in a nearly saturated atmosphere, the ratio of the soil moisture content at permanent wilting as found by actual observations to that obtained by calculations from physical constants is practically unity. Caldwell makes the significant statement that "for a series of plants grown in any one soil and wilted under a number of aerial conditions as many different soil moisture contents are obtained as there are sets of conditions." He observed that the moisture remaining in the soil at the time of permanent wilting at the maximum evaporation rates at Tucson, Ariz., varied from 30 to 40 per cent in excess of that taking place when plants were wilted in damp chambers. Shive and Livingston (1914) grew potted plants of corn, common beans, and Spanish pepper under different evaporating conditions and determined the ratio of the actual water content at the time of wilting to the calculated moisture content. The following table shows the result which they obtained with corn 4 weeks of age growing in a soil with a calculated wilting coefficient of 3.80.

Position	Evaporation for 2-hr. period previous to the wilting, cubic centimeters	Actual moisture content of soil at wilting, per cent	Ratio of actual to calculated moisture at wilting
Glass box.....	0.3	4.30	1.13
Lath shelter.....	2.4	5.78	1.52
Cheesecloth shelter.....	3.0	6.04	1.58
Open.....	3.7	6.16	1.68

The great bulk of the experimental evidence thus indicates that the amount of water remaining in a given soil when a plant permanently wilts will depend upon the atmospheric conditions prevailing just previous to the time of wilting. The wilting of a plant is due to the excess of the water loss from the stem and leaves over the amount absorbed by the roots. The rate of water loss from a plant is influenced primarily by the evaporating power of the air. If it is high, the rate of water loss from

the plant is relatively high; and if it is low, the rate of water loss from the plant is relatively low. At the time that the water available to the plant has been depleted nearly to the critical stage, the rate of absorption by the roots becomes low. If the rate of water loss from the plant under such conditions is relatively high, the plant will soon wilt permanently, even though the roots are still absorbing considerable moisture from the soil. If the rate of water loss, however, is slow due to mild atmospheric conditions, the roots can continue for a considerable length of time to absorb water from the soil sufficient to supply the loss from the leaves and as a consequence deplete the moisture in the soil to a point lower than they could if the evaporating rate were high.

3. Kind of Plant.—It has generally been supposed that the various groups of plants differ in their ability to reduce the moisture content of the soil. It has also been assumed that the ability of certain plants to withstand drought is due to their power to obtain water by depleting the soil moisture to a lower point than could other plants which consequently perish from lack of moisture. These suppositions seem to be based, however, on little or no experimental evidence, and it is the intention here to consider the facts that have been observed in this regard. Briggs and Shantz (1912) found in their experiments that the plants with which they worked differ only slightly in their ability to deplete the moisture content of a given soil. If 100 is taken to represent the average wilting coefficient for all the plants considered, their results show that the value for corn would be 103, legumes 101, wheat 99, oats 99, sorghum 98, millet 97, barley 97, grasses 97, and rice 94. According to the figures just quoted, in a soil whose mean wilting coefficient is 10 per cent, a corn plant would wilt with a moisture content of 10.3 per cent, while the sorghums would wilt with a moisture content of 9.8. The advantage to be gained by this difference in depletion of soil moisture is very slight, and Briggs and Shantz state "that if the roots were distributed to a depth of 4 ft. this would correspond to an additional amount of water for the sorghum plants in the four feet of soil equivalent to a rain of $\frac{3}{10}$ in., all of which penetrated to the root zone." They consider that this additional amount of moisture would be of slight benefit to a plant and would scarcely suffice to ameliorate conditions during a drought to any greater extent than a cool, cloudy day. Alway (1913) grew Red Fife and Kubanka wheat, milo, corn, Mexican beans, the desert legumes, *Prosopis velutina*, *Acacia Greggii*, and *Acacia constricta* in water-tight galvanized-iron cylinders. These cylinders were 6 ft. long and 6 in. in diameter and contained known amounts of soil and water. The plants were allowed to grow without the further addition of water until they died. The cylinders were then opened and the moisture content determined at different depths. Alway found that in their ability to exhaust the moisture of the soil before dying, wheat, corn, milo, and Mexican beans showed little difference but that

in their ability to continue alive after first showing injury from drought, they exhibited marked differences. The interval between wilting and death in the case of the beans amounted to only a few days, while in the case of wheat and milo it amounted frequently to several weeks. He found that if no unfavorable conditions occurred before the death of the plants, the moisture content could be reduced by any of them almost to the hygroscopic coefficient. The desert legumes mentioned above remained alive after the water content of the soil had been depleted slightly below the hygroscopic coefficient after the above-mentioned annual crops had died. While this does not mean that these plants can utilize for growth the small amount of this water that they obtain from the soil of so low a moisture content, it does indicate that this portion of water has a very high value for the maintenance of life.

The experimental evidence at hand thus indicates that in the cases observed, one kind of plant cannot deplete the soil moisture in a given soil more significantly than can another before wilting permanently. The experimental work, however, has been done for the most part with seedling plants or with plants in a comparatively early stage of development (Crump 1913) and is open to criticism in that regard. It has been found difficult to determine the wilting point in the case of fully developed plants, since as the water content in the soil becomes low the lower leaves of the plant droop, dry up, and drop off while the upper ones continue to be turgid and function normally. Powers (1922) from observations of plants growing in the field under arid conditions concluded that the wilting point varies more than has commonly been supposed when judged in the light of crop appearance, soil moisture, and the yield of dry matter. It appears to vary more for different crops on a soil which is rather heavy in texture than on a soil of narrow moisture limits. The results so far indicate that the cells of the roots of different plants have practically the same osmotic pull or tractile force on the water of the soil. This is what one would expect when the behavior of the concentration of the cell sap in response to environmental conditions is taken into consideration. It has been stated in Chap. I that the osmotic pull or pressure of the cell sap is practically the same for all plants growing under the same environmental conditions and that the concentration varies with the water supply. While it is generally admitted that the tractile force exerted upon the water of the soil varies little for different plants, there are methods of growth and morphological differences that will enable certain plants to reduce the moisture of the soil more than others before permanent wilting occurs, especially under conditions of high evaporation. The distribution of the root system has a marked influence in this regard. Briggs and Shantz (1912) found that rice, a plant which grows for the most part in a saturated soil, depleted the soil moisture to a lower degree than did plants which grow in the more arid regions. They attributed this

to the fact that the latter plants possessed abundant fine fibrous roots which permeated all parts of the soil. This is no doubt true also in the case of the sorghums as compared to corn. Miller (1916) found that the sorghum plants have almost twice as many fibrous roots as have the corn plants, so that the soil is more thoroughly penetrated by roots and the water in the soil thus has a much shorter distance to move before it enters the roots of the sorghums than it does in the case of the corn where the roots are more sparsely distributed. Under mild atmospheric conditions where evaporation is low, these characteristics would be of little importance, but under conditions of exceedingly high evaporation, as encountered in the field in actual agricultural practice, they become very significant. While Briggs and Shantz found that the sorghum seedlings showed but little more ability to reduce the moisture content of the soil than did corn under the mild conditions of the greenhouse, the fact that the sorghum plants in the field survive under severe climatic conditions while corn wilts and dries up gives indirect evidence that these sorghum plants under these conditions can deplete the moisture content of the soil lower than can corn before permanent wilting occurs. These plants survive not because their individual root hairs exert a greater tractive force on the water in the soil than does corn but simply because the water in the soil has a shorter distance to move in order to come in contact with the roots in the case of the sorghums and thus keep the water lost from their leaves replaced and the turgidity of their leaves prolonged for a longer period than in the case of corn.

The roots in the upper region of the soil can deplete the soil moisture below the wilting coefficient provided that there is a sufficient water supply in the lower levels and that enough roots penetrate therein to furnish the bulk of the water necessary to replace that lost from the leaves. The roots in the upper portion of the soil thus continue to absorb a small amount of water and pass it on to the stem where, if this small amount of water in the upper portion of soil was all that was available, the plant would die from lack of moisture and the water in the soil at that level would not be depleted to so low a degree.

The following table shows the calculated wilting coefficient and percentage of moisture at different depths under corn and milo at Garden

Depth of sample, feet	Per cent of moisture	Calculated wilting coefficient
1	7.7	12.7
2	12.2	14.5
3	11.4	14.5
4	12.9	16.3
5	15.6	17.1
6	19.1	16.1

City, Kan., at the close of the growing season, which extended from June 5 to Sept. 6, 1914.

A small leaf surface is no doubt an important factor in delaying the wilting of plants when the moisture supply of the soil is low. In general, the smaller the leaf surface the smaller the amount of water lost in a given time so that even the low rate of absorption which prevails when the lower limits of the water supply in the soil has been reached would suffice to replace the water lost by evaporation from a small leaf surface. Thus the soil moisture could be reduced to a lower level than would be possible if the amount of water lost was large due to a large leaf surface. The case of the desert legumes mentioned by Alway (1913) illustrates this point. As the water supply in the soil became low their leaf surface was greatly decreased by the shedding of the lower leaves, while the upper ones continued to live until the water content had been reduced even below the hygroscopic coefficient.

C. WATER-SUPPLYING POWER OF THE SOIL AT THE TIME OF WILTING

The rate at which water is delivered to the roots of plants by the soil has been termed the "water-supplying power" of the soil. It is intended here to consider the causes for the failure of a plant to obtain its needed water supply at the time it begins to wilt. The experimental work in this regard has been conducted along two main lines—a study of the back pull of the water of the soil at the time of wilting and a study of the speed at which water moves from the soil to the roots at the lower limits of the water supply of the plant. Shull (1916) investigated the back pull of the water of the soil at various percentages of moisture content by means of the amount of moisture that air-dry seeds can extract from it. Seeds will imbibe water under a high pressure or against an enormous back pull. Shull placed air-dry seeds of the cocklebur (*Xanthium pennsylvanicum*) in salt solutions of various concentrations and determined the percentage of moisture that they could imbibe under these different conditions. The table on page 161 shows the intake of water by these seeds in the different concentrations after 48 hr.

Since the percentage of water absorbed by these seeds is an indicator of the force or back pull exerted by the external medium to its entrance, they were used by Shull after the following manner to measure the back pull exerted by the water of the soil at different percentages of water content. Sixty grams of soil of the desired moisture content were placed with seeds in 200-cc. bottles, sealed, and kept agitated for 15 days. At the end of that period the bottles were opened and the moisture contents of the seeds and of the soil were determined. The moisture content of the seeds and soil at the end of the experiment shows the equilibrium

Solution	Osmotic pressure or back pull of the water of the solution, atmospheres	Intake of water by the seeds, per cent
H ₂ O.....	0.0	51.6
0.1 M NaCl.....	3.8	46.3
0.2 M NaCl.....	7.6	45.5
0.3 M NaCl.....	11.4	42.0
0.4 M NaCl.....	15.2	40.3
0.5 M NaCl.....	19.0	39.0
0.6 M NaCl.....	22.8	35.2
0.7 M NaCl.....	26.6	32.8
0.8 M NaCl.....	30.4	31.1
1.0 M NaCl.....	38.0	26.7
2.0 M NaCl.....	72.0	18.5
4.0 M NaCl.....	130.0	11.8
Saturated NaCl.....	375.0	6.4
Saturated LiCl.....	965.0	- 0.3

relation of that soil moisture content. The following abbreviated table shows the relation of the soil moisture in the subsoil of Oswego silt loam to the water intake of *Xanthium* seeds. This soil had a moisture equivalent of 35.2 and a calculated wilting coefficient of 19.1.

Moisture in soil, per cent air dry	Intake of moisture by seeds, per cent	Back pull of water of the soil, atmospheres
5.83	0.0 sat. LiCl	965
9.36	6.47 sat. NaCl	375
11.79	11.94 4 M NaCl	130
13.16	21.36 2 M NaCl	72
14.88	28.61 1 M NaCl	38
17.10	37.70 0.5 M NaCl	19
17.93	43.20 0.3 M NaCl	11.4
18.07	45.15 0.2 M NaCl	7.6
18.87	47.26 0.1 M NaCl	3.8
19.34	49.31	
20.04	50.50 sat.	0.0

An examination of this table shows that in the case of the subsoils of the Oswego silt loam the back pull of the water in the soil when it is air dry reaches the enormous force of 965 atmospheres. As the moisture content of the soil increases, this back pull becomes less and less, so that

by the time the former has reached about 19 per cent, the wilting coefficient of that soil, the back pull of the soil water is somewhat less than that of a 0.1M NaCl solution, which is equivalent to between 3 and 4 atmospheres. Numerous types of soils were used ranging from sands to clay loams, and it was found that the average intake of water by the seeds from the seven different types of soil used was approximately 49 per cent at the percentage of soil moisture that represents their calculated wilting coefficient. Shull concludes that these results probably mean that the wilting coefficient represents a fairly definite water-holding power for the soil particle regardless of its size. Thus the force with which the soil particles of any type of soil withhold water from the root hairs of plants at the wilting coefficient is no greater than 3 to 4 atmospheres. Let us now consider how the soil forces at the wilting coefficient compare with the osmotic pull of the root hairs. In Chap. I it was stated that their osmotic pressure varied with the conditions under which they were grown and that the work of Roberts (1916) showed that the root hairs adjust their osmotic pressure as the medium changes, keeping it approximately 4 atmospheres above that of the surrounding medium. It thus seems reasonable to assume that as the soil dries out even below the wilting coefficient the root hairs maintain an osmotic pressure a few atmospheres in excess of the soil forces until these forces become relatively very high. Shull concludes that the wilting of the plant at the wilting coefficient of the soil cannot be due to the lack of moisture in the soil nor the lack of a gradient of forces tending to move the water toward the plant but that the wilting of the plants at this critical soil moisture content must be due to the increasing slowness of the water movement from soil particle to soil particle and from these to the root hairs, the rate of movement falling below that necessary to replace that lost from the aerial parts even under conditions of low water loss from the plant.

Methods for measuring the water-supplying power of the soil have been studied and devised by Livingston and Hawkins (1915), Pulling and Livingston (1915), Livingston and Koketsu (1920), Mason (1922), Livingston and Ohga (1926), Hardy (1923), Baldwin (1928), and Wilson (1928). The method devised by Livingston and Koketsu (1920) has proved very satisfactory and gives promise of furnishing a means of predicting the need and time of application of water to plants. This method consists of pushing into the soil porcelain cones which have a known area of unglazed surface. These cones are weighed before insertion into the soil and after remaining there for a given period are brushed free from soil particles and weighed. In this manner the amount of water that they absorb is determined. The amount of water absorbed by these cones is taken as an index of the water-supplying power of a given soil under a given condition. Two points must be considered in the use of an absorbing instrument to measure the water-supplying power of the soil: (1)

whether the absorbing surface is in such capillary contact with the soil as to allow the water to move from the soil to the instrument as rapidly as it arrives at the soil surface adjacent to it and (2) whether the absorbing surface itself is able to absorb water as rapidly as it is delivered to it by the soil. Numerous investigations by the authors mentioned above indicate that the soil points of Livingston and Koketsu (1920) are reliable in these respects.

Livingston and Koketsu (1920) studied *the critical water supplying power of the soil* or the rate at which the water moves toward the plant when the moisture content has been depleted to or near the wilting coefficient. Their method of procedure was somewhat as follows: Plants of *Coleus blumei* and *Triticum sativum* were grown in 4-in. flowerpots and allowed to go until they had reduced the soil moisture to or near the wilting point. At this point the dry unglazed porcelain cones were pushed into the soil and allowed to remain approximately 2 hr. These were then removed and their intake of water determined. The amount of water received by these cones, the area of which approximated 10 sq. cm., in a given time was taken as an index into the water-supplying power of the soil at that moisture content. The investigators worked with 12 types and mixtures of soils and found that the water-supplying power of the soil at the wilting coefficient does not vary with the physical make-up of the soil and is thus the same for sand, loam, humus, or any mixture of these. They found the average water-supplying power of the soil at the wilting coefficient to be 85 mg. during each two-hour period for the type of soil points used. They also found that the movement of water when the soil was drained saturated was six thousand times more rapid than when the moisture content was reduced to the wilting coefficient. These authors state that this critical water-supplying power of the soil must not be considered as a constant for all kinds of plants or for all degrees of evaporation. It will not be a constant any more than the wilting coefficient, which varies in a regular and predictable way for any given soil and plant with the evaporating power of the air which prevails during the period of wilting. This work supplements that of Shull in that the same rate of water movement at or near the wilting points would be expected if the back pull of the water at the time of wilting was the same for all soils. The work of Shull (1916) and of Livingston and Koketsu (1920) shows that the movement of the water in the soil from particle to particle toward the roots is one of the most important factors that influences the intake of water by the plant, especially when the water supply becomes low. This substantiates the statement of Livingston and Hawkins (1915) that whatever may be the nature of the forces producing the migration of water from soil to plant, it seems that osmotic pressure does not play a prime and direct rôle in this movement but that the power of the soil to deliver water to root surfaces is

the principal condition that determines the moisture supply to plants in non-saline and non-toxic soils.

III. ENTRANCE OF WATER INTO THE ROOT

A. THE STRUCTURE OF THE ROOT

In order to discuss the forces which are considered to act in the intake of water by the root, its structure must be clearly understood. From Fig. 9A it is seen that water must transverse three definite tissues in moving through the root from the soil to the stele or fibrovascular bundle




FIG. 9.—Drawings showing the cells of the root that are concerned in the absorption of water and its translocation to the central cylinder. *A*, longitudinal section of the absorbing portion of a root of the lupine; *rh*, root hair; *c*, cortex; *e*, endodermis; *x*, central cylinder. *B*, enlarged portion of the endodermis and adjoining cells; *e*, endodermis; *cs*, Casparian strip. *C*, the endodermis showing the Casparian strip and the attachment of the protoplasm to it at plasmolysis. *D*, diagram illustrating the manner in which water may be absorbed and translocated across the root. Description in the text.

and the cells enclosing it. These three tissues are the epidermis, the cortex, and the endodermis. The general nature of the epidermal cells of the root has been discussed in considerable detail in Chap. III and need not be considered here. The cortical cells are of the typical thin-walled vacuolated parenchyma type that is very common in plant tissue. The endodermis is the most outstandingly differentiated of these three tissues. It is a cylindrical layer of cells one layer thick which surrounds

the fibrovascular bundle and tissues adjoining it (Eames and MacDaniels, 1925). The cells of this layer are living and are closely packed together and devoid of any intercellular spaces. The differentiations peculiar to the endodermis lie principally in the structure of the cell walls that compose it. In the young root these cells are thin walled, but the end and radial walls are thickened by a band or strip which is known as the "Casparian strip" (Fig. 9B and C). The development of the endodermis has recently been studied by Priestley, Rhodes, and North (1922, 1926) especially in regard to the nature of the substances which compose the cell wall and the Casparian strip. They observed that the first noticeable differentiation of the endodermal cells from the apical meristem is the appearance of the Casparian strip which is laid down even before cellulose can be detected in the walls of these cells. The wall of the cells of the endodermis with the exception of the Casparian strip develops into a thin cellulose wall which is soluble in sulphuric acid. The Casparian strip, however, does not so dissolve and remains intact when the other portions of the cell wall go into solution. It is more resistant to sulphuric acid and less resistant to oxidizing agents than the cellulose wall. These various reactions suggest the presence in the Casparian strip of basal substances which at a very early time in the development have been impregnated with complex substances containing derivatives of certain compounds which are apparently allied with suberogenic and cutinogenic acids and with substances giving reactions to lignins. The basal material of the Casparian strip is not definitely known. Priestley and Rhodes (1926) state that upon treatment of this material with concentrated nitric acid it yielded a brown body insoluble in water and dilute acids and an ether-soluble body of a waxy appearance. Neither of these bodies, however, could be identified. The cell wall of the endodermal cells at a later stage of the development of the root becomes greatly thickened, lignified, and suberized, but from the standpoint of water absorption that later differentiation need not be considered.

The endodermal cylinder of the young root has thus in the Casparian strip an anatomical structure which renders difficult the radial passage of water across it by way of the radial walls. The passage of water through the endodermal cells of the young root must then take place through the protoplasm. The protoplasm of the endodermal cell is apparently closely attached to or interwoven with the Casparian strip, since it has been shown by De Ruz de Lavison that when the cells are vigorously plasmolyzed, the protoplasm does not withdraw from the Casparian strip but remains suspended across the cell from strip to strip after plasmolysis around the remainder of the cell wall has been complete (Fig. 9C). The roots of certain plants have some cells in the endodermis which remain unsuberized and are termed "passage cells." It was observed by Scott (1928) that lead salts and dyes which cannot

penetrate the suberized walls of the endodermis pass through these passage cells.

Priestley and Tupper-Carey (1922) obtained evidence to show that very little water can enter the root through the root apex. They state that the meristematic tissue or cap closing the endodermal cylinder in the young root will prevent the passage of water under a pressure of 2 atmospheres. This tissue is also relatively impermeable to salts in solution. The stem apex, on the other hand, is very permeable to water and solutes. Its cell walls are composed of cellulose, while the cells that make up the apex of the root have walls of an unknown substance which apparently may be converted into cellulose by boiling with potassium hydroxide.

B. MODES OF WATER ENTRANCE INTO THE ROOTS

Three main forces are apparently concerned in the entrance of water into the root from the soil and its movement across it to the fibrovascular bundle. These forces are imbibition, osmotic forces, and passive absorption.

1. Imbibition.—The rôle of imbibition in the processes of plants has been shown by Shull (1924) and others to be of much import. The attraction or affinity of dry cell walls and protoplasm for water amounts in many cases to hundreds of and even 1,000 atmospheres (Shull, 1914 to 1915) and it has also been shown that very strong imbibitional forces may be developed within the plant even when the cell walls and protoplasm contain considerable water. If moisture is withdrawn from any region of an imbibing system, the surface tension of the watery films in that region is increased and a corresponding force or pull is exerted upon the surrounding medium for the movement of water into the region of loss to restore the equilibrium of the surface tension of these films. This deficiency of water in any region of an imbibing system has been termed by Livingston (1912) "incipient drying" and by Renner (1912) "the saturation deficit."

All the external contacts of the plant which are concerned in the intake of water and also in water loss are made through the medium of imbibing surfaces. The cell wall of an epidermal cell of the young root is colloidal in nature and has a strong affinity for the water of the soil particles with which it is in close contact. The protoplasm which borders upon the cell wall likewise has a strong attraction for water. Let us now consider an epidermal cell of a young root in which the imbibitional and osmotic forces are in equilibrium with the soil and the surrounding cells. Let us now assume that water is withdrawn from the exterior surface of the cell wall (Fig. 9Df). A saturation deficit is set up at f and a pull of equal magnitude is exerted upon the water farther back in the cell wall. When the imbibing forces of the cell wall are thus set in action and cause a

movement of water toward it, the supply of water must be secured from the protoplasm *e* with which it is in close contact. Holle (1915) found that during wilting the cell wall keeps in close contact with the protoplasm, thus permitting the continual withdrawal of water from it! The withdrawal of water from the protoplasm produces in it a saturation deficit which is satisfied by imbibing free water from the cell sap *d*. This action increases the absorbing power of the cell sap and causes the entrance of imbibed water from the protoplasm at *b*, which draws finally upon the exterior cell wall whose saturation deficit must be supplied by the water of the soil. (The migration of water across the root to the endodermis could be explained, in part at least, under certain conditions after the same manner as has been described for the movement of water across the epidermal cell. Kunkel (1912) considered that imbibitional factors were the main ones in the intake of water by the root. It seems very evident, however, that imbibitional factors do not act independently but in connection with osmotic factors, since the imbibitional disturbances create osmotic disturbances and both together are equally important in the process of water intake and translocation across the root.) Some water apparently may enter the cell wall of the epidermal cell and travel across the root through the cell walls of adjacent cells as far as the Casparian strip of the endodermis without the aid of the protoplasm or the cell sap. In such a case, imbibitional forces alone would be concerned. The intake of water by the young cells of the root where no vacuole is yet developed is apparently a purely imbibitional process. The amount of water, however, that may enter the plant under the direct influence of imbibitional forces alone is very small in amount compared to the intake through the vacuolated cells.

2. Osmotic Forces.—The osmotic value of the cell sap of the epidermal cells of the roots is always higher than that of the soil solution, and apparently, as mentioned in Chap. I, this superiority is maintained as the concentration of the external medium is increased. The effective force, however, with which water will be drawn into the cell by osmotic action will be the difference between the osmotic value of the cell sap and the osmotic value of the external soil solution less the turgor pressure of the cell wall (Thoday, 1918). This absorbing power of the epidermal cell is equivalent to one atmosphere or more in the cases that have been observed. The conditions are fulfilled for the migration of water into the root, provided that there is an increasing gradient of absorbing power from cell to cell across the cortex to the fibrovascular bundle. The absorbing power of the cells of the root has been investigated by Ursprung and his workers and they have determined that there is a gradient of absorbing power proceeding from the epidermal cell across the cortex to the endodermis and then a marked decrease in the endodermis and wood parenchyma. The following table is taken from Molz (1926):

ABSORBING POWER IN THE ABSORBING ZONE OF THE ROOT OF *Vicia faba*

Position of cells	Suction power, atmospheres	Position of cells	Suction power, atmospheres
Epidermis.....	0.7	Fifth row.....	2.8
Cortex cells.....		Sixth row.....	3.0
First row.....	1.4	Endodermis.....	1.7
Third row.....	1.5	Wood parenchyma.....	0.9
Fourth row.....	2.1		

In the intake of water by the root and in its movement across the same, osmotic forces always act in connection with imbibitional forces. There is in this connection as well as in the general movement of water through plant cells a tendency for these two forces to proceed toward equilibrium (Shull, 1924). Wherever imbibitional forces exceed osmotic forces, water will move into the imbibing matter, or if the osmotic forces are the larger, water will move from the imbibed material into the cell vacuole.

Under conditions of low transpiration or in the spring before the leaves are unfolded, water is forced into the conducting vessels of the root and up through the stem under pressures varying from a fraction of an atmosphere to several atmospheres. This pressure is evidenced by the bleeding of cut vines and branches of certain species of plants and is apparently connected with the exudation of water from the leaves of plants which occurs under certain conditions. This pressure which is set up in the fibrovascular bundles of the stem and root due to the water which is being forced in them is known as "root pressure." The forces that are involved in the transference of water across the endodermis into the fibrovascular bundle are not known. The effects of the deprivation of oxygen and of changes in temperature suggest that root pressure cannot be explained by means of osmotic and imbibitional forces alone and indicate that the vital relations of the cell involving energy transference are concerned (Blackman, 1921). The nature of the Casparian strip which prevents the transference of water across the radial walls of the endodermal cells would indicate that the water transference across the endodermis is under control of the protoplasm of these cells (Priestley, 1920, 1921). The manner in which the protoplasm brings about this migration of water into the bundles has not been determined experimentally, and any suggestions that have been made are purely theoretical. Most of the theories proposed assume that the processes involved are of a secretory or excretory nature. Since little or nothing is known, however, concerning the nature of the factors involved in the processes of secretion or excretion either in plants or animals, to state that water transference into the bundle from the endodermis is a process of secretion

does not illuminate the matter at all. We must, therefore, in the words of Blackman (1921), have a much greater knowledge of cell dynamics than we possess at present before we can explain the exudation of water and root pressure with any degree of satisfaction.

Under conditions of little or no transpiration and an abundant water supply the intake of water and its movement across the root can be explained by purely osmotic and imbibitional forces, provided that a saturation deficit is created in the endodermis. At present, however, there is no satisfactory way of explaining how this saturation deficit is brought about by the endodermal cells.

3. Passive Absorption.—The term “passive absorption” as here used denotes the entrance of water into the root under the influences of forces exterior to it. When transpiration is proceeding even at a low rate during the daylight hours the leaves tend to dry out on account of water being abstracted from them by evaporation, and a saturation deficit is produced. This results in the water of the vessels passing into a state of tension which is transmitted equally in all directions, so that under these conditions water is not being forced up through the fibrovascular bundles by the roots but is apparently being pulled up the stem under great stress by the forces operative in the leaves. Under these conditions when a stem is cut off water does not exude from the stump, and if the cut surface of the stump is immersed in water, water will be sucked back into it, showing that there is a negative pressure in the conducting vessels as far as the roots are concerned. Dixon (1909) and Renner (1912) consider that the water-absorbing power of the roots is directly related to the saturation deficit in the leaves and that the tensile stress developed in the cells of the leaves and conducting vessels on this account is transmitted to the root and has the ultimate effect of drying out the root surface. According to this theory of water intake in the absence of root pressure, the passage of water from the soil into the root is purely passive and the root acts merely as a filter in the process. Of what importance the osmotic forces of the root are under the conditions of passive absorption is not known. Pulling and Livingston (1915) consider that the osmotic forces may influence the process of absorption in an indirect manner by maintaining the form of the roots and their contact with the water films of the surrounding soil. They also state that it has been shown that roots do not take up water at rates proportional to the osmotic pressures of the cells and that absorption may go on equally well with low or high turgidity of roots as long as the protoplasts of the cells involved are not deformed by plasmolysis.

It is evident that the intake of water by the root and its movement across it is a very complex process and that numerous factors and forces are involved. Imbibition, osmotic forces, and passive absorption are evidently concerned in the process and under certain conditions act

separately and under others jointly. That these forces can supply the plant with sufficient water to replace that lost during vigorous transpiration seems doubtful, and, in the words of Overton (1921), little is actually known about the forces which are operative in the passage of water from the soil through the root into the vessels in sufficient quantity to supply the transpiration needs.

Questions

140. Discuss the evidence in regard to the intake of moisture by the aerial parts of plants. By what methods have these data been obtained?

141. What amount of water may leaves absorb from the air? Of what physiological importance is this water to the plant? Why? Which leaves absorb the most water?

142. Why does a wilted plant revive when the air becomes humid? Can leaves absorb dew? Why?

143. Distinguish between incipient wilting, evident wilting, and permanent wilting.

144. What is the wilting coefficient? The observed wilting coefficient? Describe the direct method used in determining the wilting coefficient.

145. What difficulties are encountered in attempting to determine the wilting coefficient in the field? In attempting to determine it with large plants?

146. What is the calculated wilting coefficient? Of what advantage is it? Upon what assumption is the indirect method of determining the wilting coefficient based?

147. What is the moisture equivalent of a soil? The hygroscopic coefficient? The moisture-holding capacity? What is the relationship of each of these values to the wilting coefficient?

148. Explain in detail how the changes in the rate of transpiration at the lower limits of soil moisture may indicate the permanent wilting point of the plant.

149. How does the wilting coefficient vary for different soils? Give examples.

150. How does the wilting coefficient vary with the atmospheric conditions? Why? Cite examples.

151. State three general laws in regard to the relation of the observed to the calculated wilting coefficient under different climatic conditions.

152. What observations have been made in regard to the variation of the wilting coefficient for different species of plants? What objections are there to the experimental evidence in this regard?

153. How may the distribution of the root system enable some plants to reduce the moisture of the soil more than others before permanent wilting? Give examples.

154. How may a small leaf surface be an important factor in delaying permanent wilting of plants when the moisture supply is low? Give illustrations.

155. How may the moisture content of the soil be reduced by the roots below the wilting coefficient in the case of plants growing in the field?

156. What is the water-supplying power of the soil? Along what two lines has the experimental work in this regard been conducted?

157. Describe in detail the method used by Shull for determining the back pull of the water of the soil.

158. How does the force of attraction of the soil particles for water at the wilting coefficient compare with the absorbing power of the epidermal cells of the root? How does this force of attraction of the soil particles for water at the wilting coefficient compare for different soils?

159. What is the critical water-supplying power of the soil? Describe the method by which its value has been determined. How does the critical water-supplying power of the soil compare in different soils?

160. Name the tissues that water must cross in moving from the soil across the root to the central cylinder of the root.

161. What is the endodermis? The Casparian strip? What is known concerning the origin and composition of this strip? What relation does this strip have with the protoplasm? What function does this strip perform?

162. Name the three modes of water entrance into the root and its transference across the root to the endodermis. What is the saturation deficit?

163. Explain how water might be absorbed and moved across the root to the endodermis by imbibitional forces alone.

164. Explain how the absorption and translocation of water across the root could be accomplished by imbibitional and osmotic forces working together.

165. How does the osmotic value of the cell sap of the epidermal cells of a root compare with that of the external solution? Discuss the gradient in the absorbing power of the cells from the epidermis to the endodermis.

166. What is root pressure? When is it manifest? How is it brought about? What evidence is there that the vital activity of the cells is concerned in the process?

167. What is meant by passive absorption of water by the root? Under what conditions does it occur?

168. Explain how water might enter the roots under the influence of forces operative in the leaves. Of what value are the osmotic forces of the root under conditions of passive absorption?

Bibliography

- ALWAY, F. J., 1913: Studies of the relation of the non-available water of the soil to the hygroscopic coefficient, *Nebr. Sta. Res. Bull.* **3**: 5-122.
- BAKKE, A. L., 1915: The index of foliar transpiring power as an indicator of permanent wilting in plants, *Bot. Gaz.*, **60**: 314-319.
- , 1918: Determination of wilting, *Bot. Gaz.*, **66**: 81-116.
- BALDWIN, H. I., 1928: A comparison of the available moisture in sod and open soil by the soil point method, *Bull. Torrey Bot. Club*, **55**: 251-255.
- BLACKMAN, V. H., 1921: Osmotic pressure, root pressure, and exudation, *New Phytol.*, **20**: 106-115.
- BRIGGS, L. J., and H. L. SHANTZ, 1911: Application of wilting coefficient determinations in agronomic investigations, *Jour. Amer. Soc. Agron.*, **3**: 250-260.
- and ———, 1912: The wilting coefficient for different plants and its indirect determination, *Bur. Plant Ind., U. S. Dept. Agr., Bull.* 230.
- and ———, 1912: The wilting coefficient and its indirect determination, *Bot. Gaz.*, **53**: 20-37.
- and ———, 1912: The relative wilting coefficient for different plants, *Bot. Gaz.*, **53**: 229-235.
- and ———, 1913: Die relativen Welkungskoeffizienten verschiedener Pflanzen, *Flora*, **105**: 224-240.
- BROWN, W. H., 1912: The relation of evaporation to the water content of the soil at the time of wilting, *Plant World*, **15**: 121-134.
- CALDWELL, J. S., 1913: The relation of environmental conditions to the phenomenon of permanent wilting in plants, *Physiol. Res.*, **1**: 1-56.
- CRUMP, W. B., 1913: Notes on the water content and the wilting point, *Jour. Ecol.*, **1**: 96-100.
- DIXON, H. H., 1910: Transpiration and the ascent of sap, *Prog. rei Bot.*, **3**: 1-66.

- EAMES, A. J., and L. H. MACDANIELS, 1925: "An Introduction to Plant Anatomy," pp. 100-103, McGraw-Hill Book Company, Inc., New York.
- GANONG, W. F., 1894: On the absorption of water by the green parts of plants, *Bot. Gaz.*, **19**: 136-143.
- HALKET, A. C., 1911: Some experiments on absorption by the aerial parts of certain salt plants, *New Phytol.*, **10**: 121-139.
- HARDY, F., 1923: The soil point method for directly estimating the water supplying power of a soil in the field, *Jour. Agr. Sci.*, **13**: 355-360.
- HENSLOW, GEORGE, 1908: On the absorption of rain and dew by the green parts of plants, *Jour. Roy. Hort. Soc.*, **34**: 167-178.
- HOLLE, HANS, 1915: Untersuchungen über Welken, Vertrocken und Wiederstraffwerden, *Flora*, **108**: 73-126.
- KUNKEL, L. O., 1912: A study of the problem of water absorption, *Mo. Bot. Garden Ann. Rept.* **23**: 26-40.
- LIVINGSTON, B. E., and W. H. BROWN, 1912: Relation of the daily march of transpiration to variations in the water content of foliage leaves, *Bot. Gaz.*, **53**: 309-330.
- and L. A. HAWKINS, 1915: The water relation between plant and the soil, *Carnegie Inst. Wash. Pub.* **204**: 1-48.
- and R. KOKETSU, 1920: The water supplying power of the soil as related to the wilting of plants, *Soil Sci.*, **9**: 469-485.
- and I. OHGA, 1926: The summer march of soil moisture conditions as determined by porcelain soil points, *Ecology*, **7**: 427-439.
- , T. HEMMI, and J. D. WILSON, 1926: Growth of young wheat plants in auto-irrigated soils, as related to the water supplying power of the soil and to the adjustment of the autoirrigator, *Plant Physiol.*, **1**: 387-395.
- MACDOUGAL, D. T., 1925: Absorption and exudation pressures of sap in plants, *Amer. Phil. Proc.*, **64**: 102-130.
- MASON, T. G., 1922: The physiological humidity of the soil and its direct determination, *W. Ind. Bull.* **19**: 137-154.
- MILLER, E. C., 1916: Comparative study of the root systems and leaf areas of corn and the sorghums, *Jour. Agr. Res.*, **6**: 311-331.
- OVERTON, J. B., 1921: The mechanism of root pressure and its relation to sap flow, *Amer. Jour. Bot.*, **8**: 369-374.
- POWERS, W. L., 1922: Field moisture capacity and wilting point of soils, *Soil Sci.*, **14**: 159-167.
- PRIESTLEY, J. H., 1920: The mechanism of root pressure, *New Phytol.*, **19**: 189-200.
- , 1922: Further observations upon the mechanism of root pressure, *New Phytol.*, **21**: 41-48.
- and E. E. NORTH, 1922: Physiological studies in plant anatomy. III, The structure of the endodermis in relation to its function, *New Phytol.*, **21**: 113-139.
- and E. RHODES, 1926: On the macro-chemistry of the endodermis, *Proc. Roy. Soc., B*, **100**: 119-129.
- PULLING, H. E., and B. E. LIVINGSTON, 1915: The water supplying power of the soil as indicated by osmometers, *Carnegie Inst. Wash. Pub.* **204**: 49-84.
- , 1917: The rate of water movement in aerated soils, *Soil Sci.*, **4**: 239-268.
- RENNER, O., 1912: Versuche zur Mechanik der Wasser-versorgung. I, Der Druck in den Leitungsbahnen von Freilandpflanzen. II, Über Wurzelatätigkeit, *Ber. d. d. bot. Ges.*, **30**: 576-580, 642-648.
- SACHS, J., 1859: Ueber den Einfluss der chemischen und physikalischen Beschaffenheit des Bodens auf die Transpiration der Pflanzen, *Landw. Versuchs-Stat.*, **1**: 203-241.
- SCOTT, L. I., and J. H. PRIESTLEY, 1928: The root as an absorbing organ. I, A reconsideration of the entry of water and salts into the absorbing region, *New Phytol.*, **27**: 125-141.

- SCOTT, L. I., 1928: II. The delimitation of the absorbing zone, *New Phytol.*, **27**: 141-174.
- SHIVE, J. W., and B. E. LIVINGSTON, 1914: The relation of atmospheric evaporating power to the soil moisture content at permanent wilting in plants, *Plant World*, **17**: 81-121.
- SHULL, C. A., 1913: Semipermeability of seed coats, *Bot. Gaz.*, **56**: 169-199.
- , 1914: Measurement of the internal forces of seeds, *Trans. Kans. Acad. Sci.*, **27**: 65-70.
- , 1916: Measurement of the surface forces in soils, *Bot. Gaz.*, **62**: 1-29; *Science*, n. s., **43**: 331.
- , 1924: Imbibition in relation to absorption and transportation of water in plants, *Ecology*, **5**: 230-241.
- SPALDING, V. M., 1906: Biological relation of desert shrubs. II, Absorption of water by leaves, *Bot. Gaz.*, **41**: 262-283.
- THODAY, D., 1918: On turgescence and the absorption of water by the cells of plants, *New Phytol.*, **17**: 108-113.
- VEIHMEYER, F. J., and A. H. HENDRICKSON, 1928: Soil moisture at permanent wilting of plants, *Plant Physiol.*, **3**: 355-357.
- WETZEL, KARL, 1924: Die Wasseraufnahme der höheren Pflanzen gewässiger Klimate durch oberirdische Organe, *Flora*, **117**: 221-269.
- WILSON, J. D., 1927: The measurement and interpretation of the water supplying power of the soil with special reference to lawn grasses and some other plants, *Plant Physiol.*, **2**: 385-440.
- WOOD, J. G., 1925: The selective absorption of chlorine ions and the absorption of water by the leaves in the genus *Atriplex*, *Australian Jour. Expt. Biol. Med. Sci.*, **2**: 45-46; *Bot. Abst.*, **15**: 1164 (1926).

CHAPTER V

THE INTAKE OF SOLUTES BY THE PLANT

Under this heading it is intended to discuss more particularly the entrance of the inorganic compounds into those cells of the plant which border upon the medium in which the plant is growing. The discussion will include not only the mode of entrance of the solutes but also the general influence of the environmental factors on the intake of materials by the plant as well as the nature and composition of the solutions that are commonly used in the study of plant nutrition.

I. MODE OF ENTRANCE OF SOLUTES

Numerous experiments have been performed to show that inorganic salts readily penetrate the protoplasmic membrane and enter the vacuole of the cell, but a simple experiment by Osterhout (1909) in this regard will suffice as an example. He noted that *Dianthus barbatus* could be grown with its root hairs entirely free from calcium oxalate if the seeds of this plant were simply placed on the surface of distilled water and allowed to grow. After the root hairs thus grown had reached the desired length they were transferred to a calcium solution and examined from time to time under the microscope for the appearance of calcium oxalate crystals. Controls in the distilled water were examined at the same time and treated in the same manner as the plants in the solution. In no case did the controls produce crystals, but calcium oxalate crystals were always produced in the root hairs when grown in the following solutions: 0.05M CaSO₄, 0.005M Ca(NO₃)₂, 0.005M CaCl₂, and 0.001M Ca(OH)₂, dilute sea water, and tap water. In each of these solutions the crystals of calcium oxalate made their appearance within the root hairs inside 4 hr. at 30°C. The shortest time required for the formation of crystals was 1½ hr. in the case of CaSO₄ solution. It was also found that the root hairs in contact with particles of precipitated CaCO₃ and Ca₃(PO₄)₂ produced calcium oxalate crystals but only after several days. It has generally been considered that inorganic salts penetrate the protoplasm in the dissociated or ionic form. Recently, however, work by Osterhout (1925), Irwin (1926), and Cooper, Dorcas, and Osterhout (1929) indicates that, in some cases at least, certain compounds enter the plant cell through the protoplasm only in the undissociated form.

A. PASSIVE OR PHYSICAL ABSORPTION

It has generally been observed that the protoplasmic membrane of the cells bordering upon the soil or the medium in which the plants are growing is permeable to practically all the inorganic solutes present in the soil solution. It has thus been considered that the entrance of any given solute into the vacuole of these cells is a process of diffusion from the higher concentration of this solute in the soil to a lower concentration in the cell sap. If no disposition were made of the solute which entered, equilibrium in concentration between the cell sap and the soil solution in regard to this solute would be reached and no more would enter. If, however, some or all of this solute were removed from the cell, combined, precipitated, adsorbed, or otherwise rendered osmotically inactive, the concentration of the solute would continue to be lower in the cell sap than in the surrounding medium, so that it would continue to enter the cell. This principle can be illustrated by an experiment, as shown in Fig. 10. A solution of tannin is separated by a membrane of collodion or parchment paper from a solution of ferric chloride. The tannin will not diffuse through the membrane but the FeCl_3 will. As soon as the iron salt enters *A*, it is precipitated as iron tannate so that the concentration of FeCl_3 in *A* never becomes equal to that in *B* and more will continue to enter. All the FeCl_3 in *B* will pass through into *A* provided that there is a sufficient quantity of tannin in *A* to combine with the iron salt.




FIG. 10.—Diagram to illustrate the principle of physical absorption. Description in the text.

In many cases the analysis of certain tissues has indicated a higher concentration of certain elements or ions in the cell sap than in the surrounding medium, and this fact has been explained until recently by assuming that a portion of the ions in question was adsorbed, combined, or precipitated so that the concentration was never greater than that of the surrounding medium.

In the opinion of Breazeale (1923), the demand for the various elements originates in the tissues of the plants and is carried to the absorbing surface of the root by means of unsaturated colloidal compounds bearing a plus or minus electric charge. For example, let us suppose that the protoplasm in a leaf cell removes an atom of K from a colloidal compound and uses it in building up a permanent compound which is to be one of the final constituents of its tissues. This leaves the colloidal compound or molecule out of equilibrium and with a minus charge. This charge is transmitted by replacement and not by bodily movement down through the cells to the epidermal cells of the root and there appears as a minus charge. If an ion of K were present in the soil solution, it would be attracted to the negative charge. The potassium could in this manner be

transported from the absorbing surface of the root to any part of the plant without the bodily movement of a K compound through the sap. Breazeale further considered that if an ion of K bearing a plus charge is removed from the soil solution by the root, this ion can be filled by replacement and the charge carried along through the soil, where the source of supply of potassium exists. If this is true, the plant will not be dependent upon the soil grains that come in contact with the epidermal cells of the root, but it may actually obtain its nutrients at a distance from the roots. The objections to this theory will be brought out in the following discussions.

Recent examinations, however, of the uncontaminated sap of individual cells show that, in some cases at least, the concentration of the osmotically active solutes is higher in the cell sap than in the surrounding medium. This indicates that the intake of solutes is not always so simple a process as has been mentioned in this topic.

B. ACTIVE OR PHYSIOLOGICAL ABSORPTION

The ability to obtain a sufficient quantity of uncontaminated sap from the large cells of *Valonia* and *Nitella* for chemical analyses (Wodehouse, 1917; Osterhout, 1922; and Hoagland and Davis, 1923) has greatly enhanced our knowledge concerning the concentration of the cell sap as compared to the external medium. Osterhout (1922) made an analysis of the cell sap of *Valonia* and found the concentration of certain elements in it as compared to the sea water in which it grew to be as follows:

Element	Concentration in sea-water, ppt.	Concentration in cell-sap, ppt.
Chlorine.....	19.6	21.2
Sodium.....	10.9	2.1
Potassium.....	0.5	20.1
Calcium.....	0.45	0.7
Magnesium.....	1.31	Trace
SO ₄	3.3	0.005

The data show that some factor or factors prevented the Na, Mg, and SO₄ from reaching as high a concentration in the cell sap as in the medium in which the cells were growing. The chlorine content was practically the same inside the cell as in the sea water. The most striking fact of the experiment was the high concentration of potassium in the cell sap as compared to the external concentration. Its concentration in the sap in this case was approximately forty times as high as in the sea water. Practically all the K in the cell sap was in the form of chlorides, so that this accumulation could not be attributed to its combination with other

compounds. The concentration of ions in the cell sap of *Nitella clavata* compared to that of the surrounding medium was investigated by Hoagland and Davis (1923). A summary of their work is given in the following table:

Items considered	K	Na	Ca	Mg	Cl	SO ₄	PO ₄	NO ₃
	Ppm.							
Pond water in which plants grew..	Trace	5	31	41	32	31	0.4	34
Sap from cells.....	2,120	230	410	430	3,220	800	350	0
Ratio of cell sap concentration to external concentration.....	2,000	46	13	10	100	26	870	

They considered that the major portion of the inorganic elements in the cell sap was in the ionic state since its conductivity was slightly greater than that of a *N/10* KCl solution. By a comparison of the positive and negative ion equivalents it was possible to balance 80 to 90 per cent of the positive ions by negative ions. The remaining ions were ascribed to organic acids and other organic compounds.

The analysis of the sap showed that the concentration of each of the ions with the exception of NO₃ was higher than in the water in which the cells were growing. The accumulation of K was the highest and that of Mg the lowest. The insoluble or combined elements found in the cell wall and protoplasm included Ca, Mg, S, Si, Fe, and Al, the calcium being the most abundant. No K was present in the insoluble form. Hoagland (1919) and Hoagland and Davis (1925) observed that the expressed sap of the leaves of barley growing in an ordinary cultural solution had a conductivity four to fifty times greater than that of the solution from which the plants obtained their inorganic nutrients. This also indicates that the concentration of the ions within the cell is higher than that of the surrounding medium. In a study of the relation between the composition of young orange trees and the concentration of nutrient solutions, Reed and Haas (1924) concluded that there is apparently no evidence to support the assumption that the absorbed materials are converted into insoluble compounds as rapidly as they accumulate in the plant or that absorption necessarily depends upon the precipitation of ions within the plant.

Stiles (1924) in a study of the absorption of salts by storage tissues concluded that the absorption of salt by them is not a simple process of diffusion of the salt through a cell membrane. The vital force which overcomes the physical equilibrium and enables the cell to accumulate salts in concentration greater than the outside is termed "epictesis" by Lapique (1925). He considers that the rotation of the protoplasm brings every part of it alternately in contact with the external medium and the vacuole. Thus at the surface of the cell it is in contact with a

neutral or alkaline medium and at the vacuole it is in contact with an acid one. Under the former condition it takes up Na, K, etc., and under the latter condition it gives them up, a process which is in accord with the amphoteric character of the proteins (Chap. IX).

The isoelectric point of such a substance is that point of the P_H value of the solution in which it is distributed at which the substance acts neither as an anion nor as a cation. The isoelectric point thus may be called the "neutral point" of the substance in question. An ampholyte thus on the acid side of the isoelectric point behaves as a cation and combines with anions, while on the alkaline side of the isoelectric point it behaves as an anion and combines with cations. Since the absorption of ions is intimately connected with certain characteristics of the protoplasm and since many of these characteristics are bound up apparently with the peculiar properties of its constituent proteins, it would seem possible that the amphoteric nature of the plant proteins would exert an influence on the absorption of ions (Robbins 1923). In this regard, evidence has been presented by Pearsall and Ewing (1924) to show that rapid outward diffusion of chlorine ions ensues when living plant tissue is brought to a hydrogen-ion concentration equal to or greater than that at which its chief protein, in the case of potato and carrot, or its protoplasm, in the case of *Nitella*, is isoelectric. Since the outward diffusion of colored sap from the beet becomes rapid at or below P_H 4.3, it is assumed that this is the isoelectric point for the protoplasm of this tissue.

In considering the isoelectric points of membranes, Harvey (1927) states that these points may be produced in two ways: (1) the commonly known isoelectric point produced by the ionization of ampholytes and (2) the membranes without going into solution appreciably may show an isoelectric point produced by differential absorption. He considers that these conditions can be referred to as ionization isoelectric points and adsorption isoelectric points.

According to Briggs and Petric (1928), the conception of a simple Donnan equilibrium operating between two homogeneous phases is inadequate to explain the phenomenon of the ionic intake by plants, since experimental evidence indicates that the product of the apparent internal concentration of cation and anion, estimated on the basis of the total volume of the tissue, may be greater than that of the concentrations of the two ions in the external medium instead of equal to it, as the above conception would require. According to these authors, the interior of the plant tissues comprises a number of phases each of which may be in Donnan equilibrium with the external solution. The product of the apparent internal ionic concentrations resulting from the total effect of all these internal phases is shown under such circumstances to be greater than the external product. Even in such a system as this, however, if the ratio of the apparent internal to the external concentration is

greater than unity, the same ratio of the corresponding anion would be less than unity. Experimental evidence, however, indicates that both may be greater than unity. Briggs and Petrie suggest that this behavior may be accounted for by assuming that one internal phase contains indiffusible cations and that another contains indiffusible anions.

Since the penetration of ions into the cells that have just been mentioned apparently takes place from a solution of low to a solution of high concentration of these ions, the plant cell must do work in absorbing them. The processes involved would seem to be similar to those which occur in the secretion by the glands of animals by which compounds are taken from a dilute concentration in the blood and excreted to the outside into a much higher concentration. Just how such a process is brought about is not known, so it is only expressing our ignorance when we state that the transference of an ion from a low concentration to a higher one is a process of secretion. The data that have been presented show that little is yet known concerning the means by which absorption of solutes occurs. The ratio of the internal concentration of a given solute in the cell to its external concentration has been termed the "absorption ratio." Some of the factors which influence its value will be discussed in the following topic.

II. FACTORS THAT AFFECT THE ABSORPTION RATIO

A. LIGHT

Since light either directly or indirectly is the source of the energy of the plant cell, Hoagland and Davis (1923) and Hoagland, Hibbard, and Davis (1926) undertook a study of the influence of light upon the removal of certain ions from the external solution by *Nitella clavata*. The solution and plants were exposed to light for different lengths of time and the amounts of certain elements remaining in the solution were observed and the absorption ratio determined. In one experiment the solution employed was $0.01M$ $KH_2PO_4 + KCl$ in varying amounts. The general plan of the experiment together with certain of the data is shown in the following table:

Experiment number	Length of experiment, days	Concentration of KCl in external solution ppm.	Chlorine remaining in solution, ppm.					Dark
			Full illumination	Dim light	Light 9 a. m. to 5 p. m.	Light 11 a. m. to 4 p. m.	Light 11 a. m. to 2 p. m.	
1	4	17.8	0	1.5	5.0	13.5		
2	4	35.5	0	14	27	..	31
3	5	35.5	3	35	16	22	26	
4	4	35.5	2	27	10	15	25	34

In the case of $0.01M$ KNO_3 , heavy tests for NO_3 were found in the sap for all cells in the light but only slight tests for those in the dark. In

every experiment where the absorption of bromine was under consideration, the exposure to light strikingly increased the ability of the cells to accumulate this element. When a concentration of 5 milli equivalents of bromine was used, the concentration of bromine in the cell sap of *Nitella* kept in the dark did not exceed that of the outside solution, while the sap of those exposed to illumination for an equal period of time had a much higher concentration than the surrounding solution. The following figures will serve as an example of the results obtained. These results were noted at a temperature of 20°C.

Illumination	Time, hours	Concentration of bromine in cell sap, milli equivalents
Continuous light.....	25	6.4
Continuous darkness.....	25	2.6
Continuous light.....	50	12.3
Continuous darkness.....	50	3.3

It is evident, in the case of *Nitella* at least, that light greatly increases the absorption of certain ions. These cells contain only a very limited supply of organic material which might release energy by respiration, so that little kinetic energy is available except that received directly from the sun. It is suggested that if energy is needed for the absorption of solutes by the cells of the roots, it is supplied by the process of respiration. It is worthy of note here that in the absorption of bromine by *Nitella* the temperature coefficient between 10 to 20 and 14 to 24°C. ranged between 2 and 3. This is of such a high value that it would be considered characteristic of a chemical reaction rather than a physical process of diffusion.

B. CONCENTRATION OF THE EXTERIOR MEDIUM

The data on this subject have been obtained, for the most part, by immersing disks of plant tissue of known dimensions and volume in the solution and then either directly or indirectly determining to what degree the external solution had been depleted of the salt or ions in question. The tissues that have been used are carrot, beet, dahlia, and the tubers of *Helianthus* and Irish potato. The solution is either analyzed chemically, or its changes in concentration determined by those in its conductivity. Since the volume of the tissue is known and since the decrease in the concentration of a given salt or ion in the solution can be determined after any period of absorption, it is possible to obtain values for the amount of salt or ion absorbed per unit of volume of tissue. The values thus obtained give an expression for the internal concentration of the salt. Thus the ratio of the concentration of the solute in the tissue to its concentration in the exterior medium can be obtained.

It has been observed by Nathansohn (1903, 1904) and Stiles and Kidd (1919) that the equilibrium reached in the absorption of a given solute by living tissue depends upon the external concentration of the solute. While the absolute amount of solute absorbed increased with the increasing concentration of the solute in the external solution, the amount absorbed relative to the external concentration nevertheless decreases rapidly from the lowest concentration upward. When the external concentration of the solute is low, the absorption ratio becomes more than unity, while if the external solution is relatively high, the absorption ratio is always less than unity. The following examples will illustrate these statements: Nathansohn (1903) found in the case of the marine alga *Codium* in twentieth-normal to normal solutions of sodium nitrate that the absorption ratio varied from 0.41 to 0.68 but that it did not take up the nitrate ion in sufficient amount to produce equal concentrations on the inside and outside of the tissue. He observed, however, that in sea water where the concentration of the nitrate ion was low, its concentration was greater in the tissue than in the exterior medium. The effect of different concentrations and different salts upon the absorption ratio of carrot tissue as found by Stiles and Kidd (1919) is shown in the following table:

Salt	Initial external concentration	Length of experiment, hours	Absorption ratio
KCl.....	{ N/5,000	52	25
		N/500	17.6
		N/50	2.4
		N/10	0.8
NaCl.....	{ N/5,000	48	46.7
		N/500	27.0
		N/50	3.5
		N/10	0.8
CaCl ₂	{ N/5,000	42.5	15.3
		N/500	2.8
		N/50	0.5
		N/10	0.24

These results show that the degree of absorption depends not only on the concentration of the external solution but also upon the nature of the ions absorbed. Calcium ions are apparently less absorbed than those of potassium and sodium. It is worthy of note that the absorption ratio for dead tissue never becomes greater than unity and that the concentration within the cells is practically identical with that of the external solution. Irwin (1925) noted when living cells of *Nitella* were placed in different concentrations of brilliant cresyl-blue solutions at P_H 6.9 that the greater the concentration of the external dye solution the greater

was the speed of accumulation of the dye in the cell sap and the higher the concentration of the dye in the sap at equilibrium. This behavior may be explained as a chemical combination of the dye with a constituent of the cell, since this explanation harmonizes with the fact that the temperature coefficient is about 5.0. It has been observed by Sideris, Krauss, and Masunaga (1928) that pineapple plants grown in cultures of higher salt concentrations absorbed more salts than those that were grown in cultures of low salt concentrations. A very high salt concentration in the cultural solution will increase that of the tissue fluids of young but fully developed leaves between 25 and 50 per cent and that of older leaves between 50 and 150 per cent. A very low salt concentration, on the other hand, will decrease that of the tissue fluids of young but fully developed leaves between 25 and 50 per cent and that of older leaves from 50 to 750 per cent. In the case of high salt concentrations in the outside solution, the oldest leaves are used as storage organs for the excess of salt. In the case of low concentrations in the outside solution, the stored-up salts of the oldest leaves are released to the young but fully developed leaves to make up for their salt deficiency.

III. THE UNEQUAL ABSORPTION OF IONS

The constituent ions of a salt are not necessarily absorbed in equivalent quantities by plant tissue or by the roots, as has been shown by the work of Nathansohn (1903, 1904), Meuer (1909), Ruhland (1909), Pantanelli (1915, 1918), Johnson (1915), Stiles and Kidd (1919), Redfern (1922), Hoagland (1923), Stiles (1924), Rudolfs (1925), Harris, Hoffman, and Lawrence (1925), and others. This fact has been determined directly by the chemical analysis of the solutions in which the living tissues had been placed or in which the roots of the plants were growing. The three following experiments will serve to illustrate the main facts observed and the chief points of interest in this regard. Redfern (1922) grew plants of corn and peas in a nutrient solution for two weeks and then transferred them to various solutions of CaCl_2 . After varying periods of time, these solutions were analyzed and the amount of calcium and chloride remaining determined. A sample of the results where the plants were placed in a tenth-normal solution of CaCl_2 is shown in the following table:

Corn			Peas		
Duration of experiment, hours	Percentage absorption of calcium	Percentage absorption of chloride	Duration of experiment, hours	Percentage absorption of calcium	Percentage absorption of chloride
23	17.5	6.5	36	17.7	3.6
48	25.3	6.5	60	12.7	4.0
57	27.0	5.9	84	14.6	3.8

The unequal absorption of ions by the barley plant from a variety of different salt solutions was observed by Hoagland (1923). His observations are summarized in the following table:

ABSORPTION OF IONS FROM DIFFERENT SALTS BY THE BARLEY PLANT

Adapted from Hoagland (1923)

Salt used	Initial concentration, milli equivalent	Ions absorbed, milli equivalents		Ions entering solution, milli equivalents			Length of absorption period, days
		Cation	Anion	Ca	Mg	K	
K ₂ SO ₄	6.32	0.74	0.40	0.32	0.24	} 1½
KCl.....	6.32	1.28	1.30	0.24	0.18	
KNO ₃	6.45	1.66	3.19	0.19	0.21	
KH ₂ PO ₄	6.32	0.90	0.14	0.28	0.21	
KHCO ₃	6.30	1.20	0.84	0.24	0.20	
CaCl ₂	12.50	1.50	2.37	0.28	0.02	} 2
Ca(NO ₃) ₂	12.70	1.66	5.48	0.20	0.09	
Ca(H ₂ PO ₄) ₂	12.30	1.03	0.95	0.27	0.20	
CaSO ₄	12.30	0.88	0.83	0.20	0.09	

Stiles (1924) studied the absorption of the constituent ions of single salts by the storage tissues of the carrot, parsnip, beet, and artichoke. Some observations of his work are shown in the following table:

Salt	Concentration, normality	Tissue	Duration of experiments, hours	Absorption, percentage of original amount	
				Cation	Anion
NH ₄ Cl.....	1/100	Carrot	48	57.2	32.2
(NH ₄) ₃ PO ₄	2/100	Carrot	23.5	28.8	6.0
(NH ₄) ₃ PO ₄	2/100	Parsnip	24.3	34.5	8.2
(NH ₄) ₂ SO ₄	1/100	Carrot	22.0	3.9	4.2
KCl.....	1/100	Carrot	22.0	4.6	6.3
NaCl.....	1/100	Carrot	47.1	18.5	8.5
Na ₂ SO ₄	1/100	Carrot	22.0	15.0	8.0

A. MECHANISM

Although it is an established fact that the ions of a given salt are not absorbed equally by the plant, the mechanism of this unequal absorption is not very clear. According to Stiles (1924), there appear to be two possible consequences. In the first place, the excess of the more absorbed ion may be accompanied into the tissue by a quantity of one of the constituent ions of water, either hydrogen or hydroxyl, whichever is of the opposite sign to the more absorbed ion. If this theory is granted,

then the external medium will be left either alkaline or acid depending on whether the anion or cation is absorbed in the greater amount. Let us consider a solution of NaCl as an example in which living tissue is immersed. If the sodium ion is absorbed in excess of the chlorine ion, the former will be accompanied into the tissue by an equivalent quantity of hydroxyl, leaving the same equivalent quantity of hydrogen ion to balance the excess of chlorine ion remaining in the external solution. The external medium would thus become acid. If, however, the chlorine ion is absorbed in excess, hydrogen ion accompanies it into the tissue and the external solution becomes alkaline. The acidity and alkalinity of water-cultural solutions have been ascribed in some cases to the result of the unequal absorption of ions.

In the second place, it is possible that the excess of the more absorbed ion is replaced in the external solution by some other ion or ions of the same sign diffusing out from the tissue. Thus in the case of NaCl, the excess sodium absorbed might be compensated by the diffusion out from the tissue of Mg, K, Ca, or other cations. If, however, chlorine is the more absorbed ion, its excess absorption could be compensated by the diffusion outward of nitrate, citrate, malate, or other anions.

B. REACTION OF THE EXTERIOR SOLUTION

The factors that may influence the reaction of the solution in which a plant is growing are numerous and complex. Some of these are the type and concentration of the salts used, the rate of growth, and type of plant, in addition to the unequal absorption of ions. It is the intention to state here some of the observations that have been made in this regard in order to show the great variation of results and the complexity of the problem.

One of the earliest observations along this line was made by Skene (1915), who found that the cell walls of sphagnum moss caused the solutions of neutral salts in which they were placed to become acid. The amounts of acid hydrogen thus liberated varied with the salt. In the case of NaCl, K_2SO_4 , $CaCl_2$, and $NaNO_3$, it amounted to from 0.012 to 0.025 g., in the case of Na_2SO_3 , sodium formate, and sodium butyrate, approximately 0.07 g. per 100 g. of dry sphagnum used. Skene found further that this property of sphagnum is exhibited generally by the cell walls of vascular plants but not to such a marked degree, since the number of grams of acid hydrogen liberated ranged only from 0.015 to 0.035 per 100 g. of dry matter. The cell walls of the sphagnums and other plant parts thus have the power to break up salts, removing the base and liberating the acid. It is supposed that this reaction is due to the negatively charged colloidal substances of the cell walls which absorb the cation and set free the anion, thus causing an acid reaction in the exterior medium. Skene found that the different types of sphagnum with which

he worked did actually utilize in growth the cations thus absorbed. Since plant cell walls in general exhibit this same property, although to a slighter degree, he suggested that the absorption of inorganic compounds by the root hairs and the epidermal cells of the root might take place in a similar manner (see also Dufrenoy, 1920).

Denny and Youden (1927) observed that when tissues of potato tubers, carrot roots, apple, whole seeds of corn, rye, and wheat came in contact with a tenth-normal solution of CaCl_2 the solution soon became acidified and within an hour might increase as much as twentyfold. They showed that this increase in H ions was not due to the unequal rôle of absorption of anions and cations by the tissue, since they found that similar acidifications were produced by adding the salts to the water extract obtained by bringing the tissues in contact with water instead of the salt solution. In these cases, the salt came in contact not with the tissue itself but only with the soluble substances that leached out of the tissue. It was further found that the non-coagulable, non-colloidal, and non-protein portions of the water extract underwent acidification upon the addition of salts, giving results analogous to those obtained by bringing the salts in contact with the tissues themselves. They further found that increases in H-ion concentration were obtained when salts were added to various organic acids such as malic, oxalic, succinic, aspartic, and others. The precipitation of insoluble salts of these acids with the resulting increase of the ionization of the remaining acid was shown to account in part for this development of acidity on adding solutions to organic acids, although acidifications were observed in cases where no precipitation occurred. They concluded, therefore, that the observed changes in hydrogen-ion concentration cannot be interpreted as indicating an isoelectric point for the tissue as a whole nor furnish proof that reaction has occurred between the ions of the salt solution and proteins with characteristic isoelectric points. The findings of Denny and Youden are in contrast to those of Rudolfs (1925), who found that when seeds were immersed in representative salt or acid solutions they were able to change the hydrogen-ion concentration of the solutions to definite points and that a certain equilibrium was reached in all solutions after the seed had been immersed for a sufficient period of time. He considered that the chemical properties of the chief protein constituent of the seeds seemed responsible for the changes in the hydrogen-ion concentrations of the solutions.

The effect of the unequal absorption of ions upon the external medium has been especially studied in the case of cultural solutions. Redfern (1922) noted that the cultural medium in which corn and peas were grown remained neutral, although the cations were absorbed to a much greater degree than the anions. Hoagland (1923) found that single solutions of ammonium salts, K_2SO_4 , Na_2SO_4 , and KH_2SO_4 in which barley, peas, and

cucumbers were grown generally increased in acidity. When barley, however, was grown in solutions of $\text{Ca}(\text{NO}_3)_2$, CaCl_2 , $\text{Mg}(\text{NO}_3)_2$, NaNO_3 , $\text{Ca}(\text{HPO}_4)_2$, $\text{Mg}(\text{H}_2\text{PO}_4)_2$, or NaH_2PO_4 the actual acidity tended to decrease. In the case of any nitrate (except ammonium) the solution generally attained a reaction very close to neutrality. The changes of reaction of certain salt solutions are not always the same in different experiments. Thus, for example, Hoagland (1923) noticed in one experiment that even a slight shading of barley cultures markedly diminished the rate of increase of acidity in a K_2SO_4 solution. After a short period of growth, the cultures nearest the window had a P_H value of 4.0 and those at the opposite end of the row a P_H value of 5.7. Haas and Reed (1926) considered that the changes in reaction of cultural solutions in which citrus seedlings were grown could be attributed directly to unequal absorption of ions together with the excretion of certain ions by the plants. In a complete nutrient solution, citrus seedlings in some cases brought about in a comparatively short period such a high concentration of H ions as to be injurious to the roots, but acidities greater than P_H 3.0 to 3.2 were not observed to develop. In the case of walnut seedlings the acidity of the residual solution was entirely dependent upon the absorption rate of the two ions employed. In solutions of potassium phosphate with initial hydrogen-ion concentrations of P_H 5.0 and lower, the preferential absorption of K by wheat seedlings resulted in increased acidity. In solutions with initial hydrogen-ion concentrations of 6.0 and 7.0, the increase in acidity was slight owing to the buffer properties of the solutions (Davidson, 1927).

C. INTERCHANGE OF IONS FROM THE PLANT TO THE EXTERIOR SOLUTION

When the unequal absorption of ions occurs, it frequently happens that the more absorbed ion is replaced by the diffusion outward from the plant of some other ion or ions of the same sign. This interchange of ions thus tends to keep the medium in which the plant is growing from becoming either acid or alkaline in its reaction to any degree. Thus Redfern (1922) found that when corn and peas were grown in a solution of CaCl_2 it remained neutral in its reaction, although the calcium ions were absorbed greatly in excess of the chlorine ions. Potassium and magnesium, however, were found in appreciable quantities in the external medium, having diffused out from the roots, and it was considered that this interchange of bases caused the solution to remain neutral in spite of the unequal absorption of the calcium and chlorine. In the case of barley growing in single salt solutions (Hoagland, 1923), Ca and Mg diffused outward as K was removed. When calcium salts were used, K and Mg entered the solution from the plant. Thus in one case where the plant absorbed the K ions from a K_2SO_4 solution to the extent of 1.44 milli equivalents, the calcium and magnesium ions entering the solution

amounted to 0.50 and 0.53 milli equivalents, respectively. In another case where a $\text{Ca}(\text{NO}_3)_2$ solution was used the absorption of the calcium ions amounted to 1.66 milli equivalents, and the K and Mg ions entering the solution amounted to only 0.09 and 0.20 milli equivalents, respectively. The anion HCO_3 , according to Hoagland (1923), is the one, at least, which most abundantly replaces the anions that have been more abundantly absorbed. For example, in his experiments with barley growing in the solution of CaCl_2 , the absorption of the cation amounted to 0.83 milli equivalents and the anion to 2.06 milli equivalents, while the amount of the HCO_3 ions diffusing into the external solution equaled 1.26 milli equivalents. In the case of a solution of calcium nitrate, the cations were absorbed to the extent of 1.66 milli equivalents and the NO_3 ion to the extent of 5.48 milli equivalents. The amount of HCO_3 ions that enter the exterior solution totaled 4.12 milli equivalents. Apparently, there has been no really satisfactory explanation advanced for the mechanism concerned in the interchange of ions between the plant and the external solution.

D. FACTORS THAT INFLUENCE THE UNEQUAL ABSORPTION OF IONS

The absorption and exchange of ions by a plant are influenced by a wide variety of conditions. Some of these are the concentration of the solution, the effect of one ion upon the absorption of another, the nature and concentration of the ions present, temperature, light, and numerous others.

1. Concentration of the External Solution.—The concentration of the solution has a marked influence upon the proportion of ions absorbed. For example, Redfern (1922) noted that peas growing in tenth-normal solution of CaCl_2 absorbed 17.7 per cent of the calcium and 3.6 per cent of the chlorine in 36 hr., while in a thousandth-normal solution of the same salt during the same time they absorbed 23.1 per cent of the cation and 15.1 per cent of the anion. The relative absorption of ions by storage tissue is also influenced by the concentration of the solution, as is shown by the following experiments with carrot (Stiles, 1924):

Initial concentration of solution, normality	NH ₄ Cl, percentage of absorption		NaCl, percentage of absorption	
	48 hr.			
	Cation	Anion	Cation	Anion
1/10	12.9	5.9	25.2	8.3
1/100	57.2	32.2	36.1	15.8
1/1,000	97.1	80.7	38.1	22.8

These figures indicate that the two ions of the salts used tend to be absorbed more nearly equally as the concentration of the solution decreases.

2. The Influence of One Ion upon Another.—The topic here under discussion refers only to ions in dilute solutions which are not toxic to the plant and should not be confused with the subject of antagonism which has to do with the influence of one ion on another in overcoming the toxic effect of solutions on plants.

Ions differ greatly in the rapidity with which they are absorbed. The initial rate of absorption of ions may be in a different order from that which prevails when equilibrium is reached. Thus Stiles and Kidd (1919) found that the cations with which they worked were absorbed initially by storage tissue after the following order: K, Ca, Na, Li, Mg, but when equilibrium was approached the order of absorption was K, Na, Li, Ca, Mg. The absorption of anions under the same conditions was initially in the order SO_4 , NO_3 , Cl, but this later gave way to the order NO_3 , Cl, SO_4 .

Of the cations, potassium seems to be the most rapidly absorbed in practically all cases observed (Haas and Reed 1926), while calcium probably is the least absorbed. Of the anions NO_3 is the most rapidly and abundantly absorbed, while the SO_4 ion has been observed by practically all workers to be the most slowly absorbed. In the majority of cases that have been observed, the cations have been absorbed in greater amount than the anions. The main exception has been NO_3 and sometimes the chlorine anion.

Hoagland (1923) and Haas and Reed (1926) have noted especially the effect of one ion upon the absorption of another. This effect occurs whether the ions have like or unlike electrical charges, and all three types of relations are involved: cation to anion, cation to cation, and anion to anion. In the case of barley (Hoagland, 1923), the slowly absorbed sulphate ion decreased the rate of absorption of the associated cations. Thus potassium was absorbed much more rapidly from the nitrate and the chloride than from the sulphate. The absorption of cations was always greatest when they were accompanied by an anion like NO_3 that is rapidly absorbed (Haas and Reed, 1926). The presence of sodium decreased the rate of absorption of other cations especially potassium and calcium in the case of barley, citrus, and walnut plants. Potassium ions retarded the absorption of calcium in the case of citrus seedlings. When the potassium in the culture solution was low in amount, more calcium, magnesium, and phosphate were absorbed from the solution than when it was abundant. The work of Haas and Reed (1926) with citrus and walnut seedlings indicated that the amount of chlorine absorbed stood in the following order with respect to the accompanying cation: Ca, K, Na, Mg. With barley plants Hoagland (1923)

observed that the order of absorption for chlorine was K, Na, Mg, Ca. The presence of chlorine seems to retard the absorption of nitrate, but other ions seem to have little effect upon its absorption. It has been observed that the nitrate ions penetrate more readily from an acid solution than from an alkaline one in experiments with *Nitella* (Hoagland and Davis, 1923). In the case of experiments with barley (Hoagland, 1923), evidence was obtained which indicated that from an alkaline solution cations were absorbed to a greater extent than anions. True and Bartlett (1915, 1916) found that the seedlings of *Lupinus albus* absorbed more salts from the mixtures of the nitrates of K, Ca, and Mg than from equally concentrated solutions containing only one or two of these nitrates. The solutions, however, of the three nitrates which were most favorable to absorption were much inferior to corresponding solutions in which the three anions H_2PO_4 , NO_3 , and SO_4 were present. It was observed by Hoagland, Davis, and Hibbard (1928) that the accumulation of Br ions in the cell sap of *Nitella* was significantly retarded by Cl or I ions also present in the cultural medium but was not retarded by SO_4 , NO_3 , or PO_4 ions. The accumulation of Br ions was definitely influenced by the nature of the cation, being most rapid when solutions of KBr or RbBr were used and least rapid with solutions of LiBr, $CaBr_2$, $SrBr_2$, and $MgBr_2$.

3. Other Factors.—The effect of light on the absorption of ions by the barley plant has been studied by Hoagland (1923). During the absorption period a part of the plants were left in the light and a part placed in darkness. The concentration of all the ions in solution except K and PO_4 was increased to a greater extent in light than in the dark. In the case of the two ions mentioned, there was a decrease of concentration in the solution in the light, although more water was transpired. The relation of the amount of water absorbed to the intake of different ions is of much interest. Hoagland grew two sets of barley plants under such conditions that the amount of water absorbed by one set was practically twice that absorbed by the other. The results may be summarized by the following table:

Concentration	Milli equivalents						Water absorbed, cc.
	K	Ca	Mg	NO_3	PO_4	SO_4	
Initial.....	4.5	8.0	4.4	11.4	1.3	7.2	
Final.....	1.5	12.5	7.3	9.5	0.4	18.5	505
Final.....	3.2	9.6	5.2	9.7	1.4	13.1	265

The cultural solution thus became more concentrated with respect to certain ions and more dilute with respect to others as the absorption of

water was increased. The ions which regularly increased in concentration were Ca, Mg, and SO_4 , while K and NO_3 decreased in concentration. The ions thus are not removed from the solution by the plant in the same proportion as water. Under some conditions at least, K, NO_3 , and PO_4 ions may be removed from the solution at a greater rate than water, while at the same time Ca, Mg, and SO_4 ions may be removed less rapidly than water. On this account, therefore, as the plant absorbs water and ions, the solution may become more dilute with respect to certain ions and more concentrated with respect to others.

The amount of any ion absorbed is not strictly related to the amount present in the plant, since in certain cases the phosphate and nitrate ions are rapidly absorbed, although the plant parts concerned are very rich in these ions. The rate of absorption of ions is not related to their velocities or any other of their physical chemical properties so far as they are known. Since the absorption of ions depends upon light, temperature, humidity, concentration and reaction of the solution, the amphoteric character, amount, and kind of protein present, and the kinds of ions present, it is a complex problem to handle experimentally and no two experiments will give the same results unless every condition is identical.

IV. TRANSPIRATION AND THE INTAKE OF SALTS

Previous to 1914 the evidence was very confusing in regard to the relationship between the rate of transpiration of a plant and the amount of solutes taken up from the soil. It was considered by Schloesing (1869), Kohl (1886), Sachs (1887), Wollney (1898), Burgerstein (1897), Pfeffer (1900), Jost (1907), and others that the amount of solute taken up by the plant from the soil is proportional to the amount of water transpired. Their conclusions, however, were in most cases based on purely theoretical grounds, although in a few cases they were based on very meager and fragmentary experimental evidence. On the other hand, Ilienkov (1865), Fittbogen (1873), and Haberlandt (1892) concluded also from a small amount of experimental evidence that there is no relation between transpiration and the quantity of mineral nutrients absorbed from the soil. The example of plants growing in the tropics has been frequently presented to substantiate the view that the transpiration rate under the conditions existing there is very low as compared to that of the temperate regions, yet the intake of salts is apparently abundant. There seems, however, to be insufficient evidence to prove that such a low rate of transpiration exists as is evidenced by the contentions of Haberlandt (1897), who considers that the rate of transpiration in the tropics is lower than in central Europe, and Burgerstein (1897), Stahl (1894), and Giltney (1897), who claim that the plants in the tropical rain forests transpire more than those in a temperate region such as Europe.

Beginning with Hasselbring (1914), well-controlled and rather extensive work has been conducted by Kiesselbach (1916), McLean (1919), Muenschler (1922), and Mendiola (1922) to determine the influence of the amount of transpiration upon the quantity of minerals in the plant. The method used, in general, has been to determine the ash content of plants whose rate of transpiration has been made to vary by changing the environmental conditions.

Hasselbring (1914) working in Cuba grew tobacco in large containers under field conditions and under the shelter of cheesecloth after the manner that is used in growing certain qualities of tobacco. Under the cheesecloth shelter the total light was reduced by one third from that of the open. The temperature of the two stations showed practically no difference, but during the daylight hours the relative humidity under the shade was higher than that in the open. The shading used in this experiment did not diminish the production of total dry matter, but the leaves of the shade-grown plants had a much greater total area than those of the plants grown in the open. The following table gives a summary of the results obtained by the experiment, the figures representing the average for six plants:

Total dry weight, grams	Total water absorbed, cubic centimeters	Total ash in plants, grams	Water absorbed per gram of ash, cubic centimeters
188.4	Plants grown in the open 46,344	18.3	2,548
188.1	Plants grown in the shade 36,187	21.1	1,718

The plants in the open transpired nearly 30 per cent more water than those growing under the shelter, while the transpiration rate per unit of leaf surface was nearly twice as great for the plants in the sun as those growing in the shade. As indicated by the table, however, the plants that transpired the greater quantity of water contained the smaller amount of ash in percentage of the total dry matter and in absolute amount. Hasselbring, therefore, concluded that the absorption of salts is independent of the absorption of the water and that an accelerated transpiration rate does not exert an accelerating effect on the entrance of salts.

Kiesselbach (1916) studied the relation of transpiration to the ash content of corn grown under different climatic conditions in soils of different degrees of fertility and moisture content. The data obtained from growing plants in a dry and a humid greenhouse may be taken as an example to represent the effect of climate upon the relation of transpira-

tion to the intake of salts. If the evaporation in the dry greenhouse be taken as 100 per cent, then that in the humid greenhouse would be only 54 per cent. Popcorn and Hogue Yellow Dent were the two varieties used.

Content	Popcorn			Hogue Yellow Dent corn		
	Dry greenhouse	Humid greenhouse	Ratio dry to humid	Dry greenhouse	Humid greenhouse	Ratio dry to humid
Dry weight per plant, grams	67.9	71.9	100.9	90.5	
Ash content per cent, dry basis	12.28	11.91	100:97	13.6	12.22	100:94
Total weight of ash, grams	8.34	8.56	100:102	13.18	11.06	100:84
Water transpired per plant, cc.	24,279.0	14,304.0	100:59	33,640.0	19,067.0	100:57
Water transpired per gram of ash cc.	2,910.0	1,670.0	100:57	2,550.0	1,720.0	100:67

These data indicate that there is no relationship between the amount of water transpired and the amount of ash in the plant. Kiesselbach noted that the greater the availability of the soil solutes the greater was the total amount of solute taken into the plant and the greater the amount taken in per unit of water transpired. Less water was transpired per gram of ash content in a relatively low soil saturation than where an abundance of water was present. Kiesselbach observed considerable variation in the ash and transpiration relationships of different corn varieties but considered that there is no absolute correlation among the percentage of ash, the quantity of water transpired per gram of ash, or the transpiration per gram of dry matter, a conclusion also reached by Mendiola (1922) in regard to tobacco plants grown in Pfeffer's nutrient solution under humid and dry conditions. Milo and Black Amber sorghums transpired a slightly smaller quantity of water per gram of ash than did corn, while sunflower plants transpired much more water per gram of ash content. McLean (1919) found that leaves taken from plants growing in the tropical rain forests of Brazil showed a higher ash content than sun plants. He assumed that the transpiration rate is lower for the leaves of the rain forest and considered, therefore, that the absorption of the mineral salts is independent of foliar transpiration.

Muenschler (1922) grew barley plants for five weeks in Knop's solution under conditions of high and low transpiration. He reduced the transpiration rate by increasing the humidity of the atmosphere, by reducing the light intensity by shading, and by increasing the concentration of the nutrient solution. It was found that the ash content expressed in

percentage of total dry weight of the plants varied but slightly, regardless of whether the plants were grown under conditions of high or low transpiration and irrespective of how transpiration was reduced. The effect of reduced transpiration upon the total ash content, however, expressed in grams depended upon how transpiration was reduced. With a uniform concentration of nutrient solution the ash content of the barley plants varied but slightly even though the quantity of water transpired was reduced to less than one half by increasing the humidity of the atmosphere. In the case of plants, however, in which the transpiration was reduced to less than one half by shading and the photosynthetic activity was also reduced, the total ash content was correspondingly reduced. When the total transpiration was reduced by increasing the concentration of the nutrient solution, the total ash content was only slightly reduced. Muenscher considered that his results indicated that there is little or no relation between transpiration and the absorption of salts in barley plants. He considered, however, that the amount of food available for growth, in which process salts are used, is a very important factor in determining the quantities in which and the rapidity with which the essential salts enter the plant.

It seems to be well established that the solutes enter a plant independently of the entrance of water. A simple observation by Scofield (1927) will serve further to illustrate this point. He found that barley and wheat seedlings absorbed during a 24-hr. period a quantity of water equivalent to the original volume of the cultural solution, while at the end of that period the residual solution contained from 78 to 91 per cent of the salts originally present (see also Hoagland, 1923). Since plants do not absorb water and dissolved substances from the soil in the same proportion as these constituents occur in the solution, it is difficult to understand how transpiration may in any way influence the amount of salts in the plant. It is considered by many that the water current set up through the conducting elements in the stem is a factor in carrying the dissolved salts to the leaves. Presumably then, the more rapid the transpiration, the more rapid the current and the more salts thus translocated. However, as Muenscher (1922) states, it must be borne in mind that although an upward current of water apparently exists, the existence of a transpiration stream in the sense of mass movement of a solution in normally growing plants has not yet been demonstrated.

V. NUTRIENT SOLUTIONS

It is impossible to study in any definite manner the nutrient requirements of a plant when it is growing in the soil, since by the present known methods the soil solution cannot be controlled, analyzed, or varied with any degree of satisfaction. A water solution offers the best known means to study in a quantitative way the nutritional needs of the plant. Nearly

all the cereals, beans, peas, buckwheat, and many other plants lend themselves favorably to growth in such solutions, in spite of the unusual conditions in which their roots are placed. The solutions that are thus used have been termed "nutrient" or "cultural solutions" or "water cultures." When plants are grown in pure sand to which the solution has been added, the medium is called a "sand culture." For quantitative work, however, the water culture has proved the most satisfactory. A nutrient or cultural solution is generally defined as one that contains all the essential elements in the form of salts that a plant absorbs from the soil. A solution that does not contain all the essential elements is sometimes termed a cultural solution, but it is generally inferred when the term is used that the solution contains all the known essential elements that the plant obtains from the soil.

A. HISTORICAL

The earliest recorded experiment with water cultures was that of Woodward (1699) who grew plants in spring, river, rain, and distilled water to determine whether it was the water or solid particles of the soil which nourished the plants. Very little additional study, however, was made in this regard until Sachs, Knop, and Nobbe from 1859 to 1865 developed the general procedure in water cultures that is in use at the present time. Sachs (1860) published the first standard formula for a culture solution for plants, and in 1865 Knop proposed a solution which has been one of the most widely used in the study of plant nutrition. Other nutrient solutions have been proposed by Tollens (1882), Schimper (1890), Pfeffer (1900), Crone (1902), Tottingham (1914), Shive (1915), Hoagland (1920), and many others. From 1859 to 1900 the preparation of nutrient solutions and the methods for their use were well established. By their use during that period ten of the essential elements for plant growth were determined. It was found that the concentration of the standard solutions that were used could vary in concentration of total salts from 0.1 to 0.6 per cent and yet produce an optimum growth of the plants provided that the solutions were frequently renewed. The proportions of the different components of these solutions varied greatly, and it was considered that these had little apparent influence upon the growth and development of the plant, provided that a sufficient quantity of salt was present for the plant's needs.

From 1900 to the present time the investigations of cultural solutions have been characterized by a study of the effects of the physical as well as the chemical properties of the nutrient solutions upon the growth of the plant (Livingston, 1900). In this regard the osmotic properties of the solutions have been especially considered. The relationship to growth of the proportion of salts in the solution has been extensively studied, as has also the effect of light and temperature upon the relative value of different solutions for plant development. It has also been found that the unequal absorption of ions of a given salt may have a marked effect upon the reaction of the nutrient solution. Finally, a thorough reinvestigation is in progress to determine the number of elements that are essential to the life of the plant and the function they subserve in its metabolism.

B. KINDS

It is the intention to present here only a few of the many formulae for nutrient solutions. Others may be obtained by consulting Tottingham (1914), Tollens (1882), and Schimper (1890).

Sach's solution (1860), grams		Knop's solution (1865), grams		Pfeffer's solution (1900), grams		Crone's solution (1902), grams	
KNO ₃	1.00	Ca(NO ₃) ₂	0.8	CaNO ₃	0.8	KNO ₃	1.00
Ca ₃ (PO ₄) ₂	0.50	KNO ₃	0.2	KNO ₃	0.2	Ca ₃ (PO ₄) ₂	0.25
MgSO ₄	0.50	KH ₂ PO ₄	0.2	MgSO ₄	0.2	MgSO ₄	0.25
CaSO ₄	0.50	MgSO ₄	0.2	KH ₂ PO ₄	0.2	CaSO ₄	0.25
NaCl.....	0.25	FePO ₄	Trace	KCl.....	0.2	FePO ₄	0.25
FeSO ₄	Trace	H ₂ O.....	1,000 cc.	FeCl ₃	Small amount	H ₂ O.....	1,000 cc.
H ₂ O.....	1,000 cc.			H ₂ O.....	1,000 cc.		

The nutrient solutions used prior to 1914 varied greatly in their total concentration and in the proportion of the ions present (Tottenham, 1914). The total concentration of salts ranged from 0.1 to 0.5 per cent, while the ratio of K to Mg varied from 1:1 to 5:1, that of Ca to Mg from 2:1 to 3:1, that of nitrate to phosphate from 3:1 to 10:1, and that of nitrate to sulphate from 1.3:1 to 7:1.

In 1914 Tottenham, using Knop's solution as a basis, began an investigation to determine the influence of a wide range of variations in the proportions of the components of this solution. Three different total concentrations were used having on a percentage basis a concentration of 0.01, 0.6, and 2 per cent and an osmotic pressure of 0.05, 2.5, and 8.15 atmospheres, respectively. In each of these concentrations the approximate osmotic pressure was divided into 10 equal parts and these 10 parts were distributed among the four component salts of the solution. This arrangement gives for any given concentration of solution 84 solutions each having the same osmotic pressure but no two of them containing the same relative proportion of salts. Tottenham found that the solution having the total concentration of 0.6 per cent or 2.5 atmospheres osmotic pressure gave the best growth for wheat in the seedling stage. The best combination of the 84 solutions in this series as judged by the dry weight of tops produced in the experiment was T3R1S4, in which the salts were distributed as follows:

Tottenham's best combination of Knop's solution



For iron two drops of a suspension containing 0.0024 gr. of ferric phosphate per cubic centimeter was added to each liter of solution at the time of renewal. The nutrient solutions used prior to 1915 contained, excluding the iron, at least four different salts. When the effect upon growth of the various proportions of these salts in solutions of this type is to be studied, the number of possible combinations becomes large and thus renders the experiment very tedious and cumbersome. Thus, as has been mentioned, if the osmotic pressure of a four-salt solution is distributed in tenths, there are 84 different combinations possible. If the number of salts in a solution could be reduced to three and the osmotic pressure distributed in tenths, the experiment would employ only 36 combinations. If this type of solution could be used, the experimental work would be greatly simplified and more rapid determinations could be made. If a two-salt solution could be used, only nine combinations would be possible on the basis that has just been mentioned. This, however, is impossible, since six elements at least are required in every nutrient solution and only two of these can be carried by any single salt.

In 1915 Shive carried on experiments with a three-salt solution. The KNO₃ was omitted from the Knop's formula, the solution being composed of the three salts monopotassium phosphate, calcium nitrate, and magnesium sulphate and a trace of ferric phosphate and thus containing all the elements of the four-salt solution. Shive

experimented with three different total concentrations of this three-salt solution, the osmotic pressures of which amounted to 0.1, 1.75, and 4.0 atmospheres, respectively. For each of these three total concentrations, 36 different proportions of the three component salts were tested. It was found that the solution with an osmotic pressure of 1.75 atmospheres was the optimum one of the three for the growth of wheat and buckwheat plants. The production of dry matter by plants growing in this solution was equal to or greater than that produced by plants growing in any of the four-salt solutions. For the growth of young wheat plants Shive found that the solutions *R5S2* and *R3S3* were the best as determined by the production of dry matter. The following are the formulae for these best three-salt solutions:

Best solution		Next best solution	
<i>R5S2</i>	<i>R3S3</i>	
KH_2PO_4	0.0180 <i>M</i>	KH_2PO_4	0.0108 <i>M</i>
$\text{Ca}(\text{NO}_3)_2$	0.0052 <i>M</i>	$\text{Ca}(\text{NO}_3)_2$	0.0078 <i>M</i>
MgSO_4	0.0150 <i>M</i>	MgSO_4	0.0020 <i>M</i>

Ferric phosphate 0.0044 g. per liter of solution.

Because of the simplicity of their preparation and the ease of manipulation in experiments, three-salt solutions of various types have practically superseded the four-salt solutions in the study of plant nutrition. A three-salt solution, however, has the disadvantage that if the proportion of one ion or radical of a salt is altered, the other ion of the salt is changed in a like proportion, so that the effects of an individual ion cannot be so well studied as in a four-salt solution. Six types of three-salt solutions are possible in order to supply K, P, Ca, Mg, S, and N to plants. These have been numbered and catalogued by Livingston and Tottingham (1918) and are now commonly called by their serial number when discussed in experimental work in plant nutrition. They are arranged as follows:

I	II	III	IV	V	VI
$\text{Ca}(\text{NO}_3)_2$	$\text{Ca}(\text{NO}_3)_2$	$\text{Ca}(\text{H}_2\text{PO}_4)_2$	$\text{Ca}(\text{H}_2\text{PO}_4)_2$	CaSO_4	CaSO_4
KH_2PO_4	K_2SO_4	KNO_3	K_2SO_4	KNO_3	KH_2PO_4
MgSO_4	$\text{Mg}(\text{H}_2\text{PO}_4)_2$	MgSO_4	$\text{Mg}(\text{NO}_3)_2$	$\text{Mg}(\text{H}_2\text{PO}_4)_2$	$\text{Mg}(\text{NO}_3)_2$

Solution III was tested by Livingston and Tottingham and found to be as good as solution I (Shive's) for the growth of wheat seedlings.

In the soil many of the plant nutrients are present only in relatively small amounts in the soluble form, although there is generally a considerable reserve in the form of compounds that are only slightly soluble. In order to have a nutrient solution in which the available nutrients would more nearly approximate the concentration in the soil, Duggar (1920) used as nearly as possible salts that are quite insoluble. As a source for calcium he used CaSO_4 , CaCO_3 , $\text{Ca}_3(\text{PO}_4)_2$, CaHPO_4 , while for magnesium MgCO_3 and $\text{Mg}_3(\text{PO}_4)_2$ were used and iron was supplied in the form of FePO_4 and ferric citrate. The plants grew in the cultures with these salts just as vigorously as when the more soluble salts were used. Hoagland (1919) used nutrient solutions of various concentrations which were so constituted as to give approximately the same relation between the more important ions as that found in the water extract of soils at the time when the crop was actively absorbing. It was found that solutions with total concentrations ranging from 0.48 atmosphere to 1.45 atmospheres gave

very similar results if renewal was frequent. The following solution was found by Hoagland (1920) to be as favorable for the growth of young barley plants as Shive's R5S2 solution:

Ions	Ppm.	Ions	Ppm.
K.....	190	PO ₄	117
Ca.....	172	NO ₃	700
Mg.....	52	SO ₄	202

C. TECHNIQUE

It is the intention here to discuss only in a broad and general manner the methods of procedure in experimental work with nutrient solutions. The detailed directions can be found by consulting Livingston, Crocker, and Kellerman (1919) and the other references herein mentioned. Various methods can be used for obtaining the seedlings necessary for the experiment, the method of procedure depending to a great extent upon the kind of seeds that are to be germinated. For the cereals and some other seeds the following method has given very satisfactory results: The seeds are soaked in water for 5 or 6 hr. and then placed upon a germination net which consists of ordinary mosquito netting that has been dipped quickly into melted paraffin of a high melting point so that the threadwork of the network is covered but the meshes still remain intact. The treated netting is tied as tightly as possible over the top of any wide-mouthed vessel or jar so that when the jar is filled with water or solution the surface practically coincides with the plane of the net. For ordinary demonstration experiments tap water may be used in the germinating vessel but for exact work a cultural solution should be used in order to avoid a too abrupt change when transferred from the germination container to the cultural vessel. The solution in the germination vessel should be changed frequently, preferably daily, by adding fresh solution through a glass tube that extends to the bottom of the container. The control of the temperature during germination is desirable and may be obtained by a water bath or any other means available to the experimenter. The germination jar should be placed in diffuse daylight until the seedlings have reached the desired stage of growth (see also Livingston, 1906). After the choice of the seedlings for the cultural experiment has been made, they are lifted from the net, preferably by paraffined forceps, and placed in a glass vessel containing a germination solution 2 cm. in depth so that the roots are in the solutions and the shoots above its surface. The seedlings are thus taken from the vessel one by one as needed to be placed in position in the cultural jars, care being taken to avoid contamination.

The best cultural vessels are wide-mouthed glass jars, the ordinary Mason fruit jars of pint, quart, or 2-qt. capacity, being especially adapted for that purpose. Many different arrangements have been used for closing the cultural vessels and for supporting the plants growing therein. One of the most common methods is to use corks of the flat form about $\frac{1}{2}$ in. thick which have been thoroughly impregnated and lightly coated with paraffin. The desired number of holes about 3 cm. in diameter are made through the cork at convenient locations, as described by Tottingham (1914). The young plants are placed in position in these holes and held firmly just above the seed by means of ordinary cotton, which remains dry and becomes compressed as the stem enlarges. The cultural vessels should be filled with nutrient solution so that when the corks are tightly forced into position they will be within 1 to 2 cm. of the surface of the solution (see Livingston, 1906). If the growing plants require support, uprights of light glass or wooden rods anchored to the cork may be used. It is

desirable that the uprights be light, but substantial, easily attached, and interfere as little as possible with the handling of the cultural vessels. McHargue (1923) has devised two methods of supports for the larger sand- or water-cultural vessels. In one case, four sockets made from galvanized iron into which wooden uprights may be fitted are placed equidistant around the top of the jar and held tightly in place by means of wire tightly twisted around it. In the other case, the earthenware cover is perforated in the central portion in numerous places in which the plants are held by cotton, while around the edge of the cover equally distant from each other are four holes in which light wooden supports can be tightly fitted. Perforated paraffin disks may also be used, according to Hammett (1928).

In order to make a comparative study of water cultures it is necessary that all plants be exposed to as nearly the same atmospheric conditions as possible. If the cultures are grouped in a given area, the plants shade each other so that they do not all receive the same amount of light. The transpiration loss of some plants is thus reduced and perhaps also their photosynthetic rate. The unequal atmospheric conditions may be overcome in part by changing the position of the plants at numerous intervals. This, however, requires close attention and a great amount of labor and is at the best unsatisfactory. One of the most convenient methods so far devised for placing the cultures under the same conditions is that used by Shive (1915). The plants are placed on the edge of a slowly revolving circular table approximately 4 ft. in diameter which makes a revolution every 4 min. and is continuously rotated during the time of the experiment except when stopped for short intervals for the renewal of solutions. By this means all the plants in the cultural solution are exposed to approximately the same light, heat, and cultural conditions. Trelease (1925) has devised a chamber with thermostatic control and a rotating table for plant cultures.

1. Renewal.—A common practice in water-culture experiments is to renew the solution at intervals of three days or, more generally, to remove the plants from the solution and place them in a fresh solution in clean containers. The vessels that have been used are emptied, cleaned, and then refilled at the next change. This method, however, is subject to criticism because it introduces several errors which could be entirely or at least partially overcome if the nutrient solution could be continually renewed. In the first place, if the nutrient solution is relatively dilute, the lack of an optimum amount of a given nutrient might be a limiting factor to growth if the solution were not renewed except at the intervals that have been mentioned. If a study is being made of the effect of a certain strength of solution upon plant growth, it is evident that a certain strength of concentration will not long continue unless a constant renewal is made, since the loss of water by transpiration continually increases the concentration of certain salts, at least in the solution, because they are not absorbed in the same relative amount as the water. In the third place, the influence of the organic compounds that arise from the cells that are lost from the root cap and the epidermis may have a detrimental influence upon the growing plants if allowed to accumulate for any period of time.

The depletion of oxygen and accumulation of carbon dioxide in the solution due to the respiration of the roots are factors to be considered as well as the disturbance of the physiological balance of the solution due to the unequal absorption of salts. Stiles (1915) observed with rye plants growing in cultural solutions that if the solutions were changed frequently so as to maintain more nearly a constant composition, the solution could vary over a considerable range without producing much effect upon the rate of growth as measured by the amount of dry matter produced within a given time. In the case of barley and wheat seedlings (Brenchley, 1916) growing in nutrient solutions, the improvement in growth was more marked in concentrations up to fifth normal when the solutions were changed frequently. Trelease and Free (1917)

investigated the effect of the renewal of solution upon the production of dry weight of the tops of wheat growing in Shive's best solution. The cultures ran for 41 days, and some of the results obtained were as follows:

Change	Dry weight, grams	Change	Dry weight, grams
Daily.....	1.243	After 2 weeks, then every 3 days.....	1.131
Every 3 days.....	1.012	After 1 month.....	0.654
After 1 week, then every 3 days.....	0.995	Not at all.....	0.621
Every 2 weeks.....	0.780		

In another experiment the culture solution was allowed to flow at the rate of one liter per day through the cultural jars which had a capacity of 250 cc. The results obtained were as follows:

	Dry weight, grams
Continual renewal.....	1.678
Changed every 3 days.....	1.222
Not changed at all.....	0.666

Soybeans grown in sand or water cultures with a continuous solution renewal of 1 l. of new solution per culture during each 24-hr. interval throughout the growing period always produced plants which were superior in every respect to those grown in cultures with intermittent solution renewal (Allison and Shive, 1923). Methods for supplying a continuous renewal of nutrient solution for water cultures have been described by Clark (1916), Trelease and Livingston (1922), and Johnston (1927), while a method for renewal of plant nutrients in sand cultures has been published by McCall (1916).

2. Aeration.—Various methods have been devised for the aeration of water and sand cultures some of which are described by Weatherwax (1916), Andrews (1920), and Allison (1921). One method that is frequently used is to pull a stream of air through the medium by use of a filter pump. Another is the drip method in which the cultural solution is replaced drop by drop, the fresh air supply being carried in, with, or by the drops. In the third case, partial aeration, at least, is secured by allowing a slow but steady flow of renewal solution into the cultural vessel. The benefits derived from aeration as measured by the amount of dry matter produced, height of plants, or their general vigor have been rather varied, which, however, is to be expected, since plants differ greatly in their oxygen demands when growing under natural conditions. Hall, Brenchley, and Underwood (1914) greatly increased the root and top growth of barley and lupine in water cultures by pulling a stream of air through the medium. Free (1917), however, in experiments with buckwheat growing in Shive's nutrient solution found that the degree of aeration of the cultural solution had no important influence on the growth of these plants. His results were verified by Stiles and Jorgensen (1917), who found that aeration of the nutrient solution increased the rate of

growth of barley growing in water cultures but that it had no effect on the growth of buckwheat under the same conditions. Pember (1917) noted that barley did not respond to aeration when grown in nutrient solutions that were renewed every two weeks. In experiments with corn plants, Beal (1918) and Andrews and Beal (1919) obtained much better growth in the aerated sand and water cultures than in the unaerated ones. In one case, the plants growing in the aerated cultures were 65 cm. in height as compared to a height of 46 cm. for the plants in the unaerated vessels. Aeration showed its effect upon the anatomy of the plant, since the intercellular spaces were smaller and the tissues more compact in those plants growing in the aerated cultures. Oats, mustard, and peas growing in nutrient solutions respond very favorably to aeration, as is shown by the work of Andrews (1921), who found that the height of plants growing in aerated solutions was twice as much and the dry weight in some cases five times greater than plants growing in solutions that were not aerated. In the case of soybeans, Allison (1921) and Allison and Shive (1923) state that the best plants with respect to health, vigor, and yield were always secured in the cultures with continuous solution renewal and with constant and thorough aeration of the medium. They also found that the continuous renewal of the nutrient solution did not alone maintain the supply of dissolved oxygen necessary for the maximum development of the plants and that the roots showed a much greater response to aeration than the aerial portions of the plant.

3. Preparation.—Since the method to be followed in the preparation of nutrient solutions will depend upon the type of solution to be used and the nature of the experiment, it will be impossible to give here anything but general methods of procedure. This perhaps can be best accomplished by giving in detail the methods to be followed in one or two specific cases. The first step in the preparation of nutrient solutions, especially if quantitative work is to be done, is to obtain salts of known purity either dry or containing a known amount of water. The next step is the preparation of stock solutions from which solutions of the desired composition and concentration may be made when desired. One of the greatest difficulties that has been experienced in the preparation of four-salt solutions and to some extent in three-salt solutions is to obtain a solution of the desired concentration and proportions and avoid any precipitate. In ordinary demonstration experiments with water or sand cultures, the formation of some precipitate is of small matter, but in a quantitative study it becomes an important factor and must be avoided. Tottingham (1914) in his work with Knop's solution found it best to employ the component salts in stock solutions, one part, *A*, containing only $\text{Ca}(\text{NO}_3)_2$ and the other, *B*, containing the other three salts. The maximum possible concentration without precipitation of part *B* for a period of 14 days at temperatures of 20 to 23°C. was found to be 10 per

cent when KH_2PO_4 was used and 9 per cent when K_2HPO_4 was used. This limits the concentration of solution A to 12.33 and 12 per cent, respectively. Tottingham found the maximum possible concentration of the complete Knop's solution without precipitation for a period of from three to four days at a temperature of 20 to 26°C. to be 2.8 and 2.2 per cent when KH_2PO_4 and K_2HPO_4 were used, respectively. It was found that the precipitate formed in unstable Knop's solution consisted almost entirely of CaSO_4 .

For a supply of iron a suspension of ferric phosphate, FePO_4 , of approximately 0.02 g. molecular concentration is generally recommended. A suspension of this type contains about 3 g. of FePO_4 per liter or 3 mg. per cubic centimeter. Enough of this preparation may be made to last for several years. Enough of this suspension should be added to each liter jar at each filling to give 3 mg. of FePO_4 . The general consideration of the iron supply in nutrient solutions is discussed under the heading of Iron in Chap. VI.

Five characteristics of a nutrient solution may be distinguished when its osmotic, ionic, and molecular relationships to plant response are considered: (1) the solution type or kinds of salt entering into the solution; (2) osmotic salt proportions, the division of the osmotic pressure of the solution into a definite number of parts, and their distribution among the salts in all the various proportions; (3) volume molecular salt proportions; when considered in its relationship to osmotic salt proportions it would mean that part of a volume molecular concentration of each salt that must be added to each solution to produce the osmotic proportion that is desired for that particular salt; (4) total volume molecular concentration or the total number of molecules of all kinds per liter; (5) the total osmotic concentration which is the resultant of the number of molecules and ions in the solution per liter. This calculated osmotic value or potential osmotic pressure is commonly expressed in terms of atmospheres. Due to ionization and in some cases also to hydration, the osmotic salt proportions and the volume molecular salt proportions of a solution will not vary proportionally from solution to solution. If a series of solutions are planned, therefore, so as to vary by definite increments of osmotic salt proportions, the volume molecular concentration will vary irregularly. The preparation of nutrient solutions for the study of their osmotic and salt relationships to plant growth, therefore, involves a rather tedious procedure and entails much care and labor if accurate and satisfactory results are to be obtained. In the case of a four-salt solution, if the osmotic pressure is divided into ten equal parts and distributed among the four salts in all the various proportions, 84 different solutions must be prepared. With a three-salt solution the same procedure requires the preparation of 36 different solutions. Let us here consider a yet more simple case in which the total osmotic pressure of one

atmosphere of a three-salt solution of type I is distributed in eighths among the three component salts KH_2PO_4 , $\text{Ca}(\text{NO}_3)_2$, and MgSO_4 in all the possible proportions. The molecular proportions of each of the salts and the partial molecular concentrations necessary to produce an osmotic pressure of 1.0 atmosphere for the 21 different solutions that are possible under this combination are given in the following table. This is taken from the *Report of the Committee of Biology and Agriculture of the National Research Council (1919)*.

The method by which the figures presented in this table were obtained for each solution was somewhat as follows: For example, in the case of solution R1S1, a solution was prepared containing $\frac{1}{8}$ g. molecule of KH_2PO_4 , $\frac{1}{8}$ g. molecule of $\text{Ca}(\text{NO}_3)_2$, and $\frac{6}{8}$ g. molecule of MgSO_4 . This solution was then diluted until its freezing point indicated a total osmotic pressure of 1.0 atmosphere. In a solution that has thus been diluted, the molecular proportion of each salt can easily be calculated

PARTIAL MOLECULAR CONCENTRATIONS AND MOLECULAR PROPORTIONS (OSMOTIC PROPORTIONS) OF KH_2PO_4 , $\text{Ca}(\text{NO}_3)_2$, AND MgSO_4 (TYPE I) IN 21 SOLUTIONS ALL HAVING A CALCULATED OSMOTIC VALUE OF APPROXIMATELY 1.00 ATMOSPHERE AT 25°C. BUT DIFFERING BY INCREMENTS OF ONE-EIGHTH IN SALT PROPORTIONS

Solution	Molecular proportions			Partial molecular concentrations necessary to produce the fractional pressures desired		
	KH_2PO_4	$\text{Ca}(\text{NO}_3)_2$	MgSO_4	KH_2PO_4	$\text{Ca}(\text{NO}_3)_2$	MgSO_4
R1S1	1	1	6	0.0027	0.0027	0.0161
S2	1	2	5	0.0025	0.0049	0.0123
S3	1	3	4	0.0024	0.0071	0.0094
S4	1	4	3	0.0022	0.0089	0.0067
S5	1	5	2	0.0022	0.0108	0.0043
S6	1	6	1	0.0020	0.0122	0.0120
R2S1	2	1	5	0.0053	0.0027	0.0132
S2	2	2	4	0.0049	0.0049	0.0099
S3	2	3	3	0.0047	0.0071	0.0071
S4	2	4	2	0.0045	0.0090	0.0045
S5	2	5	1	0.0041	0.0104	0.0021
R3S1	3	1	4	0.0076	0.0025	0.0101
S2	3	2	3	0.0072	0.0048	0.0072
S3	3	3	2	0.0068	0.0068	0.0045
S4	3	4	1	0.0065	0.0086	0.0021
R4S1	4	1	3	0.0099	0.0025	0.0074
S2	4	2	2	0.0094	0.0047	0.0047
S3	4	3	1	0.0090	0.0068	0.0022
R5S1	5	1	2	0.0123	0.0024	0.0049
S2	5	2	1	0.0118	0.0047	0.0023
R6S1	6	1	1	0.0145	0.0024	0.0024

from the original volume, and since the degree of ionization of each of the salts at that dilution can be obtained from prepared tables, the fractional molecular concentration of each salt necessary to produce the fractional osmotic pressure desired can thus be calculated. If, for example, at a given concentration the dissociation value is 50 per cent for a given salt, then the osmotic value of that salt is 1.5 times its molecular concentration so that the molecular concentration divided by 1.5 would give the molecular concentration necessary to produce the fractional osmotic pressure that is desired (see table, page 202).

In the next table is given the strength of stock solutions and the proportion of distilled water to make 1,000 cc. of each of the 21 nutrient solutions that have just been described.

NUMBER OF CUBIC CENTIMETERS OF DISTILLED WATER, AND OF THE SINGLE SALT-STOCK SOLUTIONS REQUIRED TO MAKE 1 L. OF EACH OF THE 21 NUTRIENT SOLUTIONS OF TYPE I WITH A TOTAL CONCENTRATION OF 1.00 ATMOSPHERE

Adapted from recommendations of Research Council, 1919

Solution	H ₂ O	KH ₂ PO ₄ , <i>M</i> 3.5	Ca(NO ₃) ₂ ·4H ₂ O, <i>M</i> 3.5	MgSO ₄ ·7H ₂ O, <i>M</i> 3.5
R1S1	924.7	9.45	9.45	56.4
S2	931.1	8.75	17.15	43.0
S3	935.85	8.4	24.85	32.9
S4	937.7	7.7	31.15	23.45
S5	939.45	7.7	37.8	15.05
S6	943.3	7.0	42.7	7.0
R2S1	925.8	18.55	9.45	46.2
S2	931.05	17.15	17.15	34.65
S3	933.85	16.45	24.85	24.85
S4	937.0	15.75	31.50	15.75
S5	941.9	14.35	36.4	7.35
R3S1	929.3	26.6	8.75	35.35
S2	932.8	25.2	16.80	25.20
S3	936.55	23.8	23.80	15.75
S4	939.80	22.75	30.10	7.35
R4S1	930.7	34.65	8.75	25.9
S2	934.2	32.9	16.45	16.45
S3	937.0	31.50	23.80	7.7
R5S1	931.4	43.05	8.4	17.15
S2	934.2	41.3	16.45	8.05
R6S1	932.45	50.75	8.4	8.4

4. The Triangle System in the Studies of Nutrient Solutions, Sand Cultures, and Fertilizer Experiments.—In the study of nutrition experiments dealing with a large number of cultures of different salt combinations it is desirable to employ some diagrammatic scheme or arrangement to represent concretely the various salt proportions and to interpret more easily the results obtained. The triangle method, which was sug-

gested by Schreinemocher (1893) and Bancroft (1902) for certain percentage experiments in physical chemistry, was first adapted by Schreiner and Skinner (1910) to nutrition experiments. Later the method was used by Tottingham (1914), Shive (1915), and McCall (1916) in both water- and sand-culture experiments and has now become the general method for interpreting the data obtained in that type of work. A summary of the method and its various applications has been given by Schreiner and Skinner (1918) and a critical review of the same has been made by Espino (1919).

As an example of the application of the triangle system let us here consider first the distribution of the 36 different combinations that are possible when the osmotic pressure of a three-salt solution is divided into




Fig. 11.—Diagram showing the 36 different combinations of a three-salt solution if the osmotic pressure is distributed in tenths among the three salts. (Redrawn from Shive in "Physiological Researches.") Description in the text.

tenths and proportioned in all the possible ways among the component salts. In Fig. 11, the distribution of the various proportions of type-I solution consisting of KH_2PO_4 , MgSO_4 , and $\text{Ca}(\text{NO}_3)_2$ is represented on the plane of an equilateral triangle according to the arrangement now in use for all three-salt solutions. The base of the triangle is considered as the K side, the left side as the Ca side, and the right as the Mg side. Each of the sides of the triangle is divided into seven equal parts and lines are drawn through each of these points parallel to each of the other two sides of the triangle. Each of the original points on the sides of the triangle and the points of intersection of the lines drawn represents one of the cultures under consideration. The base of the triangle and the lines parallel with it are numbered from the base, which is row 1 (R1), to the apex, which is row 8 (R8). The points of intersection are numbered as series (S) from the line on the left S1 to the extreme point on the right S8.

All the cultures on the base line in the case of type-I solution have one-tenth of their osmotic pressure due to KH_2PO_4 , all the cultures on R2 have two-tenths of their osmotic pressure due to KH_2PO_4 , and so on until R8, which has eight-tenths of its osmotic pressure due to that salt. In the first line on the left of the triangle S1, all the cultures have one-




FIG. 12.—Diagrams showing the 84 different combinations of a four-salt solution if the osmotic pressure is distributed in tenths. (Redrawn from Tottigham in "Physiological Researches.") Description in the text.

tenth of their osmotic pressure due to $\text{Ca}(\text{NO}_3)_2$, while in S2, two-tenths of the osmotic pressure is due to that salt, and so on until S8, where eight-tenths of the pressure is due to the $\text{Ca}(\text{NO}_3)_2$. The proportion of the osmotic pressure due to MgSO_4 at any points can be obtained by subtracting from ten the sum of the osmotic proportions of KH_2PO_4 and $\text{Ca}(\text{NO}_3)_2$ for that point. Thus, as an example, if a culture is at the point

R3S4 it has three-tenths of its osmotic pressure due to KH_2PO_4 , four-tenths to $\text{Ca}(\text{NO}_3)_2$, and three-tenths to MgSO_4 . It is also customary to designate the type of solution being used by placing the type number before the symbol of concentration. Thus *IIR4S3* signifies that the solution in question is type II and that four-tenths of the osmotic pressure is due to K_2SO_4 , three-tenths to $\text{Ca}(\text{NO}_3)_2$, and three-tenths to $\text{Mg}(\text{H}_2\text{PO}_4)_2$.

When a four-salt solution is under consideration and the osmotic pressure is distributed in tenths among the various salts, the representation by the triangle method becomes much more complicated, since 84 different combinations are possible. Figure 12 represents the schematic arrangement of the 84 combinations of Knop's solution as used by Tottingham (1914). For a procedure of this type seven triangles are necessary, the one, however, forming only a single point. The triangles are designated as *T1* to *T7* corresponding to the tenths of the total osmotic pressure due to KH_2PO_4 . The base of each of these triangles is the KNO_3 side, while the left and right sides are the $\text{Ca}(\text{NO}_3)_2$ and MgSO_4 sides, respectively. Taking any point as *T2R3S4* for an example, we know that two-tenths of the total osmotic pressure of the nutrient solution at that location is due to KH_2PO_4 , three-tenths to KNO_3 , four-tenths to $\text{Ca}(\text{NO}_3)_2$, and one-tenth to MgSO_4 .

D. FACTORS THAT MAY DETERMINE THE RELATIVE VALUE OF NUTRIENT SOLUTIONS

One of the main aims in studying nutrient solutions has been to determine the best proportions, concentrations, and means of presenting the nutrient salts in order to secure the maximum response in the growth of the plants. It has frequently been stated that the aim is to determine or find the "best solution" with the idea of applying the proportions and concentrations of solutes thus found for a maximum response in agricultural practice. It is important, then, to consider some of the factors that may determine whether or not a nutrient solution will be the "best solution" for plant growth.

1. Temperature and Light.—It was reported by Gericke (1921) that the nutrient solutions which produced the best growth of Marquis wheat in the early growth phases varied with the temperatures under which the experiment was conducted. The plants were grown in the six types of three-salt nutrient solutions in which the total molecular concentration was distributed in eighths among the component salts in all possible proportions. The temperatures used were 28 and 17°C., the former being considered about the optimum and the latter distinctly below the optimum for the early growth of wheat. The "good or best solutions" were considered to be those in which the growth values obtained lay within the upper one-fourth of the total range of values for the same

temperature and the same solution type. The following table shows some of the best solutions for the two temperatures observed:

Temperature, degrees Centigrade	Type I KH ₂ PO ₄ Ca(NO ₃) ₂ MgSO ₄	Type II K ₂ SO ₄ Ca(NO ₃) ₂ Mg(H ₂ PO ₄) ₂	Type III KNO ₃ Ca(H ₂ PO ₄) ₂ MgSO ₄	Type IV K ₂ SO ₄ Ca(H ₂ PO ₄) ₂ Mg(NO ₃) ₂
28.....	R1S3	R1S3	R1S3	R1S4
	R1S4	R1S4	R1S4	R1S5
	R3S4	R2S1	R1S6	
	R4S1	R2S1	
	R3S2	R3S3	R2S5	R4S1
17.....	R3S3	R5S1	R3S4	R5S1
	R4S1	R5S2	R4S1	R5S2
	R5S1	R5S1	

These figures indicate that there is generally a marked difference between proportions that give the best growth at higher temperatures and those that give the best growth at the lower temperatures. It appears, for example, that the proportion of K may be less for high than for low temperatures.

Trelease and Trelease (1926) grew wheat plants in nutrient solutions at temperatures of 14, 19, and 30°C. and studied the relation of temperature to the physiological values of these solutions as indicated by the growth of the roots. There was little or no differences at the first two temperatures, but at a temperature of 30° there were marked differences in the physiological values of the different solutions.

From a comparison of the relative value of a series of solutions for the growth of wheat plants under different degrees of illumination, Trelease and Livingston (1924) conclude that if a number of markedly different nutrient solutions are repeatedly compared by tests made under different climatic complexes, the relative physiological values assigned to the several solutions may be either the same or more or less different for the several tests according to the nature and magnitude of the climatic differences dealt with. They consider that the comparative physiological values of different salt solutions cannot be stated with any degree of precision without having described in an adequate manner the climatic condition under which the tests were made.

2. Concentration.—The experimental evidence in regard to the effect of the concentration of the nutrient solution on the growth of plants is confusing. Since the information is not very definite, it is the intention to present here only the results that have been reported and the criticisms that have been offered upon the question. Breazeale (1905) grew wheat seedlings in nutrient solutions with concentrations,

respectively, of 15, 75, 155, 750, and 1,550 ppm. The seedlings were grown for 28 days and the solution changed daily. The plants increased in growth and vigor with the increasing concentration of the solutions up to 155 ppm., but above that point they were small and resembled those grown in the weaker solutions. Breazeale concluded that there is an optimum physical concentration of the nutrient solution in which plants thrive best aside from variations in the amounts present of the different nutrient materials. The work of Breazeale was substantiated by that of Hall, Brenchley, and Underwood (1914) who concluded from their experiments with barley, which was grown in both water and sand cultures with a standard nutrient solution of four concentrations, that the growth made by plants in the soil solution is, in the main, determined by the amount of nutrients that are available. They also considered that the concentration of the solution within certain wide limits, irrespective of the total amount of plant food available, is a factor in the rate of plant growth. Ayres (1917), Tottingham (1914), and Shive (1915) furnish evidence which indicates that the effect upon growth of any given set of salt proportions varies with the total concentration of the solution. Shive found that in experiments with solutions of 0.01, 1.75, and 4.00 atmospheres osmotic pressure the best growth of tops of young wheat was obtained in the solution with an osmotic pressure of 1.75 atmospheres, the poorest growth in the weakest solution, and the medium growth in the most concentrated solution. Trelease (1917) observed young wheat plants growing in a solution consisting of KH_2PO_4 , MgSO_4 , KCl , and $\text{Ca}(\text{NO}_3)_2$ in the molecular proportions of 1.000, 0.587, 0.485 and 0.341, respectively, for these salts in which the concentration of the solution varied by six increments from 0.5 atmosphere to 7.0 atmospheres. The maximum yield of tops was obtained when the nutrient solution had a total osmotic concentration of 1.6 atmospheres. Between the concentrations of 1.6 and 7.0 atmospheres the dry weight of the tops was approximately a linear function of the concentration, decreasing as the concentration increased. When, however, the molecular proportion of the salts in the solution was changed to 1.000, 1.155, 7.282, and 0.699, the optimum concentration for growth was between 4.5 and 5.5 instead of at 1.6 atmospheres (see also Hoagland, 1919). Cameron (1911) and Stiles (1915) working with solutions similar to some of those used by the authors just mentioned were unable to obtain any marked variations in the amount of growth over a fairly wide range of concentrations. They consider that the slight differences observed might have been due to the depletion of some one element and that this, perhaps, could be overcome by the more frequent renewal of the solution. The conflicting results obtained in regard to the effect of the concentration of the solution on growth may, in part at least, be due to factors other than the ones under consideration which have been overlooked by those conducting the experiments.

3. Water vs. Sand Cultures.—A comparative study of sand and water cultures as media for plant growth has been made by McCall (1917), Stolhane (1914), Hall, Brenchley, and Underwood (1914), Shive (1920), Shive and Martin (1918), Bakke and Erdman (1923), Hoagland and Martin (1923), and others. A sand culture furnishes a medium that apparently is more nearly comparable to the soil than is a water culture. It has been found by practically all investigators that the growth of roots as judged by the production of dry matter as well as by the profuse branching and general extent is much higher in sand cultures than in water cultures. This has generally been interpreted as due to better aeration of the sand cultures. In many cases, however, the best growth of tops as measured by both green and dry weight occurs in the water cultures. One of the first questions that arises is what effect the sand has upon the nutrient solution that is added to it. Shive (1920) with three-salt nutrient solutions showed that different grades of washed sand gave no evidence of the adsorption of salt or ions in sufficient amount to alter materially either the reaction or the total salt concentration of the solution in contact with the solid particles. The adsorptive capacity, however, of the unwashed sand was sufficient to reduce the total concentration of the solution from 1.76 to 1.61 atmospheres, an average reduction of 8.5 per cent, during the first 24-hr. period. The reaction of the nutrient solution was not markedly altered by its contact with the unwashed sand. By the renewal of the nutrient solution the initial adsorptive effect of the unwashed sand was soon eliminated, apparently by saturating its adsorptive capacity. As an example of the contrast between water and sand cultures the work of Bakke and Erdman (1923) may be mentioned. In the case of Marquis wheat grown to the heading stage in type III three-salt solution with a concentration of 1.00 atmosphere, they found, in general, a greater dry weight of tops produced in the water cultures and a greater dry weight of roots in the sand cultures. The solutions producing the maximum yield of tops for the water and sand cultures showed marked variations in salt proportions. The best water-culture solution was *R1S1*, while the best sand-culture solution was *R3S3*. The amount of water transpired was with but few exceptions greater from the water cultures than from the sand cultures. The sand cultures that transpired more water than the water cultures were characterized by a high proportion of $\text{Ca}(\text{H}_2\text{PO}_4)_2$ with only a small proportion of KNO_3 and MgSO_4 .

4. Physiological Balance.—It has been already noted that one of the outstanding lines of recent investigations in plant nutrition has been the attempt to determine whether certain combinations and ratios of salts or ions in nutrient solutions are more beneficial to plant growth than others.

The experimental data obtained have indicated that the question of physiological balance is an intricate and complex one, since it varies with

the type and concentration of the solution, the type of plant under consideration, and the general conditions of the environment. Certain phases of this question are treated under other topics and it is the intention here to consider only a few of the experiments that have been conducted along this line.

The results obtained by Tottingham (1914) with wheat seedlings are very striking. He grew these plants in ordinary Knop's solution and in 84 different combinations of this solution in which the osmotic pressure was distributed in tenths among the component salts. He found, for example, that with a concentration of 0.01 per cent and an osmotic pressure of 0.05 atmosphere the solution producing the greatest dry weight of tops was 39 per cent superior to the ordinary Knop's solution of the same concentration. This solution contained 0.6, 3.1, 0.5, and 1.4 times as much of KH_2PO_4 , MgSO_4 , $\text{Ca}(\text{NO}_3)_2$, and KNO_3 , respectively, as occurs in the corresponding Knop's solution. In the case of roots, the best solution was 15.4 per cent superior to Knop's solution of the same total concentration. This solution contained 1.8, 0.8, 0.2, and 3.4 times as much of the respective salts as occurs in the corresponding Knop's solution. In the solutions in which the concentration was 0.6 per cent and the osmotic pressure approximately 2.5 atmospheres, the one that produced the greatest dry weight of tops was 11 per cent better than Knop's solution of the same concentration. The greatest dry weight of roots obtained in this series was 15.4 per cent better than that obtained in the same concentration of the ordinary Knop's solution.

Evidence that different plants require different physiological balances for their best development was furnished by Shive (1915, 1917). In a series of 36 combinations in a three-salt solution with an osmotic pressure of 1.75 atmospheres, it was found that the solution which gave the best growth for buckwheat was I R4S2, while the best solution for the growth of young plants of Marquis wheat was I R5S2. Johnston (1925) in a study of the relative value of the six types of three-salt solutions for the growth of Irish Cobbler potatoes found that types I and II were the best suited if the dry weight of the plants is used as a criterion.

Experimental evidence secured by Gericke (1922) shows that the pairing of ions or the type of salt in which they are made available to the plant exerts a marked influence upon growth. He grew wheat seedlings for one day in a solution of KNO_3 with a concentration of 1.0 atmosphere and then removed the plants, rinsed the roots in distilled water, and placed them in a solution of MgHPO_4 of the same concentration. The next day the plants were transferred to a like solution of CaSO_4 and after 24 hr. again transferred to the KNO_3 solution. It was found that the plants which were thus changed by this continued rotation at 24-hr. periods grew as large and produced approximately the same dry weight as those grown in the complete nutrient solutions of the same salts

or in other three-salt solutions which supplied the same ions. It was further found that plants grown in these three single-salt solutions above mentioned were much superior to those grown in other types of single-salt solutions which were likewise changed every 24 hr.

In an experiment in which 10 different salts were selected to give six different types of nutrient solutions, it was found that the order of change from one salt to another was of only minor importance. It was also found that the differences in the P_H value of the single-salt solutions were within the range of good plant growth and thus exerted little or no influence but that the kind of salt used in making the change was of great importance. Thus when KNO_3 , $MgHPO_4$, and $CaSO_4$ were used singly as above mentioned they gave much better yields than did the salts of any other type solution. Gericke considered that the cause for this might be the way in which the two essential ions are paired. Thus the best results were obtained when NO_3 and K were present together, since the absence of the other essential elements for a period of 48 hr. was apparently of little consequence. Likewise, $MgHPO_4$ seemed to be the best salt with which to supply the Mg and P to the plant, since if the plants, for example, were placed in $MgSO_4$ or $Mg(NO_3)_2$ alone for 24 hr. they were decidedly injured. It seems apparent, then, that the pairing of nutrient elements or ions of opposite charge is an important factor in securing the maximum growth of plants in water cultures. This does not necessarily mean that a definite cation-anion ratio must exist, since ionic ratios can cover a considerable range of values without any apparent physiological effect. Results of a somewhat similar nature were obtained by Sewell (1924), who found that when wheat is growing in a soil with a sufficient supply of N, the plant will produce a maximum yield with less of the salts containing K and P than if the nitrogen supply is limited. On that account, if these elements are deficient in the soil a smaller application is required if there is a liberal supply of N present.

The problem of physiological balance in the soil under agricultural practice is of vast importance if the application of fertilizers is to be placed upon a scientific basis. The most thorough work along this line has been done by Hibbard (1927). The plants which he especially considered were Marquis wheat and Worthy oats and the salts used as fertilizers were $Ca(HPO_4)_2$, $NaNO_3$, and K_2SO_4 . The wheat plants were grown in soil in the greenhouse, while the oat plants were grown in the field, but in each case the N, P_2O_5 , and K_2O were varied by increments of 10 per cent so that there were 36 combinations or ratios. The plants were grown to maturity and the yields of grain taken as a measure of the results. Hibbard concluded that the data obtained indicate that the yields of cereals such as wheat, oats, and corn may be identical under somewhat wide variations of nutrient ratios. He considers that his work suggests that nothing can be gained by attempting to find a definite

ratio or physiological balance in soil cultures through the triangular system of fertilizer tests. He considers further that many of the crop plants have become accustomed to wide variations in environmental conditions and for that reason are not suitable indicators for studies of this kind. Under field conditions the proportions of various salts available to the plant must vary from time to time because of the fluctuations of the salt content of the ordinary soils. Similar conclusions were drawn by Eisenmenger (1928) in studying the rate of elongation of wheat roots supplied with simple solutions of KH_2PO_4 , $\text{Ca}(\text{NO}_3)_2$, and MgSO_4 and with solutions containing pairs of these salts. He considered that the wide range of salt proportions which allow nearly optimum growth is one of the conspicuous features of his results. Optimum salt proportions probably could be defined precisely if a sufficient detailed study were made, but the growth rate in the optimum solution would be only slightly higher than in many solutions differing considerably with respect to the relative proportion of their constituent salts. Hibbard found, however, under the conditions of his experiment that the use of a single fertilizer ingredient did not give so good results in soil cultures as a combination of the three and suggests that only under conditions where the price for a mixture of the three fertilizer ingredients is prohibitive would the use of single fertilizers be advisable.

The relationship of the moisture content of the soil to the physiological balance has been studied by Shive (1919 to 1922). He found that good physiological balance and optimum total concentration of a nutrient solution are not alone sufficient to produce the best growth of which the solution is capable unless it is diffused as a film on the particles of a solid substratum. An optimum supply of moisture is thus necessary to impart to the soil its maximum physiological value so that the actual plant-producing value of any fertilizer treatment is largely determined by the moisture conditions of the soil.

E. THE HYDROGEN-ION RELATIONS IN NUTRIENT SOLUTIONS

The data relating to the effect of the plant on the H-ion concentration of the culture solution and the effect of this reaction upon the plant are very confusing. This is to be expected, since the reactions under consideration are influenced by so many different factors. Among these are the type of plant, the rate of ion absorption, exosmosis from the roots, temperature, and the nature of the nutrient solution. It is the intention here to state only a few experimental results to show the general complexity of the question. Tarr and Noble (1922) grew seedlings of wheat, soybeans, and corn in nutrient solutions which were maintained at constant H-ion concentrations extending over a range from P_H 3 to 8 at definite gradations of 1 P_H . They found that a reaction of P_H 3 was prohibitive to growth in all cases. The maximum growth of

wheat seedlings occurred at a reaction of approximately P_H 4, while a lesser concentration exerted no harmful effect until a P_H of 6 was reached, when chlorosis began to appear. The maximum growth of soybeans and corn was obtained at a reaction of P_H 5. In both these cases chlorosis occurred at a reaction of P_H 6 due to the insolubility of iron at all H-ion concentrations less than P_H 6. According to Hoagland (1926), slight acidity P_H 5 to 7 is not in itself injurious to various types of plants, but alkaline solutions above P_H 8 in general prove to be less favorable, while P_H values above 9 are injurious to most agricultural plants. Bermuda grass, however, can grow vigorously when the medium in which it is growing has a P_H value of 9. The effects of alkalinity on the plant are both direct and indirect, so that they are difficult to interpret, chiefly because it is difficult or impossible to maintain the desired concentration of the essential salts, since some of these precipitate out under alkaline conditions. Hoagland (1923) obtained some indications that barley, cucumbers, and peas grow more rapidly when a certain degree of acidity is maintained than when the reaction of the solution is allowed to change under the influence of the plant. In no case did he observe as good a growth at P_H 7 as when the nutrient solution was slightly acid. It seems therefore to be uncertain whether the reaction to which a solution is brought by a plant growing in it is the most favorable for the growth of that plant. Duggar (1920) found in the case of wheat, corn, and Canada field peas growing in modified Shive and Livingston-Tottingham solutions among others that these plants under favorable conditions gave excellent growth even though the P_H value of the solutions varied from 4.5 to 7.1. He concluded from these observations that there is a considerable range of P_H values within which plants will grow well.

It has been observed by numerous investigators, in the study of the relationship of the H-ion concentration to growth of plants, that there is, in many cases between the extreme limits of acidity or alkalinity which are injurious and interfere with growth, a third region where the reaction affects the plant injuriously. Thus if the growth of the plant or plant part is plotted against the hydrogen-ion concentration of the solution in which the plant is grown, the curve has a double maximum with a minimum located between the two maxima. The fact that this phenomenon has not been observed in all cases should not be considered (Robbins, 1923) as necessarily indicating the non-existence of such a curve, since there are many conditions which might conceal or obliterate the minimum located between the two maxima. The P_H values of the solutions in which the plants were grown may have been so separated that the minimum point for growth could not have been observed. Then such factors as temperature, water supply, and salt content may have limited growth so that the maximum and minimum points could not be distinguished. It may be well to give a few examples in this regard.

Salter and McIlvane (1917) noted a double maximum curve for the growth of wheat seedlings grown in nutrient solution with different P_H values and found the minimum between these two maxima to lie at a P_H value of 6, the same minimum point as that observed by Cole (1922) for corn seedlings. Hixon (1920) found a double maximum for growth in the case of peas, corn, wheat, and oats, a P_H value of 5.0 representing the minimum point for peas, and P_H 6.0 the minimum point for the other three plants. Arrhenius grew numerous crop plants in soils in which the H-ion concentration ranged from P_H 3.0 to 10.0. The two H-ion concentrations giving the highest yield were as follows:

Dale oats.....	P_H 7 and 5	Alfalfa.....	P_H 8 and 7
Rubin wheat.....	P_H 9 and 4	Flax.....	P_H 6 and 4
Red clover.....	P_H 6 and 5	Sugar beets.....	P_H 8 and 6

The data indicate clearly the presence of a double maximum and also show that the same H-ion concentration may show wide variations in plant production.

A double-maximum curve also apparently results when the swelling, osmotic pressure, viscosity, and electrical conductivity of certain colloids are plotted against the P_H value of the solution, and it has been found that the minimum between the two maxima is located at the isoelectric point of these substances. These facts led Robbins (1923) to consider that there may be an isoelectric point for plant tissue which may correspond to the P_H value of the minimum point of growth. By means of experiments with the absorption of water and dyes by potato tuber tissue in contact with solutions of different H-ion concentrations, he obtained a double-maximum curve with a minimum between for water absorption. His results indicated that an ampholyte, possibly a protein, plays a chief rôle in this process and that its isoelectric point is approximately P_H 6.0. He considers that this assumption of an isoelectric point for plant tissue and its influence on water absorption offers a satisfactory explanation for the double-maximum curves in the growth of plants and other physiological functions when the plants are grown in media of different H-ion concentrations.

The effect of the nature of the nutrient solution upon the rate of change of the P_H value when plants are growing therein has been studied by Jones (1921), Jones and Shive (1922), and McCall and Haag (1920). In the case of wheat growing in three-salt nutrient solutions, the rate of change of the H-ion concentration decreased with an increase in the total osmotic value of the solution and with its volume. The following table shows the change of the P_H value of different types of nutrient solutions in which wheat had been grown for 52 hr. (Jones and Shive 1922).

Kind of solution	P _H value	
	Original	After 52 hr.
Crone's.....	6.6	6.6
Sach's.....	6.7	6.6
Knop's.....	4.6	5.7
Shive's R5S2.....	4.5	5.3
Tottingham's T3R1S4.....	4.6	5.5
Detmer's.....	4.7	5.9

They considered that the resistance offered to reaction change resulting from contact with the roots of growing plants was largely dependent upon the volume molecular proportions of the soluble phosphate salts contained in the solution. McCall and Haag (1920) state that the H-ion concentration of various types of three-salt solutions is a function of the volume molecular proportion of the dihydrogen phosphate salt.

The majority of observations indicate that plants growing in nutrient solutions whose reactions are either above or below the neutral point tend to change the H-ion concentration toward neutrality, although this will depend in part upon the nature of the solution (Toole and Tottingham, 1918; Hoagland, 1917; and Meier and Halstead, 1921). Thus Bakke and Erdman (1923) noted that wheat plants at the heading stage changed the reaction of type-III salt solution in which they grew for 3½ days from P_H 3.75 to 5.94 when water cultures were used and to 6.66 when sand was the substratum for the roots. An example of the different reactions brought about by different plants is afforded by the work of Jacobson (1925) with wheat and rice plants. With Marquis wheat plants 97 days old placed in quart jars which contained solution type III R2S1 with the molecular proportions distributed in one eighths, the P_H value increased from 3.9 to 6.3 during the first 12 hr., after which the reaction of the solution remained fairly constant for the 72-hr. period of observation. The nitrogen concentration of the solution decreased from 85 to 24 ppm., a loss of practically 72 per cent during the first 12 hr., and by the end of the 36-hr. period only a trace of nitrogen remained. The results indicated that the K of the KNO₃ was not taken up nearly so rapidly as the NO₃ and that it combined with other elements after being liberated from its anion so that the combination thus formed was capable of partly neutralizing the acidity of the nutrient solution. In the case of rice plants, however, growing in four different types of nutrient solutions, the P_H value decreased from 5.0 to about 3.5 during the first 24 hr., after which it remained practically constant for the 3 days that the experiment was continued. It was considered that the cations of the salts containing SO₄ might have been removed from the solution more rapidly than the

anion so that the acidity was increased. This has also been suggested by Hoagland (1918). It was observed in both the rice and wheat cultures that the excretion of CO_2 by the roots tended to decrease the P_{H} value of the solution.

F. CRITICISM OF THE DATA OF PLANT NUTRITION

The basic purpose of the study of plant response in water and sand cultures is to determine the nature of the nutrients, their concentration, their proportions, and the method of their application that will give the best response when applied in agricultural practice. The question then arises as to how far the observations that have been made with sand and water cultures are comparable and applicable to plants growing under conditions in the field.

One of the chief objections to the use of water and sand cultures from the practical standpoint is that the plant is growing in a very unnatural medium. The differences between the plants grown in sand and in water cultures illustrate the fact that the medium in which the roots grow may affect the plant response. While many plants grow to maturity and produce seed in water and sand cultures, the production is, with but few exceptions, less than that of plants growing in the soil. The seed produced, however, has in the cases which have been tested shown little difference in its germinating power from that produced by plants growing in the soil. The concentration of the solutions used in most cultural work is much higher than the soil solution upon which a plant normally has to depend (Crocker, 1919). Apparently, too, the solutes in cultural solutions are more readily available than they are in the soil, from both the standpoint of solubility and the rate of diffusion. Neither the frequent renewals nor continuous renewals of the solution in cultural work furnish a medium like that of the soil, although the exact status of the soil solution in regard to its variability of concentration, solubility, and composition is as yet quite uncertain. On that account, therefore, in the words of Stiles (1915), it is a very uncertain procedure to argue from a comparatively simple medium like a nutrient solution of mineral salts to a complex substance like the soil. As pointed out by Davis (1921), a very great defect in most plant nutrition work has been the comparatively small number of plants and cultures used in each experiment. The variation of plants growing even under field conditions is very great, so that unless a large number of individuals is considered in cultural work the results may be of no significance. Davis selected three combinations of Shive's three-salt solution (1.75 atmosphere) which had been reported, respectively, as the best, medium, and poor solution for the growth of wheat and grew in them Sonora wheat in 33 to 50 triplicate cultures for each of the three selected solutions. He found that when the probable error was obtained for the number of cultures used, there was no signifi-

cant difference between the cultural solutions which had been reported as the best and medium, respectively, but that the solution reported as poor showed a decided inferiority.

The wide variations in cultures was illustrated by the chance selection of duplicate cultures. Thus where the mean of the dry weights of the series was 2.15 g., the mean of 16 pairs selected at random ranged from 1.82 to 2.55 g. Since in most of the experimental work that has been published on plant nutrition the cultures were grown only in duplicate or triplicate, considerable doubt is thrown upon the value of the data that have been reported.

One of the chief aims of nutrition work with plants has been to find the "best solution" for plant growth. The criterion for judging this has been the best response as measured by growth obtained from a series of solutions under conditions that too frequently have not been well defined. The standards by which the best response has been measured are the length and weight of tops, the amount of transpiration, the total amount of dry matter produced, and others. In outlining the standards by which the so-called "best growth" is to be judged, the purpose for which the plant is to be grown must obviously be taken into consideration. If a plant is to be grown for forage, a different standard must be considered from that which would have to be considered if only a grain crop were desired. Clements (1928) made chemical analyses of plants grown in the various positions in the triangle for starch, total sugars, hemicellulose, nitrate nitrogen, total organic nitrogen, and ash in the various parts, with the idea of determining the internal relations of the plant to the various salt combinations. It was found, however, that these criteria, for the most part, are unreliable for determining the best response of plants to nutrient solutions. Hoagland and Martin (1923) have pointed out that we are not justified in stating that a normal plant is the one making the best growth under a given set of environmental conditions. No solution has a fixed value so far as its ionic, atomic, or molecular properties are concerned for growth, since the relation of a plant to a cultural medium is dependent upon the environmental conditions. On that account, therefore, no statement of any value can be made in regard to the "best solution" unless a strict account of the various environmental conditions is presented—a requirement that is practically impossible. The stage of growth of the plant must also be taken into consideration when considering the value of a given nutrient solution, since the nutrient requirements of a plant vary with its stage of development, as will be discussed in the following chapter.

The concensus of opinion among workers in plant nutrition at the present time is that there is a wide range of solutions in regard to concentration, composition, and proportion of components in which plants will thrive equally well and that the response of plants to any solution

will depend to a great extent upon the environmental conditions under which they are growing. In the words of Stiles (1916), we may state that the value of water- and sand-culture work is limited because of the difficulty of analyzing results due to complex factors that are not under control and because of the further difficulty of controlling in some cases even the factor whose action is being investigated. On the other hand, however, it must be remembered that nutrient solutions furnish the best means that are available at present to study the nutrition of plants in a quantitative way and much of our knowledge of plant nutrition has been gained by their use. Care should nevertheless be exercised in interpreting the results obtained with nutrient solutions in terms of the behavior of plants under natural conditions.

VI. ANTAGONISM AND BALANCED SOLUTIONS

It has long been known that solutions of certain single salts are toxic to living organisms placed therein but that in a mixed solution of these salts the organisms function normally and are not injured (True, 1915). The best example is the organisms living in sea water. They grow and develop in this mixture of salt solutions, but if placed in a solution of any one of the single salts that compose it they perish, in many cases in a relatively short time. The term "antagonism" is used to designate the hindrance which a given salt has upon the toxic action of another salt. By antagonism thus is meant that one toxic substance acts as an antidote to another.

As has been mentioned above, it is possible to mix two or more toxic substances in solution in such proportions that they lose their individual toxic properties. Such a solution has been termed a "physiologically balanced solution" (Loeb, 1906) and may be defined as a solution in which the toxic effects that each salt would have were it alone present in the solution are hindered by one or more antagonistic salts in the solution. It has also been defined as a solution containing salts in such proportions that they have none of the toxic properties of the individual salts. The term, however, has been used in a very broad sense and has referred in many cases to the proportional arrangement of the component parts of nutrient solutions regardless of their toxic properties. A physiologically balanced solution may contain only two salts, so that it is not necessarily a nutrient solution, but on the other hand a nutrient solution to be of the best advantage must be a balanced one.

The question of antagonism and balanced solutions in regard to plants has been extensively investigated by Osterhout and his pupils (1906 to 1922). It is not the intention here to discuss this problem in any detail but only to mention a few examples to illustrate the importance of this subject in relation to plant life. Osterhout (1914) has pointed out that a mixture of two equally toxic solutions must have precisely

the same effect on growth as the pure solutions themselves, provided the effects of the salts are additive. By the additive effect is meant the effect produced when each salt acts independently of every other so that its toxicity is neither augmented nor diminished by the presence of other salts. If antagonism between the salts exists, there will be better growth in the mixed solutions than in the single ones. The amount of this increased growth expressed as percentage of the growth obtained in the pure solution is the most satisfactory measure of antagonism. Precautions must be taken in the determination of antagonism that only those parts of plants that come in contact with the solution should be used for measurement. Trelease and Trelease (1926) and Eisenmenger (1928) have demonstrated that the roots of young wheat seedlings can be used satisfactorily for demonstrating the growth-retarding effects of single-salt solutions and the antagonistic action of mixed solutions. The following table shows the relative effect of mixed- and single-salt solutions on the growth of wheat roots therein (Osterhout, 1907):

Medium	Growth of roots in 40 days, millimeters	Medium	Growth of roots in 40 days, millimeters
NaCl 0.12M	60	1,000 cc. NaCl 0.12M	327
MgCl ₂ 0.12M	7	78 cc. MgCl ₂ 0.12M	
KCl 0.12M	68	10 cc. CaCl ₂ 0.12M	
CaCl ₂ 0.12M	70	Dilute artificial sea water	360
1,000 cc. NaCl 0.12M } 10 cc. CaCl ₂ 0.12M }	254	0.12M NaCl 1,000 cc. 0.12M MgCl ₂ 78 cc. 0.12M MgSO ₄ 38 cc. }	
1,000 cc. NaCl 0.12M } 22 cc. KCl 0.12M }	324	0.12M KCl 22 cc. 0.12M CaCl ₂ 10 cc. }	
		Distilled water	740

Osterhout and others have found antagonism between the following cations:

- | | | |
|------------------------|------------------------|-----------|
| NH ₄ vs. Ca | NH ₄ vs. Na | Na vs. Ba |
| K vs. Ca | NH ₄ vs. K | K vs. Ba |
| Na vs. Ca | Na vs. K | Na vs. Sr |
| Mg vs. Ca | Mg vs. K | K vs. Sr |
| Mg vs. Sr | Fe vs. Mn | |

Raber (1920) from experimental work with sodium acetate and sodium sulphate concluded that antagonism existed between anions so that any theory of the antagonistic action of salts must take into account the action of the anions as well as the cations.

Kearney and Harter (1907) noted the effect of calcium sulphate in overcoming the toxic effect of the magnesium and sodium salts that are

found in alkali soils. The following table shows the critical concentrations for plants of lupine and corn grown in pure solutions of the various salts and in the same solutions after an excess of calcium sulphate had been added. The term "critical concentration" as here used was the concentration of solution that allowed the root tips of any one-half of the total number of seedlings tested to retain their capability of further elongation after being in the solution for 24 hr.

Salt	Critical concentrations			
	In pure solutions		After adding CaSO ₄ in excess to solutions	
	Lupine	Corn	Lupine	Corn
MgSO ₄	0.007 <i>M</i>	0.25 <i>M</i>	0.40 <i>M</i>	0.60 <i>M</i>
MgCl ₂	0.007 <i>M</i>	0.08 <i>M</i>	0.20 <i>M</i>	0.30 <i>M</i>
Na ₂ CO ₃	0.010 <i>M</i>	0.02 <i>M</i>	0.03 <i>M</i>	0.05 <i>M</i>
Na ₂ SO ₄	0.040 <i>M</i>	0.05 <i>M</i>	0.30 <i>M</i>	0.40 <i>M</i>
NaCl.....	0.040 <i>M</i>	0.04 <i>M</i>	0.20 <i>M</i>	0.25 <i>M</i>
HNaCO ₃	0.030 <i>M</i>	0.05 <i>M</i>	0.05 <i>M</i>	0.10 <i>M</i>

The neutralizing effect of CaSO₄ was much greater toward the magnesium salts than toward the sodium salts, while the order of toxicity of the different salts was also changed by its addition.

The causes of antagonism are little understood, and it is not the intention here to enter into any discussion of the various theories that have been proposed. The relationship of the changes in permeability produced by salts and their antagonistic relations as suggested by Osterhout (1915) may give some insight into the causes of antagonism. As has been mentioned in Chap. II, the substances that alter the permeability of the protoplasm may be divided into those which cause an increase and those which cause a decrease in its permeability. Osterhout considers that substances belonging to one class will antagonize those belonging to the other class so that in order to predict which substances will antagonize each other it is necessary only to determine to which of these classes the substances belong. The amount of antagonism between salts may also be predicted, at least to a certain extent, since the greater their effect on the permeability the greater will be their antagonistic action. This theory of antagonism assumes that the protoplasmic membrane possesses a certain degree of permeability at which it functions normally and that when this permeability is increased or decreased beyond a certain limit the activities of the protoplasm are impaired. If an organism is placed, for example, in a solution of NaCl, the permeability of the protoplasm is increased to a point that is injurious to it; and if it is placed

in a single solution of CaCl_2 , the permeability will be decreased to the point of injury. If, however, these two salts are mixed in the proper proportion, their effects on the protoplasm will counteract each other and the permeability of the protoplasm will be unaltered so that the cell or organism will function normally.

Questions

169. Cite experiments which show that inorganic salts readily penetrate the protoplasmic membrane and enter the cell sap.

170. What is meant by passive or physical absorption of solutes? How may this be illustrated with solutions of tannin and ferric chloride separated by a collodion or parchment membrane? In what four ways may the solutes which enter the cell sap be rendered osmotically inactive?

171. State how the absorption and translocation of solutes from cell to cell might be considered as an electrical phenomenon.

172. What is meant by active or physiological absorption of solutes? What is epictesis?

173. Give examples in which the concentration of certain solutes of the cell sap greatly exceeds the concentration of these solutes in the medium in which the cells are growing. In what form are these solutes within the cell?

174. What is an ampholyte or amphoteric substance? What is the isoelectric point of an amphoteric substance? How may the amphoteric nature of the proteins be related to the absorption of ions by the cell?

175. How may the rotation of the protoplasm be of importance in the absorption of ions? At what P_H value is the protoplasmic membrane apparently the most permeable?

176. What is meant by ionization isoelectric points and adsorption isoelectric points in relation to membranes? How does the phenomenon of the intake of solutes by plants differ from a Donnan equilibrium operating between two homogeneous phases? How might this difference be accounted for?

177. What is the absorption ratio? How does light affect its value? Why? Give examples.

178. How is the value of the absorption ratio affected by the concentration of the external solution? By the nature of the ions absorbed? Cite examples. What is the value of the absorption ratio of dead tissue?

179. What is meant by the unequal absorption of ions by plant tissue? How is the unequal absorption of ions determined? Give some examples in regard to the unequal absorption of ions.

180. What are the two possible consequences to the external solution of the unequal absorption of ions? Illustrate with NaCl as the salt in question.

181. How do the cell walls of *Sphagnum* and vascular plants affect the reaction of solutions of nutrient salts in which they are placed? Why? How has this behavior been considered in regard to the absorption of ions by the plant?

182. How do the storage tissues of tubers, roots, fruits, and various seeds change the reaction of the solutions of neutral salt in which they come in contact? To what may this change be attributed? Proof?

183. How do plants affect the reaction of the cultural solution in which they are growing? Give examples to show how this reaction may vary for different solutions, or different plants, and for different external conditions.

184. Discuss the interchange of ions between the plant and the exterior solution when the unequal absorption of ions occurs. Give some examples to illustrate this phenomenon.

185. Enumerate some factors that may influence the unequal absorption of ions. How is the unequal absorption of ions influenced by the concentration of the external solution? Give examples.

186. Which cation is apparently the most rapidly absorbed by plants? Which most slowly absorbed? Which anion is absorbed the most rapidly? Which the most slowly? Which are absorbed the most rapidly, anions or cations? What are the exceptions?

187. Give examples in which the rate of absorption of a cation is increased because of its accompanying anion. In which the rate of absorption of the cation is decreased because of the accompanying anion.

188. Give examples in which the presence of one cation decreases the rate of absorption of other cations. In which the presence of one anion retards the entrance of others.

189. Explain the fact that as the plant absorbs water and ions from a solution, the solution becomes more concentrated with respect to certain ions and more dilute in respect to others. Give a specific example.

190. What is the relationship between the rate of transpiration of a plant and the amount of solutes taken up from the soil? Explain the methods used in determining this relationship. Give some data in this regard.

191. Why is it difficult to study the nutrient requirements of a plant growing in the soil? What is a nutrient solution? A cultural solution? A water culture? A sand culture?

192. What facts were determined in regard to water cultures during the period 1860 to 1900? During the period 1900 to the present time?

193. Name six standard nutrient solutions and give the concentration of the salts that compose them.

194. How many combinations of salts are possible if the value of the osmotic pressure of a four-salt nutrient solution is distributed in tenths among the component salts? How many combinations are possible with a three-salt solution?

195. What are the objection and advantage of a four-salt nutrient solution? Of a three-salt nutrient solution? Why is a two-salt nutrient solution not possible?

196. What types of three-salt nutrient solutions are possible? How are they numbered? Of what significance are slightly soluble salts in a nutrient solution? Give some examples.

197. State the technique of water cultures in regard to the preparation of seeds and seedlings, transference of seedlings to cultural vessels, types of cultural vessels, covers, supports, and methods for securing uniformity of conditions for each plant.

198. Why is it necessary to renew nutrient solutions? Name the methods used in renewing nutrient solutions. Give some data to show the effects of the renewal of nutrient solutions upon growth.

199. In what manner may water cultures be aerated? Give examples to show how the aeration of water cultures affects the growth of the plants growing therein.

200. What are stock cultural solutions? What precautions must be followed in the preparation of such stock solutions? Describe the limitations of the stock solutions of Knop's nutrient solution.

201. What five characteristics of a nutrient solution may be distinguished when its osmotic, ionic, and molecular relationships to plant response are considered?

202. Describe in detail the manner in which the 21 different solutions may be prepared in order to distribute the total osmotic pressure of one atmosphere of a three-salt solution in eighths among the three component salts KH_2PO_4 , $\text{Ca}(\text{NO}_3)_2$, and MgSO_4 , in all the possible proportions.

203. What is the triangle system in plant nutritional studies and what are its advantages?

204. Explain by diagrams the manner in which the osmotic pressure of a four-salt solution may be distributed in tenths for the various salts.

205. Explain in the same way the manner in which the osmotic pressure may be distributed in tenths in a three-salt solution. In eighths in a three-salt solution.

206. What do the following symbols mean: $T3R2S1$, $T1R3S2$, $IR1S3$, $IIR3S2$, $T2R3S4$?

207. How does temperature affect the relative value of nutrient solutions as measured by the rate of growth of plants growing therein?

208. How does the concentration of the nutrient solution affect the growth of plants? To what may these effects be due? Give some examples in which differences in the concentration of the solutions gave marked differences in the rate of growth.

209. What is the relative value of sand and water cultures in the study of plant nutrition? How do washed and unwashed sands compare in adsorptive power? How does the yield of tops and roots compare in the two media? How do the transpiration rates of the plants growing in the two media compare?

210. Discuss the effect of the physiological balance of nutrient solutions upon plant growth in regard to (a) the relative amount of the various salts and (b) the pairing of ions.

211. What does the experimental evidence indicate in regard to the value of the physiological balance of nutrients in agricultural practice? What relationship is there between the moisture content of the soil and the physiological balance?

212. State the factors which may affect the hydrogen-ion concentration of the nutrient solution in which plants are growing. In what range of P_H values can plants grow?

213. Discuss the occurrence of the double-maximum curve in relation to growth and the hydrogen-ion concentration of the nutrient solution. Give examples. What may be the cause of this double-maximum curve?

214. How does the nature of the nutrient solution affect the rate of change of its P_H value when plants are growing therein? Give examples of how different plants affect differently the P_H value of the nutrient solutions in which they are growing.

215. What is the basic purpose for studying plant responses in nutrient solutions? State the objections to considering that the results obtained with water cultures are comparable and applicable to plants growing under conditions in the field.

216. What is meant by a "best nutrient solution"? Why is it difficult to determine that a nutrient solution is the best one for plant growth? Of what value to plant physiology is the study of nutrient solutions?

217. What is meant by antagonism? What is a physiologically balanced solution? What difference is there between a nutrient solution and a physiologically balanced solution?

218. How is the rate of growth used in measuring antagonism? What precautions must be observed in this regard? Give an example of the antagonistic effect of one salt on another as measured by root growth.

219. Name 10 sets of salts that are antagonistic to each other. Give data to show the effect of calcium sulphate in overcoming the toxic effect of magnesium and sodium salts in alkali soils.

220. How do antagonistic salts affect the permeability of the protoplasm? How might these actions in this regard explain the cause of antagonism?

Bibliography

ALLISON, R. V., 1921: The relation of aeration to the development of the soybean plant in artificial culture, *N. J. Agr. Expt. Sta. Ann. Rept.* 1921: 338-345.

- ALLISON, R. V., and J. W. SHIVE, 1923: Studies on the relation of aeration and continuous renewal of nutrient solution to the growth of soybeans in artificial culture, *Amer. Jour. Bot.*, **10**: 554-567.
- ANDREWS, F. M., and C. C. BEAL, 1919: The effect of soaking in water and of aeration on the growth of *Zea mays*, *Bull. Torrey Bot. Club*, **46**: 91-100.
- , 1920: Apparatus for aerating plants, *Proc. Ind. Acad. Sci.*, **1919**: 165-167.
- , 1921: The effect of aeration on plants, *Proc. Ind. Acad. Sci.*, **1920**: 147-148.
- ARRHENIUS, O., 1922: Hydrogen ion concentration, soil properties and growth of higher plants, *Arch. Bot.*, **18**: 1-54.
- , 1923: Soil reaction and plant development, *Medd. Centralanst. Jordbruk-somradet*, 245, pp. 14, *Abst. Expt. Sta. Rec.*, **50**: 532.
- AYRES, A. H., 1917: Influence of the composition and concentration of the nutrient solution on plants grown in sand cultures, *Univ. Calif. Pub. Agr. Sci.*, **1**: 341-394.
- BAKKE, A. L. and L. W. ERDMAN, 1923: A comparative study of sand and solution cultures of Marquis wheat, *Amer. Jour. Bot.*, **10**: 18-32.
- BANCROFT, W. D., 1902: Synthetic analysis of solid phase, *Jour. Phys. Chem.*, **6**: 178.
- BEAL, C. C., 1918: The effect of aeration on the roots of *Zea mays*, *Proc. Ind. Acad. Sci.*, **1917**: 177-180.
- BREAZEALE, J. F., 1905: Effect of the concentration of the nutrient solution upon wheat cultures, *Science*, n.s., **22**: 146-149.
- , 1923: Nutrition of plants considered as an electrical phenomenon, *Jour. Agr. Res.*, **24**: 41-55.
- BRENCHLEY, W. E., 1916: The effect of the concentration of the nutrient solution on the growth of barley and wheat in water cultures, *Ann. Bot.*, **30**: 77-91.
- BRIGGS, G. E., and A. H. K. PETRIE, 1928: On the application of the Donnan equilibrium to the ionic relations of plant tissues, *Biochem. Jour.*, **22**: 1071-1083.
- BURGERSTEIN, A., 1897: Ueber die Transpirationgrösse von Pflanzen feuchter Tropengebiete, *Ber. d. d. bot. Ges.*, **15**: 154-165.
- CAMERON, F. K., 1911: "The Soil Solution," The Chemical Publishing Co., Easton, Pa.
- CLARK, O. L., 1916: A method for maintaining a constant volume of nutrient solutions, *Science*, n.s., **44**: 868-869.
- CLEMENTS, H. F., 1928: Plant nutrition studies in relation to the triangular system of water cultures, *Plant Physiol.*, **3**: 441-459.
- COLE, A. M., 1922: Effect of variations in H-ion concentration on the growth of seedlings, *thesis, Univ. Mo.*
- COOPER, W. C., M. J. DORCAS, and W. J. V. OSTERHOUT, 1929: The penetration of strong electrolytes, *Jour. Gen. Physiol.*, **12**: 427-433.
- CROCKER, WILLIAM, 1919: Review of plant nutrition work, *Bot. Gaz.*, **67**: 174-178.
- CRONE, G., 1902: Ergebnisse von Untersuchungen über die Wirkung der Phosphorsäure auf die höhere Pflanzen und eine neue Nährlösung, *Sitzungber. Niederrhein. Ges. Nat. Heilkunde Bonn*, **1902**: 167-173.
- DAVIDSON, JEHIEL, 1927: Effect of hydrogen ion concentration on the absorption of phosphorus and potassium by wheat seedlings, *Jour. Agr. Res.*, **35**: 335-346.
- DAVIS, A. R., 1921: The variability of plants grown in water cultures, *Soil Sci.*, **11**: 1-33.
- DENNY, F. E., and W. J. YOUNDEN, 1927: Acidification of unbuffered salt solutions by plant tissue in relation to the question of tissue isoelectric points, *Amer. Jour. Bot.*, **14**: 395-414.
- DUFRENOY, J., 1920: The biological significance of selective adsorption, *Amer. Midland Nat.*, **6**: 159-165.
- DUGGAR, B. M., 1920: The effect of conditions on the relation of seed plants to H-ion concentration of nutrient solutions, *Science*, n.s., **52**: 416.

- DUGGAR, B. M., 1920: Hydrogen ion concentration and the composition of nutrient solutions in relation to the growth of seed plants, *Ann. Mo. Bot. Gard.*, **7**: 1-50.
- , 1920: The use of insoluble salts in balanced solutions for seed plants, *Ann. Mo. Bot. Gard.*, **7**: 307-327.
- EISENMENGER, W. S., 1928: Toxicity, additive effects and antagonism of salt solutions as indicated by growth of wheat roots, *Bull. Torrey Bot. Club*, **55**: 261-305.
- ESPINO, R. B., 1919: Critical review of article by Schreiner and Skinner on the triangle system for fertilizer experiments, *Plant World*, **22**: 53-54.
- FITTBGEN, J., 1873: Untersuchungen über das für eine normale Production der Haferpflanze notwendige Minimum von Bodenfeuchtigkeit sowie über die Aufnahme von Bestandteilen des Bodens bei verschiedenen Wassergehalt desselben, *Landw. Jahrb.*, **2**: 252-371.
- FREE, E. E., 1917: The effect of aeration on the growth of buckwheat in water cultures, *Johns Hopkins Univ. Circ.*, n.s., **3**: 198-199.
- GERICKE, W. F., 1921: Influence of temperature on the relations between nutrient salt proportions and the early growth of wheat, *Amer. Jour. Bot.*, **8**: 59-63.
- , 1922: Water culture experimentation, *Science*, n.s., **56**: 421-422.
- , 1922: On the physiological balance in nutrient solutions for plant cultures, *Amer. Jour. Bot.*, **9**: 180-182.
- GILTAY, E., 1897: Vergleichende Studien über die Stärke der Transpiration in den Tropen und in mitteleuropäischen Klime, *Jahrb. f. wiss. Bot.*, **30**: 615-644.
- GREGORY, F. G., 1928: The differential effect of the ions of three-salt solutions on the growth of potato plants in sand culture, *Proc. Roy. Soc.*, B, **102**: 311-327.
- HAAS, A. R. C., and H. S. REED, 1926: The absorption of ions by citrus and walnut seedlings, *Hilgardia*, **2**: 67-106.
- HABERLANDT, G., 1892: Anatomisch-physiologische Untersuchungen über das tropische Laubblatt, *Sitzungsber. d. k. Akad. d. Wiss. Wien.*, **101**: 785-816.
- , 1897: Ueber die Grösse der Transpiration im feuchten Tropenklima, *Jahrb. f. wiss. Bot.*, **31**: 273-288.
- HALL, A. D., W. E. BRENCHELEY, and L. E. UNDERWOOD, 1914: Soil solution and mineral constituents of the soil, *Phil. Trans. Roy. Soc.*, B, **204**: 179-200.
- , ———, and ———, 1914: The soil solution and the mineral constituents of the soil, *Jour. Agr. Sci.*, **6**: 278-301.
- HAMMETT, F. S., 1928: A convenient device for plant solution culture work, *Science* n.s., **67**: 106-107.
- HARRIS, J. A., W. F. HOFFMAN, and J. V. LAWRENCE, 1925: Differential absorption of anions by varieties of cotton, *Proc. Soc. Expt. Biol. Med.*, **22**: 350-352.
- HARVEY, R. B., 1927: Ionization and adsorption isoelectric points, *Plant Physiol.*, **2**: 220.
- HASSELBRING, H., 1914: The relation between the transpiration stream and the absorption of salts, *Bot. Gaz.*, **57**: 72-73.
- , 1914: The effect of shading on the transpiration and assimilation of the tobacco plant in Cuba, *Bot. Gaz.*, **57**: 257-286.
- HIBBARD, R. P., 1917: Physiological balance in the soil solution, *Mich. Agr. Coll. Expt. Sta. Tech. Bull.* 40.
- , 1927: Negative results on physiological balance in soil cultures, *Plant Physiol.*, **2**: 1-38.
- HIXON, R. M., 1920: The effect of the reaction of a nutrient solution on germination and the first stages of plant growth, *Medd. Vetenskapsak. Nobelinstitut*, **4**: 1-28.
- HOAGLAND, D. R., 1917: The effect of hydrogen and hydroxyl ion concentration on the growth of barley seedlings, *Soil Sci.*, **3**: 547-560.
- , 1918: The relation of the plant to the reaction of the nutrient solution, *Science*, n.s., **48**: 422-425.

- HOAGLAND, D. R., 1919: Relation of the concentration and reaction of the nutrient medium on the growth and absorption of the plant, *Jour. Agr. Res.*, **18**: 73-117.
- , 1919: Relation of nutrient solution to composition and reaction of cell sap to barley, *Bot. Gaz.*, **68**: 297-304.
- , 1920: Optimum nutrient solutions for plants, *Science*, n.s., **52**: 562-564.
- , 1923: The effect of the plant on the reaction of the culture solution, *Univ. Cal. Publ. Agr. Expt. Sta. Tech. Paper* 12.
- , 1923: The absorption of ions by plants, *Soil Sci.*, **16**: 225-246.
- and A. R. DAVIS, 1923: Further experiments on the absorption of ions by plants, including observations on the effect of light, *Jour. Gen. Physiol.*, **6**: 47-62.
- and ———, 1923: The composition of the cell sap of the plant in relation to the absorption of ions, *Jour. Gen. Physiol.*, **5**: 629-647.
- and J. C. MARTIN, 1923: A comparison of sand and solution cultures with soils as media for plant growth, *Soil Sci.*, **16**: 367-388.
- , 1925: Physiological aspects of soil solution investigations, *Hilgardia*, **1**: 227-257.
- and A. R. DAVIS, 1925: Suggestions concerning the absorption of ions by plants, *New Phytol.*, **24**: 99-111.
- , 1926: Some phases of the inorganic nutrition of plants in relation to the soil solution, *Sci. Agr.*, **6**: 141-151, 177-189.
- , P. L. HIBBARD, and A. R. DAVIS, 1926: The influence of light, temperature and other conditions on the ability of *Nitella* cells to concentrate halogens in the cell sap, *Jour. Gen. Physiol.*, **10**: 121-146.
- , A. R. DAVIS, and P. L. HIBBARD, 1928: The influence of one ion on the accumulation of another by plant cells with special reference to experiments with *Nitella*, *Plant Physiol.*, **3**: 473-486.
- ILIENKOFF, P. A., 1865: Einige Versuche zur Bestimmung des Einflusses, welchen die Bodenfeuchtigkeit auf die Vegetation ausübt, *Ann. Chem. Pharm.*, **136**: 160-165.
- ILJIN, W. S., 1924: The influence of salts on the alternation of concentration of cell sap in plants, *Studies in Plant Physiol. Lab. Charles Univ., Prague*, **2**: 5-25; *Bot. Abst.*, **15**: 799.
- IRWIN, MARIAN, 1923: The behavior of chlorides in the cell sap of *Nitella*, *Jour. Gen. Physiol.*, **5**: 427-428.
- , 1925: On the accumulation of dye in *Nitella*, *Jour. Gen. Physiol.*, **8**: 147-182.
- , 1926: Mechanism of the accumulation of dye in *Nitella* on the basis of the entrance of the dye as undissociated molecules, *Jour. Gen. Physiol.*, **9**: 561-575.
- JACOBSON, H. G. M., 1925: Changes in hydrogen-ion concentration in nutrient solutions. I, In a culture with wheat. II, In cultures with rice, *Jour. Amer. Soc. Agron.*, **17**: 577-583; 583-586.
- JOHNSON, H. V., 1915: The absorption of ions by living and dead roots, *Amer. Jour. Bot.*, **2**: 250-254.
- JOHNSTON, E. S., 1925: Comparative study of the "six types" of nutrient solutions in relation to the growth of potato plants in sand cultures, *Soil Sci.*, **20**: 397-403.
- , 1927: An apparatus for controlling the flow of nutrient solutions in plant cultures, *Plant Physiol.*, **2**: 213-215.
- JONES, L. H., 1921: Some factors affecting the rate of change of hydrogen-ion concentration in nutrient solutions, *N. J. Sta. Rept.* **1921**: 330-333.
- and J. W. SHIVE, 1922: Influence of wheat seedlings upon the hydrogen ion concentration of nutrient solutions, *Bot. Gaz.*, **73**: 391-400.
- JOST, L., 1907: "Lectures on Plant Physiology," Eng. ed., pp. 43, 79, Clarendon Press.
- KEARNEY, T. H., and L. L. HARTER, 1907: The comparative tolerance of various plants for the salts common in alkali soils, *U. S. Dept. Agr. Bur. Plant Ind. Bull.* 113.

- KIESSELBACH, T. A., 1916: Transpiration as a factor in crop production, *Univ. Nebr. Agr. Expt. Sta. Res. Bull.*, **6**: 170-184.
- KNOP, W., 1865: Quantitative Untersuchungen über den Ernährungsprocess der Pflanze, *Landw. Versuchs-Stat.*, **7**: 93-107.
- KOHL, F. G., 1886: "Die Transpiration der Pflanzen," 124 pp., II. Bruhn.
- LAPIQUE, L., 1925: Sur l'absorption des sels par les cellules végétales épictese et sélection, *Bull. Soc. Chim. Biol.*, **7**: 621-637; *Bot. Abst.*, **15**: 1161, 1926.
- LIVINGSTON, B. E., 1900: On the nature of the stimulus which causes the change of form in polymorphic green algae, *Bot. Gaz.*, **30**: 289-317.
- , 1906: A simple method for experiments with water cultures, *Plant World*, **9**: 13-16.
- and W. E. TOTTINGHAM, 1918: A new three-salt nutrient solution for plant cultures, *Amer. Jour. Bot.*, **5**: 337-347.
- , 1919: Review of Gericke's work on the influence of temperature on the physiological balance of nutrient solutions, *Plant World*, **22**: 26-27.
- , K. F. KELLERMAN, and WILLIAM CROCKER, 1919: A plan for cooperative research on the salt requirements of representative agricultural plants, *Rept. Com. Div. Biol. Agr. Nat. Res. Council.*
- LOEB, J., 1906: "Dynamics of Living Matter," Leincke & Buechner, Agents Columbia Press, New York.
- LOO, T., 1928: The effect of renewal of nutrient solutions upon the growth of culture plants and its relation to aeration, *Japan. Jour. Bot.*, **4**: 71-98.
- McCALL, A. G., 1915: A new method for the study of plant nutrients in sand cultures, *Jour. Amer. Soc. Agron.*, **7**: 249-252.
- , 1916: A method for the renewal of plant nutrients in sand cultures, *Ohio Jour. Sci.*, **16**: 101-103.
- , 1916: Physiological balance of nutrient solutions for plants in sand cultures, *Soil Sci.*, **2**: 207-255.
- and J. R. HAAG, 1920: The hydrogen-ion concentration of certain three-salt nutrient solutions for plants, *Soil Sci.*, **10**: 481-485.
- McHARGUE, J. S., 1923: Convenient supports for plants in pot or water culture experiments, *Soil Sci.*, **16**: 359-363.
- McLEAN, R. C., 1919: Studies in the ecology of tropical rain forests, with special reference to the forests of Brazil, *Jour. Ecol.*, **7**: 5-54; 121-172.
- MEIER, H. F. A., and C. E. HALSTEAD, 1921: Hydrogen-ion concentration relations in a three-salt solution, *Soil Sci.*, **11**: 325-353.
- MENDIOLA, N. B., 1922: Effect of different rates of transpiration on the dry weight and ash content of the tobacco plant, *Philippine Jour. Sci.*, **20**: 639-655.
- MEUER, R., 1909: Über die regulatorische Aufnahme anorganischen Stoffe durch die Wurzeln von *Beta vulgaris* und *Daucus Carota*, *Jahrb. f. wiss. Bot.*, **46**: 503-567.
- MUENSCHER, W. C., 1922: The effect of transpiration on the absorption of salts by plants, *Amer. Jour. Bot.*, **9**: 311-330.
- NATHANSOHN, A., 1903: Ueber Regulationserscheinungen im Stoffaustausch, *Jahrb. f. wiss. Bot.*, **38**: 241-290.
- , 1904: Über die Regulation der Aufnahme anorganischen Salze durch die Knollen von *Dahlia*, *Jahrb. f. wiss. Bot.*, **39**: 607-644.
- , 1904: Weitere Mitteilungen über die Regulation der Stoffaufnahme, *Jahrb. f. wiss. Bot.*, **40**: 403-442.
- OSTERHOUT, W. J. V., 1906: On the importance of physiologically balanced solutions for plants, *Bot. Gaz.*, **42**: 127-134.
- , 1907: On the importance of physiologically balanced solutions for plants, *Bot. Gaz.*, **44**: 259-272.

- OSTERHOUT, W. J. V., 1909: The nature of balanced solutions, *Bot. Gaz.*, **47**: 148-149.
- , 1909: The penetration of inorganic salts in living protoplasm, *Zeits. f. physikal. Chem.*, **70**: 408-413.
- , 1912: The permeability of protoplasm to ions and the theory of antagonism, *Science*, n.s., **35**: 112-115.
- , 1914: Quantitative criteria of antagonism, *Bot. Gaz.*, **58**: 178-186.
- , 1914: The measurement of antagonism, *Bot. Gaz.*, **58**: 272-276.
- , 1915: On the nature of antagonism, *Science*, n.s., **41**: 255-256.
- , 1915: The determination of additive effects, *Bot. Gaz.*, **60**: 228-234.
- , 1916: The penetration of balanced solutions and the theory of antagonism, *Science*, n.s., **44**: 395-396.
- , 1916: Antagonism and Weber's law, *Science*, n.s., **44**: 318-320.
- , 1917: Antagonism and permeability, *Science*, n.s., **45**: 97-103.
- , 1918: The basis of measurement of antagonism, *Jour. Biol. Chem.*, **34**: 363-368.
- , 1919: Decrease of permeability and antagonistic effect caused by bile salts, *Jour. Gen. Physiol.*, **1**: 405-409.
- , 1922: "Injury, Recovery and Death in Relation to Conductivity and Permeability," pp. 124-184, J. B. Lippincott Company, Philadelphia.
- , 1922: Some aspects of selective absorption, *Jour. Gen. Physiol.*, **5**: 225-231.
- , 1925: Is living protoplasm permeable to ions? *Jour. Gen. Physiol.*, **8**: 131-146.
- PANTANELLI, E., 1915: Assorbimenti elettivo di ion nelle piante, *Bull. Orto Bot. R. Univ. Napoli*, **5**: 1-54.
- , 1915: Über Ionenaufnahme, *Jahrb. f. wiss. Bot.*, **56**: 689-733.
- , 1918: Decorso dell' assorbimento di ioni nelle piante, *Bull. Orto Bot. R. Univ. Napoli*, **6**: 1-37.
- PEARSALL, W. H., and JAMES EWING, 1924: The isoelectric point of some plant proteins, *Biochem. Jour.*, **18**: 329-339.
- and ——, 1924: The diffusion of ions from living plant tissues in relation to protein isoelectric points, *New Phytol.*, **23**: 193-207.
- PEMBER, F. R., 1917: Studies by means of both pot and solution culture of the phosphorus and potassium requirements of the barley plant during its different periods of growth, *R. I. Agr. Expt. Sta. Bull.* 169.
- PFEFFER, W., 1900: "Physiology of Plants," Vol. I, p. 420, Eng. ed., Ewart, Clarendon Press.
- RABER, O. L., 1920: The antagonistic action of anions, *Jour. Gen. Physiol.*, **2**: 541-544.
- REDFERN, G. M., 1922: On the absorption of ions by the roots of living plants, *Ann. Bot.*, **36**: 167-174.
- REED, H. S., and A. R. C. HAAS, 1924: Some effects of certain calcium salts upon the growth and absorption of citrus seedlings, *Amer. Jour. Bot.*, **11**: 15-18.
- and ——, 1924: Some relations between the growth and composition of young orange trees and the concentration of the nutrient solution employed, *Jour. Agr. Res.*, **28**: 277-285.
- ROBBINS, W. J., 1923: An isoelectric point for plant tissue and its significance, *Amer. Jour. Bot.*, **10**: 412-440.
- RUDOLFS, WILLIAM, 1925: Effect of seeds upon hydrogen ion concentration equilibrium in solution, *Jour. Agr. Res.*, **30**: 1021-1026.
- , 1925: Selective absorption of ions by seeds, *Soil Sci.*, **20**: 249-252.
- RUHLAND, W., 1909: Zur Frage der Ionenpermeabilität, *Zeits. f. wiss. Bot.*, **1**: 747-763.
- SACHS, J., 1860: Vegetationsversuche mit Ausschluss des Bodens über die Nährstoffe und sonstigen Ernährungsbedingungen von Mais, Bohnen, und anderen Pflanzen, *Landw. Versuchs-Stat.*, **2**: 219-268.

- SACHS, J., 1887: "Lectures on the Physiology of Plants," Eng. ed., Clarendon Press.
- SALTER, R. M., and T. C. McILVAINE, 1917: The effect of reaction of solution on germination of seeds and on growth of seedlings, *Jour. Agr. Res.*, **19**: 73-97.
- SCHIMPER, A. F. W., 1890: Zur Frage der Assimilation der Mineralsalze durch die grüne Pflanze, *Flora*, **73**: 207-261.
- SCHLOSING, T., 1869: Tabac sous cloche et à l'air libre, *Ann. Sci. Nat. Bot.*, **V**, **10**: 366-369.
- SCHREINEMOCHER, F. A. H., 1893: Konzentrierung oder Verdünnung einer Lösung bei konstanter Temperatur, *Zeits. f. Physikal. Chem.*, **11**: 81-85.
- SCHREINER, O., and J. J. SKINNER, 1910: Ratio of phosphate, nitrate and potassium on absorption and growth, *Bot. Gaz.*, **50**: 1-30.
- and —, 1910: Some effects of a harmful organic soil constituent, *U. S. Dept. Agr. Bur. Soils Bull.*, **70**.
- and —, 1918: The triangle system for fertilizer experiments, *Jour. Amer. Soc. Agron.*, **10**: 225-246.
- SCOFIELD, C. S., 1927: The effect of absorption by plants on the concentration of the soil solution, *Jour. Agr. Res.*, **35**: 745-757.
- SEWELL, M. C., 1924: Relation of the molecular proportions in the nutrient solution to the growth of wheat, *Jour. Agr. Res.*, **28**: 387-393.
- SHIVE, J. W., 1915: A study of physiological balance in nutrient media, *Physiol. Res.*, **1**: 327-399.
- , 1915: A three-salt nutrient solution for plants, *Amer. Jour. Bot.*, **2**: 157-160.
- , 1917: A study of physiological balance for buckwheat grown in 3-salt solutions, *N. J. Sta. Bull.* **319**.
- and W. H. MARTIN, 1918: A comparison of salt requirements for young and for mature buckwheat plants in water cultures and sand cultures, *Amer. Jour. Bot.*, **5**: 186-191.
- , 1919: The influence of the moisture content of sand cultures upon the physiological salt balance for plants, *N. J. Sta. Rept.* **1919**: 358-363.
- , 1919: The influence of sand of different degrees of fineness upon the concentration and reaction of a nutrient solution, *N. J. Sta. Rept.* **1919**: 363-366.
- , 1920: Relation of moisture in solid substrata to physiological salt balance for plants and to the relative plant-producing value of various salt proportions, *Jour. Agr. Res.*, **18**: 357-378.
- , 1920: The influence of sand upon the concentration and reaction of a nutrient solution for plants, *Soil Sci.*, **9**: 169-179.
- , 1920: The influence of varying degrees of soil moisture upon the physiological salt balance for plants, *N. J. Sta. Rept.* **1920**: 387-395.
- , 1922: The relation of soil moisture to physiological salt balance for plants, *Soil Sci.*, **14**: 391-411.
- and A. L. STAHL, 1927: Constant rates of continuous solution renewal for plants in water cultures, *Bot. Gaz.*, **84**: 317-323.
- SIDERIS, C. P., B. H. KRAUSS, and E. MASUNAGA, 1928: The effect of salt concentration of the culture solution on the growth and composition of pineapple plants, *Amer. Jour. Bot.*, **15**: 353-372.
- SKENE, MACGREGOR, 1915: The acidity of sphagnum and its relation to chalk and mineral salts, *Ann. Bot.*, **29**: 65-87.
- SORAUER, P., 1880: Studien über Verdünnung, *Forschungen auf dem Gebiete der Agr. Physik.*, **3**: 351-490.
- STAHL, E., 1894: Einige Versuche über Transpiration und Assimilation, *Bot. Zeitung*, **52**: 117-146.
- STILES, WALTER, 1915: On the relation between the concentration of the nutrient solution and the rate of growth of plants in water culture, *Ann. Bot.*, **29**: 89-97.

- STILES, WALTER, 1916: On the interpretation of the results of water culture experiments, *Ann. Bot.*, **30**: 427-436.
- and I. JORGENSEN, 1917: Observations on the influence of aeration of the nutrient solution in water culture experiments with some remarks on the water culture methods, *New Phytol.*, **16**: 182-197.
- and F. KIDD, 1919: The comparative rate of absorption of various salts by plant tissue, *Proc. Roy. Soc., B*, **90**: 487-504.
- and ———, 1919: The influence of external concentration on the position of the equilibrium attained in the intake of salts by plant cells, *Proc. Roy. Soc., B*, **90**: 448-470.
- , 1924: The absorption of salts by storage tissue, *Ann. Bot.*, **38**: 617-635.
- STOLHANE, A. A., 1914: A comparative study of nutritive solutions in sand and water cultures, *Rec. Trav. Lab. Agron. Moskov. Selsk. Khoz. Inst.*, **10**: 289-336; *Expt. Sta. Rec.* **36**: 630.
- TARR, L. W., and S. C. NOBLE, 1922: The effect of hydrogen ion concentration upon the growth of seedlings, *Del. Agr. Expt. Sta. Bull.* 131.
- TOLLENS, B., 1882: Ueber einige Erleichterungen bei der Cultur von Pflanzen in wasserigen Lösungen, *Jour. f. Landw.*, **30**: 537-540.
- TOOLE, E. H., and W. E. TOTTINGHAM, 1918: The influence of certain added solids upon the composition and efficiency of Knop's nutrient solution, *Amer. Jour. Bot.*, **5**: 452-461.
- TOTTINGHAM, W. E., 1914: A quantitative chemical and physiological study of nutrient solutions for plant cultures, *Physiol., Res.*, **1**: 133-245.
- TRELEASE, S. F., 1917: The relation of the concentration of the nutrient solution to the growth of young wheat plants in water cultures, *Johns Hopkins Univ. Circ.*, n. s., **3**: 225-227.
- and E. E. FREE, 1917: The effect of renewal of culture solutions on the growth of young wheat plants in water culture, *Johns Hopkins Univ. Circ.*, n. s., **3**: 227-228.
- and B. E. LIVINGSTON, 1922: Continuous renewal of nutrient solution for plants in water culture, *Science*, n. s., **55**: 483-486.
- and ———, 1924: The relation of climatic conditions to the salt-proportion requirements of plants in solution cultures, *Science*, n. s., **59**: 168-172.
- , 1925: Chamber with thermostatic control and rotating table for plant cultures, *Bull. Torrey Bot. Club*, **52**: 389-395.
- , and H. M. TRELEASE, 1926: Relation of temperature to the physiological values of salt solutions as indicated by growth of wheat roots, *Bull. Torrey Bot. Club*, **53**: 605-609.
- and ———, 1926: Toxicity and antagonism in salt solutions as indicated by growth of wheat roots, *Bull. Torrey Bot. Club*, **53**: 137-156.
- TRUE, R. H., and W. J. GIES, 1903: On the physiological action of some of the heavy metals in mixed solutions, *Bull. Torrey Bot. Club*, **30**: 390-402.
- , 1915: Antagonism and balanced solutions, *Science*, n. s., **41**: 653-656.
- and H. H. BARTLETT, 1915: The exchange of ions between the roots of *Lupinus albus* and cultural solutions containing one nutrient salt, *Amer. Jour. Bot.*, **2**: 255-278.
- and ———, 1915: The exchange of ions between the roots of *Lupinus albus* and cultural solutions containing two nutrient salts, *Amer. Jour. Bot.*, **2**: 311-323.
- and ———, 1916: The exchange of ions between the roots of *Lupinus albus* and culture solutions containing three nutrient salts, *Amer. Jour. Bot.*, **3**: 47-57.
- WEATHERWAX, P., 1916: An apparatus for aerating culture solutions, *Proc. Ind. Acad. Sci.*, 1914: 157-160.

- WODEHOUSE, R. P., 1917: Direct determinations of permeability, *Jour. Biol. Chem.*, **29**: 453-458.
- WOLLNEY, W., 1898: Untersuchungen über den Einfluss der Luftfeuchtigkeit auf das Wachstum, *Bot. Centrbl.*, **76**: 249.
- WOODWARD, J., 1699: Thoughts and experiments on vegetation, *Phil. Trans. Roy. Soc. London*, **21**: 382-398.

CHAPTER VI

THE ELEMENTS ABSORBED BY THE PLANT

I. NUMBER AND KIND

(According to Palladin (1911), 35 elements have been detected in the analysis of plants. These are carbon, hydrogen, oxygen, nitrogen, sulphur, phosphorus, potassium, magnesium, calcium, iron, chlorine, bromine, iodine, fluorine, boron, silicon, sodium, lithium, rubidium, strontium, barium, zinc, mercury, aluminum, thallium, titanium, tin, lead, arsenic, selenium, manganese, cobalt, nickel, copper, and silver. Robinson, Steinkoenig, and Miller (1917)

analyzed a large number of plants from different regions for the rarer elements. In addition to those just mentioned, they detected chromium, vanadium, and caesium. Vanadium was found, however, in only six cases and then only in traces. Caesium was detected in only three cases and in two of them caesium beryls were known to be present in that region. A general idea of the number and relative amounts of the elements that compose plants may be had by considering a given plant, although, as will be mentioned below, the elemental composition of a plant will depend upon the species and upon the conditions under which it is grown.




FIG. 13.—Diagram showing the elemental composition of a corn plant at the late dough stage.

be taken as this example. These plants were analyzed at a stage when the grain was fully dented and in the late dough stage. The leaves were all intact and the plants were evidently at a stage where absorption of solutes from the soil had practically ceased. The proportion of these different elements is shown in Fig. 13 and in the following table:

WEIGHT OF THE ELEMENTS THAT COMPOSED THE STEM, LEAVES, COB, GRAIN, AND
ROOTS OF PRIDE OF SALINE CORN PLANTS GROWN AT MANHATTAN, KANS.,
IN 1920

(Average of Five Plants)

Average dry weight of stems, leaves, cob, grain, and roots, 835.9 g.	Weight, grams	Percentage of the total dry weight
Oxygen.....	371.4	44.431
Carbon.....	364.2	43.569
Hydrogen.....	52.2	6.244
Nitrogen.....	12.2	1.459
Phosphorus.....	1.7	0.203
Potassium.....	7.7	0.921
Calcium.....	1.9	0.227
Magnesium.....	1.5	0.179
Sulphur.....	1.4	0.167
Iron.....	0.7	0.083
Silicon.....	9.8	1.172
Aluminum.....	0.9	0.107
Chlorine.....	1.2	0.143
Manganese.....	0.3	0.035
Undetermined elements.....	7.8	0.933

From the foregoing table it is seen that the bulk of a plant is composed of a relatively small number of elements, but as will be mentioned later some of those which occur in the plant in only relatively small amounts are just as essential to its growth and development as those which compose the greater portion of it. The various elements that compose a plant will vary depending upon the species of plant and upon the composition of the soil in which it is grown.

A. INFLUENCE OF THE PLANT

(It is common knowledge that plants of different species grown under identical conditions differ in their elemental composition, especially in regard to the proportionate amount of the various elements that compose them. The variation in the percentage of N, Ca, Mg, and K in some of the more common crop plants, which is due primarily to the type of plant, is shown in the table on page 234, adapted from Parker and Truog (1920).)

Observations have been made by Richardson (1920), Headden (1921), Skinner and Reid (1921), Greaves and Nelson (1925), Wherry (1926), Wrangell (1927), Newton (1928), and others in regard to the different proportions of the elements contained in plants of different species grown under the same conditions. Richardson (1920) determined the composition of the ash of certain dune plants and the sand in which they grew.

PERCENTAGE OF NITROGEN, CALCIUM, MAGNESIUM, PHOSPHORUS, AND POTASSIUM
 IN VARIOUS CROP PLANTS

Kind of plant	Condition of plant	Percentage in dry material of				
		Nitrogen	Calcium	Magnesium	Phosphorus	Potassium
Cabbage (<i>Brassica oleracea capitata</i>).....	Mature	4.0	1.9	0.4	0.5	
Lettuce (<i>Lactuca sativa</i>).....	Green	3.9	1.9	0.7	0.7	
Tobacco (<i>Nicotiana tabacum</i>).....	Ripe	3.5	2.7	0.5	0.4	3.1
Cowpea (<i>Vigna unguiculata</i>).....	Hay	3.4	1.9	0.5	0.2	0.8
Soybean (<i>Glycine hispida</i>).....	Hay	2.8	2.0	0.7	0.3	0.9
Rape (<i>Brassica napus</i>).....	Bloom	2.8	1.2	0.2	0.4	2.2
Radish (<i>Raphanus sativus</i>).....	Mature	2.6	1.5	0.3	0.3	2.5
Mammoth clover (<i>Trifolium medium</i>).....	Bloom	2.6	1.5	0.6	0.2	2.6
Sweet clover (<i>Melilotus alba</i>).....	Hay	2.5	1.4			
Wheat (<i>Triticum vulgare</i>).....	Straw	2.1	0.3	0.1	0.3	2.7
Corn (<i>Zea mays</i>).....	Fodder	1.4	0.6	0.4	0.3	1.7
Timothy (<i>Phleum pratense</i>).....	Hay	1.4	0.4	0.1	0.3	1.9
Redtop (<i>Agrostis vulgaris</i>).....	Hay	1.3	0.4	0.1	0.2	0.9

Approximately 92 per cent of this sand was silica, while the remainder consisted of iron and aluminum oxides 4.3 per cent, calcium oxide 1.4 per cent, magnesium oxide 0.7 per cent, potassium oxide 1.0 per cent, and less than 1 per cent of organic matter. The composition of the ash of the sand cherry (*Prunus pumila*), artemisia (*Artemisia caudata*), *Andropogon* (sp.), and the scouring rush (*Equisetum hyemale*) growing in this sand will suffice to show the specific differences in the amount of certain elements absorbed by these plants.

ANALYSIS OF THE ASH OF PLANTS GROWING IN SAND DUNES

Constituent	Percentage of the ash			
	<i>Prunus pumila</i>	<i>Artemisia caudata</i>	<i>Andropogon</i>	<i>Equisetum hyemale</i>
Silica.....	1.5	12.1	65.4	49.4
Iron oxide.....	0.7	1.7	2.5	1.0
Aluminum oxide.....	0.02	0.4	2.6	2.3
Calcium oxide.....	44.1	35.5	10.2	13.4
Potassium oxide.....	10.9	11.6	6.7	6.0
Magnesium oxide.....	4.2	6.4	3.2	3.7

The most striking differences to be observed in the proportion of elements absorbed by these plants is in the amounts of silicon, calcium, and aluminum. *Andropogon* and *Equisetum* absorbed and accumulated

large amounts of silicon, while *Prunus* and *Artemisia* accumulated only a relatively small amount. *Prunus* and *Artemisia*, on the other hand, accumulated from three to four times as much calcium as did *Andropogon* and *Equisetum*, while the amount of aluminum is from six to ten times greater in some plants than in others.

Headden (1921) noted that alfalfa growing in soils which contained both lithium and strontium had little or no lithium in the ash but that strontium was present in considerable quantity. In tobacco, on the other hand, growing in the same soil, lithium was present in considerable quantity, but very little or only a trace of strontium could be detected. Greaves and Nelson (1925) found that the iron content of wheat increased with the amount of irrigation water applied during the season. Thus when 35 in. of water were applied, the wheat plants contained 1.7 times as much iron as those grown without water, but the irrigation water was without effect on the iron content of oats and barley. The chlorine content of wheat was 2.7 times as high as that grown without irrigation, but no definite effects were noted on the chlorine content by the application of water to oats and barley. Newton (1928) grew sunflowers, beans, wheat, barley, peas, and corn in the same nutrient solution in the same container. He harvested the wheat and barley at the heading stage, the corn at the time of tasseling, and the peas and beans at the blooming stage and determined the percentage of the various elements present in the plant. The similarities and differences in absorption which are characteristic of these plants are shown in the following data:

Plant	Percentage of the dry weight of				
	Ca	K	Mg	N	P
Sunflower.....	2.2	5.0	0.64	3.6	0.56
Beans.....	2.1	4.0	0.59	3.6	0.55
Wheat.....	0.8	6.7	0.41	4.5	0.49
Barley.....	1.9	6.9	0.54	4.7	0.52
Peas.....	1.6	5.3	0.50	4.5	0.19
Corn.....	0.5	3.9	0.40	2.9	0.39

The sunflower plant contained 2.7 times as much calcium as the wheat plant and 4.4 times as much as the corn. The sunflower also contained approximately 1.5 times as much magnesium as wheat and corn. Wheat and barley contained a percentage of potassium considerably higher than that for any of the other plants. Newton found that absorption from the cultural solution of the various elements was higher than by plants grown in a loam soil and that there was much less variability in absorption from the solution than from the soil. An observation of Wrangell (1927) is worthy of note in considering the different rates of

absorption by plants. He noted the differences in the amount of iodine contained in different types of plants growing in the same soil and found that lettuce and spinach contained 100 times more iodine than other agricultural plants under the same conditions.

(Since different plants are composed of different proportions of the various elements, the statement is frequently made that plants exercise "selective absorption" or "feeding power.") Since these terms have been so frequently used and since they have been so differently interpreted, they should be mentioned here. It has been assumed by some that the differences in the composition of plants are due primarily to differences in the specific absorbing powers of the roots. They consider thus that the absorbing cells of the roots differ in their ability to exclude certain elements more than others. On the other hand, some consider that the difference in the amount of certain elements in plants is due to the specificity of the protoplasm, which requires different proportions of materials for its development in different plants. The protoplasm of the developing cells is thus considered to regulate the amount of any given element in the plant rather than the regulatory action of the absorbing cells of the root. The speed of absorption of a given compound in this case would thus be determined by the rate at which it was utilized by the cells in the interior of the plant. As has been mentioned in Chap. V, the absorption of solutes is apparently not so simple a process and the phenomenon of the heaping up of salts in the ionic form on the interior of the absorbing cells cannot be explained by either of the above-mentioned theories. Davis, Hoagland, and Lipman (1923) also point out that the differences in the extent of the root systems and the differences in the rate of production of CO_2 by these roots are factors which may determine to a considerable degree the differences in the amount of minerals absorbed by plants. It seems fairly certain that the absorption of ions by plants is not a selective process in the strict sense of the term and that the factors which control it are little or imperfectly understood.

B. INFLUENCE OF THE ELEMENTS OF THE SOIL

(The amount of any element that is found in the plant is influenced by the abundance and location of that element in the soil.) Thus Sharrer and Strobel (1927) and Orr, Kelly, and Stuart (1928) found that they could greatly increase the iodine content of sugar beets, peas, oats, and alfalfa by the addition of this element to the soil in which these plants were growing. Parker and Pierre (1928) grew corn in various concentrations of PO_4 from 0.05 to 50 ppm. During the younger stages of growth, increased concentration increased absorption; but in later periods, the absorption was not proportional to the concentration of the external solution in many cases. In case of potassium, the maximum growth of corn was secured with 2 ppm. The concentration necessary for growth,

however, varies with the species. Thus soybeans and tomatoes give maximum growth at 3 to 5 ppm. of K, while maximum growth is secured for oats at 2 ppm. and alfalfa at only 1 ppm.

The location of the various nutrients with respect to the roots may have a marked effect upon the amount of elements contained in the plant, as indicated by the work of Gile and Carrero (1917, 1921). They grew corn plants in such a way that the roots were divided among three solutions each of which lacked two elements so that the N was in one flask, the P in another, and the K in a third. It was found that the amount of these three elements in the plants thus grown was lower than under normal conditions, although the rate of absorption of N, for example, was greatly increased by the roots in that solution. The cause of the smaller amount is seemingly due to the slowness of distribution of these elements within the plant, since they have to be transferred over the plant by and from a comparatively small number of fibrovascular bundles.

The amount of a given element in a plant may be influenced by the proportion and kind of other elements contained in the soil or culture solution. Thus Ginsburg (1925) found that soybeans growing in a complete nutrient solution had an ash content of 13.3 per cent. When P was withheld from the solution, the ash content was 18.6 per cent and amounted to 18.4 per cent when magnesium was lacking. The plants growing in the incomplete cultural solutions, with the exception of those grown in solutions lacking sulphur, always absorbed higher percentages of calcium and lower percentages of both N and Mg than did the checks. In the case of spinach, which was grown on soil that was heavily fertilized with different fertilizers or mixtures thereof, it was observed that the Ca, Mg, and S content of the plant soon reached an equilibrium regardless of the quantity or kind of nutrients applied but that the Si, K, and Na content showed wide fluctuation with the various applications of nutrients (True, 1919). Leaves of orange trees growing in cultures to which no calcium salts were added were found to be rich in K, while those of plants receiving no K salts in the nutrients were high in calcium (Reed and Haas, 1923).

If there is an abundance of the soluble inorganic salts present in the soil, most plants will absorb a greater quantity of them than is necessary for their maximum growth. This has been especially noted for the salts of P, K, and S. Jordan (1913) in nutrition experiments with barley, peas, tomatoes, tobacco, buckwheat, and rape noted that both P and K compounds increased in amount in these plants after the maximum increase in growth had been reached. Similar observations have been made by Hoagland (1919 and 1926), who found that the concentration of the cell sap in regard to electrolytes is much higher than its concentration in the soil. A further indication that many of the elements are

present in the plant cells in excess of their needs is the fact that a large proportion of them in many cases can readily be extracted with water. Thus Ames and Boltz (1912) found in the alfalfa plant that 90 per cent of the K, 85 per cent of the Mg, 75 per cent of the N, and 50 per cent of the S were soluble in water. A considerable portion of the N is known to be in simple soluble protein compounds, but apparently the other elements mentioned are only loosely combined and probably not at all.

These observations indicate that an analysis of the plant does not necessarily give any indication of the deficiencies or fertilizer needs of the soil and that the amount of a certain element in a plant must not necessarily be regarded as a measure of what must be supplied in order to meet the needs of maximum growth (Salter and Ames, 1928). Some work, however, by Gilbert and Hardin (1927) and Gilbert, McLean, and Adams (1927) indicates that in some cases under certain conditions the current nutrient content of the plant solution may be an indicator of the fertilizer needs of the plant.

The proportion of the various elements that may be found in plants depends thus upon numerous and varied factors such as the species of plant, the type of soil, the distribution of roots, the rainfall, and general climatic conditions as well as the methods of cultivation. It is doubtful, therefore, whether any sort of rule governing these proportions can ever be formulated.

C. DISTRIBUTION OF THE ELEMENTS IN THE PLANT

The distribution of these various elements in the different parts of the plant is shown in the following table. A knowledge of their distribution is of importance in interpreting the rôle which they serve in the functions of the plant.

PERCENTAGE DISTRIBUTION OF THE DIFFERENT ELEMENTS IN VARIOUS PARTS OF CORN PLANTS GROWN AT MANHATTAN, KANS., IN 1920

Organ	C	O	H	N	P	K	Ca	Mg	S	Fe	Si	Al	Cl	Mn
Leaves.....	26.6	27.7	26.3	25.0	28.6	45.2	58.2	32.3	39.8	23.0	62.3	19.5	42.8	27.9
Stems.....	24.5	23.7	22.7	13.8	10.5	32.2	18.0	21.0	22.7	14.6	8.6	2.9	36.9	12.6
Grain.....	32.0	31.8	34.8	46.0	52.3	14.2	3.4	34.2	25.8	15.7	0.4	6.7	7.1	35.7
Roots.....	7.0	7.1	9.5	6.3	4.2	3.6	19.5	6.8	10.7	44.1	27.6	66.3	5.4	14.9
Cobs.....	9.8	9.7	6.6	8.9	4.4	4.7	0.9	5.6	1.1	2.7	1.1	4.6	7.8	8.0

The distribution of the various elements in the plant parts varies to some extent with the stage of growth. The distribution of the elements in barley will suffice as an example (Pfeiffer, Rippel, and Pfothenauer, 1919). The total ash in this plant increased up to the time of the milk stage. The total P increased up to harvest time, being highest in the leaves before heading and in the stems at heading time. The total Ca

increased up to the milk stage and was highest in the leaves at heading time and in the stems during the milk stage. The total K increased up to the milk stage and was highest in the leaves before heading. The total N increased up to harvest time, being highest in the leaves before heading and in the stem at heading time.

II. FORM

A green plant obtains practically all its carbon and a part of its oxygen from the air and all the other elements from the soil. With the exception of some of the oxygen, all the elements that enter a plant must be presented to it in the form of soluble compounds. Oxygen is the only element that the plant can utilize when presented in the elemental form, but it, too, enters the plant dissolved in water.

A. INORGANIC COMPOUNDS

It is a definitely established fact that the green plant is able to grow and develop to maturity if it is supplied with the necessary inorganic compounds in sufficient quantity for its needs. Under the proper conditions of light, climate, and soil fertility, the green plant is capable of manufacturing from the simple inorganic compounds which it obtains from the soil and the air all the numerous and varied organic substances that enter into its composition. The kind of inorganic compounds that best serve the needs of the plant will be discussed later in this chapter.

B. ORGANIC COMPOUNDS

The concentration of the soluble organic substances in the soil may be as high as that of the inorganic compounds, so it is of interest to know to what extent the green plant can absorb and utilize organic material. The most extensive experimental work has been done with the carbohydrates, organic acids, and nitrogenous compounds, although numerous other substances have been used.

1. Carbohydrates.—Acton (1889) supplied various carbohydrates and glycerin to *Acer pseudoplatinus*, *Phaseolus vulgaris*, *Quercus robur*, and *Euphorbia hirsuta* among other plants growing in water cultures. He found that glucose, saccharose, and glycerin were absorbed and utilized in the dark by these plants in the formation of starch but that glycogen, dextrin, and soluble starch were not so utilized. Laurent (1904) showed that corn, beans, and other plants could absorb glucose through their roots and utilize it, as indicated by the formation of starch in their leaves. The same results were also noted by Mazé and Perrier (1904) for corn grown in water cultures.

Knudson (1916) studied the influence of carbohydrates on plant growth by growing them under sterile conditions in an agar medium to

which Pfeffer's nutrient solution and a sugar solution varying in concentration from one to two per cent had been added. The assimilability of the sugar was judged by noting the influence on the dry weight of the plants. Knudson found that corn thus grown was able to absorb by means of its roots and utilize in its metabolism glucose, fructose, saccharose, and maltose, the beneficial effects being in the order that the sugars are here named. Canada field peas responded in growth to the presence of saccharose, glucose, maltose, and lactose in the order stated. Timothy, vetch, and radish were also benefited by the presence of sugar. In the case of radish, the average dry weight of 71-day-old plants was as follows:

WEIGHT IN GRAMS

Case	Plants grown in Pfeffer's solution plus				
	Check	Sucrose 2 per cent	Maltose 2 per cent	Glucose 2 per cent	Lactose 2 per cent
I.....	0.791	1.237	1.572	1.713	1.128
II.....	1.208	1.950	2.461	1.900

The beneficial effects of sugar when supplied to the roots of the radish were also observed by Molliard (1907). Robbins (1918) grew the moss plant (*Ceratodon purpureus*) on sterile culture media and found that organic carbon in the form of levulose, glucose, galactose, lactose, sucrose, and maltose was absorbed and utilized, as was evidenced by the formation of starch in the plant in the dark. Mannite, glycerin, and starch, however, could not be utilized. He observed that the amount of growth with levulose as a source of carbon was from two to seven times greater than that with glucose as a source of carbon and that with the presence of levulose the greater amount of growth occurred in the dark, while with glucose the greater amount occurred in the light. Light, however, seems to be necessary for the continued growth of this moss plant, even though a supply of available carbohydrates is furnished.

Brannon (1923), using the methods of Knudson, obtained data that indicate that different kinds of plants differ as to the sugar they are able to use most efficiently. Alfalfa grew best for him in solutions containing glucose, while timothy did better in solutions containing fructose. The radish used both sugars equally well. It seems that all the plants tested can use glucose and sucrose to some degree, while galactose, mannose, and fructose have been shown to be toxic to some plants under certain conditions. Roach (1926) studied the relation of soluble carbon compounds to the growth of certain soil algae. He found the relative average rates of growth in the different media to be as follows: glucose in the

light 100 per cent, maltose 100 per cent, galactose 94 per cent, sucrose 84 per cent, fructose 73 per cent, glycerin 43 per cent, and mineral salts alone 60 per cent. He also observed (1927) that the five species examined were capable of growing in complete darkness provided that a suitable organic compound was present in the medium.

The evidence that green plants can absorb and utilize carbohydrates is based in many cases upon the behavior of plants grown in the dark. The abnormal development and behavior of plants when grown in darkness, however, prevents one from drawing a general conclusion as to the response of green plants to organic nutrients under normal conditions of plant growth. The process of photosynthesis is a factor, too, which prevents a clear conception of the response of plants to organic nutrients, and this process cannot be eliminated in green plants when grown in the open in daylight even if the atmosphere is depleted of carbon dioxide. The process of respiration releases within the cells a considerable quantity of this gas, which is utilized at once by the chloroplasts in the process of photosynthesis. Excellent material for a study of organic nutrition would seem to be the albino plants, which frequently appear as sports in numerous species. These plants are apparently comparable in every regard to the green plants with the exception that they lack chlorophyll and functional plastids so that they cannot carry on photosynthesis.

Knudson and Lindstrom (1919) studied the effect of sugars upon the duration and growth of albino corn plants. Plants that were grown in Pfeffer's solution to which was added a two-tenth molecular solution of sucrose showed a very appreciable gain in weight during a 55-day experiment, while those grown in Pfeffer's solution alone showed a loss and perished 25 days sooner than those supplied with sugar. These authors attribute the failure of the albino plants to make a sustained growth to the slow diffusion of the sugar so that the plants were unable to absorb a sufficient amount of organic material to supply the needs of the entire plant. Their hypothesis is strengthened by the fact that after the leaves are dead, the roots continue to remain alive in the sugar solution several months after the check plants are dead. Robbins (1925) observed that excised root tips of peas, corn, and cotton made considerable growth in the dark in solution cultures containing mineral salts and glucose and fructose but that they made little growth under the same conditions when carbohydrates were lacking. The growth of these roots was markedly greater in the cultures containing glucose than in those containing fructose.

2. Organic Acids.—Ravin (1913) investigated the influence of certain organic acids and their neutral and acid salts on the growth of the radish. His results as summarized in the following table by Knudson (1916) indicate that the radish can absorb and make use of in growth such acids as malic, tartaric, succinic, and citric and their salts:

Culture medium	Dry weight grown in free atmosphere, milligrams	Dry weight grown in confined atmosphere, milligrams
Knop's solution.....	36.3	11.7
+ KHSO ₄	41.0	16.9
+ K ₂ SO ₄	42.0	17.0
+ Glucose.....	54.9	30.5
+ free organic acid.....	52.5	30.5
+ acid potassium salts of or- ganic acids.....	53.9	33.0
+ neutral potassium, salts of organic acids.....	53.6	28.7

3. Organic Nitrogenous Compounds.—The utilization of organic nitrogenous compounds is discussed in detail under The Nitrogen Metabolism of the Green Plant (Chap. IX).

The absorbing system of the green plant is apparently adjusted for the absorption of the rapidly diffusing inorganic compounds and cannot readjust itself for the intake of sufficient quantities of the more complex organic compounds to supply all its needs for growth and repair. The experimental evidence indicates that green plants are capable of absorbing by their roots and utilizing in their metabolism a sufficient amount of organic matter to have a beneficial influence upon their growth. It seems evident, therefore, that the soluble organic matter of the soil may play a direct rôle in the nutrition of green plants.

III. ESSENTIAL VS. UNESSENTIAL ELEMENTS

From 1860 to 1900 much experimental work was done by Sachs, Knop, Nobbe, Pfeffer, and others to determine the elements that are essential to plant life. Their work indicated that ten elements are absolutely necessary for all green plants. These are C, O, H, N, P, K, Ca, Mg, S, and Fe and have been considered until quite recently as the only ones necessary for the normal growth and development of plants. The other elements found in plants were considered of little or no physiological importance and their presence was attributed to the fact that they entered the plant simply because of their occurrence in the soil in the soluble form; if comparatively large amounts were present, it was attributed to a specific power of the plant to accumulate them.

The experimental work by which the so-called "essential" elements were determined was considered to be above criticism until quite recently, when it was discovered that there are three important sources of error that had been overlooked. In the first place, many at least of the so-called "chemically pure" chemicals then used contained impurities that might

supply elements other than the ten in sufficient amount to influence plant growth. In the second place, the various elements in the seed were not taken into consideration and it is now known that the seed contains a sufficient amount of certain elements to supply the needs of the plant even up until the time of fruiting. Thirdly, no precautions were taken to avoid the contamination of the cultures by certain elements which may dissolve in small amounts from the walls of the containers. The elements needed by plants subserve two main functions: (a) Some of them are component parts of the cell structure. The amount of the different elements used for these purposes is relatively large and any deficiency of them is soon noticed in the general growth of the plant. (b) Some of the elements apparently act as carriers of other ions, catalyzers of reactions, or antidoting agents. For these purposes the amount of some of the elements needed is very small and could easily be supplied in sufficient amount by impurities from the three sources that have just been mentioned. The observation that small amounts of certain of the so-called "unessential" elements improve the growth of certain plants and the discovery of the relation of vitamins in animal nutrition have perhaps given the impetus to renew the investigations concerning the rôle of many of the elements that have been considered unessential.

Mázé (1914, 1915, 1919) has led the field in this work. He considered that zinc, silicon, chlorine, aluminum, boron, and perhaps other elements are essential to the growth and development of green plants. McHargue (1919 to 1927) in extended experiments, which will be discussed later in the chapter, has furnished very convincing data to prove that manganese is an essential element for plant growth. He considers that plants obtain such factors as are necessary for their growth from the mineral elements contained in a fertile soil, taking up small amounts of iron, manganese, copper, zinc, boron, nickel, and others with the aid of which are synthesized complex organic compounds in the plant. He considers that these organic compounds function as enzymes, catalysts, and vitamins and that when they are consumed by animals they are resynthesized into catalases, oxidases, hormones, and animal vitamins. Warrington (1923, 1926), Brenchley (1914), and Brenchley and Thornton (1925) have shown that *Vicia faba* (Windsor bean) will not grow normally in water cultures unless small quantities of boron are added. A histological study showed that there is also a marked change in the anatomy of the root and nodules in the absence of this element (see boron). Sommer and Lipman (1926) furnish evidence that boron is indispensable to the development of Windsor bean, buckwheat, flax, mustard, castor bean, cotton, and barley and that zinc is essential for the dwarf sunflower and barley. Sommer (1928) noted in the case of buckwheat that the plants grown without zinc were much smaller than the controls. The average dry weight per culture grown without zinc was 1.94 g., while that with zinc was 8.45 g. In

Vicia faba there was no visible difference between plants grown with and without zinc until the flowering stage was reached. Then most of the flower buds fell off and if pods developed no seeds were formed when zinc was lacking, but where it was supplied, the plants bloomed freely and produced seed. The plants of buckwheat and sunflower that survived in the absence of zinc had the appearance of plants that had grown on poor soil. Haas and Reed (1927) found that young orange trees grown in sand cultures with the ordinary nutrient solutions showed marks of decline, while those receiving cultural solutions made with tap water did not show these symptoms. The leaves curled, became spotted and corky, and split along the veins. In other cases, the leaves were shed prematurely and multiple buds were formed in the leaf axils or above the former leaf scars, but none of them was able to develop. They discovered that these plants could be rejuvenated by the addition to the sand culture solution of a suspension so as to give a concentration of 0.2 ppm. of Al, I, Ti, Br, Sr, Li, Mn, B, and NH_4 , respectively. The salts used were $\text{Al}_2(\text{SO}_4)_3$, KI, $\text{Ti}(\text{SO}_4)_2$, KBr, $\text{Sr}(\text{NO}_3)_2$, LiNO_3 , MnSO_4 , NH_4NO_3 , and boric acid. Within a week after this application, signs of rejuvenation were observed, new growth was in evidence, and none of the symptoms previously mentioned remained. These results indicate that some elements other than those in the regular nutrient solutions exerted a beneficial influence upon the growth of these plants.

As our knowledge now stands, we are not justified in saying that only ten elements are necessary for plant life but must acknowledge that apparently others are essential. At least we are safe in saying that many of the so-called "non-essential" elements have a marked influence on the growth and development of plants.

IV. OCCURRENCE AND FUNCTION

A. CARBON, HYDROGEN, OXYGEN, AND NITROGEN

Carbon, hydrogen, and oxygen enter into the composition of practically all organic compounds of the plant and make up approximately 95 per cent of its dry weight. The carbon is practically all obtained from the air in the form of carbon dioxide. The hydrogen and a considerable portion of the oxygen are obtained from the water absorbed by the plant. The remainder of the oxygen is obtained in the elemental state from the atmosphere. Nitrogen enters into the composition of the proteins which in turn are apparently the active components of the protoplasm. The subject of nitrogen nutrition is discussed in detail in Chap. IX and will not be further mentioned here.


B. PHOSPHORUS

1. **Occurrence.**—The amount of P in plants ranges from 0.2 to 0.8 per cent of the total dry substance. It is generally present in somewhat greater quantities than

sulphur and magnesium and in smaller quantities than calcium.) A considerable amount of the P in plants is soluble in water. In the case of alfalfa (Ames and Boltz, 1912), 75 per cent; in the case of immature cabbage (Peterson and Peterson, 1926), 61 per cent; and in the turnip, 80 per cent (Hartwell, 1917) of the total P present is soluble in water. The P in plants occurs in the greater amounts in the seeds and fruits.) In the mature corn plant, 29 per cent of the total P is in the leaves, 11 per cent in the stem, 56 per cent in the grain and cobs, and 4 per cent in the roots (Miller and Latshaw, 1924). This is in accordance with the observation of MacGillivray (1926) that one-half of the total P in the tomato plant is located in the fruit. The amount of P found in plant tissue will depend upon the amount present in the soil, and Jordan (1913) has shown that up to a certain point the production of plant substance increased with the increased P supply but that beyond this the P was not utilized in an increased plant growth. Hartwell (1917) found that young turnips which had been deprived of P and later placed in a nutrient solution well supplied with it showed crystals of ammonium-Mg-phosphate within 24 hr. after the addition of the Mg mixture. An examination for the relative abundance of the P showed it to be most abundant in the bundles and surrounding tissues near where the taproot merges into the thickened root. Next in amount is inside the cambium in the more active xylem elements and next outside the cambium in the cortex, while only traces are in the pith and leaf petioles. MacGillivray (1927) found that the percentage of P in tomato plants receiving an ample supply of P showed a steady increase in amount from the bottom to the top regions of the stem. Plants, however, grown in nutrient solutions lacking P did not show such an increase in P content but had approximately the same percentage P content in all regions of the stem from the bottom to the regions near the tip where it was higher. This indicates that high percentages of P are associated with regions of rapid growth. Phosphorus is apparently redistributed in plants to a greater extent than most of the other elements, and this property of redistribution may be one reason for plants having a smaller total amount of P than N, K, or other elements.

2. Form.—Plants absorb and utilize P for the most part in the form of phosphates, although they can to a limited extent utilize some organic phosphorus, especially nucleic acid (Schreiner, 1925). Certain species of plants possess marked differences in their ability to acquire P from different sources (Baguley, 1912; Jordan, 1913; Truog, 1916; and Bauer, 1923). Cabbage, rape, sweet clover, alfalfa, and buckwheat were found to utilize to good advantage the P of phosphate rock, while barley, millet, corn, and oats were relatively less efficient in this regard.

Truog (1916) has proposed that according to the laws of mass action and chemical equilibrium, the reaction making the P of phosphate rock available to the plant may be represented as follows:



According to this theory, if the soluble phosphate is removed, but only a portion of the soluble calcium bicarbonate, an equilibrium will finally be established in which little or no P will be brought in solution. Truog thus considers that plants containing a relatively high amount of calcium oxide have a relatively high feeding power and plants of a relatively low calcium oxide content have a relatively low feeding power for the P of phosphate rock (see also Wrangell, 1922).

Hartwell and Damon (1927) found under conditions of an insufficient amount of P accompanied by liberal amounts of N and K that over long periods of time beets, cabbage, rape, and rutabagas are high P-response crops. In contrast to this, carrots, millet, tomatoes, and spring wheat are low P-response crops while sorghums, soybeans, and oats occupy an intermediate position in this regard.

3. Physiological Rôle.—Phosphorus is above all necessary for the formation of lecithin, the nucleo proteins, and nucleic acid, which are present in practically every living plant cell (Loew, 1891, 1903). Reed (1907) found that when P is withheld from plants the formation of lecithin does not go on and that as a consequence there is an accumulation of fat in the cells. He could find no evidence that the lack of P interfered with the process of starch formation, but the transformation of starch into water-soluble carbohydrates was seriously impaired. Hartwell (1917) noted that simultaneously with the increase in the absorption of P by the turnip root, which previously had been deprived of it, the leucoplasts containing the starch grains shrank in size as the grains were corroded and dissolved until finally all the starch had disappeared from the root tissue only to reappear when P was again withdrawn from the nutrient solution.

Phosphorus is abundant in embryonic cells, and in the tomato fruit the tissues contain the highest percentage of P in the embryonic stage (MacGillivray, 1926). He noted also (1927) that the plants growing in sand cultures in the absence of P usually have a higher percentage of N than those having an ample supply of P. The amount of coagulable protein, however, is decreased so that the increase in N is confined to the water-soluble form of N, excluding nitrates. The quantity of reducing sugar and the total quantity of sugar increased greatly in the plants grown in the absence of P.

Lyon (1923, 1927) reported that phosphates exert an accelerating effect upon potato oxidase, so that CO_2 is produced by an oxidation of some component in a solution of glucose. Phosphate also catalyzes the slow oxidation of pyrogallol and of tannic acid by atmospheric oxygen. It also increases the rate of production of CO_2 by the anaerobic phase of respiration through its action as a catalyst toward oxidases. These accelerated actions are equally pronounced when enzymes are contained within the cells of *Elodea* or wheat seedlings. On account of these observations, Lyon considers that phosphate plays an important rôle in respiration.

The application of P promotes root formation, especially lateral and fibrous roots (Russell, 1915; Noll, 1923). This rapid growth of roots causes them to grow deeper into the soil and more thoroughly to permeate it. This behavior is beneficial if drought conditions should prevail, and Russell (1915) states that some suggest that this explains the marked effect of phosphate on wheat in the dry regions of Australia, althou

phosphorus has never given very marked returns in semiarid regions of North America. Dressings of phosphates are especially used in certain regions for root crops like turnips, mangolds, and rutabagas. In the absence of P these roots do not swell but remain permanently dwarfed. The general impression that the development of roots is increased by the application of P is probably due to the marked returns obtained from its use as a fertilizer for these crops. There seems to be little or no experimental evidence to show that the proportion of roots to tops of ordinary field crops is increased by the application of phosphorus.

It has long been observed that phosphate fertilizers induce earlier ripening of the grain crops growing on soil low in phosphorus. The same effect has also been noticed for cabbage and cotton. The effects seem to vary with the different types of P, the more soluble ones hastening maturity to a greater degree. Increasing the rates of application, however, above the needs of the crop as indicated by yields has not been accompanied by further increases in earliness (Noll, 1923). Phosphorus, however, is not the only element that promotes earliness, since moderate applications of N and K and sometimes Ca when they are present in insufficient amounts have similar effects on maturity to those of P.

C. CALCIUM

Calcium is essential to the growth and development of all green plants with the exception of some of the lower algae. Non-chlorophyllous flowering plants must also be supplied with this element, although such plants as a whole contain less Ca than green plants. Calcium, however, is not necessary for the development of the fungi.

1. Occurrence.—A considerable portion of the Ca found in plants is in forms that are soluble in water. In cabbage that is ready for storage, 60 per cent of the Ca present is soluble in cold water (Peterson and Peterson, 1926), but after the plants have been in storage for six weeks, the soluble Ca amounts to only 42 per cent of the total amount present. Ames and Boltz found that 40 per cent of the Ca in alfalfa can be extracted with water. The leaves contain the greatest amount of Ca, while the seed or grain contains the lowest amount. In the case of the corn plant (Latshaw and Miller, 1924), 58 per cent of the Ca was found in the leaves, 18 per cent in the stems, 20 per cent in the roots, and only 4 per cent of it in the grain and cob.

The amount of Ca in the plant varies greatly with the species and with environmental conditions. Thus, for example, the percentage of Ca based on dry weight has been found to vary from 3 to 8 per cent in the vines of the cucurbits, to be 2.7 per cent in mature tobacco, and to amount to only 0.4 per cent in the case of timothy hay and wheat straw. As a rule, the legumes, lettuce, cabbage, and tobacco have a high percentage of Ca on a dry basis, while the members of the grass family have a relatively small amount. In the case of cucurbit vines, the amount of Ca increases from the early to the late stage of development, while the K, P, and N percentage decreases (Wilkins, 1917).

2. Function.—Numerous physiological rôles have been ascribed to Ca, although some of these are little understood. The rôles may be

classified under three main headings: (a) influence on the translocation of carbohydrates, (b) component part of plant structures and compounds and influence on the physiological availability of other ions, and (c) an antidoting agent.

a. *Influence on the Translocation of Carbohydrates.*—It was observed by Boehm (1875), who first studied the functions of Ca, that an abnormal accumulation of starch occurred in *Phaseolus vulgaris* grown in water cultures lacking that element—an observation which has since been verified for numerous plants by many investigators. The movement of starch from any tissue in a plant will depend primarily upon the diastase activity or the power of digestion and the depletion of the sugar in the surrounding tissues. It has been found (Groom, 1896) that potassium oxalate retards the action of diastase, and it has been considered that with a sufficient supply of Ca, calcium oxalate is formed instead of the potassium compound and that this salt is not detrimental to diastatic action. Hartwell (1916) suggests that an accumulation of starch may accompany any general disturbance of the metabolism of the plant, so in the absence of Ca the accumulation of starch may be only an indirect result. It has also been observed (Grafe and Portheim, 1906) that the addition of levulose, dextrose, and saccharose to Ca free solutions enables bean plants to live in them a longer period than where no sugar is added. The cause for the growth of plants not being inhibited at once by the absence of Ca is attributed to the fact that considerable carbohydrate is present in the form of sugar and that this is sufficient for its immediate needs. In some cases, a deficiency of either Mg or Ca causes an increased growth, but under such conditions the weight of the grain is less than where a sufficient supply of Ca is available, so that the total dry weight of the plant is less. This observation is held to indicate that a deficiency in Ca causes a disturbance in the translocation of carbohydrates and proteins and in their storage during seed formation rather than a hindrance to their synthesis.

b. *As a Component of Plant Structures and Compounds and Influence on the Physiological Availability of Other Ions.*—It has long been known that oxalic acid is one of the most abundant and the strongest of the acids in the plant and is supposed to be a by-product of carbohydrate and protein metabolism. Schimper (1888, 1890) suggested that one of the principal functions of Ca is to precipitate oxalic acid and soluble oxalates in the form of calcium oxalate, thus preventing the injurious effects which they might exert upon the plant. Calcium, for this purpose, however, is apparently not necessary in certain cases, for neither oxalic acid nor oxalates have been observed in some plants. The theory of Schimper was further weakened by the work of Bruch (1902), who showed that the grain plants tolerate relatively large amounts of oxalates, since wheat plants growing in nutrient solutions containing 18 to 278 ppm. reached the

blooming stage. He further found that calcium oxalate could replace other calcium salts as a source of calcium in nutrient solutions, while Ames and Boltz (1912) found in the alfalfa plant that one-third of the calcium present was in an insoluble form other than oxalates, which indicates that Ca is essential for the formation of some of the organic compounds. Parker and Truog (1916) have more recently revived the theory that Ca plays an important rôle in the neutralization of acids within the plant. They observed that there is a close relationship between the Ca and N content in plants. In regard to the ratio of Ca to N, plants can be divided into two groups. The first group has a calcium-nitrogen ratio of about 0.3 and contains almost entirely members of the grass family which have low Ca requirement and are more or less tolerant to soil acidity. The second group has an average calcium nitrogen ratio of about 0.55 and includes the legumes and those plants which require a large amount of Ca and are sensitive to soil acidity. These authors consider then that the larger the amount of N the more protein is formed and the more oxalic, acetic, succinic, and formic acids are produced in protein metabolism. Larger amounts of Ca are thus necessary to neutralize these acids than if a smaller amount of protein were manufactured. They assume that if Ca is lacking, the above acids accumulate in such quantity that they become injurious to the cells and inhibit further protein production. Hobart (1924), however, considers that the neutralization of these acids can be performed by other bases and that the necessity of Ca can be explained by assuming that it acts as a stimulant to the protoplasm.

It is considered by some that Ca enters into the composition of proteins and Loew (1903) believed that Ca-protein compounds enter into the organized substance of the nucleus and plastids. He considered that these Ca compounds have a well-defined power of imbibition which if disturbed by replacement substances like K-protein compounds leads to fatal results.

It was stated in Chap. I that Ca pectate is one of the compounds of the middle lamella. It was noted by Reed (1907) that when Ca was withheld from the plant, new cell walls were imperfectly formed if at all, although the nuclei of the cell divided mitotically. The most important observations on the function of calcium in the cell wall have been made by True and his workers (1918, 1921, 1922). They found that plants growing in various concentrations of a single salt of K or Na were not able to carry on a sustained absorption but in the end gave up more ions to the medium than they were at any time able to take up. In solutions of Ca and Mg salts, there was a concentration below which the roots were not able to absorb, and ions leached out into the medium, although in solutions above this concentration absorption took place in a greater or lesser degree. In mixtures containing Ca and other nutrient salts, the

total quantity of ions absorbed by the plants exceeded by far the total number of Ca ions present. This indicates that in a solution of mixed salts, Ca in some way produces conditions that bring about the absorption of ions which without the presence of calcium would not be absorbed or would cause the leaching of ions from the plant. This behavior of the diffusion relations can, in part at least, be explained by the following microchemical observations:

It was found that when seedlings were grown in K solutions, ions readily entered the cells of the root but that within 24 hr. Ca ions began to diffuse out of the Ca pectate middle lamella of the cells. Potassium pectate was formed in the cell walls instead of Ca pectate and soon dissolved out, since it is readily soluble in water. At this stage organic matter and salts began to leach rapidly from the cell vacuole. Approximately two-thirds of this material was organic and non-electrolytes and consisted principally of sugars and amino acids. This action of the K salt upon the cell wall not only changed its character but also greatly changed the permeability of the protoplasmic membrane next to it. These changes are seen also by the inward passage of materials. Corn seedlings after 5 days in a KNO_3 solution were placed in a one per cent solution of CuSO_4 and within 1 hr. the Cu ions had penetrated all the root tissue. Similar seedlings after 5 days in a $\text{Ca}(\text{NO}_3)_2$ solution showed the penetration of Cu ions only after 24 hr. in a similar Cu solution. In solutions of Mg salts, the Ca pectate in the middle lamella is replaced by Mg, which is also an insoluble compound but more permeable than the Ca pectate. The fatal results from growing plants in Mg solutions do not occur until the Ca of the middle lamellae has been wholly replaced by Mg, after which apparently sufficient Mg ions are free to penetrate the protoplasm and injure it. True considered that the integrity of the Ca pectate forming the middle lamella is maintained when a sufficient quantity of Ca ions are present in the external medium and with it the normal retention of the cell contents. When according to the laws of mass action this quantity of Ca ion falls below the equilibrium concentration, other cations replace the Ca in the middle lamella. No cation apparently can replace Ca in this regard, although Mg comes more nearly to doing it than any other. Sorokin and Sommer (1929) found that plants of *Pisum sativum* grown in culture solutions without Ca usually die within two or three weeks. The death of the plants is associated with the degeneration which takes place in the protoplasts of the meristematic cells of the root tips. The first visible effect of the absence of calcium is a decrease in the amount of cytoplasm and of the appearance of large vacuoles in the meristematic cells which thus resemble old cells. With the gradual depletion of the amount of calcium, the cells of the meristematic regions of the roots show transitional stages from interrupted and irregular mitoses to almost typical amitoses. Sorokin and Sommer

consider that the absence of Ca does not have a direct effect on the disintegrating tissues due to the separation of the cells because of the absence of calcium pectate. According to these investigators, the effect of the absence of Ca is on the meristematic cells, either because it is a necessary chemical constituent of the protoplast or because its absence so affects the physical condition of the colloidal system that normal action of the protoplast is not possible.

c. As an Antidoting Agent.—Calcium reduces the toxic effects of single-salt solutions of Na, K, and Mg, as was discussed under Antagonism and Balanced Solutions. Since Ca or Mg salts in single solutions are toxic or injurious to plants and since either will neutralize, in part or in whole, the deleterious effects of the excess of the other, Loew (1903) proposed the hypothesis that one of the principal functions of Ca in plant metabolism is to neutralize the toxic action of Mg and that a certain calcium-magnesium ratio varying with the type of plant is necessary for the proper growth and development of the plant. An enormous amount of experimental work was carried on by Loew and his pupils and by many others in an attempt to prove this hypothesis and to find the proper proportion of Ca and Mg for various crop plants. Lipman (1916), however, after a thorough résumé of the literature on the subject, concluded that the experimental work presents no evidence in support of the hypothesis that a specific lime-magnesium ratio exists for any plant or group of plants. He considered that there is no more reason to assume that there should be a proper ratio in the soil between Ca and Mg than that there should be a proper ratio between Ca and K or between Ca and any other essential element.

The conclusions of Lipman are further upheld by the work of Wyatt (1916) with wheat, soybeans, cowpeas, and alfalfa. The crop yields of these plants and the ratio of Ca to Mg in them bear no direct relations to the ratio of the carbonates applied. Different ratios of Ca to Mg within rather wide limits produced no marked differences in yield, although increasing the size of the applications increased the Ca and Mg content of the plants. Prianischnikow (1923) found that weak solutions of the salts of Mg, Ca, Ba, and Sr in concentrations of 0.0005*N* to 0.005*N* increase the resistance of cells to free acid, and of the cations used Ca showed the strongest antagonism.

3. General Responses of Plants to Calcium.—When Ca is withheld from water cultures, the size of the roots of the plants growing therein is greatly reduced. Reed and Haas (1923) showed that the roots of citrus seedlings grown in the absence of Ca were injured, as indicated by the gelatinization of the superficial layers and the ultimate death of the roots. If injury has not progressed too far, the addition of Ca induces the production of lateral rootlets, the lowest of which mark the boundary between the dead and living portions of the root. In a deficiency of

Ca in the soil or water culture, the lower leaves in the case of the cereals show an inrolling of the margins which Loew (1903) and Tottingham (1914) ascribe to a high magnesium-calcium ratio. Dickson (1918) observed this behavior and noticed that later brown spots appeared on these inrolled leaves, which finally became dry and twisted around the stem. Mann (1924) found that young apple trees in sand cultures deficient in Ca produced leaves that were larger than those borne by trees supplied with a complete cultural solution and that in the case of the gooseberry a deficiency of Ca resulted in leaf water content higher than that shown in the complete nutrient. Resistance to evaporation in bright light was greatest in the case of the plants grown in a deficiency of calcium. In this relation it is well to mention the work of Larson (1928), who found that the concentration of soluble Ca favorable for normal plant growth is apparently about 32 to 64 ppm., while 16 to 32 ppm. seem to be the minimum concentration. He considered that 32 ppm. is the most economical concentration, since above that point, although the yield is increased, the increases become successively smaller.

D. MAGNESIUM

Magnesium is usually present in the plant in somewhat smaller amounts than calcium. It is relatively more abundant in seeds and leaves than in the other parts of the plant. In the case of the corn plant, 34 per cent of the Mg is in the grain, 32 per cent in the leaves, 21 per cent in the stems, 7 per cent in the roots, and 6 per cent in the cobs. Most soils are not deficient in magnesium. Wheeler and Hartwell (1904), however, showed that the application of Mg salts to certain Rhode Island soils was beneficial to various plants and that a single application of Mg lime would cover the deficiency of Mg for many years to come.

Magnesium, as first shown by Willstätter (1908), is one of the constituents of chlorophyll, and when this element is lacking a disturbance in the formation of chlorophyll is soon noticed. (Dickson (1918) found that oat plants grown in a nutrient solution which had only approximately one-tenth of the requisite Mg supply developed numerous broad leaves which at first were very bright green but which when older showed marked stripings between the veins because of the disappearance of the chlorophyll. Sand drown, a chlorosis of tobacco involving both the green and yellow pigments of the chloroplasts, has been shown (Garner and McMurtrey, 1923) to be due to a deficiency of Mg in the soil. This trouble can be remedied by the application of Mg salts in various forms to the soil as fertilizers. Reed and Haas (1924) also observed that chlorosis of young citrus and walnut trees resulted from a low application of magnesium, while Mameli (1918) found that within certain limits the develop-

ment of chlorophyll is proportional to the magnesium supplied in the solution. Jones (1929) concluded that chlorosis of corn in certain regions of Massachusetts was due to the lack of Mg, since the normally green plants contained a larger amount of this element than did the chlorotic ones. Lutman and Walbridge (1929) believed that lack of Mg may lead to early chlorosis of the older leaves of the potato plant.

Magnesium appears to function in many cases as a carrier of phosphorus. The salts of Mg undergo dissociation very easily and thus readily give up the anions which they carry. (Phosphorus enters into the formation of nucleoproteins and lecithins, two compounds which enter into the composition of protoplasm. If Mg functions as a carrier of P, then the content of Mg should be relatively high in those regions where these compounds are being formed. This apparently is the case, since Mg is more abundant and frequently increases in amount in the tissues—as the tips of stem and roots—where rapid development is taking place.

Magnesium is more abundant in oily seeds like those of flax and cotton than it is in starch containing seeds like the cereals. The average proportion of Mg in starchy seeds to that in oily seeds is about 2:5 (Loew, 1903). Since the formation of oil is preceded or accompanied by the formation of lecithin, it would appear that Mg in the case of oil formation serves as a carrier of P, and this supposition is further supported by the fact that when both lecithins and nucleoproteins are present in the cell, Mg occurs in greater amounts than if only one of these compounds is present. In regard to oil formation, Reed (1907) observed that the filaments of *Vaucheria* growing in Mg-free solutions were devoid of oil globules, although globules were present in those plants growing in the control solutions. He considered that there is an intimate relationship between the presence of Mg and the formation of vegetable oils. Oat plants growing in a nutrient solution deficient in Mg produced inferior grain, and the ratio of grain to straw was decreased (Dickson, 1918). Apparently only a small amount of Mg is needed to satisfy the needs of the plant and it seemingly can be used over and over again as a carrier. It has been observed that beans can reach their full vegetative growth with no supply of Mg other than that stored in the seed.

When Mg in the form of $MgSO_4$ is present in relatively large amounts in nutrient solutions, the leaves of cereals growing therein show characteristic Mg injury. The tips first wilt, then dry up and drop off. This injury occurs in a much greater degree under conditions conducive to high transpiration than for low. The addition of Ca salts is beneficial in overcoming this injury and the results have been considered as proof that one of the functions of Ca is to overcome the toxic action of Mg, but Gericke (1922) has shown that this injury can also be prevented by having a proper proportion of P present in the solution.

E. POTASSIUM

Potassium is absolutely essential for plants and cannot be entirely replaced by any other element. Sodium may be substituted for K to a certain degree, but by no means entirely. The plant can apparently absorb from the soil and utilize in its metabolism any soluble inorganic compound of potassium. The form in which it is presented to the plant apparently makes little difference in some cases, while in other cases the differences observed may be attributed to the nature of the soil, environmental conditions, or the nature of the plant.

1. Occurrence.—The range of distribution of K in the plant has been studied by McCallum (1905), Weevers (1911), Dowding (1925), and Lukaszewicz (1926). All meristematic tissues are rich in this element, as indicated by strong positive microchemical tests obtained in the growing tips and cambium. Potassium appears especially abundant in the growing parts in those cells in the region of secondary root outgrowths and the formation of new leaves. McCallum (1905) noticed that the cell in the *Equisetum* spore which will give rise to the primary root hair is rich in K and that as the tip elongates the K keeps in contact with it. The same thing holds true in the development of the pollen tube. The K in the pollen grain migrates into the tube and keeps in contact with the growing tip. Potassium is in the mesophyll cells of the leaf, the cells of the medullary rays, the phloem, and to some extent in other parenchymatous tissue, but little or none is found in the older xylem portions of the stem. In the spruce when the bud elongates, there is a translocation of the K within the embryonic cone to the next year's meristem and to the embryonic leaves (Dowding, 1925). This author noted also that in the wheat grain the cells of the aleurone layer contain a large amount of K but that the endosperm has only a trace. After 15 days of germination the K disappears from the aleurone layer, having apparently leached out into the surrounding medium, since there is no evidence that it is transferred into the endosperm. All parts of the embryo contain K, but the greatest amounts are contained in the root and stem apices.

Chemical analysis of the corn plant at early maturity (Latshaw and Miller, 1921) shows that 45 per cent of the K in that plant is located in the leaves, 32 per cent in the stems, 14 per cent in the grain, approximately 5 per cent in the cob, and 4 per cent in the roots. Dickson (1918) found by analysis that K is localized first in the growing region of the young wheat seedling but that later it appeared in large quantities in the region of grain formation. Potassium is well distributed over the plant, and André and Demoussy (1927) consider that it is the predominant soluble salt in plants because of its mobility.

In the individual cells, K seems to be absent from the nucleus. Stocklasa (1911) could find none in the chloroplasts, and Dowding (1925) states that in the spruce leaves during the summer, K occurs as a network of granules between the chloroplasts. He observed that in the epidermal cells of the hyacinth and onion K occurs in the corners of mature guard cells where oil and starch can be found but that in the initial cells that have not yet divided there is no localization of this element. McCallum (1905) observed K in the cytoplasm, but Stocklasa could not positively recognize it there in many cases but considered that the greater portion of it is in the vacuole of the cell.

The K present in the plant is for the most part in forms readily soluble in water (Janssen and Bartholomew, 1929). Kostytschew and Eliasberg (1920) report that when plant tissue is extracted with cold water, the tissue yields K-free ash and lead acetate, and tannin precipitates were also found to contain no potassium. Weevers

(1911) by water extraction removed 99 per cent of the total K from the pollen tubes of *Pinus sylvestris* and leaves of the horse-chestnut. Since the extracts made before and after ashing yielded the same amount of K, the indications are that it is present in the plant in the ionic form. At least it would appear that if it is combined at all with the protoplasm, it is easily dissociated from it. It apparently then is present in the cells chiefly in the form of inorganic compounds and as salts of the organic acids.

2. Physiological Rôle.—The rôle of K in the plant is not definitely known. The only criterion by which its function can be judged is the general behavior of the plants which are deprived of a normal supply.

a. Use in Food Manufacture.—It was first pointed out by Nobbe and his worker (1870) that carbohydrates are formed normally only when the K supply is sufficient. The production of sugar by sugar beets, mangolds, potatoes, and other crops that form a large amount of carbohydrate is reduced by a deficiency in K before any diminution in the vegetable growth of leaves and stems can be observed. In an experiment with mangolds, Russell (1915) reports that when K was deficient in the soil 7,255 lb. of leaves produced 14,684 lb. of root, while with plants growing on the same soil with a sufficient supply of K with very little more leaf weight (8,508 lb.) produced 40,128 lb. of root, or nearly three times as much as the plants growing under a deficiency of potassium. In all the green plants studied by Reed (1907), K was apparently essential for starch formation. The lack of this element gives rise so far as can be observed to no pathological condition of the chloroplasts, and under conditions of K deficiency they remained normal for two months and even increased in number. The loss of the power of synthesis by green plants in the absence of K has also been observed by Stocklasa (1908, 1912) and by Weiszmann (1923), but Smith and Butler (1921) could not sustain these general observations in their work with blue-stem wheat growing in a solution deficient in potassium.

As has previously been mentioned, K is present in comparatively large amounts in the growing tips. It was first shown by Schimper (1890) that a K supply is necessary for the normal development of the growing apices (see also Janssen and Bartholomew, 1929). Dickson (1918) grew oat plants in a nutrient solution containing only one-tenth of the optimum K supply. Plants grown after this manner produced only about one-half the amount of total dry matter of stem and leaves as did those growing in a solution with the proper amount of potassium. The total dry weight of the plants including grain, however, was two-thirds that of the normal plants. The decrease in grain thus was not proportional to the decrease in the dry matter of the vegetative parts of the plant. This result is evidently due to a lack of K for meristematic development, and as a consequence the vegetative growth of the plant was checked.

Potassium evidently plays a rôle in the formation of proteins and oils in plants. Stocklasa (1916) considers that in the presence of sunlight and

with a sufficient supply of carbohydrate and other material, protein can be formed in either the presence or the absence of potassium. In the dark, however, the formation of protein occurs only in the presence of K, provided the necessary materials are at hand. Soybean plants grown with a deficient K supply produce small and immature seeds which have an oil content lower than that of the normal seeds (Schuster 1927). It is assumed that the carbohydrates have not under these conditions become fully transformed into oil.

b. *As a Catalyst.*—Most authors are agreed that K plays the rôle of a catalyst or condensing agent. Loew (1903) believed that the superiority of K over Na in plant nutrition is due to its superiority as a condensing agent. He cites numerous cases in organic chemistry where condensation processes take place only in the presence of K or much more rapidly than with Na or related elements. Stocklase (1908, 1920) considered that K acts as a catalyst in the formation of organic compounds. He is of the opinion that K is concerned through its radioactivity in photosynthesis and that there is a relationship between the β and γ rays which K emanates and this process. Further evidence that K acts as a condensing agent is furnished by the work of Reed (1907). In *Spirogyra*, which can be stimulated to divide, mitotic nuclear division did not proceed in the absence of a K supply. The cells elongated but the nucleus did not divide. The assumption for this behavior is that nucleoprotein cannot be synthesized in the absence of K even if the necessary constituents are present. When such elongated cells are placed in a solution of K, normal mitotic division proceeded in some cases, but in a majority of them it did not. This behavior may be due to an insufficient supply of nucleoprotein, but K may also play some important function in the initial steps of mitotic division and being absent at that time could not function at a later stage.

3. General Response of Plants to Potassium.—Plants differ to a considerable degree in their response to potassium. Hartwell (1927) found that the yield on an area with insufficient K in comparison with the yield with optimum fertilizer ranged from 16 per cent for onions to 88 per cent for oats. He grouped the plants in reference to their response to the application of K as follows: low K-response crops, oats, rye, wheat, millet, and carrots; medium K-response crops, barley, rutabagas, parsnips, potatoes, and cabbage; high K-response crops, tomatoes, mangels, buckwheat, corn, and onions.

Quality in fruit and grain has been attributed to an optimum K supply. There is some evidence that K causes stiffness of the straw in cereals. Brown (1927) found that in the apple low values for the hydrogen-ion concentration are associated with total ash and K content so that K and acidity are inversely correlated. A correlation seems also to exist in the apple between K and P and between carbohydrate and

K, but none exists between protein and this element. Schuster (1927) considered that the effect of the application of K on the quality of the crop will depend upon the amount of K in the soil and the property of the soil to correct the effect of the acid derived by the liberation of the applied potassium. He considers that the literature on K nutrition produces evidence which indicates that K aids in producing quality in potatoes, sugar crops, tobacco, soybeans, and wheat.

Lanham (1927) found that the application of K had no influence on the carrying quality of tomatoes grown in Texas. He considered that the carrying quality is mainly varietal and is influenced to some extent by the time of harvesting. Both the fruit and the plants from the fertilized plots contained more K than the checks, but the tomatoes containing the highest amount of K were not always those from the plots having the highest application of potassium. Mann (1924) noted that young apple trees in sand cultures deficient in K had small leaves subject to leaf scorch and that the gooseberry under similar conditions had leaves with lower water content and were less resistant to water loss than those growing in the controls.

F. SULPHUR

It has long been recognized that S is necessary for plant development, but the amount needed by the plant was until recently underestimated. Much S was lost by the ash-analysis method which until comparatively recent time was used in its determination. By more accurate methods of analysis it has been found that plants need from two to one hundred times as much S as had formerly been supposed. Hart and Peterson (1911) state that cereal crops remove from the soil about two-thirds as much S as P, the legumes as much S as P, and in the case of alfalfa a greater amount, while such crops as turnips and cabbage remove two to three times as much S as phosphorus. In the case of mustard, potato, onions, and chives, also, the S content of the plant greatly exceeds that of the P (Crocker, 1923).

1. Occurrence.—Sulphur occurs in plant tissues chiefly in the form of proteins, volatile compounds, and sulphates. In the proteins it exists in the form of cystine. Some of the various volatile forms of S are mustard oil, allyl sulphide, vinyl sulphide, and mercaptans. Those volatile compounds are most abundant in the mustard family, but some of them are to be found in the *Liliaceae* (onion and garlic), *Tropaeolaceae*, and other families. The mustard oils do not occur as such in the plant but are found in the form of glucosides, the best known of which are sinigrin found in black mustard and sinalbin found in white mustard. Sulphur occurs in the inorganic form in plants principally as sulphates, and as much as 65 per cent of the S found in certain plants is in the form of soluble sulphates. Plants cannot utilize elemental S, but it apparently

must be oxidized to the form of sulphates before it is of any benefit to them. According to Reimer and Tartar (1919), all of the sulphates produce similar beneficial results when applied as fertilizers. It is also of interest to note that when S is applied as a fertilizer in the soil, a marked increase in the amount of sulphates in the plant is soon noted. In the case of rape, radishes, and clover which had been grown on a soil with only the normal amount of S present, the plants grew vigorously but showed little or no sulphates in their tissues. This indicates that a considerable portion at least of the S that is found in the plant in the form of sulphates is simply an excess supply of sulphur.

The following brief table adopted from Peterson (1914) shows the relative amount of the various types of S compounds in certain plants:

DISTRIBUTION OF THE SEVERAL FORMS OF SULPHUR IN PERCENTAGE OF THE TOTAL SULPHUR

Material	Soluble sulphate A	Volatile sulphur B	Soluble sulphur C	Insoluble sulphur D	Sum of fractions B, C, D	Loss on drying	Total unoxidized sulphur (C - A) + D
Rutabagas, average 4 samples.....	37	12	73	11	96	19	47
Cabbage.....	24	9	74	15	98	..	65
Sugar beets.....	34	..	62	38	100	11	66
Alfalfa hay.....	50	..	70	30	100	4	50
Rape, dried ¹ .	64	..	85	8	93	..	29

¹ Potassium, nitrogen and phosphorus, and sodium sulfate added to soil.

Sulphur is fairly evenly distributed throughout the plant. In a mature corn plant, 40 per cent of the total amount was in the leaves, 23 per cent in the stem, 26 per cent in the grain, and 11 per cent in the roots. Marsh (1922) observed that the amount of S in the tomato plant increased from the tip toward the base, the oldest tissues having the highest sulphur content. In the case of the apple, the highest percentages of sulphur are found in the leaves and then in descending order in spurs, young bark, and old bark. Sulphur thus resembles Ca in that it is not mobilized to any great extent. The percentage of S is at a minimum in the apple spur at the time of fruit-bud differentiation.

2. Physiological Rôle.—Sulphur functions as building material for the formation of protein and other constituents of the plant. The proteins of plants contain from 0.003 to 7.2 per cent, and it has been noted that plants with a high protein content or especially rich in organic S compounds respond most markedly to the application of S as a fertilizer. In Washington (Olson and St. John, 1921; Peterson, 1923) alfalfa grown on soils treated with sulphur was found to contain a higher percentage

of protein than alfalfa on soils not so treated. This indicates that the S under these conditions was used by the plant in the production of protein. This supposition is strengthened by the work of Tottingham (1918) on red clover which indicated that a deficiency of S restricted growth in that plant by limiting the synthesis of protein.

✓**3. Formative Effects.**—Aside from functioning as building material, S produces certain formative effects in plants. These are manifest especially in three ways: (1) An increased root or absorbing system. The effect of S fertilizer on the root system of plants has been noted by Hart and Tottingham (1915), Pitz (1916), Miller (1919), Reimer and Tartar (1919), and others. It was found in the case of alfalfa that the root systems of plants which have been fertilized with various S fertilizers were from two to three times as large as those of the unfertilized plants. This holds true also for clover and rape. It was suggested by Crocker (1923) that the increased root development which has been so frequently observed from the application of superphosphates and attributed to P might be due, in part at least, to the sulphates therein rather than entirely to the phosphates. (2) The appearance of chlorophyll. It has been observed that plants grown on soils deficient in S have a pale green color and that this can be remedied by the application of S as fertilizer. The plants thus treated show a dark, vigorous, green color (Eaton, 1922; Demolon, 1912). Just what rôle S plays in this regard, however, is not known. Nicolas (1921) observed that very little if any starch was found in any part of the plants of bean and pea when they were grown without sulphur. This element is apparently necessary for the formation of chlorophyll, but it must act in an indirect manner, since it does not enter into the composition of the pigment. (3) Effect on the nodules of the legumes. Duley (1916) was the first to note an increase in the number of nodules on the roots of sweet clover by the application of flowers of sulphur as a fertilizer. Pitz (1916) found that calcium sulphate when added to soil apparently had no marked effect on the total number of bacteria that grow on agar plates and did not increase to any extent ammonification or nitrification. The application of S did, however, increase the growth of the legume bacteria and the number of nodules on red clover. Powers (1923) noticed in the case of clover that the plants fertilized with sulphates had a higher nitrogen content than the controls. Since the number of nodules on the roots was increased, and since rape which assimilated a large amount of S did not show any relationship between the content of N and S, he attributed this increased N content of clover to the stimulating effect of the sulphates on the action of the legume bacteria.

4. As a Fertilizer.—Sulphur is present in the soil in the form of either sulphates or organic matter. Most of the sulphates are quite soluble and are not readily adsorbed, so they are leached out rapidly and only

small amounts are found in the soil. In a large number of soils analyzed by Woodard (1922), the S content was less than the P content. He estimated that the highest S content found in these soils was sufficient for 39 years of alfalfa, 355 years of wheat, and 232 years of corn, while the lowest S was sufficient for only 5 years of alfalfa, 46 years of wheat, and 30 years of corn. Good to excellent crops of alfalfa remove annually from 37 to 90 lb. of S per acre from the soil, and, in general, hay from fields with the heaviest crops have the highest percentage of sulphur (Hall, 1922). The response of plants to the application of S as a fertilizer will depend upon the type of plant and upon the soil. In many regions the S supply is not a limiting factor in production, as shown by Bruce (1925) for Kansas soils and by Stewart (1920) for Illinois soils.

Hart and Tottingham (1915) working in Wisconsin found that plants most affected by the application of sulphates to the soil were members of the legume and mustard families. They observed, however, a noticeable stimulation to seed production in barley and oats but no increase in the quantity of straw. In the case of clover, they obtained an increase in dry matter due to CaSO_4 of about 23 per cent. With rape, the greatest increase occurred where the CaSO_4 was applied with a complete fertilizer, giving an increase of 17 per cent over the complete fertilizer. In general, the CaSO_4 was more effective than the more soluble sodium sulphate.


Shedd (1914, 1917) reported that wheat, corn, oats, timothy, alfalfa, rape, beets, potatoes, turnips, radishes, beans, tobacco, and grapes were benefited by the application of S to certain Kentucky soils. He found that the S content of 32 varieties of tobacco averaged 0.458 per cent of the total dry matter as compared to a P content of 0.302 per cent. Olson and St. John (1921) in Washington obtained increases of twofold or more in alfalfa yields by treating the soil with gypsum, acid phosphate, and sulphuric acid, while Powers (1923) from Oregon showed that marked results could be obtained by the application of S for alfalfa, red clover, and alsike, but only a moderate response in yield was had with wheat and potatoes and little or no increase for corn, kale, or sunflowers.

G. IRON

1. Occurrence.—Iron is necessary for the growth and development of green plants and cannot be replaced by any other element. Although Fe is universally distributed in plants, its detection microchemically is difficult, since it occurs in very small quantities. Molisch (1892) found that in plants, combined Fe occurs in the greatest amount and that very little of the Fe is in a form that is readily soluble in water. He observed combined Fe in the protoplasm, the vacuole, and the globoids of the aleurone bodies. Jones (1920) states that, as a whole, plant tissues give the Fe reaction more rapidly and intensely than animal tissues. The Fe stain occurred in the chloroplasts, nuclei, and in large masses scattered

throughout the cytoplasm. The leaves of some plants did not show the Fe stain, while others did with a very definite reaction.

2. Physiological Rôle.—If plants are deprived of Fe, they do not normally produce chlorophyll, a fact which was first noted by Gris (1844). The new leaves and stems formed by plants deprived of Fe are pale or yellow, a condition that has been termed "chlorosis." It has been definitely proved, however, that Fe does not enter into the composition of chlorophyll (Willstätter and Stoll, 1913). The quantity needed by the plant at any time is very small. Gile (1916) estimated the available Fe in the nutrient solution in which he grew normal healthy rice plants to be always less than 1 part per 10,000,000 parts of solution. The use to which Fe is put in the plant is not known. Wolff (1913) and others considered that it acts in plants as a catalyzer, since such marked results are obtained with such small amounts, while Warburg (1925) has proposed the theory that iron is the oxygen-carrying component of the respiration ferment. Oddo and Pollacci (1915, 1920) grew plants of *Zea mays*, *Solanum nigrum*, *Datura stramonium*, *Euphorbia* sp., and *Aster sinensis* in a standard nutrient solution lacking Fe but to which was added the magnesium salt of pyrrole-carbonic acid which has the formula



in a concentration equivalent to 0.0232 g. Mg. in a liter of water. These plants, although deprived of Fe, when supplied with this organic compound formed chlorophyll. Since Fe under ordinary conditions is indispensable for green plants, these authors suggested that the formation of chlorophyll in the presence of Fe is due to the catalytic action of this element in the formation of the pyrrole nucleus which in itself is the center of the chlorophyll complex. They believed that if this nucleus is already formed, the presence of Fe is not necessary for the greening of the plant. This observation is in line with the statements of Willstätter (1906) and Mameli (1918) that the function of Mg in the greening of the plastids is directly proportional to the presence of pyrrole. Deuber (1926), however, was unable to confirm the work of Pollacci and Oddo in this regard. He grew plants of corn, cowpea, soybean, and *Spirodela* in nutrient solutions containing a magnesium salt of pyrrole carbonic acid substituted for iron. In no case did this compound prevent chlorosis of the leaves of the plant. He found further that the pyrrole salt in concentrations of 0.001 to 0.250 g. per liter was toxic to the plants used and that when the salt was applied as a paint to the leaves of cowpeas it had the same injurious effects as in solution.

3. Form and Amount Necessary for Plant Growth.—This is a subject that formerly was considered of little import in the nutrition of plants.

All the directions of nutrient solutions stated that only a trace of Fe was necessary and that it mattered little in what form it was presented to the plant provided it was soluble in water. Quite recently, however, much work has been done on the question of Fe nutrition which shows that not only the quantity of Fe available but the form in which it is presented to the plant can exert a marked influence upon plant growth and development. These two factors in turn are dependent upon the composition of the medium or nutrient solution—its hydrogen-ion concentration, the nature of the general environment—and to some extent upon the kind of plant under consideration. There is at the present time no criterion by which to determine whether a plant is receiving sufficient Fe except by its general appearance of health and vigor. Gile (1916), however, remarks in this regard that while the color of the leaves will indicate a marked deficiency of Fe, a slight deficiency may materially diminish the yield without appreciably affecting the appearance of the plant.

Jones and Shive (1921) used ferric phosphate and ferrous sulphate as a source of Fe in Shive's nutrient solution (*R5C2*, 1.75 atmosphere) in which Marquis wheat was grown. The solution was renewed at intervals of about 4 days for a period of 90 days. The results obtained are shown in the following table:

Iron per liter of solution, milligrams	Series I FePO ₄ , dry weight, grams	Series II FeSO ₄ , dry weight, grams
0.01	4.55	10.95
0.10	5.75	14.65
0.25	8.20	15.95
0.75	12.05	27.40
1.00	14.90	18.75
1.50	16.25	19.15
2.00	20.50	23.50
3.00	18.00	20.90
5.00	16.80	18.45

Control no Fe..... 8.40

In series I the plants showed more or less chlorosis even when large amounts of Fe were supplied, a condition which could easily be remedied in a day or two by the introduction of ferrous sulphate. There was no chlorosis in series II except when small amounts of Fe were used. Ferrous sulphate, however, was apparently toxic in higher concentrations.

That plants may differ in regard to their utilization of iron was shown by Corson and Bakke (1917). They found a marked difference in the growth of wheat plants when the source of Fe was ferric phosphate and

ferrous sulphate, the former being the more efficient. Little or no difference, however, was observed in the behavior of Canada field peas to these two sources of iron. They considered that the Fe stored in the seed might be a determining factor, a fact which was also suggested by Tottingham and Beck (1916) in their observations on the response of wheat plants to the salts of Fe and manganese. Hartwell and Pember (1908) noted that ferrous sulphate was equally effective as a source of Fe for barley and rye seedlings growing under the same conditions.

Marsh and Shive (1925) studied the relation of the growth of soybean to the amount and form of Fe in several types of cultural solutions. The iron compounds used were ferric glycerophosphate, soluble ferric phosphate, ferric tartrate, and ferrous tartrate. Considering that the availability to the plant of Fe in cultural solutions is closely correlated with the solubility of the Fe compound in the solution, their data suggest that in a general way ferric glycerophosphate could be used to advantage in solutions in which the hydrogen-ion concentration is kept at a high level. Soluble ferric phosphate and ferrous sulphate are not very usable when the P_{H} values approach the neutral point. In solutions of this type they suggest that ferric tartrate should prove the most effective source of Fe for the plant. Marsh and Shive further found that if the Fe supply is adjusted from day to day, large healthy plants are produced regardless of the type of cultural solution or the iron compound used. The Fe in healthy plants was present in a smaller percentage, based on dry weight, than in the chlorotic plants or those suffering from Fe toxicity. The Fe in healthy plants although low in concentration seems to be uniformly distributed throughout the stem and leaves, while in the case of those suffering from toxicity of Fe it is high in concentration. The Fe content of chlorotic plants is low in the leaves but high in the stems. These authors suggest that in order to maintain the plant in healthy green condition, the supply of soluble Fe in the cultural solution must be kept at as low a concentration as possible without inducing chlorosis from lack of available iron. A concentration of soluble Fe slightly above this optimum may result in toxicity due to a too high content throughout the plant. Chlorosis, however, may occur due to the lodgment of Fe in the roots and stems, thus preventing the translocation of this element to the leaves in sufficient amount (Hoffer, 1920). Marsh and Shive consider that the general appearance of the plant must serve as an index of the Fe supply in each case, since the changing plant environment has pronounced influence upon the Fe requirement. A striking observation in this regard was noted by Gericke (1925) in the effects of two different light intensities on the growth of wheat in nutrient solutions devoid of iron. It appeared from the general behavior and appearance of the plants that the need for Fe is much greater per unit of growth of plants exposed to high light intensities than to low ones. The conditions, which in the

presence of Fe in the cultural medium are decidedly beneficial to growth, become relatively harmful in the absence of iron. This observation is an important one, for it not only indicates that there can be no fixed minimum amount of Fe for a unit yield of product, but it suggests that this may apply to other elements as well.

4. Relation to Hydrogen-ion Concentration.—Jones (1920) and Jones and Shive (1921 to 1923) replaced potassium nitrate with ammonium sulphate in Tottingham's solution and noted that the solution became more acid when plants were growing therein, changing from P_H 4.8 to 4.2 during a $3\frac{1}{2}$ -day period, while the regular Tottingham solution became less acid during that time. One milligram of Fe per liter in the form of ferric phosphate was not sufficient to supply the needs of plants in Tottingham's solution, but one-half milligram was ample when ammonium sulphate replaced the potassium nitrate. In Tottingham's solution 0.25 to 0.50 mg. of Fe in the form of ferrous sulphate was sufficient, but in the modified solution this amount was toxic to the plants. McCall and Haag (1921) observed that wheat plants growing in solutions having P_H values ranging from 4.02 to 7.0 suffered from a lack of available Fe or from a change in metabolism that resulted in the immobility of Fe within the plant. This observation is in line with that of Hoffer (1920), who considered that the rate of growth of young plants of corn and the degree of chlorosis may be determined by the relative ability of the plant to develop and maintain a sufficiently high H-ion concentration to keep the Fe compounds mobile as occurs in normal green plants.

The solubility of ferric citrate, $FePO_4$, $Fe_2(SO_4)_3$, and $FeSO_4$ in Tottingham's solution within a P_H concentration of 4.2 and 6.0 was investigated by Tottingham and Rankin (1923). Using the growth measurements of young wheat plants as an indicator, the results showed that ferric citrate was the most favorable form of Fe used. It remains soluble over a considerable range of P_H values of the nutrient solution, and when supplied at the rate of 10 mg. of Fe per liter of nutrient solution, although it is not completely dissolved, it provides abundant Fe for plant growth when the solution is renewed every four days. Reed and Haas (1921) found that the addition of certain organic compounds to an alkaline nutrient solution, in which ferric tartrate was the source of Fe, increased the amount of soluble iron in the solution. The Na and K salts of organic acids, *e.g.*, citrates and tartrates, effect marked solubility of Fe without appreciably altering the P_H of the solution. Starch and sugars added to the solution also dissolved appreciable amounts of iron. Deuber (1926) in using potassium ferrocyanide in concentrations equal to 0.033 and 0.066 ppm. of iron noted that the higher concentration produced a stoppage of growth in soybeans. Ferric ferrocyanide was a satisfactory source of Fe when the solution had a reaction of P_H 5.0 but at a less acid reaction growth of these plants, and chlorophyll development were restricted.

A direct correlation was found by Barnette (1921) and Barnette and Shive (1923) between the decrease in hydrogen-ion concentration of the cultural solution and the appearance of chlorosis in plants when ferric phosphate and ferric sulphate were used as sources of iron. They could partially control the hydrogen-ion concentration of the solution in contact with the roots of the growing plants by the use of large volume of solution accompanied by frequent renewals. Hopkins and Wann (1926, 1927) also observed that iron was unavailable to *Chlorella* in nutrient solutions at the higher P_H values. The addition of sufficient sodium citrate, however, kept the iron in solution even at alkaline reactions for an indefinite period. If too high an amount of sodium citrate is present, the ionization of the ferric citrate is decreased, so that although there may be a large total amount of iron present little or no growth will occur because of the low concentration of the ferric ion. The availability of Fe is

determined apparently in a large measure by the composition, concentration, and general reactions of the cultural solutions, as it is influenced by the action of the plants growing therein.

5. Absorption from the Soil.—Certain plants, especially rice and pineapple, on certain calcareous and manganese soils are affected with chlorosis and do not make a normal growth. This phenomenon has been encountered and studied most extensively on the calcareous soils of Porto Rico and the manganese soils of Hawaii. Gile (1911) applied a solution of ferrous sulphate to calcareous soils, but this showed no effect in reducing the chlorosis of the leaves of the pineapple. Crystals of the salt, however, applied in the soil in close proximity to the roots gave very evident results in reducing chlorosis. In another experiment (1916), rice plants were grown in acid, neutral, and alkaline solutions with 0.008 g. of Fe per liter in various forms. The plants grown in the acid solution contained the highest percentages of iron. Plants in the neutral solution contained more Fe than the alkaline solution when some forms of Fe were used and an equal amount when others were used. The percentage of nitrogen-, phosphorus-, calcium-, magnesium-, and carbon-free ash remain the same in all plants regardless of the reaction of the solution. From these and other similar experiments, Gile (1911, 1916), Gile and Carrero (1920), Mazé (1912), Sidorin (1914), and Willis and Carrero (1921) agree in considering that lime-induced chlorosis is due to a depression in the available iron. They are inclined to believe that the carbonate of lime in the soil reacts with the Fe forming ferric carbonate and thus depressing the availability of the Fe for the plants. In the manganese soils of Hawaii, Johnson (1924) has shown that it is present mainly in the dioxide form. He considers that the manganese dioxide either present as such or formed from manganese salts keeps the Fe that is present in the soil oxidized to the ferric form which is not readily available to the plants.

The lack of Fe available in the soil for pineapples has been overcome by spraying the plants with Fe solutions. The most effective and economical spray that has been used in Hawaii is an 8 per cent solution of ferrous sulphate, although other forms of Fe may be used. Plants that are already yellow are sprayed three or four times at intervals of a week and then as often thereafter as is necessary to keep them green and healthy. The cost of the Fe spray above mentioned amounts to about 60 cts. per acre per spraying (Johnson, 1916). It is worthy of note that leaves nicked or injured recover from chlorosis more quickly than do the intact ones after being sprayed.

6. Immobility within the Plant.—It has been observed that when plants which have their needed Fe supply are deprived of it, the new stem and leaves which develop are chlorotic or almost pure white so that there is a marked and abrupt contrast between the green leaves and the

colorless ones. This phenomenon was observed by Molisch (1902) in squash, sunflower, corn, pineapple, and rice. The leaves of plants growing in an Fe-free solution begin to die at the top in marked contrast to the behavior of plants which are deprived of or have a limited supply of N, K, or P, since in that case the lower leaves dry up while the uppermost ones are the last to perish. These observations point to the fact that Fe is immobile in plants and is not readily withdrawn from where it occurs to be translocated to newer organs. The immobility of Fe was further demonstrated by Gile and Carrero (1916). The young leaves of rice plants growing in a solution lacking Fe were brushed at the tips with a 0.2 to 0.4 per cent solution of ferrous sulphate. The tips of the leaves just emerging from the stalk were used, and after they grew out, the part which had been brushed was a normal green while the lower unbrushed part of the leaf was strongly chlorotic and remained so until treated with iron. Gile and Carrero found that spraying with Fe compounds completely restored the green color of the pineapple leaves but that the new leaves formed after the treatment were chlorotic.

H. SILICON

1. Occurrence.—Silicon is an element that has an almost universal occurrence in plants but the amount present varies greatly for different plants and for different parts of the same plant. Richardson (1920) considers that for plants of all types and for all parts of plants Si is the greatest variable of all the elements that compose them. It is especially abundant in the aerial parts of *Equisetum*, the *Gramineae*, and in the bark of trees. Silicon has been found to compose 71 per cent of the ash of *Equisetum telemantia* and 51, 67, and 46 per cent, respectively, of the straw of barley, wheat, and oats. On the other hand, the Si content of the stem and leaves of red clover and alfalfa equals only 2.7 and 9.5 per cent, respectively, of their ash content. The distribution of Si in the different parts of the plant is shown in the analysis of the corn plant at the dent stage (Latshaw and Miller, 1924). The percentage of Si present in the different parts was as follows:

Plant part	Per cent of silicon in dry matter	Plant part	Per cent of silicon in dry matter
Leaves.....	2.50	Grain.....	0.02
Stem.....	0.45	Cob.....	0.14

2. Physiological Rôle.—The large amounts of Si present in many plants early led to the belief that it might be an essential element in the nutrition of these plants. It has been shown, however, that those plants which normally contain such large amounts of Si can be grown to maturity in nutrient solutions that lack Si or which, at least, have only a trace present. Sachs (1887) and Knop (1861 to 1862) grew corn and Kreuzhage and Wolff (1884) grew oats in nutrient solutions lacking Si and the resulting plants contained only a fraction of the normal content

of this element. Jodin (1883) grew corn through four generations without the application of silicon. Gile and his workers (1915 to 1916) found that rice which normally contains about 10 per cent of Si in the dry matter contained only 0.2 per cent when grown in a silica-free nutrient solution. It appears doubtful whether any experiments have been carried out where Si has been entirely withheld from the plants. The amount of Si in the seed, accruing from the glass container or occurring as impurities in the water or chemicals used, may be sufficient to supply the physiological demands for this element, so that it is at present not possible to state if it is absolutely necessary to plant growth (see Mazé, 1914 to 1919; Sommer, 1926).

It was formerly believed that Si added stiffness to the straw and prevented the lodging of cereals, but it is now considered that the stiffness of straw is due to other factors. Pierre (1866) showed that those varieties which possessed the most Si were often the most liable to lodge and that for equal weights the leaves contained seven or eight times as much Si as the nodes. Pfeffer (1900) considered that the stiffness of straw is not due to Si but that it depends upon the development of the internodes under the influence of such factors as illumination and exposure.

Although plants can be grown to maturity in the absence of Si or at least when only a trace is present, certain benefits that we shall now discuss accrue to the plant by its presence. Palladin (1927) considers that Si plays an important rôle in protecting plants from the attacks of various parasites. He states that wheat and rye grown in nutrient solutions deficient in silicic acid often suffer very severely from rusts. He also considers that silicated cell walls are a protection against the attacks of plant lice and mentions an experiment with *Lithospermum arvense* grown in a nutrient solution lacking silicic acid which suffered much more than control plants grown in solutions in which an ample amount of silicon was present. Sommer (1926) reports that seeds of millet grown without silicon were badly infected by fungi and germinated very poorly with and without disinfection, while the seeds of plants grown with silicon were not infected by fungi and germinated well.

The effect of silica upon the phosphorus nutrition of plants has been extensively studied. Kreuzhage and Wolff (1884) in cultural-solution experiments with oats observed that the total growth of these plants was not much increased by the presence of soluble silicates but that the proportion of grain formed was constantly raised. This effect is very similar to that brought about by the addition of phosphoric acid to cultural solutions which are deficient in that element, so they concluded that the action of Si and phosphoric acid are in some way related. Hall and Morison (1906) reported the results obtained from plots at the Rothamsted station which had been treated with soluble silicates during a period of more than 40 years. One series of plots received sodium

nitrate with various combinations of fertilizers so as to provide plots receiving (1) nitrogen alone, (2) nitrogen and phosphoric acid, (3) nitrogen and potassium, and (4) a complete fertilizer. From 1864 to 1904, one-half of each of these plots was cross-dressed with sodium silicate. The effect of sodium silicate on the yield of barley for a period of 41 years is shown in the following table:

Plot	Fertilizer per acre					Yield per acre			
	NaNO ₃ , pounds	Acid phosphate, pounds	K ₂ SO ₄ , pounds	Na ₂ SO ₄ , pounds	MgSO ₄ , pounds	Grain, bushel		Straw, hundredweight	
						Without silicate	With silicate	Without silicate	With silicate
1	275	27.3	33.8	16.2	19.8
2	275	350	42.2	43.5	24.6	25.8
3	275	...	200	100	100	28.6	36.4	17.9	21.7
4	275	350	200	100	100	41.2	44.5	25.3	27.6

The table shows that the effect of the sodium silicate is chiefly on those plots which are low in phosphoric acid, and it appears to ripen the grain in a similar but not so striking manner as the application of phosphorus.

Hall and Morison concluded that the increased and earlier grain formation observed in the presence of silicates is due to an increased assimilation of phosphoric acid by the plant but that there is no evidence that the function of phosphorus can be replaced by silicon. Jennings (1919) increased the dry weight of wheat seedlings from 18 to 29 per cent by the addition of 1 per cent silica to the culture solution in which they were growing. He also showed that the Si content of these plants was increased as much as 10 to 15 per cent over those grown in the solutions containing no silica. Lemmerman and his workers (1922 to 1925) found that yields were increased by the application of silicates particularly where there was an absence of P but where K and N were applied in the requisite amounts. They found that colloidal silicic acid was the most favorable form in which to apply the silicon. These workers considered that Si does not replace phosphoric acid in the nutrition of the plant but increases the amount of phosphoric acid which can be taken up from the soil and the efficiency with which it is utilized. Gile and Smith (1925) observed in experiments with millet grown in sand cultures that the addition of silica gels greatly increased the growth of plants supplied with acid phosphate. The growth of the plants was approximately proportional to the quantity of phosphoric acid in the plants but bore no relation apparently to the quantity of Si taken up. These authors ascribe the beneficial action of the silica gels to those plants supplied with rock phosphate to the increased quantity of phosphoric acid. Schollenberger (1922), however, found that plots treated with various Si compounds and

soluble phosphates furnished no data on which to base conclusions as to the action of silica in phosphorus assimilation. Brenchley, Maskell, and Warington (1927) found that under control conditions in water cultures in the absence of phosphorus the addition of soluble silicates brought about a significant increase in the dry weight of barley. This addition of silicates caused an increase in the height of the main stem, hastened the development of leaves, and was the most marked in phosphate-free solutions. The soluble silicates were more active in causing the increase in dry weight than the glass silicates. In the heaviest application of silica the shoots contained ten times as much silica as they did in solutions which did not contain it. These authors considered that there is a variation in the response of mustard and barley to silicates on different types of soil. They suggest that silica might act within the plant by unlocking phosphate from relatively quiescent parts of the plant and enabling it to be transferred to regions where assimilation and growth are active.

I. BORON

1. Occurrence.—Boron is very widespread in the plant kingdom, and Agulhon (1910) has determined its presence in the fungi, algae, ferns, and various members of the flowering plants. In the plants examined by him the amount of B ranged from 1.2 per cent of the ash in the case of *Betula alba* to as low as 0.12 per cent of the ash in *Cannabis sativa*. Brenchley (1914) states that, in general, annual plants seem to have the least B in the composition of their ash and that the bark and wood are richer in this element than the leaves. The work of Cook (1916) shows that the absorption and distribution of B varies greatly with different plants. In growing plants in soil to which manure treated with borax and calcined colemanite had been added, wheat and oats absorbed very little B, while leguminous and succulent plants absorbed comparatively large amounts. The amount of boron in the entire plants of oats and peas grown in the same kind of soil varied in the case of oats from no detectable amount to 0.025 per cent of the total dry matter and in the case of the pea from 0.0005 to 0.04 per cent of the dry matter, the amounts depending on the amount and form of the B applied. The fruit of the tomato plant contained only traces of B, while the seed of the cowpea contained large amounts, from 0.0094 to 0.0222 per cent of boric acid on an ash free basis. Potatoes showed a small amount of B in the tops and relatively large amounts in the roots and tubers. Wheat, beets, cowpeas, and potatoes contained B principally in the tops and, with the exception of beets, comparatively little or none in the roots. String beans, soybeans, and cowpeas showed a more equal distribution of B among the roots, tops, and fruits than any of the other plants tested.

2. Influence.—Haselhoff (1913) found that beans benefited by the application of 1 mg. of B per liter of water cultures but that corn was injured by that amount or by only a slightly greater concentration. One hundred-thousandths per cent B in the soil was not injurious to beans when borax was used, but if boric acid was used it was detrimental at that concentration. Warington (1923) investigated in a thorough manner the effect of B in water cultures upon the broad bean (*Vicia*

faba). It was found that in water cultures a continual supply of boric acid appears to be essential to the healthy growth of this plant and that concentrations of 1:12,500,000 to 1:25,000 of this acid were beneficial but that a concentration of 1:5,000 or above was injurious. In the absence of B in the solution, the death of the broad bean occurs in a very characteristic manner, the shoots becoming withered and blackened. The plant, however, can be revived by the addition of boric acid after these symptoms have set in and growth is renewed by means of new lateral shoots and roots. These plants do not show these symptoms when grown in soil in pot cultures and it is considered that the trace of B there present is sufficient for the needs of the plant. It was also found that the absence of B apparently does not cause death in barley and rye, their growth being healthy in cultural solutions lacking it. It remains, however, to be proved whether the cereals can develop in the complete absence of B or whether they require so little that the supply stored up in their seeds is sufficient for their development. The cereals are more susceptible to injury from boric acid than the legumes, barley being injured in water cultures by a concentration as low as 1 to 2,500,000. Voelcker (1910), however, reports that any concentration over 0.001 per cent of B either as boric acid or borax prevented wheat and barley plants from developing and forming grain, while with quantities not exceeding 0.00025 per cent of B, there is a slight stimulating effect amounting to a maximum of 7 per cent and 20 per cent in the case of boric acid and borax, respectively. Boron is evidently essential to the development of the broad bean and probably also to the runner bean, dwarf bean, crimson clover, and melon, while white peas, white clover, and winter vetch appear to be but little benefited by its presence.

Sommer and Lipman (1926) consider that B is absolutely essential to the life and growth of certain higher plants and probably all of them. They grew plants under every precaution to prevent contamination from the outside or from impure chemicals and found B essential to Windsor bean, cotton, barley, buckwheat, castor beans, flax, and mustard. They removed the seed from the seedlings as soon as possible so that the plants could obtain little or no B from that source. The effect of the lack of B under those conditions made itself manifest early in the life of the seedling, as was evidenced by the almost total lack of growth.

It has also been found by Warington (1926) that a definite connection exists between the presence or absence of B and the anatomical structure of *Vicia faba*. The anatomical structure of the stem of this plant grown in a nutrient solution containing boric acid in the proportion of 1:2,500,000 is exactly similar to that of plants grown in the soil. If, however, B is omitted, frequent disintegration of phloem and ground parenchyma, poor development of the xylem, and hypertrophy, discoloration and disintegration of the cambium cells occur. Similar symptoms were

observed by Johnston and Dore (1928) in tomato plants which were grown in a boron-free medium. The chemical combination in which B is presented to the plant is immaterial, even the insoluble borates being effective according to Brenchley and Warington (1927). They tried to substitute 52 elements for B but found that none could replace it. They considered that the concentration of B is of little importance provided that an adequate total quantity is supplied over a given period. Warington (1923) considers that in those plants to which B is essential this element acts in a nutritive way rather than in a catalytic manner, since a continuous supply of it appears to be required throughout the life of the plant. It was noted by Sommer and Sorokin (1928) in a study of the effect of the absence of boron on the root tips of *Pisum sativum* that the meristematic tissues are the first to show the effects of the absence of this element. In a relatively short time after the plants are transferred to boron-free solutions, the cells cease dividing and a general arrest of growth follows. The existing cells undergo premature development or pathological changes. Isolated xylem elements appear in regions occupied by the meristem or in the region of elongation in normal roots. The root apices are enlarged due to the hyperplasia of the plerome and hypertrophy of the perilem regions. McMurtrey (1929) found in the case of tobacco plants grown in nutrient solutions that growth was greatly reduced in boron-deficient media, the most characteristic effect being the injury produced on the growing point. The young leaves that make up the bud take on an abnormal appearance, characterized at first by a light green color at the base. This is followed by the death of the leaf tissue at the base of the younger leaves and the death and drying of the terminal growing point. Brenchley and Thornton (1925) observed that the absence of B had a marked effect upon the development of nodules in the root of *Vicia faba*. The number of nodules of macroscopic size was smaller in those plants that were not supplied with boron. In one case the number of nodules per plant was 353 and 199, respectively, for the plants receiving B and those deprived of it. In the absence of B the vascular supply of the nodule is defective, being either entirely absent or when present very weakly developed and running only a short distance into the nodule. The nodules which have no vascular strands remain minute and are usually buried in the cortical tissue. Very little nitrogen is fixed in these abnormal nodules, being in one case only one-tenth of that fixed in plants where the nodules were normally developed.

The effect of B compounds in fertilizers and in manures treated with them has received considerable attention in the United States. Cook and Wilson (1917) applied manure which had been treated with borax and calcined colemanite to soil at Arlington, Va., and observed the effect of these B compounds thus applied upon the growth and yield of wheat. The presence of 0.0022 per cent of boric acid added as borax to the first 6 in. of soil or 0.0029 per cent as colemanite was apparently non-toxic

to this crop, although, in 2 years out of 3, borax applied at the above rate reduced the yield of grain 10 per cent while colemanite had little if any effect. Only minute quantities of B were absorbed by these plants, but more was absorbed from the borax than from the colemanite.

These workers (1918) observed that there is a decided difference in soils in rendering added B non-toxic to plants. In some soils there is a tendency for the plant to absorb B in proportion to the quantities added, while in others the same amount of B is absorbed irrespective of the quantities added. The behavior of plants grown at Arlington, Va., and Bethesda, Md., will serve as an example in this regard. At the latter station, 0.0044 per cent of boric acid as borax and 0.0058 per cent as colemanite in the upper 6 in. of soil caused no injury to lettuce, spinach, or kale; but at the former station, these concentrations caused a reduction in the crop of these plants.

Skinner, Brown, and Reid (1923), Neller and Morse (1921), and Blair and Brown (1921) found that the potato can tolerate a greater quantity of borax than corn and beans. The effect of borax on potatoes at Arlington, Va., when used in quantities of less than 5 lb. per acre applied in the furrows was one of stimulation, but 20 lb. per acre produced injury and depressed the yield. In Maine, however, 5 lb. of borax applied in the drill at the time of planting produced definite injury. In the case of corn, 4 lb. of borax per acre in the drill caused a decrease in yield of both grain and stover. When sown broadcast, 20 lb. per acre were required to produce any decrease in yield, while practically no plant growth took place where the application exceeded 50 lb. of borax per acre. Skinner and Allison (1923) observed on the silt loam at Arlington, Va., that cotton was slightly injured by the broadcasting of 10 lb. of borax per acre and decidedly so by the application of 20 lb. Boric acid and to a lesser degree borax exerted a stimulating effect on plants in nutrient solution (Collins, 1927), the greatest stimulation appearing when 2.5 mg. of B per liter of cultural solution was used. He, however, does not consider that B is necessary to the production of mature plants in nutrient solutions. In field experiments, all compounds of borax tested reduced the dry weight of plants when applied in quantities equivalent to 1 to 7.5 lb. of B per acre depending upon the type of soil.

The evidence indicates that boron is an essential element for plant growth but that only extremely small amounts are necessary to supply the needs of the plant. The application of the compounds of boron, however, as fertilizers must be made in relatively small amounts or they will have a toxic effect upon the plants. In most cases, applications as low as 5 lb. per acre cause detrimental effects on crop growth and production.

J. MANGANESE

1. Occurrence.—Manganese is universally distributed in plants (Bertrand and Rosenblatt, 1921 to 1922), and, according to Robinson (1917), it fluctuates more in amount than most of the other elements. Most investigators concur that it tends to accumulate in the leaves and that this element reaches its highest concentration in that part of the plant. In corn grown in Kansas, the Mn content was 0.017, 0.037, and 0.043 per cent of the dry matter of the stem, grain, and leaves, respectively (Lashaw and Miller, 1924). According to Kelley (1914), the leaves of the pineapple contain ten times as much Mn as the stalk. In the various plants grown in Kentucky, McHargue (1925) found Mn present in parts per million of air-dry material as follows: Soybean leaves 160, soybean seeds 32, wheat bran 125, wheat embryos 150, corn embryos 40, corn endosperm 16, rice polishings 100, and polished rice 10. In Oregon,

alsike clover utilized Mn in larger amounts than any other legume there grown (Jones and Bullis, 1921). The average Mn content for legumes considered in terms of milligrams per kilo of air-dry material was alsike clover 68, vetch 42, white clover 34, field peas and red clover 33, sweet clover 27, and alfalfa 23. Gössl (1904) found that swamp plants and water plants, in general, contain more Mn than dry-land plants and that the evergreens have a greater quantity than the deciduous trees. It has been observed that the total amount of Mn in the plant will vary according to the nature of the soil, and McDonnell and Roark (1917) state that the stems of *Chrysanthemum cinerariaefolium* if grown in Japan contain more Mn than those from other countries.

The amount of Mn in the seeds is an important point to consider, since it is assumed by those who consider Mn an element essential to the normal growth of plants that the seed, in some cases at least, contains a sufficient quantity to supply the plant during its growing period. Wester (1921) found that seeds from 13 plant families contained in every case Mn ranging in amount from 2 to 6 mg. for every 100 g. of dry material. McHargue (1923) investigated the Fe and Mn content of a wide list of seeds, and the observations may be summed up in the following table:

Plant	Per cent iron content on dry basis	Per cent manganese content on dry basis	Plant	Per cent iron content on dry basis	Per cent manganese content on dry basis
Wheat, 10 varieties ...	0.0039	0.0047	Alsike clover ...	0.0517	0.0028
Oats, 6 varieties	0.005	0.005	Crimson clover ..	0.0016	0.0029
Garden peas, 3 varieties	0.0096	0.0012	Tobacco.....	0.024	0.007
Beans, 5 varieties	0.0103	0.0018	Hemp.....	0.0085	0.0165
Soybeans, 9 varieties ..	0.0074	0.0028	Sunflower.....	0.0034	0.0023
Alfalfa.....	0.010	0.0012			

The average Mn content of the seeds of wheat, oats, and hemp, produced under natural conditions, is equal to or greater in amount than the average amount of Fe found therein. This observation agrees with that of Headden (1915), who found that Mn is present in the grain of wheat in approximately the same proportion as Fe, although the latter greatly predominates in the soil. Although the Fe and Mn were present in approximately the same amounts in the grain, the former was present in the straw in amounts from two to six times greater than the latter. Headden examined samples of wheat seed which had been grown over wide areas and under a wide range of cultural conditions, climate, and soils and found that the Mn content ranged from 0.003 to 0.006 per cent of the dry seeds regardless of the conditions under which the crop was grown.

2. Need.—Manganese is considered by Bertrand (1897, 1905, 1912) and by McHargue (1919 to 1925) to be an element that is necessary for at least the majority of green plants. They consider that because the amount needed by plants is so small, it has been supplied to the plant in sufficient quantities as impurities in salts or other lack of control conditions. McHargue (1922) found that the salts of Ca, Mg, and Fe generally used for plant nutrients may contain as impurities a supply of manganese sufficient for the plant's needs. This fact has apparently been

overlooked by most investigators in plant nutrition. McHargue observed that crocks which were supposed to be perfectly glazed absorbed during the growing season from the soil with which they were filled a sufficient amount of Mn to supply the needs of the succeeding crop grown in them in a Mn-free medium. This experiment emphasizes the need for acid-proof glazed jars in experimental nutrition work. McHargue (1922) observed that when wheat seedlings were grown in Pfeffer's nutrient salt solution from which Mn was excluded, they showed no observable differences from those supplied with Mn during the first 6 or 8 weeks. Shortly after this period, the plants from which Mn was withheld began to give evidence of unequal growth. The first observable difference was the lack in the development of chlorophyll, the leaves becoming a yellowish green. The plants deprived of Mn made a stunted growth and produced no seed, whereas those to which manganese was available grew normally and produced seed. There was an increase of 135 per cent in the dry matter produced in the plants receiving Mn when compared with the dry weight of an equal number of other plants from which it was withheld. It was found that the seeds of radish, soybean, cowpea, field bean, and corn do not contain a sufficient amount of manganese for the growth of these plants to maturity. Samuel and Piper (1929) studied the relation of manganese to the growth of rye and oats. They found that these two plants differ in regard to their requirements for manganese. Thus rye developed to maturity in water cultures on an amount of manganese which did allow the complete development of oats. A concentration of 1 part in 50,000,000 parts of nutrient solution allowed complete development of rye, while the minimum quantity of manganese which allowed healthy growth of Algerian oats was about 14 parts per 1,000,000 of dry matter at the flowering stage. Samuel and Piper found that on certain soils oats are unable to absorb this minimum quantity and that they suffer from the grey-speck disease, a manganese-deficiency disease which can be cured by the application of soluble manganese salt. On soils with abundant available manganese, considerably more manganese is absorbed by oats than is required for normal development. These investigators tried to replace manganese with ten different rarer elements, but none of these, singly or in combination, was able to replace it in the growth of oats.

3. As a Fertilizer.—The influence of Mn as a fertilizer in soil and in water cultures has been studied by numerous investigators. The results indicate that the effect of the application of this element will depend upon the concentration of the various salts used and upon the type of plant under observation. Nagaoka (1903, 1904, 1906) showed that the application of 50 kilos of manganous sulphate per hectare increased the rice harvest over one-third the first year, 16 per cent the second, only slightly the third year, and caused a depression in yield the fourth

year due probably to the increased acidity of the soil. Small quantities of manganese sulphate in soil cultures stimulated the growth of rice, peas, and cabbage according to the observations of Loew and Sawa (1902), while Loew and Honda (1904) report that *Cryptomeria japonica* growing in soil treated with manganese sulphate doubled in one and one-half years its cubic contents over plants which had grown in soil not treated with this compound. Katayma (1906) applied both iron and manganese sulphate to soil at the rate of 0.01 per cent and observed an increase of 6.2 per cent straw and 7.2 per cent increase in grain yield of barley but a depression in the yield if larger amounts were applied. Brenchley (1910) states that at the Rothamsted station concentrations of less than 1:100,000 of manganese sulphate stimulated the vegetative growth of barley but retarded the ripening of the grain. The application of 100 lb. of manganese sulphate per acre increased appreciably both ammonification and nitrification (Brown and Minges, 1916). The increase in activity was lower in applications above this amount, but a decrease occurred if amounts greater than 2,000 lb. per acre were applied.

Schreiner and Dawson (1927) observed that a highly calcareous soil occurring in certain regions of Florida failed to produce a crop even with a heavy application of inorganic fertilizer unless stable manure was applied. Striking results were obtained by the application of 25 to 50 ppm. of $MnSO_4$ in addition to the balanced inorganic fertilizer. In control greenhouse experiments with this soil plants did not flower, developed chlorosis, and were stunted in growth. These effects rapidly disappeared on the application of manganese.

4. Physiological Rôle.—The function performed by Mn in the metabolism of the plant rests almost entirely on theoretical grounds. Bertrand (1897, 1905, and 1912) considered that the addition of small amounts of soluble Mn increases the oxygen-carrying power of the oxidases. This enzyme is universally present in plants and fulfills a definite function in their metabolism. From their observations on the effect of manganese on the germination of seeds, Michiels and DeHeen (1906) considered that this element has a rôle in enzymic action. Kelley (1914) from his observations on the effect of manganese on the plants of pineapple believes that manganese may act in two general ways: (1) It may have an effect upon the inert bases of the soil by bringing about a greater degree of mobilization of calcium and magnesium therein, and (2) it may cause a stimulation of the necessary oxidation going on in the plant and in the soil. The first effect is substantiated by the work of Aso (1907), who found that a 41.8 per cent increase in the yield of rice was obtained from the first application of manganese sulphate, while similar applications to the same soil the following year produced only a little better than a 2 per cent increase. McHargue (1922) thinks that manganese is concerned in nitrogen assimilation and the synthesis of proteins

and that it plays the rôle of a necessary catalyst in plant metabolism and also functions with iron in the synthesis of chlorophyll. He also considers that since the lack of manganese affects the production of dry matter, the indications are that it has some very important function in carbon assimilation.

Chlorosis of plants seems to occur when they are deprived entirely of a Mn supply, and this may prevail also even when an abundance of this element is in the soil or the cultural solution (McCool, 1913). McGeorge (1923) considered that the chlorosis of pineapple leaves on plants grown in soils rich in Mn is due to a greater assimilation of lime indirectly caused by the presence of manganese in the soil. He believed that the principal physiological disturbance is the greater immobility of the iron in the plant, resulting from the excessive lime content of the leaves and stalks, since iron is present in an equally available form in both manganiferous and non-manganiferous soil types of the same hydrogen-ion concentration. Rippel (1923) observed that manganese in the form of soluble salts produced chlorosis in barley plants grown in water cultures. This was overcome or cured by increasing the iron supply. Since the iron content of green and chlorotic plants was the same, it was concluded that Mn did not interfere with iron absorption but with the activity of iron within the plant. McLean and Gilbert (1925) were able to effect a complete cure of chlorosis of spinach, growing on heavily limed soils, by spraying the plants with a solution of 8 parts per 1,000,000 of manganese sulphate. When harvested, a 40 per cent increase in yield was obtained from the treated plants as compared with the untreated ones. The injection of solutions containing 5 to 50 ppm. of Mn into the leaves through the stomata brought about the recovery of the chlorotic spinach plants.

K. CHLORINE: ITS OCCURRENCE, FUNCTION, AND VALUE AS A FERTILIZER TO THE PLANT

With the exception of the conifers, Cl is present in practically all plants, according to Jung (1920), who studied microchemically the occurrence and distribution of this element in plant tissue. This author considers that Cl occurs in the plant only in the form of chlorides which are generally dissolved in the cell sap. It usually increases in amount from the roots to the leaves, being most abundant in succulent parenchymatous tissue. It is especially abundant in fleshy roots and rhizomes and is very scant in the epidermis, fibrovascular bundles, pollen, and woody tissue. The mosses, ferns, and epiphytes contain little or no chlorine. All seeds that have been examined contain more or less of Cl. Most soils contain considerable amounts of it in the form of chlorides. Schmidt (1915) found that the entire Cl content of the sugar-beet seed is soluble in water and can be precipitated directly by AgNO_3 . This strongly indicates that the chlorine in this seed exists largely in the form of inorganic chlorides and that if it is involved in any organic compounds they must be very unstable.

In consequence of the results obtained by the earlier experimenters in plant nutrition, Cl has generally been considered as one of the unessential elements for the growth of plants. Nobbe and Siegert (1862), and Leydhecker (1866), however,

observed certain peculiarities in the development of buckwheat in a Cl-free nutrient solution which led them to conclude that Cl was necessary for the proper growth and development of this plant. As a result of this work, the buckwheat plant has been repeatedly mentioned in the literature as an example of a plant that requires Cl for its development. Many other investigators, however, since that time, among whom are Shulov (1909), Tottingham (1920), Johnston (1917), and Trelease (1917, 1920), have concluded that, aside from the small amount of Cl contained in the seed, the buckwheat plant does not need Cl for its normal growth and development.

A great amount of work has been done to determine the value of the chlorides as fertilizers. The results that have been published are very confusing. In many cases, Cl is apparently beneficial to plant development while in others it is deleterious in its influence on growth. The environmental conditions under which the experiments have been conducted have been very poorly defined, and this no doubt has been one of the main reasons for the contradictory data that have been reported. The student is referred to Tottingham (1919) for a thorough review of the literature on this subject. Tottingham (1915, 1917, 1919) carried on extensive and well-controlled experiments in chlorine nutrition. Wheat, buckwheat, radish, carrot, parsnip, sugar beet, and potato were grown in nutrient cultures, in soil cultures in the greenhouse, and in field plots. The chlorides of potassium and sodium were used chiefly as sources of Cl, the sulphate or nitrate of potassium being replaced partly or wholly by the potassium chloride, while sodium chloride was applied either alone or supplementary to a complete nutrient mixture.

In the case of wheat grown in water cultures, increasing amounts of KCl depressed slightly the yield of dry matter in the tops and roots as well as the length of roots. The addition of NaCl, while it depressed the length of roots, led to a slightly increased yield of dry matter as compared with other solutions. Buckwheat grown in similar cultural solutions showed that the Cl ion in all cases produced disturbances which were shown in a decreased root length, decreased production of dry matter of leaves and roots, and decreased water absorption per culture. The application of chlorides to radishes growing in soil cultures in the greenhouse increased the dry weight of the roots. The production of dry matter in the roots was decreased in proportion to tops by the application of Cl in the carrot but increased in the case of the sugar beet. The percentage of glucose in the radish and parsnip was depressed by both KCl and NaCl, while in the case of the carrot and sugar beet they induced an increase of this sugar. Sodium chloride increased the amount of sucrose in the radish and carrot and depressed it in the case of the parsnip and sugar beet. The application of the chlorides led to the production of a more watery root of the radish, carrot, parsnip, and sugar beet, a result which has been observed by several other investigators (Bolin, 1916).

In greenhouse experiments with potatoes the percentage of starch in the Triumph variety was not altered by the application of KCl, while the Rural New Yorker showed a decrease in starch under these conditions. Sodium chloride produced more watery tubers than the unfertilized controls. In field experiments no significant variations in the percentage of starch resulted from the varied treatments with the chlorides. Tottingham considered that the depressing effect of Cl on the starch content of potatoes as reported by Pfeiffer (1898) and his workers does not occur under all conditions of culture. The application of NaCl alone in the field, however, produced tubers of an inferior quality which were possessed of a bitter alkaline flavor. Rudolfs (1919) from data secured in determining the effects of NaCl on oak, birch, and maple trees considered that the application of small amounts of the salt exerted a stimulating effect, as shown by the luxuriant growth and the extremely dark color of the leaves. Lomanitz (1923) in growing alfalfa in cultural solutions found that the solutions containing NaCl gave higher yields than did the checks. The greatest increase was obtained with the solution in which one-tenth atmospheric osmotic concentration

of NaCl was substituted for the one-tenth atmosphere of KNO_3 of Tottingham's solution *TIRLS5*, the roots showing a greater relative increase than did the tops. In another experiment (1924) alfalfa was grown in nutrient solutions with varying amounts of NaCl. An increase in yield over the checks was observed in five out of six cultures. He considered that NaCl might function as a mineral nutrient.

Chlorine in many cases has a morphological effect upon the plants growing in the medium to which it is applied. Harter (1908) found that plants of wheat, oats, and barley grown from seeds in soil containing 0.7, 1.0, and 1.4 per cent, respectively, of NaCl developed a waxy bloom upon the leaf surface and a thickening of the cuticle and that this thickening increased with the concentration of the solution. The size of the epidermal cells decreased as the concentration of the salt in the soil increased, but when the amount of NaCl present was much below the minimum concentration that is injurious under field conditions no perceptible modification of the plant structure occurred. Hendry (1918) grew Windsor, kidney, lima, Red Mexican, Terparry, and other varieties of beans in sand to which was added 0.04, 0.16, 0.3, 0.5, and 1.0 per cent, respectively, of NaCl based on the dry weight of the sand. The visible effects of the NaCl upon the development of the plants were retardation of height, a reduction in the number and size of the leaves, a retardation of the blooming period, and a reduction in the number and size of the nodules formed. It was noted by Hendry and also by others that there is a distinct difference in the ability of different species of plants to withstand the toxic effects of chlorides when they are applied in excessive amounts to the medium in which the plant is growing, while Harrison and King (1925) have shown that the age of the plant is an important factor in determining the degree of toxicity of sodium chloride.

Asparagus is an example of a plant that can tolerate a large amount of sodium chloride and the salting of asparagus beds with NaCl has long been a traditional practice among gardeners. Rudolfs (1927) applied NaCl at the rate of 150, 300, and 500 lb. per acre to asparagus beds for 2 years. The application of 150 lb. did not increase the number of stalks over plants on unsalted plots. Doubling the amount of salt resulted in an increase in average number of stalks from six to seven, while an application of 500 lb. per acre brought the yield per plant up to seven and one-half stalks.

The manner in which the chlorides may bring about the responses that have been mentioned is not known. All the explanations that have been put forth are purely theoretical. Tottingham (1919) considers that the apparent relation of the chlorine content to the accumulation of starch in the potato tuber is a suggestion that enzyme activity might be the main controlling condition for this effect. The fact that chlorides have a stimulating effect upon the enzymes obtained from plant sources would seem to lend strength to this general theory. Since many of the vital activities of the plant are apparently controlled by enzyme action, the physiological responses might be brought about in this manner. Rudolfs (1919) from his observations on the effects of NaCl on trees considers that it is possible that the chlorine increases the acidity of the cell which could accelerate the vital activities or enzymotic actions to a certain extent but that by a too large increase of acidity the acceleration would change into a toxic action.

Our knowledge of the influence of chlorine upon the metabolism of the green plant is extremely meager. Tottingham (1919) is of the opinion that the most valuable general conclusion that can be drawn from the review of the literature is that the influence of chlorine upon plants seems to be impossible of any general statement. The facts observed indicate that the effect of chlorine will depend upon the nature of the plant under consideration and upon the nature of the soil or other medium in which the plant is growing, other than the chlorine content. Some consider that the influence of chlorine is in many cases indirect in that the reactions of the plant are

due to changed conditions in the mineral content of the soil induced by the applied chlorides and not to their direct action upon the plant cells (Wheeler and Hartwell, 1902; Prianischnikow, 1905). Trelease (1917, 1920) reported extensive experiments which greatly illuminate this subject. He found in growing wheat in water cultures that if the solutions were properly balanced, the same growth was obtained regardless of the addition of chlorine. If the cultural solutions, however, were not properly balanced, the addition of chlorine apparently diminished to some extent the retarding effect produced by the unbalanced solution, and a better growth was obtained. The addition of an unessential element may thus improve the properties of the medium which contains the essential ones in improper proportions.

The action of chlorides on plants is evidently influenced also by the general climatic conditions that prevail during growth. This fact is suggested by Tottingham (1917) and also by Lipman, Davis, and West (1926), who obtained evidence in the study of the tolerance of wheat, barley, and peas to NaCl that led them to state that the environmental conditions are a very important determinant of the kind of results which may be obtained in studying the influence of chlorine upon plant life.

L. ALUMINUM

1. Occurrence.—Aluminum has been found in the ash of all plants that have been examined. The amount of this element varies greatly for different plants, and Kratzmann (1914), who analyzed 130 species of plants, considers that they possess specific selective powers toward aluminum. As a rule, the percentage of Al in plants is very small, but in a few cases, as certain species of club mosses, Al approximates 22 to 39 per cent of the ash. Latshaw and Miller (1924) found that Al made up 0.07, 0.013, 0.023, and 0.98 per cent of the dry weight of the leaves, stem, grain, and roots, respectively, of corn plants that had reached their full vegetative growth and development. Berthelot and André (1895) also state that the amount of Al in the roots is much higher than that in the leaves. There is some question, however, in regard to the relatively high amounts of Al reported in the roots, since the adhering particles of soil even in exact preparation of material could exert a marked influence on the results. Meyers and Voegtlin (1914) analyzed several of the grain and vegetable foods for Al compounds with the results shown in the following table:

Food	Percentage of aluminum on dry basis	Food	Percentage of aluminum on dry basis
Corn.....	0.120	Sunflowers (hulled).....	0.401
Corn oil cake.....	0.810	Cotton seed.....	0.996
Rye.....	0.175	Carrots.....	0.301
Millet.....	0.428	Irish potato.....	0.126
Wheat flour.....	0.045		

At least 65 per cent of the Al in corn and carrots was soluble in water, while the total Al content was completely soluble in 0.3 per cent of HCl. Only a trace of the Al present in wheat flour and in the sunflower seed was soluble in water. McLean and Gilbert (1927) found in the case of corn, cabbage, peppers, redtop, lettuce, and timothy that the greatest accumulation of Al is in the cortex of the roots. In the cell they observed that it accumulates in the protoplasm rather than in the cell walls or vacuoles and that it is especially abundant in the nucleus. Little or nothing is known concerning the form in which Al occurs in plants.

2. Influence upon Plant Life.—The rôle of aluminum has been studied along three general lines: (a) the effect of this element upon growth and production, (b) the effect upon the soil relationships, and (c) the rôle of this element if any in the functions of the plant cell.

a. *Growth and Production.*—Yamano (1905) found that 0.2 per cent of ammonium alum injured wheat and rye plants in nutrient solutions after three weeks and that 0.8 per cent killed the plants in a few days. Prianischnikov (1911) grew wheat, oats, barley, peas and buckwheat in sand cultures fertilized with aluminum phosphate alone and with calcium carbonate alone. He concluded that aluminum phosphate is assimilated and that calcium carbonate has no appreciable depressing effect on the assimilability of aluminum phosphate. Baguley (1912) made comparative tests with the orthophosphates of iron, calcium, and aluminum on oats, peas, and Swedish turnips grown in sand and chalk. He obtained better results with the iron and aluminum phosphate than with calcium phosphate. Truog (1913) working at Wisconsin with ten different kinds of plants concluded that precipitated ferric and aluminum phosphates produced, with but few exceptions, as good growth as and in a few cases better growth than the acid phosphate. Kratzmann (1914) found that salts of aluminum in a concentration of 0.005 per cent hindered the growth of corn, horse beans, lentils, and sunflowers, while a solution of 0.0001 per cent somewhat increased growth. Ruprecht (1915) found that a solution of aluminum sulphate greater than 40 parts per 1,000,000 had a very toxic action on clover seedlings. The effect of the aluminum salts was localized in the cells near the root hairs, and he attributed the death of the plants grown in aluminum salts to starvation incident upon the inability of the plant to obtain nutrient salts for normal metabolism. Miyake (1916) showed that aluminum chloride is toxic to rice seedlings in concentrations greater than $N/7,500$ and that the toxicity of the salt is not due to the hydrogen formed by the hydrolysis of the salt solution. Mirasol (1920) reports that in the case of barley growing in aluminum sulphate the solution is toxic up to $N/10,000$ but with a concentration $N/30,000$ it seemed to have a stimulating effect. McLean and Gilbert (1927) found that lettuce, beets, timothy, and barley are the most sensitive crops to aluminum poisoning. The medium-sensitive crops are radishes, sorghum, cabbage, oats, and rye, while corn, turnips, and redtop are noticeably resistant to the toxic effects of Al, redtop being the most resistant of the three. Later (1928) they observed that very low concentrations of aluminum (3 to 13 ppm.) were stimulatory to plants, while higher concentrations were toxic. Non-dialyzing forms of aluminum which could not pass through a collodion membrane in sufficient amount to cause toxicity were decidedly toxic when placed in contact with barley roots. High acidity is not necessarily an accompaniment of toxicity, since aluminum citrate is toxic at P_H 6.5 or less acid.

b. *Relationship of the Soil to the Plant.*—It is not the intention here to enter into any detailed discussion of the chemical reactions that concern Al in the soil but to mention only a few observations in which the beneficial results of lime or fertilizers are apparently due to their action upon the Al compounds of the soil. Hartwell and Pember (1918) noted that in treating acid soil with lime the growth of rye was very little benefited but that the yield of barley was increased from two- to threefold. In an acid nutrient solution, however, these two plants were affected equally, while aqueous extract of the acid soil like the soil itself affected the two kinds of plants very differently. These facts indicated that the toxicity of the so-called "acid" soils is not due only to the acid but to some ingredient not present in the ordinary nutrient solution. After a search for the cause of this toxicity they decided that Al is the causative agent under conditions such as have been described. The application of phosphoric acid or acid phosphate, while it increases the acidity of the soil, has a beneficial effect on the crop, since the solubility of the Al in the soil is reduced by the

phosphate. Their results indicate that the practical advantage of phosphating and liming may often be due to the precipitation of active Al, which is toxic to many plants quite as much as supplying phosphorus as a nutrient or lime as a reducer of acids. Conner and Sears (1922) likewise consider that the toxicity of Al salts is due to the Al ion more than it is to the hydrogen ion on such plants as barley and that this toxicity is reduced when much phosphate is used in the nutrient solution. They consider that acid soils are toxic to many plants largely because they obtain easily soluble Al salts. Magistad (1925) notes the difference in plants in the reaction to aluminum and considers that the benefits obtained in practice through the use of lime in the case of clover, alfalfa, oats, and rye result usually from a decrease in acidity and not from a decrease of Al present. In corn and barley, however, over the same range of acidity this benefit results from a decrease in both acidity and soluble aluminum. Hoffer and Carr (1923) and Hoffer and Trost (1923) in investigations on corn diseases reported on the accumulation of iron and Al compounds in the nodal tissues of the plant which causes a purplish brown discoloration of these tissues and finally disintegration. They found that the accumulation of Al in these tissues is affected by the genetic composition of the strain of corn and by conditions of the soil. When abundant Al injury occurs in the corn plant it is an indication that the soil is deficient in available phosphates. This injury from Al can be corrected by the application of lime and phosphates to the soil. Arndt (1922) likewise observed that the composition of the nutrient solution had a marked influence in determining the toxicity of Al salts. Coville (1923) obtained striking results in the growth of plants of *Rhododendron catawbiense* by the addition of Al sulphate to a rich garden soil in which the plants were growing. One set of plants was treated with distilled water, another with distilled water and magnesium sulphate, and a third with distilled water and aluminum sulphate. The increase in the diameter of the rosettes of leaves was 0, 30, and 250 per cent, respectively. Potted plants which for more than a year had made sickly growth in rich garden soil were revived in an 11-weeks period by two mild applications of aluminum sulphate. The leaves of the treated plants became a bright green color, while those of the controls remained sickly and dull. Coville believed that the aluminum sulphate acts to replace lime with aluminum, the released lime leaching away in the form of calcium sulphate, and as a result the soil reaction is changed from neutral or alkaline to acid and this is a favorable medium for this plant, which thrives best on an acid soil.

c. Function in the Cell.—The physiological rôle of Al in plants is not definitely known, although marked reactions of plants due to this element have frequently been observed. Fluri (1908) found that Al salts cause the disappearance of starch from certain water plants. He used the salts aluminum nitrate, sulphate, chlorate, and bichromate and observed that these salts caused a disappearance of starch even when the plants were well illuminated. The Al found in the cell was small and the results could not be attributed to chemical reaction. Fluri considered that the disappearance of starch under these conditions is probably due to three reactions induced by the Al salts: (1) Increased permeability of the protoplasm causes a more rapid loss of sugar; (2) the diastatic action is increased; and (3) the action of photosynthesis is slowed down. Meurer (1908) considered that aluminum forms some chemical compound with the pectic bodies of the middle lamella, since he found that tissues killed with chloroform absorbed aluminum as readily as living tissue. Szücs (1912) believed that Al salts cause the protoplasm to set or harden, while Stocklasa (1911, 1918, 1922) considered that they combine with the cell wall to form colloidal salts, an action which renders the cell less permeable. He suggested that Al may act as a catalytic agent performing a function in the assimilation of carbon by increasing the rate of photosynthetic action. Mazé (1915) considers that it is an essential element in the growth of corn.

The influence of aluminum upon the color of the flowers of *Hydrangea hortensis* was discovered by Molisch (1907). It had long been known that this plant when grown in certain soils had reddish flowers and in other soils, blue flowers. Cultures of soil treated with potassium sulphate produced plants which bore the ordinary reddish flowers, while the soil treated with aluminum sulphate produced plants which bore blue flowers.

M. SODIUM

Although Na is not generally considered essential to the growth and development of the plant, its presence apparently has a marked effect upon the growth of some plants under certain conditions. Hellriegel (1898) found that Na salts always gave increases in yield even when K salts were present in quantity. The same fact was also observed by Breazeale (1906) for wheat plants growing in culture solutions. Wheeler, Hartwell, Pember, and others (1904 to 1913), however, obtained no increase in growth by the addition of Na when an optimum amount of K was present, but they observed, as did Breazeale (1906, 1916), that a larger amount of K was left in the solution by the growing plants when the K was supplemented by sodium. Sodium thus seems to retard the absorption of K or to conserve it in the metabolism of the plant. Wheeler, Hartwell, and others found that when the deficiency of K was great enough to bring about a 30 per cent depression in the green weight of plant produced, the addition of Na gave an increase in growth amounting to 10 to 25 per cent within a period of from 2 to 3 weeks. Hartwell and Wessels (1913) observed no decrease in the percentage of sugar in the onion when the K deficiency was supplemented with Na, although there was a decrease in the crop corresponding to the scarcity of potassium. In the case of mangel roots there was a tendency toward depression in both the total and the reducing sugars as a result of the addition of Na to supplement a K deficiency. Pfeiffer, Rippel, and Pfothenauer (1920) state that Na salts may to some extent replace K salts as a nutritive material for oats. In the production of dry matter Na replaced K in the molecular ratio of 0.25:1. When relatively small quantities of K and relatively large quantities of Na are present, this ratio is increased to 0.38:1. When such a replacement occurs, the Na appears in the grain as well as in the leaves and stems.

Sodium salts are apparently necessary for numerous marine algae, according to Osterhout (1912). His experiments show that the replacement in sea water of Na by NH_4 , Ca, Mg, Ba, and others is decidedly injurious. Sodium is apparently not needed for osmotic pressure in this case, since an equivalent concentration of other compounds does not satisfy the plants. Osterhout could not determine the value of Na as a nutrient but considered that it might serve to antagonize the toxic action of other salts that are present in the sea water. From the experimental evidence at hand it seems that Na may be able to perform one or

more of the following rôles depending, however, upon the environmental conditions and the type of plant under consideration: (1) It appears to be a conserver of potassium, since less is absorbed by the plant when sodium is added. (2) It may to a limited extent replace K as a plant nutrient (Schulze, 1913). It can apparently perform certain functions of K but by no means all of them. It may delay K starvation for the plant but cannot keep it off entirely. (3) When applied to a soil that is deficient in K it may liberate a certain amount of K which was adsorbed by the soil and make it available for the plant, thus bringing about an increase in growth. The experimental evidence with water cultures, however, makes it appear doubtful whether sodium functions in this manner, although it is doubtful whether water cultures would indicate anything in regard to base exchange that might occur in the soil. (4) In certain specific cases, it evidently acts as an antidoting agent against certain toxic salts present in the medium in which the plant is growing.

N. OTHER ELEMENTS

The influence upon plant growth of barium, strontium, selenium, titanium, copper, arsenic, zinc, and other elements has been observed by numerous investigators. McHargue (1919) in his experiments with cowpeas, soybeans, oats, wheat, and corn grown in sand cultures found that neither barium nor strontium compounds can be considered as important plant nutrients but that the presence of a small amount of the carbonate of each of these elements in the presence of calcium carbonate gives increased yields that are noteworthy. Both the barium and strontium carbonate accelerate especially the growth of the roots of plants under consideration. The compounds of both of these elements are toxic to plants in the absence of calcium carbonate. He also found, as did Suzuki (1900), that neither can replace calcium in any degree in the metabolism of the plant. Osterhout (1916) noted that *Spirogyra* underwent a peculiar cytological reaction when placed in a 0.0001 *M* solution of BaCl₂. The reaction observed was a characteristic contraction of the chloroplasts, while the protoplasm remained intact in its normal position. Numerous other salts including CaCl₂, MgCl₂, MnCl₂, NiCl₂, CoCl₂, NaCl, and KCl were tried in the same manner but none produced this peculiar result. This reaction suggests that there is some specific constituents of the protoplasm of *Spirogyra* that reacts in this peculiar manner to barium.

The reaction of plants to titanium has been studied by Nemeč and Kas (1923), who obtained increased crop yields by manuring *Sinapis alba*, *Pisum sativum*, and *Medicago sativa* with titanium as the insoluble titanate and the soluble titanium sodium citrate. The amount of phosphorus, silicon, and aluminum increased and decreased with the titanium content of the plants. Since the iron content decreased with increasing applications of titanium, it was considered that iron might be replaced by this element.

Selenium compounds in concentrations of 0.01 per cent and over exert a detrimental influence on the growth of white lupine and timothy seedlings, according to Levine (1925). He, however, obtained increased growth of these plants in solutions of 0.0001 and 0.001 per cent concentration, respectively, of selenium dioxide and selenic acid.

Arsenic in the form of disodium arsenate showed a beneficial influence in low concentrations upon beans, peas, wheat, and radish, according to the observations of

Stewart (1922). The beneficial influence of arsenic was not manifest by any increase in dry weight but by the more vigorous and healthy appearance of the plant. He considered that the accumulation of arsenic in the soil from sprays might be beneficial rather than injurious to plants. Beans, peas, and wheat were stimulated by concentrations of disodium arsenate up to 75 ppm. Radishes were stimulated by concentrations up to and including 240 ppm. Beans were the most sensitive to this element. When the above plants were killed due to the absorption of arsenic, they contained the following parts per million of dry weight of plant: wheat 269, potato 524, bean 678, pea 1,190, and radish 940. Brenchley (1914) states that the toxic effect of arsenic upon higher plants is much more marked with arsenious acid and its compounds than with arsenic acid and its derivatives.

Brenchley (1914) concluded from a careful survey of the literature to that date that copper compounds under the most typical conditions act as poisons to the higher plants and that it is only under particular and peculiar conditions and in very great dilution that copper shows any stimulating action. It is, however, very widely distributed in plants and in considerable quantity. McHargue (1925) found that the copper content of various plants and plant parts ranged from a trace to 46 ppm. of dry material, while Maquenne and Demoussy (1920) found 0.25 mg. of it per liter of expressed sap of the potato and as high as 40 mg. per kilo of dry leaf substance of lettuce. The last named authors found copper in the greatest abundance in cells which are active in growth and consider that its translocation is controlled by processes accompanying metabolism. They further found that the addition of other solutions of copper sulphate to the extent of 0.02 to 0.2 mg. per liter increased not only the length of life of various plants but also their dry weight (Forbes, 1917). A wide range of plants has been found by Allison, Bryan, and Hunter (1927) to respond in growth and production in a remarkable way to the application of 30 to 50 lb. per acre of CuSO_4 to the raw peat soils of the Florida Everglades.

The action of zinc compounds on plants is very uncertain. Mazé (1915) considered it one of the elements essential for the best development of the corn plant, and his statement has been verified, to some extent at least, by Lipman, Davis, and West (1926). Nakamura (1904), however, could observe no stimulatory effect of zinc, cobalt, or nickel upon the growth of rye, peas, onion, or mustard. Conner (1920) observed that the zinc salts formed by the action of acid soils on galvanized iron containers were very toxic to the plants of oats and buckwheat growing therein. Lithium in the form of lithium carbonate in amounts ranging from 10 to 100 mg. per kilo of soil exerted a stimulating action upon barley and peas, according to Nakamura (1904), who also found that caesium chloride in an amount of 100 mg. per kilo of soil increased the height of rice plants.

The effect of iodine on plants grown in the field was studied by Suzuki and Aso (1903). They found that iodine in the form of KI applied at the rate of 0.5 g. to 20 sq. m. of soil surface brought about an increase in production for oats and a dosage of 0.05 g. for the same surface, a beneficial result for the radish. Brenchley (1924), however, could not find any significant reaction of mustard and barley to the application of iodine. She suggests that it might have some specific and effective action if means could be found to prevent it from being converted so rapidly from the elemental state to the form of compounds as appears usually to be the case when it is applied to the soil.

V. ELEMENTAL REQUIREMENTS AND THE AGE OF THE PLANT

The amount of nutrients necessary for the optimum growth of plants at the different stages of their growth is an important factor from the

standpoint of crop production and is a subject that has received considerable experimental attention.

McCall and Richards (1918) studied the salt requirements of wheat plants at three stages of growth when grown in a three-salt solution composed of KH_2PO_4 , $\text{Ca}(\text{NO}_3)_2$, and MgSO_4 . Of these salts, 36 different proportions were used, which necessitated the growing of 36 different cultures for each of the three growing periods. The three stages of development of the plant that were studied were: (a) the first 30 days from germination, (b) the second 30 days of growth, and (c) the period extending from the close of the second 30-day period to the maturity of the plant. For the early growth period, the solutions which gave the highest yield of tops were characterized by a high $\text{Ca}(\text{NO}_3)_2$ content and a low proportion of MgSO_4 , while the lowest yield of tops was associated with low $\text{Ca}(\text{NO}_3)_2$ and a high proportion of MgSO_4 . For this period the effect of KH_2PO_4 appeared to be overshadowed by the other two salts. The results for the second 30-day period showed results very similar to those of the first period. This indicates that the elemental requirements of the plants during the second 30-day period were substantially the same as for the first period. For the third and final growth period, the solutions which gave the highest-yielding plants were characterized by a relatively high concentration of $\text{Ca}(\text{NO}_3)_2$ and a low proportion of both MgSO_4 and KH_2PO_4 , while the solutions producing low yields were characterized by a high proportion KH_2PO_4 without regard to the ratio of the other two salts. Hibbard and Gershberg (1924) in the case of Marquis wheat using a cultural solution high in MgSO_4 and relatively low in both $\text{Ca}(\text{NO}_3)_2$ and potassium phosphate produced the best growth during the vegetative period between the time the plants were 3 weeks old and the time of blooming. Shive and Martin (1918) found in the case of buckwheat that during the 4 weeks following germination the highest yields of tops and roots were produced by a solution of KH_2PO_4 0.0144 *M*, $\text{Ca}(\text{NO}_3)_2$ 0.0052 *M*, and MgSO_4 0.0200 *M*. During the second 4-week period, including seed production and ripening, the best solution was 0.0108 *M* potassium hydrogen phosphate, 0.0130 *M* calcium nitrate, and 0.0100 *M* magnesium sulphate.

In the case of corn, Hornberger (1882) noted that when the tassels were beginning to form, there was an abrupt slowing down of the rate of absorption of the various elements. This was followed by a period of rapid absorption, which was succeeded by the ripening period in which there was some loss of practically all the elements, due perhaps to diffusion outwardly of solutes and to the loss of leaves and roots. Jones and Huston (1914) found that for 8 weeks after the germination of corn a very rapid absorption of K occurred. This was followed by a period of relatively slow absorption and then, at the time of greatest starch formation in the grain, a period of rapid absorption. They observed no striking difference in the rate of P absorption during the growing season. The

rate of N absorption reached its highest point about the end of the 8-week period. This was followed by a decreased rate which again became high at the 16-week period. In the case of corn grown in nutrient solutions, Duley and Miller (1921) found that an optimum nutrient during the last 30-day period largely determined ear production but that when there was a copious supply of mineral elements at the end of the vegetative stage, the leaves and stems contained enough material to produce fair ears even if there was a small amount of nutrient supply during the last 30-day period of the plant. Burd (1919) studied the rate of absorption of certain elements from the soil by the barley plant at different stages of its growth under conditions that precluded leachings or gains to the soil or the removal of elements from the leaves by rain. During the first period of growth, ending 8 or 9 weeks from planting or about the time the heads begin to form, the increase of N and K conformed very closely to the gain in total weight and water content of the plant. The increase of Ca, Mg, and P closely paralleled the formation of dry matter up to 8 to 9 weeks, respectively, after which they lagged behind. At this time the absolute amounts of K and N contained in the plant very closely approximated the amount present at maturity, while the K content may be even greater than at maturity. During the second period, which extended from the beginning of head formation to the beginning of the ripening of the grain, there was not only a decreased rate of absorption, as has been noted in corn, but there was a decided loss of K and N from the aerial parts of the plant. This loss took place concurrently with the migration of these same constituents into the developing head. The plant, however, had a tendency toward the close of the period to absorb again the soil constituents previously lost. The third period or stage occurring at the time of ripening of the grain was characterized by a practically complete cessation of absorption of all constituents and an actual loss of some of these. The striking thing in this experiment is the fact that the absorption of K and N during the first period of growth is approximately proportional to the growth attained and that in the succeeding periods the final dry-matter content of the crop more than doubles without any very substantial increase in nitrogen content and with an actual loss of K. Burd concludes from his work that it is generally desirable to have the large amounts of solutes in the soil solution at the commencement of the plant's growth cycle but that it is unnecessary and may be undesirable to maintain this condition during certain later stages of growth. Pember (1917) and Pember and McLean (1924) found that K was utilized most successfully by barley, oats, and wheat when supplied early in the growth period. Wheat was able to make a more effective use of a limited amount of K if supplied during a 4-week period from the fourth to seventh week after planting than if the same amount were supplied over a period of 12 weeks. The time of the applica-

tion of phosphorus made little difference, but deficient amounts of N were most beneficial if supplied gradually over the entire growth period.

The tendency toward a delayed rate of absorption or the absolute loss of some constituents at a comparatively early age is probably characteristic of certain types of plants, as indicated by the work of Wilfarth, Römer, and Wimmer (1905) with wheat, barley, and potatoes. They found evidence of K and N losses from wheat and barley at comparatively early stages of development, but in the case of the potato they found no losses of K and N at any stages of development, nor did they observe any outstanding changes in the rate of absorption of these elements during its growing period.

Rice grown in Porto Rico (Gile and Carrero, 1915) showed a decrease in the percentage of K, P, and S in the ash and of N in the dry matter with the age of the plant, which is a common observation for most plants. The amount of Mg, P, Fe, S, and N in 103-day-old plants when the panicles were just out was the same as found in 123-day-old plants when the seed was ripe. The amount of K, however, was approximately twice as much in the mature as in the younger stage. The amount of iron in the ash of the green leaves and straw decreased regularly with the age of the plant, but the amount in the whole plant, including stem, leaves, and grain, remained constant. According to Chizhov (1926) all the necessary ash and nitrogenous substances are accumulated by winter and spring crops about the period of blooming or grain forming. In the sunflower this accumulation is complete at about the time of ripening, while in beans and potatoes it is completed at the end of the vegetative period.

Gericke (1924 to 1926) grew wheat plants in complete nutrient solutions for varying periods and then transferred them to cultural solutions lacking one of the following elements: K, Ca, Fe, Mg, P, N, and S, and allowed them to complete their growth. The following is a summary of the results obtained:

After plants had grown for 4 weeks in a complete nutrient solution and had attained approximately one-seventh of the dry weight obtainable in such a medium and were transferred to solutions devoid of Mg, P, or S, they produced more grain and straw than did the plants grown to maturity in complete nutrient solutions which were three times renewed. The removal of plants grown for 4 weeks in a complete nutrient solution to a K-free medium resulted in a production of dry matter equal to that obtained from cultures grown in a complete nutrient solution. The removal of plants grown 4 to 10 weeks in complete nutrient solutions to solutions lacking N decreased the production of both grain and straw, but otherwise the plants appeared normal. The maximum development among all cultures was obtained from the plant grown 4 weeks in a complete nutrient solution and then transferred into a solution lacking phosphorus. A better growth of plants was obtained from the cultures grown

to maturity in a complete nutrient solution which was not renewed than was obtained from cultures grown in a complete nutrient solution which was three times renewed. The elements required longest in available form in the growth media for the normal development of wheat were calcium and iron.

Brenchley (1929) tested the effect of depriving barley plants of phosphorus after varying initial periods during which it had been supplied and also supplying P after initial periods of deprivation. The providing of P for the first 6 weeks or longer permitted normal growth to be made as judged by appearance, increase in dry weight, and grain produced. If P was withheld for the first 4 weeks, tiller production was not affected, but no heads were produced. With longer periods of initial deprivation, growth was steadily depressed in all respects. The amount of P absorbed by the plant increased steadily in more or less direct proportion to the length of time P was given at the beginning of growth. Sufficient P, however, was taken up the first 6 weeks to enable the plant to make its maximum dry weight. The percentage of P in the dry matter rapidly increased from this time onward.

In connection with the elemental requirements of plants at different stages of their growth, it is important to consider the availability to the seedling of the elements stored in the seed and to note how the amounts thus supplied correspond to the total amounts found in the young seedling. Buckner (1915, 1919) studied the translocation of the mineral constituents of the bean and corn seed and of the potato tuber during germination. He found that approximately 47 per cent of the minerals stored in the cotyledons of garden beans was retained in them when they were no longer functional. The cotyledon of corn contained about 39 per cent of its original mineral content when it had ceased to supply any nutrients to the young seedling. In the case of the potato tuber, the young stem removed only about 50 per cent of the minerals stored in the fresh tuber. The percentage distribution of the various mineral constituents in the seedlings studied is found in the table on page 289.

It was observed that there were no very striking differences in the quantities of the minerals translocated and no marked selective influences shown by the root, stem, or leaves of the seedlings for any particular mineral reserve contained in the seeds or tuber.

The intake of N, K, and P by wheat plants grown in nutrient solutions for fractional parts of a day was studied by Breazeale (1923). The absorption of these elements for 1 hour or other fractional parts of a day was out of proportion to what might be expected if time alone governed absorption. Thus during the first hour the plants absorbed 0.0520 g. of potassium. During a 24-hr. period the same plants absorbed 0.2157 g. of this element. If the rate of absorption of the plants kept

PERCENTAGE DISTRIBUTION OF THE MINERAL CONSTITUENTS IN SEEDLINGS

Adapted from Buckner, 1915

Part	P ₂ O ₅	CaO	MgO	K ₂ O	SiO ₂
Beans:					
Exhausted cotyledons.....	47.2	54.5	45.7	45.1	40.8
Leaves.....	24.3	10.5	27.3	27.8	23.5
Stems.....	20.7	22.4	20.8	18.4	15.4
Roots.....	7.7	13.7	6.1	8.7	19.5
Corn:					
Exhausted cotyledons.....	43.2	43.9	47.0	20.0	58.6
Leaves.....	26.4	30.0	28.7	35.7	19.8
Stem.....	17.4	13.2	16.8	21.2	6.4
Root.....	12.9	12.9	7.4	23.1	15.1
Potato:					
Exhausted tuber.....	67.1	42.0	65.7	64.4	12.4
Sprouts.....	17.8	13.1	15.8	12.7	5.1

in the nutrient solution 1 hour had been maintained for 24 hr., the plants would have absorbed 1.248 instead of 0.2157 g. of K. Thus over five times as much K was absorbed during the first hour period as might be expected if time alone governed absorption.

Davidson (1926) observed that 18-day corn seedlings had absorbed from the soil eight to ten times the amount of K contained in the seed. The amount absorbed during one week after the plants had been thinned in the hill was about twice that which had been absorbed during the previous 18 days. The P content of the seedlings was lower at both stages of growth in the seedling than in the seed. During the first 18 days the amount of N absorbed by the seedling was about equal to that in the original seed, but during the next 7 days it absorbed twice as much.

QUESTIONS

221. Enumerate the elements that have been detected in the analysis of plants. Which compose the greater portion of the dry weight of the plant? Name some that are present in only very small amounts.

222. Give some figures to illustrate how plants, in general, vary in their percentage composition of N, Ca, Mg, P, and K. Give examples to show the wide variation in the amounts of Si, Al, and I absorbed by different plants under the same conditions.

223. Give the extremes in percentage composition of Ca, K, Mg, N, and P for plants which were grown in the same nutrient solution. What is meant by the term "selective absorption" or "feeding power of plants"? In what sense should this term be used?

224. Cite examples to show that the amount of a given element in the plant may be influenced by its abundance in the soil, by its location in the soil, and by the proportion and kind of other elements present.

225. How do the amounts of the various elements absorbed compare with the needs of the plant for them? What is the proof for this? Why does the analysis of a plant not necessarily give an indication of its nutritional needs?

226. Discuss the distribution of the elements in the various organs of the plant. How does this distribution vary with the age of the plant?

227. In what form are the elements absorbed by plants? Which elements does a plant obtain from the soil? From the air?

228. Name the carbohydrates that apparently can be absorbed and utilized by the plant. How are data in this regard obtained? Name some organic acids that can be absorbed and utilized by plants.

229. What is the advantage of using albino plants in the study of organic nutrition of plants? Why cannot a plant be nourished entirely through its roots by sugars and other organic materials? Cite examples in agricultural practice in which the plants may absorb at least some organic compounds.

230. What are essential elements? Unessential elements? What two main functions do the essential elements perform in plants? Which requires the greater quantity of the elements?

231. What 10 elements have generally been considered the essential ones? What three experimental errors were overlooked in the determination of the essential elements?

232. Name five elements in addition to the ten named above which are now considered to be essential to plant life. What general evidence is there that this is the case?

233. State the general functions of C, H, O, and N in the plant.

234. In what amounts and in what form does phosphorus occur in plant tissues? In what parts of plants does it occur in the largest amounts? In what parts in the smallest amounts? What does its general distribution in the tissues signify?

235. In what forms may phosphorus be absorbed by the plant? How do plants differ in their ability to acquire P from different sources? Name some plants that are termed high P-response crops. Some that are low P-response crops. Some that are intermediate in their response to this element.

236. Of what organic compounds in the plant is P a component part? How does the absence of P affect the fat content of the cell? Why? The transformation of starch? The amount of coagulable protein?

237. How may P play a rôle in respiration? How does P affect root formation? How does it affect the date of maturity? Cite examples. What other elements may promote earliness?

238. What portions of the plant contains the highest amount of Ca? Which the lowest amount? In what form is much of the Ca? Cite examples.

239. Name some plants that have a high calcium content— Some that have a low content of this element. What three general physiological rôles may Ca play in plants?

240. Discuss the evidence in regard to the influence of Ca on the translocation of carbohydrates.

241. What rôle has been ascribed to Ca in relation to oxalic acid? What evidence is there that oxalic acid is not formed in some plants? That it is not injurious to plants?

242. To what has the high calcium content of the legumes as compared to the low calcium content of the grass family been attributed? How might Ca-protein compounds function in the activities of the cell?

243. How does the presence of Ca in a mixed solution influence the intake and outgo of ions from the plant? What is the physiological rôle of Ca in the cell wall? How does its absence affect the formation of cell walls?

244. What element can more nearly replace Ca in its function in the cell wall? Why? Why will not K or Na do as substitutes in this regard?

245. How has Ca been considered as an antidoting agent? What is the magnesium-calcium ratio? What is its significance in agricultural practice? Why? State some general responses of plants to the absence of calcium.

246. What two main functions does Mg perform in plants? Cite examples to show the importance of this element in regard to the formation of chlorophyll.

247. Give in considerable detail the evidence which indicates that Mg acts as a carrier of phosphorus. What is the "magnesium injury" that is frequently obtained in water-culture experiments? How may it be overcome?

248. In what tissues of the plant has K been observed? In what parts of the cell has it been observed? In what form does K occur in plants? What does this indicate?

249. Cite examples to show the effect of the presence or absence of K upon the formation of carbohydrates, fats and oils, and proteins. What rôle does K apparently play in the plant?

250. How does the absence of K affect the mitotic division of cells? Why?

251. What plants show a marked response to the application of potassium? Name some that show only a slight response. Some that show a medium response to the application of this element. Name some qualities of fruits and grains that have been attributed to an optimum supply of potassium.

252. Which plants require the largest amount of sulphur? Which the least? How does the amount of sulphur needed by these different plants compare with their phosphorus needs?

253. In what three forms does S occur in plants? State the relative proportion of these three compounds in different plants.

254. In what form must S be presented to the plant? What evidence is there that S occurs in plant cells in excess of its needs? In what plant parts does S occur in the greatest amount?

255. What is the function of S in the plant? How does S affect the root systems of plants? How does it affect the formation of chlorophyll? The formation of nodules?

256. What will determine the response of plants to the application of S as a fertilizer to the soil? What plants are especially benefited by the application of sulphur? Name some plants that have been benefited by the application of S, stating the region in which the observations have been made.

257. In what parts of the plant cell has Fe been detected? In what form does it occur in the cell? What is chlorosis? How does the lack of Fe affect green plants?

258. What theories have been advanced for the function of Fe in the plant? What evidence is there that Fe acts as a catalyst in the formation of pyrrole-carbonic acid? What evidence is against it?

259. What amount of Fe is necessary for plant growth? How is the necessary amount determined? What is the relative value of ferric phosphate and ferrous sulphate as sources of iron in nutrient solutions for wheat? What sources of Fe have been tried in the nutrition of soybeans? Which has proved the most efficient? How is the availability of iron from different sources affected by the concentration of iron used? By the frequent renewal of the iron solution?

260. Cite an example to show the effect of changing environment upon the Fe requirement. Discuss the relationship between the H-ion concentration of the nutrient solution and the availability of iron.

261. Why are rice and pineapple plants affected with chlorosis when grown on certain calcareous and manganese soils? How has this lack of availability of Fe in the soil been overcome in the case of pineapples?

262. How frequently must these plants be sprayed with solutions of iron? With what concentrations? What facts indicate that iron is very immobile in the plant?

263. In what plants and in what plant parts does Si occur in the greatest abundance? What general benefits to plants have been attributed to silicon?

264. Discuss the observations that have been made in regard to the effect of silicon upon the phosphorus nutrition of oats and barley growing in the field.

265. How does the addition of silicon to nutrient solutions affect the growth of wheat, barley, and millet growing therein? In what form is silicon best supplied to nutrient solutions? How does the application of silicates to nutrient solutions affect the silicon content of the plant?

266. Name some plants and plant parts in which boron has been detected. Name some plants to which boron has been found to be an essential element. How does the absence of boron affect the conducting tissues, parenchyma, cambium cells, and other meristematic tissues.

267. How does its absence affect the nodule formation in *Vicia faba* in regard to size, number, and structure? What concentrations of boron are sufficient to supply this element? In what form may it be supplied?

268. Discuss the effect upon plant growth and production of various boron compounds which have been used as fertilizers.

269. Discuss the occurrence of manganese in plants and plant parts. How does the amount of Mn in plants compare with the amount of iron? Why had the needs of plants for Mn been overlooked? How does the absence of Mn affect plants?

270. How has the application of manganese salts as fertilizers to the soil and to nutrient solutions affected the growth and yield of plants?

271. What function does Mn perform in the plant? How might the presence of manganese cause chlorosis? How may chlorosis due to deficiency of Mn be overcome by spraying? Examples.

272. In what form does chlorine occur in plants? In what tissues? Review the results that have been obtained for various plants in the use of chlorides as fertilizers.

273. Why have the results in regard to the benefits of chlorine been so confusing? Give an example of a plant which is benefited by the application of NaCl.

274. How might chlorine influence enzyme action? How might it be of value in an unbalanced nutrient solution? Give example.

275. In what form and in what amounts has aluminum been observed in plants? Discuss the observations that have been made in regard to the influence of aluminum upon the growth and production of plants.

276. Discuss the influence of aluminum upon the soil in relation to the plant. What functions may aluminum serve in the plant cell? How does Al affect the color of the flowers of *Hydrangea hortensis*?

277. Name and discuss four functions that Na might serve in the plant. Make some statements in regard to the influence of barium, strontium, selenium, titanium, copper, arsenic, zinc, and iodine upon growth or development of plants.

278. Discuss the elemental requirements of plants at different stages of their growth under the following headings: (a) plants that have been studied, (b) methods used, and (c) the facts observed.

279. What proportion of the elements available in the seed are utilized by the seedling? How does the amount absorbed from the soil during the seedling stage compare with that obtained from the seed during the same time?

Bibliography

ACTON, E. H., 1889: The assimilation of carbon by green plants from certain organic compounds, *Proc. Roy. Soc.*, **47**: 150-175.

AGULHON, H., 1910: "Recherches sur la présence et le rôle du bore chez les végétaux," thèse, 163 pp., Paris.

- ALLISON, R. V., O. C. BRYAN, and J. H. HUNTER, 1927: The stimulation of plant response on the raw peat soils of the Florida Everglades through the use of copper sulphate and other chemicals, *Fla. Agr. Expt. Sta. Bull.* 190.
- AMES, J. W., and G. E. BOLTZ, 1912: Nitrogen and mineral constituents of the alfalfa plant, *Ohio Agr. Expt. Sta. Bull.* **247**: 755-773.
- , 1923: Sulfur experiments, *Ohio Sta. Mo. Bull.* **8**: 85-90.
- ANDRÉ, G., and E. DEMOUSSY, 1927: Sur la répartition du potassium et du sodium chez les végétaux, *Compt. Rend. Acad. Sci. Paris*, **184**: 1501-1503.
- ARNDT, C. H., 1922: The growth of field corn as affected by iron and aluminum salts, *Amer. Jour. Bot.*, **9**: 47-72.
- ASO, K., 1907: On the continuous application of manganous chloride in rice culture, II, *Coll. Agr. Imp. Univ. Tokyo Bull.*, **7**: 449-453.
- BAGULEY, ALLAN, 1912: The phosphate nutrition of plants, *Jour. Agr. Sci.*, **4**: 318-322.
- BARNETTE, R. M., 1921: The influence of volume upon the rate of change in the hydrogen-ion concentration of nutrient solutions in contact with plant roots and the effect of this change upon iron availability, *N. J. Sta. Rept.* **1921**: 345-347.
- and J. W. SHIVE, 1923: The influence of solution volume upon plant growth in relation to reaction change and iron availability in culture solutions, *Soil Sci.*, **15**: 413-425.
- BARRENSCHEEN, H. K., and W. ALBERS, 1928: Ueber die Rolle der Phosphorylierung im intermediären kohlenhydrat Stoffwechsel der Pflanzen, *Biochem. Zeits.*, **197**: 261-277.
- BAUER, F. C., 1923: The foraging power of plants for phosphate rock, *Jour. Amer. Soc. Agron.*, **15**: 99-110.
- BERTHELOT, M., and G. ANDRÉ, 1895: Sur la présence de l'alumine dans les plantes et sur sa répartition, *Compt. Rend. Acad. Sci. Paris*, **120**: 288-290.
- BERTRAND, G., 1897: Sur l'intervention du manganèse dans les oxydations provoquées par la laccase, *Compt. Rend. Acad. Sci. Paris*, **124**: 1032-1035.
- , 1897: Sur l'action oxydante des sels manganéux et sur la constitution chimique des oxydases, *Compt. Rend. Acad. Sci. Paris*, **124**: 1355-1358.
- , 1905: Sur l'emploi favorable du manganèse comme engrais, *Compt. Rend. Acad. Sci. Paris*, **141**: 1255-1257.
- , 1912: Sur le rôle des infiniment petits chimiques en agriculture, *Ann. Inst. Pasteur*, **26**: 852-867.
- and M. ROSENBLATT, 1921: Recherches sur la présence du manganèse dans la règne végétal, *Ann. Inst. Pasteur*, **35**: 815-819.
- and ———, 1921: Sur la présence générale du manganèse dans le règne végétal, *Compt. Rend. Acad. Sci. Paris*, **173**: 333-336.
- and ———, 1922: Recherches sur la variations de la teneur en manganèse des feuilles avec l'âge, *Ann. Inst. Pasteur*, **36**: 491-501.
- and ———, 1922: Sur la répartition du manganèse dans l'organisme des plantes supérieures, *Ann. Inst. Pasteur*, **36**: 230-232.
- BLAIR, A. W., and B. E. BROWN, 1921: The influence of fertilizers containing borax on the yield of potatoes and corn—season 1920, *Soil Sci.*, **11**: 369-385.
- BOEHM, J., 1875: Ueber den vegetabilischen Nährwerth der Kalksalze, *Sitzungsber. d. k. Akad. d. Wiss. Wien.*, **71**: 287-384.
- BOLIN, P., 1916: Sodium chloride as a fertilizer, *Chem. Abs.*, **10**: 2268-2269.
- BORROWNICKA-ORDZYWOLSKA, A., 1926: Effect of K and Na salts on metabolism in barley seedlings grown in the dark, *Bull. Internat. Acad. Polonaise Sci. et Lett. B. Sci. Nat.*, **1925**: 80-846.
- BRRANNON, J. M., 1923: Influence of certain sugars on higher plants, *Bot. Gaz.*, **75**: 370-390.

- BREAZEALE, J. F., 1906: The relation of sodium to potassium in soil and solution cultures, *Jour. Amer. Chem. Soc.*, **28**: 1013-1025.
- , 1916: Effect of sodium salts in water cultures on the absorption of plant food by wheat seedlings, *Jour. Agr. Res.*, **7**: 407-416.
- , 1923: Nutrition of plants considered as an electrical phenomenon, *Jour. Agr. Res.*, **24**: 41-54.
- BRENCHLEY, W. E., 1910: The influence of copper sulphate and manganese sulphate upon the growth of barley, *Ann. Bot.*, **24**: 571-583.
- , 1914: "Inorganic Plant Poisons and Stimulants," 110 pp., Cambridge University Press.
- , 1914: On the action of certain compounds of zinc, arsenic and boron on the growth of plants, *Ann. Bot.*, **28**: 283-302.
- , 1924: The effect of iodine on soils and plants, *Ann. App. Biol.*, **11**: 86-112.
- and H. G. THORNTON, 1925: The relation between the development, structure and functioning of the nodules on *Vicia faba* as influenced by the presence or absence of boron in the nutrient medium, *Proc. Roy. Soc., B*, **98**: 373-400.
- , E. J. MASKELL, and KATHERINE WARRINGTON, 1927: The inter-relation between silicon and other elements in plant nutrition, *Ann. App. Biol.*, **14**: 45-82.
- and KATHERINE WARRINGTON, 1927: The rôle of boron in the growth of plants, *Ann. Bot.*, **41**: 167-187.
- , 1929: The phosphate requirement of barley at different periods of growth, *Ann. Bot.*, **43**: 89-110.
- BROWN, B. E., 1922: Effect of borax in fertilizer on the growth and yield of potatoes, *U. S. Dept. Agr. Bull.* 998.
- BROWN, J. W., 1927: Chemical studies in the physiology of apples. VI, Correlation in the individual apple between the mineral constituents and other properties, *Ann. Bot.*, **41**: 127-139.
- BROWN, P. E., and G. A. MINGES, 1916: The effect of some-manganese salts on ammonification and nitrification, *Soil Sci.*, **2**: 67-87.
- BRUCE, O. C., 1925: The relation of sulfur to alfalfa production, *Jour. Agr. Res.*, **30**: 937-949.
- BRUCH, P., 1902: Zur physiologischen Bedeutung des Kalkiums in der Pflanze, *Landw. Jahrb.*, **30**: 127-144.
- BUCKNER, G. D., 1915: Translocation of mineral constituents of seeds and tubers of certain plants during growth, *Jour. Agr. Res.*, **5**: 449-459.
- , 1919: The translocation of the mineral constituents of the jack bean, *Jour. Amer. Chem. Soc.*, **41**: 282-287.
- , 1919: The composition of the ash of crab grass (*Digitaria sanguinalis*) as affected by the soil in which it is grown, *Jour. Amer. Chem. Soc.*, **41**: 1384-1385.
- BURD, J. S., 1919: Rate of absorption of soil constituents at successive stages of plant growth, *Jour. Agr. Res.*, **18**: 51-72.
- CHIZHOV, B. A., 1926: The accumulation of dry matter, ash and nitrogenous substances in cultivated plants under field conditions, *Jour. Exp. Landw. Südosten Russ.*, **3**: 40-75.
- COLLINGS, G. H., 1927: The influence of boron on the growth of the soybean plant, *Soil Sci.*, **23**: 83-107.
- CONNOR, S. D., 1920: The effect of zinc in soil tests with zinc and galvanized iron pots, *Jour. Amer. Soc. Agron.*, **12**: 61-65.
- and O. H. SEARS, 1922: Aluminum salts and acids at varying hydrogen-ion concentrations, in relation to plant growth in water cultures, *Soil Sci.*, **13**: 23-43.
- COOK, F. C., 1916: Boron: Its absorption and distribution in plants and its effect on growth, *Jour. Agr. Res.*, **5**: 877-891.

- COOK, F. C., and J. B. WILSON, 1917: Effect of three annual applications of boron on wheat, *Jour. Agr. Res.*, **10**: 591-599.
- and ———, 1918: Boron: Its effect on crops and its distribution in plants and soil in different parts of the United States, *Jour. Agr. Res.*, **13**: 451-471.
- CORSON, G. E., and A. L. BAKKE, 1917: The use of iron in nutrient solution for plants, *Proc. Iowa Acad. Sci.*, **24**: 477-482.
- COVILLE, F. V., 1923: The effect of aluminum sulphate on *Rhododendron* seedlings, *Amer. Hort. Soc. Bull.* **1**: 6.
- CROCKER, WILLIAM, 1923: The necessity of sulfur carriers in artificial fertilizers, *Jour. Amer. Soc. Agron.*, **15**: 129-141.
- DAVIDSON, JEHIEL, 1926: Removal of plant food in thinning corn, *Jour. Amer. Soc. Agron.*, **18**: 962-967.
- DAVIS, A. R., D. R. HOAGLAND, and C. B. LIPMAN, 1923: The feeding power of plants, *Science*, n.s., **57**: 299-301.
- DAY, D., 1928: Some effects on *Pisum sativum* of a lack of calcium in the nutrient solution, *Science*, n.s., **68**: 426.
- DEMOLON, M. A., 1912: Sur l'action fertilisante du soufre, *Compt. Rend. Acad. Sci. Paris*, **154**: 524-526.
- DEUBER, C. G., 1926: Can a pyrrole derivative be substituted for iron in the growth of plants? *Amer. Jour. Bot.*, **13**: 276-285.
- , 1926: Potassium ferrocyanide and ferric ferrocyanide as sources of iron for plants, *Soil Sci.*, **21**: 23-27.
- DICKSON, J. G., 1918: The value of certain nutritive elements in the development of the oats plant, *Amer. Jour. Bot.*, **5**: 301-325.
- DOWDING, E. S., 1925: The regional and seasonal distribution of potassium in plant tissues, *Ann. Bot.*, **39**: 459-474.
- DULEY, F. L., 1916: Relation of sulphur to soil productivity, *Jour. Amer. Soc. Agron.*, **8**: 154-160.
- and M. F. MILLER, 1921: The effect of a varying supply of nutrients upon the character and composition of the maize plant at different periods of growth, *Mo. Agr. Expt. Sta. Tech. Bull.* **42**.
- DYMOND, T. S., F. HUGHES, and C. W. C. JUPE, 1905: The influence of sulphates as manure upon the yield and the feeding value of crops, *Jour. Agr. Sci.*, **1**: 217-229.
- EATON, S. V., 1922: Sulphur content of soils and its relation to plant nutrition, *Bot. Gaz.*, **74**: 32-59.
- FLURI, M., 1909: Der Einfluss von Aluminumsalzen auf das Protoplasma, *Flora*, **99**: 81-126.
- FORBES, R. H., 1917: Certain effects under irrigation of copper compounds upon crops, *Univ. Cal. Agr. Sci.*, **1**: 395-494.
- GARNER, W. W., J. E. McMURTREY, C. W. BACON, and E. G. MOSS, 1923: Sand grown, a chlorosis of tobacco due to magnesium deficiency, and the relation of sulphates and chlorids of potassium to the disease, *Jour. Agr. Res.*, **23**: 27-41.
- GERICKE, W. F., 1922: "Magnesia injury" of plants grown in nutrient solutions, *Bot. Gaz.*, **74**: 110-113.
- , 1924: The beneficial effect to plant growth of the temporary depletion of some of the essential elements in the soil, *Science*, n.s., **59**: 321-324.
- , 1924: The beneficial effect to wheat growth due to depletion of available phosphorus in the cultural media, *Science*, n.s., **60**: 297-298.
- , 1925: Salt requirements of wheat at different growth phases, *Bot. Gaz.*, **80**: 410-425.
- , 1925: Effect of light on availability of iron to wheat plants in water cultures, *Bot. Gaz.*, **79**: 106-109.

- GILBERT, B. E., and L. J. HARDIN, 1927: The current mineral nutrient content of the plant solution as a possible means of chemical control of optimum fertilization, *Jour. Agr. Res.*, **35**: 185-192.
- , F. T. McLEAN, and W. L. ADAMS, 1927: The current mineral nutrient content of the plant solution as an index of metabolic limiting conditions, *Plant Physiol.*, **2**: 139-153.
- GILE, P. L., 1911: Relation of calcareous soils to pineapple chlorosis, *Porto Rico Agr. Expt. Sta. Bull.* 11.
- , and J. O. CARRERO, 1914: Assimilation of colloidal iron by rice, *Jour. Agr. Res.*, **3**: 205-210.
- and ———, 1915: Ash composition of upland rice at various stages of growth, *Jour. Agr. Res.*, **5**: 357-364.
- and ———, 1916: Assimilation of iron by rice from certain nutrient solutions, *Jour. Agr. Res.*, **7**: 503-528.
- and ———, 1916: Immobility of iron in the plant, *Jour. Agr. Res.*, **7**: 83-87.
- and ———, 1917: Absorption of nutrients as affected by the number of roots supplied with the nutrient, *Jour. Agr. Res.*, **9**: 73-95.
- and ———, 1920: Cause of lime-induced chlorosis and availability of iron in the soil, *Jour. Agr. Res.*, **20**: 33-63.
- and ———, 1921: Assimilation of nitrogen, phosphorus and potassium by corn when nutrient salts are confined to different roots, *Jour. Agr. Res.*, **21**: 545-575.
- and J. G. SMITH, 1925: Colloidal silica and the efficiency of phosphates, *Jour. Agr. Res.*, **31**: 247-260.
- GINSBURG, J. M., 1925: Composition and appearance of soybean plants grown in cultural solutions each lacking a different essential element, *Soil Sci.*, **20**: 1-15.
- GÖSSL, J. V., 1905: Ueber das Vorkommen des Mangans in der Pflanze und über seinen Einfluss auf Schimmelpilze, *Beih. bot. Centrbl.* I, **18**: 119-132.
- GRAFE, V., and L. PORTHEIM, 1906: Untersuchungen über die Rolle des Kalkes in der Pflanze, *Sitzungsber. d. k. Akad. d. Wiss. Wien.* **18**: 324.
- GREAVES, J. E., and D. H. NELSON, 1925: The iron, chlorine and sulfur contents of grains and the influence of irrigation water upon them, *Soil Sci.*, **19**: 325-330.
- GRIS, E., 1844: Nouvelles expériences sur l'action des composés ferrugineux solubles appliqués à la végétation et spécialement en traitement de la chlorose et de la débilité des plantes, *Compt. Rend. Acad. Sci. Paris*, **19**: 1118-1119.
- GROOM, P., 1896: Preliminary note on the relation between calcium and the conduction of carbohydrates in plants, *Ann. Bot.*, **10**: 91-96.
- HAAS, A. R. C., and H. S. REED, 1927: Significance of traces of elements not ordinarily added to culture solutions for growth of young orange trees, *Bot. Gaz.*, **83**: 77-85.
- , 1928: Water solubility of dry matter in relation to calcium nutrition of normal orange and lemon leaves, *Bot. Gaz.*, **85**: 334-341.
- HALL, A. D., and C. G. T. MORISON, 1905: On the function of silica in the nutrition of cereals, Part I, *Proc. Roy. Soc.*, B, **77**: 455-477.
- HALL, E. H., 1922: Sulfur and nitrogen content of alfalfa grown under various conditions, *Bot. Gaz.*, **73**: 401-412.
- HARRISON, G. T., and C. J. KING, 1925: Age of seedlings as a factor in the resistance of maize to sodium chloride, *Jour. Agr. Res.*, **31**: 633-641.
- HART, E. B., and W. H. PETERSON, 1911: Sulphur requirements of farm crops in relation to the soil and air supply, *Wis. Res. Bull.* 14.
- , and W. E. TOTTINGHAM, 1915: Relation of sulfur compounds to plant nutrition, *Jour. Agr. Res.*, **5**: 233-251.
- HARTER, L. L., 1908: The influence of a mixture of soluble salts principally sodium chloride upon the leaf structure and transpiration of wheat, oats, and barley, *U. S. Dept. Agr. Bur. Plant. Ind. Bull.* 134.

- HARTWELL, B. L., H. J. WHEELER, and F. R. PEMBER, 1907: The effect of the addition of sodium to deficient amounts of potassium upon the growth of plants in both water and sand cultures, *R. I. Agr. Expt. Sta. Rept.* **20**: 299-357.
- , and F. R. PEMBER, 1908: The relative toxicity of ferrous sulfate to barley and rye seedlings, *R. I. Agr. Expt. Sta. 21st Rept.* 286-294.
- , 1913: The percentage of total phosphorus in flat turnips as influenced by the amount available in soils, *R. I. Agr. Expt. Sta. Bull.* 154.
- and P. H. WESSELS, 1913: Effect of sodium manuring on the composition of plants, *R. I. Agr. Expt. Sta. Bull.* 153.
- , 1916: Starch congestion accompanying certain factors which retard plant growth, *R. I. Expt. Sta. Bull.* 165.
- , F. S. HAMMETT, and P. H. WESSELS, 1917: Reactions of the phosphorus of the thickened root of the flat turnip, *Jour. Agr. Res.*, **11**: 359-371.
- and F. R. PEMBER, 1918: The presence of aluminum as a reason for the difference in the effect of so-called acid soil on barley and rye, *Soil Sci.*, **6**: 259-281.
- and ———, 1918: Aluminum as a factor influencing the effect of acid soils on different crops, *Jour. Amer. Soc. Agron.*, **10**: 45-47.
- , 1927: Relative crop response to potash, *Jour. Amer. Soc. Agron.*, **19**: 479-482.
- and S. C. DAMON, 1927: The degree of response of different crops to various phosphorus carriers, *R. I. Agr. Expt. Sta. Bull.* 209.
- HASELHOFF, E., 1913: Über die Einwirkung von Borverbindungen auf das Pflanzenwachstum, *Landw. Versuchs-Stat.*, **79-80**: 399-429.
- HEADDEN, W. P., 1915: Occurrence of manganese in wheat, *Jour. Agr. Res.*, **5**: 349-355.
- , 1921: Titanium, barium, strontium, and lithium in certain plants, *Colo. Sta. Bull.* 267.
- HELLRIEGEL, H., and H. WILFARTH, 1898: Vegetationsversuche über den Kalibedarf einiger Pflanzen, *Arb. d. landw. Ges.*, **34**: 1-101.
- HENDRY, G. W., 1918: Relative effect of sodium chloride on the development of certain legumes, *Jour. Amer. Soc. Agron.*, **10**: 246-250.
- HIBBARD, R. P., and S. GERSHBERG, 1924: The salt requirements of Marquis wheat in water culture for the vegetative phase of development, *Mich. Agr. Expt. Sta. Tech. Bull.* 64.
- HOAGLAND, D. R., 1919: Relation of nutrient solution to composition and reaction of cell sap of barley, *Bot. Gaz.*, **68**: 297-304.
- , 1926: Some phases on the inorganic nutrition of plants in relation to the soil solution, *Sci. Agr.*, **6(5)**: 141-151, 177-189.
- HOBART, F. G., 1924: Calcium in plant metabolism, *Pharm. Jour.*, **113**: 500; *Bot. Abst.*, **14**: 569.
- HOFFER, G. N., and R. H. CARR, 1920: Iron accumulation and mobility in diseased corn stalks, *Phytopath.*, **10**: 56.
- and ———, 1923: Accumulation of aluminum and iron compounds in corn plants and its probable relation to root rots, *Jour. Agr. Res.*, **23**: 801-825.
- and J. F. TROST, 1923: The accumulation of iron and aluminum compounds in corn plants and its probable relation to root rots, *Jour. Amer. Soc. Agron.*, **15**: 323-331.
- HOPKINS, E. F., and F. B. WANN, 1926: Relation of hydrogen ion concentration to growth of *Chlorella* and of the availability of iron, *Bot. Gaz.*, **81**: 353-376.
- and ———, 1927: Iron requirement for *Chlorella*, *Bot. Gaz.*, **84**: 407-427.
- HORNBERGER, R., 1882: Chemische Untersuchungen über das Wachstum der Maispflanze, *Landw. Jahrb.*, **11**: 359-523.
- JANSSEN, GEORGE, and R. P. BARTHOLOMEW, 1929: The translocation of potassium in tomato plants and its relation to their carbohydrate and nitrogen distribution, *Jour. Agr. Res.*, **38**: 447-465.

- JAVILLIER, M., and S. IMAS, 1926: Le manganese dans le grain de blé et dans les produits de mouture, *Compt. Rend. Acad. Agr. France*, **12**: 721-727.
- and ———, 1926: Le zinc dans le grain de blé et dans les produits de mouture, *Compt. Rend. Acad. Agr. France*, **12**: 727-732.
- JENNINGS, D. S., 1919: The effect of certain colloidal substances on the growth of wheat seedlings, *Soil Sci.*, **7**: 201-215.
- JODIN, V., 1883: Du rôle de la silica dans la végétation du maïs, *Ann. Chim. et Phys.*, **30**: 485-494.
- JOHNSON, M. O., 1916: The spraying of yellow pineapple plants on manganese soils with iron sulphate solutions, *Hawaii Agr. Expt. Sta. Press Bull.* 51.
- , 1917: Manganese as a cause of the depression of the assimilation of iron by pineapple plants, *Jour. Ind. Eng. Chem.*, **9**: 47-49.
- , 1924: Manganese chlorosis of pineapples: its cause and control, *Hawaii Agr. Expt. Sta. Bull.*, 52.
- , 1928: Control of chlorosis of the pineapple and other plants, *Jour. Ind. Eng. Chem.*, **20**: 724-725.
- JOHNSTON, E. S., 1917: Seasonal variations in the growth rates of buckwheat plants under greenhouse conditions, *Johns Hopkins Univ. Circ.*, n.s., **3**: 211-217.
- and W. H. DORE, 1928: The relation of boron to the growth of the tomato plant, *Science*, n.s., **67**: 324-325.
- JONES, H. W., 1920: The distribution of inorganic iron in plants and animal tissues, *Biochem. Jour.*, **14**: 654-659.
- JONES, J. P., 1929: Deficiency of magnesium the cause of a chlorosis in corn, *Jour. Agr. Res.*, **39**: 873-892.
- JONES, J. S., and D. E. BULLIS, 1921: Manganese in commonly grown legumes, *Jour. Ind. Eng. Chem.*, **13**: 524-525.
- JONES, L. H., 1920: The effect of ammonium sulfate upon the availability of iron in nutrient solutions, *N. J. Sta. Rept.* **1920**: 405-409.
- and J. W. SHIVE, 1921: The influence of iron in the forms of ferric phosphate and ferrous sulphate upon the growth of wheat in a nutrient solution, *Soil Sci.*, **11**: 93-101.
- and ———, 1921: Effect of ammonium sulfate upon plants in nutrient solutions supplied with ferric phosphate and ferrous sulphate as sources of iron, *Jour. Agr. Res.*, **21**: 701-729.
- and ———, 1923: Influence of ammonium sulphate on plant growth in nutrient solutions and its effect on hydrogen-ion concentration and iron availability, *Ann. Bot.*, **37**: 355-377.
- JONES, R. L., and F. R. PEMBER, 1925: The fertilizer nutrients required by barley, wheat, and oats as shown by both soil and water cultures, *Soil Sci.*, **19**: 169-201.
- JONES, W. J., and H. A. HUSTON, 1914: Composition of maize at various stages of its growth, *Ind. Agr. Expt. Sta. Bull.* 175.
- JORDAN, W. H., 1913: Studies in plant nutrition, I, *N. Y. Agr. Expt. Sta. (Geneva) Bull.* **358**: 11-30.
- , 1913: Studies in plant nutrition, II, *N. Y. State Agr. Expt. Sta., (Geneva) Bull.* **360**: 53-77.
- JUNG, J., 1922: Über den Nachweis und die Verbreitung des Chlors im Pflanzenreiche, *Sitzungsber. d. k. Akad. d. Wiss. Wien.*, **129**: 297-340; *Abs. Jour. Chem. Soc.*, **121**, **122**: 1098.
- KATAYMA, T., 1906: On the degree of stimulating action of manganese and iron salts on barley, *Bull. Coll. Agr. Tokyo*, **7**: 91-93.
- KELLEY, W. P., 1912: The function and distribution of manganese in plants and soils, *Hawaii Agr. Expt. Sta. Bull.* 26.
- , 1914: The function of manganese in plants, *Bot. Gaz.*, **57**: 213-227.

- KNOP, W., 1861-1862: Quantitativ-analytische Arbeiten über den Ernährungsprocess der Pflanzen, *Landw. Versuchs-Stat.*, **3**: 295-324; **4**: 173-185.
- KNUDSON, L., 1915: Toxicity of galactose for certain of the higher plants, *Ann. Mo. Bot. Garden*, **2**: 659-666.
- , 1916: Influence of certain carbohydrates on green plants, *N. Y. Cornell Mem.* 9.
- , 1917: The toxicity of galactose and mannose for green plants and the antagonistic action of other sugars toward these, *Amer. Jour. Bot.*, **4**: 430-437.
- and E. W. LINDSTROM, 1919: Influence of sugars on the growth of albino plants, *Amer. Jour. Bot.*, **6**: 401-406.
- KOSTYTSCHEW, S., and P. ELIASBERG, 1920: Über die Form der Kaliumverbindungen lebenden Pflanzengewebe, *Zeits. f. Physiol. Chem.*, **111**: 228-235.
- KRATZMANN, E., 1913: Der microchemische Nachweis und die Verbreitung des Aluminiums im Pflanzenreich, *Sitzungsber. d. k. Akad. d. Wiss. Wien.*, **122**: 311-336.
- , 1914: The physiological action of the salts of aluminum upon plants, *Sitzungsber. d. k. Akad. d. Wiss. Wien.*, **123**: 211-233; *Abs. Expt. Sta. Rec.* **34**: 525.
- KREUZHAGE, C., and E. WOLFF, 1884: Bedeutung der Kieselsäure für die Entwicklung der Haferpflanze, *Landw. Versuchs-Stat.*, **30**: 161-197.
- LANHAM, W. B., 1927: Effect of potash fertilizer on carrying quality of tomatoes, *Tex. Agr. Expt. Sta. Bull.* 357.
- LARSON, H. W. E., 1928: The relation of the concentration of calcium ion required by alfalfa to the amount present in the soil solution, *Soil Sci.*, **25**: 399-408.
- LATSHAW, W. L., and E. C. MILLER, 1924: Elemental composition of the corn plant, *Jour. Agr. Res.*, **27**: 845-861.
- LAURENT, J., 1904: Recherches sur la nutrition carbonée des plantes vertes à l'aide de matières organiques, *Rév. Gén. Bot.*, **16**: 14-48, 66-80, 96-119, 120-128, 155-166, 188-202, 231-241.
- LEMMERMANN, OTTO, 1922: Die ertragssteigernde Wirkung der Kieselsäure bei unzureichender Phosphorsäuredüngung, *Sonderabdruck a. d. Zeits. Pflanzen Düng.*, 8 vo., 72 pp.
- , H. WIESSMANN, and K. SAMMETT, 1925: Untersuchungen über die Ursache der ertragssteigernden Wirkung der Kiesselsäure, *Zeits. Pflanz. Düng.*, A, **4**: 265-315.
- LEVINE, V. E., 1925: The effect of selenium compounds upon growth and germination in plants, *Amer. Jour. Bot.*, **12**: 82-91.
- LEYDHECKER, A., 1886: Ueber die physiologische Bedeutung des Chlor in der Buchweizenpflanze, *Landw. Versuchs-Stat.*, **8**: 177-187.
- LIPMAN, C. B., 1916: A critique of the hypothesis of the lime-magnesium ratio, *Plant World*, **19**: 83-105, 119-135.
- , A. R. DAVIS, and E. S. WEST, 1926: The tolerance of plants for NaCl, *Soil Sci.*, **22**: 303-322.
- , 1928: The chemical elements indispensable to plants, *Sci. Monthly*, **26**: 289-294.
- LOEW, O., 1891: Ueber die physiologische Function der Phosphorsäure, *Biol. Centrbl.*, **11**: 269-281.
- and S. SAWA, 1902: On the action of manganese compounds on plants, *Bull. Coll. Agr. Tokyo*, **5**: 161-172.
- , 1903: The physiological role of mineral nutrients in plants, *U. S. Dept. Agr. Bull.* 45.
- and S. HONDA, 1904: Über den Einfluss des Mangans auf Waldbaume, *Bull. Coll. Agr. Tokyo*, **6**: 125-130.
- LOMANITZ, S., 1923: A preliminary study of the effects of sodium chloride upon alfalfa grown in solution cultures, *Soil Sci.*, **16**: 183-195.

- LOMANITZ, S., 1924: The influence of sodium chloride upon alfalfa grown in solution cultures, *Soil Sci.*, **18**: 353-371.
- LUKASZEWICZ, J., 1926: Über das Vorkommen von Kalium in manchen pflanzlichen Gebilden, *extr. du Bull. de l'Académie Polonaise des Sci. et Lettres*, **1926**: 559-576.
- LUTMAN, B. F., and N. L. WALBRIDGE, 1929: The role of magnesium in the aging of plants, *Vt. Agr. Expt. Sta. Bull.* 296.
- LYON, C. J., 1923: The effect of phosphates on respiration, *Jour. Gen. Physiol.*, **6**: 299-306.
- , 1927: The rôle of phosphate in plant respiration, *Amer. Jour. Bot.*, **14**: 274-284.
- MAC GILLIVRAY, J. H., 1926: The importance of phosphorus in the production of seed and non-seed portions of a tomato fruit, *Proc. Amer. Soc. Hort. Sci.*, **22**: 374-379.
- , 1927: Effect of phosphorus on the composition of the tomato plant, *Jour. Agr. Res.*, **34**: 97-129.
- MAGISTAD, O. C., 1925: The aluminum content of the soil solution and its relation to soil reaction and plant growth, *Soil Sci.*, **20**: 181-227.
- MAMELI, E., 1918: Sulla influenza del magnesio sopra la formazione della chlorofilla, *Univ. di Pavia. Atti Ist. Bot.*, **15**: 151-205.
- MANN, C. E. T., 1924: The physiology of the nutrition of fruit trees. I, Some effects of calcium and potassium starvation, *Univ. Bristol Agr. Hort. Res. Sta. Ann. Rept.* **1924**: 36-45.
- MAQUENNE, L., and E. DEMOUSSY, 1920: Sur l'absorption du calcium par les racines des plantes et ses propriétés antitoxiques vis-à-vis du cuivre, *Compt. Rend. Acad. Sci. Paris*, **170**: 420-425.
- and ———, 1920: Sur la distribution et la migration du cuivre dans les tissus des plantes vertes, *Compt. Rend. Acad. Sci. Paris*, **170**: 87-93.
- and ———, 1920: Un cas d'action favorable du cuivre sur la végétation, *Compt. Rend. Acad. Sci. Paris*, **170**: 1542-1545.
- MARSH, R. S., 1922: Preliminary studies on the sulfur content of the tomato, *Amer. Soc. Hort. Sci. Proc.* **19**: 83-84.
- , 1923: Seasonal variation of sulphur content in certain tissues of the apple tree, *Bot. Gaz.*, **75**: 400-413.
- MARSH, R. P., and J. W. SHIVE, 1925: Adjustment of iron supply to requirements of soybean in solution culture, *Bot. Gaz.*, **79**: 1-28.
- MAZÉ, P., and A. PERRIER, 1904: Recherches sur l'assimilation de quelques substances ternaires par les végétaux à chlorophylle, *Ann. Inst. Pasteur*, **18**: 721-747.
- and M. LEMOIGNE, 1912: Recherches sur la chlorose végétale provoquée par le carbonate de calcium, *Compt. Rend. Acad. Sci. Paris*, **155**: 435-437.
- , M. RUOT, and M. LEMOIGNE, 1913: Chlorose calcaire des plantes vertes. Rôle des excréments des racines dans l'absorption du fer des sols calcaires, *Compt. Rend. Acad. Sci. Paris*, **157**: 495-498.
- , 1914: Influences respectives des éléments de la solution minérale sur le développement du maïs, *Ann. Inst. Pasteur*, **28**: 21-68.
- , 1915: Détermination des éléments minéraux rares nécessaires au développement du maïs, *Compt. Rend. Acad. Sci. Paris*, **160**: 211-214.
- , 1919: Recherche d'une solution purement minérale capable d'assurer l'évolution complète du maïs cultivé à l'abri des microbes, *Ann. Inst. Pasteur*, **33**: 139-173.
- MCCALL, A. G., and P. E. RICHARDS, 1918: Mineral food requirements of the wheat plant at different stages of its development, *Jour. Amer. Soc. Agron.*, **10**: 127-134.
- and J. R. HAAG, 1921: The relation of the hydrogen-ion concentration of nutrient solutions to growth and chlorosis of wheat plants, *Soil Sci.*, **12**: 69-77.

- McCALLUM, A. B., 1905: On the distribution of potassium in animal and vegetable cells, *Jour. Physiol.*, **32**: 95-128.
- McCOOL, M. M., 1913: The toxicity of manganese and the antidotal relations between this and various other cations with respect to green plants, *Cornell Agr. Expt. Sta. Mem.* 2.
- McDONNELL, C. C., and R. C. ROARK, 1917: Occurrence of manganese in insect flowers and insect flower stems, *Jour. Agr. Res.*, **11**: 77-83.
- McGEORGE, W. T., 1923: The chlorosis of pineapple plants grown on manganiferous soils, *Soil Sci.*, **16**: 269-275.
- McHARGUE, J. S., 1919: The effect of manganese on the growth of wheat: A source of manganese for agricultural purposes, *Jour. Ind. Eng. Chem.*, **11**: 332-335.
- , 1919: Effect of certain compounds of barium and strontium on the growth of plants, *Jour. Agr. Res.*, **16**: 183-195.
- , 1921: The occurrence and distribution of manganese in plants, *Ky. Sta. Rept.* **1921**: 36-37; **1922**: 35-36.
- , 1922: The role of manganese in plants, *Jour. Amer. Chem. Soc.*, **44**: 1592-1598.
- , 1923: Effect of different concentrations of manganese sulphate on the growth of plants in acid and neutral soils and the necessity of manganese as a plant nutrient, *Jour. Agr. Res.*, **24**: 781-795.
- , 1923: Common earthenware jars a source of error in pot experiments, *Jour. Agr. Res.*, **26**: 231-233.
- , 1923: Iron and manganese content of certain species of seeds, *Jour. Agr. Res.*, **23**: 395-401.
- , 1925: The occurrence of copper, manganese, zinc, nickel and cobalt in soils, plants and their possible function as vital factors, *Jour. Agr. Res.*, **30**: 193-196.
- , 1925: The significance of the occurrence of copper, manganese and zinc in forage crops and foods, *Jour. Amer. Soc. Agron.*, **17**: 368-372.
- , 1926: Mineral constituents of the cotton plant, *Jour. Amer. Soc. Agron.*, **18**: 1076-1083.
- , 1927: Significance of the occurrence of manganese, copper, zinc, nickel and cobalt in Kentucky bluegrass, *Jour. Ind. Eng. Chem.*, **19**: 274-276.
- McKIBBEN, R. R., 1928: The effect of sulphur on soils and on crop yields, *Md. Agr. Expt. Sta. Bull.* 296.
- McLEAN, F. T., and B. E. GILBERT, 1925: Manganese as a cure for chlorosis of spinach, *Science*, n.s., **61**: 636.
- , 1927: Feeding plants manganese through the stomata, *Science*, n.s., **66**: 487-489.
- and B. E. GILBERT, 1927: The relative aluminum tolerance of crop plants, *Soil Sci.*, **24**: 163-177.
- and ———, 1928: Aluminum toxicity, *Plant Physiol.*, **3**: 293-302.
- McMURTREY, J. E., 1929: The effect of boron deficiency on the growth of tobacco plants in aerated and unaerated solutions, *Jour. Agr. Res.*, **38**: 371-380.
- MEURER, R., 1909: Ueber die regulationische Aufnahme anorganischer Stoffe durch die Wurzeln von *Beta vulgaris* and *Daucus Carota*, *Jahrb. f. wiss. Bot.*, **46**: 503-568.
- MEYERS, C. N., and C. VOEGTLIN, 1914: Soluble aluminum compounds, *U. S. Health Rept.*, **29**: 1625-1629.
- MICHELIS, H., and P. DEHEEN, 1906: Note au sujet de l'action stimulante du manganese sur la germination, *Bull. de l'Acad. Roy. Belg.*, **5**: 288-289.
- MILLER, H. G., 1919: The relation of sulfates to plant growth and composition, *Jour. Agr. Res.*, **17**: 87-103.
- , 1921: Further studies on relation of sulfates to plant growth and composition, *Jour. Agr. Res.*, **22**: 101-111.

- MIRASOL, J. J., 1920: Aluminum as a factor in soil acidity, *Soil Sci.*, **10**: 153-219.
- MIYAKE, K., 1916: The toxic action of soluble aluminum salts upon the growth of the rice plant, *Jour. Biol. Chem.*, **25**: 23-28.
- MOLISCH, H., 1892: "Die Pflanze in ihren Beziehungen zum Eisen. Eine physiologische Studie," 8 vo., 119 pp., G. Fischer, Jena; *Bot. Centrbl.*, **60**: 370.
- , 1897: Der Einfluss des Bodens auf die Blütenfarbe der *Hortensien*, *Bot. Zeitung*, **55**: 49-61.
- , 1902: Ueber vorübergehende Rothfärbung der Chlorophyllkörner in Laubblättern, *Ber. d. d. bot. Ges.*, **20**: 442-448.
- MOLLIARD, M., 1907: Action morphogénique de quelques substances organiques sur les végétaux supérieurs, *Rév. Gén. Bot.*, **19**: 241-291, 329-349, 357-391.
- MORSE, F. W., 1927: Relation between water and potash in plant production, *Jour. Agr. Res.*, **35**: 939-946.
- NAGAOKA, M., 1903, 1904: On the stimulating action of manganese upon rice, *Bull. Col. Agr. Tokyo*, **5**: 467-472; **6**: 135-136.
- , 1906: On the stimulating action of manganese upon rice, III, *Bull. Coll. Agr. Tokyo*, **7**: 77-81.
- NAKAMURA, M., 1904: Can lithium and caesium salts exert any stimulant action on Phanerogams? *Bull. Coll. Agr. Tokyo*, **6**: 153-160; *Bot. Centrbl.*, **95**: 669.
- , 1904: Can salts of zinc, cobalt and nickel in high dilution exert a stimulating action on agricultural plants? *Bull. Coll. Agr. Tokyo*, **6**: 147-153; *Bot. Centrbl.*, **96**: 109.
- NELLER, J. R., and W. J. MORSE, 1921: Effects upon the growth of potatoes, corn and beans resulting from the addition of borax to the fertilizer used, *Soil Sci.*, **12**: 79-132.
- NEMEC, A., and V. KAS., 1923: Studien über die physiologische Bedeutung des Titans im Pflanzenorganismus, *Biochem. Zeits.*, **140**: 583-590.
- NEWTON, J. D., 1928: The selective absorption of inorganic elements by various crop plants, *Soil Sci.*, **26**: 85-91.
- NICOLAS, G., 1921: Contribution à l'étude du mécanisme de l'action fertilisante du soufre, *Compt. Rend. Acad. Sci. Paris*, **172**: 85-87.
- NOBBE, F., and T. SIEGERT, 1862, 1863: Über das Chlor als spezifischer Nährstoff der Buchweizenpflanze, *Landw. Versuchs-Stat.*, **4**: 318-340; **5**: 116-136.
- and ———, 1864: Ueber das Chlor als Pflanzennährstoff, *Landw. Versuchs-Stat.*, **6**: 108-120.
- , 1865: Ueber die physiologische Function des Chlor in der Pflanze, *Landw. Versuchs-Stat.*, **7**: 371-386.
- , J. SCHRÖDER, and R. ERDMANN, 1871: Ueber die organische Leistung des Kalium in der Pflanze, *Landw. Versuchs-Stat.*, **13**: 321-423.
- NOLL, CHARLES F., 1923: The effects of phosphate on early growth and maturity, *Jour. Amer. Soc. Agron.*, **15**: 87-99.
- ODDO, B., and G. POLACCI, 1920: Influenza, del nucleo pirrolico sulla formazione della chlorofilla, *Gaz. Chim. Italiana*, **50**: 54-70.
- OLSON, G. A., and J. L. ST. JOHN, 1921: An investigation of sulfur as a plant food, *Wash. Sta. Bull.* 165.
- ORR, J. B., F. C. KELLY, and G. L. STUART, 1928: The effect of iodine manuring on the iodine content of plants, *Jour. Agr. Sci.*, **18**: 159-161.
- OSTERHOUT, W. J. V., 1912: Plants which require sodium, *Bot. Gaz.*, **54**: 532-536.
- , 1916: Specific action of barium, *Amer. Jour. Bot.*, **3**: 481-483.
- PALLADIN, V. I., 1927: "Plant Physiology," Eng. trans. Livingston, p. 86, P. Blakiston's Son & Co., Philadelphia.
- PARKER, F. W., and E. TRUOG, 1920: The relation between the calcium and the nitrogen content of plants and the function of calcium, *Soil Sci.*, **10**: 49-56.

- PARKER, F. W., and W. H. PIERRE, 1928: The relation between the concentration of mineral elements in a culture medium and the absorption and utilization of these elements by plants, *Soil Sci.*, **25**: 337-343.
- PEMBER, F. R., 1917: Studies by means of both pot and solution culture of the phosphorus and potassium requirements of the barley plant during its different periods of growth, *R. I. Agr. Expt. Sta. Bull.* 169.
- , and F. T. McLEAN, 1925: Economical use of nitrogen, phosphorus and potassium by barley, oats, and wheat in solution cultures, *R. I. Agr. Expt. Sta. Bull.* 199.
- PETERSON, W. H., 1914: Forms of sulphur in plant materials and their variation with the soil supply, *Jour. Amer. Chem. Soc.*, **36**: 1290-1300.
- and C. B. PETERSON, 1926: The water-soluble content of calcium and phosphorus in cabbage, *Jour. Agr. Res.*, **33**: 695-699.
- and C. W. LINDOW, 1928: Variations in the manganese content of certain vegetables, *Soil Sci.*, **26**: 149-153.
- PFEFFER, W., 1900: "Physiology of plants," Eng. trans. Ewarts, Vol. I, pp. 416, 435; Vol. II, pp. 33, 55, Clarendon Press.
- PFEIFFER, T., E. FRANK, O. LEMMERMANN, and H. SCHILLBACH, 1898: Über die Wirkung verschiedener Kalisalze auf die Zusammensetzung und den Ertrag der Kartoffeln, *Landw. Versuchs-Stat.*, **49**: 349-385.
- , A. RIPPEL, and C. PFOTENHAUER, 1919: Über den Verlauf der Nährstoffaufnahme und Stofferzeugung bei der Gerstenpflanze, *Führung landw. Zeitg.*, **68**: 81-101.
- , ———, and ———, 1920: The action of sodium in the presence of potassium as a plant nutrient, *Jour. Landw.*, **68**: 255-284; *Abst. Expt. Sta. Rec.* **45**: 624.
- PIERRE, I., 1866: La silice et la verse des blés, *Compt. Rend. Acad. Sci. Paris*, **63**: 374-377.
- PITZ, WALTER, 1916: Effect of elemental sulfur and of calcium sulfate on certain of the higher and lower forms of plant life, *Jour. Agr. Res.*, **5**: 771-781.
- POLLACCI, G., and B. ODDO, 1915: Influenza, del nucleo pirrolico sulla formazione della chlorofilla. Nota preliminare, *Roy. Acad. Lincei*, **24**: 37-39.
- POWERS, W. L., 1923: Progress of sulfur investigations with Oregon soils, *Jour. Amer. Soc. Agron.*, **15**: 158-160.
- PRIANISCHNIKOW, D. N., 1905: Results of vegetation experiments in the years 1901-1903, *Ann. Inst. Agron. Moscow*, **11**: 155-219; *Expt. Sta. Rec.* **18**: 320-321.
- , 1911: Über den Einfluss von Kohlensäuren Kalk auf die Wirkung von verschiedenen Phosphaten, *Landw. Versuchs-Stat.*, **75**: 357-376.
- , 1923: Zur Frage über die Bedeutung des Calciums für die Pflanzen, *Ber. d. d. bot. Ges.*, **41**: 138-144.
- RAVIN, PAUL, 1913: Nutrition carbonée des plantes à l'aide des acides organique libres et combinés, *Ann. Sci. Nat. Bot. ser. IX*, **18**: 289-446.
- REED, H. S., 1907: The value of certain nutritive elements to the plant cell, *Ann. Bot.*, **21**: 501-543.
- and A. R. C. HAAS, 1923: The pseudo-antagonism of sodium and calcium in dilute solutions, *Jour. Agr. Res.*, **24**: 753-759.
- and ———, 1923: Studies on the effects of sodium, potassium, and calcium on young orange trees, *Calif. Agr. Expt. Sta. Tech. Paper* **11**: 1-23.
- , and ———, 1924: Nutrient and toxic effects of certain ions on citrus and walnut trees with especial reference to the concentration and P_H of the medium, *Calif. Agr. Expt. Sta. Tech. Paper* **17**: 1-75.
- and ———, 1924: Iron supply in a nutrient medium, *Bot. Gaz.*, **77**: 290-300.
- REIMER, F. C., and H. V. TARTAR, 1919: Sulphur as a fertilizer for alfalfa in southern Oregon, *Ore. Agr. Expt. Sta. Bull.* 163.

- RICHARDSON, W. D., 1920: The ash of dune plants, *Science*, n.s., **51**: 546-551.
- RIPPEL, A., 1923: Über die durch Mangan verursachte Eisen-chlorose bei grünen Pflanzen, *Biochem. Zeits.*, **140**: 315-323.
- ROACH, B. M. B., 1926: On the relation of certain soil algae to some soluble carbon compounds, *Ann. Bot.*, **40**: 149-203.
- , 1927: On the carbon nutrition of some algae isolated from soil, *Ann. Bot.*, **41**: 509-517.
- ROBBINS, W. J., 1918: Direct assimilation of organic carbon by *Ceratodon purpureus*, *Bot. Gaz.*, **65**: 543-551.
- , 1922: Cultivation of excised root tips and stem tips under sterile conditions, *Bot. Gaz.*, **73**: 376-390.
- , and W. E. MANEVAL, 1924: Effect of light on growth of excised root tips under sterile conditions, *Bot. Gaz.*, **78**: 424-432.
- ROBBINS, W. R., 1927: Nutrient requirements of the sweet potato plant when grown in sand culture and effect of various nutrient salt proportions on the composition of the roots, *Ann. Rept. N. J. Agr. Expt. Sta.*, **48**: 178-179.
- ROBINSON, W. O., L. A. STEINKOENIG, and C. F. MILLER, 1917: The relation of some of the rarer elements in soils and plants, *U. S. Dept. Agr. Bull.* 600.
- RUDOLFS, W., 1919: Influence of sodium chloride upon the physiological changes of living trees, *Soil Sci.*, **8**: 397-427.
- , 1927: Influence of salt on the growth rate of asparagus, *Bot. Gaz.*, **83**: 94-98.
- RUPRECHT, R. W., 1915: Toxic effect of iron and aluminum salts on clover seedlings, *Mass. Agr. Expt. Sta. Bull.*, **161**: 125-129.
- RUSSELL, E. J., 1915: "Soil Conditions and Plant Growth," p. 35, Longmans Green and Co., New York.
- SACHS, J. VON, 1887: "Lectures on the Physiology of Plants," p. 288, Clarendon Press.
- SALTER, R. M., and J. W. AMES, 1928: Plant composition as a guide to the availability of soil nutrients, *Jour. Amer. Soc. Agron.*, **20**: 808-837.
- SAMUEL, G., and C. S. PIPER, 1929: Manganese as an essential element for plant growth, *Ann. App. Biol.*, **16**: 493-523.
- SCHIMPER, A. F. W., 1888: Ueber Kalkoxalatbildung in den Laubblättern, *Bot. Zeitung*, **46**: 65-69, 81-89, 97-107, 113-123, 129-139, 145-153.
- , 1890: Zur Frage der Assimilation der Mineralsalze durch die grüne Pflanze, *Flora*, **73**: 207-278.
- SCHMIDT, E. W., 1915: The effects of chlorides on plant growth, *unpub. thesis, Univ. Wis.*, quoted by Tottingham, 1919.
- SCHOLLENBERGER, C. J., 1922: Silica and silicates in relation to plant growth and composition, *Soil Sci.*, **14**: 347-363.
- SCHREINER, O., 1923: Organic phosphorus in soils, *Jour. Amer. Soc. Agron.*, **15**: 117-125.
- , and P. R. DAWSON, 1927: Manganese deficiency in soils and fertilizers, *Jour. Ind. Eng. Chem.*, **19**: 400-404.
- SCHULZE, B., 1913: Beitrag zur Frage der Düngung mit Natronsalzen, *Landw. Versuchs-Stat.*, **79-80**: 431-448.
- SCHUSTER, G. L., 1927: Potash in relation to quality of crop, *Jour. Amer. Soc. Agron.*, **19**: 506-517.
- SHEDD, O. M., 1913: The sulphur content of some typical Kentucky soils, *Ky. Agr. Expt. Sta. Bull.* 174.
- , 1914: The relation of sulphur to soil fertility, *Ky. Agr. Expt. Sta. Bull.* 188.
- , 1917: Effect of sulphur on different crops and soils, *Jour. Agr. Res.*, **11**: 91-105.
- SHIVE, J. W., and W. H. MARTIN, 1918: A comparative study of salt requirements for young and for mature buckwheat plants in solution cultures, *Jour. Agr. Res.*, **14**: 151-176.

- SHIVE, J. W., 1918: A comparison of salt requirements for young and for mature buckwheat plants in water cultures and sand cultures, *Amer. Jour. Bot.*, **5**: 186-191.
- , 1918: A comparative study of salt requirements for young and mature buckwheat plants in sand cultures, *Soil Sci.*, **6**: 1-32.
- SHULL, C. A., 1920: Sulphur as a fertilizer, *Science*, n.s., **52**: 376-378.
- SHULOV, I. S., 1909: Various smaller experiments with fertilizers and soils, *Ann. Inst. Agron. Moscow*, **15**: 116-125; *Expt. Sta. Rec.* **22**: 223-224 (1910).
- SIDORIN, M. I., 1914: On the assimilation of iron by plants, *Rec. Trav. Lab. Agron. Moscow, Selsk. Khoz. Inst.*, **10**: 241-257; *Expt. Sta. Rec.* **36**: 633.
- SKINNER, J. J., and F. R. REID, 1921: Nutrient requirements of clover and wheat in solution cultures, *Soil Sci.*, **12**: 287-301.
- , and F. E. ALLISON, 1923: Influence of fertilizers containing borax on the growth and fruiting of cotton, *Jour. Agr. Res.*, **23**: 433-445.
- , B. E. BROWN, and F. R. REID, 1923: The effect of boron on the growth and yield of crops, *U. S. Dept. Agr. Bull.* 1126.
- SMITH, T. O., and O. BUTLER, 1921: Relation of potassium to growth in plants, *Ann. Bot.*, **35**: 189-227.
- SOMMER, A. L., 1926: Studies concerning the essential nature of aluminum and silicon for plant growth, *Univ. Cal. Publ. Agr. Sci.*, **5**: 57-81.
- , and C. B. LIPMAN, 1926: Evidence of the indispensable nature of zinc and boron for higher green plants, *Plant Physiol.*, **1**: 231-249.
- , 1927: The search for elements essential in only small amounts for plant growth, *Science*, n.s., **66**: 482-484.
- , 1928: Further evidence of the essential nature of zinc for the growth of higher green plants, *Plant Physiol.*, **3**: 217-223.
- , and H. SOROKIN, 1928: Effect of the absence of boron and of some other essential elements on the cell and tissue structure of the root tips of *Pisum sativum*, *Plant Physiol.*, **3**: 237-261.
- SOROKIN, H., and A. L. SOMMER, 1929: Changes in the cells and tissues of root tips induced by the absence of calcium, *Amer. Jour. Bot.*, **16**: 23-40.
- STEWART, JOHN, 1922: Some relations of arsenic to plant growth I and II, *Soil Sci.*, **14**: 111-127.
- STEWART, R., 1920: Sulphur in relation to soil fertility, *Ill. Agr. Expt. Sta. Bull.* 227.
- STOCKLASA, J., and J. PITRA, 1901: Ueber die Einwirkung der Kalisalze auf die Entwicklung der Gerste, *Zeits. f. landw. Versuch. im Oesterr.*, p. 567.
- , 1908: Beiträge zur Kenntniss der physiologischen Funktion des Kalis in Pflanzenorganismus, *Zeits. f. landw. Versuch.*, **11**: 52-61.
- , 1911: Catalytic fertilizers for sugar beets, *Bl. Zuckerrühenbau*, **18**: 193-197; *Expt. Sta. Rec.* **26**: 225.
- , and E. SENFT, 1912: Ist das Kalium an dem Auf- und Abbau der Kohlenhydrate bei höheren Pflanzen beteiligt? *Zeits. f. landw. Verwesen Österr.*, **15**: 711-736.
- , 1916: Ist das Kaliumion an der Eiweissynthese in der Pflanzenzelle beteiligt? *Biochem. Zeits.*, **73**: 107-160.
- , 1918: Über den Einfluss des Aluminiumions auf die Keimung des Samens und die Entwicklung der Pflanzen, *Biochem. Zeits.*, **91**: 137-223.
- , 1918: Über die Verbreitung des Aluminiumions in der Pflanzenwelt, *Biochem. Zeits.*, **88**: 292-322.
- , 1920: Der Mechanismus der physiologischen Wirkung der Radiumemanation und der Radioaktivität des Kaliums auf die biochemischen Vorgänge bei den Wachstumsprocess der Pflanzen, II, *Biochem. Zeits.*, **108**: 140-172.
- , 1920: Bedeutung der Radioaktivität des Kaliums bei der Photosynthese, *Biochem. Zeits.*, **108**: 173-184.

- STOCKLASA, J., 1920: Ueber die Radioaktivität des Kaliums und ihre Bedeutung in der chlorophyllösen und chlorophyllhaltigen Zelle, I, *Biochem. Zeits.*, **108**: 109-139.
- , 1922: Ueber die Resorption des Aluminumions durch das Wurzelsystem der Pflanzen, *Biochem. Zeits.*, **128**: 35-47.
- , 1922: "Über die Verbreitung des Aluminums in der Natur und seine Bedeutung beim Bau- und Betriebsstoffwechsel der Pflanzen," 8 vo., x + 500 pp., Fischer, Jena.
- SUZUKI, V., 1900: Can strontium and barium replace calcium in phanerogams? *Bull. Coll. Agr. Tokyo*, **4**: 69-77.
- and K. Aso, 1903: On the stimulating action of iodine and fluorine compounds on agricultural plants, *Bull. Coll. Agr. Tokyo*, **5**: 4; *Bot. Centrbl.*, **93**: 143.
- , 1919: The translocation of the mineral constituents of the jack bean, *Jour. Amer. Chem. Soc.*, **41**: 282-287.
- SWANBACK, T. R., 1927: The effect of boric acid on the growth of tobacco plants in nutrient solutions, *Plant Physiol.*, **2**: 475-486.
- SWANSON, C. O., and R. W. MILLER, 1917: The sulfur content of some typical Kansas soils and the loss of sulphur due to cultivation, *Soil Sci.*, **3**: 139-148.
- SZÜCS, J., 1913: Über einige charakteristische Wirkungen des Aluminiums auf das Protoplasma, *Jahrb. f. wiss. Bot.*, **52**: 269-332.
- THATCHER, R. W., and G. A. OLSON, 1912: Experiments in fertilizing alfalfa, *Wash. Agr. Expt. Sta. Pop. Bull.* 49.
- TOTTINGHAM, W. E., 1915: The role of chlorine in plant nutrition, *Science*, n.s., **42**: 68.
- and A. J. BECK, 1916: Antagonism between manganese and iron in the growth of wheat, *Plant World*, **19**: 359-370.
- , 1917: On the rôle of chlorine to plant growth, *Johns Hopkins Univ. Circ.*, n.s., **3**: 217-221.
- , 1918: The sulphur requirement of the red clover plant, *Jour. Biol. Chem.*, **36**: 429-438.
- , 1919: A preliminary study of the influence of chlorides on the growth of certain agricultural plants, *Jour. Amer. Soc. Agron.*, **11**: 1-33.
- and E. J. RANKIN, 1923: The availability of iron in nutrient solutions for wheat, *Amer. Jour. Bot.*, **10**: 203-211.
- TRELEASE, S. F., 1917: A study of salt proportions in a nutrient solution containing chlorid as related to the growth of young wheat plants, *Johns Hopkins Univ. Circ.*, n.s., **3**: 222-225.
- , 1920: The relation of salt proportions and of concentrations to the growth of young wheat plants in nutrient solutions containing a chlorid, *Philippine Jour. Sci.*, **17**: 527-603.
- TRUE, R. H., and R. B. HARVEY, 1918: The absorption of calcium salts by squash seedlings, *Brooklyn Bot. Gard. Mem.* **1**: 502-512.
- , O. F. Black, and J. W. KELLY, 1919: Ash absorption by spinach from concentrated soil solutions, *Jour. Agr. Res.*, **16**: 15-27.
- , 1921: The function of calcium in the nutrition of seedlings, *Jour. Amer. Soc. Agron.*, **13**: 91-108.
- , 1922: The significance of calcium for higher green plants. *Science*, n.s., **55**: 1-6.
- TRUOG, E., 1913: Availability of phosphates to various crops, *Wis. Agr. Expt. Sta. Bull.* 240.
- , 1916: The utilization of phosphates by agricultural crops, including a new theory regarding the feeding power of plants. *Wis. Agr. Expt. Sta. Res. Bull.* 41.
- , 1922: The feeding power of plants, *Science*, n.s., **56**: 294-298.

- VOELCKER, J. A., 1915: The influence of boron compounds on wheat and barley, *Jour. Roy. Agr. Soc. England*, **76**: 347-351.
- WARBURG, O., 1925: Iron, the oxygen-carrier of respiration-ferment, *Science*, n.s., **61**: 575-582.
- WASHINGTON, KATHERINE, 1923: The effect of boric acid and borax on the broad bean and certain other plants, *Ann. Bot.*, **37**: 629-672.
- , 1926: The changes induced in the anatomical structure of *Vicia faba* by the absence of boron from the nutrient solution, *Ann. Bot.*, **40**: 27-42.
- WESTER, D. H., 1921: Über den Mangangehalt von (holländischen) Samen, *Biochem. Zeits.*, **118**: 158-163.
- WEEVERS, T., 1911: Untersuchungen über die Lokalisation und Funktion des Kaliums in der Pflanze, *Rec. Trav. Bot. Neerland.*, **8**: 289-332; *Expt. Sta. Rec.* **26**: 823.
- , 1917: Die physiologische Bedeutung des Kaliums in den Pflanzen, *Biochem. Zeits.*, **78**: 354-357.
- WEISZMANN, II., 1923: Ueber den Einfluss des Kaliums auf die Entwicklung der Pflanzen und ihren morphologischen und anatomischen Bau, bei besonderer Berücksichtigung der landwirtschaftlichen Kulturpflanzen, *Zeits. f. Pflanzenzüchtung*, **2**: 1-79.
- WHEELER, H. J., and B. L. HARTWELL, 1902: Conditions determining the poisonous action of chlorides, *R. I. Agr. Expt. Sta. 15th Ann. Rept.* 287-304.
- and ———, 1904: Magnesium as a manure, *R. I. Expt. Sta. 17th Ann. Rept.* **1904**: 221-260.
- , 1905: Plant peculiarities as shown by the influence of sodium salts, *R. I. Agr. Expt. Sta. Bull.* 104.
- and G. E. ADAMS, 1905: Concerning the agricultural value of sodium salts, *R. I. Agr. Expt. Sta. Bull.* 106.
- WHERRY, E. T., and R. BUCHANAN, 1926: Composition of the ash of Spanish moss, *Ecology*, **7**: 303-307.
- WILCOX, E. V., and W. P. KELLEY, 1912: The effect of manganese on pineapple plants and the ripening of the pineapple fruit, *Hawaii Agr. Expt. Sta. Bull.* 28.
- WILFARTH, II., H. RÖMER, and G. WIMMER, 1906: Über die Nahrstoffaufnahme der Pflanzen in verschiedenen Zeiten ihres Wachstums, *Landw. Versuchs.-Stat.*, **63**: 1-70.
- WILKINS, LOUIS K., 1917: The high calcium content of some cucurbit vines, *N. J. Agr. Expt. Sta. Bull.* 310.
- WILLIS, L. G., and J. O. CARRERO, 1921: Rice investigations, *Porto Rico Sta. Rept.* **1921**: 8-9.
- WILLSTÄTTER, R., 1906: Zur Kenntniss der Zusammensetzung des Chlorophylls, *Ann. Chem.*, **350**: 48-82.
- and M. BENZ, 1908: Untersuchungen über Chlorophyll. VI, Ueber Krystallisiertes Chlorophyll, *Annalen*, **358**: 267-287.
- and A. STOLL, 1913: "Untersuchung über Chlorophyllen, Methoden, und Ergebnisse," Julius Springer, Berlin.
- WOLFF, J., 1913: De l'influence du fer dans le développement de l'orge et sur la spécificité de son action, *Compt. Rend. Acad. Sci. Paris*, **157**: 1022-1024.
- WOODARD, JOHN, 1922: Sulphur as a factor in soil fertility, *Bot. Gaz.*, **73**: 81-110.
- WRANGELL, M. VON, 1922: Laws governing the phosphoric acid nutrition of plants, *Landw. Jahrb.*, **57**: 1-78; *Expt. Sta. Rec.* **48**: 426, 1923.
- , 1927: Das Jod als Pflanzennährstoff, *Natur. Wiss.*, **15**: 70-73.
- WYATT, F. A., 1916: Influence of calcium and magnesium compounds on plant growth, *Jour. Agr. Res.*, **6**: 589-621.
- YAMANO, Y., 1905: Can aluminum salts enhance plant growth? *Bull. Coll. Agr. Tokyo*, **6**: 429-432.

CHAPTER VII

THE LOSS OF WATER FROM PLANTS

I. GENERAL NEED OF WATER BY PLANTS

It is common knowledge that water is absolutely essential to animal life and that if it is withheld for a relatively short period from animal organisms death ensues. Water is just as essential to plant life, and if a plant is deprived of water it will perish, perhaps not so quickly as an animal but just as surely nevertheless. Let us now consider the relationship of water to the life of the plant in order to ascertain the need of a continuous water supply by a plant which is normally carrying on its various functions.

A. THE PROTOPLASM

A large amount of water is necessary to the proper functioning of the protoplasm, so that it has been said that "All living matter lives in water." The younger, the more vigorous, the more impressionable, the more active, and the more rapidly growing protoplasm is the more water it contains. As an example of the large amount of water in the actively growing regions of plants, the tip of a young stalk of corn or the base of the growing leaves of the same plant may be cited. These regions of the corn plant are composed of 92 to 93 per cent of water, most of which is directly associated with the protoplasm which completely fills the cells of these portions of the plant. When we consider that the flesh of a ripe watermelon contains no higher percentage of water than the growing regions just mentioned, we can realize the relatively large amount of water that is required in the protoplasm of plant cells to bring about normal growth and development.

If the normal amount of water in the protoplasm is removed, it becomes less and less active until a point is reached where death ensues. The case of seeds is a good example of what takes place when water is withdrawn from the protoplasm. The protoplasm in the cells that make up the seed is living, but so much water has been withdrawn from it in the process of curing that it is very inactive or dormant. If water, however, is supplied to the seed, the protoplasm obtains the amount necessary to carry on its functions actively, and the seed begins to grow.

B. VACUOLE OF CELLS

The relationship of the vacuole to the plant cell has been discussed in Chap. I. A certain amount of water in the vacuole is necessary to main-

tain the normal condition of turgor essential for the growth of the cells and for the erectness of the plant. The amount of water in the various parts of plants will depend upon the type of plant and the conditions under which it is examined. The following list shows the amount of water in the leaves of plants grown at Manhattan, Kans. These leaves were fully developed and in full vegetative vigor. The samples were collected at 10 a.m.

Kind of leaf	Percentage of water	Kind of leaf	Percentage of water
Cabbage.....	86	Pumpkin.....	80
Tomato.....	84	Corn.....	77
Cowpea.....	82	Apple.....	60

C. FOR CONTINUAL TRANSLOCATION OF MATERIALS FROM ONE PART OF PLANT TO ANOTHER

As far as is known, all foods and materials translocated in a plant move from cell to cell in a watery solution.

D. FOR CHEMICAL COMBINATION

Many of the various organic compounds found in plants are formed by the combination of water with certain materials that enter the plant from the soil and the air.

The water needed by any plant during its growing season for the purposes that have just been mentioned amounts to very little. Thus, for example, a normal corn plant that reached a height of 10 to 12 ft. and produced a good yield of grain had, including the stem, leaves, grain, cob, and roots, a moist weight of 2,707 g. at the height of its full vegetative growth when the vegetative parts were all intact and the grain was in the late dough stage and was well glazed and dented. The total weight of dry matter of this plant was 835 g. The water content of the plant was thus 1,872 g. This means that the water in this plant, which was needed for the vacuoles of the cells, for the protoplasm, and for the translocation of materials, did not exceed this amount. The amount of water necessary for chemical combination in this case would not amount to over 250 g. even if we consider that all the hydrogen and oxygen in the dry matter was obtained by the plant from water. According to these figures, a corn plant would thus need during its entire growing season only 2,122 g. (a little over 2 l. or approximately $2\frac{1}{5}$ qt.) of water to supply it with a sufficient amount for the four uses that have just been mentioned. It is well known, however, that a single corn plant requires during its growing season a much greater quantity of water than that which has just been stated. A single corn plant during the growing season of 1924 at Man-

hattan, Kans., removed from the soil 54 gal. or 1 $\frac{4}{5}$ bbl. of water. This is approximately ninety-eight times more than needed for the cell vacuoles, translocation, protoplasm, and chemical combination. What, then, is the need of such a large supply of water for a plant during its growing season?




FIG. 14.—Graphs showing the transpiration rates of different plants under the same conditions and the distribution of their water loss during the day. The evaporation from a porous cup atmometer for the corresponding periods is also shown. The squares at the bottom of the figure represent the extent of the leaf surface of each plant expressed in square centimeters. A, the transpiration rates of Pride of Saline corn and Dwarf Yellow milo. B, the transpiration rates of Pride of Saline corn, Dwarf Yellow milo, Red Amber sorgho, and Freed's sorgho.

E. REPLACEMENT

A supply of water in the soil is thus needed by a plant at all times during its growing season to replace that which is being lost continuously from its stem and leaves by transpiration and by guttation.

II. THE EVAPORATION OF WATER FROM PLANTS. TRANSPIRATION

Transpiration is the loss of water in the form of vapor from the stem and leaves of the living plant. Practically all the water that is lost from plants escapes in this manner. The amount of water that evaporates from the stem, however, is small, the greater portion of transpirational loss being from the leaves.

A. TRANSPIRATION DURING THE DAY AND NIGHT

Transpiration occurs during both day and night, but by far the greater amount of water is lost in this process during the daylight hours. The percentage of water lost during the night as compared with the total lost during the day will depend upon various factors that will be mentioned later. Any statements, therefore, that are made in this regard must be general and relative only to the conditions prevailing at the time the observations were made.

The general distribution of the water loss during a 24-hr. period can be shown by an experiment selected from the work of Miller and Coffman (1918), as shown in Fig. 14 and in the following table:

HOURLY RATE OF TRANSPIRATION OF PRIDE OF SALINE CORN AND DWARF YELLOW MILO DURING A 24-HR. PERIOD AT GARDEN CITY, KANS., JULY 26 AND 27, 1916

Period	Evaporation per hour, porous cup atnometer, cc.	Corn, Pride of Saline		Milo, Dwarf Yellow	
		Rate of transpiration per hour, grams			
		Per plant	Per square meter of leaf surface	Per plant	Per square meter of leaf surface
July 26:					
6-8 a.m.....	3.9	121	93	35	126
8-10 a.m.....	6.7	212	163	79	281
10-12 noon.....	8.2	291	223	99	350
12-2 p.m.....	9.5	329	253	122	432
2-4 p.m.....	9.5	259	198	117	413
4-6 p.m.....	9.1	236	181	58	206
6-8 p.m.....	6.7	164	126	27	94
8-10 p.m.....	3.9	11	8	3	12
10-12 mid.....	3.4	25	19	13	44
July 27:					
12-2 a.m.....	1.6	25	19	5	19
2-4 a.m.....	0.8	18	14	2	6
4-6 a.m.....	0.9	31	24	5	19
6-8 a.m.....	2.7	71	55	21	75

They found that from 94 to 96 per cent of the water transpired was lost during the daylight hours under the climatic conditions prevailing at Garden City, Kans. Briggs and Shantz (1916) observed at Akron, Colo., that the transpirational loss from various crop plants from sunset to sunrise amounted to only 3 to 6 per cent of the total transpiration for the 24-hr. period, according to the following table:

Plant	Percentage of total transpiration	
	Daylight	Darkness
Wheat.....	96	4
Oats.....	94	6
Rye.....	95	5
Sorghums.....	95	5
Alfalfa.....	97	3
Pigweed (<i>Amaranthus</i>) ...	97	3

Under the climatic conditions that prevail in the Great Plains area of the United States less water is transpired by plants during the forenoon than during the afternoon. The percentage of water transpired during the forenoon hours is, as a rule, from 40 to 50 per cent of the total water transpired during the daylight hours. As a general rule, the maximum rate of transpiration is reached somewhere between 11 a.m. and 3 p.m. Miller and Coffman (1918) found in 30 experiments with corn that the maximum rate of transpiration occurred eighteen times between 11 a.m. and 1 p.m. and twelve times between 1 p.m. and 3 p.m. In the case of 52 observations of various varieties of the sorghums, the maximum rate of transpiration occurred twenty-eight times between 11 a.m. and 1 p.m. and twenty-four times between 1 p.m. and 3 p.m.

B. AMOUNT OF WATER LOST

The total amount of water that is evaporated from plants during a growing season will depend primarily upon the prevailing climatic conditions, but the following data will serve as an example of the relatively large amount that escapes from the plant by transpiration. The data here presented were obtained by the author at Manhattan, Kans., in 1924 to 1925. The plants were grown in sealed containers and the soil was kept in good moisture tilth by the daily addition to it of the water that had been removed by the plants during that time (Fig. 21).

As shown in the table on page 313, a single Kansas Sunflower corn plant during its growing season in 1924 lost 54 gal. of water. Let us consider how much water would thus be evaporated by an acre of corn plants during the growing season if the soil were supplied with sufficient moisture for normal growth and development.

Plant	Length of season	Total water lost during the season per plant, gallons
Cowpea.....	May 19 to Sept. 2, 1924	13
Potato, Irish cobbler, 1 hill, 2 to 3 plants.....	April 18 to July 30, 1924	25
Tomato, Louisiana Pink, pruned to 1 stem.....	May 19 to Sept. 2, 1924	34
Corn, Kansas Sunflower.....	May 5 to Sept. 8, 1924	54
Winter wheat, Kanred, 1 plant 15 stalks.....	Oct. 15 1924 to June 28, 1925	25
Sunflower, Russian.....	May 26 to Aug. 23, 1925	123
Sunflower, wild.....	May 24 to Aug. 23, 1925	130
Giant ragweed (<i>Ambrosia trifida</i>).....	May 24 to Aug. 23, 1925	140

If the corn were in 44-in. rows, the plants 2 ft. apart in the row, and 1 plant per hill, we should have about 6,000 plants per acre if a perfect stand were obtained. The total amount of water that would be evaporated from the leaves and sheaths of an acre of corn during the growing season under these conditions would be 324,000 gal. or 1,296 tons of water. Since 1 in. of rainfall per acre weighs 113.25 tons, this is equivalent to approximately 11 acre in. of rainfall. A single corn plant that has reached its full leaf development has been observed to transpire as much as 32 qt. of water during a single week under the summer conditions of the Great Plains. This means an average of approximately $4\frac{1}{2}$ qt. per plant per day. When the body weight of the plant is considered, it is found that the plant during each day of the 7-day period which has just been mentioned evaporated a quantity of water equal to twice its body weight.

The question naturally arises as to what is the cause of such a large loss of water from plants. In order to understand this, we must consider the general structure of the leaves, and it is to that topic that we shall now devote our attention.

C. FACTORS THAT INFLUENCE THE RATE OF TRANSPIRATION

1. Leaf Structure.—It is not the intention here to enter into any detailed discussion of the anatomy of the leaf but only to mention in a general way those characteristics of its structure that are conducive to the loss of water by evaporation. The structure of leaves varies greatly for different plants, as can be seen by comparing the cross-sections of the leaves of corn and alfalfa as shown in Fig. 15 *A* and *B*. Certain general characteristics, however, are common to all leaves in relation to water loss, and it is these facts that we wish here to consider.

The leaf of most angiosperms is a relatively broad, flat, thin organ with a large amount of surface in proportion to its mass. A better conception of the large amount of surface exposed by leaves may be had by citing one or two examples. The leaf and sheath surface of an ordinary variety of corn plant grown under the conditions of the corn belt amounts to from 30 to 35 sq. ft. or is from four to six times as extensive as the surface of the soil in which the plants are growing. A wild sunflower plant growing under favorable conditions may have as much as 40 to 50 sq. ft. of leaf surface.




FIG. 15.—Cross-section of leaves. *A*, alfalfa leaf. *B*, corn leaf. *a*, air space. *ue*, upper epidermis. *lc*, lower epidermis. *gc*, green cells. *vb*, fibrovascular bundle. *bs*, bundle sheath. *e*, ordinary epidermal cell. *c*, cuticle. *sc*, subsidiary cells. *g*, guard cells. *s*, stoma.

The ordinary leaf is composed, for the most part, of thin-walled parenchyma tissue through which numerous finely divided vascular bundles permeate and end free so that as many as 6,000 of these minute veins may end in a square centimeter of leaf. The entire leaf is covered by a layer of cells, generally only one cell in thickness, called the "epidermis." The outer wall of the epidermis is generally somewhat thickened and is cutinized and, as described in Chap. I, is impervious to moisture and gases in varying degrees. The epidermis of the leaf, however, is not completely intact but is perforated with numerous minute

pores. Each of these pores is called a "stoma" (plural, stomata). The mesophyll or parenchyma tissue of the leaf is very loosely constructed so that there are many air spaces between the cells. In fact, in most leaves there is scarcely a mesophyll cell which does not come in contact with an intercellular space. In a typical dorsiventral leaf (Fig. 15 A) the intercellular spaces are more numerous and larger in the lower than in the upper portion of the leaf. These intercellular spaces join with one another and finally unite with one of the relatively large air spaces that is directly beneath each pore or stoma (Fig. 15 A and B). These intercellular spaces form from 3 to 70 per cent of the total volume of the leaf. It is seen that the thin-walled cells of the mesophyll are in direct contact with the fibrovascular bundles, which, in turn, are in direct connection with the water supply of the roots and the soil. These cells, on the other hand, have a portion of their moist surface exposed to the intercellular air cavities which are connected either directly or indirectly with the atmosphere through the stomata of the leaf. The leaf structure thus is such that conditions are very favorable for the loss of water by evaporation. A moist porous cell wall surface is exposed to the air on at least one side and is in contact on the other side under favorable conditions with a continuous water supply. The facts that have just been mentioned in regard to the leaves applies also in a more limited sense to the young stems of plants. Although the amount of water lost from the young stem parts is often considerable, the amount is negligible in comparison with the amount lost from the leaves. The large loss of water from plants by transpiration is thus due primarily to the structure of the leaf. The structure of the leaf is apparently an adaptation for the absorption of gases that it needs (Bessey, 1898) or for the excretion of those that arise in its metabolism, but it is poorly adapted for the retention of water, so that the continuous loss of water from it is a constant menace to the life of the plant.

It should be mentioned here that different plants exposed to the same environmental conditions do not have the same rate of transpiration. This may be illustrated, for example, by the experimental data obtained by Miller (1925) at the Kansas Agricultural Experiment Station in observations of corn, milo, pumpkin, cowpea, and soybean plants grown under field conditions, as shown in the table on page 316.

Blaydes (1928) collected data by means of the cobalt chloride paper method on the transpiration rate of 123 species of plants growing under a wide range of conditions. The average standard water loss for all the species on which data were collected was 1.150 g. of water vapor per hour per 100 cm.² of leaf surface. On this same basis the greatest water loss was from *Plantago major*, *Polygonum amphibium*, and *Iris versicolor* with a rate of 3.802, 3.661, 3.452 g. per square centimeter per hour, respectively. The lowest transpiration rates were 0.074, 0.076, and 0.085

RELATIVE TRANSPIRATION OF CORN, MILO, PUMPKIN, COWPEAS AND SOYBEANS UNDER THE SAME ENVIRONMENTAL CONDITIONS IN THE FIELD AT MANHATTAN, KANS.

Date	Corn, Kansas Sunflower		Milo, Dwarf Yellow		Pumpkin, Cheese		Cowpeas, New Era		Soybeans, Midwest		Evapo- ration
	Per plant	Per square meter of leaf surface	Per plant	Per square meter of leaf surface	Per plant	Per square meter of leaf surface	Per plant	Per square meter of leaf surface	Per plant	Per square meter of leaf surface	Porous cup at- mometer, cc.
July 7-8:											
9 a.m.-4 p.m. . .	222	146	142	167	126	177	54	129	68	136	35.4
4 p.m.-9 a.m. . .	22	14	10	12	13	18	7	16	9	18	23.1
July 8-9:											
9 a.m.-4 p.m. . .	240	158	178	210	168	234	65	156	81	161	41.5
4 p.m.-9 a.m. . .	18	12	5	6	9	13	7	17	6	12	17.5
July 9-10:											
9 a.m.-4 p.m. . .	227	150	183	216	165	230	78	188	90	179	30.0
4 p.m.-9 a.m. . .	19	12	9	10	12	17	6	13	6	12	14.0

g. per 100 cm.² per hour, respectively, for *Juglans nigra*, *Bromus inermis*, and *Silphium perfoliatum*. He also observed that the maximum rate of water loss occurred at different times of the day in different species.

Weaver and Mogensen (1919) noted that the autumnal transpiration losses from conifers were as high per unit of surface or even higher than those from broad leaves. The winter losses from conifers were found to be only $\frac{1}{251}$ to $\frac{1}{55}$ as great as those in the autumn. The winter losses from conifers were scarcely greater than those from defoliated stems of broad-leaved trees.

A striking example of the different effects of the changes in the environmental conditions upon the rate of transpiration of different plants is offered by the observations of Sayre (1919), who found that an increase in temperature of 23°F. and a decrease in humidity of 35 per cent increased the transpiration rate of the mullein plant only twenty-five times as compared to forty times for the tobacco plant. The two main factors which may contribute to these differences in response to the environment are the differences in anatomical structure and the specific ability of the plant to bring about changes in itself. Of the anatomical differences which apparently contribute to variation in the transpiration rate of different plants, the structure of the leaves is probably the most important. On account of their variation in structure, the leaves differ in their response to solar energy. Their absorption coefficients may not be the same, while the dissipation of the absorbed energy may be very

different for different plants. We shall now discuss the more important structural differences in the anatomy of the leaves and the influence of the structural differences upon the rate of transpiration.

a. The Stomata.—The stomata or stomates (singular, stoma or stomate) are minute more or less elongated openings through the epidermis of plants. They occur in the epidermis of any part of the plant (Anderson, 1897; Jivanna, 1923) except the root but are found in the greatest numbers in the leaves. A stoma or stomate is simply an intercellular opening between two specialized epidermal cells which are termed “guard cells.” (Figure 16A, B, and C.) In the most simple development, the stoma is formed by the division of a young epidermal cell which has become ellipsoidal in outline into two daughter cells. The dissolution of the middle lamella of the walls separating these two cells then occurs and the stoma or intercellular passage is formed by the splitting of these two walls. The stoma may be opened and closed in varying degrees by changes in the size and shape of the guard cells. These changes are caused by the variation of the turgor of the cells in connection with the structure of their cell walls. In some cases, the epidermal cells which border on the guard cells are also different from the ordinary epidermal cells and are called “subsidiary” or “accessory cells.” The guard cells are richer in protoplasmic material, contain chloroplasts, are different in form, and have a higher concentration of the cell sap than the ordinary




FIG. 16.—Stomata. Surface view of the epidermis of A, alfalfa leaf; B, leaf of cowpea; and C, leaf of corn. s, stoma. gc, guard cells. sc, subsidiary cells. e, ordinary epidermal cells.

epidermal cells. The term "stoma" is also used to denote collectively the intercellular opening, the guard cells, and the subsidiary cells. In that case, the orifice is known as the "stomatal pore." In this text, however, the term stoma will be used to denote only the pore through the epidermis, while the guard cells and accessory or subsidiary cells will be collectively termed the "stomatal apparatus." The structure of the stomatal apparatus is markedly different in the different groups of plants. These peculiarities in structure may vary slightly under different conditions, but their general characteristics are constant. The peculiar type of guard cells and subsidiary cells of the grains and grasses is a good example of this fact (Schwendener, 1889). Rehfoos (1917) considered that the structures of the stomatal apparatus are so constant within a given group of plants that they are of first importance in indicating phylogeny and relationships.

1. *Number.*—The number of stomata per unit of leaf surface is, within certain limits, a characteristic of the particular species or variety of plant under consideration. There seems to be evidence that environmental conditions do influence the number of stomata per unit of surface, although the information in that regard is rather meager and contradictory. Mariana (1903) studied the effect of the humidity of the air upon the development of the stomata on the cotyledonary leaves of buckwheat, beet, white lupine, crimson clover, and other plants and concluded that there were fewer stomata produced per unit of leaf area in a relatively moist than in a relatively dry atmosphere. He considered that humidity favors the development of the superficial areas of the leaves but that it does not increase the absolute number of the stomata. Duggar (1911) grew plants of wheat and corn in sand cultures containing, respectively, 38, 30, 20, 15, and 11 per cent of moisture and observed that the greatest number of stomata per unit area was found on the leaves of the plants growing in the sand with the highest moisture content, while the smallest number was on the leaves of plants grown in the sand with the lowest percentage of water. Kiesselbach (1916), however, in experiments with Hogue Yellow Dent and Pride of the North varieties of corn did not find any striking response in the relative number of stomata to variations in either soil moisture or soil fertility. Weiss (1866) also concluded from extensive observations that the conditions under which plants are grown do not influence either the size or the number of their stomata. Salisbury (1927) in an extensive study of the stomatal frequency of the woodland flora of England concluded that the indications are that stomatal frequency is mainly dependent on the humidity of the environment, dry exposed conditions being associated with high frequencies and humid conditions with low frequencies. He noted also that the total pore space per unit area of leaf surface is greater in dry than in moist conditions, despite the larger size attained by the stomata in a humid environment. He makes the very important statement in this regard that there

is a high positive correlation coefficient between the number of stomata and the number of epidermal cells per unit of area. The difference in frequency of stomata in wet and dry soil, small leaves as compared with large leaves, and different parts of the same leaf is due to differences in growth. Such differences in frequency are thus due to the spacing of the stomata and not to the differences in the number of stomata developed.

Salisbury proposed the stomatal index $I = \frac{S}{E + S} \times 100$, where S equals the number of stomata per unit of area and E the number of ordinary epidermal cells in the same unit area. The stomatal index thus aims at expressing the percentage proportion of the ultimate divisions of the dermatogen of the leaf which have been converted into stomata. This infers that under a given set of conditions a species tends to form a definite proportion of stomatal initials. Salisbury considers that there is some evidence that high humidity tends to reduce the proportion of stomata formed, and aquatics would seem to have low stomatal indices. Variations in the stomatal index appear to be due to internal factors, of which nutritional conditions are perhaps the most important.

Miller (1928) recorded the number of stomata per unit area for one variety each of corn, milo, and kafir during nine successive growing seasons. A summary of the data is given in the following table:

NUMBER OF STOMATA ON THE LEAVES OF PRIDE OF SALINE CORN, DWARF YELLOW MILO, AND BLACKHULL KAFIR DURING NINE GROWING SEASONS

Year	Number of stomata, thousands per square inch of leaf surface											
	Corn, Pride of Saline				Milo, Dwarf Yellow				Kafir, Blackhull			
	Upper	Lower	Total	Ratio lower to upper	Upper	Lower	Total	Ratio lower to upper	Upper	Lower	Total	Ratio lower to upper
Garden City, Kans.:												
1914.....	43	55	98	1.28	66	97	163	1.42	48	103	151	2.14
1915.....	40	50	90	1.25	64	76	140	1.17	44	89	133	2.02
1916.....	49	53	102	1.08	67	90	157	1.34				
1917.....	40	51	91	1.27	53	74	127	1.49	45	82	127	1.82
Manhattan, Kans.:												
1918.....	60	73	133	1.21	81	100	181	1.23	58	103	161	1.94
1919.....	39	51	90	1.51	59	85	144	1.27	55	91	146	1.65
1920.....	36	49	85	1.36	56	91	147	1.66	46	106	152	2.30
1922.....	43	56	99	1.30	61	87	148	1.42	51	98	149	1.92
1923.....	34	48	82	1.41	58	89	147	1.53	55	100	155	1.81
Average.....	42.6	54.0	96.6	1.27	62.8	87.6	150.4	1.40	50.2	96.5	146.7	1.92

The number was found to vary greatly from year to year. Thus for corn the number ranged from 82,000 in 1923 to 133,000 per square inch in 1918; for milo leaves from 140,000 in 1915 to 181,000 per square inch in 1918; and for kafir from 127,000 in 1917 to 161,000 per square inch in 1918. The number for each of the three plants was higher in 1918 than in any other of the growing seasons, but the variations in numbers during the other growing seasons were not consistent. Thus, for example, in 1923 the total number of stomata on corn leaves was only 82,000 per square inch, the lowest for corn of any of the nine seasons, while under the same conditions the leaves of kafir showed next to the highest number of stomata for that plant during the nine seasons.

The relative number of stomata on the lower and upper surfaces also showed marked fluctuations. For example, in the case of corn the ratio of the number on the lower to that on the upper surface varied from 1.08 in 1916 to as much as 1.40 in 1923, and on kafir from 1.6 in 1919 to 2.3 in 1920. The indications, from these observations, are that different plants may vary in their response to certain conditions as far as the number of stomata per unit of area is concerned.

Miller (1928) also observed the number of stomata of various other agricultural plants growing in the field during from two to nine growing seasons. The results of the observations, together with a summary of those just given, are shown in the table that follows:

SUMMARY OF THE OBSERVATIONS ON THE NUMBER OF STOMATA ON THE LEAVES OF CROP PLANTS

Plant	Number of years observed	Average number stomata, thousands per square inch of leaf surface			
		Upper	Lower	Total	Ratio lower to upper
Corn:					
Pride of Saline.....	9	43	54	97	1.255
Sherrod White Dent.....	4	48	60	108	1.250
Freed White Dent.....	6	44	57	101	1.295
Kansas Sunflower.....	5	49	59	108	1.204
Reid Yellow Dent.....	5	43	58	101	1.348
Sorghums:					
Sudan Grass.....	6	58	79	137	1.362
Feterita.....	6	71	98	169	1.380
Milo, Dwarf Yellow.....	9	63	88	151	1.396
Milo, White.....	4	65	86	151	1.322
Kafir, Blackhull.....	8	50	97	147	1.940
Kafir, Dawn.....	5	57	94	151	1.649
Kafir, Pink.....	4	53	100	153	1.886
Sorgo, Freed.....	5	65	98	163	1.507

SUMMARY OF THE OBSERVATIONS ON THE NUMBER OF STOMATA ON THE LEAVES OF CROP PLANTS.—(Continued)

Plant	Number of years observed	Average number stomata, thousands per square inch of leaf surface			
		Upper	Lower	Total	Ratio lower to upper
<i>Sorghums: (Continued)</i>					
Sorgo, Red Amber.....	5	51	86	137	1.686
Sorgo, Kansas Orange.....	4	53	86	139	1.622
Sorgo, Sumac.....	4	47	75	122	1.595
Broom Corn, Acme Dwarf.....	3	53	79	132	1.490
<i>Wheat:</i>					
Kanred.....	3	39	28	67	0.718
Blackhull.....	3	41	24	65	0.585
Triplet.....	2	40	28	68	0.700
Improved Turkey.....	2	45	28	73	0.622
Fulcaster.....	2	37	26	63	0.702
Harvest Queen.....	2	35	25	60	0.714
<i>Rye:</i>					
Abruzzi.....	3	33	30	63	0.909
Kansas.....	3	33	31	64	0.939
Rosen.....	3	32	28	60	0.875
<i>Barley:</i>					
Manchurian.....	3	37	39	76	1.054
Mariout.....	3	32	34	66	1.062
Kansas.....	3	36	35	71	0.972
<i>Oats:</i>					
Burt.....	3	25	27	52	1.080
Fulghum.....	3	27	28	55	1.036
Kherson.....	2	27	28	55	1.036
Texas.....	2	25	29	54	1.160
Alfalfa, common.....	3	109	89	198	0.816
Clover, white sweet.....	3	163	105	268	0.644
Clover, red.....	3	138	197	335	1.427
Cowpeas, New Era.....	3	74	157	231	2.121
Soybeans, Medium Yellow.....	2	95	107	202	1.126
Potato (several varieties).....	3	33	104	137	3.151
Cabbage (several varieties).....	3	91	146	237	1.604
Watermelon, Knobs Gem.....	3	127	234	361	1.842
Cucumber, Long Green.....	3	143	285	428	1.993
Squash, Hubbards.....	2	185	202	387	1.091
Tomato (several varieties).....	3	62	131	193	2.112
Pumpkin, Cheese.....	2	135	182	317	1.348
<i>Apple:</i>					
Delicious.....	2	0	190	190	
Grimes Golden.....	2	0	266	266	
Jonathan.....	2	0	188	188	
Stayman Winesap.....	2	0	186	186	
Peach, Elberta.....	2	0	145	145	
Cherry, Early Richmond.....	2	0	161	161	

Of the plants observed, oats had the smallest number of stomata per unit of area—54,000 per square inch—while cucumber had the largest number—428,000 per square inch of leaf area. When stomata occur on both upper and lower surfaces, the majority of plants have more on the lower than on the upper surface. In these cases, the ratio of the number on the lower to that on the upper surface ranged from 1 in the case of barley and oats to 3 in the case of potato. The leaves of apple, peach, and cherry showed no stomata on the upper surface. Wheat, alfalfa, and white sweet clover consistently had more stomata on the upper surface of their leaves than on the lower, the ratio of the lower to the upper being 0.66, 0.82, and 0.64, respectively, while rye was found to have slightly more on the upper than on the lower surface.

An interesting observation was made by Dodge (1923) in regard to the effect of orange rusts of blackberries and raspberries on the distribution of the stomata on the upper and lower surfaces of the leaves of these plants. In general, normal leaves of these plants had more stomata on the lower side of the leaves. Some few may be scattered singly or in groups of two or three on the upper surface along the large veins or near the edge of the leaf. Dodge found, however, that in blackberry plants which had been systemically infected with the orange rust for 2 or more years, from one-fourth to one-half of the total number of stomata were found on the upper surface.

It may be stated as a general rule (Eckerson, 1908) that there is an inverse relation between the number and size of stomata of a given type. Thus they are the smallest where they occur in the largest numbers. For example, the stomata of oats are considerably larger than those of corn or the sorghums, while those of cucumber, squash, or watermelon are much smaller than the stomata of alfalfa, soybean, potato, or tomato.

The number of stomata vary on the different leaves of the same plant and on different parts of the individual leaf. Miller (1928) observed that the middle leaves of a mature corn plant have from 25 to 45 per cent more stomata per unit of surface than the lowest three or four leaves. The fact that the upper leaves have more stomata per unit area than the lower has been observed by Yapp (1912) for *Spiraea ulmaria*, L., by Rea (1921) for *Campanula rotundifolia*, and by Salisbury (1927) for a wide range of plants. The stomatal frequency in relation to the position of the leaf upon the plant is illustrated in the case of *Polygonatum multiflorum*, as shown by the data given by Salisbury in the table on page 323.

The number of stomata per unit of area varies for different regions of the same leaf. Thus Salisbury (1927) found that the highest frequency was near the leaf tip and the lowest frequency toward the base, while the frequency for the middle region of the leaf was intermediate between the base and the apex. Salisbury also noted that, in some cases at least, the number of stomata per unit area increased from the midrib toward

RELATION OF HEIGHT OF LEAF ON THE PLANT TO THE STOMATAL FREQUENCY IN
Polygonatum multiflorus

Height of leaf above ground, cm.	Number of stomata per square millimeter	Height of leaf above ground, cm.	Number of stomata per square millimeter
21.5	53.6	51.8	77.0
27.0	59.0	53.8	83.6
30.2	76.5	55.2	88.3
50.2	73.0	56.5	91.0

the margin. According to Maximow (1926), this is a part of the general law, first set forth by Zalenski, according to which the higher the leaf is attached to the stem the larger in comparison with the lower leaves are the total number and length of the vascular bundles per unit area, the smaller are the cells of the epidermis and mesophyll and also the cells of the stomata, but the more there are per unit of surface. Salisbury (1927) considers that the increase in the number of stomata on the leaves from the base of the plant toward the tip and from the base of an individual leaf toward its apex is determined by the water relations. Conditions favoring high rates of transpiration or a low rate of water intake favor high stomatal frequency. It was found that under constantly humid conditions the frequency gradient of stomata tends to disappear.

The total number of stomata per plant is enormous. Thus the number on the entire leaf surface of a fully grown corn plant amounts to 140,000,000 to 240,000,000, depending upon the variety and size of the plant, while a single fully developed pumpkin leaf of average size has from 50,000,000 to 60,000,000 of stomata.

Although the stomata occur in very large numbers, they occupy only a relatively small portion of the epidermal surface of the leaves. Kiesselbach (1916) found that the dimensions of the stomatal aperture of the leaves of corn under the conditions of his experiment were 3.5 by 25.6 μ and that the area of the pore was approximately 90 μ^2 . He estimated that the area of the stomata was about 1.5 per cent of the total leaf surface. Brown and Escombe (1900) considered that the area of the stomata of the sunflower plant approximated 1 per cent of its leaf surface. Eckerson (1908) found the average dimension of the stomata of over 30 different species of plants grown in the greenhouse to be 6.7 by 17.7 μ and that when fully open they occupied about one-ninetieth of the total leaf surface. From the various observations that have been made it may be stated, in general, that the area of the stomata may equal from 1 to 3 per cent of the leaf surface of plants.

2. *Opening and Closing*.—The opening or closing of the stomata has been attributed to the changes in turgor of the guard cells since the time of Von Mohl (1856). The opening is apparently brought about by an

increase in the turgor of the guard cells and the closing by a decrease in their turgor. These changes in turgor result in the opening or closing of the stoma because of the uneven thickenings of the cell walls of the guard cells, a fact which was first pointed out by Schwendener (1881). These uneven thickenings in the walls vary in their arrangement but are fairly constant for large groups of plants. The structure of the different types of guard cells and its relation to the opening and closing of the stomata have been extensively described by Copeland (1902). It is the intention here to mention only one type of structure to illustrate the relationship of turgor and the structure of the cell walls of the guard cells to the opening and closing of the stomata.

In one of the most common types of guard cells, the cell wall is much thinner where it borders on the epidermal cell than on the opposite side next to the stoma. When the turgor of the cell is increased, this thinner wall is stretched or dragged out farther than the other and pulls the more rigid and thicker wall bordering the stoma with it, thus increasing the size of the pore. This action is illustrated by a simple experiment which is described in practically all elementary textbooks of botany. Two pieces of rubber tubing are connected by a Y tube to a water faucet or an air pump and are placed parallel with each other. The lower end of the tubes are stoppered, tied securely together, and the exterior side of each piece of tubing is pared through by means of a sharp knife. When the pressure is turned into the tubing, the thin exterior walls bulge and draw the pieces of tubing apart, producing an ellipsoidal opening between them.

(a) *The Physiology of the Guard Cells.*—It has just been stated that the opening or closing of the stomata is due primarily to changes in the turgidity of the guard cells, but no mention was made in regard to the manner by which these changes in turgor might be brought about. In order to understand the explanations that are commonly offered to account for these changes in turgor, a certain knowledge of the anatomy and physiology of the guard cells is necessary and it is the intention here to mention a few facts in this regard.

The guard cells always contain green plastids in contrast to the ordinary epidermal cells. These plastids have until recently commonly been called "chloroplasts" and considered similar to those of the mesophyll, but there seems to be considerable evidence that such is not the case. Sayre (1926) noted in the case of patience dock (*Rumex patientia*) that the chloroplasts of the mesophyll appear as single structures and do not vary in size with their starch content. The green plastids of the guard cells, on the other hand, have the appearance of compound structures, vary in size with their starch content, and are somewhat smaller than the chloroplasts of the mesophyll cells. Chlorophyll develops only in the chloroplasts of the mesophyll when exposed to light, while the green

color of the plastids of the guard cells develops in either light or darkness. If a green plant is placed in continued darkness, the chlorophyll of the chloroplasts of the mesophyll disappears, while the green coloring matter of the plastids of the guard cells does not. Sayre (1926) could not obtain the microchemical tests for chlorophyll from the plastids of the guard cells, but he did not consider the proof conclusive due to the difficulty of making the test on such small bodies. On account of these differences, Sayre considered that the plastids of the guard cells are different structurally, physiologically, and genetically from the chloroplasts of the mesophyll cells of the leaf.

(1) *Osmotic Relations of the Guard Cells*.—It has been established by Iljin (1914), Wiggins (1921), and Sayre (1923, 1926) that the osmotic value of the cell sap of the guard cells is greater than that of the ordinary epidermal cells. Sayre also reported that the osmotic value of the cell sap of the subsidiary cells of *Rumex patientia* is higher than that of the ordinary epidermal cells. The osmotic value of the cell sap of the guard cells is not constant but is highest when the stomata are open and lowest when they are closed, while that of the epidermal cells remains practically constant throughout the day. Iljin (1914) reported that the osmotic value of the cell sap of the guard cells of the numerous plants with which he worked was 70 to 80 atmospheres higher than that of the epidermal cells. These results are perhaps too high, since Iljin used KNO_3 as a plasmolytic agent and Sayre (1926) has pointed out that the protoplasmic membrane of the guard cells is readily permeable to this salt. Wiggins (1921) used a solution of $CaCl_2$ to plasmolyze the cells and substantiated the observations of Iljin, although he was unable to obtain such great differences. The results of Wiggins expressed in the table below show that the osmotic value of the guard cells averaged about 13 atmospheres higher than that of the epidermal cells.

Plant	Osmotic value, atmospheres			
	Ithaca, N. Y.		Columbia, Mo.	
	Epidermis	Guard cells	Epidermis	Guard cells
<i>Zebrina pendula</i>	5.4	11.5		
Cyclamen.....	9.5	12.6	10.1	29.5
Iresine.....	11.3	18.1	11.6	39.5
Beets.....	12.6	31.5

The osmotic values of the cell sap of the guard cells and epidermal cells of *Rumex patientia* were determined by Sayre (1926) by using sucrose, glucose, and $CaCl_2$ as plasmolyzing agents. His results with all

three agents were practically the same and showed the osmotic value of the cell sap of the guard cells to be higher than that of the epidermal cells and that the differences were greater when the stomata were open than when they were closed. The table which follows gives the data obtained by using sucrose as a plasmolytic agent:

OSMOTIC VALUE OF THE CELL SAP OF THE GUARD, SUBSIDIARY, AND EPIDERMAL CELLS OF PATIENCE DOCK

Items considered	8:30 a.m.	10:30 a.m.	1:30 p.m.	3:30 p.m.	7:30 p.m.
Size of stomata, microns.	3 by 30	6 by 31	12 by 34	9 by 31	0 by 0
Osmotic value of the cell sap, atmospheres of guard cells. . .	16.6	16.6	21.0	20.2	13.2
Subsidiary cells.	16.6	16.6	16.6	17.8	15.5
Epidermal cells.	14.4	14.4	14.4	14.4	13.2

The experimental evidence seems to show conclusively that during the daylight hours the osmotic value of the cell sap of the guard cells is greater than that of the epidermal cells and that this difference rises to a maximum during the day and falls off in the afternoon following somewhat parallel the opening and closing of the stomata. The difference between the osmotic value of the cell sap of the guard cells and the epidermal cells varies, no doubt, with different plants and with the different conditions under which the observations are made.

(2) *Changes in the Cell Contents.*—Almost without exception, starch occurs in the plastids of the guard cells under any condition where these cells are fully formed. It is found in the guard cells where the plant has been grown from the seed in complete darkness, in the white area of variegated leaves, in albino plants, and in the guard cells of numerous plants which never produce starch in the chloroplasts of their mesophyll cells. It was formerly supposed that this starch was synthesized by the green plastids of the guard cells, but the evidence at present indicates that the carbohydrate content of the guard cells may be obtained entirely from the green cells of the mesophyll. It has been noted by various observers that the starch content of the plastids of the guard cells changes during the opening and closing of the stomata. Darwin (1898), Lloyd (1908), Iljin (1914), and Sayre (1926) found, in general, that the starch content in the guard cells is greatest in the early hours of the morning and gradually disappears until the stomata are at their maximum opening. It, however, is never wholly depleted. After the stomata begin to close, there is a gradual accumulation of starch in the guard cells until the maximum content is again reached early in the evening after which no marked changes can be detected during the night. It has been observed that when the starch content decreases the osmotic value of the cell sap increases and that the reverse is the case when the starch content

increases. Hagen (1918) observed that when the stomata are open sugar is present in large amounts, while Sayre (1926) showed that in the guard cells of *Rumex patientia* there was two to two and one-half times more sugar present when the stomata were open than when they were closed. Strugger and Weber (1926) in studying the stomata of *Galium mollugo* observed that as starch disappeared in the guard cells, it appeared in the companion cells, and *vice versa*. They concluded from this observation that the subsidiary cells cooperate in the movement of the stoma. This change of starch to sugar and sugar to starch seems to be a reversible reaction in which the total amount of carbohydrate material does not vary to any extent. This reaction has generally been assumed to be due to the enzyme diastase, but so far it has not been isolated from the guard cells, although Hagen (1918) by treating the guard cells with diastase converted the starch into sugar and thus caused the stomata to open.

Sayre (1926) made some observations on the acidity of the guard cells. He found that they were slightly more alkaline when the stomata were open than when they were closed, but no quantitative data could be secured. By using the pressed juice from the leaves as a buffer solution and varying its acidity he could cause the stomata to open or close in light or in darkness. When placed in a solution with a P_H value of 4.2 to 4.4 they opened after 2 hr., but when placed in a solution with a P_H of 3.6 to 4.0 and 4.6 to 5.0 they remained closed. In a study of the effects of different ions on the guard cells, Weber (1923) found that Na and K ions favored the change of starch to sugar while Ca ions favored the change of sugar to starch.

The series of changes which result in the opening of the stomata of a turgid leaf are enumerated by Sayre (1926) and Loftfield (1921) as follows: In the morning, light initiates the action of diastase, probably by decreasing the acidity of the cell sap of the guard cells. The diastase changes the starch to sugar, which results in an increase of the osmotic value of their cell sap. This causes water to enter the guard cells, since the osmotic value of the cell sap of the epidermal cells remains constant. A swelling of the guard cells results and this causes the stoma to open. The procedure during the closing of the stomata is perhaps the reverse of that during the opening.

The rapidity with which the stomata close or open, however, is considered by Scarth (1926) and others to be too rapid to be due entirely to the hydrolysis of starch or its condensation. They consider that the action of diastase is so slow that long before the starch can undergo any great amount of change, the movement of the guard cells is completed. Scarth (1926) found that illuminated and open guard cells are alkaline in reaction, probably from the utilization of CO_2 in photosynthesis, and that certain colloidal constituents of these cells become much swollen as the P_H value increases. He considered that high turgidity in the guard cells

is mainly caused by colloidal imbibition. Closure is accompanied by increased hydrogen-ion concentration due to the accumulation of CO_2 of respiration when photosynthesis ceases on account of low light intensity. The colloids are dehydrated as they approach their isoelectric point, the bound water is freed, the cells quickly lose their surplus water to the surrounding cells, and the guard cells close. Search considered that if hyperacidity develops due to prolonged darkness, the colloids of the guard cells may become more acid than the isoelectric point, produce an acid swelling of the colloids, and thus bring about night opening of the stomata. According to this theory, we have a mechanism whose response is almost instantaneous to light changes. In such a case, the sugar and starch reactions which are commonly associated with stomatal opening and closing may be subsidiary to the main regulatory mechanism. It is worthy of note in this connection that the guard cells have been observed in the case of *Carnegiea gigantea* to function in the opening and closing of the stomata for as long as a century (Long, 1928).

(b) *Methods of Measuring the Changes of Stomatal Apertures.*—Darwin (1898) considered that the amount of water vapor escaping from the leaf could be taken as an index of the condition of the stomata. He used shavings of horn and other materials as hygrosopes. The degree of curvature of these hygrosopes, which was an indication of the rate of water loss, was read on a graduated quadrant. This method measured the change in the transpiration rate but not necessarily the condition of the stomata. Another method reported by him in 1904 in which the degree of stomatal opening was measured by the changes in the temperature of the leaves is open to the same objections. Various types of porometers have been devised and used by Darwin and Pertz (1911), Balls (1912), Jones (1914), Laidlow and Knight (1916), and Knight (1915, 1916) to measure changes in stomatal apertures. The general procedure has been to use a constant-pressure aspirator to draw air through a leaf either intact or detached from the plant. The speed of the air stream is measured by the rate at which water flows from the aspirator and is considered to indicate the relative size of the stomatal openings. The main objections to such porometers are the unnatural condition of drawing air through the intercellular spaces of the leaf and the uncertainty as to what the results indicate. Trelease and Livingston (1916) made a comparative study of the porometer and standardized cobalt paper in regard to the transpiration rate. They obtained results which show a general agreement of data from the two methods during the morning hours but a lack of accord later in the day. The evidence indicates that the porometer measures the diffusive capacity of the stomata but fails to take into account other factors influencing transpiration. Darwin (1911) considered the porometer method to have an advantage over any microscopic method, since it strikes an average of the degree of opening of many hundreds of stomata at each reading instead of the comparatively few that can be observed through a microscope. Lloyd (1908) devised a method of stomatal observation which is the most applicable and the most widely used of any of the methods yet presented for stomatal study. His method consists of stripping the epidermis from the leaf and quickly plunging it into absolute alcohol. The effect of the alcohol is to dehydrate the cell wall and to cause it to become very stiff and hard before removing the water from the cell. As a result, the cell walls retain their original shape and the size of the stoma is unaltered as long as the material is kept dehydrated. The specimens can thus be collected, preserved, stained and mounted, and studied at leisure. The

reliability of this method was verified by Loftfield (1921), who compared the dimensions of the stomata of leaves in position and of those of the stripped epidermis treated with absolute alcohol and found that the measurements were practically identical. Lloyd (1913) used a specially arranged microscope to observe the stomata in position in their natural state. The microscope was provided with a condenser, a 4-mm. objective with a long working distance, and a cooling cell in the form of a flask wired beneath the substage apparatus. By this method it is possible to observe accurately the size of the stomata without injury, but it has its objections in that it cannot be used at night or in poor light and is more or less cumbersome and too slow to be used under the conditions which frequently occur in the field.

(c) *Factors Affecting Opening and Closing.*—Any statements that may be made in regard to factors that affect the opening and closing of the stomata must be considered only as very general in their application, since in this regard, as in many others, different plants may not only respond differently to the same factors, but the nature of the response may be greatly influenced by other environmental factors.

(1) *Light.*—In general, it can be stated that light is the factor to which the stomata most universally respond. As a rule, the stomata of the majority of plants open in light and close in darkness, but the light requirements for opening and closing are not identical, even for closely related plants (Kuyper, 1915; Livingston and Estabrook, 1912; Gray and Peirce, 1919; and Smith, 1922). Light appears to induce the opening of the stomata by initiating conditions favorable to the conversion of the starch in the guard cells to sugar, which increases the osmotic value of their cell sap. The closing of the stomata at night is, however, by no means universal. Of the 75 species of plants examined by Darwin (1898), 13 per cent did not close their stomata at night. Burgerstein (1920) examined 48 species of herbaceous and 27 species of woody plants from 9 to 10 p.m. and found that the stomata of 15 species were fully open, 13 species partially open, 14 species only slightly open, and 33 species fully closed. The stomata of nyctitropic plants are frequently open at night, as are also those of some of the marsh and aquatic plants, while Loftfield (1921) has noted the same condition for the stomata of the potato plant. Although the closure of the stomata in darkness is the rule for the majority of plants, it is not necessarily so complete as entirely to prevent the interchange of gases between the interior of the leaf and the external medium, although it does greatly diminish it. In many cases, too, some stomata remain open, although the great majority of them on the same leaf are completely or partially closed, a fact which was first reported by Leitbeg (1888).

It was observed by Loftfield (1921) that the reduction of light to less than one-half of normal is usually necessary to produce any effect upon the stomata of plants growing in the open and that when stomata are closing they respond to a decrease in light more rapidly than when opening. Darwin (1898) found that artificial darkness is more effective

in producing closure in the afternoon than in the morning and that illumination opens closed stomata more readily in the morning than later in the day.

The question of the periodicity or rhythm of the movement of stomata has received considerable attention, but the experimental results that have been obtained are very conflicting. Sayre (1926) observed that if the plants of *Rumex patientia* growing under normal conditions were placed in a dark chamber in the late afternoon, the stomata began to open at the usual time in the morning, had opened to 10 to 15 per cent of their maximum width by the middle of the forenoon, and had closed by noon. This rhythm occurred to some extent the following day but was not noticeable the third and fourth days. Kuyper (1915) found that in sugar cane there is some indication that after prolonged darkness the stomata tend to open between 8 and 10 a.m. Loftfield (1921) states that the stomata open at night as a result of moonlight or a strong artificial light of much less intensity than one per cent of the sunlight maximum. He also observed that in response to light they opened more readily toward morning than toward midnight.

(2) *Temperature*.—The temperature of the air affects the speed with which the stomata open. Loftfield (1921) observed that within the limits of temperature at which protoplasm functions, the length of time for opening is reduced one half for every 10°C. rise in temperature. Zalenski (1921) noted that when the temperature rises to 35 to 50°C. starch in the guard cells is transformed to maltose and the turgor of these cells increases, in consequence of which the stomata open widely, a fact which is also observed in the wilting of plants. Of the 50 species observed, only millet and succulents showed no opening of the stomata at high temperatures.

(3) *Humidity*.—It is generally considered that high humidity of the air permits the stomata to open wider and remain open longer than a low humidity. This factor is especially important when the water content of the leaf is near the minimum point for normal stomatal behavior.

(4) *Moisture*.—Next to light, the moisture supply of the leaves is the factor which most universally affects the opening or closing of the stomata. The effect of wilting on the movement of the stomata will be discussed under subsequent topics. It will suffice here to state that if the supply of water in the leaf reaches a certain minimum which causes the guard cells to lose their rigidity, the stomata close regardless of the influence of light or any of the other factors that have been mentioned.

(d) *Daily Movement*.—The general behavior of the stomata during the 24-hr. period has been studied extensively by Loftfield (1921) for about 60 species of cultivated, native herbaceous plants, shrubs, and trees. He found that there is a great variation in the behavior of the stomatal aperture of the different leaves of the same plant and even on the same

leaf (see also Leick, 1928). The stomata on the upper surface may behave differently from those on the lower. Thus in the case of alfalfa those on the lower surface open more slowly and close earlier than those on the upper. On all leaves there are a certain number of stomata that are functionless, while a certain portion are more or less inactive. Loftfield observed that 80 per cent of the stomata of alfalfa acted alike as far as movement was concerned and that 18 per cent behaved approximately as the majority, while 2 per cent were completely functionless. The closure of some stomata is frequently prevented by particles of sand or dust wedging in the opening. The general behavior of the movements may be greatly modified by the prevailing physical conditions, so that as many reactions may be observed as there are combinations of physical factors. Loftfield considered that the stomatal behavior of the plants which he examined provided a basis for classifying the stomata into three general types as typified by alfalfa, potato, and barley.

(1) *The Alfalfa Type*.—The stomata of this type under favorable conditions are open all day and closed all night. In alfalfa they open in from 2 to 6 hr. after daylight, remain open from 3 to 6 hr., and then gradually close during a period about twice as long as that required for opening. When conditions become less favorable for moisture, the stomata close partially for a time during the middle of the day, this period of midday closure increasing to complete closure as the conditions become less and less favorable. With the appearance of midday closure, night opening develops and increases with the increase of day closure, until finally there is a partial opening of the stomata all night and a complete closure all day. This type of stomata behavior Loftfield considers to be characteristic of most thin-leaved mesophytes and includes sweet, red, and white clovers, peas, beans, turnip, radish, muskmelon, cucumber, watermelon, carrot, parsnip, apple, peach, pear, and many others.

(2) *The Potato Type*.—The daily stomatal movement in potato was found to be markedly different from that of alfalfa under the same favorable conditions. The stomata of potato are open continuously except for about three hours following sundown. Midday closure is observable in alfalfa before wilting is evident, but midday closure does not occur in potato until the plants are visibly wilted, and only after very extreme lack of moisture do the stomata open at dusk. The stomata of the cabbage, onion, tulip, salsify, plantain, squash, pumpkin, and leek show the general or modified behavior of those of the potato. The stomata of *Scirpus validus*, *Equisetum hyemale*, and *Equisetum palustre* were found to be continuously wide open under normal conditions and even during wilting or death from water loss.

(3) *The Barley Type*.—The behavior of the stomata of the barley is typical of the cereals. They show no opening during the night no matter

how slight the day opening. Also, there are many closed stomata during the day occurring more or less in groups. They open and close comparatively rapidly, but even under favorable conditions they are fully open for an hour or two only.

The optimum conditions for the full opening of the stomata vary widely for different groups of cereals. Thus in the case of corn and the sorghums, very warm to hot weather, bright sunlight, and a high water content of the leaves seem to be the optimum conditions; while in the case of wheat, oats, and barley, cool, humid conditions with relatively mild sunlight are the best.

The examples that have been mentioned refer to the stomata of the leaves. According to Loftfield, the stomata that are found on the stem differ considerably in structure and water relations and consequently in their behavior from those that occur on the leaves.

3. *Capacity for the Diffusion of Gases.* (a) *The Stomata as Paths of Gaseous Exchange.*—It has been proved through the work of Blackman (1895), Stahl (1894), and Buscalioni and Pollacci (1902) that practically all the interchange of gases between the interior of the leaf and the atmosphere takes place through the stomata. Blackman found that leaves which have stomata only on the lower surface that on an average only 3 per cent of the total CO_2 exchange occurred through the upper surface. When stomata occur on both upper and lower surface, the amount of CO_2 diffusing through each epidermis was approximately proportional to the number of stomata on each side of the leaf. Stahl (1894) observed that the loss of water by transpiration is confined, for the most part, to the leaf surface which contains the stomata. By using the cobalt chloride paper method to determine the transpiration rate, he observed that leaves with stomata only on the lower surface that the paper on this surface colored pink in a few minutes, while that on the upper surface did not change color until after several hours. The relative loss of water through the stomata and cuticle was observed by Buscalioni and Pollacci (1902) by placing a collodion film over the leaf and noting that the film clouded very quickly only just above the stomata. The water that evaporates through the stomata is termed "stomatal transpiration," while that which evaporates from the surface of the cuticle is termed "cuticular transpiration." Sayre (1920) in the case of the mullein leaf estimated that the cuticular transpiration amounted to only from one-fortieth to one-twentieth of that of the total water loss. Darwin (1916) found in the case of the ivy leaf that during the day the cuticular transpiration was one-thirtieth of the total but that at night it amounted to as much as one-twelfth of the entire water loss. Since practically all gaseous exchange between the leaf and the air takes place through the stomata, the question arises as to the capacity of the stomata for carrying gases to and from the interior of the leaf and whether their capacity

might be a limiting factor for the maximum activity of its various functions.

(b) *Diffusion of Gases through Small Openings.*—In 1900 Brown and Escombe made certain observations in regard to the intake of carbon dioxide by the leaves of *Catalpa bignonioides*. They found that these leaves which have stomata only on the lower surface could extract from the air under favorable conditions for photosynthesis about 0.07 cc. of CO₂ per square centimeter of leaf surface per hour (measured at 0°C. and 760 mm. Hg). Assuming that all this gas entered the plant through the stomata whose area equaled only 0.009 of the lower leaf surface, the rate of diffusion would be at the rate of $0.07 \div 0.009$ or 7.77 cc. per square centimeter of the stomatal opening per hour. The surface of a strong solution of caustic soda when freely exposed to moderately still air, as is the surface of a leaf, absorbs CO₂ at ordinary temperatures at the rate of only 0.12 cc. per square centimeter per hour, and even though the air current is increased, the maximum absorption is only about 0.177 cc. per square centimeter per hour. If all the carbon dioxide entered through the stomata of the lower surface of the leaf, the absorption per unit of area of these openings was from forty-three to sixty-four times or an average of more than fifty times as rapid as that of the surface of a constantly renewed concentrated solution of alkali. The observance of these facts led Brown and Escombe to take up the investigation of the free diffusion, especially of CO₂ and water vapor, through small apertures of known dimensions under conditions comparable to those existing in the leaf.

In the static diffusion of a gas, vapor, or solute, as the case may be, the amount of substances diffusing in a given time, all other conditions being the same, is directly proportional to the sectional area of the column. Brown and Escombe found, however, that by interposing at any point in the line of flow a thin septum pierced with a circular aperture, the rate of flow across unit area of the aperture is greater than it would be across an equal area of the unobstructed column at this point. When the size of the pore is diminished beyond a certain size relative to the cross-section of the column, the amount of gas which passes becomes proportional to the linear dimensions of the aperture and not to the area. The following tables on page 334, giving data secured by Brown and Escombe (1900) and by Sayre (1926) will illustrate this point.

In order to understand more fully the diffusion of gases through small apertures let us consider experiments 3 and 5 in Table A. The diameters of the apertures are approximately 6 and 2 mm., respectively, and the ratio of their diameters is as 3:1, while the amount of CO₂ diffused in a unit of time stands in approximately the same ratio. The areas of the two openings, however, stand in the ratio of 9:1. Again let us consider experiments 3 and 5 in Table B. Here the diameters of the apertures are

TABLE A.—THE RELATION OF THE SIZE OF APERTURE TO DIFFUSION OF CARBON DIOXIDE
Brown and Escombe

No.	Diameter of aperture, mm.	CO ₂ diffused per hour, cc.	Ratio of		
			Area of aperture	Diameter of aperture	CO ₂ diffused in unit of time
1	22.70	0.238	1.00	1.00	1.00
2	5.86	0.055	0.068	0.25	0.23
3	6.03	0.062	0.07	0.26	0.26
4	3.23	0.039	0.023	0.14	0.14
5	2.00	0.023	0.0077	0.088	0.10

TABLE B.—DIFFUSION OF WATER VAPOR THROUGH SMALL OPENINGS UNDER UNIFORM CONDITIONS
After Sayre, 1926

No.	Diameter of aperture, mm.	Diffusion of H ₂ O vapor, grams	Ratio of		
			Area of aperture	Diameter of aperture	Diffusion of H ₂ O vapor
1	2.64	2.655	1.00	1.00	1.00
2	1.60	1.583	0.37	0.61	0.59
3	0.95	0.928	0.13	0.36	0.35
4	0.81	0.762	0.09	0.31	0.29
5	0.48	0.455	0.03	0.18	0.17
6	0.41	0.393	0.02	0.15	0.15

95 and 48 mm., respectively, and their ratio is practically 2:1. The amount of water vapor diffusing through them in a unit of time is also in the ratio of 2:1. The areas of the two apertures, however, are in the ratio of 4:1. These data show another general law in regard to the diffusion of gases through small pores, *viz.*, that as the size of the openings decreases the velocity of flow through unit area increases, or, in other words, the velocity of flow varies inversely as the diameter of the pore.

Since the velocity of the diffusion flow of CO₂ and water vapor increases with the decrease in the diameter of the openings, it might reasonably be expected that a diaphragm could be so perforated with a series of very small holes that when interposed in the line of diffusive flow, diffusion could take place through such a partition approximately as rapidly as though no partition intervened at all, although the total area of the small holes might represent only a small fraction of the area of the partition.

Brown and Escombe investigated this question by using a thin celluloid kodak film 0.1 mm. in thickness, perforated at regular intervals

with holes about 0.380 mm. in diameter. These films were placed over a solution of caustic potash 1 cm. from its surface and the diffusion of carbon dioxide studied. The general results obtained are expressed in the following table:

No.	Diameter of holes, mm.	Distance of holes apart in terms of diameters	Number of holes per square centimeter	Percentage area of holes on unit area of septum	Observed flow expressed as percentage of septum diffusion on open-tube diffusion	Theoretical flow through porous septum expressed as percentage on open-tube diffusion
1	0.380	2.63	100.0	11.34	56.1	87.6
2	0.380	5.26	25.0	2.82	51.7	63.7
3	0.380	7.8	11.1	1.25	40.6	44.0
4	0.380	10.5	6.2	0.70	31.4	30.7
5	0.380	13.0	4.0	0.45	20.9	21.9

From the preceding table it is seen that the area of the pores in a diaphragm may be only a small percentage of the total area of the diaphragm but that the amount of gas diffusing through them is much greater than the ratio of their area to that of the total area of the diaphragm. Thus in experiment 1 the total area of the pores is only 11.34 per cent of the area of the membrane, yet the flow of gas is equal to 56.1 per cent of the unobstructed tube. In experiment 4 the area of the perforations equals only 0.7 per cent of the area of the cross-section, yet the flow is over 31 per cent of that of the unobstructed column. Brown and Escombe found in one case where the length of tube was 4 mm. that with an area of pores totaling only 11.34 per cent of the total cross-section, little obstructive influence on the flow of gas was produced and the amount diffusing was practically equal to the open-tube diffusion. It may also be noted from the table that when the pores are placed at least eight to ten times their diameter apart, the amount of diffusion approximates very closely the calculated rate but that when the holes are more closely spaced, the flow is less than the calculated. This is explained by assuming that in perfectly quiet air the lines of flux in a diffusive column are approximately parallel at some distance from the diaphragm but that as these stream lines approach the apertures they converge and gradually again become parallel on the other side of the diaphragm. This behavior is somewhat similar to the entrance and exit of water from a pipe. On entering the pipe it converges toward the opening and then again spreads out upon leaving it. In the case of gaseous diffusion, the rate of flow is slowed down if the pores are so close that the lines of flux of one pore interfere with those of another, but not if the apertures

are so spaced that these lines of flow do not intercept one another, the maximum efficiency of flow being maintained. We shall now consider the application of these observations to the diffusion of carbon dioxide and water vapor through the stomata of the leaves.

(c) *The Stomata in Relation to Such Diffusion.*—Brown and Escombe (1900) considered that the ordinary green leaf has the structure for producing the phenomena of diffusion which is associated with a perforated diaphragm. They noted that the stomata on the lower side of the sunflower leaf are about 8 diameters apart, if they are regarded as circular openings, a distribution which allows each stoma to exercise its full efficiency for diffusion without any interference from the neighboring stomata. So far as is known to the author, however, it has never been determined how nearly the spacing of the stomata of all plants is within the limit for their maximum diffusion capacity. Jeffreys (1918) in a mathematical study of the laws of evaporation of water from circular surfaces calls into question the conclusions of Brown and Escombe in this regard. He concludes that the stomata in a leaf must close to one-fiftieth of that of their full aperture before they act independently of one another. The conclusions of Jeffreys have been adversely criticized by Lamor (1918), so that it would seem that a reinvestigation of the behavior of the stomata in this regard should be made.

The amount of gas which enters the leaf through an individual stoma will be conditioned by the gradient density of that gas between the exterior and interior of the leaf and by the linear dimensions of the stoma. In regard to the stoma of the leaf of the sunflower, Brown and Escombe found that when fully opened, its depth was about 0.014 mm. and that it was elliptical in section. They determined that the area of this elliptical cross-section was 0.0000908 mm.², which is about equal to that of a circle with a diameter of 0.0107 mm. They assumed from previous work in regard to diffusion through circular and elliptical openings (Stefan, 1873) that the elliptical stomatal tube would function the same as a cylindrical tube having the same area of cross-section. Sayre (1926), however, considered that diffusion through an elliptical opening would be more nearly equal to that from a circular opening having the same perimeter rather than the same area.

Brown and Escombe considered that if the stomata are wide open and the partial pressure of the CO₂ in the intercellular spaces is maintained practically at zero by the absorbent action of the parenchyma cells, the maximum amount of carbon dioxide which could pass into the sunflower leaf through the stomata would be 2.578 cc. per square centimeter per hour. The maximum rate of photosynthesis which has been recorded for the sunflower leaf by the weighing method of Sachs is approximately 1.8 g. of carbohydrate per square meter of leaf surface per hour. Such a rate of photosynthesis requires an intake of only 0.134 cc. of CO₂ per

square centimeter per hour, or only about 5 per cent of that which could diffuse through the stomata of this leaf if they were wide open and the conditions for ideal diffusion were present. When the stomata of the sunflower are wide open, it would be necessary to have difference of pressure of CO_2 of only about 5 per cent between the inside of the leaf and the outer air in order to supply the gas needed by the leaf during maximum photosynthesis.

The theoretical carrying capacity of the stomata for water vapor was also determined by Brown and Escombe. At a temperature of 20°C . with the water vapor in the intercellular spaces maintained at 17.4 mm. of Hg—the maximum pressure corresponding to that temperature—with the pressure of the water vapor in the outer air at one-fourth this pressure, they considered that the maximum amount of water vapor which would diffuse through the open stomates of the sunflower leaf would amount to 1,730 cc. of water per square meter of leaf surface per hour. The maximum rates of transpiration which have been observed for the sunflower plant vary from 276 to 500 cc. per square meter of leaf per hour according to the prevailing atmospheric conditions. Thus it appears that when the stomata of the sunflower are fully opened they are capable of carrying from three to six times as much water vapor as escapes from the plant at the maximum transpiration rate.

From the previous discussion it is seen that although the stomata occupy only from 1 to 3 per cent of the surface of the epidermis, they have, nevertheless, a carrying capacity for gases greatly in excess of that needed by the plant. Consequently they may close to a considerable degree and yet provide for all necessary gaseous exchange.

4. *Regulation or Control of Water Loss.*—After it had been observed by the earlier workers that the stomata are the main passageways for water vapor from plants, the general view came to be held that the stomata, by opening and closing, control or regulate the transpirational water loss from the plant. The opinions regarding the degree to which the stomatal apparatus may control transpiration have changed with increased knowledge of the stomata and the physiology of the guard cells. The earlier idea was that the stomata could close in anticipation of wilting and thus conserve the water supply of the leaf and prevent it from wilting. This has sometimes been called “active regulation.” When it was found, however, that the stomata do not close until the leaf wilts to some extent, it was considered that stomatal regulation of water is passive, since under such conditions the stomatal closure is not due to any special activity of the guard cells but to a decrease in their turgor which is caused by the loss of water from the leaf cells being greater than the intake. It is now considered that passive regulation or hindrance of water loss is operative only after the stomata have closed to a considerable degree, since when they are fully open their carrying capacity

for water vapor is from three to six times greater than that which escapes at the maximum rate of transpiration.

The question of stomatal regulation of water loss is complicated by several factors, the chief of which are the climatic conditions and the

water supply of the soil. The actual rate of diffusion of water vapor through the stomata is not influenced alone by the size of the pore and the length of the tube but by the gradation of the density of the water vapor between the surface of the mesophyll cells and the outer air. This gradient is dependent upon the water-supplying power of the plant and upon the humidity of the outer air which is, in turn, determined by the prevailing conditions. Thus the gradient of density of the water vapor from the inside of the leaf to the outside may vary independently of the size of the pores. The question of stomatal regulation of water loss has been considered along the three following general lines:

(a) *Stomatal Movement and the Water Content of the Leaf.* The outgo of water from a leaf during the day is generally greater than the intake, while the reverse is generally true at night. The water content of the leaf thus may vary over a considerable range during a 24-hr. period even




FIG. 17.—Graphs showing the variation in the amount of water and dry matter in the leaves of Pride of Saline corn and Dwarf Yellow milo during 24 hr. and the evaporation from a porous cup atmetrometer for the corresponding period.

though no visible signs of wilting can be observed. This variation in water content may be demonstrated in various ways (Trelease, 1924) and will depend not only on the type and age of the plant but also to a large degree upon the prevailing atmospheric conditions. Livingston and Brown (1912) observed that the daily variation in the moisture content of a number of species of plants at Tucson, Ariz., was about 8

per cent on a moist basis. Lloyd (1913) noted for the leaves of the cotton plant grown under the conditions of Auburn, Ala., and Tucson, Ariz., that the loss of leaf water was from 7 to 15 per cent of the initial amount at sunrise. Shreve (1914) observed that the water content of the leaves of *Parkinsonia microphylla* fluctuated as little as 2 per cent and as much as 9 per cent during the day at Tucson, Ariz. Knight (1922), however, found that the diurnal changes in leaf water content in England amounted to not over 1 per cent. Miller (1917) studied extensively the daily variation of the water content of the leaves of corn and the two sorghums kafir and yellow milo growing under field conditions in the Great Plains area of Kansas. The average difference between the maximum percentage of water in the leaves at night and the minimum percentage during the day was 5.4 for corn, 5.9 for kafir, and 6.0 for milo. The minimum percentage of water in the leaves during the day occurred from 11 a.m. to 5 p.m., but in the majority of cases it was reached between 1 and 3 p.m. The maximum percentage of water in the leaves occurred between 1 and 5 a.m., but in the majority of the 30 observations it occurred around 5 a.m. Hawkins (1927) reports that the lowest amount of water in the leaves of Acala and Pima cotton growing at Tucson, Ariz., occurred about 1:30 p.m. An example of the variation in the moisture content of the leaves of corn and milo during a 36-hr. period is shown in Fig. 17 and in the table on page 340.

Lloyd (1912) observed that the stomata continued to open when the water content of the leaves was decreasing and concluded, as did Knight (1917), that the stomata were ineffective in maintaining a constant water supply in the leaf and were thus of little or no value in controlling the water loss. Loftfield (1921) criticizes these conclusions on the ground that there is a certain amount of the water present in a turgid leaf which may be regarded as a working margin and which may be lost without interfering with the opening of the stomata or the various other functions of the leaf. After the loss of water has fallen to or below this working margin, the stomata begin to close due to a fall in the turgor of the guard cells. Hendrickson (1924) noted in the case of peach trees that the decrease in moisture content of the leaves appeared at a period considerably in advance of the maximum opening of the stomata. Loftfield observed that plants may wilt during the early forenoon to such an extent that the stomata completely close but may again regain their turgor during that part of the day when the evaporation is the highest to such an extent that the stomata again open. He attributes this recovery of turgor to the influence of the stomata in retarding water loss so that the cells of the leaf again accumulate a supply of water above the working margin.

(b) *Number of Stomata and Transpiration.*—Kuyper (1915) could establish no relationship between the transpiration rate and the number

VARIATION OF THE WATER AND DRY MATTER IN THE LEAVES OF PRIDE OF SALINE
 CORN AND DWARF MILO AT GARDEN CITY, KANS., AUG. 1 AND 2, 1916

Time	Water per square meter of leaf, grams		Dry matter per square meter of leaf, grams		Percentage of water, wet basis		Percentage of water, dry basis	
	Corn	Milo	Corn	Milo	Corn	Milo	Corn	Milo
Aug. 1:								
7 a.m.	123	105	49	51	72	68	251	206
9 a.m.	119	102	50	53	70	66	238	191
11 a.m.	112	100	51	56	69	64	219	179
1 p.m.	107	98	51	58	68	63	208	168
3 p.m.	104	99	51	61	67	62	203	162
5 p.m.	115	102	52	62	69	62	223	166
7 p.m.	123	107	51	60	71	63	241	177
9 p.m.	124	109	50	58	71	65	247	187
11 p.m.	129	113	49	58	72	66	262	195
Aug. 2:								
1 a.m.	131	117	48	56	73	68	275	210
3 a.m.	129	116	47	55	73	68	273	210
5 a.m.	125	115	47	52	73	69	268	221
7 a.m.	127	117	47	54	73	68	270	217
9 a.m.	120	112	47	55	72	67	258	205
11 a.m.	116	110	50	60	70	65	230	183
1 p.m.	115	110	52	62	69	64	224	176
3 p.m.	108	107	47	62	70	63	230	173
5 p.m.	115	113	50	63	70	64	232	180
7 p.m.	...	114	..	62	..	65	...	184

of stomata per unit area of different varieties of sugar cane. Muenscher (1915) studied the relation of the number and size of stomata to the rate of transpiration of sunflower, bean, wheat, and corn among others. He found no relation between the amount of transpiration and the number of stomata per unit of leaf surface. He also found no constant relation between the amount of transpiration and the number of stomata per unit of leaf surface or between the amount of water lost and the number of linear units of stomatal pore, *i.e.*, the number of stomata per unit of leaf surface multiplied by the average length of the pore.

In comparing different species of plants for transpiration rates, it should not be overlooked that they possess structural differences other than the number of stomata which may greatly influence transpirational loss. The length of time the stomata are open is also a very important factor, and Loftfield (1921) points out that only when the stomata are open for comparable periods can we draw conclusions in regard to the number of stomata and the transpiration rate of different plants. Thus,

for example, Muenscher (1915) found that the ratio of the linear units of the stomatal pore of the sunflower to that of corn was 4:3, while the transpiration rate for a 24-hr. period was 2:1. He concluded that there is no relationship between the number and size of the stomata and the transpiration rate. Loftfield (1921), however, found that the stomata of corn are open 8 hr. while those of sunflowers are open for 12 hr. Thus the water lost by the sunflower plant was during a 12-hr. period and by corn during an 8-hr. period, so that the hourly loss would stand in the ratio of 4:3, which is the same as the ratio of the linear units of the stomatal pores.

(c) *Changes in Stomatal Openings.*—It would be expected that the rate of transpiration could undergo sudden and relatively wide fluctuations with little or no alteration in the size of the stomata provided their full diffusion capacity for water vapor at the stage of observation is greater than the prevailing transpiration rate. This fact was observed by Lloyd (1908) for the cut stems of *Fouquieria splendens*, *Verbena ciliata*, and other plants placed in potometers for transpiration experiments. He noted that the rate of transpiration frequently continued to increase for a considerable period of time after the maximum stomatal opening had been reached and that in the later part of the day there were increases in transpiration without any increase in the size of the stomata. It was concluded from these observations that the stomata are non-regulatory in regard to the loss of water by transpiration. Loftfield (1921) considers that the evidence obtained by Lloyd in this regard is of doubtful value as relating to plants growing under natural conditions, since he found that the stomatal movements and rates of water loss from cut stems in potometers differed greatly from field or potted plants. Kuyper (1915) found that the maximum transpiration rate in sugar cane was frequently reached after the stomata had begun to close, so that the rate of transpiration under the conditions of his observations was independent of stomatal behavior. Knight (1917) found that the interrelationship of stomatal aperture and transpiration was not consistent. In some cases the graphs of transpiration and stomatal openings ran closely parallel, but in other cases there appeared to be no relationship at all between the two. Zhemchuzhnikov (1924, 1925) found in the case of sunflowers, corn, and sorghums growing in soil with 60 per cent of complete saturation that the curves of transpiration usually, but not always, paralleled those of the dimensions of the stomatal pore. He considered that this datum indicates a relationship between stomatal aperture and the rate of transpiration, although meteorological factors may modify it. The prevailing atmospheric conditions without doubt determine to a great extent the correlation between the degree of stomatal opening and the rate of transpiration. Thus Livingston (1909) and Darwin (1916) found in diffuse light and under relatively mild atmospheric conditions that the variation

in the size of stomatal openings were parallel with the changes in the rate of transpiration. As the intensity of the sunlight increases, the stomata apparently respond more quickly in their opening than does the transpiration rate to the increasing intensity of the atmospheric conditions, so that they reach their maximum opening ahead of the maximum transpiration rate.

The general opinion concerning the relation of stomatal opening to the rate of transpiration can be summed up in the words of Loftfield to the effect that when the stomata are fully opened or nearly so, the transpiration rate is determined by the factors of evaporation alone, since the diffusion capacity of the stomata is so great as to interfere in no way with their action. As the stomata close, the influence of the evaporation factors is lessened, but even after the size of the apertures has been reduced over 50 per cent, stomatal regulation is still largely overshadowed by the influence of atmospheric conditions. When the stomata are almost closed, they begin to exert a controlling influence on the water loss regardless of the evaporating factors prevailing at the time. Jeffreys (1918) considers that nearly all the reduction due to the closure of the stomata occurs in the last 2 per cent reduction of the aperture.

The degree of closure of the stomata would appear to have an influence on the moisture content of the air of the intercellular spaces of the leaf. As the stomata close, the degree of saturation of the air in the intercellular spaces increases, so that there would be an increase in the gradient of density of water vapor between the interior of the leaf and the atmosphere. This would increase the rate of diffusion outwardly, so that it is conceivable that as a stoma closes, the rate of transpiration through it may decrease little or none at all over what it was before it began to close. When the closure of the stomata is complete, the air within the leaf must reach saturation. It is not known, however, how completely transpiration is prevented by the apparent complete closure of the stomata.

b. Hairy Coverings.—In most plants certain of the young epidermal cells grow out either singly or in groups to form appendages of various shapes which are termed “hairs” or “trichomes” (Haberlandt, 1914). These epidermal hairs are readily divided into two classes: those that contain protoplasm and sometimes chlorophyll, which are termed “glandular hairs,” and those which have lost their protoplasmic contents and are filled with air. The glandular hairs evidently affect transpiration only by adding to the evaporating surface of the leaf, but the influence which the dead, air-containing hairs have on transpiration is considerably in doubt, although numerous textbooks state that the hairy covering of leaves reduces transpiration. Haberlandt (1914) states that the transpiration rate of leaves of *Stachys lanata* was increased by 20 per cent in the shade and as much as 50 per cent in bright sunlight by shaving off

the hairs from the upper surface. He considered that a dense woolly coat of hairs reduces transpiration considerably when the leaf is exposed to direct sunlight and to a much lesser extent in diffuse light.

Weigand (1910) studied the effect of artificial hairy coverings on the rate of evaporation, since he considered that such experiments would throw some light on the function that such coverings play in transpiration. He used as an evaporating surface a good quality of blotting paper saturated with water and then rolled with a pencil and placed tightly on a glass surface. The edges of the paper were dipped in paraffin and pressed down tightly upon the glass. The loss of water was determined by weighing. Cotton, made waterproof by paraffin in gasoline, was used for protective coverings of various degrees of thickness. The experiments were performed in still air and in air in motion, the wind being produced by an electric fan. The results showed that porous coverings like cotton, wool, or hair must be very thick to produce any appreciable effect in retarding evaporation if the air is still but become very efficient even in thin layers when the air is in motion.

The leaves of the mullein plant (*Verbascum thapsus*) have one of the most dense coverings of dead hairs of any of the more common plants, these hairs being many-celled structures much branched and having the branches both parallel and perpendicular to the leaf surface. Sayre (1919, 1920) studied the influence of these hairs upon transpiration. Three plants, which may be designated as M^{1+h} , M^{2+h} , and M^{3+h} , with the hairs of the leaves intact were exposed to the desired conditions and their rates of transpiration determined. The ratios of the daily transpiration rates of these three plants in the greenhouse in the light and in still air were as follows:

$$\frac{M^{1+h}}{M^{2+h}} = 0.98 \text{ and } \frac{M^{1+h}}{M^{3+h}} = 0.82.$$

The hairs were then removed from the upper surface of M^{2+h} and from the lower surface of M^{3+h} , after which the plants were designated as M^{2-h} and M^{3-h} , respectively. The plant M^{1+h} was left intact as a check. These three plants were placed in the greenhouse in the light and in still air and their daily transpiration rates obtained. The ratios of the rates of the treated plants to the check were as follows:

$$\frac{M^{1+h}}{M^{2-h}} = 0.99 \text{ and } \frac{M^{1+h}}{M^{3-h}} = 0.83.$$

These were practically the same ratios as were obtained when the hairs were intact.

In the light and in a gentle breeze produced by an electric fan the ratios of the water loss were $\frac{M^{1+h}}{M^{2-h}} = 0.91$ and $\frac{M^{1+h}}{M^{3-h}} = 0.78$. In a dark room in still air the ratios were $\frac{M^{1+h}}{M^{2-h}} = 0.56$ and $\frac{M^{1+h}}{M^{3-h}} = 0.65$.

These data indicate that the removal of hairs from the mullein leaves does not appreciably alter their resistance to water loss in still air and light but does slightly decrease the resistance of the leaves to water loss in wind and light as compared with still air and light. The removal of the hairs, however, greatly decreases the resistance of the leaves to water loss in still air and darkness as compared with still air and light. The removal of the hairs affects the transpiration rate most noticeably when the plants are placed in the dark. The stomata are then closed and the transpiration is practically all cuticular. Sayre concludes that the effect of the hairs of the mullein leaf on transpiration in ordinary intensities of wind and light may be disregarded, since the removal of these hairs affects only the cuticular transpiration which is not over one-fortieth to one-twentieth of the stomatal transpiration upon which the removal of hairs apparently has no effect. The effect of hairs upon transpiration of the leaf will no doubt vary according to their number and arrangement, and it must be admitted, in the words of Cowles (1910), that the known uses of the hairs of plants are small in comparison with their abundant development, and it is probable that most of them are of little or no advantage to the plant.

c. General Structure and Composition of the Leaf.—Little work is available to indicate the relation of the transpiring power of the leaf to its general structure or composition. It has always been assumed that the structural characteristics of the leaves of xerophytic plants are useful in reducing the loss of water by transpiration. The structural characters that are commonly associated with the xerophytic leaf are stated by Pool (1923) as follows: The leaf is, as a rule, relatively thick and sometimes without chlorophyll at the center. The epidermis is frequently very thick and waxy, resinous, or heavily cutinized, and the stomata-bearing surface is often hairy. The stomata are sometimes protected by being enclosed and are frequently structurally rigid. Xerophytic leaves generally have prominent palisade cells often in very densely packed layers, extending from one epidermis to the other. Frequently the palisades in the lower part of the leaf are less prominently developed or less densely packed than in the upper portion of the leaf. When the sponge or lower chlorenchyma is present, it is, as a rule, comparatively densely packed with a relatively small amount of intercellular space. As a rule, the fibrovascular elements are more copiously developed in the xerophytic leaf than in the mesophytic one. Of all the structural differences between the xerophytic leaf and the mesophytic one, the most striking are the relative development of the palisade and sponge tissue and the relative proportion of the intercellular spaces. The entire chlorenchyma of the mesophyte is likely to be much more open and, as a whole, thinner than the xerophyte.

Pool (1923) studied by means of the cobalt chloride paper method the transpiring power of some 40 representative species from the various plant communities from the short-grass mesas and plateaux east of Colorado Springs up through the foothills to an altitude of 12,000 ft. It was found that there was some correlation between the transpiring power and the leaf anatomy, leaves of the xerophytic types being found generally to have the lowest transpiring power. The indications were that the compactness of the chlorenchyma of the xerophytic leaves has a marked effect in preventing the evaporation of water in the interior of the leaf and thus reduces the ability to give off water in the form of vapor (see also Lesage, 1894). Pool, however, found many apparent exceptions to this rule. Thus, for example, the leaf of *Pentstemon unilateralis* showed a more xerophytic structure than that of *Populus angustifolia*, yet the index of transpiring power of the latter was 0.641 while that of the former was 0.908. Miller and Coffman (1918) made a somewhat similar observation in regard to the relationship of the leaf structure of corn and the sorghums and the rate of transpiration. The leaves of the sorghums show a marked xerophytic structure in comparison with the leaves of corn, yet the transpiration rate in numerous cases was over twice that of the corn. Pool (1923) states that he is unable to explain the discrepancies between leaf anatomy and the index of foliar transpiring power. He suggests that in his experiments it might be possible that the cobalt chloride paper method was not sufficiently accurate to differentiate accurately between the more nearly similar forms. He considers also that the stomatal behavior should be considered in a study of this kind, since it is to be expected that such behavior would modify the transpiring power to a marked degree. Shreve (1924) considered that the differences in the anatomical structure of the mesophytic and xerophytic leaves does not account for the difference in resistance to water loss by plants in arid regions. A complete summary of the studies on the relation of leaf structure to transpiration is to be found in Burgerstein (1904, 1920).

It appears evident that internal factors other than the general structure of the leaf may influence the transpiration rate, although the extent to which they may do so is in most cases not definitely known. It has frequently been suggested that the osmotic value of the cell sap of the leaf cells might have some influence on the rate of water loss from the plant. The concentration of the cell sap, however, must vary over a wide range in order to have any appreciable effect upon the transpiration rate, as can be illustrated by the examples mentioned by Drabble and Drabble (1907). In these observations they found that osmotic concentration of the cell sap of plants growing in three different habitats was respectively equivalent to 3,728, 8,812, and 14,958 mm. of mercury. They considered that the evaporation of water from the surfaces of these

three solutions would be in the ratio of 1.011:1.005:1, respectively. The influence of the osmotic value upon the rate of water loss would thus be slight, since an increase in concentration of 400 per cent would reduce the rate of evaporation of water by only 1 per cent. Since the osmotic value of the cell sap varies with the accumulation or disappearance of osmotically active substances within the cells of the leaf, the metabolic changes which use or produce these substances must be taken into consideration for slight modifications of the transpiration rate.

Variations in the water-holding capacity of the internal tissues of the leaf may also influence the transpiring power of the plant. The emulsoid colloids of the protoplasm and the component compounds of the cell wall have an imbibitional attraction for water which varies with the changes in structure and composition of these two parts of the plant cell or of the structures with which they come in contact (Shreve, 1916). It is well known that acids, bases, and neutral salts affect the distribution of water between the dispersed and continuous phases of emulsoids. On that account, the alternation of the chemical constituents causes variations in the distribution of water among the cell wall, cell sap, and the protoplasmic membrane, so that the water-holding capacity of the tissues may be altered. The imbibitional forces of the cell walls are especially important factors in influencing the rate of transpiration and will be discussed under the following heading. ✓

2. Incipient Drying or Incipient Wilting.—It has been observed in many cases when the hourly rate of transpiration is plotted that the graph shows a marked flattening in its slope as the evaporating power of the air increases. This flattening of the graph appears to be due to some change in the plant which causes a reduction in the transpiration rate below that which would be expected from the form of the curve during the earlier hours. This reduction in the increase of the transpiration rate has sometimes been interpreted to mean that the plant initiates certain changes under conditions of increasing transpiration which retard the loss of water and thus protect the plant against excessive water loss.

The causes of this retardation of the increase in the transpiration rate are apparently to be found in certain physical phenomena which were pointed out by Renner (1910) and by Livingston and Brown (1912). They suggested that the internal retardation in water loss which frequently occurs prior to the maximum rate of transpiration may be due largely to an increase in the rate of water loss itself. This fact can be illustrated, as shown by Livingston and Brown (1912), by mounting two filter-paper disks saturated with water over glass tubes in such a manner that one will be in continuous contact with water while the other will be deprived of a water supply. When these disks are exposed to conditions favoring evaporation, the one that is in contact with a water

supply will maintain a moisture content that is practically constant, while the moisture content of the one mounted over the empty tube will become less and less. An experiment of this type was performed by Livingston and Brown and it was found that a fall in the moisture content of the paper of 6 per cent produced a corresponding decrease in the rate of evaporation of 5 per cent. A fall of 17 per cent in water content produced a rate of evaporation 8 per cent lower than when the paper was saturated, the effect becoming more and more pronounced as the paper dried out. The conditions which prevail in the leaf as the transpiration rate increases are apparently in some cases similar to those which prevail in the paper-disk experiment, since if at any time the rate of water loss from the leaf surpasses the rate of supply, the tissues of the leaf bordering on the intercellular spaces would become less moist after the manner of the filter paper above mentioned.

✱ This drying out of the cell walls which border on the internal atmosphere of the leaf has been termed "incipient drying" or "incipient wilting" and is substantiated by experiments which have shown a decrease of the water content of the leaves as the evaporating power of the air increases. As incipient drying progresses, the water films gradually retreat into the pores or capillaries of the cell walls bordering on the intercellular spaces and thus increase the surface tension of these water surfaces. This increase of the surface tension of the water films decreases their vapor tension, which causes a fall in the rate of the vaporization of water from them. This means that the retardation of the increase of the transpiration rate under an increasing evaporating power of the air may, in some cases at least, be due to a rate of transpirational loss slightly greater than the rate of water intake by the leaves. When the transpiration of different plants is observed, it is seen that certain plants do not manifest this flattening of the transpiration graph. Thus Briggs and Shantz (1916) found that wheat, oats, and rye showed a flattening of their transpiration graph, while alfalfa and the sorghums under like conditions showed no such behavior. Huber (1924) noted that the transpiration of the lower twigs of *Sequoia gigantea* was six times that of the higher ones. If, however, they are allowed to stand in water for 24 hr., this transpiration difference disappears, which fact he considered proves that these observed differences are the result of unequal water saturation. Zalenski (1923), however, found that the intensity of transpiration per unit of surface increased from the lower to the upper leaves notwithstanding the more xeromorphous structure of the lower leaves.

We want now to inquire what internal factors may influence the imbibitional action on the transpiration rate. Two of the factors which apparently may greatly influence the degree of incipient drying in the leaf and thus influence its rate of transpiration are the leaf surface and

the nature of the root system. We shall now consider the effect of these two factors.

a. Leaf Surface of the Plant.—In transpiration experiments with corn and sorghum plants Miller and Coffman (1918) observed that, in general, if two or more of these plants were placed under the same conditions, the total amount of water lost by each stood in the same relative order as the leaf surfaces. The results of an experiment conducted from 7 a.m. to 7 p.m., as shown in the following table, illustrate this relation:

LEAF SURFACE AND THE AMOUNT OF WATER TRANSPIRED BY CORN AND SORGHUMS FROM 7 A.M. TO 7 P.M.

Plant	Leaf surface, square centimeters	Water transpired, cubic centimeters
Corn, Pride of Saline.....	16,943	3,853
Sorgo, Red Amber.....	4,844	1,702
Sorgo, Freed.....	2,973	989

Although the amount of water transpired per plant stood in the same relative order as the extent of the leaf surface, the loss of water was not exactly proportional to it, so it follows that the rate of transpiration per unit of leaf surface was not the same for each plant (see table below).

THE RATE OF TRANSPIRATION OF CORN AND SORGHUM EXPRESSED AS G.M.² HR. FOR EACH 2-HR. PERIOD FROM 7 A.M. TO 7 P.M.

Time	Corn, Pride of Saline	Sorgo	
		Red Amber	Freed
7 to 9 a.m.....	122	205	190
9 to 11 a.m.....	165	293	304
11 to 1 p.m.....	216	374	376
1 to 3 p.m.....	199	483	379
3 to 5 p.m.....	161	353	272
5 to 7 p.m.....	94	124	147

It is to be observed from the above table that the rate of transpiration of the sorghums per unit of leaf surface was approximately twice as high as that of the corn, while the leaf surface of the Red Amber sorgo and Freed sorgo was only 28.5 and 16.5 per cent, respectively, of that of the corn plant. This same fact also holds when two varieties of plants of different extent of leaf surface are used. For example, Miller and Coffman (1918) observed in the case of a plant of Pride of Saline corn with a leaf surface of 14,568 cm.² and a plant of Sherrod White Dent corn with a leaf surface of 12,989 cm.² that the actual amount of water lost by the

larger plant during a 6-hr. period was 918 cc. as compared to 784 cc. for the smaller plant. The rate of transpiration, however, for the larger plant was only 629 g.m.² hr. as compared to 723 g.m.² hr. for the smaller one. Cullinan (1920) made a similar observation on severely pruned and unpruned 2-year-old apple trees. The unpruned trees transpired more water per plant than did the pruned, but the latter transpired more water per unit of leaf surface. It has been further observed that the differences in the transpiration rate per unit of leaf surface were more marked when the differences in the leaf surfaces were the greatest and when the evaporating power of the air was the highest.

One of the chief causes for the higher transpiration rate of the plants with the smaller leaf surface is apparently their ability to maintain a more saturated condition of the external cell walls of the leaves than the plant with the larger surface. If the facilities for absorption and translocation are approximately the same in two plants with unequal leaf surface, then it is apparent that incipient drying would progress faster and farther in the leaves with the greatest extent of surface. As a consequence of this, the rate of transpiration per unit of area of the plant with the larger leaf surface would be less than that of the plant with the smaller surface.

b. Nature of the Root System.—The ability of the root system to absorb water must exert a marked influence upon the degree of incipient drying and therefore the rate of transpiration. This fact is illustrated by the root systems of corn and the sorghums. Miller (1916) observed that plants of corn, kafir, and milo growing under the same conditions in the field had practically the same number of roots of the first order and that these penetrated vertically to the same depth and showed no difference in their lateral spread. The roots of the second order, however, were twice as numerous in the sorghums as in corn, as is shown in the following table:

NUMBER OF ROOTS OF THE SECOND ORDER PER UNIT OF LENGTH OF ROOT OF THE FIRST ORDER OF CORN, KAFIR, AND MILO GROWING IN THE FIELD

Plant	Number of observations	Number of roots of second order per inch of root of first order
Corn, Pride of Saline.....	127	15
Milo, Dwarf Yellow.....	147	26
Kafir, Blackhull.....	100	28

If the number of fine roots can be taken as a criterion of the efficiency of absorption, it would appear that the sorghum plants would be able

to supply the leaves with more water and prevent incipient drying to a greater degree than in the corn plant. The sorghums illustrate how in some plants both the root system and the extent of leaf surface may be important factors in keeping the water supply in the leaves sufficient to retard incipient drying. Maximow and Rybin (1925) in experiments with magnolia and cherry laurel also came to the conclusion that transpiration may be regulated by the conditions of absorption as well as by the action of the stomata.

3. Aerial and Meteorological Conditions.—The conditions that affect the evaporation of water act directly to influence the transpiration rate. Our knowledge, however, concerning the influence of physical environmental factors upon the rate of transpiration is as yet very limited. Efforts to find algebraic formulae or equations by which transpiration can be estimated from observed environmental conditions have produced none that is satisfactory. These efforts are handicapped primarily since the experimental data at the present time are not sufficient to enable a proper evaluation of radiation, wind, light, temperature, and humidity in relation to transpiration and since the effect of stomatal movement is very little understood. The two main environmental factors which affect the evaporation of water are the evaporating power of impinging solar radiation and the evaporating power of the air.

a. Evaporating Power of Solar Radiation.—By impinging solar radiation is meant the total energy received from the sun by a given surface in a unit of time. The intensity of solar radiation is frequently expressed as the number of calories falling per minute upon a square centimeter of surface normal to the sun's rays. The known methods for measuring solar radiation, however, are not very satisfactory (Livingston, 1911; Briggs and Shantz, 1916; and Pulling, 1919). Solar radiation may be direct from the sun or indirect as from the sky, clouds, or earth. With no clouds or other shade intervening, direct solar radiation is predominant, but when the sun is obscured by clouds indirect radiation may be the more influential of the two upon evaporation (Livingston, 1923).

The influence of solar radiation on evaporation is always positive and is confined to the daylight hours. Briggs and Shantz (1915) found that the radiation graph always rises in advance of the other cyclic environmental factors. This is to be expected, however, since the change in radiation is the primary cause of the cyclic changes of these factors. These investigators observed that radiation rose in advance of transpiration in the case of wheat, oats, and rye and approximately with it in the case of the sorghums, alfalfa, and *Amaranthus*. In the afternoon, radiation fell off somewhat in advance of the transpiration of wheat and oats but approximately with it in the case of rye, alfalfa, sorghum and *Amaranthus*. They found that the correlation coefficient of transpiration with radiation ranged from 0.82 to 0.89 for the plants under consideration,

with temperature from 0.77 to 0.86, and with relative humidity from 0.75 to 0.85. These figures show that intercorrelations exist among the environmental factors, since the sum of the squares of the coefficients of the independent causative factors influencing transpiration cannot exceed unity.

Briggs and Shantz (1916) in transpiration experiments with wheat, oats, millet, and alfalfa under shaded and unshaded conditions concluded that the energy consumed in transpiration is only partially attributable to direct radiation. They considered that indirect radiation from the sky and surrounding objects and the heat energy received directly from the air contribute materially to the heat energy dissipated through transpiration. If, however, the total energy necessary to evaporate all the water lost from an acre of crop plants is compared to the total radiant energy falling upon that area, it is found that less than one-half of it is necessary to evaporate the water lost from the plants even at the time of the maximum transpiration rate.

The primary influence of solar radiation in determining transpiration is indicated by a consideration of the changes in the physical environmental conditions and of transpiration at night when solar radiation is zero. These conditions were determined during the hour from 8 to 9 p.m. and again from 3 to 4 a.m., together with the corresponding transpiration rate. It was found that a simultaneous diminution in the wet-bulb depression of one-fourth its maximum range and in temperature of one-third its maximum range resulted in only a 3 per cent drop in the transpiration rate. This would seem to indicate that the high correlation obtained between transpiration and air temperature and wet-bulb depression is largely due to the direct correlation between radiation and temperature or wet-bulb depression.

The study of the effect of impinging radiation upon transpiration has for the most part been confined to a consideration of the influence of light intensity upon this process, and it has been definitely shown that light has a direct accelerating action on transpiration aside from any secondary effect brought about by stomatal movement (Sampson and Allen, 1909). In order to eliminate any influence of stomatal action, Darwin (1914) covered the leaves with vaseline or cocoa fat and then slit them in various places for the escape of water. Under such conditions the acceleration in transpiration in diffuse daylight was found in the case of *Prunus laurocerasus* and *Hedera helix* to be as much as 50 per cent of the rate in darkness. The figures obtained by Darwin were perhaps too high, since he took data directly after making incisions in the leaves and did not take into consideration the increased water loss due to wound stimulation. Henderson (1926), who followed the same method but allowed the leaf to recover from the wound stimulation before collecting data, could not obtain the large increases in the transpiration rate

obtained by Darwin. Electric light of the intensity of diffuse daylight was found to increase the mesophyll water loss in *Hedera helix* and *Eupatorium adenophorum* by an average amount of 5 per cent of which 1 per cent was due to the heating effect. Thus the direct effect of the light on the transpiration rate amounted to 4 per cent. This amount varied from 1.5 to 9.4 per cent, indicating that the increase in water loss from the mesophyll due to light varies greatly for different plants and for different leaves on the same plant. The increased rate of transpiration due to light may be due to one or more of the following causes: (1) higher temperature of the leaves, although the impinging light may give some of the molecules of water sufficient kinetic energy to escape as vapor without generally raising the temperature of the leaves. (2) Greater permeability of the protoplasmic membrane as suggested by the work of Iwanoff and Thielmann (1923), who found a great increase in transpiration of the living, but not the dead, leaves of *Bromus inermis* and *Cyperus alternifolius* by changing the illumination from red-yellow to blue-violet rays. If light thus reduces the resistance to the passage of water through the protoplasm, the supply available to the cell wall will be increased, its imbibition will be higher, and the vapor tension at the evaporating surface of the cell wall will tend to rise. (3) Imbibitional changes in the cell wall colloids in such a manner as to render it more permeable to water.

b. Evaporating Power of the Air.—The term “evaporating power of the air” is used to designate the combined influences of air temperature, air humidity, and air movement upon the evaporation of water. In contrast to impinging solar radiation, the evaporating power of the air acts on the evaporation of water, not only during the day but also during the night. It generally acts in a positive manner but sometimes in a negative way, as, for example, when the plant absorbs some moisture from the air or when dew is formed upon its surfaces. We wish now to consider individually the effect of temperature, relative humidity, and air movements upon the rate of transpiration.

1. *Temperature.*—The transpiration rate increases, in general, as the temperature rises. Briggs and Shantz (1915) observed that the behavior of transpiration in regard to temperature varies to a considerable degree with different plants. Thus they found in the case of wheat, oats, and alfalfa that the transpiration graph rose in advance of the temperature but rose with the temperature for rye and sorghums and after the temperature in the case of *Amaranthus*. In the afternoon the transpiration for all plants always fell off more rapidly than the temperature, and when the transpiration had reached its night level, the temperature was still above the minimum by an amount equal to about one-third the daily range. In considering the relation to temperature of the average hourly transpiration rates of the above plants on clear days for periods of from 10 to 15 days, they found that the correlation coefficient of transpiration

with temperature varied from 0.77 to 0.86 depending upon the plant. When, however, the correlation between the physical environmental factors and the transpiration of over 20 different crop plants during the growing season was determined as one population, the correlation coefficient between temperature and transpiration was found to be 0.64. This means that in the former case if temperature is considered as the primary causative factor, from 59 to 73 per cent of the transpiration was due to temperature, while in the latter observation only 41 per cent was due to this factor (Briggs and Shantz, 1916).

2. *Relative Humidity*.—In general, it is known that a decrease in the relative humidity will induce a higher transpiration rate, but the amount of quantitative data on the effect of this factor on transpiration is very meager. Montgomery and Kiesselbach (1912) and Kiesselbach (1916) grew corn plants in two greenhouses in which the physical environmental conditions were practically the same with the exception of the relative humidity. During three growing seasons the humidity averaged 22 per cent higher for one greenhouse than for the other. The evaporation from a free water surface in the more humid greenhouse was 54 per cent and the transpiration per unit of leaf area was 62 per cent as much as in the drier greenhouse. Darwin (1913) found that the relation between relative humidity and the magnitude of transpiration in most cases is a linear one and that the straight line representing this relation is approximately in the position giving it an angle of 45 deg. with the horizontal. In some cases, however, the change in the rate of transpiration lagged behind the change in relative humidity so that the experimental graph became a curve instead of a straight line. Darwin also observed that transpiration is not zero in saturated air and apparently would not reach that point until the hypothetical humidity was 105 per cent. This means that the vapor tension of the leaf is higher than that of a saturated atmosphere and is about what it should be if the temperature of the leaf was 0.8°C. higher than that of the surrounding air. Darwin concluded that the temperature of the leaf above that of the atmosphere is produced by respiration. Dixon (1898, 1914) also obtained evidence that plants may transpire in a saturated atmosphere. Briggs and Shantz (1915) found in the case of the plants studied by them that transpiration rose in advance of the depression of the wet-bulb thermometer. They found that the correlation coefficient between transpiration and the wet-bulb thermometer depression varied from 0.75 to 0.85 for 10- to 15-day periods in clear weather.

3. *Wind*.—The effects of wind upon transpiration may be twofold. In the first place, moving air tends to remove the blanket of more or less saturated air which surrounds the leaf and thus tends to reduce the distance that the escaped molecular water must move in order to find free air conditions. The movement of air thus helps to increase the diffusion

gradient and so increases the rate of transpiration. This influence may be understood by considering the opinion of Renner (1910). He considers that the rate of diffusion from leaves will be inversely modified by an increase in the distance between the region of minimum density outside the leaf and the maximum density within the leaf. This distance is increased in still air by the water-vapor cap which forms over the surface of the leaf, and the larger the leaf the greater the average thickness of the vapor cap, so that if the air were perfectly still, transpiration would vary as the diameter of the leaves. On this account, Renner considered that wind increases the transpiration of small mature leaves by a much greater percentage than it does the large ones. In the second place, wind may influence transpiration if its velocity is sufficient to agitate the leaves and bring about a circulation of air in the intercellular spaces.

Copeland (1906) in experimenting with the coconut palm in the Philippine Islands observed that transpiration in one case in direct sunshine was four times as great in a wind with a velocity of 5 miles per hour as in a calm, but the increase usually was not over 100 per cent. Brown (1910) found that while gentle air currents stimulate transpiration, strong air currents may check it. In observations on *Silphium laciniatum*, Giddings (1914) noted that wind velocity increased the activity of the leaves until a velocity of about 8 miles an hour was reached. If the velocity, however, rose above this, the activity of the leaves was impaired and the rate of transpiration became less. Wilson (1924) noted that certain Australian plants had their transpiration checked when the wind velocity reached 20 miles per hour. If wind influences the rate of transpiration independently of the other physical environmental factors, it should show a higher correlation with transpiration than with these factors. This, however, is not the case, according to the work of Briggs and Shantz (1915), who found that the wind velocity showed the lowest correlation with transpiration of any of the other physical environmental factors that were studied. When the correlation between the environmental factors and transpiration is considered for the growing season for a large variety of plants, Briggs and Shantz (1916) considered that only from 2 to 6 per cent of the transpirational loss can be attributed directly to the action of the wind.

Although the experimental evidence in regard to the influence of wind on transpiration is somewhat confusing, the indications are that the rate of water loss does not increase as the wind velocity increases above a gentle breeze. A method for controlling the rate of air movement in transpiration experiments has been devised by Blackman and Knight (1917).

4. Water Content of the Soil.—From what has been previously mentioned in regard to the relation of incipient drying to the rate of transpiration, it should be expected that the rate of transpiration would be

higher if there were an abundant supply of water in the soil than if it were limited. A rapid movement of water to the roots would greatly aid in preventing incipient drying and thus aid in keeping up the transpiration rate (Shreve, 1924). Shreve (1905) and Hendrickson (1921) mention that the transpiration rate of plants is considerably increased by adding water to the relatively dry soil but submitted no quantitative data either in regard to soil moisture or in regard to the transpiration rates. Yuncker (1916) found in growing corn plants in a loam soil with moisture contents of 25, 45, and 65 per cent of saturation that the rate of transpiration for a 24-hr. period was 4.9, 5.8, and 7.2 g.m.² hr., respectively, for each of these moisture contents. Miller and Saunders (1923) determined the rate of transpiration of wilted and turgid plants. The soil with a wilting coefficient of 12 per cent had in the case of the turgid plants a moisture content of 20 to 22 per cent and was in good tilth, while that of the wilted plants was depleted to slightly above the wilting coefficient at the beginning of the experiment and slightly below it at its close. The transpiration rate for the turgid and wilted plants of cowpeas and soybeans is shown in the following table:

TRANSPIRATION RATE OF TURGID AND WILTED PLANTS

Date	Rate of transpiration, g.m. ² hr.			
	Cowpeas		Soybeans	
	Turgid	Wilted	Turgid	Wilted
July 24:				
1 to 3 p.m.....	69.8	32.0	82.6	26.2
3 to 5 p.m.....	78.3	44.8	92.2	24.0
5 to 7 p.m.....	57.9	25.6	37.6	13.0
July 25:				
7 to 9 a.m.....	20.4	19.2	21.4	10.9
9 to 11 a.m.....	71.5	12.8	64.3	15.3
July 26:				
11 a.m. to 1 p.m.....	126.0	6.3	75.1	4.3
1 to 3 p.m.....	165.2	9.6	92.9	4.3

It is a significant fact that when the evaporation rate is relatively low, as in the morning and evening, the differences in the transpiration rate of the turgid and wilted plants are the least. This is due evidently to the fact that incipient drying at these times has not progressed to such an extent as it does when the evaporating power of the air and solar radiation is high.

Frei (1924) grew plants of apple, sunflower, maize, and beans among others in a soil with an optimum water content of 60 to 70 per cent of the

total moisture capacity and in the same type of soil with a minimum moisture content of 35 to 40 per cent of the water-holding capacity. The intensity of transpiration from the plants in the moist soil was always greater than in the dry soil. Also, an increase in the moisture content of the dry soil led to an increase in the intensity of transpiration until it equaled that of the plants growing in the soil of optimum moisture content. Plants, however, which were growing in the soil with the optimum water content showed a considerably lower transpiration rate when the soil moisture was reduced to the minimum (35 to 40 per cent) than was exhibited by the plant which had been grown in the soil with this water content. Dodsall (1922) grew *Equisetum fluviatile* in a soil with a moisture content of 35 per cent, in mud, and with the roots submerged in water and found that the plants growing in the mud lost the most water, while those in the soil of 35 per cent water content lost the least. Dole (1924) found with young plants of *Pinus strobus* growing in a soil with a saturation point of 24 per cent, that the transpiration rate with a moisture content of 20 per cent was from two to six times greater than that from plants growing in a soil with a moisture content of 10 per cent.

Miller (1928) in 12 experiments, each of which extended over an 8-hr. period during the daylight hours, studied the rate of transpiration of corn plants in a water-saturated soil and in a soil in good tilth. The plants which had reached about one-half their vegetative growth were grown in soil in good tilth in sealed cans, and just previous to the experiment water was added in an amount sufficient to saturate the soil. It was found that the average transpiration rate for the 12 plants growing in the soil in good tilth averaged 104 g.m.² hr. while the rate for the plants in the saturated soil averaged 107 g.m.² hr., a difference which is of little or no significance. It is apparent (Livingston, Hemmi, and Wilson, 1926) that after the water supply in the soil has increased to a certain degree, the effects of a deficiency in the oxygen-supplying power of the soil is manifest, so that factors other than the water-supplying power of the soil must be considered.

The experimental evidence in regard to the effect of the water content of the soil on transpiration thus seems to indicate that a plant will transpire the maximum amount of water when the soil has sufficient moisture for good tilth but that an increase above that amount has no effect. A decrease, however, below that for good tilth lowers the rate of transpiration so that when the water content has been reduced to the wilting coefficient or below and the plant is badly wilted, the rate of transpiration may be only one-twentieth to one-thirtieth of that which prevails when the optimum amount of moisture is present.

5. Chemicals.—The effect of chemicals on transpiration has been studied along two different lines: their effect when (a) applied to the soil or nutrient solution in which the plant is growing and (b) in the form of sprays applied to the leaves.

a. *Chemicals Applied to the Soil.*—The presence of any substance in the soil, which will injure the absorbing parts, prevent their development, or decrease the permeability of the protoplasmic membrane to water will decrease the absorption of water and consequently lower the transpiration rate as compared with that of a control plant growing in a medium lacking this substance. The addition of chemicals to the soil may also diminish the transpiration rate due to the increased concentration of the soil solution which lowers the diffusion gradient of water into the plant.

On the other hand, the presence in the soil of substances which increase the permeability of the cell membranes to water and stimulate the growth and development of absorbing organs or act in an antagonistic way upon substances which would lower the transpiration may greatly increase the rate of transpiration. Also, any substance which increases or hinders the growth of the plant in general increases or decreases the transpiration. It is thus seen that the relation of chemicals to transpiration is very complicated and is interwoven with changes in growth, nutrition, and permeability.

Burgerstein (1904) found, in general, that weak acids and extremely weak solutions of alkali accelerated transpiration but that stronger solutions retarded it. He also found that corn plants growing in solutions of 0.1 and 0.25 per cent of $\text{Ca}(\text{NO}_3)_2$ and MgSO_4 increased their transpiration rates, while those in 0.5 and 1 per cent solutions decreased their rates as compared with the controls. Harter (1908) in the case of wheat plants found that when NaCl was present in the soil in sufficient concentration to cause the modification of the structure of the plant, transpiration was considerably reduced but that when present in amounts too small to produce any measurable structural effect, the salt had a stimulating effect upon transpiration. Wheat plants grown in soils containing 0.06 to 0.08 per cent of NaCl showed an increased transpiration as compared with plants growing in a non-saline soil, the lower concentration of salt inducing the higher rate of transpiration (Riceome, 1903). Sampson and Allen (1909) in experiments with *Zea mays* and *Helianthus annuus* studied the effect of the acids HCl , HNO_3 , and $\text{C}_2\text{H}_4\text{O}_2$ and the alkalies KOH , Na_2CO_3 , and NH_4OH . For the plants growing in solutions, concentrations of 0.065 and 0.13 per cent were used, while concentrations of 1.0 and 1.5 per cent were added to the plants growing in the soil. In all cases the acids accelerated transpiration, while in most cases the alkalies retarded it. In some few cases the rate was increased. Reed (1910) noted the effect on transpiration of the wheat plant of the addition to 189 soils from different localities of 100 ppm. of NaNO_3 , K_2SO_4 , and $\text{CaH}_4(\text{PO}_4)_2$ and 1,000 ppm. of CaCO_3 . Considering the transpiration from the control plants as 100, that for NaNO_3 was 90.4; for K_2SO_4 , 94.8; for $\text{CaH}_4(\text{PO}_4)_2$, 100.8; and for CaCO_3 , 97.8. Similar experiments with solutions of various organic and inorganic acids ranging in concentration from $N/2,500$ to $N/40,000$ however, showed very contradictory results. Bouyoucos (1911) in a very exhaustive study of the effect of salts on transpiration found that the transpiration rate was affected by different densities of nutrient and non-nutrient solutions, by different chemical salts, and by the ions of these salts. Reed made the observation that the addition of pyrogallol or tannic acid to soil extracts markedly increased the rate of transpiration. Large increases in transpiration were also obtained by treating soil extracts with absorbent compounds like carbon and ferric hydrate. The increased transpiration in this case is apparently due to the action of these substances upon the toxic or injurious compounds in the soil. Burgerstein (1885) found that solutions containing 1 part of camphor per 1,000 had an accelerating effect upon the transpiration of most plants. Newton (1924) performed experiments which show that the rate of root respiration is increased as related to transpiration when the concentration of the cultural solution is increased. The rate of transpiration is decreased when the concentration of the cultural solution is increased, but this is not accompanied by a corresponding decrease in the rates of root respiration.

This indicates that as the concentration of the cultural solution is increased, the plant roots must expend more energy in absorbing a given volume of water.

b. Films from Sprays.—It has long been recognized that Bordeaux mixture applied as a spray exerts a marked influence upon the physiological functions of the plant aside from its action as an insecticide or fungicide. For example, spraying with Bordeaux mixture has been observed to prolong the life of the potato plant for 25 days and to increase the yield of tubers 100 bu. per acre over that of unsprayed plants during a season when no disease or insect pests were present. Considerable work has been done to determine the nature of the reactions of plants to Bordeaux mixture when applied as a spray, but it is the intention to consider here only its reaction upon the process of transpiration.

Prior to 1914, observations, for the most part, on the effect of Bordeaux mixture on the rate of transpiration were incidental to other experimental work, so that the reports on that subject previous to that date are very brief, with little or no information concerning the state of the plants or the conditions under which the observations were made. Rumm (1893) considered that Bordeaux mixture decreased the rate of transpiration, since he observed that the unsprayed abscised leaves of the grape wilted before the sprayed ones. Bayer (1902) and Schander (1904) also considered that decreased transpiration rates followed spraying with Bordeaux mixture. Schander suggested that the decreased rates might be due to the exclusion from the leaves of certain rays which in the unsprayed leaf tend to accelerate the process of transpiration. The increased vigor and yield of potato plants in the field when sprayed with Bordeaux mixture, even when no diseases and insects are a source of loss, was believed by Clinton (1909) to be largely due to the conservation of moisture in the leaves in dry seasons by the spray. This conservation of water he considered prevented tip burn. This theory was strengthened by the fact that the application of sprays with little sediment did not prolong the life of the plants or give increased yields as did Bordeaux mixture.

Frank and Krüger (1894) concluded that Bordeaux mixture applied to the leaves as a spray exerted an accelerating influence upon the rate of water loss by transpiration. These observations were later confirmed by Zucker (1896).

Since 1914 experimental work in considerable detail has been undertaken by various investigators to determine the effect of sprays and especially Bordeaux mixture upon the rate of transpiration. Duggar and Cooley (1914) instituted the method of procedure that has been generally followed by other workers along this line. The general plan has been to divide the plants under consideration into two groups, which may be designated test plants *T* and control plants *C*. These plants are then paired and the ratio *T:C* of their units of transpiration during a given period is obtained. After this standardization period the plants *T* are sprayed and the ratio of the units of transpiration *T:C* is again obtained for each pair of plants. If the ratio *T:C* has increased over what it was during the standardization period, the transpiration rate has been increased by the spray. If the ratio has decreased, the transpiration rate has been lowered. Duggar and Cooley found that spraying abscised leaves of the castor bean with 4-6-50 Bordeaux mixture increased the rate of transpiration as much as 80 per cent. In the case of potted tomato plants 12 in. high growing in the greenhouse, the transpiration rate was

increased as much as 40 and 25 per cent during a period from Oct. 18 to Nov. 4 by spraying with 4-6-50 and 2-3-50 Bordeaux mixtures, respectively. They also determined the effect upon the transpiration of tomato plants of $\text{Ca}(\text{OH})_2$, $\text{Al}(\text{OH})_3$, clay suspension, and lime sulphur as liquid sprays and powdered $\text{Al}(\text{OH})_3$, charcoal, and CaCO_3 as dust sprays. With the exception of $\text{Ca}(\text{OH})_2$ during one period, all these applications produced during two 15-day periods an increase in the transpiration rate which varied from 8 to 15 per cent above that of the controls. In the case of potted potato plants, the effect of various sprays upon transpiration during two 5-day periods was as follows:

Spray used	Water transpired, cubic centimeters	
	May 6 to 11	May 11 to 15
Bordeaux mixture 4-6-50.....	5,266	4,633
Bordeaux mixture 2-3-50.....	6,424	5,740
Lime wash (60 g. CaO per liter).....	5,845	6,136
Lime sulphur (1-25).....	4,430	4,507
Bordeaux + lamp black.....	7,921	6,530
Lime wash + lamp black.....	5,966	5,856
Controls.....	4,138	4,333

The lime sulphur spray produced the least effect upon the transpiration rate. Lamp black added to Bordeaux mixture produced a higher rate of transpiration than the mixture alone. Martin (1916) at the New Jersey experiment station found that Bordeaux mixture (5-5-50) had a much more marked effect upon the rate of transpiration of abscised leaves than upon those of potted plants. Considering the ratio of $T:C$ before spraying as 1.00, the ratio of $T:C$ after spraying for abscised leaves was as follows:

EFFECT OF BORDEAUX MIXTURE UPON THE RATE OF TRANSPARATION OF ABCISED LEAVES

Plant	Duration of experiment	$T:C$ after spraying
<i>Ricinus communis</i>	6 days	1.50
<i>Datura meteloides</i>	4 days	2.12
<i>Phaseolus vulgaris</i>	10 hr.	2.39
<i>Beta cycla</i>	10 hr.	1.57
<i>Raphanus sativus</i>	10 hr.	1.63
<i>Hibiscus cardinalis</i>	10 hr.	3.72

The average increase in transpiration due to this spray in these and other experiments was about 100 per cent over that of the standardization

period. In the case of potted plants of cabbage, eggplant, pepper, and tomato, the increase in transpiration of the sprayed plants over that of the unsprayed plants was respectively 3, 11, 29, and 8 per cent. Martin also observed that a surface covering of dry powdered copper sulphate was less effective in the acceleration of transpiration than the film of Bordeaux mixture. Lutman (1916) found that the transpiration of potato plants was only slightly increased by spraying with Bordeaux mixture under the conditions of his experiments. The increase that he noted amounted to only 1 per cent, which is apparently insignificant. Shive and Martin (1917) determined the relative rate of transpiration of the sprayed and unsprayed leaves of tomato plants by means of the cobalt chloride method. They found that the rate of transpiration from the sprayed leaves was from 18 to 29 per cent higher than that of the unsprayed ones on the same plant.

Miller (1928) in a series of experiments during four growing seasons studied the effect on transpiration of Bordeaux mixture applied as a spray to tomato plants. The plants were grown in soil in large sealed containers under conditions of the field and were vegetatively normal and produced a normal crop of fruit. The data were collected during a period of 20 days when the plants were in full vegetative vigor. The method used was essentially that used by Duggar. The plants were arranged in pairs and the ratio of the transpiration rate of each pair was determined for a 10-day period. After this period one plant of each of the pairs was sprayed and their ratio obtained for another period of 10 days. The results for the four years are summarized in the following table:

EFFECT OF BORDEAUX MIXTURE UPON THE RATE OF TRANSPIRATION OF THE TOMATO PLANT

Year	Number of experiments performed	Spray used	Effect on transpiration, number		Transpiration of sprayed plants (unsprayed = 1)
			Increased	Decreased	
1924	6	4-8-50	4	2	0.990
1925	17	4-8-50	11	6	1.050
1926	47	4-8-50	20	27	0.994
1927	49	4-5-50	16	33	0.970

Miller thus was unable to obtain any of the striking results on transpiration from spraying as had been reported by other investigators. With the exception of Shive and Martin (1917), most of the experiments reported have been done under greenhouse conditions and under conditions, too, of relatively low transpiration as compared to the experiments at Manhattan, Kans. The results of Shive and Martin were obtained by the cobalt-paper method, while those of Miller were obtained by weighing.

Whether the spray may in some way affect the reaction of the cobalt chloride paper is not known. The conflicting results, however, suggest that more investigation is necessary to determine the effect of sprays upon the rate of transpiration.

6. Fungous Diseases.—Fungous diseases affect the rate of transpiration, in most cases, apparently in a manner that would be expected from the effect that the fungus has on the morphology of the host. In others the effect cannot be explained by any of the known reactions that the diseases have upon the plant. Müller-Thurgau (1894) seems to have been the first to note the effect of fungi upon the transpiration of the host. He noted by the use of hygrometric paper that when pear leaves were infected with *Fusicladium pyrinum* (pear scab) and apple leaves with *Fusicladium dendriticum* (apple scab), the rate of transpiration was considerably increased, the transpiration of the diseased areas being higher than the healthy adjacent portions. Grape leaves infected with *Peronospora viticola* (downy mildew) showed a much lower rate of transpiration than the healthy leaves and this was attributed to the fact that the conidiophores almost completely filled the stomata. Blodgett (1901) noted that leaves of *Rubus* which were infected heavily on the lower surface with *Gymnoconia interstitialis* transpired almost twice the amount of water as did the normal healthy leaves. Montemartini (1904) found in the case of 20 species of plants each infected by a different fungus that almost without exception the transpiration rate was higher for the diseased than for the healthy plants. Reed and Cooley (1913) by means of Freeman's method studied the effect of *Gymnosporangium juniperi-virginianae* upon the rate of transpiration of 8-year-old York Imperial and Ben Davis apple trees. The rate of transpiration per unit of surface of the diseased leaves was, in the majority of cases, less than that of the healthy ones. The average ratio of the transpirational loss of the diseased to the healthy leaves was 0.783 for the York Imperial and 0.742 for the Ben Davis. The ratios showed certain differences if they were grouped according to different stages in the development of the disease. The rate of transpiration was depressed to the greatest extent when the fungus had reached maturity and many of the cluster cups were open for the release of the aeciospores.

This fungus brings about certain changes in the morphology of the leaf which would apparently lower the transpiration rate. The apple leaves bearing the cluster cups are thicker by three or four times than the normal leaf. The large intercellular spaces in the spongy tissue disappear due to the formation of columnar cells, while the stomata are scarce or lacking and the substomatal cavities are absent altogether.

Weaver (1916) made a study of the influence of the rusts of wheat, rye, oats, barley, corn, sunflower, cocklebur, and carnation upon the transpiration rate. In the case of wheat infected with *Puccinia graminis*

tritici, the transpiration rate of the diseased plants was increased 30 per cent above that of the healthy plants. This difference in rate was produced by the fungus when the rust pustules amounted to only nine-tenths of 1 per cent of the leaf surface. A striking increase in transpiration was noticeable when the pustule area was increased by only two-tenths of 1 per cent. Rye infected with *Puccinia rubigo-vera secalis* showed the same increase in the rate of transpiration per unit of leaf area over that of the healthy plants as did wheat. Thus an increase of 20 per cent in the transpiration rate was noted when the pustules represented only 3.8 per cent of the leaf surface.

In oats infected with *Puccinia graminis avenae* in which the pustules equalled only 0.5 per cent of the leaf surface, a transpiration rate 37 per cent higher than that of the healthy leaves was obtained. Corn, sunflower, and carnation plants infected with rust behaved in a similar manner to the cereals that have just been discussed. Cocklebur plants which were inoculated with *Puccinia xanthii*, however, showed a transpiration rate which was only 50 to 60 per cent of that of the healthy plants. This behavior of the cocklebur seems to be due to a change in the tissue of the leaves similar to that which occurs in the apple leaf when infected with *Gymnosporangium juniperi-virginianae*.

In the case of the rusts of the cereals, the increase in the transpiration rate occurs about the time that the pustules break through the epidermis. After the pustules are for the most part broken out, no increase in the transpiration rate is apparent. The cause of this increased transpiration rate is not known. Dufrenoy (1918) considered that a number of fungi accelerate transpiration owing to localized necrosis, rupture of the epidermis, or changes in the permeability of the cells.

In the case of the cereal rusts, however, Weaver considers that the cause of the accelerated transpiration is not wholly due to the torn epidermis. The whitish areas around the pustules indicate that some striking change has occurred in the cells composing these regions. The mesophyll cells which are penetrated by the haustoria certainly do not function normally. It is conceivable, as was suggested by Weaver, that the fungi may excrete substances into these cells which may cause a change in the permeability of the protoplasmic membrane that accelerates water loss. Weiss (1924) considered that the infection of wheat by either leaf or stem rust resulted in a lowered water economy of the host, as indicated by the higher water requirement of the rust-infected plants as compared to the healthy ones.

D. TEMPERATURE OF THE LEAVES

It is commonly stated that transpiration is beneficial to plants because it cools the leaves and thus prevents their temperature from becoming so high in bright sunlight as to cause their death or at least to hinder their

normal activities. The temperature of a leaf, however, depends upon numerous and varied factors, so that in order to understand the influence of transpiration upon it, a general discussion of the subject is necessary. The most important factors which influence the temperature of leaves are the temperature of the air, the supply of available moisture in the soil, the evaporating power of the air, currents of air, the intensity of light, and the angle at which it is incident to the leaf surface. Under identical conditions the temperature of one kind of leaf is different from that of another kind, while different regions of the same leaf have different temperatures. Any data, therefore, that are presented upon this subject must be regarded as relative only to the atmospheric conditions that prevailed when the temperature determinations were made.

1. Methods of Measuring.—The earlier determinations of leaf temperatures were made by pressing the thermometer against the leaves or by wrapping the leaves about the thermometer. This method is still used when only approximate results are desired. It is not accurate, however, due primarily to the relatively slow response of the ordinary thermometers to changes in temperature and to the inability to get a proper contact of leaf and thermometer with the leaf in its normal position.

More accurate determinations of leaf temperatures are now made by means of thermocouples, with which it is possible to measure not only accurately but very quickly either the internal or the surface temperature of the leaf. The thermocouple method has been used by Blackman and Matthaei (1905), Ehlers (1915), and Clum (1926) for measuring the internal temperature of leaves and by Shreve (1919), Miller and Saunders (1923), and Eaton and Belden (1929) for measuring the surface temperature.

In the determination of leaf temperatures by means of the thermocouple method, the general procedure of each investigator has been very similar, although the methods have varied somewhat in detail. The method used by Miller and Saunders (1923)—a modification of that used by Shreve (1919)—for determining the surface temperature of leaves will serve as an illustration of the general procedure for the determination of plant temperatures by the thermocouple method. A diagram of the apparatus used is shown in Fig. 18. It consists of two thermo junctions TC and $T'C'$ approximately 5 mm. in length, which are formed by braiding two wires and then uniting them by an acid-free solder. The wires generally used are No. 36 copper and No. 36 constantan with insulated connecting lengths A , B , and B' totaling approximately 3 ft. One of the thermocouples $T'C'$ is placed with a thermometer graduated to 0.1°C . in a stoppered Dewar flask surrounded by any suitable insulating material as glass wool (GW), and water, in any convenient container. The air in the flask remains practically constant, since under the most severe conditions it does not fluctuate more than 0.1°C . during a 15- to 20-min. period. The other thermo junction TC is attached to a clamp C in such a way that it can be conveniently placed upon the surface of the leaf. This clamp may consist of a pair of crucible tongs 44 cm. in length, modified by filing their distal ends to narrow dimensions. One of these filed ends is inserted in a small wedge shaped piece of cork CK , the edge of which measures 1 by 5 mm. and holds the thermocouple TC . On the other tip of the tongs is inserted a small cube of cork CK 5 by 5 mm. which serves as a support to the leaf when the thermocouple is placed upon it. By means of a clamp of this kind, the thermo junction can easily be placed as desired in direct contact with either the upper or the lower surface of the leaf and the temperature determined. Similarly, the tempera-

ture of the air can readily be determined by holding the open clamp in the air and taking precautions to shield the thermo junction from the direct rays of the sun, A galvanometer *G* and a damping switch *K* are placed in the circuit. Since the temperature of the thermo junction *T'C'* is known and can be kept approximately constant, the difference in temperature *T'C'* and *TC* can be calculated from the swing of the galvanometer, which has previously been calibrated. By such an instrument a difference in temperature of 0.1°C . can be accurately detected. This apparatus when in use in the field with leaves that are some distance above ground is placed upon a small table which is shaded by a piece of heavy canvas placed about 2 ft. above its surface. When vines and low plants are being investigated, the apparatus is placed on a low box and shaded with an umbrella.




FIG. 18.—Apparatus used in measuring the surface temperature of the leaf by the thermocouple method. Description in the text.

2. Temperature. *a. Fluctuations in Temperature of the Air.*—In direct sunlight, when the temperature is relatively high and the air is in motion, the temperature of a leaf and the surrounding air is not constant but shows sudden and marked fluctuations even during so brief a period as a few seconds. These changes in temperature, which vary from a small fraction of a degree to as much as 4°C ., are easily detected by the galvanometer through the thermo junctions but are of such short duration that as a rule they are not visibly recorded by a mercury-bulb ther-

nometer even when it is graduated to tenths of a degree. These rapid fluctuations in the temperature of the air are due, in all probability, to the fact that the air is not uniformly heated throughout but contains warmer or cooler pockets which suddenly replace the air surrounding the measuring instruments. The leaves of most crop plants respond very quickly to these changes in air temperature, since even a very slight increase or decrease in the temperature of the air is almost immediately followed by a corresponding change in the temperature of the leaves. When the air is still and when the temperature is relatively low, the fluctuations in the temperature are so few and so slight that they are seldom detected by the galvanometer. The rapid fluctuations of the temperature of the leaf and the surrounding air emphasize the necessity not only of having a rapid means of determining temperatures but also of making a large number of observations in order to obtain the relative temperature relations of a leaf and its surroundings. The thermocouple method for measuring temperatures is relatively rapid. The swing of the galvanometer for a temperature determination can be read in 2 or 3 sec. The time, however, that elapses during the recording of the deflection and the return of the galvanometer to equilibrium amounts to approximately 10 to 12 sec., so that an interval of about 15 sec. occurs between any two consecutive observations.

b. Temperature of Normal Turgid Leaves.—Miller and Saunders (1923) made numerous determinations of the temperature of the upper surface of the leaves of corn, sorghum, cowpeas, soybeans, watermelon, pumpkin, and alfalfa growing under field conditions in Kansas. The average of 1,000 determinations of the temperature of the air and of the upper surface of the turgid leaves of corn in direct sunlight between the hours of 9 a.m. and 4 p.m. and under a wide range of atmospheric conditions was 30.58°C. for the air and 30.64°C. for the leaves. The average of the same number of determinations made with the leaves of five varieties of sorghums under conditions of exposure similar to those of the corn leaves showed that the temperature of the leaves was 30.64°C., while the average of an equal number of determinations of the air temperature during the same period was 30.66°C. Five hundred observations on soybeans gave an average temperature of the air of 33.13°C. and an average of 33.66°C. for the temperature of the upper surface of the leaves. A similar number of determinations on the leaves of cowpeas showed an average temperature of 34.4°C., while the temperature of the air averaged 34.2°C. during the observations. These observations show that the temperature of the turgid leaves of corn, sorghum, pumpkin, watermelon, and soybean in direct sunlight under the general climatic conditions which prevail in Kansas fluctuates slightly above and below air temperatures but that their average temperature is essentially the same as that of the surrounding air. The temperature of the leaves of alfalfa under the

same conditions as the plants above mentioned consistently showed less than 1° below that of the surrounding air. In the case of corn, sorghum, watermelon, pumpkin, soybean and cowpeas the heat absorbed by the leaves from the sun is quickly utilized in transpiration or rapidly disseminated into the surrounding air, so that the temperature of the leaves is always approximately that of the air. In the case of alfalfa the rate of transpiration is evidently rapid enough to reduce the temperature of the leaf slightly below that of the air.

The internal temperature of the leaves of *Fuchsia speciosa*, *Phaseolus vulgaris*, *Brassica oleracea*, and *Syringa vulgaris* was determined by Clum (1926) by means of thermocouples. The plants were in the direct sunlight in the open or in the greenhouse at Ithaca, N. Y. He found that the temperature of the leaves with which he worked was nearly always higher than the air during the day and that in direct sunlight it was 5 to 10°C. higher. The maximum difference observed between leaf and air temperature in the open was 13°C. and in the greenhouse, 16°C.

The type of leaf has an important bearing on its temperature in relation to the surrounding air. It seems reasonable to suppose that a thick, fleshy leaf will absorb and retain more heat than a thin one. This supposition is borne out generally in experimental observations. Thus Askenasy (1875) and Ursprung (1909) by placing thermometers in close contact with the surface of the fleshy leaves of *Sempervivum* found that the leaves attained a temperature in the sunlight of 18 to 25°C. above that of the surrounding air. Askenasy attributed the high temperature of these leaves primarily to the fact that the heat which they absorbed was not readily dissipated by air currents or radiation. As mentioned above, Clum (1926) obtained temperatures of leaves that were 5 to 10°C. higher than that of the surrounding air. The type of leaves with which he worked had, in general, a much greater mass in proportion to the surface exposed than did the leaves investigated by Miller and Saunders (1923), which in no case had temperatures appreciably different from that of the surrounding air. An example of the relation between the compactness and general mass of a plant organ and its temperature in relation to that of the air is afforded by the work of Brooks and Fisher (1926) with the apple. They found that the side of an apple exposed to the sun may have a temperature from 12 to 25°C. higher than the air temperature and from 10 to 16°C. higher than the shaded side of the same apple. In the case of the thin sunflower leaves, Brown and Escombe (1905) calculated their temperature to be only approximately 2° above or below that of the air. The experiments that have just been discussed were conducted under summer conditions, but it is interesting to note that Ehlers (1915) found that evergreen conifer leaves under winter conditions maintain internal temperatures from 2 to 10°C. higher than that of the surrounding air.

In considering the temperature of a leaf, the air currents must be taken into consideration. A leaf in direct sunshine freely exposed to a breeze always has a lower temperature than one under like conditions of sunlight but in such a position as to be protected from air currents. Smith (1909) observed that breezes reduce the temperature of leaves in sunlight by amounts varying from 2 to 10°C. and that a thin leaf is much more noticeably affected than a thick one. Similar observations were also made by Miller and Saunders (1923) and by Ehlers (1915).

Miller and Saunders observed for the plants with which they worked that in diffuse light the temperature of attached turgid leaves is always consistently lower than the temperature of the surrounding air. The average temperature differences between the turgid leaves and the surrounding air under conditions of diffuse light varied from 0.1 to 3°C. In direct sunlight the temperature of a turgid leaf may be above the air temperature, but as soon as a cloud obscures the sun the temperature of the leaf almost immediately drops below the temperature of the air and remains there until the leaf is again exposed to direct sunlight (see the following table):

THE TEMPERATURE CHANGES OF THE AIR AND OF THE TURGID LEAVES OF SOYBEAN PLANTS IN DIRECT SUNSHINE AND IN DIFFUSE LIGHT CAUSED BY A HEAVY CLOUD OBSCURING THE SUN

Time, p.m.	Temperature, degrees centigrade, of	
	Air	Turgid leaf
In direct sunlight		
1:10	32.0	34.0
1:11	32.1	33.9
1:12	32.7	33.3
1:13	30.7	30.7
1:14	31.0	32.3
1:15	31.3	31.8
1:16	32.8	32.6
1:18	32.0	34.2
In diffuse light due to cloud passing over sun		
1:19	30.0	26.3
1:20	28.0	26.3
1:21	27.7	26.0
1:22	26.7	25.3
1:23	26.3	25.3
1:24	26.8	25.3
1:25	26.3	25.1
1:26	25.9	25.0

During the night the temperature of the leaves falls to the same level as that of the surrounding air or slightly below it.

c. Rate of Transpiration and the Temperature of the Leaf.—It has long been known that a wilted leaf has a higher temperature than a turgid one under the same conditions, but the actual differences in temperature and the correlation of the transpiration rate with this temperature difference has been but little studied. Darwin (1898) in the observation of withered detached leaves and normal attached leaves of *Tropaeolum majus* found in intermittent sunshine and relatively low humidity that the temperature of the withered leaves was from 1.2 to 3.9°C. higher than that of the attached leaf. Kiesselbach (1916) by inserting the bulb of a thermometer momentarily in the folds of corn leaves found that a transpiring leaf was uniformly cooler than a dry dead one, the difference in temperature amounting in one case to as much as 8.5°F. in direct sunshine and to 4.2°F. in the shade. Using a similar method, Loftfield (1921) made a few observations on the temperature of the leaves of alfalfa, potato, and sugar beet in relation to stomatal behavior. He found that usually the temperature of the leaves with stomata open was lower than that of the air, while the temperature of the leaves with closed stomata was higher than that of the air.

Rather extensive experiments in relation to transpiration and leaf temperature were conducted by Miller and Saunders (1923) and by Clum (1926). The former investigators measured the surface temperature of the leaves and the latter their internal temperature by means of the thermocouple method. The transpiration temperature experiments of Miller and Saunders were conducted with turgid and wilted plants of three varieties of corn, three varieties of sorghums, and one each of cowpeas and soybeans. The plants designated as turgid were those which showed no visible signs of wilting during the experiments. The soil in the containers in which the plants were growing was kept at a moisture content sufficient for good tilth by the frequent addition of water to replace that lost from the plants. In order to obtain wilted plants, certain containers were set aside to which no water was added to replace that lost by transpiration and the plants were considered sufficiently wilted for the experiment when they did not regain their turgid condition during the night. The water content of the soil in which the wilted plants were rooted averaged about 2 per cent above the wilting coefficient. The rate of transpiration was determined at intervals of 2 hr. and the temperature determinations were made at times intermediate between these periods.

A typical response of the turgid and wilted leaves of plants in regard to temperature and the rate of transpiration is shown by the graphs in Fig. 19, representing the data obtained with corn leaves in direct sunlight.

The data obtained from several thousand observations on corn, sorghum, soybeans, and cowpeas showed that the temperature of a wilted leaf in direct sunlight is always higher than the temperature of a turgid leaf exposed to the same conditions. The average temperature of the wilted leaves of corn, sorghum, soybeans, and cowpeas during the hours of 9 a.m. to 4 p.m. was respectively 1.85, 1.55, 2.8, and 4.6°C. higher than that of the turgid leaves. The maximum temperature difference observed between the turgid and wilted leaves of corn in direct




FIG. 19.—Graphs showing the transpiration rate of turgid and wilted corn plants and temperature of the leaves of these plants at different periods of the day.

sunlight was 4.3°C. when the temperature of the air was 32.3°, and the transpiration rate of the turgid leaves was approximately five times that from the wilted leaves. The maximum temperature difference between the wilted and turgid leaves of cowpeas was 6.7°C. when the temperature of the air was 37.6°C., and the transpiration of the wilted leaves was approximately only one-sixteenth that of the turgid plants.

The observations of Miller and Saunders agree, in general, with the results obtained by Clum (1926) with *Fuchsia speciosa*, *Phaseolus vulgaris*, *Brassica oleracea*, and *Syringa vulgaris*. He reduced transpiration by allowing the soil to dry and in some cases by vaselining the surface of the leaves. In general, the vaselined leaves and the leaves of the plants in the dry soil were 2 to 4°C. warmer than the controls. In no case, however, did he find a definite correlation between the transpiration rate and the

difference between the leaf and air temperatures or between differences in the transpiration rates of two leaves or plants and differences in their temperatures.

d. The Thermal Death Point.—It has been observed by numerous investigators that the thermal death point of most plant cells lies between 45 and 55°C. and that, in many cases at least, the fatal temperature must be prolonged some little time before death ensues. It has been shown that transpiration lowers the temperature of leaves even under severe conditions only to the extent of 2 to 5°C. with an average difference somewhat less than 3°C. This difference in temperature is not striking and it would seem doubtful whether the increased temperature of the wilted leaves could to any marked degree injure the protoplasm or even retard its vital activities. Even if a leaf became heated to a critical temperature, the lowering of it from 2 to 3°C. by transpiration would not greatly prolong life. The temperature of a leaf does not long remain constant, due to rapid radiation, convection, and air currents, so that these factors may be more effective in protecting the leaves from overheating than is transpiration. The cause of the death of leaves under severe climatic conditions would thus seem to be due to the dehydration of the protoplasm rather than to a critical temperature induced by the lowering of the transpiration rate.

E. EVAPORATION

Since the days of Unger (1861), who regarded transpiration as a physical process modified by the nature or peculiarities of the plant, transpiration has frequently been defined as the evaporation of water from the plant altered to some extent by its structure and functions (see also Woods, 1893). Because of the similarity of evaporation and transpiration and because of the aim apparently to show that transpiration is a relatively simple physical process, the rate of evaporation has been frequently used as a standard to which transpiration is compared or referred. The rate of water loss from plant surfaces exposed to the air is always lower than the rate of evaporation from an equal area of water surface under the same environmental conditions (Livingston, 1906, 1913). Briggs and Shantz (1916) noted that the loss of water from wheat, oats, barley, sorghum, and alfalfa during a 10-day period of maximum transpiration at Akron, Colo., amounted to only 5 to 14 per cent of the loss during the same period from a free water surface. McLean (1919), however, states that transpiration in the tropical rain forests was in his observations four-fifths of that from a free water surface. It is evident from these facts that certain internal factors exert a retarding influence upon the evaporation of water contained in the plant. This retardation or resistance to the evaporation of water will vary with the kind of plant,

its age, the portion of the plant considered, and the changes of internal conditions.

Evaporation and transpiration are both determined largely by the same factors—solar radiation, temperature, saturation deficit, and wind—so that if transpiration is a purely physical process, then a high correlation between it and evaporation is to be expected. Briggs and Shantz (1916) found in comparing the rate of evaporation from a small shallow tank with the transpiration rate from wheat, oats, rye, alfalfa, and *Amaranthus* that the correlation coefficient ranged from 0.84 to 0.95. In the case of the highest correlation it would thus appear that nine-tenths of the transpiration was determined by the same factors which determine evaporation. They noted that the transpiration graph of these plants showed a tendency to rise somewhat earlier than the graph of evaporation from the small tank and to fall off somewhat later in the afternoon. Owing, however, to the greater slope of the transpiration graph in the late afternoon, they both reach the night level at the same time. These authors consider that the relation of transpiration to evaporation should be considered associative, both responding to the same environmental factors but not in the same way or to the same degree. The extent of this association, however, depends upon the manner in which evaporation is measured, so that a consideration of that subject is next in order.

1. Measurement. *a. Value of Data.*—A knowledge of evaporation in considering the water relations of plants is of importance in several ways. In the first place, the rate of evaporation from a free water surface or from a moist porous surface is considered the best single valued expression of the intensity of the weather factors influencing transpiration (Briggs and Shantz, 1917). Evaporation thus serves as a simple means of expressing the aerial conditions under which experimental work is performed. A study of the evaporating power of the environment which prevails in a given section during the growing season furnishes an approximate measure of the transpiration loss which would occur in that region. The intensity of evaporation thus gives a standard by which it is possible to correlate some of the general facts of plant distribution and to predict whether certain plants are adapted to the atmospheric conditions prevailing in the region under consideration. The rate of evaporation thus may be an indicator of the vegetative possibilities of a given region (Livingston, 1907, 1911).

b. Instruments for Measuring Evaporation.—Any instrument that is used for the measurement of evaporation is termed an "atmometer" or "evaporimeter." Numerous types of atmometers have been used, and one of the main handicaps in evaporation studies so far has been to obtain a standard instrument. It should be kept in mind that the water surface from which evaporation proceeds is as truly a control of the rate of water loss as are the atmospheric conditions. The loss of water from one instrument is thus different from the loss from another under the same conditions, and

furthermore the evaporation from one instrument cannot be reduced to that of another. Thus suppose that under one set of conditions an instrument *A* loses twice the water per hour as an instrument *B*. If the environmental conditions are changed,

this relation between the two rates of loss does not hold, and the instrument *A*, does not lose twice the amount of water as does *B*. Hence the readings from any evaporating instrument cannot be reduced to the losses from another instrument of unlike form. It is of course impossible to produce two instruments that are exactly alike, but if their form and volume are approximately the same, they may be very accurately standardized, as will later be mentioned. The exposure of two instruments must be the same if the readings are to be at all comparable. If one of the two instruments that are alike in all details is placed 1 ft. from the level of the ground and the other 2 ft. from the ground, the evaporating rates will be different. The exposures thus need to be specific as well as the kind of instruments if the rates of evaporation are to be comparable (Livingston, 1915, 1917). These facts in regard to evaporation have in many cases been little appreciated or considered by those who have studied evaporation, so that the data are very confusing.




FIG. 20.—*A*, Bellani plate type of atmometer. *B*, cylindrical porous cup atmometer. *C*, spherical porous cup atmometer. *D*, apparatus for measuring the evaporation from an atmometer: *sa*, spherical porous cup atmometer; *c*, perforated rubber stopper; *c'*, notched cork; *b*, buret; *rt*, rubber tubing; *gt*, glass tubing.

of the water constant, so that the evaporation alters the nature of the instrument. The removal of water by birds, insects, and toads and the addition of water by rains and its loss by splashing also tend to make the data thus obtained less exact. Accu-

1. *Atmometers with a Free Water Surface.*
The two instruments of this type that have been the most extensively used have been designated the large tank and the small tank. The large open tank has been used extensively by the U. S. Department of Agriculture Office of Dry Land Agriculture. It is circular in form, made of galvanized iron, and is about 6 ft. in diameter and 2 ft. in depth, being sunk into the ground so that its surface and that of the ground are on approximately the same level. The loss in evaporation is measured in terms of depth by means of a vernier arrangement attached to the side of the tank, but a self-recording apparatus may also be attached. There are many objections to this means of measuring evaporation. The wind not only increases the surface exposed by waves or ripples but may frequently remove water by whipping it over the sides.

There is no means of keeping the depth

rate readings for short periods have never been possible with the large tank, so that for hourly comparisons of evaporation with transpiration it is of little or no value. For a comparison of transpiration and evaporation for the entire growing season, however, it has proved very satisfactory (Briggs and Shantz, 1916).

The small tank type of atmometer was devised and perfected by Briggs and Shantz (1916, 1917) and consists of a shallow copper tank 91 cm. in diameter and 2.5 cm. high and blackened on the inside. It is supported on a wooden disk 4 cm. in thickness and mounted about 1 m. above the ground on an automatic scale sufficiently sensitive to record the loss of a layer of water 10μ in thickness. The depth of the water is automatically maintained at about 1 cm. by means of a Mariotte apparatus mounted on the scale platform. This instrument is automatic, accurate, and has few of the disadvantages of the large tank. It is the best yet devised for determining the loss of evaporation from a free water surface.

2. *Atmometers with a Moist Porous Surface.*—The most widely used porous surfaces for evaporation studies are those of porous clay, although filter and blotting paper has sometimes been used. The first known porous-clay atmometer was the Bellani porous plate devised by Bellani in 1820 (Fig. 20A). It consists of a horizontal porous-clay disk forming the top of a container completely filled with water so that the lower surface of the disk is in contact with the liquid while the upper surface is exposed to the air. The porous-clay cup atmometer is now the most universally used of any of the porous surface evaporimeters. This instrument was independently devised three times, first by Babinet (1848), then by Mitscherlich (1904), and finally by Livingston (1906, 1910). These atmometers as now used are hollow cylinders or spheres of unglazed porcelain and have a capacity of about 50 cc. They are provided with a neck or collar which is either glazed or shellacked and are so arranged that they may be connected with a water supply by means of a rubber cork carrying a glass tube (Fig. 20B and C). The porous surface atmometers are filled with water and the porous unglazed portions of the walls absorb water by capillarity or by imbibition, so that a moist porous surface is exposed to the air. These atmometers may be connected with a relatively large container whose supply of water need not be replenished for a number of days or weeks, the evaporation being determined by noting the amount of water necessary to fill the reservoir to its original level. The porous atmometers may be connected with a buret as shown in Fig. 20D when accurate readings are required at brief intervals of a few minutes to several hours. The porous cup atmometers present to the action of the air a water surface which is held in position by surface tension, adhesion, and the rigidity of the material which composes the instrument. The form of the surface is thus not disturbed by wind, insects, or splashing, as is so frequently the case with free water surfaces. The intake of water by rains can be almost prevented by various rain-excluding attachments that have been described by Livingston (1910), Livingston and Thone (1920), Shive (1915), Johnston (1918), and Nichols (1923). The porous-clay cup atmometers that are generally used are white in color, but in order to obtain responses to the atmospheric complex that more nearly correspond with those of the plant or to study the effect of solar radiation on water loss, atmometers of darker colors have been employed. These are either made from colored clay or are painted with lamp black (Livingston, 1911, 1923, 1926).

Before setting up a porous-clay cup atmometer it should be soaked in water for several hours at least, so as to replace the air in the interstices with water. The atmometer and connecting tubes must be filled with water and connected with the water supply in such a manner that no air bubbles enter the apparatus. If any bubbles enter they will collect at the top of the cup on the inside and thus hinder evaporation from that portion of its surface. The cup must always be placed higher than the water level in the reservoir, otherwise water will be forced out of the atmom-

eter by hydrostatic pressure. It has been found, however, that the cup may be placed several feet above the level of the water in the buret or reservoir without perceptibly influencing the rate of water loss.

Similar forms of porous-clay cup atmometers may be standardized by operating them along with a cup that has been checked to a given standard. The atmometers are mounted upon a rotating table so that they will all be similarly exposed (Nichols, 1913). The evaporation is determined for a given period of time and the reading of the standardized cup is then divided by the reading from the cup that is to be standardized to determine the coefficient of correction. The calculation of this coefficient K may be stated algebraically as follows (Livingston, 1918): $K = CR/r$ where R is the reading of the standardized cup that is being used and C is its coefficient of correction, while r is the reading of the instrument that is being standardized. K is thus the coefficient by which the reading from the instrument under consideration must be multiplied to reduce it to the loss of the standard cup with a coefficient of unity. The readings from similar atmometers can thus all be reduced to the same basis, and the atmospheric conditions under which the observations are made can thus be more correctly interpreted than if no such reduction could be made.

Thomas and Ferguson (1917) considered that an attempt should be made to realize a standard which should be invariable under given conditions and capable of replacement at any place or time. They concluded from rather elaborate experiments that the free water surface contained in a cylindrical vessel and protected by a rim 3 cm. in depth fulfills these conditions, although many factors must yet be considered before definite statements in this regard can be made.

2. The Ratio of Transpiration to Evaporation.—The term "absolute transpiration" is used to denote the observed rate of water loss from the plant. In a general way, the curve of absolute transpiration usually follows very closely the curve of evaporation and may give no indication of any retardation or acceleration of transpiration that is due to causes other than the evaporating power of the surrounding air.

The ratio of the rate of transpiration to evaporation was termed by Livingston (1906, 1907) "relative transpiration" and by Briggs and Shantz (1916), the "transpiration coefficient." It has also been called the "transpiring power" of the plant, a term used to denote the reciprocal of the resistance or acceleration manifest by plants to water loss by transpiration as compared to evaporation from an atmometer. It represents the group of internal conditions influencing the transpiration rate. If the plant and an atmometer responded alike to changes in the environment, the rate of relative transpiration would give a straight line when plotted hour by hour.

The graph of relative transpiration, however, is periodic in form and exhibits a marked minimum during the night hours. This fluctuation in the rate of transpiration has been interpreted by Livingston (1906, 1913), Shreve (1914, 1915), Livingston and Hawkins (1915), Burns (1915), Trelease (1922), and others to represent departures in the transpiration rate of the plant from that which would prevail if the plant responded freely to its environment. When considered in this light the curve of relative transpiration should thus indicate the magnitude of

the physiological retardation or acceleration of the transpiration rate due to closure of the stomata or to reversible changes taking place within the plant. In making this interpretation, it is assumed that an evaporimeter responds freely to its environment and that the rate of evaporation from it affords a perfect summation of the environmental condition determining evaporation from the plant. It should be kept in mind, however, that all atmometers do not respond to their environment in the same manner, so that it evidently makes a great difference in determining relative transpiration as to what atmometer is used. Its value, therefore, may not be so definite an indicator of internal changes in the plant as was formerly supposed.

The hourly transpiration rate of alfalfa was compared with the hourly evaporation rate from various types of atmometers by Briggs and Shantz (1917). This comparison rate was made by superimposing the hourly transpiration graph on each of the hourly evaporation graphs, choosing the scale of ordinates of the transpiration graph so that the total area under the transpiration graph was equal to the total area under the evaporation graph. The average hourly departure of each of the evaporation graphs from the superimposed transpiration graph was expressed in percentage of the mean hourly evaporation for the day. The summation of the data obtained is shown in the following table:

AVERAGE-HOURLY DEPARTURE OF EVAPORATION RATE FROM TRANSPIRATION RATE FOR ALFALFA, PERCENTAGE OF THE MEAN EVAPORATION RATE FOR VARIOUS TYPES OF ATMOMETERS

Type of atmometer	Day periods, 6 a.m. to 6 p.m., per cent	24-hr. period, per cent
White cylinder.....	38	49
Brown cylinder.....	29	41
White sphere.....	31	43
Bellani plate.....	30	41
Filter-paper atmometer.....	22	31
Shallow tank.....	12	17
Large deep tank.....	93	89

Since the greater part of the transpiration and evaporation occur during the daylight hours, calculations are made for that period as well as for the 24-hr. period.

These figures indicate, for example, in the case of the white sphere atmometer, that the average error in predicting the amount of transpiration at each hour in the day from the evaporation, when the ratio of daily transpiration of the plant to the daily evaporation of the atmometer under consideration is known, would amount to 43 per cent of the mean

hourly value of the transpiration in the case of the alfalfa plant. The departure of the hourly transpiration rate and the hourly evaporation rate was the least when evaporation was measured by the small shallow tank.

It is evident from the foregoing that an atmometer has not yet been secured that responds in the same manner to its environment as the plant. The atmometers depart widely from the plant during the night hours—the rate of evaporation being relatively much higher than transpiration in all the cases that have been observed. Knight (1917) found that the plants with which he worked and the porous-clay cup atmometer responded unequally to changes of wind velocity but that changes in temperature and relative humidity acted upon the rate of evaporation and transpiration equally (Freeman, 1920). He concluded that changes in relative transpiration do not necessarily represent changes in the intrinsic transpiring power of a plant unless conditions of air movement are maintained constant. The transpiration rate of different plants varies under the same environmental conditions due to internal factors, so that when a comparison of the responses of transpiration and evaporation to the environment is made, the kind of plant as well as the type of atmometer must be taken into consideration.

F. METHODS OF MEASURING TRANSPIRATION

The rate of transpiration may be measured by determining the amount of water lost per plant during a given period of time or the rate of loss per unit of leaf surface per unit of time. One of the most common ways of expressing the loss is in grams per square meter of leaf surface per hour ($\text{g.m.}^2 \text{ hr.}$). Comparative transpiration between different plants may also be obtained in a qualitative way by means of color standards, as will later be described.

The determination of the rate of water loss per unit of leaf surface per unit of time makes the measurement of the leaf surface of the plants necessary. This may be accomplished in any of the following ways: (1) by tracing the outlines of the leaves on paper and then at a convenient time measuring the inclosed areas by means of a planimeter; (2) by cutting out the traced areas and by comparing the total weight of paper thus obtained with that of a known area of paper; (3) by obtaining the form of the leaf on sensitized paper and then either measuring or weighing the enclosed areas as above mentioned; (4) by rough measurement of the leaves and determining their area by direct calculations; (5) by measurement with the photoelectric cell. The essentials of the apparatus used in this method comprise a light-tight cabinet or photometer within which is mounted a selenium cell and having at its upper surface a fairly large plate-glass window illuminated from above by means of a balopticon. The leaves to be measured are placed upon the glass window, and the change in the electrical resistance of the selenium cell occasioned by the reduced amount of light passing into the cabinet is measured by a suitable electrical device. Gerdel and Salter (1928) state that this device is accurate to within 3 per cent for an area of 500 cm.^2 and 0.8 per cent for areas of $2,000 \text{ cm.}^2$

One of the main things to be desired in measuring the rate of transpiration is that the plant be placed during the experiment as nearly as possible under the same

conditions of the soil and atmosphere as prevail in the field. The accuracy, rapidity, and convenience of the method are factors that also must be considered. No method, however, has been devised for the measurement of transpiration that is entirely satisfactory in all these regards. Numerous methods for measuring transpiration have been reported, detailed descriptions of which have been given by Burgerstein (1904, 1920), but it is the intention here to describe only the four methods that have been the most universally used, especially in experiments with agricultural plants. These are the potometer method, the weighing method, the cobalt chloride paper method, and Freeman's method.

1. The Potometer.—This method consists of placing the severed plant or branch thereof directly in water and after proper sealing determining by weight or volume the amount of water lost. One of the most common methods of procedure is to connect the severed branch or plant with a buret by means of rubber tubing and to note the loss of water volumetrically. This method was formerly used very extensively, but at present it is very little used. It has the very serious objection that the plant is placed under abnormal conditions, and it has been definitely shown that the rate of transpiration under these conditions is in most cases not comparable at all to that occurring where the plant is normally rooted in the soil. Thus, as an example, Freeman (1908) found that the rate of transpiration for the daisy, coleus, portulaca, and geraniums growing in the soil was, respectively, 7.21, 2.77, 1.72, and 0.65 mg. per square centimeter per hour but that from like plants which were severed and placed in potometers under like conditions, the rate of transpiration was 1.44, 0.37, 0.47, and 0.65 mg. per square centimeter per hour, respectively. Not only was the rate of transpiration much less, but the order of the transpiration rate was entirely different from what it was with the plants growing in the soil. Loftfield (1921) has also pointed out the fact of the difference in the behavior of stomata of plants in potometers as compared to those growing in the soil.

2. The Weighing Method.—For quantitative data the weighing method of measuring transpiration is the most convenient and satisfactory. The amount of transpiration from the entire plant is obtained, while the conditions under which the plant is placed previous to and during the experiment can be made very comparable to those which occur in the field. The method consists, in general, of growing the plants in soil in containers which can be sealed so that no water escapes except that which evaporates from the plant (Fig. 21) and determining the loss by weighing. The containers that have been most frequently used for experiments with crop plants have been cylindrical galvanized-iron cans with a capacity of from 250 to 1,000 lb. of soil which is tightly packed therein. The cans are covered with galvanized-iron lids supplied with perforations for the plant and for the addition of water (Fig. 21). This lid is either sealed with tape that is waterproof (Briggs and Shantz, 1913, 1914) or rendered so by shellac (Miller, 1916, 1923) or is covered with oilcloth or other waterproof material (Kisselbach, 1916). The escape of water around the plant is prevented by using as a seal a mixture of beeswax and paraffin (Briggs and Shantz,




FIG. 21.—Diagram showing the method used in growing plants in soil in large metal containers for the determination of the loss of water by transpiration. *a*, plant. *b*, cover of galvanized iron. *c*, corks. *e*, wax seal. *g*, flower pots. *h*, soil. *i*, gravel beneath flower pots and extending to the bottom of the container.

1913, 1914), beeswax and a small amount of Venetian turpentine (Miller, 1916, 1923), or plastic modeling clay (Kiesselbach, 1916). One of the greatest difficulties experienced in growing plants in soil in large containers is to replace evenly throughout the soil the water that has been removed by the plant. Kiesselbach (1916) placed in each container 16 ft. of $\frac{3}{4}$ -in. brass tubing made into a spiral coil perforated every 8 in. and obtained a good distribution of moisture through the soil by adding water to a container connected with this coil. Briggs and Shantz (1913, 1914) placed 5-in. flower pots over a small bed of gravel placed near the upper surface of the soil and obtained in this manner a good distribution of water. A modification of this method was used by Miller (1916, 1923), as shown in Fig. 21. Two more or less cone-shaped masses of soil 6 in. in diameter and 15 in. in depth are removed from the upper portion of the container. From the bottom of this cavity a hole 1.5 in. in diameter is made to the bottom of the can by means of a soil tube. The entire cavity is then filled with coarse sand and gravel to within 5 or 6 in. of the top of the can. A 5-in. clay flowerpot with the bottom removed is placed directly on top of this sand so that the rim of the pot is flush with the metal lid of the can. A 1-in. hole for the addition of water is in the lid of the can directly over each flowerpot. By this device not only is water evenly distributed through the soil, but sufficient aeration is apparently also provided, since the roots do not collect between the soil and the surface of the container, as is so frequently the case in pot experiments, but are evenly distributed throughout the soil.

When small plants and only a small quantity of soil are to be used, it has been found satisfactory to use unglazed porous-clay atmometers of the cylindrical, cone, or Bellani plate types as distributors of moisture. These are buried in the soil and connected with the surface by glass tubing so that water may be added directly or supplied automatically as it is needed from a reservoir (Livingston, 1908, 1919; Livingston and Hawkins, 1915). A small, inverted, porous flowerpot buried in the soil and connected with the surface by means of glass tubes is also a very satisfactory watering device for small volumes of soil (Kiesselbach, 1916).

The plant containers are weighed at stated intervals by hand or on automatic scales connected with recording devices (Ganong, 1905; Briggs and Shantz, 1915; Transeau, 1911; and Blackman, 1914). By the latter method a continuous record of the water loss during the day and night is obtained. The use of automatic balances, however, is rather difficult in the field and is almost prohibitive in price when a large number of plants must be considered. The most common method is to weigh the plants at certain stated intervals and in that manner determine their water loss for the period. The large containers may be lifted by means of a differential block and tackle and weighed with steelyard or spring balances (Kiesselbach, 1916; Briggs and Shantz, 1913, 1914), or they may be permanently mounted on small platforms provided with wheels or castors and pulled on and off the ordinary platform scales (Miller, 1916, 1923).

Since such a large mass of soil is required in many cases to grow normal plants, it is not possible to employ scales with a very high sensitivity, so that when the transpirational loss is desired for short intervals, the readings are not so accurate as are sometimes desired. The weighing method does not take into consideration the increased weight of the plant due to growth, but this increase in weight is very insignificant when compared to the large loss in weight due to transpiration.

3. The Cobalt Chloride Method.—Cobalt chloride $\text{CoCl}_2 \cdot 6\text{H}_2\text{O}$ occurs in the form of dark red crystals which may be dehydrated in different stages, forming successively red or violet $\text{CoCl}_2 \cdot 4\text{H}_2\text{O}$, and $\text{CoCl}_2 \cdot 2\text{H}_2\text{O}$, and finally the blue anhydrous CoCl_2 . Taking advantage of this property of cobalt chloride, Stahl (1894) prepared a hygrometric paper by dipping filter paper in a solution of $\text{CoCl}_2 \cdot 6\text{H}_2\text{O}$ and then drying it. Such a paper is blue when dry but changes its color to white or rose when

moist. When this dry blue paper is placed upon the leaf and covered with glass or a thin piece of mica held firmly in place by a small spring clamp, it will in time become pink due to the escape of water vapor from the leaf surface. Stahl used this method to compare the rate of transpiration from the upper and lower leaf surfaces and from the leaves of different plants by comparing the time required for the paper to assume the pink color. He, however, did not attempt to standardize these readings to any standard physical evaporating surface. Livingston (1913) conceived the idea of comparing the power of a standard evaporating surface to give off water to the hygrometric cobalt chloride paper with that possessed by any leaf surface that might be considered. The method first devised by Livingston (1913) has been modified, improved, and studied by Bakke (1914), Bakke and Livingston (1916), Livingston and Shreve (1916), and Shreve (1917, 1919). The improved method of procedure is approximately as follows (Livingston and Shreve, 1916):

a. *Preparation of the Hygrometric Paper.*—Circular filter paper of a high grade of uniformity of texture is placed for one minute in an agitated solution of 3 g. of CoCl_2 in 100 cc. of water made distinctly acid by the addition of hydrochloric acid. It is then placed on a clean glass and the excess solution is squeezed out with a rubber roller. The paper is then partially dried in the oven between two filter papers, but while still pink it is removed from the oven and thoroughly pressed and dried between the two filter papers by means of a flatiron. The blue color of the paper must be more intense than that of the standard to be later mentioned, the intensity of color being varied by altering the time the paper remains in the solution. After the paper is dried, it is placed in a desiccator over a convenient dehydrating agent and left until needed.

b. *Standard Colors.*—Since the cobalt chloride paper takes up some moisture during the transfer from the desiccator to the leaf and since it is difficult to determine with any degree of accuracy the end point in color of the moist paper, Livingston and Shreve (1916) devised two permanent standard colors with which to mark the beginning of the experiment. Both of these colors are blue, one being just a little less intense than the color of the dried cobalt chloride paper while the other is much less intense but clearly blue. The permanent color standards are made by precipitating Prussian blue in the same type of filter paper as is used for the cobalt chloride paper. The paper is first dipped in a solution of ferric chloride and after the excess solution is removed it is then dipped into a solution of potassium ferrocyanide, the excess solution removed, and the paper dried after the manner described for the preparation of the cobalt chloride paper. The two intensities of color are obtained by varying the concentration of the solutions and the time of treatment. The color-standard papers thus prepared do not alter their color when exposed to air and sunshine or with changes in the moisture content of the air. A composite strip of the cobalt paper and the two standard color papers is made by taping together square pieces of each 4 mm. square with the cobalt chloride square in the center.

These composite strips are taken from the desiccator and clamped upon the leaf as has previously been described. When the cobalt chloride paper matches in color that of the more intense standard, the experiment is considered started, and it is considered concluded when it reaches the intensity of the lighter color standard.

c. *The Standard Evaporating Surface.*—For a standard evaporating surface in this method, a free water surface (Livingston, 1913), a moist filter paper supplied from beneath with water (Bakke, 1914), and a porous-clay cup atmometer filed to a flat surface (Livingston and Shreve, 1916) have been used. In all cases, the cobalt chloride paper is held by suitable appliances at a distance of 1 mm. from the evaporating surface. The length of time that is required for the hygrometric paper to reach the color end point is determined after the same manner as when the paper is applied to the leaves.

d. The Index of Transpiring Power.—The time that is required for the hygrometric paper to reach its end point in color over the leaf is called the “leaf-test time” and over the evaporating surface the “water-test time.” The ratio of the water-test time to the average leaf time is called the “index of transpiring power,” a value which varies greatly at different times of the day; Bakke (1916), for example found that within a single hour just after sunrise it increased 240 per cent in the case of sunflower. He also found (1914) that the younger leaves have a higher index of transpiring power than do the older ones. Let us consider a specific example to illustrate the application of the cobalt chloride method of determining the index of transpiring power. Let us assume that the water-test time is 15 sec. and the leaf-test time for the upper surface 300 sec. and for the lower surface 150 sec. The index of transpiring power for the upper surface would thus be $\frac{15}{300}$ or 0.05 and for the lower surface $\frac{15}{150}$ or 0.10. The average index of transpiring power for the whole leaf would thus be $\frac{0.05 + 0.10}{2}$ or 0.075. The evaporation from the leaf thus goes on at the rate of 0.075 times that from the standard evaporating surface under observation.

The cobalt chloride paper method of determining transpiration is valuable since it makes possible the determination of the relative transpiring power of plants growing in the open soil under field conditions. The method thus is applicable and very convenient for determining the relation of the position of leaves on the plant to the rate of water loss, the xerophytism or mesophytism of plants, and the wilting point. Its chief disadvantage is that it is only a qualitative method and gives no quantitative data in regard to the amount of water actually lost from the plant.

Meyer (1927) used a modified method of procedure in the application of the cobalt chloride method so that the rate of water loss may be expressed in absolute units instead of only relative values. He determined the amount of water by weight that must be taken up by a given area of standardized cobalt chloride paper to reach the pink end point. From this datum it is thus possible to determine the number of units of water vapor being lost from a given area of leaf in a unit of time if the area of the paper used and the time required for it to reach the end point are known. In the method of Meyer the paper is so placed that the conditions of humidity, radiation, and air movement are practically constant beneath it, so that the only variable atmospheric factor is the temperature and thus all readings can be standardized to the same temperature. Meyer adopted the term “standard rate of water loss” for designating the amount of water vapor lost under the conditions of the experiment in terms of grams per hour per 100 cm.² of leaf surface at 20°C.

Howes (1923) has devised a CaCl₂ method for measuring the transpiring power of plants. Small tubes of CaCl₂ are attached to the leaf by means of special clips. The CaCl₂ retains its efficiency as a water absorber for a considerable period even when small amounts are used, and the results are not affected by the amounts of CaCl₂ in the tubes.

4. The Freeman Method.—This method was first used by Freeman in 1908 and is a modification and adaptation of the methods used by Ganeau de Lamarlière (1892) and E. and J. Verschaefelt (1890). The general details of the apparatus used in this method are shown in Fig. 22. The apparatus consists of a large glass cylinder of suitable size for a transpiration chamber for the twig or portion of the plant whose water loss is to be measured, two U tubes containing P₂O₅ for absorption of moisture, and a water aspirator of known capacity. These are connected together by rubber tubing so that as water flows from the aspirator a known quantity of air may be drawn through the cylinder over the leaves under experiment and through the P₂O₅ which is loosely packed in order to allow the free passage of air. The glass cylinder containing the twig is closed at its distal end with a split cork which fits tightly around the twig and which carries a tube for the intake of air. The upper end of this

cylinder is closed with a two-holed cork carrying a thermometer and a glass tube for connection with the rest of the apparatus.

In preparation for an experiment, the aspirator is filled with water, the U tubes containing P_2O_5 are weighed and placed in the circuit with stop cocks closed, and lastly the stem of the plant is inserted in the cylinder. The stop cocks in the U tubes are then opened and the water started running from the aspirator, the speed with which the air is drawn over the twig being regulated according to its size and rate of transpiration. After all the water or a certain measured portion of it has flowed from the aspirator, the U tubes are closed, disconnected, and weighed and the amount of moisture absorbed by them determined. This moisture, however, includes not




FIG. 22.—Apparatus for the determination of transpiration by the Freeman method. *a*, aspirator. *b*, branch of plant. *gc*, glass cylinder. *p*, plant. *pc*, perforated cork for the entrance of a portion of the plant and air. *u*, tubes containing phosphorous pentoxide. *w*, water.

only that which escapes from the plant but also that contained in the air which is drawn through the apparatus. The amount of moisture contained in the volume of air that has been drawn over the leaf is determined by running a control experiment at the same time with the transpiration experiment. The amount of water lost by transpiration is obtained by subtracting the increase in weight of the tubes used for the normal air from the increase in weight of those used with the plant. After the experiment, the leaf area may be determined by any convenient method and the rate of transpiration calculated. This method of measuring transpiration is adapted to cases where the plants are too large to be grown in containers or where the whole plant cannot be sacrificed for the experiment. It is adapted to give quantitative data on the comparative rate of transpiration of different plants. The method, however, has some serious objections. In the first place, the leaves are placed under very abnormal conditions of temperature in the transpiration cylinder—the tempera-

ture being much higher than that of the open air. In the second place, unless great care is exercised in the selection of a small amount of leaf surface and in the rate at which air is drawn through the apparatus, the moisture escaping from the leaves cannot be removed rapidly enough to prevent its condensation upon the walls of the cylinder. Such a collection of moisture of course renders the experiment void. The period of time that must necessarily elapse in setting up the apparatus also tends to add considerable error.

G. THE SIGNIFICANCE OF TRANSPIRATION

Although transpiration has been studied, perhaps more thoroughly than any other plant process, very little is yet known concerning the significance of this function in the life of the plant. The opinions that have been expressed, in regard to the possible value of transpiration, vary all the way from those which ascribe to this function benefits to the plant that are as important as photosynthesis and respiration to those which assume that transpiration brings nothing to the plant but harm (Curtis, 1926). When the present data in regard to transpiration are surveyed, it must be admitted that its obvious harmful effects outweigh any of the benefits that might be attributed to the process.

It has frequently been stated in texts that transpiration cools the leaves and prevents their death or injury by high temperatures. The change of water from the liquid to the vapor form within a leaf does absorb a considerable amount of heat and this vaporization would thus tend to lower the temperature of the leaf. As previously mentioned, however, the average leaves are cooled by transpiration rarely more than 2 to 5°C.—a difference which, so far as our knowledge of protoplasm goes, could be of no marked benefit in preventing injurious effects. The death of leaves during hot, dry weather is apparently due to the excessive loss of water from the protoplasm rather than to any injury caused by an excessive increase in temperature. Thus it would seem that the injury to leaves which frequently occurs on hot days is due chiefly to the injurious drying effects of transpiration itself. Transpiration thus apparently is more harmful than beneficial on hot days when the cooling effects are most needed (Curtis, 1926).

It has frequently been stated that transpiration increases the rate and amount of absorption of solutes from the soil, but, as stated in Chap. V, conclusive experimental evidence indicates that there is no relationship whatsoever between the rate of transpiration and the amount of nutrients absorbed.

It has also been claimed that transpiration plays an important part in transferring solutes from the roots to the leaves in the transpiration stream or current. As Curtis (1926), however, points out, if the rate of removal of nutrients from the roots were largely determined by transpiration, the removal of solutes from the absorbing organs should increase

absorption. Increased transpiration should therefore increase absorption, but, as mentioned above, the experimental evidence indicates that it does not. The upward transpiration stream is in the xylem, so that if the transfer of solutes upward is in the phloem, as indicated by the work of Curtis, which will be discussed in Chap. XII, it seems apparent that transpiration can have little or no effect on their movement.

The loss of water by transpiration always results in a reduction of turgor of the cells, since the water lost cannot be instantaneously replaced. A slight reduction in turgor, however, has but little influence on the various processes of the plant, especially if there is an abundant supply of water in the soil to replace the loss from the plant. When, however, the moisture content of the soil is low, the decrease in turgor soon reaches a point where the reactions of the cells are greatly or completely retarded, so that death finally ensues.

It is estimated that more plants perish or are retarded in their development from a deficient water supply due primarily to its loss by transpiration than from all other factors combined, a fact which indicates that if transpiration is of any benefit to a plant, it may be attended by very dangerous effects.

Barnes (1902) considered that the significance of transpiration is to be seen in its origin and in tracing its development. Thus it is considered that the most primitive plants lived in water and absorbed the CO_2 and O_2 needed in the process of photosynthesis and respiration directly from this medium. In the course of their development, plants have apparently not modified to any great extent the manner of obtaining these two gases, so that under the present organization of the plants, exposed wet cell walls cannot be waterproofed on that account. Thus wherever moist cell surfaces are exposed to the atmosphere, evaporation of water must occur, so that transpirational loss must be considered unavoidable, although in itself it is a constant menace to the activity and life of the plant.

H. THE WATER REQUIREMENT OF PLANTS

The term "water requirement" in the most restricted sense is defined as the ratio of the number of units of water absorbed by the plant during the growing season to the number of units of dry matter produced by the plant during that time. In most cases, however, the dry matter considered in this relation is the amount harvested and in most instances includes all the plant except the roots. The water under consideration is in reality the amount lost through transpiration during the growing season, since of the total water absorbed the amount retained within the plant is very insignificant compared to the amount evaporated from it.

The term water requirement is a rather misleading one, since it seems to imply that it denotes the amount of water necessary for the growth of the plant. It merely, however, denotes that under certain conditions of climate, soil, and water supply, there was evaporated from the stem and leaves or retained within the plant and leaves water to the amount of so many times the number of units of dry matter produced. The water requirement of plants has been studied, for the most part, in those regions where water is a limiting factor in crop production, since it was formerly considered that there was a relationship between the ability of a plant to withstand drought and its water requirement. This relationship in the light of investigations, however, does not appear to exist.

1. Methods of Determining.—The methods of determining the water requirement of plants were, previous to 1910, not under very well-controlled conditions. A summary of the methods used previous to that time and the results thus obtained are discussed by Montgomery (1911), Briggs and Shantz (1913), and Kiesselbach (1916) in their review of the literature on the subject. Since 1910 the main work on water requirement has been reported by Briggs and Shantz (1913, 1914), Briggs and Piemeisel (1927) at Akron, Colo., Montgomery and Kiesselbach (1912), Kiesselbach (1916) in Nebraska, Miller (1916, 1923) in Kansas, and Khankoje (1914) and Thom and Holtz (1917) in Washington. The water requirement was determined by these investigators by growing the plants in large sealed containers after the manner described in the discussion of the weighing method for transpiration determinations. The containers are weighed at frequent intervals and the amount of water which has been lost from the soil is replaced by adding a known amount of water to the container by means of the watering devices that have previously been described.

After the plant or plants in a given container have reached maturity, they are harvested and the amount of dry matter determined by drying to a constant weight at a temperature of 100 to 105°C. The amount of water taken from the soil is known from the weights of the container at the beginning of the experiment and at its close and from the amounts of water which have been added from time to time during the season. The water requirement is determined by dividing the number of units of water absorbed during the season by the number of units of dry matter produced. Thus, for example, if a plant absorbs from the soil 251,020 g. of water and produces 652 g. of dry matter during the season, its water requirement would be $251,020/652$ or 385. The water requirement may be stated also in terms of the grain produced and is frequently determined in this manner when the plants under consideration are of importance in the production of grain. The measurement of the water requirement under field conditions has been attempted by Briggs and Shantz (1913), Thom and Holtz (1917), and others. The general method is to determine

the amount of water removed by the crop as shown by the difference between the initial and final water content combined with the rainfall entering the soil as determined by daily sampling. In some of the attempts, fallow plots are used to determine the loss of water from the soil by evaporation. Briggs and Shantz (1913) consider this method uncertain, owing to the difficulty of determining what proportion of the rainfall enters the soil and actually is used by the crop.

2. Factors Affecting the Water Requirement.—The water requirement of different plants varies greatly under the same conditions. Thus Briggs and Shantz (1913, 1914) and Briggs and Piemeisel (1927) found in their extensive work in Colorado that the water requirement of some 150 plants studied ranges from 216 for Kursk millet to 1,131 for *Franseria sp.*, a native weed. Thus *Franseria* evaporated five times as much water during the production of a unit of dry matter as did the millet. Briggs and Piemeisel (1927) summarized the variation in the water requirement in regard to the plants studied by them as follows: Considering the water requirement of proso millet as 1.00, the water requirement of the various crops would be: millets 1.07, sorghums 1.14, corn 1.31, barley 1.94, wheat 2.09, oats 2.18, rye 2.37, legumes 2.81, and grasses 3.10. In general, the millets, sorghums, and corns had the lowest water requirement, while the small grains, barley, wheat, oats, and rye lost almost twice as much water and the legumes almost three times as much per unit of dry matter produced as did the millets, sorghums, and corns.

Since the water requirement is the ratio between the amount of water taken up by the plant and the amount of dry matter produced, it is evident that its value will be affected by any factor that influences either transpiration or growth. Perhaps the most influential factor in this regard is the climatic complex which prevails during the growth of the plant.

a. Climatic Conditions.—The effect of air humidity on the water requirement is conclusively shown by the work of Montgomery and Kiesselbach (1912). Corn was grown in two greenhouses; in one the relative humidity was kept at 37 per cent during 12 hr. of the day, and in the other at 58 per cent for that time. The water requirement of the plants in the dry greenhouse was 340, while in the more humid greenhouse it was 191—the corn in the dry greenhouse having a water requirement 56 per cent higher than in the humid one. The range of the water requirement during different years due to prevailing climatic conditions is very great. Thus, for example, the lowest value for any one year at Akron averaged only about 60 per cent of that of the highest value. Some idea of the variation in the water requirement due to climatic conditions may be obtained from the following table, which gives the water requirement of some of the more common crop plants and a summary of the weather conditions in terms of evaporation from a free water surface:

WATER REQUIREMENT FOR THE YEARS 1911 TO 1917 AT AKRON, COLO., AND THE EVAPORATION IN INCHES FROM A FREE WATER SURFACE FROM APR. 1 TO SEPT. 1

Plant	1911	1912	1913	1914	1915	1916	1917
Alfalfa.....	1,068	657	834	890	695	1,047	822
Oats, Burt.....	639	449	617	615	445	809	636
Barley, Hannehen.....	527	443	513	501	404	664	522
Wheat, Kubanka.....	468	394	496	518	405	639	471
Corn, N W. Dent.....	368	280	399	368	253	495	346
Millet, Kursk.....	287	187	286	295	202	367	284
Sorghum, Red Amber.....	298	239	298	284	303	296	272
Evaporation, inches, April to September.....	48.8	37.7	43.0	41.8	33.4	47.1	42.7

Due to changes in weather conditions the loss of water from plants may vary as much as 600 per cent on successive days. Thus the weather conditions which prevail during a month or even so short a period as 10 days or a week may determine whether the water requirement is going to be high or low for that season. In this regard, Briggs and Shantz (1916) found that during a period of 10 days from July 7 to 16, 1914, many of the crop plants including wheat, barley, rye, corn, and Sudan grass lost 25 per cent of the total water transpired during the entire season. Richardson (1923) working in Australia found that in September to November, 80 per cent of the water lost from winter cereals was transpired, although the growing period was 7.5 months, while alfalfa in bloom transpired as much as 25 per cent of its total water in 3 days. The stage of development of the plant when certain climatic conditions occur also is an important factor in determining the value of the water requirement. If a high evaporating period occurs when the plant has as yet only a small leaf development, it may affect the water requirement but little, but if a high evaporation period of a week or ten days should occur when the full leaf development has been attained, it will greatly increase the value of the water requirement for that season. An example from the work of Miller (1923) will illustrate that point. In 1920 the water requirement of Sudan grass at Manhattan, Kans., was only 81 per cent of what it was in the previous year. The evaporation from a free water surface for May, June, July, and August during 1920 was 98.9 per cent of that in 1919. It would seem that the difference in the water requirement for the two years should be small. The evaporation, however, during August when the Sudan grass had reached its full leaf development was in 1920 only 83 per cent of that of 1919—a difference which is very comparable to the difference in the water requirement for the two years.

b. Soil Fertility.—Many investigations have been made concerning the effects of the fertility of the soil on the water requirement. Almost without exception, the application of fertilizers to the soil has shown a

reduction of the water requirement. In very productive soils this reduction is extremely slight, but in poor soils the water requirement may be reduced one half and sometimes as much as two thirds by the application of nutrients. When the supply of nutrients in the soil approaches exhaustion, the rate of growth of the plant is greatly reduced, but no corresponding change occurs in the transpiration rate. This fact is evidence that transpiration is not a measure of growth. An example to illustrate the effect of soil fertility on the water requirement may be taken from the work of Kiesselbach (1916). He grew corn in an infertile soil *a*, a fertile soil *c*, and an intermediate soil *b* composed of equal parts of *a* and *c*. The amount of dry matter produced and the water requirement obtained were as follows:

Soil	Dry matter produced, grams	Water requirement
<i>a</i>	113	550
<i>b</i>	184	479
<i>c</i>	270	392

By the application of sheep manure in equal amounts to soils *a*, *b*, and *c*, the dry matter was increased 194, 79, and 41 per cent and the total water transpired 106, 43, and 29 per cent in the order named, but the water requirement by this treatment was reduced 29, 17, and 8 per cent, respectively.

The effect of the fertility of the soil is shown indirectly when the relation of the volume of soil in which the plants are growing is considered in relation to the water requirement. Much of the experimental data that have been reported in regard to water requirement are in error because the plants were grown in such a small volume of soil that they did not mature normally due primarily to an insufficient nutrient supply for the plant. In such cases, as the volume of soil is increased the water requirement is reduced within certain limits. Thus Kiesselbach (1916) found that when he used various amounts of soil he obtained the following results with corn:

Amount of soil used, pounds	Dry matter produced, grams	Water requirement
32	97.5	411
85	205.7	362
150	316.0	341
239	442.0	277
583	627.0	290
956	728.0	240

In these cases when $1\frac{3}{4}$ lb. of sheep manure was added to each can, the water requirement was 322, 311, 304, 272, 269, and 252, respectively. These results indicate that the nutrients contained in the volumes of soil used were in most cases insufficient for the plant's needs.

c. Soil Moisture.—The experiments that have been reported in regard to soil moisture and the water requirement show, as a rule, an increase in the water requirement when the soil moisture content approaches either extreme (Briggs and Shantz, 1913). Kiesselbach (1916) obtained in the case of corn a maximum production of dry matter when the water content of the soil was at approximately 70 per cent of saturation. The average for three years showed that the reduction of the moisture content below the optimum reduced the water requirement 7.9 per cent but that this was accompanied by a 30.7 per cent lower yield of dry matter. An increase in the soil moisture content above the optimum for the three years increased the water requirement 8.2 per cent, but this was accompanied by a 16.7 per cent lower yield of dry matter.

III. LOSS OF WATER FROM PLANTS IN THE LIQUID FORM. GUTTATION

The loss of water in the form of liquid from the uninjured leaf or stem of the plant is called "guttation." Guttation occurs, for the most part, under conditions which are favorable for the absorption of water by the roots but conducive to reduced evaporation from the leaves. Cool nights following warm days provide excellent conditions for this phenomenon. The soil retains warmth and absorption is very active, while the air is cool and humid and transpiration is reduced almost to zero. Although guttation occurs, for the most part, at night, it may occur in daylight if the proper conditions prevail and it may be caused in many plants at any time by artificial means. The water of guttation usually collects in drops along the edges and at the tips of leaves, but in some cases it appears over the entire leaf surface when conditions are very favorable. The water exuded in the case of the sorghums and sometimes corn is so abundant that it runs down the leaves and collects in the leaf axils. Under the conditions of the Great Plains it is not uncommon for the sorghum leaves to be very badly wilted during the day yet recover their turgidity at night and form abundant water of guttation.

In the tropics, guttation occurs to a greater extent than under conditions of the temperate region, since at night the air is very humid, while the soil is warm, making conditions ideal for absorption. The water of guttation, especially on the leaves of cereals and grasses, is frequently mistaken for dew. The process of guttation has been observed for a large range of plants, and Burgerstein (1920) lists 333 genera and 115 families of plants for which guttation has been reported.

The quantity of water lost by guttation is often considerable, the largest recorded amount being 100 cc. for a single night from a young leaf

of *Colocasia nymphaefolia*. In this case, the water is exuded near the tip of the leaf and is actually forced out or ejected in drops which follow one another in rapid succession. It is stated by some observers that in the tropics in the early morning the bamboos in dense growths produce a fine mist due to the loss of water by guttation.

The water of guttation in most cases escapes from the plant through more or less specialized organs called "hydathodes." These organs are generally located on the leaves and their structure is subject to a considerable amount of variation. There are two main types of hydathodes in their relation to the vascular system. The one type has no direct connection with the water-conducting system. The hydathodes of this group are purely epidermal structures such as specialized hairs, conical protrusions, and other forms of modified epidermal cells.

The other type, called generally the "epithem hydathode," is characterized by the fact that it is in direct communication with the water-conducting system. One of the most common forms of hydathodes of this type opens to the outside through a water stoma beneath which is located a mass of thin-walled cells loosely arranged and called the "epithem" which borders directly upon the xylem elements of the fibrovascular bundle. The main distinction between the water stomata or water pores and the ordinary stomata consists in the fact that the guard cells of water stomata have lost their power of adjustment to a large extent. They are located at the end of a fibrovascular bundle and are generally much larger. Haberlandt (1914) states that they usually become stationary at a very early stage of development, while in some cases from the first they are incapable of movement.

Lepeschkin (1923) noted that when the edge of the leaf bearing the epithem hydathode is severed and laid with its cut surface in water, guttation does not occur. Flood (1919) noted that when the tip of the leaf of *Colocasia antiquorum* is anaesthetized, the exudation of water continues at the normal rate. Both these investigators conclude that their experimental results indicate that guttation in the case of epithem hydathodes is simply a process of filtration, the force being supplied by sap pressure which in some cases may also force the water through the ordinary stomata.

The water exuded from the purely epidermal hydathodes is apparently purely water of excretion, the cells of the hydathode themselves developing the force necessary for such an excretion process. It seems, however, that an exudation pressure or sap pressure must be set up in the conducting system before this type of hydathode will function. The rôle that the sap pressure here plays seems to be that of a stimulus which sets the action of these hydathodes in motion.

The water excreted in guttation is not pure but contains a small amount of total solids. One of the most recent and thorough investiga-

tions on this subject was conducted by Wilson (1923). He found that the total solids in the water of guttation from corn plants growing under non-sterile conditions amounted to 1,030 ppm. The total solids in water from timothy plants growing under sterile conditions was 573 ppm. in one case and 220 ppm. in another. In all cases, the total solids were more than one-half organic matter. In the guttation water from corn, oats, and timothy reactions were obtained which indicated the presence of nitrates, nitrites, catalases, and peroxidases, but the presence of reductases was uncertain. Materials were present also which were capable of reducing methylene blue. The P_{H} value of the exudate from young plants was found neutral, but the acidity increased as the plants became older.

The physiological significance of the hydathodes and of the loss of water by guttation is not definitely known. This escape of water from the plant would seem to be a means of regulating the turgor of the leaves and prevent it from becoming so high as to interfere with the metabolism of the cells when transpiration is almost or completely suppressed. This, however, is purely an assumption and is based upon no experimental evidence whatsoever.

Questions

280. Name and discuss the main functions that water serves in the plant. What amount of water is needed for each of these functions?

281. What is transpiration? How does its rate vary during the daylight hours? During the day and night?

282. Give some data to show the total amount of water transpired by plants during their growing season. From an acre of plants. How can the latter data be determined?

283. Under the following headings show how the general structure of the leaf is conducive to water loss: (a) the leaf surface, (b) the distribution of the veins, (c) intercellular spaces, (d) nature and arrangement of the parenchyma cells, (e) nature of the epidermis.

284. For what functions is the leaf apparently adapted? Why do different plants differ in their transpiration rates under the same conditions? Give examples.

285. What are the following: (a) stoma, (b) stomata, (c) guard cells, (d) subsidiary cells, (e) stomatal apparatus?

286. Give some examples to show the relative number of stomata on the upper and lower surfaces of the leaves of various crop plants. Which plants have the greatest number of stomata per unit area? Which have the least?

287. Give some data to show the variation in the number of stomata during different growing seasons. How is the number of stomata influenced by humid conditions? By dry conditions? Why? How is the number of stomata influenced by rusts?

288. What is the stomatal index? How does the number of stomata compare on the upper and lower portion of the plant? On different parts of the leaf? What is Zalenski's law? What portion of the total leaf surface do the stomata compose?

289. What seems to be the general principles underlying the opening and closing of the stomata? How do the chloroplasts of the guard cells differ from those of the

cells of the mesophyll? How does the green coloring matter of the guard cells differ from that of the mesophyll cells?

290. How do the guard cells differ from the ordinary epidermal cells in regard to plastids? In regard to osmotic pressure? In regard to changes in osmotic pressure during the day? Give examples.

291. How does the carbohydrate content of the guard cells vary during the day? How is this correlated with the concentration of their cell sap? What seems to be the origin of the carbohydrates in the guard cells?

292. How does the acidity of the cell sap of the guard cells change with the opening and closing of the stomata? Enumerate in detail the series of changes which are considered to occur in the guard cells in the opening of a stoma of a turgid leaf. What changes occur in the closing of the stoma?

293. Explain in detail how changes in the turgidity of the guard cells might be caused by colloidal imbibition and colloidal dehydration?

294. Name and describe the three methods that have been used for measuring the changes of stomatal aperture? What are advantages and disadvantages of each method?

295. How does light affect the opening and closing of the stomata? The temperature? The humidity of the air? The moisture content of the leaf?

296. Discuss the daily movement of the stomata of the alfalfa leaf under optimum, severe, and extreme conditions of evaporation and water supply. Enumerate the plants which have stomata that behave in this manner.

297. How do the stomata of the leaves of the potato behave under different conditions of evaporation and water supply during a 24-hr. period? What plants have stomata that behave in this manner?

298. What peculiarities of movement do the stomata of cereals have? What conditions are favorable for the opening of the stomata of corn and sorghum? For the opening of the stomata of wheat, oats, and barley?

299. In what two ways has it been proved that the main loss of water from the leaf takes place through the stomata? Distinguish between stomatal and cuticular transpiration. How do they compare in amount? When is cuticular transpiration the most significant? Why?

300. State the general law in regard to the amount of gas diffusing through a relatively large opening in a unit of time. Through a minute opening. Give examples.

301. How does the decrease in area of a small opening affect the velocity of gaseous flow? What is the relation of the amount of gas diffusing through a small pore in a membrane as compared with the same area of cross-section in which no membrane is interposed? Why? Give examples.

302. How must pores in a membrane be spaced in order to allow for the maximum diffusion of gases through them? Why? How are the stomata arranged in this regard?

303. How does the diffusion of gas through a small elliptical opening compare with that through a circular opening? What capacity do the stomata have for the diffusion of CO_2 as compared with the needs of the leaf for this gas? What capacity do the stomata have for the diffusion of water vapor as compared with the maximum transpiration rates? Give examples.

304. What is meant by the active regulation of water loss by the stomata? Passive regulation? To what degree must the stomata close in order to hinder the loss of water vapor? Enumerate the factors that influence the rate of diffusion of water vapor through the stoma.

305. Discuss the daily variation of the water content of leaves and its relation to stomatal movement. What is meant by the working margin of water in the leaf? How may the closing of the stomata restore this margin?

306. What is the relation between the number of stomata and the rate of transpiration?

307. What is the relation of the change in stomatal opening to the rate of transpiration? How might the rate of transpiration be increased as the stomata are closing?

308. What is the state of the water content of the air in the intercellular spaces when the stomata close? When is the transpiration rate influenced by the factors of evaporation alone? When by the stomata?

309. What are the two main types of epidermal hairs? How do hairs affect stomatal transpiration? Cuticular transpiration? How can this be shown?

310. Name some of the structural characters that are commonly associated with the xerophytic leaf. Which is the most striking of these characteristics? What relationship is there between the xerophytic characters of leaves and their rates of transpiration?

311. How may the concentration of the cell sap affect the rate of transpiration? Why? How may the colloids of the protoplasm and cell wall influence the transpiration rate?

312. How does incipient drying or wilting affect the transpiration rate? Why? Explain by means of a filter-paper apparatus.

313. How does the extent of leaf surface influence incipient drying and the rate of transpiration? Why? At what stage of development is this influence most marked? At what period of the day? Why? Give examples.

314. How may the nature of the root system affect the transpiration rate? Give examples.

315. What is impinging solar radiation? How is its intensity expressed? What is direct solar radiation? Indirect solar radiation?

316. How does solar radiation affect the other cyclic environmental factors? What is the relation of the radiation curve to the transpiration curves of wheat, oats, rye, sorghum, and alfalfa? What is the value of the correlation coefficient of transpiration with radiation?

317. What is the value of the correlation coefficient of transpiration with temperature? With relative humidity? What do these values indicate? How do marked changes in temperature and relative humidity during the night affect the transpiration rate? What does this indicate?

318. How does light influence the rate of transpiration? How has this been determined? To what causes may the increased transpiration rates due to light be attributed?

319. What is meant by the evaporating power of the air? How does it differ from impinging solar radiation on the evaporation of water? How may it act in a negative manner?

320. How does the temperature curve during the day correspond with the transpiration rate? Give examples.

321. What is meant by the depression of the wet-bulb thermometer? How does the relative humidity of the air affect transpiration? Why is transpiration not zero in saturated air?

322. In what two general ways may wind influence the rate of transpiration? Why does it increase the rate of transpiration more from small mature leaves than from large ones? How do gentle air currents and strong air currents affect the rate of transpiration? What proportion of transpiration loss may be attributed to the action of the wind?

323. How does the moisture content of the soil affect the rate of transpiration? Why is the difference between the transpiration rates of wilted and turgid plants less in the morning and evenings than during the day?

324. How may the addition of chemicals to the soil increase the transpiration rate? How decrease it? How do acids affect transpiration? Alkalies? Tannic acid? Carbon black or ferric hydroxide applied to the soil? Why?

325. How do films from sprays affect the rate of transpiration of abscised leaves? Of intact plants? Give examples in each case. After what manner is this determined?

326. How is the rate of transpiration of the cereals affected by rusts? Of apple leaves? Of sunflower leaves? Of cocklebur leaves? Why the differences in effects? Name some other fungi that affect the transpiration of their hosts.

327. Name six factors that may influence the temperature of a leaf. What methods have been used for determining the temperature of leaves? What is a thermocouple or thermo junction? Explain in detail the apparatus used in determining the temperature of a leaf by the thermocouple method.

328. Explain in detail how the apparatus above mentioned may be calibrated and the readings observed reduced to degrees of temperature. What are the advantages of the thermocouple method?

329. Why are there such sudden and marked fluctuations in the temperature of the air? Why are these differences not detected by the thermometer?

330. How does the temperature of a turgid leaf in the sun compare with the air temperature? Why? How does the temperature of a turgid leaf in the shade compare with the air temperature? Why?

331. How does the temperature of a turgid leaf in the sun compare with that of a wilted leaf? Why? How do air currents affect the temperature of leaves?

332. To what degree is the temperature of a leaf lowered by transpiration? Give examples. What relationship is there between this lowering of temperature to the thermal death point of the leaves?

333. Why is evaporation studied in relation to transpiration? How does the loss of water from transpiration compare with that from a free water surface? Give examples.

334. What is the value of the correlation coefficient between transpiration and evaporation? Upon what does this value depend? In what two ways is a knowledge of the evaporation rate important in considering the water relations of plants?

335. What is an atmometer or evaporimeter? Why cannot the loss of water from one type of instrument be reduced to that of another type? Illustrate by an example. What are the two general types of atmometers?

336. Describe in detail the small and the large tank which are used in determining the rate of evaporation and state the advantages and disadvantages of each.

337. What types of moist porous surface atmometers have been used? What is the Bellani plate? The spherical and cylindrical porous-clay cup atmometers?

338. Explain in detail how a porous-clay cup atmometer should be set up. Explain how such atmometers may be standardized.

339. What is absolute transpiration? How does its curve compare with that of evaporation? What is relative transpiration, transpiring coefficient, or the transpiring power of the plant?

340. What is the nature of the graph of relative transpiration? What has this been considered to indicate? What is the objection to this assumption?

341. When does the rate of evaporation from atmometers depart most widely from the transpiration rate? Why must the plant as well as the evaporation instrument be taken into consideration in studying relative transpiration?

342. In what two ways may the rate of transpiration be expressed? In what five ways may the leaf surface of a plant be determined?

343. Name the four methods that have been used to measure the rate of transpiration. Describe the potometer method and state its objections and advantages.

- 344.** Describe in detail the weighing method for determining the rate of transpiration. What are the advantages and disadvantages of this method?
- 345.** Describe in detail the cobalt chloride method for measuring transpiration in regard to the preparation of the hygrometric paper, the preparation of standard colors, and the standard evaporation surface.
- 346.** What is the index of transpiring power? How does it vary? What are the advantages of the cobalt chloride method? The disadvantages?
- 347.** How may the cobalt chloride method be modified in order to express the water loss in absolute units? Describe Freeman's method for measuring transpiration. What are its advantages? Its disadvantages?
- 348.** Discuss the advantages and disadvantages of transpiration to the plant.
- 349.** What is meant by the water requirement of a plant? Why has it been studied? How is the water requirement determined?
- 350.** How does the water requirement vary for different plants? For different climatic conditions? Give examples.
- 351.** How is the water requirement affected by the fertility of the soil? Why? How does the amount of moisture in the soil affect the water requirement?
- 352.** What is guttation? Under what conditions does it occur? Through what parts of the leaf and stem does the water of guttation escape? What is the composition of the water of guttation?
- 353.** What are the hydathodes? Distinguish between the two types. In which type is the water of guttation purely an excretion? In which a pure process of filtration? How is this proved? What is the physiological significance of the hydathodes and the loss of water by guttation?

Bibliography

- ANDERSON, A. P., 1897: Stomata on the bud scales of *Abies pectinata*, *Bot. Gaz.*, **24**: 294-295.
- ASKENASY, E., 1875: Über die Temperatur, welche Pflanzen im Sonnenlicht annehmen, *Bot. Zeitung*, **33**: 441-444.
- BABINET, M., 1848: Note sur un atmidoscope, *Compt. Rend. Acad. Sci. Paris*, **26**: 529-530.
- BAKKE, A. L., 1914: Studies of the transpiring power of plants as indicated by the method of standardized hygrometric paper, *Jour. Ecol.*, **2**: 145-173.
- , and B. E. LIVINGSTON, 1916: Further studies on foliar transpiring power in plants, *Physiol. Res.*, **2**: 51-71.
- BALLS, W. L., 1912: The stomatograph, *Proc. Roy. Soc. London*, B, **85**: 33-44.
- BARNES, C. R., 1902: The significance of transpiration, *Science*, n.s., **15**: 460.
- BAYER, L., 1902: Beitrag zur pflanzenphysiologischen Bedeutung des Kupfers in der Bordeaux-Brühe, *Inaug. Diss. Königsberg*.
- BELLANI, A., 1820: Descrizione di un mivo amidometro per servire di continuazione e fine alle riflessioni critiche intorno all' evaporazione, *Gior. Fis. Chim.*, **3**: 166-177.
- BESSEY, CHARLES E., 1898: Some considerations upon the functions of the stomata, *Science*, n.s., **7**: 13-16.
- BLACKMAN, F. F., 1895: Experimental researches on vegetable assimilation and respiration. II, On the paths of gaseous exchange between aerial leaves and the atmosphere, *Phil. Trans. Roy. Soc. London*, **186**: 503-562.
- , 1895: Experimental researches on vegetable assimilation and respiration. I, On a new method of investigating the carbonic acid exchanges of plants, *Phil. Trans. Roy. Soc. London*, **186**: 485-502.
- and G. L. C. MATTHAEI, 1905: Experimental researches on vegetable assimilation and respiration. IV, A quantitative study of carbon-dioxide assimilation

- and leaf-temperature in natural illumination, *Proc. Roy. Soc. London*, B, **76**: 402-460.
- BLACKMAN, V. H., and S. G. PAINE, 1914: A recording transpirometer, *Ann. Bot.*, **28**: 109-113.
- and R. C. KNIGHT, 1917: A method of controlling the rate of air movement in transpiration experiments, *Ann. Bot.*, **31**: 217-220.
- BLAYDES, G. W., 1928: A survey of rate of water loss from leaves, *Ohio Jour. Sci.*, **28**: 99-118.
- BLODGETT, F. H., 1901: Transpiration of rust-infected *Rubus*, *Torreya*, **1**: 34-35.
- BOUYOUCOS, G. J., 1911: Transpiration of wheat seedlings as affected by soils, by solutions of different densities, and by various chemical compounds, *Jour. Amer. Soc. Agron.*, **3**: 130-191.
- BRIGGS, L. J., and H. L. SHANTZ, 1913: The water requirement of plants. I, Investigations in the Great Plains area in 1910 and 1911, *Bur. Plant Ind. Bull.* 284.
- and ———, 1913: The water requirement of plants. II, A review of the literature, *Bur. Plant Ind. Bull.* 285.
- and ———, 1914: The relative water requirement of plants, *Jour. Agr. Res.*, **3**: 1-65.
- and ———, 1915: Influence of hybridization and cross-pollination on the water requirement of plants, *Jour. Agr. Res.*, **4**: 391-403.
- and ———, 1915: An automatic transpiration scale of large capacity for use with freely exposed plants, *Jour. Agr. Res.*, **5**: 117-133.
- and ———, 1916: Daily transpiration during the normal growth period and its correlation with the weather, *Jour. Agr. Res.*, **7**: 155-213.
- and ———, 1916: Hourly transpiration rate on clear days as determined by cyclic environmental factors, *Jour. Agr. Res.*, **5**: 583-651.
- and ———, 1917: Comparison of the hourly evaporation rate of atmometers and free water surfaces with the transpiration rate of *Medicago sativa*, *Jour. Agr. Res.*, **9**: 277-293.
- BROOKS, CHARLES, and D. F. FISHER, 1926: Some high-temperature effects in apples: Contrasts in the two sides of an apple, *Jour. Agr. Res.*, **32**: 1-17.
- BROWN, H. T., and F. ESCOMBE, 1900: Static diffusion of gases and liquids in relation to the assimilation of carbon and translocation in plants, *Phil. Trans. Roy. Soc.*, B, **193**: 223-291; *Ann. Bot.*, **14**: 537-542; *Proc. Roy. Soc.*, B, **67**: 124-128.
- and ———, 1905: Researches on some of the physiological processes of green leaves, with special reference to the interchange of energy between the leaf and its surroundings, *Proc. Roy. Soc. London*, B, **76**: 29-111.
- BROWN, M. A., 1910: The influence of air currents on transpiration, *Proc. Iowa Acad. Science*, **17**: 13-15.
- BURGERSTEIN, ALFRED, 1885: Ueber einige physiologische und pathologische Wirkungen des Kampfers auf die Pflanzen, insbesondere auf Laubespresse, *Verh. Zool-bot. Ges. Wien.*, **34**: 543.
- , 1904: "Die Transpiration der Pflanzen," pp. 283, Jena, Gustav Fischer.
- , 1920: "Die Transpiration der Pflanzen," II, pp. 262, Jena, Gustav Fischer.
- , 1920: Änderungen der Spaltöffnungsweite unter dem Einfluss verschiedener Bedingungen, *Verh. Zool-bot. Ges. Wien*, 113-131.
- BURNS, G. P., 1915: The relative transpiration of white pine seedlings, *Plant World*, **18**: 1-6.
- BUSCALIONI, L., and G. POLLACCI, 1902: Alteriovi ricerche sull' applicazione delle pellicole di collodio allo studio di alcuni processi fisiologici della pianta ed in particolare modo della transpirazione vegetale, *Att. Inst. Bot. Univ. Pavia*, n.s., **7**.
- CLAPP, G. L., 1908: A quantitative study of transpiration, *Bot. Gaz.*, **45**: 254-267.

- CLINTON, G. P., 1909: Spraying potatoes in dry seasons, *Conn. Agr. Expt. Sta. Bien. Rept.* 739-752.
- CLUM, H. H., 1926: The effect of transpiration and environmental factors on leaf temperatures. I, Transpiration, *Amer. Jour. Bot.*, **13**: 194-216.
- , 1926: The effect of transpiration and environmental factors on leaf temperatures. II, Light intensity and the relation of transpiration to the thermal death point, *Amer. Jour. Bot.*, **13**: 217-231.
- COPELAND, E. B., 1902: The mechanism of stomata, *Ann. Bot.*, **16**: 327-365.
- , 1906: On the water relations of the coconut palm, *Phil. Jour. Sci.*, **1**: 6-58.
- COWLES, H. C., 1910: "A Textbook of Botany," Vol. II, "Ecology," American Book Company.
- CULLINAN, F. P., 1920: Transpiration studies with the apple, *Proc. Amer. Soc. Hort. Sci.*, **17**: 232-240; *Bot. Abst.*, **9**: 226.
- CURTIS, O. F., 1926: What is the significance of transpiration? *Science*, n.s., **63**: 267-271.
- DARWIN, F., 1898: Observations on stomata, *Proc. Roy. Soc. London*, B, **63**: 413-417.
- , 1898: Observations on stomata, *Phil. Trans. Roy. Soc.*, B, **190**: 531-621.
- , 1904: On a self-recording method applied to the movements of stomata, *Bot. Gaz.*, **37**: 81-105.
- , and D. F. M. PERTZ, 1912: On a new method of estimating the aperture of stomata, *Proc. Roy. Soc. London*, B, **84**: 136-154.
- , 1914: The effect of light on the transpiration of leaves, *Proc. Roy. Soc. London*, B, **87**: 281-299.
- , 1916: On the relation between transpiration and stomatal aperture, *Phil. Trans. Roy. Soc. London*, B, **207**: 413-437.
- DIXON, H. H., 1898: Transpiration into a saturated atmosphere, *Proc. Roy. Irish Soc.*, III, **4**: 627-635; *abs. Bot. Centrbl.*, **76**: 135.
- , 1914: "Transpiration and the Ascent of Sap in Plants," Macmillan & Co., Ltd.
- DODGE, B. O., 1923: Effect of the orange-rusts of *Rubus* on the development and distribution of stomata, *Jour. Agr. Res.*, **25**: 495-501.
- DOLE, E. J., 1924: Studies on the effect of air, temperature and relative humidity on the transpiration of *Pinus Strobus*, *Vt. Agr. Expt. Sta. Bull.*, 238.
- DOSDALL, L., 1919: Water requirement and adaptation in *Equisetum*, *Plant World*, **22**: 1-13; 29-44.
- DRABBLE, E., and HILDA DRABBLE, 1907: The relation between the osmotic strength of cell sap in plants and their physical environment, *Biochem. Jour.*, **2**: 117-132.
- DUFRENOY, J., 1918: Les facteurs physiques de la transpiration chez les plantes et la transpiration des feuilles parasitées, *Rev. Gen. Sci. Ann.*, **29**: 565-566.
- DUGGAR, B. M., 1911: "Plant Physiology," pp. 92-93, The Macmillan Company.
- , and J. S. COOLEY, 1914: The effect of surface films and dusts on the rate of transpiration, *Ann. Mo. Bot. Gard.*, **1**: 1-23.
- , and ———, 1914: The effect of surface films on the rate of transpiration. Experiments with potted potatoes, *Ann. Mo. Bot. Gard.*, **1**: 351-357.
- and W. W. BONNS, 1918: The effect of Bordeaux mixture on the rate of transpiration, *Ann. Mo. Bot. Gard.*, **5**: 153-176.
- EATON, F. M., and G. O. BELDEN, 1929: Leaf temperatures of cotton and their relation to transpiration and varietal differences and yields, *U. S. Dept. Agr. Tech. Bull.* 91.
- ECKERSON, SOPHIA H., 1908: The number and size of stomata, *Bot. Gaz.*, **46**: 221-224.
- EHLERS, J. H., 1915: The temperature of leaves of *Pinus* in winter, *Amer. Jour. Bot.*, **2**: 32-70.

- FLOOD, M. G., 1919: Exudation of water by *Colocasia antiquorum*, *Sci. Proc. Roy. Dublin Soc.*, **15**: 505-512.
- FRANK, A. B., and F. KRÜGER, 1894: Ueber den Reiz, welchen die Behandlung mit Kupfer auf die Kartoffelpflanze hervorbringt, *Ber. d. d. bot. Ges.*, **12**: 8-11.
- , and ———, 1894: Ueber den direkten Einfluss der Kupfervitriolkalkbrühe auf die Kartoffelpflanze, *Arb. d. d. landw. Ges.*, **1894**: 1046.
- FREEMAN, G. F., 1908: A method for the quantitative determination of transpiration in plants, *Bot. Gaz.*, **46**: 118-129.
- , 1920: Studies in evaporation and transpiration, *Bot. Gaz.*, **70**: 190-211.
- FREJ, L., 1924: Influence of soil moisture on the transpiration capacity of plants, (Russian) *Bull. Soc. Nat. Leningrad*, **53**: 179-210; abst. in *Bot. Abst.*, **15**: 164-165.
- GANEAU DE LAMARLIÈRE, L., 1892: Recherches physiologiques sur les feuilles, développées à l'ombre et au soleil. VI, Transpiration, *Rév. Gén. Bot.*, **4**: 529.
- GANONG, W. F., 1905: New precision appliances for use in Plant Physiology. II, *Bot. Gaz.*, **39**: 145-152.
- GERDEL, R. W., and R. M. SALTER, 1928: Measurement of leaf area using the photoelectric cell, *Jour. Amer. Soc. Agron.*, **20**: 635-643.
- GIDDINGS, L. A., 1914: Transpiration of *Silphium laciniatum*, *Plant World*, **17**: 309-328.
- GRAY, JOHN, and GEORGE J. PEIRCE, 1919: The influence of light upon the action of stomata and its relation to the transpiration of certain grains, *Amer. Jour. Bot.*, **6**: 131-156.
- HABERLANDT, G., 1914: "Physiological Plant Anatomy," Eng. transl., pp. 493-498.
- HAGEN, FRITZ, 1918: Zur Physiologie des Spaltöffnungsapparates, *Beitr. Allg. Bot.*, **1**: 260-291; *Bot. Abst.*, **13**: 63-64.
- HARTER, L. L., 1908: The influence of a mixture of soluble salts, principally sodium chloride, upon the leaf structure and transpiration of wheat, oats, and barley, *U. S. Dept. Agr. Bur. Plant Ind., Bull.* 134.
- HAWKINS, R. S., 1927: Variations of water and dry matter in the leaves of Pina and Acala cotton, *Ariz. Sta. Tech. Bull.* **17**: 417-444.
- HENDERSON, F. Y., 1926: On the effect of light and other conditions upon the rate of water-loss from the mesophyll, *Ann. Bot.*, **40**: 507-535.
- HENDRICKSON, A. H., 1921: Transpiration rate of deciduous fruit trees as influenced by irrigation and other factors, *Amer. Soc. Hort. Sci. Proc.* **18**: 145-147.
- , 1926: Certain water relations of the genus *Prunus*, *Hilgardia*, **1**: 479-524.
- HOWES, F., 1923: Researches on the vegetation of Natal. Ser. I. Section II. A new calcium chloride method of measuring the resistance to water loss in leaves, *Mem. Bot. Survey S. Africa*, **5**: 23-33; *Bot. Abst.*, **13**: 925.
- HUBER, BRUNO, 1923: Transpiration in verschiedener Stammhöhe. I, *Sequoia gigantea*, *Zeitschr. Bot.*, **15**: 465-501; *Bot. Abst.*, **14**: 1218.
- ILJIN, W. S., 1914: Die Regulierung der Spaltöffnungen in Zusammenhang mit Veränderung des osmotischen Druckes, *Beih. Bot. Centrbl.*, **32**: 15-35.
- IWANOFF, L. A., and M. M. THIELMANN, 1923: Über den Einfluss des Lichtes verschiedener Wellenlänge auf die Transpiration der Pflanzen, *Flora*, **116**: 296-311.
- JEFFREYS, H., 1918: Some problems of evaporation, *Phil. Mag. Jour. Sci.*, 6 ser., **35**: 270-280.
- JIVANNA RAO, P. S., 1923: Stomata in cotton flower, *Jour. Madras Agr. Student Union*, **11**: 40-42; *Bot. Abst.*, **13**: 886.
- JOHNSTON, E. S., 1918: A simple non-absorbing atmometer mounting, *Plant World*, **21**: 257-261.
- , 1920: A method of studying the absorption-transpiration ratio in nutrient media, *Science*, n.s., **52**: 517-518.

- JONES, W. N., 1914: A self recording porometer and potometer, *New Phytol.*, **13**: 353-364.
- KHANKOJE, P., 1914: Some factors which influence the water requirement of plants, *Jour. Amer. Soc. Agron.*, **6**: 1-23.
- KIESSELBACH, T. A., and A. M. MONTGOMERY, 1911: The relation of climatic factors to the water used by the corn plant, *Nebr. Agr. Expt. Sta. Rept.* **1911**: 91-107.
- , 1916: Transpiration as a factor in crop production, *Nebr. Expt. Sta. Res. Bull.* **6**.
- KNIGHT, R. C., 1915: A convenient modification of the porometer, *New Phytol.*, **14**: 212-216.
- , 1916: On the use of the porometer in stomatal investigation, *Ann. Bot.*, **30**: 57-76.
- , 1917: The interrelations of stomatal aperture, leaf water-content and transpiration rate, *Ann. Bot.*, **31**: 221-240.
- , 1917: Relative transpiration as a measure of the intrinsic transpiring power of the plant, *Ann. Bot.*, **31**: 351-359.
- , 1922: Further observations on the transpiration, stomata, leaf water-content, and wilting of plants, *Ann. Bot.*, **36**: 361-385.
- KUYPER, J., 1915: Contributions to the physiology of stomata in *Saccharum officinarum*, *Arch. Siukerindus. Nederland. Indie.*, **23**: 1673-1700; *Expt. Sta. Rec.* **35**: 330.
- LADBLOW, C. G. P., and R. C. KNIGHT, 1916: A description of a recording porometer and a note on stomatal behavior during wilting, *Ann. Bot.*, **30**: 47-57.
- LAMOR, J., 1918: On transpiration through leaf stomata, *Phil. Mag. Jour. Sci.*, 6 ser., **35**: 270-280.
- LEICK, E., 1928: Ueber das verschieden artige Verhalten der unterseitigen und überseitigen Stomata desselben Blattes, *Ber. d. d. bot. Ges.*, **45**: 28-42.
- LEITBEG, H., 1868: Beiträge zur Physiologie der Spaltöffnungsapparate, *Graz. Bot. Inst. Mitt.*, **1**: 123.
- LEPESCHKIN, W. W., 1923: Über aktive und passive Wasserdruzen und Wasserspalten, *Ber. d. d. bot. Ges.*, **41**: 298-300; *Bot. Abst.*, **13**: 925.
- LESAGE, PIERRE, 1894: Sur les rapports des pallisades dans les feuilles avec la transpiration, *Compt. Rend. Acad. Sci. Paris.*, **118**: 255-258.
- LIVINGSTON, B. E., 1906: The relation of desert plants to soil moisture and to evaporation, *Carnegie Inst. Wash. Pub.* 50.
- , 1907: Evaporation and plant development, *Plant World*, **10**: 269-276.
- , 1907: Relative transpiration in cacti, *Plant World*, **10**: 110-114.
- , 1908: Evaporation and plant habitats, *Plant World*, **11**: 1-9.
- , 1908: A method for controlling plant moisture, *Plant World*, **11**: 39-40.
- , 1909: Stomata and transpiration in *Tradescantia zebrina*, *Science*, n.s., **29**: 269-270.
- , 1910: Operation of the porous cup atmometer, *Plant World*, **13**: 111-119.
- , 1910: A rain-correcting atmometer for ecological instrumentation, *Plant World*, **13**: 79-82.
- , 1911: Paper atmometers for studies in evaporation and plant transpiration, *Plant World*, **14**: 281-289.
- , 1911: A study of the relation between summer evaporation intensity and centers of plant distribution in the United States, *Plant World*, **14**: 205-222.
- , 1911: Light intensity and transpiration, *Bot. Gaz.*, **52**: 417-438.
- , 1911: A radio-atmometer for comparing light intensities, *Plant World*, **14**: 96-99.
- and A. H. ESTABROOK, 1912: Observations on the degree of stomatal movement in certain plants, *Bull. Torrey Bot. Club*, **39**: 15-22.

- LIVINGSTON, B. E., and W. H. BROWN, 1912: Relation of the daily march of transpiration to variations in the water content of foliage leaves, *Bot. Gaz.*, **53**: 309-330.
- , 1913: The resistance offered by leaves to transpirational water loss, *Plant World*, **16**: 1-35.
- , 1915: Atmometry and the porous cup atmometer, *Plant World*, **18**: 21-30, 51-74, 95-111, 143-149.
- and L. A. HAWKINS, 1915: The water relation between plant and soil, *Carnegie Inst. Wash. Pub.* **204**.
- and E. B. SHREVE, 1916: Improvements in the method for determining the transpiring power of plant surfaces by hygrometric paper, *Plant World*, **19**: 287-309.
- , 1917: Atmometric units, *Johns Hopkins Univ. Circ.*, n.s., **3**: 160-170.
- , 1918: Porous clay cones for the auto-irrigation of potted plants, *Plant World*, **21**: 202-208.
- and F. THONE, 1920: A simplified non-absorbing mounting for porous porcelain atmometers, *Science*, n.s., **52**: 85-87.
- , 1923: Studies upon the influence of solar radiation on the rate of transpirational water-loss from plants, *Carnegie Inst. Year Book*, **22**: 288-289.
- , 1923: Blackened spheres for atmometry, *Science*, n.s., **58**: 182-183.
- , 1926: A black collodion coating for atmometer spheres, *Science*, n.s. **63**: 362-363.
- , T. HEMMI, and J. D. WILSON, 1926: Growth of young wheat plants in auto-irrigated soils, as related to the water-supplying power of the soil and to the adjustment of the auto-irrigator, *Plant Physiol.*, **1**: 387-395.
- LLOYD, F. E., 1908: The physiology of stomata, *Carnegie Inst. Wash. Pub.* **82**.
- , 1912: The relation of transpiration and stomatal movements to the water content of the leaves in *Fouquieria splendens*, *Plant World*, **15**: 1-14.
- , 1913: Leaf-water, and stomatal movement in *Gossypium* and a method of direct visual observation of stomata *in situ*, *Bull. Torrey Bot. Club.*, **40**: 1-26.
- LOFTFIELD, J. V. G., 1921: The behavior of stomata, *Carnegie Inst. Wash. Pub.* **314**.
- LONG, F. W., 1928: Stomata which show functional movement for a century, *Science*, n.s., **69**: 218-219.
- LUTMAN, B. F., 1916: Some studies on Bordeaux mixture, *Vt. Agr. Expt. Sta. Bull.* **196**.
- MARIANA, G., 1902: The influence of humidity on the formation and development of stomata, separate from *Att. Inst. Bot. Univ. Pavia*, 2 ser., **8**: 32; *Expt. Sta. Rec.* **14**: 943.
- MARTIN, W. H., 1916: Influence of Bordeaux mixture on the rates of transpiration from abscised leaves and from potted plants, *Jour. Agr. Res.*, **7**: 529-548.
- MAXIMOW, N., and V. RYBIN, 1921: Non-stomatal regulation of transpiration. *Jour. Russ. Bot. Congress*, **1**: 25-26; *Bot. Abst.*, **14**: 287.
- , 1925: The physiological basis of drought resistance of plants, *Eng. Abst.*
- MCLEAN, R. C., 1919: Studies in the ecology of tropical rain forests. I, Humidity, *Jour. Ecol.*, **7**: 5-54; II, Illumination, 121-172.
- MEYER, B. S., 1927: The measurement of the rate of water-vapor loss from leaves under standard conditions, *Amer. Jour. Bot.*, **14**: 582-592.
- MILLER, E. C., 1916: Comparative study of the root systems and leaf areas of the corn and the sorghums, *Jour. Agr. Res.*, **6**: 311-333.
- , 1916: Relative water requirement of corn and the sorghums, *Jour. Agr. Res.*, **6**: 473-485.
- , 1917: Daily variation of water and dry matter in the leaves of corn and the sorghums, *Jour. Agr. Res.*, **10**: 11-47.

- MILLER, E. C., and W. B. COFFMAN, 1918: Comparative transpiration of corn and the sorghums, *Jour. Agr. Res.*, **13**: 579-605.
- , 1923: Relative water requirement of corn and sorghums, *Kans. Agr. Expt. Sta. Tech. Bull.* 12.
- and A. R. SAUNDERS, 1923: Some observations on the temperature of the leaves of crop plants, *Jour. Agr. Res.*, **26**: 15-43.
- , 1925: Relative transpiration in crop plants, unpub. data, *Kans. Agr. Expt. Sta.*
- , 1928: Some observations on the number of stomata of crop plants, unpub. data, *Kans. Agr. Expt. Sta.*
- , 1928: The relation of soil moisture to transpiration, unpub. data, *Kans. Agr. Expt. Sta.*
- , 1928: The effect of Bordeaux mixture on the rate of transpiration, unpub. data, *Kans. Agr. Expt. Sta.*
- MITSCHERLICH, A., 1904: Ein Verdunstungsmesser, *Landw. Versuchs-Stat.*, **60**: 63-72.
- MONTEMARTINI, L., 1904: Note di fisiopatologia vegetale, *Atti. dell' Ist. Bot. di Pavia*, Ser. II, 63 pp., **9**: 1-66; *Bot. Centrbl.*, **98**: 276-277 (1905).
- MONTGOMERY, E. G., 1911: Methods of determining the water requirements of crops, *Proc. Amer. Soc. Agron.*, **3**: 261-283.
- and T. A. KIESSELBACH, 1912: Studies in water requirements of corn, *Nebr. Expt. Sta. Bull.* 128.
- MUENSCHER, W. L. C., 1915: A study of the relation of transpiration to the size and number of the stomata, *Amer. Jour. Bot.*, **2**: 487-504.
- MÜLLER-THURGAU, H., 1894: Die Tätigkeit pilzkranker Blätter, *4 Jahresb. der Vers. Stat. f. Obst. Wein- und Gartenbau in Wädensweil*, **1894**: 54-57.
- NEWTON, J. D., 1925: The relation of the salt concentration of the culture solution to transpiration and root respiration, *Sci. Agr.*, **5**: 318-320.
- NICHOLS, G. E., 1913: A simple revolving table for standardizing porous cup atmometers, *Bot. Gaz.*, **55**: 249-251.
- , 1923: The Musch rain-correcting mounting for porous porcelain atmometers, *Science*, n.s., **57**: 26-28.
- POOL, R. J., 1923: Xerophytism and comparative leaf anatomy in relation to transpiring power, *Bot. Gaz.*, **76**: 221-241.
- PULLING, H. E., 1919: Sunlight and its measurement, *Plant World*, **22**: 151-172, 187-209.
- REA, M. W., 1921: Stomata and hydathodes in *Campanula rotundifolia* L., *New Phytol.*, **20**: 56-72.
- REED, H. S., 1910: The effect of certain chemical agents upon the transpiration and growth of wheat seedlings, *Bot. Gaz.*, **49**: 81-109.
- and J. S. COOLEY, 1913: The transpiration of apple leaves infected with *Gymnosporangium*, *Bot. Gaz.*, **55**: 421-430.
- REHFOUS, LAURENT, 1917: Étude sur les stomates, *Univ. Genève. Inst. Bot.* IX, No. 6, pp. 110.
- RENNER, O., 1910: Beiträge zur Physik der Transpiration, *Flora*, **100**: 451-547.
- RICHARDSON, A. E. V., 1923: The water requirement of farm crops, *Jour. Dept. Agr. Victoria*, **21**: 193-212, 257-284, 321-339, 385-404, 449-481; *Expt. Sta. Rec.* **50**: 733-735.
- RICOME, H., 1903: Influence du chlorure de sodium sur la transpiration et l'absorption de l'eau chez les végétaux, *Comp. Rend. Acad. Sci. Paris*, **137**: 141-143.
- RIPPEL, A., 1919: Der Einfluss der Bodentrockenheit auf den anatomischen Bau der Pflanzen insbesondere von *Sinapis alba*, etc., *Beih. Bot. Centrbl.* I, **36**: 187-260.
- RUMM, C., 1893: Ueber die Wirkung der Kupferpräparate bei Bekämpfung der sogenannten Blattfallkrankheit der Weinrebe, *Ber. d. d. bot. Ges.*, **11**: 79-93.

- SALISBURY, E. J., 1927: On the causes and ecological significance of stomatal frequency, with special reference to the woodland flora, *Phil. Trans. Roy. Soc.*, B, **216**: 1-65.
- SAMPSON, A. W., and L. M. ALLEN, 1909-1916: Influence of physical factors on transpiration, *Minn. Bot. Studies*, **1-4**: 33-60.
- SAYRE, J. D., 1919: Comparative transpiration of tobacco and mullein, *Ohio Jour. Sci.*, **19**: 422-426.
- , 1919: Factors controlling variations in the rate of transpiration, *Ohio Jour. Sci.*, **19**: 491-509.
- , 1920: The relation of hairy leaf coverings to the resistance of leaves to transpiration, *Ohio Jour. Sci.*, **20**: 55-86.
- , 1923: Physiology of stomata of *Rumex patientia*, *Science*, n.s., **57**: 205-206.
- , 1926: Physiology of the stomata of *Rumex patientia*, *Ohio Jour. Sci.*, **26**: 233-267.
- SCARTH, G. W., 1926: The influence of the hydrogen-ion on the turgor and movement of the plant cells with especial reference to stomatal movement, Plant Congress Ithaca, N. Y. rev. by C. A. Shull, *Bot. Gaz.*, **82**: 453-454.
- SCHANDER, RICHARD, 1904: Über die physiologische Wirkung der Kupfervitriolkalkbrühe, *Landw. Jahrb.*, **33**: 517-584.
- SCHWENDENER, S., 1881: Ueber Bau und Mechanik der Spaltöffnungen, *Monatsber. d. Akad. d. Wiss. Berlin*, **1881**: 833.
- , 1889: Die Spaltöffnungen der *Gramineen* und *Cyperaceen*, *Sitzber. Berl. Akad. Wiss.*, **1**: 65-77.
- SHANTZ, H. L., and L. N. PIEMEISEL, 1927: The water requirement of plants at Akron, Colorado, *Jour. Agr. Res.*, **34**: 1093-1190.
- SHIVE, J. W., 1915: An improved non-absorbing porous cup atmometer, *Plant World*, **18**: 7-10.
- and W. H. MARTIN, 1917: The effect of surface films of Bordeaux mixture on the foliar transpiring power in tomato plants, *Plant World*, **20**: 67-86.
- SHREVE, E. B., 1914: The daily march of transpiration in a desert perennial, *Carnegie Inst. Wash. Publ.* 194.
- , 1916: An analysis of the causes of variations in the transpiring power of cacti, *Physiol. Res.* **2**: 73-127.
- , 1917: The transpiring power of plants, *Carnegie Inst. Wash. Year Book*, **16**: 66-68.
- , 1919: A thermo-electrical method for the determination of leaf temperature, *Plant World*, **22**: 100-104.
- , 1919: The rôle of temperature in the determination of the transpiring power of leaves by hygrometric paper, *Plant World*, **22**: 172-180.
- , 1924: Factors governing seasonal changes in transpiration of *Encelia farinosa*, *Bot. Gaz.*, **77**: 432-439.
- SAMPSON, A. W., and LOUISA M. ALLEN, 1909: The influence of physical factors on transpiration, *Minn. Bot. Studies*, **4**: 33-59.
- SMITH, A. M., 1909: On the internal temperature of leaves in tropical isolation with special reference to the effect of color on the temperature, *Ann. Roy. Bot. Gard. Peradniya*, **4**: 229-298.
- SMITH, H. B., 1922: Stomatal behavior of plants in the greenhouse in winter, *Mich. Acad. Sci., Arts, and Letters*, pp. 109-117.
- SPALDING, V. M., 1905: Soil water in relation to transpiration, *Torreya*, **5**: 25-27.
- STAHL, E., 1894: Einige Versuche über Transpiration und Assimilation, *Bot. Zeitung*, **52**: 117-146.
- STEFAN, J., 1873: Versuche über die Verdunstung, *Sitzungsber. d. k. Akad. d. Wiss. Wien*, **68**: 385-428.

- STRUGGER, S., and F. WEBER, 1926: Zur Physiologie der Stomata-Nebenzellen, *Ber. d. d. bot. Ges.*, **44**: 272-278.
- THOM, C. C., and H. F. HOLTZ, 1917: Factors influencing the water requirements of plants, *Wash. Agr. Expt. Sta. Bull.* 146.
- THOMAS, N., and A. FERGUSON, 1917: On the reduction of transpiration observations, *Ann. Bot.*, **31**: 241-255.
- TRANSEAU, E. N., 1911: Apparatus for the study of comparative transpiration, *Bot. Gaz.*, **52**: 54-60.
- TRELEASE, S. F., and B. E. LIVINGSTON, 1916: The daily march of transpiring power as indicated by the porometer and by standardized hygrometric paper, *Jour. Ecol.*, **4**: 1-14.
- , 1922: Incipient drying and wilting as indicated by movements of cocoanut pinnac, *Amer. Jour. Bot.*, **9**: 253-265.
- , 1922: Foliar transpiring power of the cocoanut, *Philippine Jour. Sci.*, **20**: 167-176.
- UNGER, F., 1861: Beiträge zur Anatomie und Physiologie der Pflanzen. XI, XII, Neue Untersuchungen über die Transpiration der Gewächse, *Sitzungsber. d. k. Akad. d. Wiss. Wien*, **44**: 181-227, 327-368.
- URSPRUNG, A., 1903: Die physikalischen Eigenschaften der Laubblätter, *Bibl. Bot.*, **60**: 1-120.
- VERSCHAFFELT, E. J., 1890: De transpiratie der planten in koolzuurrijge lucht, *Bot. Jaarboek (uitgegeven door het kruidkundig genootschap Dodonaea te Gent)*, **2**: 305.
- VON MOHL, H., 1856: Welche Ursachen bewirken die Erweiterung und Verengung der Spaltöffnungen? *Bot. Zeitung*, **14**: 697-704, 713-720.
- WEAVER, J. E., 1916: The effect of certain rusts upon the transpiration of their hosts, *Minn. Bot. Studies*, **4**: 397-406.
- and A. MOGENSEN, 1912: Relative transpiration of coniferous and broad-leaved trees in autumn and winter, *Bot. Gaz.*, **68**: 393-424.
- WEBER, F., 1923: Enzymatische Regulation der Spaltöffnungsbewegung, *Natur. Wiss.*, **11**: 309-316.
- WEIGAND, KARL M., 1910: The relation of hairy and cutinized coverings to transpiration, *Bot. Gaz.*, **49**: 430-444.
- , 1910: Some evaporation experiments in relation to excessive transpiration, abst. in *Science*, n.s., **31**: 434.
- WEISS, A., 1865-1866: Untersuchungen über die Zahlen- und Grössenverhältnisse der Spaltöffnungen, *Jahrb. f. wiss. Bot.*, **4**: 126-196.
- WEISS, F., 1924: The effect of rust infection upon the water requirement of wheat, *Jour. Agr. Res.*, **27**: 107-118.
- WIGGINS, R. G., 1921: Variations in the osmotic concentrations of the guard cells during the opening and closing of stomata, *Amer. Jour. Bot.*, **8**: 30-41.
- WILSON, H. W., 1924: Studies on the transpiration of some Australian plants with notes on the structure of their leaves, *Roy. Soc. Victoria Proc.*, n.s., **36**: 175-237.
- WILSON, J. K., 1923: The nature and reaction of water from hydathodes, *N. Y. Cornell Mem.* 65.
- WOODS, A. F., 1893: Some recent investigations of the evaporation of water from plants, *Bot. Gaz.*, **18**: 304-310.
- YAPP, R. H., 1912: *Spirea Ulmaria*, L., and its bearing on the problem of xeromorphy in marsh plants, *Ann. Bot.*, **26**: 815-871.
- YUNCKER, T. G., 1916: A study of the relation of soil moisture to transpiration and photosynthesis in the corn plant, *Plant World*, **19**: 151-161.
- ZALENSKI, V., 1921: Action of high temperature on the behavior of stomata, *Jour. Russian Bot. Congress*, **1**: 62-63; *Bot. Abst.*, **14**: 287-288.

- ZALENSKI, V., 1923: The intensity of transpiration in the upper and in the lower leaves, *Bull. Agr. Inst. Saratov.*, **1**: 13-17; *Bot. Abst.*, **15**: 165-166.
- ZHEMCHUZHNIKOV, E. A., 1922: To the question of stomatal regulation of plant's transpiration, *Jour. Agr. Res. Don and North Caucasus*, (1922): 29-39; *Expt. Sta. Rec.* **52**: 517.
- , 1924: Transpiration by the stomata, (Russian) *Trans. Agr. Expt. Inst. Don and Northern Caucasus*, 1-34; *Bull.* 164; *Bot. Abst.*, **15**: 166 (1926).
- ZUCKER, A., 1896: Beitrag zur direkten Beeinflussung der Pflanzen durch die Kupfervitriol-Kalkbrühe, *Inaug. Diss. Stuttgart*.

CHAPTER VIII

THE FORMATION OF CARBOHYDRATES BY THE GREEN PLANT

I. THE SYNTHETIC POWER OF THE GREEN PLANT

The materials that enter the green plant from its environment are for the most part inorganic compounds of the most simple character. Thus, for example, the plant obtains CO_2 from the air; water and the nitrates, sulphates, and phosphates of K, Na, Mg, Fe, Ca, among others, from the soil. From these simple compounds or in their presence the plant is able to synthesize a large variety of substances of varying degrees of complexity, the most important and abundant of which are the carbohydrates, fats and oils, amino acids, proteins, glucosides, chlorophyll, and various other pigments, enzymes, vitamins, tannins, alkaloids, and numerous organic acids. Some of these substances named may be degeneration products under certain conditions, but if they are, they are derived from more complex compounds which, in turn, have been synthesized by the plant.

The first evident synthetic product that is formed by the green plant in any appreciable quantity from the simple inorganic compounds that are obtained from the air and soil is one of the more simple forms of carbohydrate. The first carbohydrate thus formed is the nucleus or foundation of most of the other organic compounds in the plant. A general knowledge of the carbohydrates is thus necessary for a clear understanding not only of their formation but also of the formation of other plant substances.

II. THE CARBOHYDRATES OF THE GREEN PLANT


The carbohydrates are the most abundant compounds in the plant and make up the greater portion of its dry weight. The term "carbohydrates" signifies or implies that these compounds are composed of carbon and water and the name originated from the fact that they contain C, H, and O with the two latter elements generally present in the same proportion as in water. Some few carbohydrates, however, for example rhamnose, $\text{C}_6\text{H}_{12}\text{O}_5$, do not show this simple relation between the hydrogen and oxygen atoms, while certain compounds, as, for example, acetic acid, $\text{C}_2\text{H}_4\text{O}_2$, and lactic acid, $\text{C}_3\text{H}_6\text{O}_3$, which are not carbohydrates, contain hydrogen and oxygen atoms in the same proportion as in carbohydrates. From the present knowledge of the structure of carbohydrates they may be defined more specifically as aldehyde alcohols, ketone alcohols, which

contain an "ose" or sugar group, or compounds which are converted by hydrolysis into one or both of these two types of alcohol.

The green plant alone possesses the power to synthesize carbohydrates from inorganic compounds. Although the production of carbohydrates has been accomplished artificially, it has been only in an extremely limited way as far as the number of compounds and the quantity of material obtained are concerned. The members of the animal kingdom lack the power to synthesize carbohydrates from inorganic material and are dependent either directly or indirectly upon plants for their supply of these energy-producing foods.

In addition to being the basis for the formation of numerous plant products, the carbohydrates make up the greater part of the plant's structural framework and are also one of the chief foods of the protoplasm and the main source of energy in the plant. The carbohydrates are stored in relatively large quantities as reserve food in various parts of the plant and when present in the cell sap in the soluble form they increase its osmotic value and thus play a part in maintaining the turgidity of the cells.

There are various classifications of the carbohydrates, but, in the main, their classification rests upon their solubility, taste, number of carbon atoms, the number of sugar groups that they contain, their reaction toward various reagents, their products of hydrolysis, and other physical and chemical reactions. The principal carbohydrates that occur in the green plant may be classified according to the following diagram:



¹ (R.) reducing sugars.

² (N. R.) non-reducing sugars.

From the preceding diagram it is observed that the carbohydrates may be divided into the sugars and the non-sugars and that since each carbohydrate contains one or more sugar or saccharose groups, the term "saccharose" is used as a basis for the classification of the entire group of carbohydrates.

A. THE SUGARS

The sugars are the simplest carbohydrates. They are soluble in water and have a characteristic sweet taste which varies in degree according to the type of sugar.

1. Physical and Chemical Reactions.—The sugars give certain physical and chemical reactions which vary in number and degree according to the sugar under consideration. These reactions are in many cases specific and may be utilized as a means of identification of a given type of sugar. The most striking properties of sugars are their specific rotatory power, their reducing action, and their formation of osazones.

a. Specific Rotatory Power.—All the natural sugars are optically active in that they rotate the plane of polarized light when it passes through a solution of any one of these carbohydrates. The degree of rotation depends upon the kind of sugar, the kind of light, and the concentration and length of the column of solution through which the beam of light has to pass. The same amount of the same sugar dissolved in the same volume of water and placed in a tube of the same length, however, will always cause the same rotation of the plane of polarized light. The sugar is thus said to have a specific rotatory power. It is expressed as the number of degrees of angular deviation of the plane of polarized light caused by a column of the solution 100 mm. in length composed of 100 g. of the substance dissolved in 100 cc. of water at a temperature of 20°C. This deviation is expressed by the symbol $[\alpha]_D^{20}$ which indicates that the observation was made at 20°C. and with the D or sodium light. Sugars which rotate the beam of light to the right or in the direction in which the hands of the clock move are called "dextrorotatory" and the degree of rotation is preceded by the plus sign. Those sugars which rotate the beam of light to the left or in a direction counterclockwise are termed "levorotatory" and the nature of the rotation is indicated by the minus sign. Thus, for example, the specific rotation of d-glucose is $[\alpha]_D^{20} + 52.7^\circ$ and d-fructose $[\alpha]_D^{20} - 92^\circ$.

b. Reducing Action.—Any sugar that contains a potentially active

"ose" or sugar group $\left(\begin{array}{c} \text{O} \quad \text{OH} \\ \parallel \quad | \\ -\text{C} - \text{C}- \\ | \end{array} \right)$ in its structure will behave as a reducing

agent. Certain of the metallic compounds when in alkaline solutions are

reduced when boiled with sugars of this type. Thus, for example, when treated in this manner an ammoniacal silver solution gives a silver mirror, an alkaline solution of cupric hydroxide forms cuprous oxide, and alkaline mercury salts are reduced to metallic mercury. Any sugar which possesses this power of reduction is known as a "reducing sugar." The structure of certain of the di- and trisaccharose sugars is such, however, that the aldehyde and ketone groups are linked in such a manner that they lose their reducing power. Such sugars are termed "non-reducing sugars," and saccharose, sucrose, or cane sugar is the most common of this type.

The reagent most commonly used to determine the reducing qualities of sugars is Fehling's solution. This is prepared in the following manner: Part *A* is made by dissolving 69.278 g. of pulverized $\text{CuSO}_4 \cdot 5\text{H}_2\text{O}$ in distilled water and making up to 1 l. Part *B* is made by dissolving 346 g. of sodium potassium tartrate (Rochelle salts) in 500 cc. of distilled water and 100 g. of sodium hydroxide in another 500 cc. of distilled water. Both parts of solution *B* are then mixed and kept until needed. Fehling's solution is then made by mixing equal parts of solutions *A* and *B* just before using.

The active substance in this solution as far as reducing sugars are concerned is cupric hydroxide, which is held in alkaline solution by the presence of the Rochelle salts. When this solution is heated with a solution of reducing sugar, oxygen is withdrawn from the cupric hydroxide and it is converted into cuprous oxide. The cuprous oxide thus formed is insoluble in the solution and is separated from it in the form of a reddish-brown precipitate. Advantage is taken of this reaction of sugars with the alkaline solution of cupric hydroxide for their detection and quantitative determination, since the amount of the cuprous oxide produced bears a definite relation to the amount and type of sugar used.

c. Formation of Hydrazones and Osazones.—When sugars with aldehyde or ketone groups in their molecules are treated with phenylhydrazine, $\text{C}_6\text{H}_5 \cdot \text{NH} \cdot \text{NH}_2$, they yield condensation products called "hydrazones," just as do other aldehydes and ketones. The phenylhydrazones are characteristic crystalline solids and are usually very easily soluble in water, so that they do not serve for the identification of individual sugars. When, however, these sugars are heated in aqueous solution with an excess of phenylhydrazine over that required to form the phenylhydrazone, a reaction takes place in which one molecule of the carbohydrate reacts with three molecules of the phenylhydrazine to form a substance called a "phenylosazone." The osazones of sugars are compounds which dissolve with difficulty in cold water, crystallize well, have a characteristic form and a definite melting point. The osazones are thus very characteristic for certain sugars and afford a means for their identification.


2. Kinds or Types.—The most important groups of sugars that occur in green plants are the monosaccharoses, the disaccharoses, and the trisaccharoses.

a. The Monosaccharoses.—The monosaccharoses are the simplest of the sugars and cannot be hydrolyzed or changed into simpler compounds with the property of sugar. They are so named because they contain only one sugar group. There are two classes of the monosaccharoses in plants—the pentoses and the hexoses.

1. *The Pentoses.*—The pentoses are sugars which contain five carbon atoms and have the formula $C_5H_{10}O_5$. These sugars occur in the free state in plants only in very small amounts. Davis and Sawyer (1914) determined the free pentoses in the alcoholic extract of the leaves of the mangold, turnip, *Tropaeolum majus*, *Helianthus annuus*, carrot, and potato and found that they amounted to from 0.3 to 1 per cent of the dry weight. VerHulst, Peterson, and Fred (1923) found in the leaves of corn that the free pentoses amounted to 0.69, 0.52, 0.39, and 0.47 per cent of the dry weight, respectively, at the tasseling, silking, milk, and dent stages. One of the components of the nucleic acids of plants is apparently pentose. Paracoutchouc is considered to be composed of a large number of groups of the formula C_5H_8 which have been polymerized to form an exceedingly large molecule. These C_5H_8 groups are considered reduction products of the pentoses (Spoehr, 1917, 1919). The pentoses occur in the plant for the most part in the combined state in the form of pentosans, natural gums, and hemicelluloses. As stated in Chap. I the pentoses may be obtained in various amounts by the hydrolysis of the hemicelluloses of the cell walls of seeds, pods, straw and the xylem elements of the plant. Cherry and peach gum and certain mucilages of plants also yield pentoses on hydrolysis. The two most common pentoses that are obtained from the hydrolysis of the materials above mentioned are arabinose and xylose. Both of these are reducing sugars. Rhamnose, $CH_3C_5H_9O_5$, is a pentose in which one atom of hydrogen has been replaced by a methyl group. This compound is of interest in that it has the characteristics of the sugars yet does not have the proportion of hydrogen and oxygen that ordinarily occurs in the carbohydrates.

2. *The Hexoses.*—The hexoses are the most abundant of the monosaccharoses in the plant. They contain six carbon atoms and have the formula $C_6H_{12}O_6$. The most important hexoses that are found in the green plant in the free state or in the form of condensation products are glucose, fructose, mannose, and galactose. All these hexoses are reducing sugars and all are optically active.

(a) *Glucose, Dextrose, or Grape Sugar.*—This sugar is found in considerable abundance in fruits—especially in the grape, on which account it received the name “grape sugar.” It also occurs in the seeds, roots, and leaves of plants and is thus found in varying quantities in practically every living cell of the plant. This sugar occurs in the combined state in sucrose, maltose, starch, and various other di-, tri-, and polysaccharoses and may be obtained by hydrolysis from these products. d-Glucose is dextrorotatory, its specific rotatory power being $[\alpha]_D^{20} + 52.7^\circ$, and for this property it has been termed “dextrose.” It is approximately three fifths as sweet as cane sugar. Glucose is an aldehyde alcohol and the structure of d-glucose is represented as shown on page 409.



(b) *Fructose, Levulose, or Fruit Sugar.*—Fructose is a ketone alcohol and has the structure shown above. Due to the ketose group in its molecule, it is a strong reducing agent and reduces Fehling's solution more rapidly than does glucose. Fructose is strongly levorotatory and for that reason has also been termed "levulose." Its specific rotatory power is $[\alpha]_D^{20} - 92.5^\circ$. It is slightly sweeter than cane sugar and is the sweetest of the ordinary sugars. Fructose is widely distributed in the plant and occurs in considerable quantities in fruits, generally in excess of glucose and sucrose. It occurs in the combined form in sucrose, in the trisaccharoses, raffinose, gentianose, and melicitose and in the polysaccharose inulin. It may be obtained from these substances by hydrolysis with acids or enzymes.

(c) *Mannose.*—Mannose is a sugar closely related to glucose and forms the same osazones as do that sugar and fructose. Mannose does not occur in the free state in plants but is readily obtained by hydrolysis from numerous compounds found in them. Thus the hemicelluloses of the cell wall of the date stone, ivory nuts, coffee, pea, and bean yield mannose among other sugars upon hydrolysis. The compounds in the plants which thus yield mannose are termed "mannans" or "mannosans." Mannose may also be obtained by the oxidation of mannitol, a hexatomic alcohol sometimes known as "mannite" which occurs in numerous plants. Mannose is dextrorotatory $[\alpha]_D^{20} + 14.3^\circ$ and is a reducing sugar.

(d) *Galactose.*—Galactose very rarely occurs in the green plant in the free form and when so found is only in very small amounts. It exists in the plant almost entirely in the form of condensation products which are sometimes collectively termed "galactans." This term includes the gums, mucilages, and hemicelluloses of the plant which yield galactose on hydrolysis. Galactose may thus be obtained from agar-agar, the pectins of carrot and pears, from gums occurring in peaches and plums, and from the cell walls of the seed coats of the seed of corn, lupine, bean, pumpkin, and many others. Galactose is also a constituent of the trisaccharose raffinose and may be obtained together with glucose and

fructose from this source by hydrolysis. d-Galactose obtained from the above-mentioned sources very closely resembles glucose in many of its properties, but it has one characteristic difference in that it forms mucic instead of saccharic acid when oxidized by concentrated nitric acid. Galactose is only very slightly sweet, reduces Fehling's solution more slowly than glucose, and is strongly dextrorotatory, $[\alpha]_D^{20} + 83.8^\circ$.

Although galactose, mannose, and the pentose sugars arabinose and xylose are rarely found in the plant in the free form, they may nevertheless play an important part, in some cases at least, in plant nutrition. They are formed very slowly by hydrolysis and may thus be utilized by the cells almost as rapidly as they are produced, so no considerable amount ever accumulates.

b. The Disaccharoses.—A disaccharose sugar consists of two monosaccharoses or hexoses linked together with the elimination of one molecule of water. The molecular formula for disaccharoses is $C_{12}H_{22}O_{11}$. The manner in which the two monosaccharoses are joined together to form a sugar of this kind varies with the type of disaccharose. The linkage may be through the alcoholic groups of each monosaccharose, through the alcoholic group of one and the ketone or aldehyde group of another, or through the aldehyde or ketone groups of each of the two sugars. If the linkage is through the aldehyde or ketone group of both monosaccharose units, the reducing power of these groups is destroyed and the disaccharose thus resulting is a non-reducing sugar. The most important disaccharoses occurring in green plants are sucrose, maltose, gentiobiose, and melibiose.

1. *Sucrose, Saccharose, or Cane Sugar.*—Sucrose is the most abundant and the most widely distributed sugar in green plants, being found in varying amounts in practically all living plant cells. In the stalk of the sugar cane (*Saccharum officinarum*) it is present in quantities equal to from 12 to 20 per cent of the green weight and may compose as much as 90 per cent of the soluble material in the expressed juice of this plant. This sugar composes from 15 to 20 per cent or more of the fresh weight of sugar beets and is present in considerable quantities in the sap of the sugar maple and in the stalks of the saccharine sorghums (*Sorghum saccharatum*). Sucrose is the sugar present in the greatest amount in most leaves, is the principal sugar in the nectar of flowers, and is found in most sweet fruits in amounts varying from 1 to 12 per cent.

The structure of sucrose has not been definitely established, but since it yields equal quantities of glucose and fructose by the addition of one molecule of water, it is considered an anhydride of these two sugars. Sucrose is dextrorotatory, $[\alpha]_D^{20} + 66.5^\circ$, but when it is hydrolyzed with acid or the enzyme invertase to equal amounts of glucose and fructose the resulting mixture is levorotatory. For this reason the mixture resulting from such a hydrolysis has been termed "invert sugar." Sucrose is a

non-reducing sugar, does not form a phenylhydrazone with phenylhydrazine, does not undergo direct alcoholic fermentation, and is next to fructose the sweetest of the common sugars.

2. *Maltose or Malt Sugar*.—Maltose is a reducing sugar, forms a characteristic osazone, is dextrorotatory, $[\alpha]_D^{20} + 137^\circ$, and is broken down by hydrolysis into two molecules of glucose. It does not undergo alcoholic fermentation by yeast directly but must be broken down into glucose before such fermentation can occur. Maltose is widely distributed in plants, but generally it can be detected in only very small quantities. It is derived from starch by hydrolysis and should thus occur in plants wherever this process is taking place. It is formed in the greatest amount from this source during the germination of starchy seeds. In most cases, maltose is apparently hydrolyzed into glucose almost as rapidly as it is formed, so it is never detected in any considerable amount in the plant.

3. *Other Disaccharoses*.—Two of the less common disaccharoses of the plants that have been isolated are gentiobiose and melibiose. Gentiobiose is obtained by the partial hydrolysis of gentianose, a trisaccharose found in the roots of yellow gentian (*Gentiana lutea*). Gentiobiose is a reducing sugar and upon hydrolysis yields two molecules of glucose. Melibiose is obtained by the partial hydrolysis of the trisaccharose raffinose. It is a reducing sugar and when hydrolyzed breaks up into glucose and galactose.

c. *The Trisaccharoses*.—The trisaccharoses have the general formula $C_{15}H_{32}O_{16}$. When partially hydrolyzed they yield a monosaccharose and a disaccharose, but when completely hydrolyzed they yield three molecules of monosaccharoses. This indicates that the trisaccharoses are formed by the linking together of three monosaccharoses by the elimination of two molecules of water. There are five trisaccharoses known to occur in green plants of which raffinose, melicitose, and gentianose are the most important. Raffinose occurs in cotton seeds, in the barley grain, and in the sugar beet. It is a non-reducing sugar and is strongly dextrorotatory, having a specific rotation of $[\alpha]_D^{20} + 104.5^\circ$. According to Thatcher (1921), raffinose may break down by hydrolysis into three different compounds according to the catalyst used: (1) sucrose and galactose, (2) fructose and melibiose, or (3) fructose, glucose, and galactose.

Melicitose is a very sweet sugar which is known to occur in the sap of the European larch (*Larix europaea*), Douglas fir, and other conifers and frequently collects on the twigs in small white flakes which are called "manna." When this sugar is partially hydrolyzed it yields one molecule of glucose and one molecule of a disaccharose sugar called "turanose." When completely hydrolyzed it yields two molecules of glucose and one of fructose.

Gentianose occurs in the roots of the yellow gentian (*Gentiana lutea*). When partially hydrolyzed it yields fructose and gentiobiose and when completely hydrolyzed yields one molecule of fructose and two molecules of glucose.

B. THE NON-SUGARS OR POLYSACCHAROSES

The polysaccharoses have the general formula $(C_6H_{10}O_5)_n$ or $(C_5H_8O_4)_n$ depending on whether they yield hexoses or pentoses on

hydrolysis. They are on that account termed, respectively, "hexosans" or "pentosans." The hexosans may be further classified according to the type of hexose that they yield on hydrolysis into the dextrosans (glucosans), the levulosans (fructosans), the mannans, and the galactans. The polysaccharoses are substances with high molecular weights and are apparently composed of many molecules of a monosaccharose linked together through the elimination of water. The value of n has not been accurately determined for any of the polysaccharoses on account of their slight solubility in the solvents that are used for molecular-weight determinations. The value of n is estimated to be as low as 30 in some polysaccharoses and as high as 200 or more in others. The chief polysaccharoses which occur in the green plant are the celluloses, the amyloses or starches, the mannans, the galactans, and the two pentosans araban and xylan.

1. The Celluloses.—Cellulose is the most abundant carbohydrate in the plant kingdom. It is one of the main components of the rigid cell wall that surrounds the protoplasm of practically every plant cell and, together with the various compounds that are united or closely associated with it, makes up in many cases the greater portion of the weight of the plant. The nature and properties of the celluloses are discussed fully under the subject of the constituents of the cell wall in Chap. I, so they will not be mentioned here.

2. The Amyloses or Starches.—The most important amyloses which occur in green plants are starch or amyllum, dextrans, and inulin.

a. Starch or Amylum.—Next to cellulose, starch is the most abundant and widely distributed carbohydrate in the plant kingdom and is the most universal form of storage carbohydrates in plants. It may occur in the young cells near the growing points, in the medullary ray cells of the stems and roots, in the xylem and phloem parenchyma, in the mesophyll cells of the leaf, in the guard cells, in the cells of the cortex and pith, in the bundle sheaths, in seeds, fruits, tubers, and other places. There are few green plants in which starch does not appear in some of the tissues at one time or another in the life of the plant. Starch occurs in the greatest amount in certain seeds, roots, and tubers, which thus form one of the main sources of carbohydrates for the nourishment of the animal kingdom.

Starch is present in the seeds of about one-half of the families and genera of the monocotyledons, while it is found in the seeds of about one-sixth of the dicotyledons. When starch is present as a reserve product in seeds, other non-nitrogenous foods as fats and oils are usually absent or present in only very small amounts. When fats and oils are the chief reserve foods, starch is generally absent. With but few exceptions, starch occurs in the plant in the insoluble form. In the soluble form it has been

observed in the cell sap of the epidermal cells of *Saponaria officinalis* and *Arum italicum* and some other plants (Reichert, 1913).

1. *The Starch Grain*.—With the exception of the few cases of soluble starch that were mentioned above, starch always occurs in the green plant in the form of definite granules known as starch grains. These vary in size from macroscopic to almost ultramicroscopic dimensions (Fig. 23). Starch grains are exclusively a product of green plants and are always found within the plant cells. The number of grains which may occur in a single cell varies greatly. There may be as many as 100 or more of a small size and only a few or only a single grain of considerable size. As a general rule, the tissues above ground, with the exception of seeds, contain starch grains which are smaller and less fully developed than in the underground structures. The form or shape of starch grains varies in plants of different species, in the same plant, in different parts, and even in the same part of a given plant. Lindet and Nottin (1923) observed in the case of the potato tuber that one-half the starch grains measured from less than 1 to 10μ in diameter but that the starch grains of that size comprised only 1.5 per cent of the total weight of starch. Only 0.6 per cent of the grains measured from 60 to 80μ but made up about 20 per cent of the total weight. The maximum size observed was 100μ in diameter. The form of the grain may be affected by the age of the plant and by changes in the nutritive conditions, but the form is usually the same within certain limits for a given species. The general shape of the starch grains is so constant for a given species that the adulteration of flours and meals with starch flours from other sources can be detected and the starch used as an adulterant identified by a microscopic examination of the starch grains. The form of starch grains may be spherical, ellipsoidal, ovoid, lentiform, or, where closely packed or crowded together, polyhedral.

The structure of the starch grains is very characteristic in that each grain consists of numerous layers or lamellae which are laid down either concentrically or eccentrically around one or more morphological centers or points of origin. The point of origin in the starch grain has frequently been designated the hilum, nucleus, or locus of the grain. These first two terms, however, are now universally used in botanical literature in another sense, so that the "locus," "point," or "center of origin" are perhaps the best terms to use to designate the center around which the starch of the grain is deposited (Fig. 23). When the lamellae or layers of starch are deposited around a single center of origin the grain is termed a "simple" starch grain. When the deposition of starch is around two or more points of origin, the grain is said to be "compound." The number of centers around which starch may be deposited in a compound grain may vary from two to hundreds. When simple grains predominate there are usually a few scattered compound grains, as, for example, in the potato

and wheat. In rice and oats the compound grains predominate and only a few scattered simple grains are to be found (Fig. 23*D* and *F*). The layered structure of the starch grains is very characteristic and gives the general appearance of a series of spheres arranged one within the other. Strictly speaking, however, the more truly spherical layers occur only in the concentric grains and near the center of origin in the eccentric ones, since in the latter case the outer layers are much thicker on one side and thus make the grain eccentric.

The cause of the layered or lamellar structure of the starch grain has been the subject of much discussion by plant physiologists for almost




FIG. 23.—Starch grains. *A*, from lima bean. *B*, from corn grain. *C* from potato tuber. *C*₁, compound grain from potato tuber. *D*, compound grain from rice. *D*₁, one of the simple grains which compose the compound starch grain of rice. *E*, from wheat grain. *F*, compound grain from oats.

a hundred years. The question has never been definitely answered, and it is the intention here to mention only a few of the theories that have been proposed to account for the physical structure of the starch grain. Nageli (1858) considered that the starch grain consists of two distinct substances, granulose and amylocellulose. He considered that the larger portion of the grain consists of granulose, which is slowly dissolved by the action of the enzyme diastase, and the smaller portion of the grain of amylocellulose, which under the above conditions retains the form and structure of the original grain. He considered that the proportion of these two substances differs in the different layers of the grain, the dense

layers containing relatively more amylocellulose than the soft or less dense layers, and the external parts of the grain more than the internal parts. The granulose part of the grain takes the blue color with iodine, while amylocellulose stains a dull or brownish red (Meyer, 1895). MacDougal (1895) considered that in the ordinary starch grain, amylose, consisting of two closely related forms α -amylose and β -amylose, and amyloextrin are present. He suggests that the dense layers of the grain are relatively rich in amylose and that the amyloextrins occur in larger quantities in the less dense porous layers. The amylose stains blue with iodine and the amyloextrin red. Kraemer (1902, 1905) suggests that the starch grain consists of colloidal and crystalloidal substances, these being arranged, for the most part, in distinct and separate lamellae. At the point of origin and in alternate lamellae the colloidal substance predominates but is associated with the crystalloid matter, while in the other layers the crystalloid substance occurs in the greater proportion. He held that differences in the starch grain show that starch instead of being a uniform substance is composed of several substances in varying proportions but more or less definitely arranged. Maquenne and Roux (1903, 1905) and Fernbach and Wolff (1904) considered that the starch granule consists of amylose and amylopectin. Amylose makes up the greater portion of the starch grain and is the substance which reacts with iodine. Amylopectin is not colored with iodine and is a mucilaginous substance which is considered to produce the gelatinization of starch in the form of starch paste.

Samec and Haerdtl (1920) in a study of the starches of potato, wheat, corn, rice, and horse-chestnut, among others, found that all contained an electro-diallytically precipitable viscous portion that conducts electricity and a portion that is the opposite in all these respects. They consider the first-named portion to be the amylopectin described by Maquenne and the latter amylose. They found that the relative amount of these two substances differed in different starches.

Ling and Dinshaw (1923), Clayson and Schryver (1923), and Schryver and Thomas, (1923) found in addition to amylose and amylopectin a substance resembling hemicellulose in many of the starches. This substance in wheat starch resists the action of taka-diastrase, is soluble in hot water, but separates from it in an amorphous form upon cooling. It is soluble in *N*/10 NaOH from which solution it can be precipitated by acids.

Attempts have also been made to explain the lamellar structure of the starch grain upon the assumption that it is spherocrystalline in its composition. A spherocrystal is ordinarily defined as a more or less globular body composed of radially arranged crystals. Nageli (1858) first suggested the crystalline structure of the starch grain and conceived it to be composed of minute crystalline structural units which he later termed

“micellae.” Schimper (1881) from studies with polarized light concluded that the grain is spherocrystalline in nature and consists of fibrous crystals arranged at right angles to the concentric layers. Meyer (1895) considered that the starch grain is composed of very thin, elongated needle-like or threadlike crystal units that are termed “trichites.” These trichites are arranged in a radial manner at right angles to the main mass. The stratification of the grain he considered due to the varying thickness and number in successive layers of the more or less richly branched trichites. Sponsler (1922, 1923) studied the structure of the starch grain by means of X-rays. He found that there is a regular and fairly uniform arrangement of atoms in the grain but that this regularity is destroyed by crushing the grain, which shows that the regularity is not that of a crystalline structure. The evidence indicates that the starch grain is built up of concentric layers of units and that the structure is neither an amorphous one nor a crystalline one in the ordinary sense of the terms. Parts of the grain act as crystals in that for certain distances the layers or units are in planes but taken as a whole the layers are curved.

Schimper (1881) concluded from his observations on starch formation that starch grains never arise except in plastids. His observations were later confirmed by Meyer (1895) and this view of starch formation is now the commonly accepted one. The chloroplasts and leucoplasts are the plastids concerned in the formation of starch grains. The starch found in the chloroplasts may be termed “temporary,” since it is stored there for only a very brief period until it can be translocated to other parts of the plant. Usually numerous grains are formed in a single chloroplast and sometimes project from the surface, giving the plastid an irregular appearance. These grains always remain small and are usually without a definite structure. According to Zirkle (1926), they are located within the central vacuole of the chloroplast.

The most conspicuous and definite starch grains are those formed by the leucoplasts. These are the grains that make up the great bulk of the starch in the plant kingdom and compose thus the reserve starch in all parts of the plant. This type of starch is sometimes called “permanent starch,” since it may remain intact for a considerable period of time. Apparently only a single starch grain originates in each leucoplast. The starch grain increases in size by the addition, accretion, or apposition of newly formed layers. It is not definitely known whether the grain in its development ruptures the leucoplast or whether the leucoplast stretches as the grain increases in size and thus remains intact and surrounds the exterior with a delicate film. Schimper (1881) showed that if the grain has its origin at the center of a spherical leucoplast, the strata of the grain will be laid down concentrically, because the conditions of growth are the same at every point of the surface. If the point of origin lies near the surface of the leucoplast, the stratification will be eccentric in

character, since the deposition of starch will be more favored on one side. Lindet and Nottin (1923) noted in a study of the formation of potato starch that the sugar content of the cell sap during starch formation amounted to from 0.5 to 1.5 per cent. They considered that the leucoplasts contain during this process a mixture of sucrose, invert sugar, and maltose but could not detect any soluble starch.

2. *General Properties.*—The starch substance is not a unit body but exists in a number of stereoisomeric forms (Reichert, 1913, 1919). It not only differs in the grains of different plants, in the grains of the same plant, but differences can be noted in the starch substance of the outer layer and the enclosed part of the grain, in different lamellae, and in different parts of the same lamella. The lamellae vary in density and solubility, increasing in density and decreasing in solubility from within outward.

The outermost layer is the least soluble in both hot and cold water and is less digestible by weak acids and enzymes. While the starch grains are composed for the most part of amylose, they contain various polymers ranging in complexity from amylopectin to amylocellulose (Mellanby, 1919). The grains of certain plants apparently do not contain ordinary starch but a modified form or mixture of ordinary starch and erythropectin, or erythropectin alone, since they stain a red violet or red with iodine. This reaction has been reported for the starch grains of the seeds of *Oryza sativa*, *Panicum miliaceum glutinosum*, and *Sorghum vulgare glutinosum*. The starch grains found in *Iris germanica*, *Chelidonium majus*, *Acer pseudoplatinus*, and *Gentiana lutea* among others also show this reaction (Meyer, 1886). From the above statements it would seem that it would be practically impossible to obtain a starch grain which could be considered typical in regard to its intimate structure (Kraemer, 1923).

Starch grains consist of from 80 to 85 per cent of starch substance, 15 to 20 per cent of water, and variable amounts of organic and inorganic substances including fats, protein, tannin, phosphates, and other matter. Samec and Haerdtl (1920) noted that all the starches examined by them contained phosphorus, the variation in amount being paralleled by the electric conductivity of the electrolyzed solution. The major portion of the fatty material present in starch cannot be removed by solvents before hydrolysis, according to Taylor and Nelson (1920). When corn starch is hydrolyzed, fatty acids are liberated, palmitic acid being the principal one. The fat thus contained in starch is liberated when hydrolysis has reached the erythropectin stage. The table on page 418 adapted from Reichert (1913) shows the composition of some of the more common types of starch.

COMPOSITION OF STARCH

Kind of starch	Starch substance	Water	Ash	Fat
	Per cent			
Wheat.....	83.3	14	0.4	0.2
Corn.....	84.1	14	0.4	
Arrowroot.....	84.1	15.7	0.2	0.1
Tapioca.....	84.8	14.4	0.25	
Potato.....	79.6	19.2	0.3	0.04

Starch is insoluble in cold water but when it is boiled in water a colloidal suspension is obtained which is termed "starch paste." The insolubility of uninjured raw starch grains in cold water seems to be due to some form of protective covering which is deposited by the leucoplast or by the cell sap. The idea, however, that the outer covering of the grain is a thin layer of cellulose or other non-starch substance is no longer held. Reichert (1913), however, considers that some form of protective covering exists, since the rupture of the grain by grinding with sand or glass, the erosion by diastase, or the solution of the outer film by potassium hydroxide or other agents renders the grains soluble in cold water.

By boiling starch with dilute acids or by treating with acetone, a clear solution termed "soluble starch" is obtained. The formation of soluble starch with acetone was described by Fernbach (1912). His method as described by Haas and Hill (1913) consists in pouring a one to two per cent suspension of starch in a large excess of pure acetone and shaking vigorously. A flocculent precipitate is obtained which when filtered and ground up in a mortar with more acetone yields a light white powder which is completely soluble in cold water and gives the starch reactions. Raw starch, starch paste, and soluble starch give a blue color when treated with a solution of iodine in KI or a solution of iodine in alcohol. This color reaction is the most characteristic reaction of starch.

When starch is boiled for some time with dilute mineral acids it is converted into dextrins, maltose, and finally glucose as the end product. When starch paste is treated with a malt extract containing diastase, the starch is converted only to maltose as the end product (O'Sullivan, 1872). If, however, uninjured starch grains are subjected *in vitro* to the action of diastase under sterile conditions, absolutely no digestion occurs. If the grains, however, are broken or cracked or eroded, rapid erosion takes place similar to that observed when digestion takes place in the plant under natural conditions.

b. Dextrins.—The dextrins are transition products between starch and maltose. The carbohydrate called “soluble starch” which is found in the sap of the epidermal cells of *Arum italicum* and *Saponaria officinalis* is perhaps a mixture of dextrins, while the starch grains which turn red with iodine, as has previously been described, are probably composed, in part at least, of dextrins. Weatherwax (1922) considered that the only carbohydrate in the endosperm of waxy maize is erythro-dextrin. Although dextrins are probably being formed continuously in the hydrolysis of starch or in the formation of starch from sugar, they have not been observed to accumulate to any extent in the plant except in the few cases that have been mentioned.

The dextrins are readily soluble in water from which they may be precipitated by alcohol. They are strongly dextrorotatory, do not reduce Fehling’s solution, and are converted into glucose by hydrolysis with mineral acids. A large number of dextrins have been described, but only three fairly definite forms are recognized. These are (1) amylo-dextrin, which gives a blue color with iodine and is considered the chief constituent of soluble starch; (2) erythro-dextrin, which gives a red color with iodine and has a neutral taste; and (3) achro-dextrin, which has a sweetish taste and gives no color with iodine.

c. Inulin.—Inulin occurs as a reserve carbohydrate in the cell sap of numerous plants, especially the *Compositae*. It is found in the largest amounts in roots and tubers and occurs, if at all, in only very small amounts in the aerial parts. In the underground parts it may make up as much as 15 per cent of the dry weight (Shohl, 1923). Inulin is found in comparatively large amounts in the underground parts of *Inula helenium*, *Helianthus tuberosus*, *Dahlia variabilis*, *Lappa minor*, *Cichorium intybus*, *Solidago* sp., and numerous others. In some of the monocotyledons it is found associated with starch, but as a general rule when inulin is present starch is absent. Some plants contain reserve carbohydrates of the same general type as inulin. Some of these are irisin in *Iris pseudacorus*, graminin in *Trisetum alpestre*, phleim in *Phleum pratense*, and triticin in *Triticum repens* (Dean, 1904).

Inulin is a white powder composed of finely divided granules. It is slightly soluble in cold water and very soluble in hot water, from which it may be precipitated by alcohol. An aqueous solution of inulin does not form a jelly or paste, is not colored by iodine, and is not fermentable. Inulin is slowly converted into fructose when boiled with water and very rapidly in the presence of an acid. It is also converted to fructose by the enzyme inulase. The methods for the extraction and preparation of inulin are described fully by Dean (1904), Willaman (1922), and Harding (1923).

3. Mannosans and Galactans.—The mannosans are present for the most part in the cell walls of plants and are generally classified as one of

the groups of hemicelluloses. They are found especially in the cell walls of leaves, of wood in stems and roots, and in the cell walls of seeds and seed coats. The mannosans are strongly dextrorotatory, soluble in water with difficulty, and yield mannose upon hydrolysis. The galactans are polysaccharoses which yield galactose upon hydrolysis. They are slightly soluble in water and form gummy solutions. Like the mannosans, they are for the most part associated with the cell wall of various plant parts and are generally considered under the heading of "hemicelluloses."

4. Pentosans.—The pentosans have the general formula $(C_5H_8O_4)_n$ and occur, for the most part, in the cell walls of various plant parts. According to Thatcher (1921), they compose 22 to 25 per cent of the dry weight of wheat bran, 8 to 10 per cent of clover hay, 16 to 20 per cent of oats straw, 26 to 27 per cent of wheat straw, and as much as 60 to 92 per cent of various wood gums. The pentosan content of the leaves of corn amounted to 19.9, 17.6, 18.1, and 19.4 per cent, respectively, at the tasseling, silk forming, milk, and dent stages in analyses made by Ver-Hulst, Peterson, and Fred (1923). The two chief pentosans are araban and xylan. Araban occurs in gum arabic and cherry gum. Xylan is found in the cell walls of the cells of straw, nut shells, seed coats, and corn cobs. The pentosans are soluble in cold water with difficulty but more soluble in hot water. They are very difficult to hydrolyze but finally yield the sugars arabinose and xylose.

III. PHOTOSYNTHESIS

A. NATURE

It was mentioned at the beginning of this chapter that the first evident organic product that is synthesized by the green plant from the inorganic compounds that it absorbs is some form of carbohydrate. This carbohydrate is formed by the plant from carbon dioxide and water, and the term "carbon assimilation" or "photosynthesis" has been given to the process. Barnes (1893) first proposed the name "photosyntax," but later (1898) he changed to the term photosynthesis, which is now universally used in America and to a considerable extent in England, but on the continent of Europe the term carbon assimilation is still in general use. Photosynthesis is commonly defined as the manufacture of some simple carbohydrate (probably sugar) from carbon dioxide and water by the chloroplasts in the presence of light. In this process, in addition to the formation of carbohydrate, oxygen always appears as a waste or end product. This liberation of oxygen by green plants was one of the earliest facts noted in plant physiology, and the conditions under which it is liberated were fairly well known long before the relationship of its appearance to the formation of carbohydrate was established.

The power of photosynthesis resides exclusively in the chloroplasts. These plastids thus have the power to transform the radiant energy of the sun into the potential energy of the carbohydrates. As will later be discussed, after the carbohydrates are once formed, the plant can apparently produce from them, regardless of light, most of the numerous complex compounds which compose it. The pigments of the chloroplasts are the agents in these plastids that absorb the radiant energy and aid at least in transforming it into the potential condition in the synthesized carbohydrates. A general knowledge of the nature of these pigments therefore is necessary for a proper understanding of the process of photosynthesis.

B. PIGMENTS OF THE CHLOROPLASTS

The pigments of the chloroplasts have received much consideration from the chemists and plant physiologists, and the literature concerning them is very voluminous. Due, however, to the lack of proper methods of extraction, purification, and analysis, the information in regard to these pigments was very confusing until the classical work of Willstätter and his workers from 1906 to 1926. In some of the most outstanding work of modern organic chemistry, they have succeeded in making the nature and chemistry of the leaf pigments as clear at least as that of any other plant substance. The composition and nature of the leaf pigments were found to be the same for all plants and constant for all conditions as is evidenced from the analysis of the pigments from various species of different families and from plants grown under a wide range of ecological conditions. The numerous works of Willstätter have been carefully translated and summarized by Schertz and Merz (1928), and a fine resumé is given by Jorgensen and Stiles (1917). The properties of chlorophyll, as well as methods for its determination, have also clearly been defined by Schertz (1928) in numerous publications. The following discussion of the leaf pigments is based upon these two translations and the papers of Schertz. The original papers in German have not been consulted.

According to the researches of Willstätter, the chloroplasts contain four pigments—two closely related chlorophyll pigments, chlorophyll component *a* and chlorophyll component *b*; and two yellow pigments, carotin and xanthophyll. A fifth pigment, fucoxanthin, is present in the brown algae. In the fresh green leaves the pigments occur in approximately the following proportions: chlorophyll *a*, 2 parts; chlorophyll *b*, three-fourths of 1 part; carotin, one-sixth of 1 part; and xanthophyll, one-third of 1 part per 1,000, respectively. In the chloroplasts these pigments are mixed in a colloidal state with various colorless substances—fats, waxes, and salts of fatty acids among others. Thus in an alcoholic

extract of dried leaves, the chlorophyll obtained is accompanied by six times its weight of other substances.



1. The Chlorophyll Pigments. Chlorophyll Components *a* and *b*.—The green pigment of the chloroplasts is called "chlorophyll." This pigment is the most abundant one in these plastids and consists of two components—chlorophyll component *a* of the composition $C_{55}H_{72}O_6N_4Mg$, blue black in the solid state and greenish blue in solution; and chlorophyll component *b* of the composition $C_{55}H_{70}O_6N_4Mg$, green black in the solid state and in solution pure green. The term chlorophyll as it is now commonly used refers to these two green pigments taken collectively and freed from all the others that are associated with it in the chloroplasts. Chlorophyll always contains 2.7 per cent magnesium, which is the only metal in the ash.

Chlorophyll component *a* is very easily soluble in ether and absolute alcohol, only moderately so in cold methyl alcohol, and rather easily in warm methyl alcohol. It is easily soluble in 95 per cent and with difficulty in 80 per cent ethyl alcohol. It is dissolved with difficulty in 90 per cent methyl alcohol even when warm and is almost insoluble in 80 per cent methyl alcohol. It is easily soluble in acetone, chloroform, carbon disulphide, and benzol. It dissolves in petroleum ether with difficulty even when warm.


The solubility of chlorophyll component *b* is in general somewhat less than that of component *a* but the difference is very marked in petroleum ether. Chlorophyll *b* is wholly insoluble in petroleum ether at room temperatures, and the solvent becomes scarcely colored even at boiling.

a. The Chemistry of Chlorophyll.—Chlorophyll is a combination of the tricarboxylic acid chlorophyllin ($C_{31}H_{29}N_4Mg$) $(COOH)_3$ with methyl alcohol, CH_3OH , and phytol or phetyl alcohol, $C_{20}H_{39}OH$, which together compose about one-third of the chlorophyll molecule. It is thus an ester of the acid chlorophyllin.


The formulae for chlorophyll *a* and *b* are written:



Although chlorophyllin is a tricarboxylic acid, only two of the acid $(COOH)$ groups actually function in ester formation. The third acid groups apparently does not exist as a free acid group. In chlorophyll *a*



phyll *b* it is considered by some to be in the lactone-arrangement,



different structural units in the molecule (Thatcher, 1921).

When chlorophyll is treated with dilute alkalis, the alcoholic groups of the esters are split off by hydrolysis, producing the tribasic acids—chlorophyllin *a* and chlorophyllin *b*. When these chlorophyllins are heated with alkali, the carboxyl groups are driven off successively, giving products which are termed “phyllins” but which contain magnesium. The chlorophyllins are easily decomposed but were isolated by Willstätter and were found on analysis to contain magnesium which is bound to nitrogen in a complex way. The magnesium cannot be electrolytically dissociated as a magnesium salt. The magnesium-containing group is very easily affected by acids but is stable in the presence of alkalis.

When chlorophyll is treated with dilute acids, the magnesium is removed and replaced with two hydrogen ions without otherwise changing the molecule. A series of decomposition products result which are called “phytins” and which correspond to the alkali decomposition products of chlorophyll, with the exception that the magnesium is lacking. The series of compounds thus obtained from the phyllins are called “porphyrins.”

It should be noted here that chlorophyll in nature is accompanied by the enzyme chlorophyllase. This enzyme is active in an alcoholic medium and replaces the phytol group of the chlorophyll with the ethyl group from the alcohol. When an alcoholic extract of this type is evaporated nearly to dryness, dark green crystals—crystalline chlorophyll—are obtained. When chlorophyll is extracted by solvents other than alcohol, it is obtained in the amorphous form.

b. Optical Properties.—Chlorophyll in alcoholic solution exhibits the phenomenon of “fluorescence,” a property that is possessed by a considerable number of substances, in which they exhibit one color by transmitted and another by reflected light. This phenomenon was so called because it was first observed in flourspar and appears to be due to an alteration in the wave lengths of radiant energy brought about by the action of the molecules of the substance. Generally the action is to increase the wave lengths, but in some few cases it is the reverse. Usually the yellow, green, and blue rays undergo the change. In the alcoholic solution of chlorophyll, the much shorter wave lengths of green and blue are emitted as the longer wave lengths of the red. Thus an alcoholic solution of chlorophyll *a* is blue green by transmitted light and blood red by reflected light. An alcoholic solution of chlorophyll *b* is yellow green by transmitted light and brown red by reflected light.

One of the striking properties of chlorophyll is its ability to absorb certain rays of light. This absorption is so complete that dark bands appear in the spectrum. Since the absorption spectrum of every colored solution changes with its concentration, the spectrum of chlorophyll must be determined either throughout a range of concentrations or by using layers which vary in thickness. The spectrum of chlorophyll




FIG. 24.—Spectra of chlorophyll, chlorophyll *a*, chlorophyll *b*, carotin, and xanthophyll. The nature of the solution in each case is described in the text. (Redrawn from Schertz and Merz, 1928.)

shown in Fig. 24 is that of an acetone solution of chlorophyll made by dilution of an acetone leaf extract of 40 cc. of acetone containing 0.02 g. of chlorophyll to five times its volume with 85 per cent acetone. This spectrum was obtained from a layer of this solution 1 cm. in thickness in a glass vessel with parallel walls. Figure 24 shows the absorption spectra of chlorophyll *a* and *b* obtained from a layer of solution 2 cm. in thickness made by dissolving 0.04 g. of the pure components in 1,000 cc. of ether.

The spectrum of chlorophyll (Fig. 24) shows that there are five absorption bands. The most distinct band includes the red rays of 651 to 680 $\mu\mu$ approximately on both sides of the Fraunhofer line *C*. This band appears in solutions of chlorophyll that are so dilute that none of the other absorption bands is evident. The next most distinct band and the greatest in width is one which includes most of the blue, indigo, and violet rays of 400 to 510 $\mu\mu$ approximately. Three other bands of much less intensity are located between these two prominent ones. One of these is located in the light orange and includes approximately the rays 600 to 620 $\mu\mu$. The second is in the greenish-yellow region and includes the rays 550 to 590 $\mu\mu$, while the third is in the yellowish-green portion and includes the rays 525 to 540 $\mu\mu$. These bands are rather indistinct and not intense, the intensity decreasing from the red toward the blue end of the spectrum. The ethereal solution of chlorophyll *a* gives a spectrum in which the absorption band in the red is not so distinct or wide as in the chlorophyll solution. The band in the blue end of the spectrum is only one-half the width of that of chlorophyll and includes only the more distant portion of that region. The solution of chlorophyll *b* shows a distinct absorption band in the red ultra to the line *C* and only a narrow rather indistinct one on the infra side. The band in the blue end of the spectrum is distinct and is approximately three-fourths the width of that of chlorophyll.

c. The State of Chlorophyll in the Chloroplasts.—The location of chlorophyll in the chloroplasts has been mentioned in Chap. I, but the condition or state in which it occurs has not been discussed. According to the work of Willstätter and others, the evidence seems to indicate that chlorophyll is present in the chloroplasts in a colloidal mixture. This assumption is substantiated by the behavior of chlorophyll to its solvents and from the evidence derived from spectroscopic examination.

Willstätter found that solvents which dissolve the pure extracted substance do not extract the chlorophyll from the dried leaf. Thus the pure pigment is readily soluble in acetone, but if the dried powder of nettle leaves is placed therein, it can remain in the acetone for half an hour without coloring the liquid. If a little water is added, however, the color becomes intensely green. This behavior indicates that chlorophyll occurs in the leaf in a different state of matter from extracted chlorophyll. From the above statements it would seem that chlorophyll in the chloroplasts is in the colloidal condition and that water added to the pure organic solvents dissolves the mineral substances in the leaf and that the salt solutions so formed alter the colloidal condition of the chlorophyll in the chloroplasts and make it easily soluble. The pure solvents can, however, extract chlorophyll from fresh leaves, since abundant water is present in them. Further support for the theory of the above reactions is furnished by the fact that colloidal solutions of chlorophyll in water made from a pure extracted pigment behave in a way similar to dried leaf pow-

der. If a solution of this type is mixed with ether, the ether remains colorless, but if a little salt solution of CaCl_2 or $\text{Ca}(\text{NO}_3)_2$ be added, the etherial layer becomes colored green upon shaking. The salt solution has changed some of the chlorophyll from the colloidal condition, and as a result it is soluble in the ether.

It has been observed by many (Tsweet, 1910) that the absorption bands of the spectrum of the living leaf are displaced toward the red end of the spectrum as compared with the bands in the spectrum of extracted chlorophyll. It is also known that the condition of chlorophyll in fresh leaves is altered if the leaves are plunged into boiling water and that it is then more easily extracted by its solvents. A leaf that has thus been placed in water gives absorption bands that occupy practically the same position as those in the chlorophyll extract. It is assumed that the chlorophyll has been changed by this treatment from a colloidal solution to a true solution and is now dissolved in the waxy substances with which it is associated and which have become liquid as a result of the temperature change. It has also been shown by Herlitzka (1912) that the spectrum of living leaves agrees with that of a colloidal solution of chlorophyll, while both differ in the same way from the spectrum of true solutions of chlorophyll.

d. Formation.—The formation of chlorophyll is a physiological process that occurs only in living cells and under conditions favorable to life. The substance or substances from which chlorophyll arises have never been isolated and their existence is only inferred. It is considered by some that a pigment called "chlorophyllogen" is formed independently of light in the chloroplasts and that it is rapidly transformed into chlorophyll under the influence of light (Palladin, 1922). The absorption spectrum of the pigments obtained from etiolated seedlings has an absorption band between $640\mu\mu$ and $620\mu\mu$ which is due to a red fluorescing pigment which has been termed "protochlorophyll." According to Eyster (1928), this is a pigment which develops without the aid of light and changes photochemically into chlorophyll upon exposure to light.

Light is one of the requisites for the formation of chlorophyll. The stem and leaves of most plants grown in darkness are always yellow. Such plants are said to be etiolated. They quickly turn green when exposed to light. Some plants or plant parts, however, as the seedlings of some conifers, the fronds of young ferns, the plumule of *Nelumbo*, and certain unicellular algae, are exceptions to this, since they become green in darkness. According to Palladin (1922), the conifer seedlings, however, form much less chlorophyll in darkness than in light. Light of medium intensity is the most favorable for chlorophyll formation. It is considered that in more intense light the formation and decomposition of chlorophyll occur simultaneously, so, as a net result, the greening is less pronounced than it is in diffuse light.

It was demonstrated by Wiesner (1874) that chlorophyll is formed in the red, orange, and yellow rays produced by a potassium dichromate solution and in the green, blue, and violet region produced by CuSO_4 . He also showed that plants do not become green under the non-luminous heat rays. Sayre (1928) grew plants under colored glass plates and studied the effect of different wave lengths of radiant energy on the formation of chlorophyll in the seedlings of corn, wheat, oats, barley, sunflower, and radish. The wave lengths longer than $680\mu\mu$ are not effective in the formation of chlorophyll, but all other regions of the remaining visible and ultra-violet spectrum to $300\mu\mu$ are effective, provided the energy value is sufficient. For equal energy values, the red rays are more effective than the green, and the green more than the blue. The effectiveness of radiant energy in chlorophyll formation appears to increase with wave length to about $680\mu\mu$ and then ends abruptly.

The rate of production of chlorophyll depends upon temperature. Greening occurs most quickly in etiolated plants between 18 to 30°C . Wiesner (1877) found within that range of temperature that greening occurs in about 1.6 hr., while at 10°C . 3.5 hr. were required.

A supply of iron is necessary for the formation of chlorophyll, and the probable function of that element in this regard is discussed in detail in Chap. VI. Many other elements also influence the development of chlorophyll. The effect of K, P, Ca, and Mg on the color of plants is considered under the discussion in Chap. VI of the functions of these elements in the metabolism of the plant. Ville (1889) found in the case of hemp that the greatest decrease in chlorophyll and carotin was brought about by a deficiency in nitrates, while Schertz (1921) associated the mottling of *Coleus* plants with the same cause. Deuber (1926) in case of the soybean noted that the chloroplast pigments increased with the increasing concentrations of iron and sulphur in the cultural solution. The lack of iron or potassium in the nutrient solution resulted in a more marked depression of the chloroplast pigments than a lack of sulphur. When the sulphur content reached a concentration of 46 ppm. and K, a concentration of 28 ppm., a marked decrease in the pigment content of the leaves occurred. Deuber, however, could not establish an exact proportional relation between the concentration or amount of any of the elements studied and the amount of pigment formed.

Since Mg and N enter into the molecular structure of chlorophyll, it is to be expected that a variation in the amount of these elements in the soil or in the cultural solution would influence the production of this pigment. However, the cause of chlorosis in plants which is due to variations of the Ca, S, K, Mn, P, or Fe supply is not so easily explained, since these elements do not enter into the composition of chlorophyll. This question is generally answered by saying that the production of

chlorophyll depends upon the general vigor and tone of the plant which is known to vary with certain combinations and with certain concentrations of these elements.

Palladin (1891) has shown that carbohydrates in the leaves are essential to the formation of chlorophyll. Etiolated leaves which contain a considerable supply of carbohydrates green rapidly when placed in light, but those which contain little or no soluble carbohydrate remain yellow. These leaves which are deficient in carbohydrate, however, green rapidly when floated in the light upon a solution of cane or grape sugar. The presence of oxygen is also essential for the production of chlorophyll. Etiolated leaves in an atmosphere devoid of oxygen remain yellow in light. It has been assumed by some that oxygen, mineral nutrients, carbohydrates, and a favorable temperature are necessary for the formation of chlorophyllogen which arises independently of light. The transformation of chlorophyllogen to chlorophyll in the living cells is considered to be dependent upon light.

2. The Carotinoids.—Always associated with the chlorophyll in the chloroplast are two or more yellow-red pigments which are termed the "carotinoids." This group generally includes four pigments which are quite similar in chemical composition. The four pigments are carotin and xanthophyll, which are yellow; fucoxanthin, which is reddish brown; and lycopersicin, which is a brilliant red.

a. Carotin.—Carotin is identical with the yellow pigment of carrots. It is not only found in the chloroplasts, but it is also widely distributed, occurring in both the amorphous and crystalline form, in flowers, seeds, fruits, and roots. It occurs in great abundance in carrots, is present in yellow corn and tomatoes, and is the pigment which gives them their characteristic color. Carotin is a compound with a high degree of saturation and has the formula $C_{40}H_{56}$. It is insoluble in water but very soluble in ether, chloroform, and carbon bisulphide. It becomes bleached in air and in dry air increases its weight 35 per cent by the addition of oxygen. The crystals are rhombohedra, which are orange red by transmitted and greenish blue by reflected light. Lycopin or lycopersicin, an isomer of carotin, occurs in red tomatoes and red peppers.

b. Xanthophyll.—This pigment has the general formula $C_{40}H_{56}O_2$ and is considered by some to be an oxidation product of carotin to which it is easily reduced. The crystals are pleochromatic, often with a steel-blue luster. In transmitted light they are yellow and are red only when two or more cross each other. Xanthophyll may absorb 36.5 per cent of its weight of oxygen. It is very easily soluble in chloroform and alcohol, soluble in carbon disulphide with difficulty, and insoluble in petroleum ether. Carotin and xanthophyll are very different in their color intensities but there is no simple ratio of their color strengths, since this varies with the solvent and with the concentration. Carotin is always

stronger in color and in carbon disulphide and ether is more red, while xanthophyll is rather greenish tinted.

Carotin and xanthophyll show a spectrum that consists of two bands in the blue and indigo blue in addition to the end absorption which starts at almost the beginning of the violet. In Fig. 24 the spectra of these two pigments were obtained by using a solution, one centimeter thick, of 5 mg. of pigment per liter of ether. The bands in the case of xanthophyll are displaced slightly toward the violet as compared to those of the carotin. The properties of carotin and xanthophyll, as well as refined methods for their extraction and separation, have been extensively studied by Schertz (1921 to 1925), and the student is referred to his work for detailed information on that subject.

c. Fucoxanthin.—This brownish-red pigment is associated with carotin, xanthophyll, and chlorophyll in the brown algae. It has the formula $C_{40}H_{54}O_6$ and undergoes a 7 per cent increase in weight in air due to the absorption of oxygen. This pigment does not exhibit fluorescence.

C. HISTORICAL

In 1772 Priestley discovered that green plants confined in an atmosphere rich in fixed air (carbon dioxide) produced after a period of time a considerable amount of dephlogisticated air (oxygen). He, however, had no understanding of the factors concerned in the process. At the same time, Scheele working in Sweden reported just the opposite results, since the plants with which he worked produced fixed air (carbon dioxide). Upon learning of the results of Scheele, Priestley repeated his investigations, but his results were confusing, since sometimes the plants increased the oxygen in the air and sometimes they depleted it, so that Priestley was unable to explain these variations. He, however, is given the credit for being the first to observe that oxygen is given off by green plants.

Jean Ingen-Housz, physician to the emperor of Austria, was interested in the effect of pure air upon the health of man and was led to investigate plants in this regard by the first report of Priestley. Ingen-Housz showed that plants were able to purify foul air in a few hours when placed in sunlight and that sunlight had no effect in increasing the amount of oxygen without the action of the plant. He also noted that the absorption of air and the exhaling of oxygen was more active the brighter the sunlight and that at night or under extremely shaded conditions, the plants acted upon the air just as animals. He observed that only the green parts of plants gave off oxygen and that roots, flowers, and fruits rendered the air impure. These results were published in 1774 but were not presented in the terms of modern chemistry until 17 years later.

In 1800 Jean Senebier, a minister of Geneva, published his researches on the influence of light upon vegetation. He considered that the oxygen given off came from the carbon dioxide absorbed by the plant, and by means of colored glass he was able to ascribe to the red rays of the spectrum the chief action of this process. In 1804, Nicolas de Saussure published his classical work, "Chemical Researches on Plants." Although a contemporary of the men just mentioned, his experiments were so well carried out and his data so well presented in the light of modern chemistry that Spoehr (1919) says that one might well believe that a century had elapsed between the time of De Saussure and that of his contemporaries. His experiments, which

were entirely quantitative, showed that the elements of water were fixed in the plant at the same time as the carbon and that there was an increase in weight as a result of the process. He also noted that there was no normal nutrition of the plant without the absorption of nitrates and mineral substances.

The discovery of these four men, however, found no interest among the botanists of their time. They were absorbed in the description and classification of plants and had no time for the consideration of facts about plants discovered by men foreign to the field of botany—for Priestley, Ingen-Housz, Senebier, and De Saussure were chemists and physicists. The discoveries of these men were soon forgotten or misinterpreted and little more was accomplished in this line, with the exception of the proof by Boussingault that a plant may obtain all its carbon from the air, until Sachs took up the work in 1860 to 1865.

Sachs and his pupils established, for the most part, the foundation upon which our modern views of photosynthesis rest. He was the first to discover that the chlorophyll corpuscles (chloroplasts) are the organs concerned in the appropriation of carbon dioxide and the separation of oxygen. Sachs also showed that chlorophyll, except in a few cases, is formed only in the presence of light, and he further distinguished between the effect of light in this process and in the release of oxygen by the leaf. Starch grains in the chloroplasts had been observed by Von Mohl as early as 1837 and by several subsequent investigators, but the significance of these grains was in no way suspected. It remained for Sachs, however, to connect the appearance of starch with the fixation of carbon and water and the elimination of oxygen in the chloroplasts in the presence of light. He was thus the first to observe and prove that a carbohydrate as well as oxygen is a product of the fixation of carbon and water in the green plant. He also grasped the fact that the formation of carbohydrates by this process is the starting point for the production of all other organic compounds of the plant, as shown by his statement (1882): "In the nutrition of plants it is only necessary in the first place to decompose carbon dioxide under the influence of light in the cells containing chlorophyll, with the cooperation of certain mineral matter absorbed by the roots and to produce at the cost of its carbon an organic substance—starch (carbohydrate) which then represents the starting point, so to speak, from which all the organic substances of the plant proceed by progressive chemical changes."

✓ D. PRODUCTS

Oxygen and carbohydrates are the two end products that are definitely known to be produced in the process of photosynthesis.

1. The Evolution of Oxygen.—It has already been stated that the evolution of oxygen by green plants in sunlight was the first fact observed in photosynthesis. This emission of oxygen is most easily observed in submerged aquatic plants, since in sunlight bubbles of gas escape from these plants and rise to the surface of the water. The gas which is thus emitted, however, is not pure oxygen but consists of a mixture of oxygen, nitrogen, and a small amount of carbon dioxide. The two latter gases are not emitted from the interior of the cells but are swept out of the intercellular spaces by the stream of oxygen gas. The oxygen content of the emitted gas varies from 25 to 85 per cent, increasing with the increased rate of bubble formation. Spoehr (1926) considers that when the rate of photosynthesis is high and the escaping gas stream correspondingly

high, the oxygen sweeps out the nitrogen and carbon dioxide from the intercellular spaces faster than it can be replaced from the surrounding water. When the rate of photosynthesis is low, the escaping gas stream is slow due to slow oxygen formation, so that the nitrogen and carbon dioxide which are being swept out are replaced in the intercellular spaces from the surrounding water. Under these conditions the gas which escapes contains a higher percentage of nitrogen and carbon dioxide than when the photosynthetic rate is high. The emission of oxygen from aquatic plants may also be observed after the following manner: The water in which the plants are submerged is covered with a film of oil, and the container is placed in the dark until the plants have exhausted the oxygen supply in the water. A leuco compound of methylene blue or indigo carmine is then added, and shortly after the plants are placed in sunlight the liberation of oxygen is made manifest by the formation of the bright-colored dye close to the plant. Oxygen is the only gas that has definitely been proved to be emitted by the plant during photosynthesis.

The ratio of the volume of carbon dioxide absorbed to the volume of oxygen produced is termed the "photosynthetic" or "assimilation quotient." It is now commonly written as CO_2/O_2 but in the earlier literature it was expressed as O/CO_2 or O_2/CO_2 . It was observed by De Saussure (1804) and Boussingault (1864) that the photosynthetic ratio approximated unity. Their experiments, however, did not take into account the respiration of the plants. The determination of the photosynthetic ratio is difficult, because the process of respiration is proceeding at the same time and in the opposite direction in that oxygen is being absorbed and carbon dioxide given off. Separation of these two reactions has been found very difficult. The first work on this problem was undertaken by Bonnier and Mangin (1886), who employed four methods for the separation of the gaseous exchanges due to photosynthesis and respiration of which the following are the most important: (a) comparison of the gas exchange of the plant in the light and in the dark. The amount of carbon dioxide absorbed in the light includes not only that obtained from the surrounding air but also that which has been released by the cells in the process of respiration. The oxygen that is released by the plant in the process of photosynthesis includes not only that which escapes from the plant but also that used by the cells in the process of respiration. By placing the plants in the dark for a given period, the volume of carbon dioxide C' released and the volume of oxygen O' absorbed by the cells in respiration can be determined. By placing the plants in the light for the same period, the volume of oxygen O'' released into the air and the volume of carbon dioxide C'' absorbed from the air under these conditions is measured. The total volume of oxygen released in the photosynthetic process would thus be $O' + O'' = O$ and the total volume of carbon dioxide absorbed would be $C' + C'' = C$. The true photosynthetic

quotient would thus be $\frac{C' + C''}{O' + O''} = \frac{C}{O} = \frac{CO_2}{O_2}$. This method is open to

objection, since it is not definitely known that respiration proceeds at the same rate in the light as in the dark. (b) The second method used by Bonnier and Mangin is based on an observation of Bernard (1878) that the process of photosynthesis may be suppressed by an anaesthetic without the suppression of respiration. Two similar quantities of leaves, one anaesthetised, the other not, are placed in light and the gaseous exchange due to photosynthesis estimated according to the measure just mentioned. This method is not exact, since the amount of the anaesthetic to apply in order to just suppress photosynthesis and not retard respiration is not known. (c) The third method for determining the gaseous exchange in photosynthesis consists in the removal by means of baryta water of all the carbon dioxide from the vessel containing one set of leaves. This also removes any carbon dioxide evolved in respiration which escapes from the leaf. The other set of leaves is placed under normal conditions of carbon dioxide supply. Thus, as in the second method, the difference between the oxygen content and the carbon dioxide content of the two vessels at the end of the experiment gives the true values of the oxygen and carbon dioxide evolved. Spoehr (1916) considers that this method is inexact, as the rate of carbon dioxide emission in the two vessels is not the same, since Spoehr and McGee (1924) showed that when the carbon dioxide content of the air surrounding a leaf is changed from a higher to a lower concentration the leaf showed a primary increased rate of carbon dioxide emission. When the carbon dioxide content of the air changed from a lower to a higher concentration, the leaf showed a reduced rate of carbon dioxide emission.

By the three methods Bonnier and Mangin (1886) concluded that the volume of oxygen emitted in photosynthesis was somewhat greater than that of the carbon dioxide. Maquenne and Demoussy (1913) using the first-named method of Bonnier and Mangin investigated the gaseous exchange of some 30 different species of plants and concluded that the photosynthetic quotient is equal to unity. The same conclusion was also reached by Willstätter and Stoll (1918), who determined the photosynthetic quotient under conditions in which the photosynthetic activity was from twenty to thirty times higher than that of respiration. 'This was done since the chief errors in the determinations of the photosynthetic quotient are occasioned in determining the rate of respiration. If the rate of photosynthesis is high as compared to respiration, the errors occasioned in determining the respiration rate will have an insignificant effect on the determination of the photosynthetic quotient. It was found by Kostytschew (1921) that the photosynthetic quotient varies with time. When leaves were first exposed to sunlight the value of CO_2/O_2 was considerably greater than unity, about one-third of the carbon dioxide

absorbed being fixed without oxygen evolution. After a short time, more oxygen is given off than carbon dioxide is absorbed (Spoehr, 1926). After a time, however, the CO_2/O_2 ratio will become practically unity.

The value of the photosynthetic quotient is of importance, since it yields some information in regard to the first products formed in photosynthesis, because in the determination of the nature of a reaction it is of the first importance to know the quantitative relation between the initial substances and the products of the reactions (Jorgensen and Stiles, 1919). When the photosynthetic quotient is exactly unity, it indicates that the CO_2 absorbed has been reduced to $\text{C} + \text{O}_2$, or in the hydrate form to a compound with the general formula $\text{C}_n\text{H}_{2n}\text{O}_n$. This, however, does not give any information as to the exact compound formed, since it might be formaldehyde or any other compound of that formula (Spoehr, 1926, page 93). It is interesting to note the value of the calculated photosynthetic quotient for different compounds. For formic acid it would be 2.0; for oxalic acid, 4.0; for glyoxalic acid, 2.0; for glycollic acid, 1.3; for malic acid, 1.3; and for formaldehyde, 1.0.

2. The Production of Carbohydrates in the Leaf.—Before discussing the production of carbohydrates in the photosynthetic process, it would be best to enumerate those that have been found in the leaf. Exclusive of cellulose and the pectic substances that occur in the cell walls of the leaf cells, the carbohydrates that have been detected in the leaves or other photosynthetic organs of the plant are starch, sucrose, d-glucose, d-fructose, pentosans, dextrans, mannitol, pentoses, and inulin. Some of the earlier workers (Brown and Morris, 1893) considered that maltose also is present, but later investigators (Davis, Daish, and Sawyer, 1916) were not able to detect it. Maltose is undoubtedly formed in the hydrolysis of the starch in the leaves, but it is evidently almost immediately transformed into other sugars, so that it is not detected by the ordinary chemical methods. Starch, sucrose, d-glucose, and d-fructose are the most abundant carbohydrates in leaves, the others above mentioned being found in only very small amounts.

Although carbohydrates are known to be the end products of photosynthesis, it is not definitely known which one is the first to be formed in the chloroplasts. The determination of the carbohydrate which is first formed in the leaf is attended with many difficulties. In the first place, it is impossible by any of the present methods of analysis to separate quantitatively the various groups of carbohydrates in the leaf, owing to the similarity of their properties and the relatively small amount of materials present. It would seem thus that to make any progress in this regard more exact methods for separation must be developed. The detection or isolation of the first carbohydrate formed in photosynthesis is also difficult, because as many as four functions involving carbohydrates may be proceeding simultaneously in the leaf. The first carbohydrate is

being formed, and from it almost immediately other carbohydrates may be formed by condensation for temporary storage as starch and the more complex sugars. These temporary storage products are, in turn, being hydrolyzed for translocation. An appreciable amount of carbohydrates is also broken down in the process of respiration which is proceeding at all times in the cells of the leaf. It is thus impossible by present-day methods to separate the carbohydrates first formed in photosynthesis from those which are formed as intermediate products in the condensation of the temporary reserves and in the hydrolysis of these reverses for translocation. On this account, therefore, it is no wonder that so many divergent views are held as to the kind of carbohydrate first formed in the photosynthetic process.

a. Early Observations.—The basis of our knowledge of the carbohydrates of the leaves was laid by Sachs (1862, 1864, 1884) when he proved that the appearance of starch in the chloroplasts is a direct outcome of the fixation of carbon under the influence of light and chlorophyll. He stated that starch is the first visible product of photosynthesis and that it is translocated from the leaf in the form of sugar. He seems to have considered that all the carbohydrates synthesized in the leaf pass at one time of their history through the starch stage in the chloroplasts. Sachs, however, worked almost exclusively with the leaves of sunflower, squash, bean, and other plants that are abundant starch formers.

As early as 1856 Boehm observed that the chloroplasts of *Asphodelus luteus*, *Allium fistulosum*, and others do not normally form starch. Later (1883) he placed the ends of etiolated leaves of *Phaseolus vulgaris* in sugar solutions and noted that they formed starch, while leaves of galanthus, hyacinth, and iris laid in 10 per cent sugar also showed an abundance of starch. He reasoned from these results that the same sequence of events occurred in the photosynthetic process. Schimper (1885) not only held that starch is converted into sugar in the plant but from his observations on the increase of starch in leaves which were artificially supplied with sugar solutions he concluded that glucose precedes starch in the process of photosynthesis. He considered that starch is formed from the glucose when the concentration of the latter exceeds a certain maximum which differs in different plants. Finally, in 1885 to 1886, Meyer emphasized the fact that the formation of starch in plants was by no means universal, since he observed that many of the monocotyledonous plants and especially the *Liliaceae* form very little starch in their leaves and some none at all. A very important contribution to the knowledge of the carbohydrate content of the leaves was the observation of Kayser (1883) that both sucrose and reducing sugars occur in the leaves of grape, beet, potatoes, and onion. He was the first to isolate sucrose in the crystalline form from the leaves of the grape.

The work of Boehm, Meyer, and Schimper indicates that the formation of starch in the leaves is preceded by the formation of the more simple carbohydrates. The chloroplasts like the leucoplasts form starch only when the supply of formative carbohydrates is in excess of the metabolic needs and translocating power of the cell in which they are contained or when the solution of the formation product has reached a certain stage of concentration.

The work of Kraus (1869) is also frequently quoted in order to show that starch is probably not the first carbohydrate formed in photosynthesis. He observed that the formation of starch in the cells of *Spirogyra* did not occur until five minutes after the commencement of illumination, while the evolution of oxygen commenced at

once. It is now generally considered by botanists very unlikely that such a complex and insoluble compound as starch should be the first product formed in the process of photosynthesis. The general opinion is that the first carbohydrate produced in the process is some form of sugar. The evidence as to which sugar it is will be presented in the following topics:

b. Daily Variations of the Carbohydrates in the Leaves.—The first quantitative determinations of the sugars in the leaf were made by Girard (1883, 1884). He observed that the proportion of sucrose in the leaves of the sugar beet was frequently twice as great at the close of the day as the following morning, while the amount of hexose sugars remained about the same. In 1893 Brown and Morris published their classical work on the daily variation of the carbohydrates in the leaves of the nasturtium. The evidence which they obtained was in accord with that of Meyer and Schimper that the starch in the chloroplasts is a secondary product and not the first one of photosynthesis. They also showed that the dissolution of the starch is brought about by the enzyme diastase. Brown and Morris noted that sucrose showed the greatest increase during the day of any of the carbohydrates of the leaf and that during the night it was the one most diminished.

Parkin (1912) found in the case of the leaves of snowdrop (*Galanthus nivalis*) that during any single day the percentage of hexoses remained fairly constant no matter what hour of the 24 the leaves were examined. The sucrose content, however, fluctuated greatly, increasing during the day and diminishing during the night, as may be observed by the following example:

Content	Per cent, dry basis, leaves picked at	
	9 a.m.	4:30 p.m.
Sucrose.....	9.8	14.7
Hexoses.....	12.4	11.6
Total.....	22.2	26.3

Parkin found also that the proportion of sucrose to hexoses decreased as the season advanced. In the early season the quantity of cane sugar was more than double that of the reducing sugars, whereas seven weeks later the two types were present in approximately the same quantities.

Knowledge of the daily variations in the carbohydrates of the leaves was greatly increased by the work of Davis and Daish (1913, 1914), Davis and Sawyer (1916), Davis, Daish, and Sawyer (1916), Davis (1916), and Davis and Sawyer (1916), who developed new methods and perfected old ones for the determination of the carbohydrates of leaf material.

In the leaves of the mangold, they observed the following facts: (1) During the earlier stages of growth when leaf formation is the principal function, sucrose was present in the leaf tissue in excess of the hexoses, but later in the season the latter sugars largely predominate. (2) All the sugars in the leaf increase in quantity from the first to the final stages of growth. (3) Of the total sugars, the hexoses form a progressively increasing proportion as the season advances. (4) In the first stages of growth practically all the hexoses and half the sucrose disappear during the night, but as the season proceeds a less proportion of the sugar disappears each night. (5) The pentosans form a larger and larger proportion of the matter insoluble in alcohol as the season advances.

In the case of the leaves of the potato at the stage of growth when the tubers are beginning to develop, the principal sugar present is sucrose, which increases in amount from sunrise to 2 p.m. and then falls off during the rest of the day and night. The hexoses, on the other hand, are present in the leaves in very small amounts, amounting to less than one per cent of the dry weight of the leaf. After the sucrose had reached its maximum at 2 p.m., the hexoses began to increase in the leaf, owing apparently to the hydrolysis of the saccharose. At the same time, soluble starch or dextrin is first detected in the leaf and its amount increased regularly up to 6 p.m., when the true starch reached its maximum for the day. After this time, both the soluble and the true starch decreased in amount, being converted apparently directly into hexoses. In none of the leaves of potato or other starch-bearing leaves were they able to detect maltose. The enzyme maltase evidently acts at once upon the maltose formed in the digestion of starch, so that there is no accumulation whatsoever of this sugar in the leaf.

In the leaves of *Tropaeolum majus*, *Cucurbita ficifolia*, *Vitis vinifera*, and others, Gast (1917) noted that sucrose was generally in excess of the other sugars, being less at night than during the daytime, and that the proportion of sucrose to hexoses decreased during the night. Miller (1924) determined the changes of the carbohydrates in the leaves of corn and the sorghums at 2-hr. intervals during a 24-hr. period. The total sugars in the leaves of these plants began to increase between 4 and 6 a.m., reached a maximum which varied from 12 m. to 5 p.m., and decreased gradually from that time until daylight the following morning. The insoluble carbohydrates were estimated as starch, according to the official method of acid hydrolysis, and thus include besides starch the pentosans and other insoluble carbohydrates that are converted into reducing sugars by boiling with hydrochloric acid. The insoluble carbohydrates thus estimated generally reached a maximum later in the day than the sugars and, after they had reached a maximum, showed little decrease until about midnight, after which they decreased rapidly until daylight. The non-reducing sugars in the leaves of the plants

studied were, in nine experiments out of ten, always in excess of the reducing sugars. The non-reducing sugars increased markedly during the day and decreased during the night, while the reducing sugars, as a rule, showed very little increase and the amount present at the different periods of the day was very irregular. The maximum increase in the reducing sugars in the leaves during the day amounted to only from one-




FIG. 25.—Graphs showing the variation in the water, dry matter, and carbohydrates of corn leaves during a 24-hr. period.

tenth to one-third of the increase in the non-reducing sugars. An example of the daily variation of the carbohydrates in the leaves of corn is shown in the following table and Fig. 25. These data were collected from the uppermost fully developed leaves of plants 4 to 5 ft. in height.

Stanescu (1927) noted that in the leaves of *Acer negundo* and *Medicago sativa* the monosaccharoses remained practically constant during the day and were much smaller in amounts than the disaccharoses, which showed a marked increase during the day and a diminution at night. In

DAILY VARIATION OF WATER, DRY MATTER, AND CARBOHYDRATES IN THE LEAVES OF PRIDE OF SALINE CORN, AT MANHATTAN, KANS., JULY 3 AND 4, 1919

Period ending	Dry matter	Water	Sugars			Starch ¹
			Total	Non-reducing	Reducing	
Percentage of the constituents						
July 3:						
7 a.m.	20.6	79.4	0.71	0.25	0.42	17.84
9 a.m.	21.2	78.8	1.01	0.31	0.65	18.72
11 a.m.	22.5	77.5	2.00	1.11	0.79	19.75
1 p.m.	23.4	76.6	3.44	2.34	0.90	21.12
3 p.m.	24.5	75.5	4.59	3.54	0.81	22.34
5 p.m.	24.3	75.7	5.92	4.23	1.41	22.85
7 p.m.	24.2	75.8	5.14	3.22	1.68	22.80
9 p.m.	23.6	76.4	3.47	1.77	1.05	23.13
11 p.m.	21.9	78.1	1.99	1.19	0.70	23.29
July 4:						
1 a.m.	20.7	79.3	1.60	1.04	0.48	21.61
3 a.m.	19.8	80.2	0.60	0.28	0.29	20.18
5 a.m.	19.0	81.0	1.51	1.02	0.40	19.88
Grams of constituents per square meter of leaf						
July 3:						
7 a.m.	39.3	152.2	0.28	0.09	0.16	7.01
9 a.m.	40.3	149.9	0.40	0.12	0.26	7.54
11 a.m.	42.3	146.1	0.85	0.47	0.33	8.35
1 p.m.	43.9	143.9	1.51	1.03	0.39	9.27
3 p.m.	45.3	140.3	2.08	1.60	0.37	10.12
5 p.m.	45.5	142.4	2.69	1.92	0.64	10.14
7 p.m.	45.3	142.6	2.33	1.46	0.76	10.33
9 p.m.	44.7	145.2	1.55	0.79	0.46	10.33
11 p.m.	43.0	153.8	0.85	0.51	0.30	10.01
July 4:						
1 a.m.	42.2	162.5	0.67	0.44	0.20	9.12
3 a.m.	40.0	166.0	0.24	0.11	0.12	8.07
5 a.m.	40.6	173.3	0.61	0.41	0.16	8.07

¹ The term "starch" as here used includes, besides the starch, the pentosans and other insoluble carbohydrates that undergo conversion into reducing sugars on boiling with hydrochloric acid according to the official method of acid hydrolysis for the estimation of starch.

the leaves of *Urtica dioica* and *Polygonum tuberosum* the two sugars remained constant during the day, but the disaccharoses were always present in the greater amount.

c. Variations in Different Portions of the Leaf.—It was noted by Parkin (1912) that the sugar content of the leaf of the snowdrop increased from above downward and that at the same time the ratio of the sucrose to

the hexose diminished. In the mangold leaf, Davis, Daish, and Sawyer (1916) found that the proportion of sugars and matter soluble in alcohol was always far greater in the petioles and midribs than in the blades of the leaves. In the midribs and petioles the hexoses always predominated greatly over the cane sugar. The proportion of hexoses to cane sugar was always very small in the blade of the leaf as compared with the value in the midrib. In passing from blades to midribs, from midribs to the tops of petioles, and from the tops of petioles to the bottoms, the ratio of hexoses to cane sugar steadily and rapidly increased. Thus in the blade the ratio of hexoses to cane sugar was 0.307, at the top of petioles 1.42, and at the bottom of petioles 2.48. The excess of reducing sugars over non-reducing sugars in the leaf stems of the sugar beet and in the stalks of wheat has been noted by Colin (1914) and Colin and Belval (1922). Weevers (1923) determined the sucrose and hexose content of the green and yellow parts of variegated leaves. He examined the leaves of *Pelargonium zonale*, *Acer negundo*, and *Humulus lupulus* among others and found that both cane sugar and hexoses were found in the green parts but that with few exceptions sucrose was found only in the yellow portions.

d. *The First Sugar Formed.*—Due to observations that (1) cane sugar is generally present in the leaves in considerable excess of the hexoses and shows a marked increase during the day and a decrease during the night while the hexoses remain practically constant and (2) the cane sugar of the leaves is changed into hexoses to be translocated from the leaf as is evidenced by the excess of hexoses over cane sugar in the midribs and stems, Perrey (1882), Brown and Morris (1893), Davis, Daish, and Sawyer (1916), Parkin (1912, 1925), Gast (1917), and Colin (1916, 1917) consider that cane sugar is the first product of photosynthesis. They consider that the hexoses present in the leaf are more easily accounted for as the products of the hydrolysis of cane sugar than as its precursors. Parkin (1912, 1925) considers that the carbohydrates resulting from the photosynthetic process may be in no case truly up-grade products. The earliest sugar to appear in the free state may be split off from some complex molecule, and this sugar might easily be sucrose in the higher plants. The quantitative variations of cane sugar in the leaves during the day and night and its excess over the hexoses together with the relationship of these two sugars in the midribs and veins do not necessarily indicate that cane sugar is the first sugar formed in photosynthesis. It cannot be determined definitely from chemical analysis whether the marked increase in the amount of non-reducing sugars in the leaves during the day is due to the fact that they are the primary sugars of photosynthesis or to the fact that they are formed from the more simple sugars and accumulate in the leaves during the day as temporary storage products (Miller, 1924). It is just as reasonable to suppose that hexoses are found and converted

into cane sugar as a temporary storage product as it is to reason that cane sugar is the first one formed. Dixon and Mason (1916) by microchemical tests of the photosynthetic cells of several plants found that there was a considerable concentration of hexoses in the chloroplasts or in the protoplasm immediately surrounding them. Other experiments suggest that while sucrose is concentrated in the large vacuoles, invertase is held apart from it in the protoplasm. They consider that it is thus probable that the hexoses are first formed and that when the concentration reaches a certain limit, condensation to sucrose due to invertase or some saccharogenic enzyme takes place and the sucrose thus formed is stored in the vacuole. Since the available space of the protoplasm is small, in sunlight the amount of sucrose will be greatly in excess of that in the protoplasm. On that account, the rise of sucrose on illumination shown by the analysis of leaves is not a cogent argument for regarding it as the primary sugar. The observations of Weevers (1924) also suggest that the hexoses are formed in the plants previously to the sucrose. Thus the leaves of *Pelargonium zonale*, which were kept in the dark until they were depleted of sugar, produced when exposed to light first hexoses, then cane sugar, and finally starch. The fact that in the variegated leaves in most cases hexoses were found in the green portions while sucrose was confined to the yellow portions also indicates that the hexoses are the first sugars formed. Cane sugar frequently appears in considerable quantities in leaves which contain a large amount of starch. It is contended by those who consider sucrose to be the first products of photosynthesis that this sugar is not a transition product, since so far as any one knows cane sugar does not arise directly from starch. Priestley (1924) suggests that the hexoses could be the primary photosynthetic sugars and that the starch in the leaves could be formed from them. The starch or other carbohydrates could thus be used in the synthetic metabolism of the protoplasm, while cane sugar might arise as a secondary product of the metabolism of the cell and thus have no direct relationship with either the hexoses or the starch. In regard to the question concerning the first sugar formed in photosynthesis, an observation of Miller (1924) is worthy of note. He found that the total increase in the dry matter of the leaves during the day could not be accounted for by the increase in the sugars and insoluble carbohydrates during the same period. The increase in the total sugars and insoluble carbohydrates in the leaves during the day approximated only from 46 to 92 per cent of the total increase in the dry weight of the leaves for the same period. Since the cellulose content of the leaves did not increase during that period, it would appear that certain compounds were being formed which are not detected by the methods of carbohydrate determination as now used.

From a chemist's viewpoint it would seem that the plant would first form the more simple carbohydrates from carbon dioxide and water and

then by condensation form the more complex ones like starch and cane sugar. Before making this assumption, however, one should consider the words of Pfeffer: "It is a very confusing error to presume that an organism in its metabolic economy must follow a course which seems to man, under the influence of existing chemical and physical knowledge, to be the most plausible course" (Spoehr, 1926).

E. CHEMISTRY

The chemical equation for photosynthesis is generally written as follows: $6\text{CO}_2 + 6\text{H}_2\text{O} \rightarrow \text{C}_6\text{H}_{12}\text{O}_6 + 6\text{O}_2$. This equation is based upon the fact that the volume of carbon dioxide absorbed is equal to the volume of oxygen emitted and that carbohydrates accumulate as products of the process. The equation thus represents the proportion of carbon dioxide and water used and the amount of oxygen released in the formation of hexose sugar. This equation is simple and shows little. It shows, so to speak, the materials which enter the hopper of the machine and the finished product which comes out at the spout but shows nothing concerning the intermediate stages in the process. Before considering the chemistry of photosynthesis some statements should be made in regard to the general nature of the process, so that the difficulties involved in the experimental study of this subject may perhaps be better appreciated.

The outstanding fact of photosynthesis is the building up from carbon dioxide and water of compounds of higher energy content, the energy being supplied by the radiant energy of the light from the sun. The process of photosynthesis is thus an endothermal reaction, and there are no known analogous reactions in which there is a storing of energy approaching in amount that taking place in this process (Spoehr, 1926). It is through this process, as will be mentioned later, that the energy of the sun becomes available for use on the earth.

The conditions under which the synthesis of carbohydrates occurs are also baffling, since this process proceeds rapidly in the living plant under ordinary conditions of illumination and at ordinary temperatures. Outside the living plant, however, such synthesis can be brought about only very slowly and under conditions much different from those of the living plant. The photosynthetic process is thus closely associated with or dependent upon the life activities of the plant, but the relationship between this process and the protoplasm or living matter is in no manner definitely defined.

1. The Function of Chlorophyll.—Although it is known that chlorophyll and probably the other pigments of the chloroplasts are necessary for photosynthesis, the manner in which these pigments play a part is not definitely known. Chlorophyll has very characteristic chemical and physical properties and it is possible that it may play both a physical and

chemical rôle in the photosynthetic process. Two of the physical properties of chlorophyll are the characteristic absorption spectrum and its power of fluorescence. It is now generally agreed that the chlorophyll absorbs the light energy necessary for photosynthesis, but the relation of the chlorophyll to the carbon dioxide which is ultimately reduced as a result of the absorbed energy is not known. Beyond the fact that chlorophyll absorbs certain rays of light which furnish the energy for photosynthesis, its functions are purely speculative. It is the intention here to mention only briefly some of the theories relative to photosynthesis. The student can readily discern from the discussion the almost total lack of experimental evidence on the subject, as is indicated by the wide diversity of views on the rôle that chlorophyll plays.

It has been considered by some that chlorophyll absorbs the energy of light and transmits it to another substance. Thus Usher and Priestley (1906, 1911) considered that the absorbed light energy is transferred to the carbon dioxide, which is thereupon reduced to formaldehyde. Tsweet (1911) was of the opinion that chlorophyll, since it exhibits fluorescence, functions in changing polychromatic light into monochromatic red light which is specifically absorbed by the carbon dioxide. As pointed out by Stiles (1925), however, carbon dioxide possesses no power for the absorption of light within the range of the visible spectrum. The carbon dioxide in the plant cell is present in an aqueous solution, and little is known concerning the absorption of the spectrum by the ions H^+ and HCO_3^- as they occur under this condition.

Baly, Heilbron, and Barker (1921) considered that light is absorbed by chlorophyll and radiated out again at infra-red frequencies which are utilized in the formation of formaldehyde and carbohydrates from carbon dioxide and water. Warburg and Negelein (1923), however, could observe no photosynthesis in *Chlorella* when exposed to infra-red light of wave lengths of 800 to 900 $\mu\mu$ and only a slight amount in wave lengths of 700 to 780 $\mu\mu$. Chlorophyll is considered by some to play a chemical part in photosynthesis as well as a physical rôle. It was suggested by Willstätter and Stoll (1918) that in the process of photosynthesis a compound is first formed between the chlorophyll and carbon dioxide and that light acts on this compound converting it into a substance of peroxide constitution which is then acted upon by an enzyme (Stiles, 1925). By some it is held that chlorophyll is acted upon by light to form a photochemical primary product which reacts with a derivative of carbon dioxide. Under this view it is considered that the actual reduction of the carbon dioxide or its derivatives is purely chemical, the light producing, by means of the chlorophyll, the reducing substance.

Dixon and Poole (1920) and Dixon and Ball (1922) performed experiments to determine whether the electrons were actually ejected from the chlorophyll by the incident radiation or were merely displaced within

groups of atoms or from molecule to molecule of chlorophyll. They considered that photosynthesis is apparently caused by light the frequency of which is too low to effect the expulsion of the electrons from the chlorophyll molecule. The photosynthetic reactions must thus concern the chlorophyll molecule itself. The wave lengths that are effective in displacing the electrons of chlorophyll as indicated by its sensitizing action on the photographic plate are the same as those that are effective in photosynthesis.

It would seem thus that the atomic groups of the leaf pigment enter into the reactions of photosynthesis and participate in the combinations and decompositions that ultimately lead to the formation of carbohydrates. From these observations, theories of photosynthesis which assume that the chlorophyll itself enters into the reactions are to be preferred to those suggestions which suppose that the reaction is accomplished externally to the chlorophyll by means of energy absorbed and transformed by it.

The rôle of the yellow pigments in the chloroplasts in photosynthesis is not known. The general indications are that they at least may act in a supplementary way in the process even if they may not be absolutely necessary (Ewart, 1918).

2. The Absorption of Carbon Dioxide by the Leaf.—The entrance of carbon dioxide into the leaf may rightly be considered the first stage in the photosynthetic process. It has been shown in Chap. VII that the capacity of the stomata for the diffusion of carbon dioxide into the leaf is far beyond that which is actually needed for the photosynthetic process provided that the partial pressure of this gas in the leaf is kept at approximately zero. The diffusion of carbonic acid in water, however, is a slow process, and this together with its low solubility in water and its low partial pressure in the atmosphere has long been recognized as conditions which to all appearances would be unfavorable to photosynthesis. According to Spoehr and McGee (1924), 1,000 cc. of water will dissolve 0.033 cc. of carbon dioxide at 25°C. from a concentration of 3 parts per 10,000 by volume. On the other hand, 1,000 g. of the leaves of sunflower with an area of 3.3 m.² and with a water content of 850 cc. would dissolve under normal conditions only 0.027 cc. of carbon dioxide if the water were considered as the absorption agency. This amount of leaf material, however, during the process of photosynthesis absorbs as much as 1,500 cc. of carbon dioxide per hour. The leaves of the nettle (*Urtica dioica*) have also been observed to have a high absorption capacity for carbon dioxide. Spoehr (1926), however, was unable to detect any absorption factor in the case of the leaves of spinach, turnip, lettuce, rhubarb, grass, and others, since the amount of gas that was absorbed was equivalent only to that which could be dissolved in the quantity of water present.

Since some leaves absorb a quantity of carbon dioxide greater than can be accounted for by the water present, it has been assumed that there is a substance in the leaf for absorbing this gas so that its absorption is accelerated and its concentration in the photosynthetic cells raised. Willstätter and Stoll (1918) considered that this substance is not related to the pigments of the chloroplasts but that it is an organic compound. Siegfried (1905) found that carbon dioxide combines with amino acids and concluded that the major portion of the carbon dioxide in the leaf forms definite compounds with the amino groups of the proteins and thus increases the concentration of carbon dioxide in the cells. He further considered that these compounds would dissociate to release the carbon dioxide as needed in the cells. Spoehr (1926), however, considers that the amount of nitrogen present is too small to account for all the carbon dioxide absorbed and believes that the indications are that the absorption of carbon dioxide is due to a carbonate to a bicarbonate reaction. It is not known, however, whether the absorption capacity of a leaf for carbon dioxide has any relationship to the process of photosynthesis.

3. Theories Concerning Photosynthesis.—The great difference between the chemical constitution of a carbohydrate and the carbon dioxide and water out of which it is formed suggests that these compounds are not transformed into sugar at a single step but that a series of compounds increasing more and more in complexity are produced until sugar finally appears as the finished product. Numerous theories have been proposed as to the probable course of the reactions and in regard to the intermediate products that might be formed. It is interesting to note that most of the experimental work relative to the chemistry of photosynthesis has been done in an attempt to verify these theories.

The first theory to explain the reactions which occur between the intake of carbon dioxide and water and the production of carbohydrates was made by Liebig (1843). He considered that the various organic acids as oxalic, tartaric, and malic were formed as intermediate products in photosynthesis. This theory was based on no experimental evidence and has found little or no support.

The formaldehyde hypothesis in regard to the intermediate products in photosynthesis has received by far the most consideration of any that have been proposed. In fact, with but a few exceptions all the theories of photosynthesis that have been proposed assume that formaldehyde is the final stage of reduction in the process. The main differences of opinion in regard to the various theories of photosynthesis have centered largely around the question as to whether the reduction of carbon dioxide to formaldehyde is accomplished in one step or whether there are intermediate products (Spoehr, 1926). The formaldehyde theory was first proposed by Baeyer (1870) and since this hypothesis has so greatly influenced the experimental work on photosynthesis, it seems desirable to review in

considerable detail some of the facts regarding its origin. In 1861 Butlerow discovered that formaldehyde in aqueous alkaline solution condensed to an optically inactive syrup possessing some of the properties of hexose sugars. Baeyer (1870) in discussing Butlerow's results considered formaldehyde in solution to be $\text{CH}_2(\text{OH})_2 \rightleftharpoons \text{H}_2\text{CO} + \text{H}_2\text{O}$ and suggested that the results obtained by him might be due to the condensation of six molecules of $\text{CH}_2(\text{OH})_2$ into a hexose sugar with the loss of six molecules of water. Baeyer also suggested that this might be the manner in which grape sugar is formed in the plant. He considered that the sunlight might split the CO_2 into CO and O, the oxygen escaping and the carbon monoxide being held by the chlorophyll. The monoxide is reduced to formaldehyde, $\text{CO} + \text{H}_2$, by the decomposition of water, and the formaldehyde is then condensed to sugar. Baeyer's hypothesis was formulated without any experimental evidence and was published only as a suggestion, yet it has directed the greater portion of the investigational work on photosynthesis and has become so commonplace in its mention that it is considered by many to be an established fact. The experimental evidence that has been obtained in an attempt to prove this hypothesis will be mentioned under another heading. Many modifications of Baeyer's theory have been proposed, but these differ but little from the original, and a detailed discussion of these theories is outside the province of this work.

Willstätter and Stoll (1918) considered that formaldehyde is the intermediate substance that is formed in the process of photosynthesis and proposed a theory concerning the manner of the reduction of carbon dioxide to this substance. According to Spoehr (1926), these investigators considered that carbon dioxide is added to the magnesium complex of the chlorophyll and thus becomes a component of the pigment, but this reaction does not alter the colloidal and optical properties of the chlorophyll. Under the influence of light, a molecular rearrangement of this carbonic acid derivative occurs and a compound of a formaldehyde peroxide nature is formed. The oxygen is split off from this peroxide compound, probably by an enzyme, and finally formaldehyde is released from the chlorophyll and condensed into sugar.

4. Experimental Evidence. *a. The Reduction of Carbon Dioxide.*—From the chemical standpoint, the reduction of carbon dioxide is the most important as well as the most difficult process in photosynthesis, and many attempts with many methods have been tried to bring it about. Although these attempts have been made under varied conditions, many of which are not comparable to those of the plant, and have given very contradictory results, they at least show the behavior of carbon dioxide under different conditions and may thus give some little light either directly or indirectly upon the mode of reduction in the photosynthetic process.

Previous to 1907 all the attempts to reduce carbon dioxide had resulted in the production of formic acid. In that year Fenton by passing a stream of carbon dioxide for 18 to 20 hr. through pure water in contact with several rods of amalgamated magnesium obtained a solution that indicated the presence of formaldehyde as indicated by the color tests. Weak alkalies seemed to aid materially in this reaction. In 1906 Loeb by means of the silent electrode and by using something to take up the oxygen, as, for example, chlorophyll, obtained formaldehyde and formic acid with ease and in quantity from carbon dioxide and water. He also noted the formation of glycolaldehyde from hydrogen and carbon dioxide under these conditions. The synthesis of a hexose sugar from this compound is apparently a rather simple process. Gibson (1908) formulated a photoelectric theory of photosynthesis in which it was considered that formaldehyde is synthesized from carbon dioxide in the presence of water by feeble electric changes which he considered occurred in the photosynthetic tissues when adequately illuminated, the light energy being transformed by the chlorophyll into electric energy. He considered that Loeb's experiment strengthened a part of this theory, and it has later (Dixon and Poole, 1920) been established that a slight photoelectric effect occurs in chlorophyll under illumination. Since the work of Loeb and Fenton, the experiments on the reduction of carbon dioxide have centered mainly around the influence of ultra-violet light. Work on the effect of ultra-violet light as obtained especially from the quartz mercury-vapor lamp has been reported by Berthelot and Gaudechon (1910), Usher and Priestley (1911), Stocklasa and Zdobnický (1911, 1912), Spoehr (1916, 1923, 1926), and Baly, Heilbron, and Barker (1921, 1923). The results that have been reported are very contradictory. Some workers have obtained formaldehyde only in the presence of nascent hydrogen, while others have not noted the need of such. Some have obtained formaldehyde in the polymerized form, some both formaldehyde and sugar, while yet others could obtain no formaldehyde at all. Thus Baly, Heilbron, and Barker (1921) reported that an aqueous solution of carbon dioxide gives formaldehyde when exposed to light of wave length of $200\mu\mu$. They found also that the photosynthesis of formaldehyde from carbon dioxide and water could be photocatalysed by certain colored basic substances as colloidal uranium, colloidal ferric hydroxides, malachite green, and methyl orange. Under these conditions the formation of formaldehyde took place in visible light. Spoehr (1916, 1923) in numerous well-controlled experiments was, however, unable to obtain any definite evidence of the formation of formaldehyde from carbon dioxide and water under the action of ultra-violet light. Under the conditions of his experiments, however, he was able to obtain formic acid in small amounts. The reasons for such contradictory results are not known, but Spoehr (1923) suggests that where a direct

reduction of carbon dioxide to formaldehyde by means of ultra-violet light has been reported there existed certain essential conditions or factors not known by the investigator or there were some misinterpretations of the experimental observations.

It is doubtful if the conditions under which carbon dioxide was reduced in the various experiments just reported are comparable to the conditions which exist in the plant. Apparently the ultra-violet or any rays that lie outside the visible spectrum play little or no part in photosynthesis. Photosynthesis, for example, proceeds normally when ultra-violet rays are excluded from the plant, as in the case of their growing under ordinary glass. It would thus, in the words of Spoehr (1916), seem that we have no clear record of a reduction of carbon dioxide or its salts to formaldehyde which could be applied to the process going on in the leaf under the conditions which therein exist.

Considerable work has been done to determine the behavior of isolated chlorophyll and the other pigments in regard to the reduction of carbon dioxide and the formation of formaldehyde. It was reported by Usher and Priestley (1906, 1911) that films of extracted chlorophyll in the presence of carbon dioxide and moist air produced formaldehyde and hydrogen peroxide under the influence of light. The production of formaldehyde under similar conditions was observed by Schryver (1910), who considered that it was in combination with the chlorophyll.

Since then it has been observed by Wager (1914), Warner (1914), Jorgensen and Kidd (1916), Osterhout (1915, 1918), and Ewart (1920) that formaldehyde is formed when chlorophyll is exposed to the light but only in the presence of oxygen in a moist atmosphere. The formation of formaldehyde occurs regardless of the presence of carbon dioxide. When the extracted chlorophyll is thus exposed to the light, the first change observed is its yellowing and ultimate bleaching. In the first stage while bleaching is complete, the quantity of formaldehyde reaches a maximum and then diminishes. It is considered by most of the investigators just mentioned that the aldehyde which appears under these conditions is not produced by the reduction of carbon dioxide but rather by the oxidation or decomposition of chlorophyll under the influence of light and oxygen. It is on that account, therefore, suggested by Ewart (1907) and Wager (1914) and others, that the production of sugar may be initiated by the photooxidation of chlorophyll and the subsequent polymerisation of the aldehyde thus formed rather than by the direct photosynthesis of carbon dioxide and water. That chlorophyll or some component may decompose during photosynthesis was suggested by the work of Osterhout and Haas (1918). They found in experiments with *Ulva*, *Potamogeton*, *Spirogyra*, and other plants which had been kept in the dark, that they began photosynthesis as soon as they were exposed to sunlight and

steadily increased their rate until a constant speed was attained. Since no limiting factors as light and carbon dioxide were involved, these authors considered that the behavior indicated that sunlight decomposes a substance whose products either catalyze photosynthesis or enter directly into the reaction.

Osterhout (1918) and Burk (1927) employed aniline dyes to ascertain if aldehyde could be produced by them as in the case of chlorophyll. A considerable number gave positive results. Osterhout found methyl green and iodine green to be the most reliable. Burk used malachite green. Osterhout sprayed aqueous solutions of the dyes upon filter paper until the paper was a deep green color when dried. These were then exposed to sunlight under bell jars for several days until the color disappeared. A positive test for aldehyde was obtained in the majority of cases.

b. The Condensation of Formaldehyde to Sugar.—Since it was assumed in Baeyer's hypothesis that formaldehyde is condensed to sugar in the presence of alkalis in the photosynthetic process, numerous experiments have been conducted in an attempt to bring this about in the laboratory. Positive results have been obtained but in many cases under conditions of high temperatures and in concentrations of alkalis that are in no way comparable to the conditions which prevail in the plant (Nef, 1913; Ewart, 1919). It has also been determined that a great complexity of reactions occurs when a solution of formaldehyde is treated with an alkali, so that not only some sugar but also a large number of other compounds are formed. The condensation of formaldehyde to sugar is thus not such a simple process as had formerly been supposed. The attempts to form sugar from formaldehyde under conditions comparable to those existing in the green plant have given conflicting results. Spoehr (1916) placed 3 per cent solutions of formaldehyde in tenth-normal solutions of weak alkalis in glass flasks and exposed them to sunlight for as long as four months. The solutions of formaldehyde in calcium carbonate, potassium bicarbonate, zinc carbonate, and basic magnesium carbonate showed no trace of sugar formation. The solutions of formaldehyde in lead hydroxide, calcium hydroxide, and potassium carbonate formed sugar in the dark as well as in the sunlight.

The formation of sugars on the exposure of aqueous solutions of formaldehyde to ultra-violet light was demonstrated by Moore and Webster (1918). In the same year it was reported by Baly, Heilbron, and Barker (1921), Baly (1922, 1924), and Heilbron (1923) that an aqueous solution of formaldehyde is polymerized to reducing sugars in light of wave length of $290\mu\mu$. In the presence of paraldehyde, sodium phenoxide, and certain metallic salts which absorb light of wave lengths $290\mu\mu$ the yield of formaldehyde was materially increased, since these substances protected it from polymerization when it was formed.

In contrast to these investigators, Ewart (1920) concludes that the production of formaldehyde does not form a stage in the synthesis of sugar in the plant and that alkalis do not polymerize formaldehyde to sugar except to a very slight extent. Pronounced sugar formation occurs only when the alkali acts on a polymer such as paraformaldehyde, the polyhydrate, or metaformaldehyde, and in such cases the endothermal reaction may be very violent and not applicable to the conditions in the plant. Baly (1922) and Heilbron (1923) state that ordinary formaldehyde is not condensed to sugar under ordinary conditions, but they consider that the formaldehyde molecule produced in the process of photosynthesis is in a highly reactive state and has been designated by them as "activated formaldehyde." The formaldehyde of this type is quickly condensed to sugar and cannot be detected in the plant. The formaldehyde that is detected in the leaf they consider as a secondary product from reactions other than photosynthesis. Baly (1928) by a suspension of pure aluminium hydroxide maintained by a stream of carbon dioxide exposed to ultra-violet light obtained a much greater yield of carbohydrates than if no suspensions were used. The best yield of carbohydrates, however, was obtained by passing a stream of carbon dioxide in water through a suspension of nickel carbonate or cobalt carbonate, exposed to the light from an ordinary tungsten-filament electric lamp. It was found that these particles used for the surfaces must be absolutely free from alkalis or the formation of carbohydrates will not occur. At times, even when freed from all alkali, the carbonates of nickel and cobalt were entirely ineffective in promoting photosynthesis. These suspensions could be activated, however, by heating to 120° or by exposure in thin layers to ultra-violet light. These experiments of Baly are important in that they indicate that surface phenomena are of primary importance in the reduction of carbon dioxide to carbohydrates and that sugar is formed directly from carbon dioxide by a process which is physically similar to that of the living plant. The amount of carbohydrate obtained, however, is very small, so it has not been possible to carry on a complete analysis of the different materials obtained in the process. It has, however, been fairly definitely determined that glucose and fructose are present.

c. The Detection of Intermediate Products in the Leaves.—Most of the experiments for the determination of intermediate products of photosynthesis have been confined to attempts to identify formaldehyde in the green parts of plants. Many of the reports are of no value, since it has later been found that the methods used were at fault and were in many cases not specific for the substance being determined. The identification of formaldehyde in green leaves, however, has been reported by numerous and accurate investigators among whom are Grafe and Vieser (1906), Kimpflin (1907), Gibson (1908), and Fincke (1913). There is thus appar-

ently no doubt but that formaldehyde occurs in the green parts of plants under certain conditions. There is no evidence, however, that it is a product of photosynthesis, since, as stated by Spoehr and others, there are a number of components of plants which may yield formaldehyde when exposed to light or it may arise in the general metabolic reactions of the plant.

d. Nutrition Experiments with Organic Compounds.—It has been stated in Chap. VI that plants are capable of utilizing in their metabolism certain organic compounds if presented to their roots. This utilization is manifested by increased growth and by the formation of secondary or condensation products as evidenced, for example, by the appearance of starch in the tissue after the plant has been given sugar as a nutrient. Various organic compounds, principally formaldehyde, which are considered intermediate products of photosynthesis have been presented to plants to determine whether the plant could utilize them in the formation of carbohydrates. Formaldehyde has been presented to plants in nutrient solutions, by its introduction into the water in which aquatic plants are growing and in the form of vapor in the atmosphere bathing the aerial parts of the plant.

Bokorny (1891 to 1911) was the first to try the effect of formaldehyde vapor on plants, and his work has been followed by that of Grafe and Vieser (1909, 1911) and Baker (1913). These authors agree that formaldehyde can be used to some extent in the light for the synthesis of carbohydrates and that starch in some cases appears as a secondary product, although in some cases there were chances for errors in the experiments. They also noted that formaldehyde was not utilized in the dark and that the poisonous effects of formaldehyde were always more marked in the dark than in the light. Spoehr (1916) found that formaldehyde mixed with air quickly oxidized to formic acid in sunlight and suggests that formic acid might be the source of carbon in the formaldehyde experiments that have been mentioned. Jacoby (1919, 1922) placed abscised leaves of the nasturtium in the dark with the petioles immersed in water and with the laminae of the leaves surrounded by a humid, carbon dioxide-free air, containing the vapor of formaldehyde. The leaves subjected to the formaldehyde for 24.5 to 32 hr. increased in dry weight from 12 to 15 per cent as compared with an increase of 1.7 to 5.1 per cent in the controls. He considered that the formaldehyde under these experiments was fixed by the plant. Results similar to Jacoby's have been obtained by Sabalitschka and Riesenbergl (1924) with *Phaseolus multiflorus* and *Pelargonium*.

The utilization of formaldehyde from nutrient solutions has been studied by Bokorny (1911), Nicholas and Nicolas (1922), and Sabalitschka and Weidling (1926). They find that plants can polymerize formaldehyde thus presented to carbohydrates equally well in the light

or dark. The latter investigators found the optimum concentration of formaldehyde in the nutrient solution to be 0.024 per cent. Higher concentrations injured the enzymes and retarded or inhibited the condensation. They consider that this offers strong confirmation of the hypothesis that formaldehyde is a stage in the production of starch under normal conditions.

It has generally been considered that if formaldehyde or other organic substances could be utilized in plant growth or in the formation of carbohydrates within the plants, this was evidence that they were intermediate products in photosynthesis. There seems, however, to be no grounds for such a conclusion. The organic compounds that plants may absorb and utilize in the formation of sugar and then starch are very numerous, and the experiments that have been performed, especially with formaldehyde, only make that fact the more evident but prove in no way that formaldehyde or any of the other substances so utilized are intermediate products in the process of photosynthesis.

The student can easily judge from this discussion of the chemistry of photosynthesis that but little is known concerning the mechanism of the process. The facts that are known are that the process takes place under the influence of the visible portion of the spectrum, that chlorophyll, water, oxygen, and carbon dioxide are necessary, that carbohydrates are formed and oxygen eliminated, and that the process proceeds under the general conditions which are suitable to the activities of living organisms. These facts are not new and have been known in a general way for more than 60 years. The enormous amount of research upon the process of photosynthesis during the past half century has thrown little or no additional light upon the subject. The problem is evidently too complex for specialists in any one field of science to solve, and, in the words of Spoehr (1916): "The subject of photosynthesis requires for its investigation the masterly application of many branches of science—physics, chemistry, plant physiology and the frank cooperation of the most skilled workers in these various fields."

F. FACTORS WHICH AFFECT PHOTOSYNTHESIS

The physiological processes that occur in plants are multiconditioned, so that in an investigation of the influence of one factor or condition, the interrelation of this factor with the others concerned in any process must be taken into consideration. It is, therefore, impossible to speak of a single condition as being the cause of an observed effect in a plant (Livingston, 1918), but one must consider that a given result depends upon numerous other external and internal conditions.

The conception of multiconditioned processes was first recognized by Liebig (1843) and was expressed in his law of the minimum in regard to

the yield of field crops. This law as commonly stated says that "The yield of any crop always depends on that nutritive constituent which is present in minimum amount." This means, as stated by Hooker (1917), that if the available amounts of the essential plant nutrients are divided by their respective growth values, the smallest quantity obtained gives the maximum amount of growth possible. Liebig, however, apparently did not consider water supply, oxygen supply, temperature, and other factors which influence the yield of a crop as well as the supply of nutrients, so it is not nearly so easy to express the law of the minimum as might be inferred from its original rather simple presentation.

The process of photosynthesis is one that is conditioned by numerous separate factors. It was realized by Pfeffer (1900) and Pantanelli (1903) that the optimum value in photosynthesis was not a fixed value in the case of any condition but might depend upon other conditions. It remained, however, for Blackman (1905) to enunciate this fact clearly and to crystallize the facts in regard to the interaction of factors not only in the process of photosynthesis but in regard to other physiological processes as well. In a consideration of the interaction of factors in the




Fig. 26.—Diagram to illustrate the action of a limiting factor. Description in the text. (After F. F. Blackman, "Annals of Botany," 1905.)

process of photosynthesis he stated his law of limiting factors: "When a process is conditioned as to its rapidity by a number of separate factors, the rate of the process is limited by the pace of the 'slowest' factor." The classical example used by Blackman was the interaction of carbon dioxide and light. Suppose that a leaf has enough light falling upon it to supply sufficient energy to decompose 5 cc. of carbon dioxide per hour. If the leaf is supplied, for example, with only 1 cc. of carbon dioxide per hour and then this amount is increased up to 5 cc. per hour, the rate of photosynthesis will increase from one- to fivefold. After the rate of carbon dioxide is increased beyond 5 cc. per hour, the rate of photosynthesis will remain the same as it was when the rate of carbon dioxide application was 5 cc. per hour. Light in this case is thus the limiting factor in the photosynthetic process. If the intensity of the light is increased until it is sufficient to decompose 10 cc. of carbon dioxide

per hour, an increase in the pressure of the carbon dioxide will increase the rate of photosynthesis until the leaf is supplied with 10 cc. of carbon dioxide per hour. If a larger amount of carbon dioxide is supplied, the rate of photosynthesis will remain the same, since light will at that point again become the limiting factor (Fig. 26). Thus it is impossible to investigate the relation between carbon dioxide supplied and the rate of photosynthesis without considering the factor of light.

The law of limiting factors is an elaboration of the law of the minimum and is of general application where a process depends upon a number of factors. There is considerable difference of opinion regarding the general applicability of the law of limiting factors. Hooker (1917) considered that the individual processes obey the law but that it does not apply to the questions of general development. Crocker (1918) considered that it is a question whether the law of limiting factors applies to plant activities as generally as or with anything like the rigidity assumed by some. He suggests that the question should not be so much what external factor is the limiting one as what internal condition or inhibitor must this factor act upon to initiate the reaction that is under consideration.

The factors which influence the rate of photosynthesis may, in common with other factors which influence the general process of plants, be divided or grouped into external factors and internal factors depending upon whether they are conditions which exist in the external medium or those which exist within the plant due to its structure or composition. The external factors which influence photosynthesis are the carbon dioxide supply, light, temperature, water supply, and numerous other factors which are essential to the general growth and vigor of the plant. The known internal factors which play a part in the process are the chlorophyll content and the protoplasmic factors.

1. The Carbon Dioxide Supply. *a. Amount in the Air.*—The amount of carbon dioxide in the air is approximately 3 parts per 10,000 by volume and this proportion is very constant whether the samples are taken over the sea or over the land. In industrial centers or in cities where large amounts of carbon dioxide are being liberated, the percentage may be increased somewhat, as also occurs near the surface of the soil where the decay of organic matter may considerably augment the average amount. Thus Lundegårdh (1924), as reported by Spoehr (1926), found in a well-fertilized field of beets in October that the carbon dioxide content of the air at the surface of the soil was 0.053 to 0.28 volume per cent, above the leaves 0.04 to 0.067 per cent, and at a height of one meter 0.03 to 0.07 per cent. Bornemann (1920, 1921) and Lundegårdh (1922) considered that more carbon dioxide is evolved from well-manured and well-cultivated land than from that which is not manured or cultivated and considered that one of the advantages of good cultivation is the release of

large amounts of carbon dioxide at the soil surface. Keuhl (1926) believed that mineral fertilizers are beneficial to a certain extent in that they cause a greater production of carbon dioxide by hastening bacterial action in the soil. Gerlach (1921), however, could obtain no positive evidence that stable or green manures could act as producers of carbon dioxide in amounts which might be beneficial to crops. The fact that the concentration of carbon dioxide is considerably higher near the soil surface than in the upper atmosphere may be of great importance in the growth of plants, since, as will be shown later, carbon dioxide can be used by plants to advantage in much stronger concentration than that which prevails in the general atmosphere.

The carbon dioxide content of the soil atmosphere is always higher than that of the atmosphere above ground. Lundegårdh (1924) states that it varies from 0.12 to 2.5 per cent by volume, while Banal (1926) states that the amount is from 5 to 10 per cent higher than that of the general atmosphere.

The carbon dioxide of the air that is combined by the plant is replaced by the decay of organic matter, by the respiration of animals and plants, by the combustion of wood, coal, gasoline, and other products, by the disintegration of rocks, especially limestone, and by the gases escaping from volcanoes. Due to these replacements the carbon dioxide content of the air remains practically constant. The carbon dioxide content of water should also be noted here. Water can absorb from the air, at 760 mm., 0.04 per cent of its own volume of carbon dioxide at 10°C., 0.03 per cent at 15°C., and 0.02 per cent at 20°C. Sea water contains in both the free and combined state about fifty times as much carbon dioxide as does the atmosphere, but the greater portion of it is not available to the plant.

b. Amount Used by the Plant.—The relatively small amount of carbon dioxide in the air was for a long time a stumbling block in the determination of the source of the plant's carbon supply. It was difficult to conceive that an element which constitutes from 40 to 45 per cent of the dry weight of the plant kingdom could be obtained from the small quantity that exists in the atmosphere. An enormous volume of air must be depleted of carbon dioxide to supply the carbon for a crop, as may be illustrated in the case of corn by the following example:

In 10,000 l. of air there are approximately 3.1 l. of CO₂. Since 1 l. of CO₂ weighs approximately 2.0 g. and since carbon constitutes three-eleventh of the weight of CO₂, 3 l. of carbon dioxide contain approximately 1.7 g. of carbon. Thus in 10,000 l. of air there is present in the form of carbon dioxide 1.7 g. of carbon. A single mature corn plant including stem, leaves, grain, cob, and roots contains 364 g. of carbon (Latshaw and Miller, 1924). Thus a single corn plant must deplete $364 \times 10,000 \div 1.7$ or 2,141,186 l. of air of its CO₂ to obtain the carbon that it has combined. Since 1 l. of air weighs approximately 1.3 g., the

weight of the air that would be depleted by such a plant would be 2,141,186, $\times 1.3$ or 2,783,542 g., which is equivalent to 2,783.5 kilos or 3.1 tons. A single corn plant thus to obtain its supply of carbon must deplete 3.1 tons of air of its carbon. Considering 6,000 corn plants to the acre, an acre of such plants would thus deplete 18,600 tons of air of its carbon dioxide in order to obtain the total amount of carbon which these plants contain.

The evidence in regard to the ability of the plant to use carbon monoxide is confusing. Under some conditions it apparently can be used by the plant to advantage, while under others it has a toxic effect. Thus Bottomley and Jackson (1903) found that young plants of nasturtium grown in sterilized sand and in air in which the carbon dioxide had been replaced by an equal quantity of carbon monoxide did not grow, but that when the amount of carbon monoxide was increased to twenty times the carbon dioxide, the plants grew well and were normal and healthy, provided that oxygen was added in amount sufficient to keep its pressure the same as air. Plants placed in air free from carbon dioxide but containing 10 per cent of carbon monoxide produced abundant starch when placed in the sunlight. They noted also that when carbon monoxide was so used, only one-half the normal amount of oxygen was given off. On the other hand, however, Richards and MacDougal (1904) found that CO was very toxic to seedlings of corn, sunflower, wheat, and rice which were grown in an atmosphere in which the nitrogen had been replaced with CO but with a normal oxygen pressure.

It has long been known that a plant can obtain all the carbon from the air that it needs for its growth and development, but since the soil atmosphere contains such a relatively high concentration of carbon dioxide the question has frequently arisen whether the plant is able to draw on this supply through the roots and utilize it in photosynthesis. Two early investigators, Godlewski (1873) and Moll (1878), were unable to obtain any starch in the leaves of plants which were grown in air free of carbon dioxide but with the roots growing in soil rich in organic matter. Later investigators, Cailletet (1911), Moillard (1912), Maquenne (1911), Pollacci (1917, 1920), Breazeale (1923), and Banal (1926), however, have obtained evidence that plants may absorb CO₂ from the soil to advantage in the process of photosynthesis. Thus, for example, Pollacci (1920) grew plants in an air free from carbon dioxide but with the roots in soil rich in humus or in nutrient solutions containing carbon dioxide and observed that plants of *Zea mays*, *Acer pseudoplatinus*, *Quercus aesculus*, and others lived under such conditions and stored starch. There thus appears to be good evidence that a green plant may absorb carbon dioxide from the soil and thus supplement its supply from the air.

c. Concentration and the Rate of Photosynthesis.—The experimental evidence in regard to the increase in the photosynthetic rate due to

increasing the normal carbon dioxide supply of the atmosphere is rather confusing. This is due to the fact that many workers did not consider other factors which are known to play a part and to the fact that the interaction of numerous factors in this regard are not understood by the investigators today. A rather detailed discussion of the experimental work in regard to the effect of the concentration of CO_2 on the photosynthetic rate will be given, since this subject is of interest not only from a purely scientific standpoint but from the practical viewpoint as well. In 1873, Godlewski reported that the optimum value of the CO_2 content for photosynthesis for clear days was between 5 and 10 per cent for the plants with which he worked, while Kreuzler (1885 to 1890) noted that the photosynthetic rate increased with the increase of carbon dioxide concentration and reached its maximum when the carbon dioxide content was thirty-five times that of the normal or approximately one per cent of the atmosphere. Under more exact control methods Brown and Escombe (1902) found with concentrations of CO_2 lying between 0.6 part and 6 parts per 10,000 of air, when the air was passed over leaves attached to the plant and exposed to various intensities of sunlight, that the rate of absorption of CO_2 was strictly proportional to its partial pressure. Thus for example, in the case of the leaves of the sunflower where the mean concentrations of CO_2 over the leaf were 2.22 parts per 10,000 and 14.82 parts per 10,000, respectively, the ratio of the partial pressures was as 1:6.6, while the CO_2 absorbed by the leaves under these conditions was, respectively, 248.2 cc. and 1,802.8 cc. or in the ratio of 1:7.2. In another case, the ratio of the partial pressures of the CO_2 was 1:4.4 and the ratio of the CO_2 absorbed by the leaves, 1:5.3. Blackman and Smith (1911) studied the effect of different concentrations of carbon dioxide upon the rate of photosynthesis of *Elodea* and *Fontinalis*, submerged water plants, under like conditions of temperature and light, the CO_2 supply being varied through a range of 0.0025 to 0.054 g. per 100 cc. of water. It was found that in the weaker solutions of CO_2 the rate of photosynthesis increased directly with the CO_2 supply provided light was not a limiting factor but that with higher concentrations the rate of photosynthesis became depressed. Boysen-Jensen (1918) and Lundegårdh (1921) working with leaves of land plants found results similar to those obtained by Blackman and Smith. Warburg (1919) and Harder (1921) working on water plants failed to find a direct proportionality between CO_2 concentration and the rate of photosynthesis. Thus Warburg (1919) in working with *Chlorella* found that photosynthesis is proportional to the CO_2 concentration between 0.05 and 10 where the unit concentration is that of CO_2 in water in equilibrium with the atmosphere. Above this limit further increases in CO_2 concentration resulted in increased photosynthesis until the process became constant. In this connection, too, it was observed by Blackman and Smith (1911) that plants vary in their ability to assimilate

CO₂ from the same concentration. Thus under a given set of conditions *Fontinalis* assimilated only one half as much CO₂ as did *Elodea*. They suggested that this difference in utilization might be due to the difference in the absorption ability of the two plants. The behavior of plants toward different concentrations of CO₂ and light intensity in relation to photosynthesis has been recently again investigated by Maskell (1928) and James (1928) in regard to both land plants and submerged plants with the thought of accounting for some of the differences recorded by various workers on this problem. In experiments of this type it should be remembered that only the concentration of CO₂ in the external medium is open to the direct control of the experimenter and that the internal rates of diffusion are due to many and varied factors which in many cases are beyond his control. The rate of diffusion from the external surface of the plant to the surface of the chloroplasts is apparently the important determining factor. Thus Maskell (1928) considers that the rate of apparent photosynthesis when CO₂ is a limiting factor may be regarded as being determined by a potential, the external CO₂ concentration, and a series of resistances, namely the stomatal resistance to diffusion, that in the intercellular space system, the liquid diffusion path up to the surface of the chloroplast, and, furthermore, "resistances" in the photochemical and chemical phases of photosynthesis. The form of the relation between the CO₂ supply and photosynthesis may be greatly modified by the alteration in the relative magnitude of the resistance in the diffusion phase, which may be altered by numerous and varied conditions. When the relation of the CO₂ concentration to the rate of photosynthesis is considered in this light it is seen why inconsistent results have been obtained. The whole curve expressing the relation between the rate of photosynthesis and the concentration of carbon dioxide when external factors are kept constant may be regarded as consisting of three parts (Stiles, 1925). The first ascending part of the curve, corresponding to the condition where with increasing carbon dioxide concentration photosynthesis increases proportionately, is approximately a straight line. This merges with or without a break into a part parallel or approximately so to the axis of the CO₂ concentration where light, stomata, protoplasm, rate of diffusion, etc., are limiting the process. This region of the curve then passes over into a descending part, where with increasing CO₂ concentration, the rate of photosynthesis is lowered on account of toxic action due to the high concentration of the gas.

The discovery that green plants can increase their photosynthetic rate with an increase of the CO₂ content of the atmosphere has stimulated investigations in regard to the utilization of this principle in agricultural practice. Such experiments have been confined mostly to plants growing in the greenhouse, although considerable work has been done under field conditions.

d. Application in Agricultural Practice.—Brown and Escombe (1902) and Demoussy (1903 to 1904) did the first work in applying increased amounts of CO₂ to plants upon a relatively large scale. Demoussy obtained increases in dry weight of 158 per cent for those plants growing under conditions of CO₂ fertilization. Brown and Escombe, on the other hand, obtained only negative results. They grew the plants in closed roomy compartments in which the CO₂ supply varied from three to one hundred times that of normal. They supplied the plants for 12 hr. with this concentration, after which they were exposed to normal conditions for the next 12 hr. They found that a concentration of CO₂ as high as 0.1 per cent was decidedly injurious to plants under these conditions and their control plants were always the more vigorous. The treated plants developed abnormally in that their leaf area was reduced; the internodes developed more slowly, while the flower buds did not open, and no fruit was produced. Negative results were also obtained by Cummings and Jones (1918) when plants were grown in closed containers with an increase of the normal CO₂ concentration.

It has thus developed, if any reliable results are to be obtained by CO₂ fertilization, that the plants must be grown in open compartments under as nearly normal conditions as possible with the exception of the concentration of the carbon dioxide (Bolas and Henderson, 1928). The increased humidity of the air in a closed container is apparently one of the detrimental factors when experiments are conducted in that manner. The purity of the CO₂ is a very important factor in this type of experiment (Owen and Williams, 1923; Cerighelli, 1921). The distribution of the CO₂ must also be considered. Cummings and Jones (1918, 1920) allowed the gas to diffuse slowly but continuously around the plants during the application period, the only precautions being that the escaping gas did not come in direct contact with the leaves but was liberated a few inches from the plant. In most cases, however, the amounts of CO₂ that have been used have not been definitely measured. The gas has simply been liberated alongside of or among the plants growing in open containers or in the field. Under such conditions it has been found that there is little or no danger of increasing the CO₂ content to toxic amounts. Cummings and Jones, using open boxes 26 in. high, 26 in. long, and 18 in. wide, added during an 8-hr. period as much as 348 l. of gas, the dry weight of the plants increasing with the increased quantities added up to that amount.

In practically all cases where the CO₂ supply to field and greenhouse crops has been increased, beneficial results have been obtained as measured by increased yield of grain, fruit, or amount of dry matter produced. In Europe, H. Fisher (1912 to 1927) has been one of the leading investigators in using CO₂ as an aerial fertilizer. In some cases he has purified the carbon dioxide from the gases which emanate from smelter furnaces and has conveyed it in pipes to greenhouses and field plots. By this means increased yield and more vigorous growth were obtained with potatoes, beets, tomatoes, and bush beans. Favorable results from the application of CO₂ have also been obtained by Riedel (1919, 1921), Cummings and Jones (1918, 1920), Jess (1921), Bornemann (1920), Owen, Small, and Williams (1926), and Gradenwitz (1920). Thus Riedel (1919, 1921) reported that the yields from tomato plants in a greenhouse into which CO₂ was introduced through perforated pipes was 175 per cent of the weight of the yield in a greenhouse with ordinary air. Cucumbers under like conditions increased 235 per cent over controls, while spinach, potatoes, and barley increased 150, 190, and 100 per cent, respectively, over the controls. Field plots gave yields varying from one and one-half to three times those of the ungasped plots. Jess (1921) in outdoor experiments with Irish potatoes increased the average weight of the tubers from 140 to 330 g. by the application of CO₂. In the greenhouse the yield of tomatoes was increased from 29.5 kilos for an untreated house to 81.3 kilos for the treated one, while the yield of cucumbers was increased from 138 to 235 kilos. In America the

most extensive work on the fertilization of plants with CO_2 has been reported by Cummings and Jones (1918, 1920). These experiments were all under greenhouse conditions and the plants were grown in large open containers in the manner that has previously been described. The plants used in these experiments included peas, beans, radishes, potatoes, lettuce, endive, Swiss chard, nasturtium, and strawberries. In the case of beans, the dry weight of the seeds produced by the treated plants was from 32 to 204 per cent higher than the checks, while the dry weight of the pods was from 75 to 143 per cent higher than the controls. The percentage of proteins was practically the same for both treated and untreated plants, while the carbohydrates showed an increase. In this connection it is worthy of note that Kostytschew observed that under conditions of increased CO_2 content the rate of photosynthesis is decidedly higher in legumes than in non-leguminous plants. Cummings and Jones (1918) found also, in the case of peas, that the total dry matter of the plant was from 18 to 117 per cent greater than the checks, while the dry weight of the seed increased from 167 to 291 per cent over the control. The results for the potatoes showed that the total number of tubers was 338 for the treated and 231 for the untreated, while the gain in weight of the tubers ranged from 7 to 325 per cent of the controls. Endive, lettuce, and Swiss chard all showed a marked response to treatment with CO_2 . In the case of lettuce and Swiss chard, the number of leaves was increased approximately 10 per cent. The leaves of lettuce, however, were darker green and tougher in the treated than in the untreated. The average gain for strawberries in weight was 80 per cent, while the increase in the number of plants was 55 per cent. Nasturtium plants showed marked and definite response to treatment with CO_2 . The gross weight was greater, more flowers bloomed, and blooming began earlier than with the untreated ones. Lemmermann (1920, 1926), Gerlach (1919, 1926), and Spigartis (1923) are the only investigators who do not report an increase in plant production from application of carbon dioxide. A general review of the experiments in regard to the application of increased amounts of CO_2 to plants is given by Kuiper (1920). While the application of CO_2 apparently has possibilities for increasing crop production, the experimental evidence cannot yet be welded into a scientific system or into a working basis (Rippel, 1926). The results obtained will no doubt be varied due to the interrelations of CO_2 with light, temperature, moisture conditions, time and duration of treatments, and the specific effect on different plants.

2. Supply of Light. *a. Intensity.*—The experimental work on the influence of the intensity of light upon the rate of photosynthesis previous to 1905 is of doubtful value, since the factors other than the intensity of light were not given due consideration. For a review of the early literature on this topic the student is referred to Stiles (1925) and to Brown and Heise (1917). The latter reviewers conclude that this early experimental work does not indicate that carbon dioxide assimilation in plants is proportional to the light intensity. They consider that these experiments indicate a progressively smaller increase of the rate of photosynthesis for each increase in light intensity and that this progressive decrease in the rate of augmentation continues until a point is reached at which further increase in light produces no measurable increase in assimilation.

In 1905 Blackman and Matthaei, however, investigated the influence of light intensity upon the photosynthetic rate with a full realization of the importance of other factors and under well-controlled conditions. They concluded that if the temperature and carbon dioxide are in excess,

the rate of photosynthesis is proportional to the intensity of the incident light. For every temperature there is a maximum light intensity which will produce a maximum rate of photosynthesis at that temperature. It has been observed by Osterhout and Haas (1918), Warburg (1919), and Spoehr and McGee (1923) that when plants have been kept in darkness for a period and then exposed to sunlight, the rate of photosynthesis is low at first and then steadily increases until a maximum is reached. The term "photochemical induction" has been given by Stiles (1925) to this phenomenon. The intermittent application of light has been observed to have a marked influence on the photosynthetic rate. Thus Warburg (1919), as reported by Stiles (1925) and Spoehr (1926), found in the case of *Chlorella* that with alternations of 8,000 per minute the rate of photosynthesis was 100 per cent above that in continuous illumination. With an alternation of four light and four dark periods per minute, the rate of photosynthesis was only 10 per cent above that of continuous illumination. Spoehr (1926) considered that this behavior might be explained by assuming that during the dark period CO_2 is synthesized by the chloroplasts and moved away so that when they are again exposed to light there are available higher concentrations of the necessary material for photosynthesis which would tend to increase its rate. This phenomenon occurs only under conditions of high light intensity and is not noticeable under conditions of low illumination.

In the process of photosynthesis CO_2 and H_2O are used and oxygen is given off as a by-product, while in the process of respiration, which is proceeding at the same time, oxygen is utilized and CO_2 and water are given off as waste products. Since the rate of photosynthesis increases with the intensity of light, while the process of respiration is independent of this factor, there will be a light intensity for every plant at every temperature at which the building-up process of photosynthesis will just equal the tearing-down process of respiration. Under such conditions CO_2 and O_2 will neither be absorbed nor set free. This point in the intensity of the incident light has been called the "compensation point" (Plaetzer, 1917). The value of the compensation point varies widely for different species and for different temperatures.

It was observed by Blackman and Matthaei (1905) that if light is a limiting factor, equal areas of leaves of different plants equally illuminated give equal photosynthetic rates. They also observed that plants differ in their photosynthetic rates. Thus at 29.5°C . cherry laurel leaves reached their maximum rate of photosynthesis at 0.36 of full sunlight, while *Helianthus tuberosus* required 0.69 of full sunshine to reach its maximum photosynthetic rate.

b. *Wave Lengths of Light.*—There are numerous factors entering into a solution of this problem which are difficult of estimation and control, but which greatly influence any results that may be obtained. Many of

these factors were not considered by the early investigators, while the more recent ones, who realize these difficulties, have not been able satisfactorily to measure or control them. Some of the difficulties which enter into a solution of this problem are: (1) the measurement of the energy in the different portions of the spectrum, (2) the methods of obtaining the different wave lengths used, (3) methods for measuring the rate of photosynthesis, (4) the relative absorption of the different wave lengths by different plants, (5) variation in the light supply.

The relative distribution of energy in various spectra varies widely, so, unless the sources of energy used are the same, widely different results will be obtained. Sunlight also varies in intensity and composition at the surface of the earth, from time to time, so different portions of the spectrum may vary independently of each other. It should also be noted that if equal intensities of different lights are presented to the plant, the plant exhibits selective absorption so the greatest rate of photosynthesis will be brought about by the rays which are most absorbed regardless of what would occur if the plant absorbed them equally. On account of the difficulties which have just been enumerated, the investigations in regard to photosynthesis and wave length have been productive of but few data that are conclusive.

The range of wave lengths of light in which photosynthesis may occur was investigated by Timiriazeff (1890, 1903) and Ursprung (1917) by means of the iodine-starch method. By this method the spectrum is thrown upon the leaf for a period after which the chlorophyll is removed and the leaf is tested for starch with iodine after the usual manner, the depth of color being taken as an index to the rate of starch formation in the various regions of the spectrum. In the case of *Phaseolus multiflorus* (Ursprung, 1917) exposed to various sources of light, starch formation was found to occur throughout the whole visible spectrum if sufficient time were allowed. Starch formation was thus found to occur between the wave lengths 330 and 760 $\mu\mu$. The maximum activity apparently was in the region 687 to 656 $\mu\mu$. In the normal solar spectrum, starch formation in the blue requires a longer time than in the red.- Ursprung (1918) reported that he was able to observe slight starch formation in the infra-red portion of the spectrum in the case of *Phaseolus vulgaris* which had been exposed for 40 hr. The starch-iodine method for determining the rate of photosynthesis for an experiment of this type is, however, open to serious objections. The formation of starch is, without doubt, secondary to photosynthesis and can occur in the dark as well as in the light provided a supply of sugars is present. The formation of starch might be influenced by light in an entirely different manner from that influencing the process of photosynthesis. The rôle of the ultra-violet rays in photosynthesis apparently is of little or no consequence, as has been mentioned in the discussion of the theories of photosynthesis.

Plants can perform normal photosynthesis under conditions which exclude ultra-violet rays, while the experimental attempts to produce photosynthesis in plants in ultra-violet light are not convincing.

The relative value of the different rays of light in the process of photosynthesis was studied by Kniep and Minder (1909) for *Elodea canadensis*. They measured the energy value of red, blue, and green rays incident upon the plant and determined the rate of photosynthesis by the oxygen-bubble method. Their observations indicated that the red and the blue lights of the same intensity gave the same rate of photosynthesis, but they could observe no photosynthesis in green light. This work, however, although a great step in the direction of properly controlled experiments of this type, gave results that were unreliable, since the screens used allowed rays other than those desired to pass, unless successive screens were used which diminished the intensity of the light to a point where the intensity became a limiting factor. Lubimenko (1923) in experiments with eight species of plants used monochromatic light with red rays from 760 to 600 $\mu\mu$ and blue rays from 480 to 400 $\mu\mu$ and assumed the intensity of the blue rays to be 85 per cent of the red. The experiments carried on at 20°C. for 6 hr. in a clear sky with a CO₂ content ranging from 9 to 11 per cent showed that the rate of photosynthesis was greater in red than in blue light, being double in the former as compared with the latter. The rate of photosynthesis was retarded with time in both red and blue light. In species adapted to diffuse light of low intensity, as *Hedera helix* and *Aspidistra elatior*, the activity of the blue rays equalled or exceeded that of the red rays. Wurmser (1925) in experiments with *Ulva* and other sea algae reported that the liberation of oxygen in green light of 490 to 590 $\mu\mu$ was higher than that in the red rays of 590 to 700 $\mu\mu$, the rate of green to red being as 1.15 to 1.00.

Stiles (1925) considers that the experimental evidence that has been presented indicates that with equal intensity of incident light photosynthesis is influenced by wave lengths, being the greatest in the red between the B and C lines and least in the blue violet. Warburg and Negelein (1923) agree with this in that they consider that the rate of photosynthesis decreases with decreasing wave length. They further consider that there is no apparent relation between the efficiency of photosynthesis and the absorption bands of chlorophyll. Thus the yield of photosynthesis in the red, a region of high absorption, is greater than in the green, a region of low absorption, while the yield in the green is higher than that in the blue, the region of highest absorption (Spoehr, 1926). Since there are different degrees of absorption of the different wave lengths by the leaf cells due to specific differences of the cells themselves or to the thickness of the leaves, it would appear to be impossible to find values for the relative rates of photosynthesis in light of different wave lengths which will hold in general for all plants and all conditions.

3. Temperature. *a. Coefficient.*—The temperature coefficient, as has been stated in Chap. II, is denoted by Q_{10} and is the ratio of the rate of a reaction or process at a given temperature to the rate of the process at a temperature 10° lower. The temperature coefficient for purely physical processes is relatively low, being from 1.2 to 1.4 at the temperatures that ordinarily prevail in the plant. The temperature coefficient for chemical reactions are, on the other hand, relatively high, ranging from 2 to 3, while relatively low temperature coefficients ranging from 1 to 1.4 are characteristic of photochemical reactions.

It was observed by Blackman and Matthaei (1905) that between 5 and 25°C . the temperature coefficient of photosynthesis in cherry laurel was 2.1 and for the artichoke 2.5, which suggests that it may be different for different species. Osterhout and Haas (1918) noted that the temperature coefficient of photosynthesis in the case of *Ulva rigida* between 17 and 27° was 1.81. Since light reactions ordinarily have low temperature coefficients, they assumed that the process of photosynthesis involves a light reaction with a low coefficient followed by an ordinary chemical reaction with a high temperature coefficient, so that as a result the temperature coefficient of the process as a whole is high. This is in line with the idea that photosynthesis is a complex of reactions falling under a diffusion phase, a photochemical or light phase, and a chemical or dark phase (James, 1928). In a critical review of the literature in regard to the influence of temperature on the rate of photosynthesis, Brown and Heise (1917) consider that the work, for the most part, indicates temperature coefficients which are of the same order of magnitude as photochemical coefficients. The temperature coefficient of photosynthesis is apparently influenced by the chlorophyll content of the leaves. Thus Willstätter and Stoll (1918) found that the leaves of *Ulmus* with low chlorophyll content showed a temperature coefficient of 1.34 as compared to 1.5 between 15 to 25°C . for leaves with a high content of the pigment.

The temperature coefficient of photosynthesis has been investigated with the idea that it might throw some light on the nature of the reactions involved; however, the temperature coefficient in photosynthesis is not so indicative of the nature of the process as it is in a simple reaction. The process of photosynthesis consists of a series of reactions that are influenced by numerous factors any one of which, other than temperature, might be the limiting one.

b. Range.—The threshold temperature of photosynthesis varies greatly for different plants. Matthaei (1905) found that photosynthesis took place in the leaves of cherry laurel at -6°C . Henrici observed photosynthesis in lichens at -20°C . and in alpine plants at -16°C . Ewart (1896) states that the evolution of oxygen ceases between 0 and 2°C . in the case of warm, temperate, and subtropical plants and between 4 and 8°C . for tropical plants. Provided that no other factor is a limiting

one, the rate of photosynthesis increases with an increase in temperature until about 25°C., as observed by Matthaei (1905) and Blackman and Matthaei for cherry laurel. Above a temperature of 25°C., however, complications arise. Below 25°C. the rate of photosynthesis remains constant at a given temperature hour after hour, but above 25°C. it decreases with time so that the initial rate is not maintained. The falling off of the initial rate is irregular; it is more rapid the higher the temperature; and at any temperature above 25°C., it is greater at first and subsequently becomes less rapid. The following data taken from Matthaei (1905) will illustrate the behavior of photosynthesis in the leaf of cherry laurel at a relatively low and a relatively high temperature:

Time, successive periods, hours	Rate of photosynthesis, grams of CO ₂ combined per 50 cm. ² of leaf per hour, at	
	8.8°C.	37.5°C.
2	0.0039	0.0574
2	0.0039	0.0352
2	0.0038	0.0278
2	0.00385	0.0218

Owing to this falling off in the rate of photosynthesis at the higher temperatures, the previous history of the leaf as regards temperature would determine the value of the photosynthetic rate. Thus the temperature at which the highest rate is observed will depend upon the time which has elapsed between the commencement of the experiment and the measurement of the photosynthetic rate. On this account, some regard the optimum temperature as the highest temperature which can be maintained continuously without a resulting depression of the process under consideration.

The behavior of photosynthesis to higher temperature appears similar to that of hydrolytic enzymes (Blackman, 1905). Thus Kjeldahl (1879) noted that malt diastase hydrolyzed increasing quantities of starch up to 63°C., after which the reaction falls off rapidly, becoming nothing at 86°C. This decrease in the reaction is apparently due to the destruction of the enzyme by heat. This characteristic behavior of enzymes was further investigated by Tammann (1892, 1895) and by Duclaux (1899) and has been termed "Tammann's principle." This principle is shown by the following curves (Fig. 27): The curve *OA* shows the relation between temperature and the enzyme action provided the reaction is in no way hindered by the temperature. The curve *DB* represents the relation between the temperature and the quantity of enzymes, since it is being

destroyed by heat. The curve *OMC* represents the actual curve between temperature and the enzyme action. The apparent production of an optimum is thus due to two opposed processes, the increased hydrolytic action of the enzyme and the destruction of the enzyme due to heat. Evidence was obtained by Molisch (1925) which indicated that an enzyme might be concerned in the photosynthetic process. He observed that green leaves from a wide range of plants dried at 30 to 40°C. and pulverized liberated oxygen when illuminated. Leaf material, however, which was heated to 96°C. did not thus behave, while material prepared from leaves which were killed by freezing could liberate oxygen in illumination. If Tammann's principle or some similar one is involved in photosynthesis, the position of the optimum is not a definite fixed point but depends upon other factors which will remain constant only if the plants are subjected to the same previous treatments (Jorgensen and Stiles, 1917).




FIG. 27.—Graphs showing the relation between temperature and enzyme action. (Redrawn from Jorgensen and Stiles, 1917, after Duclaux, 1899.) The graph *OA* shows the relation between temperature and enzyme action if the enzyme activity remains unimpaired. The graph *DB* represents the relation between temperature and quantity of enzyme. The graph *OMC* represents the actual graph between temperature and enzyme action.

4. Amount of Chlorophyll.—In 1879 Weber observed that equal areas of the leaves of different plants under the same conditions had different assimilatory powers, and Haberlandt (1882) attempted to explain these observations by determining the number of chloroplasts per unit area. No definite conclusions, however, can be drawn by this method, since there is no evidence that all chloroplasts contain the same amount of chlorophyll. Since it is experimentally impossible to vary the concentration of the chlorophyll in the plant, the relation of the chlorophyll content to rate of photosynthesis has been studied by using plants from different habitats, young and old leaves, green and yellow leaves of different varieties, and etiolated plants.

a. Plants of Different Habitats and of Different Varieties.—It was observed by Lubimenko (1905, 1908) that shade plants could accomplish the same amount of photosynthesis with a lower illumination than the sun plants and that the chlorophyll content of the former was higher than that of the latter. The sun plants with the low chlorophyll content showed the maximum rate of photosynthesis at the highest light intensities, while

the shade plants showed a decreased rate at the same intensities. He considered that leaves with a high chlorophyll content have a high absorption coefficient and that the optimum temperature and light intensity for photosynthesis decreases with chlorophyll content. Henrici (1919) made observations somewhat in accord with those of Lubimenko, since she noted that lowland plants may have as much as 2.3 times more chlorophyll than the alpine plants of the same species and that in strong light the rate of photosynthesis in the alpine plants was higher than in the lowland plants. She states that alpine plants assimilate more rapidly than lowland plants when red rays predominate around sunset but that when blue rays predominate, the lowland plants are the more active.

Willstätter and Stoll (1918) in their discussion of the relation of the chlorophyll content to photosynthesis introduced the term "assimilation number" or "photosynthetic number." The photosynthetic number may be defined as the number of units of CO₂ absorbed per hour per unit of chlorophyll. It is the ratio of the number of grams of CO₂ absorbed per hour by a unit of leaf to the number of grams of chlorophyll contained in that unit. If the rate of photosynthesis depends only on the chlorophyll content, then the photosynthetic number should be constant, but if other factors than chlorophyll content influence the rate, the photosynthetic numbers will show variations. These authors determined the photosynthetic number for a large number of plants at a temperature of 25°C., with a 5 per cent CO₂ supply and a supply of light equal to 48,000 lux. The following examples taken at random show the variation of the photosynthetic number for different plants: *Cucurbita pepo* 12.1, *Helianthus annuus* 10.9, *Hydrangea opuloides* 6.5, and *Acer pseudoplatinus* 5.2. In experiments with light green or yellow and normal green varieties of plants Plester (1912) and Willstätter and Stoll (1918) observed that the rate of photosynthesis increased with the chlorophyll content, but they were not able to establish any relation between these two factors.

b. Etiolated Plants.—In experiments with etiolated plants of barley, *Vicia faba*, and *Phaseolus*, Irving (1910) and Briggs (1920) concluded that etiolated leaves do not possess any appreciable power of photosynthesis. They observed further that the development of photosynthetic activity in the young leaves lagged behind greening and did not appear until after the leaves had attained a full green color, when it developed very rapidly. They considered that photosynthetic activity is dependent upon some other factor than chlorophyll and is not developed so quickly as the pigment which remains idle until the other factor becomes active. Willstätter and Stoll (1918) were not able to duplicate the results of Irving (1910), but according to Briggs (1920) the difference in the results is due to the difference in the age of the material used. In the case of seedlings of plants such as *Helianthus annuus*, *Acer*, and *Cucurbita*, where the first photosynthetic organ is one that also serves as a storage

organ, Briggs (1922) observed that the photosynthetic activity is fully developed at germination. With this type photosynthesis under natural conditions of growth in the field showed no lag behind greening. In such plants as *Phaseolus*, *Ricinus*, and *Zea* where the seedling develops a specialized photosynthetic organ different from the storage organ, the photosynthetic activity was not developed until some time after germination, and photosynthesis under natural conditions shows a corresponding lag.

At the present time it is definitely known that only those cells which contain chlorophyll are capable of photosynthesis, but the quantitative rôle of the pigment in this process has not been established.

5. Water Supply.—Water plays both a direct and an indirect rôle in the process of photosynthesis. It plays a direct rôle in that it enters into chemical combination with CO_2 to form carbohydrates in the process. It plays an indirect rôle in that it maintains the turgidity of the leaf cells and thus keeps the stomata open and allows an unobstructed intake of CO_2 . Since the amount of water used in chemical combination is relatively small, the greatest hindrance to photosynthesis due to a limited water supply comes from the secondary effect of the closure of the stomata. Thoday (1910) found that the turgid leaves of *Helianthus annuus* carried on photosynthesis approximately ten times more rapidly than did leaves which were wilted to drooping during the experiment. In withering leaves of *Tropaeolum majus*, Schroeder and Horn (1922) and Horn (1923) noted that starch was broken down into sugar and that the cane sugar steadily increased with the decreasing water content. Iljin (1923) found that when the water content of the leaves of *Bidens tripartita* was reduced 43 to 44 per cent, a reduction of 53 to 78 per cent of photosynthesis occurred. In *Phlomis pungens* a water loss of 34 per cent caused a reduction of 13 per cent in photosynthesis. In these experiments the full activity of photosynthesis was not regained at once upon the recovery of normal turgidity and in some cases showed a reduction of 29 per cent 16 hr. after complete recovery of turgor. Iljin (1915) considered that plants that are adapted to a dry habitat lose less water per amount of carbon dioxide decomposed than do mesophytes. Due to water loss the stomata of the mesophytes close, and as a result the intake of CO_2 is reduced and photosynthesis is checked, while in the xerophytic plants it is going on at the normal rate. It was observed by Brilliant (1924) that with a loss of 41 to 63 per cent of the water content of the leaves of *Hedera helix* and *Impatiens parviflora* photosynthesis was almost stopped. The process was at its maximum when the water content was reduced only 5 to 15 per cent. Young plants are not so much affected by the loss of water as are more mature ones. Dastur (1924, 1925) also found that there is a direct correlation between the decrease in the rate of transpiration and the fall in the water content, per unit of leaf area. Those plant

tissues, placed most unfavorably in regard to their water supply, are the first to lose their power of photosynthesis, this inhibition appearing first in the marginal and intravascular regions and then gradually proceeding inwardly toward the central and main fibrovascular bundles. Yuncker (1916), however, found that the greater amount of dry matter per unit of leaf area was produced in those corn plants that showed the lower amount of transpiration and that grew in the drier soil. He considered that this was due to the more active respiration and growth in the leaves with the higher water content. The leaves of the lower water content were carrying on respiration less rapidly, and as a consequence dry matter accumulated.

6. Protoplasmic Factors.—The chlorophyll and the protoplasmic structure of the chloroplast are mutually dependent upon one another. Chlorophyll cannot carry on photosynthesis when separated from the plastid, and the plastid devoid of chlorophyll is totally unable to carry on this process. The nature of the mutual dependence of the chloroplast upon the general cytoplasm of the cell, however, is not definitely known. It is considered by some (Ewart, 1898) that chloroplasts isolated from the general cytoplasm can still function in photosynthesis, while others (Kny, 1897, 1898) believe that they are unable to do so under such conditions. In general, however, it may be stated that the process of photosynthesis is intimately associated with the vital activities of the plant, so any factors that affect the protoplasm will have their effect upon photosynthesis.

The data in regard to the effect of the oxygen supply upon photosynthesis are conflicting. Harvey (1928) found that 14 species of marine algae including greens, reds, and browns are able to produce oxygen from CO_2 when illuminated in the complete absence of oxygen. The oxygen appeared in the external medium within a second after illumination. Willstätter and Stoll (1918) found that plants exhibit marked differences in regard to the amount of oxygen necessary for photosynthesis. Thus *Pelargonium* is quite sensitive, while *Cyclamen* is very tolerant to the lack of this gas. The influence of the lack of oxygen on photosynthesis is apparently thus largely one of degree, some plants being easily inhibited in photosynthesis, while others withstand the absence of oxygen for longer periods without any change in the photosynthetic rate. Willstätter and Stoll consider that some oxygen, however, is absolutely essential for photosynthesis. It seems doubtful in any of the experiments that have been reported whether the oxygen supply was completely exhausted, since it is very difficult to free the plant entirely of the gas. An amount sufficient for the plant under consideration might have been available.

Work by Ewart (1897, 1898), Pantanelli (1903), Ursprung (1917), and Yap (1920) indicates that the rate of photosynthesis may be checked by continuous exposure to light or by exposure to intense light. This

inactivation might be due to the destruction of the chlorophyll or to injury of the protoplasm of the chloroplast or to both these factors, as suggested by Pantanelli (1903). It was noted by Yap (1920) that the rate of photosynthesis of the sugar cane decreased from 10 a.m. to 4 p.m., the process being the most active from 8 to 10 a.m. He considered in this case that the intensity of light decreased the rate of photosynthesis. Ursprung (1917) found that the inactivation of photosynthesis by continuous exposure to light in the case of *Phaseolus* began first in the orange-red portion of the spectrum where the highest photosynthetic rate was proceeding and then spread as the light intensity was increased to the region of shorter wave lengths. The term "solarisation" was given by Ursprung to this effect of light upon the photosynthetic activity. Solarisation apparently has no permanent effects upon the activities of the leaf, since after a period of darkness it again regains its original photosynthetic power. Stanescu (1924) observed that solarisation is, in general, more pronounced in leaves with a medium rate of starch production. He was not able to find a definite relation between the appearance of solarisation and the intensity of light, although those leaves which grew with their surface turned toward the south were solarized more frequently and more clearly.

The rate of photosynthesis is decreased by the accumulation of the products of the process. This behavior has been observed particularly with leaves that have been removed from the plant, since no means of translocation exists under these conditions. In many plants, the sugar which is formed in excess of that which can be translocated at once is converted into temporary starch in the chloroplasts. In these cases it is considered that this accumulation of starch in the chloroplasts impairs their activity by interfering with the photosynthetic process which is considered by some to occur at the surface of these plastids. The retardation of photosynthesis by the accumulation of sugar in those leaves which do not form starch is apparently associated with the osmotic relations of the cells, and when a certain concentration of the cell sap is reached photosynthesis ceases.

The effect of the carbohydrate content of the leaf upon the rate of photosynthesis was studied by Saposchnikoff (1890, 1893). In the case of the detached leaves of *Vitis labrusca* and *Vitis vinifera* it was found that photosynthesis ceased when the carbohydrate content reached 17 to 25 per cent of the dry weight in the former and 23 to 29 per cent in the latter. These observations were confirmed by Ewart (1896), who also observed that leaves cease photosynthesis after they have been fed sugar for a time. Certain plants store up the sugar, that has been produced in excess of that which is translocated from the leaf, as temporary starch in the chloroplasts. This starch appears after from 6 min. to 2 hr. or more depending upon the plant and the conditions prevailing (Andrews, 1925).

Plants which thus form starch have been termed "starch" plants, while those which form little or no starch are termed "sugar" plants. It has been stated by Müller (1904) that starch leaves exceed the sugar leaves in the total production of carbohydrates during the day, the limit of accumulation being higher in the starch leaves. He found that the maximum rate of photosynthesis remained almost stationary during the remainder of the day. Winkler (1898) showed that in ordinary starch-forming leaves 0.2 to 0.5 per cent of sugar is the critical concentration at which they will form starch. For sugar leaves the concentration attains a concentration of sugar as high as 18 per cent in the case of the sugar cane before starch will appear. The onion was the only plant in his experiments that resisted all feeding attempts to form starch. Leaves not detached from the stems but emptied of their starch by a sufficient period in darkness carry on photosynthesis and accumulate starch at a rate very much greater than normal leaves when they are exposed anew to the light.

It was observed by Gruzit and Hibbard (1916) that the dry weight per unit area of leaves of seedlings grown in a complete culture was less than that of leaves of seedlings grown in a solution lacking an element as potassium, calcium, or phosphorus. The explanation for this lies in a reduced translocation of the carbohydrate which accumulates in the leaf and results in a retarded photosynthesis, since the actual amount of material formed is greater in those plants growing in a complete nutrient solution.

In experiments with *Phaseolus vulgaris* grown in cultural solutions devoid of K, Mg, Fe, or P, Briggs (1922) found that the photosynthetic activity was lowered. This result may be attributed to two causes. The lack of certain elements might cause an accumulation of carbohydrates, since the growing parts of the plant in their absence cannot utilize the carbohydrates as rapidly as the leaves can synthesize them. On the other hand, the deficiency of salts may act directly upon the photosynthetic mechanism by reducing the actual leaf surface or by decreasing the rate per unit of leaf. Briggs considers that the chief factor involved in the latter case is a decrease in the "reactive surface" of the chloroplast. This is not necessarily the same as the actual visible chloroplast surface. The internal surface of the plastid is just as important as the visible surface in the process and may be greatly influenced by nutritive conditions. In conclusion, it should be stated in regard to protoplasmic factors that any factor or set of factors that affects the protoplasm in general will influence, to some extent at least, the photosynthetic process. In this connection the influence of fungi upon the photosynthetic activity should be mentioned. Long (1919) observed that rusts and mildews interfered with photosynthesis in all cases that she observed. Thus in *Avena* affected by *Puccinia coronata*, when it was

well developed but not eruptive, the photosynthetic activity was reduced to 72 per cent and in the erupted stage to 48 per cent. *Puccinia graminis* on wheat reduced the rate of photosynthesis to 50 per cent in the stage before the pustules became brown and in the eruptive stage to 39 per cent

G. THE ENERGY RELATIONS OF PHOTOSYNTHESIS

The process of photosynthesis is one in which the radiant energy of the sun is transformed into potential energy in the form of the organic compounds that are synthesized. In order to study the energy relations in the process it is necessary to know the amount of the compounds synthesized and the amount of energy available to the plant, so it is those topics that will now be considered.

1. Methods of Determining the Rate of Photosynthesis.—Three general methods have been used to measure the photosynthetic activity of the leaves and stems. These methods are based on (a) the liberation of oxygen, (b) the intake of carbon dioxide, and (c) the amount of organic substance or dry matter produced. It should be mentioned at the beginning that none of the methods that have been devised for the measurement of photosynthesis is satisfactory, since none takes into consideration all the factors concerned and since frequently the three methods do not yield the same results. The conflicting results obtained by the different methods are no doubt due to the fact that photosynthesis is a series or chain of reactions more or less dependent upon each other and that each of the three methods is based upon a different chemical reaction in the process. Thus the intake of CO_2 occurs at the beginning of photosynthesis and the increase in dry matter is the last stage in the process, while it is not known at which step in the reaction oxygen is liberated.

In the measurement of photosynthesis, the process of respiration is a difficulty regardless of the method used. Respiration goes on simultaneously in the same cells with photosynthesis, so there is a reduction and an oxidation process occurring at the same time. In photosynthesis, CO_2 is absorbed and carbohydrates are formed with the release of oxygen; while in respiration, oxygen is absorbed, carbohydrates are broken down, and CO_2 released. The process of photosynthesis generally proceeds at a more rapid rate than does respiration. The quantity of CO_2 , therefore, absorbed from the exterior will be less than that actually used in the process of photosynthesis by an amount equal to the CO_2 evolved in respiration and utilized in photosynthesis before it can leave the cells. If the evolution of oxygen is used to measure photosynthesis, the amount of this gas which escapes is not all that has been liberated in the process, since some is utilized in respiration before it can escape from the cell. If photosynthesis is measured by the increase in dry weight, the loss in weight due to respiration must also be considered. The method usually

used to correct for respiration is to determine its rate in the same plant parts or upon checks in the dark and then correct for this factor. The principal objection to this method of procedure is the uncertainty as to whether respiration goes on at the same rate in the light as in the dark. The value obtained for the rate of photosynthesis without correcting for the process of respiration is termed the "apparent rate of photosynthesis" as compared to the "true rate of photosynthesis" which has been corrected for the process of respiration.

a. Liberation of Oxygen.—The methods that have been devised to demonstrate the liberation of oxygen in the process of photosynthesis may be classified under the following headings: (1) The use of bacteria, (2) the use of oxygen-absorbing compounds, (3) the bubble counting method, and (4) gas-analytical methods.

1. *The Use of Bacteria.*—Two types of bacteria have been used to demonstrate the liberation of oxygen: (a) luminous bacteria, which emit light only in the presence of oxygen, and (b) motile bacteria, which are active only in the presence of this gas. The plant material, however, that may be used in experiments of this type is limited to a size that can be observed under a relatively high power of the microscope.

2. *The Use of Oxygen-absorbing Compounds.*—Certain dyestuffs which are reduced to colorless substances react with oxygen, reforming the original colored compound. These reduced compounds are termed "leucobases" and are used to demonstrate the liberation of oxygen by plants. One of the most frequently used dyes for this purpose is indigo or indigo carmine. When an aqueous solution of this dye is reduced by sodium hyposulphite, NaHSO_2 , the blue color disappears. When a water plant is illuminated in a solution of this reduced dye, the blue color reappears in the vicinity of the leaves due to the oxidation brought about by the oxygen evolved in photosynthesis.

If a leaf is immersed in defibrated venous blood and exposed to the light, the evolution of oxygen produces the red color of oxyhaemoglobin in the vicinity of the leaf. The methods that have so far been mentioned are purely qualitative and have no value for quantitative work.

3. *Bubble Counting.*—When cut parts of an aquatic plant are placed in water with a supply of carbon dioxide and illuminated, bubbles of gas escape from the cut ends or surfaces. The major portion of this gas is oxygen, and it was shown by Sachs (1864) that the rate at which these bubbles are liberated may be taken as a relative measure of the rate of photosynthesis. This method is a comparatively simple one and has been used extensively in botanical laboratories, for both qualitative and quantitative work. A piece of water plant is securely submerged in water in which CO_2 is dissolved and the gas as it escapes is collected in an inverted funnel or test tube if it is so desired. The rate of photosynthesis is estimated by the number of bubbles which escape in a unit of time. For accurate quantitative work, however, this method is open to criticism. In the first place, the bubbles are not pure oxygen. Some of the oxygen which they contain passes out into the water, while some nitrogen from the water enters the bubbles. The bubbles are not always of the same size, being smaller when photosynthesis is rapid than when it is slow. Lastly, in some cases oxygen does not always escape from the plant in the form of bubbles at the same rate as it is formed.

4. *Gas-analytical Methods.*—These methods involve the analysis of the air in which a plant has been confined or the analysis of samples of air which has passed over the plant. The latter procedure is the more simple and satisfactory. The analysis of the air in experiments of this type is similar in procedure to ordinary gas analysis with the exception of certain modifications in apparatus that are necessary to expose

the leaf or leaves to the air and to collect the air after it has been in contact with them. A discussion of the methods of gas analysis, however, is beyond the scope of this work. A concise discussion of the forms of apparatus and of absorbents that have been used is given by Spoehr (1926).

b. Absorption of Carbon Dioxide.—The determination of the amount of carbon dioxide used is the best known method for the measurement of photosynthesis in land plants. One of the objections to the method is that generally only a single leaf can be used and the behavior of detached leaves in photosynthetic activity is known to differ greatly from leaves that are attached to the plant. The carbon dioxide content of the air is first determined and then the content of this gas in the air is determined after it has been pulled in a stream over the leaf in the dark. By this means the rate of respiration of the leaf is determined. The apparatus is then placed in the light and the CO₂ content of the air which has passed over the leaf is determined as before. The correction is made for respiration and the amount of carbon dioxide used in photosynthesis is calculated. This method was first used by Kreuzler (1885) and has been used and modified since that time by numerous workers including Matthaei (1904), Blackman and Matthaei (1905), Brown and Escombe (1905), Willstätter and Stoll (1918), and Spoehr and McGee (1923, 1924). This method, while relatively simple in its procedure, involves many details which must be very carefully manipulated or the results will be of no value. Among these details are: (1) the regulation of the air stream, (2) the constant temperature of this stream, (3) the carbon dioxide content, (4) the regularity of illumination, and (5) the construction of forms of apparatus suitable for the collection of the gas and at the same time placing the plant under favorable conditions for photosynthesis.

The amount of carbon dioxide used in photosynthesis may be demonstrated in a rather simple manner by the endiometric method first employed by Pfeffer (1871) and modified by Ganong (1908). The leaf or plant part is placed in a closed vessel of known volume to which is attached a graduated buret. A known amount of carbon dioxide is introduced into the apparatus, and after a period of time the amount remaining in the vessel is determined by using a concentrated solution of alkali as an absorbent, the CO₂ content being determined by the height to which the liquid rises in the graduated buret. Similar methods for the demonstration and measurement of photosynthesis have also been described by Osterhout (1918, 1919) and by Osterhout and Haas (1918).

c. Increase in Organic Matter. 1. Qualitative Methods.—The increase of the carbohydrates in photosynthesis is easily demonstrated in a qualitative way in those leaves that form starch. The presence of starch or its increase in amount may be easily demonstrated by the iodine method, which was first reported by Sachs (1884) and which has become the most used qualitative method for demonstrating starch in plant tissue. The plant is placed in the dark for a period before exposure to light, or portions of the leaf are shaded from light while others are exposed. When determinations are to be made, the leaf is detached, dipped in hot water, and rendered colorless by the extraction of the chlorophyll with ethyl alcohol. After this the leaves are placed in a solution of iodine in potassium iodide in water. The leaves or portions thereof that have been kept in the dark or shielded from the light will remain unstained, while the portions that have been exposed to light are colored from violet to black according to the amount of starch present. This method, however, is applicable only to those leaves which form starch.

The increase in carbohydrates by photosynthesis in sugar leaves can be demonstrated in a qualitative way by noting the increased reducing power of the cell sap with Fehling's solution or a similar one. This increase in reducing power may be determined in a microchemical way or by working directly with the expressed sap of the leaves.

2. *Quantitative Methods.* (a) *Weighing.*—This method was first used by Sachs in 1884 and is sometimes called the "half-leaf method." As originally devised, it consisted in removing one-half of an attached leaf at the beginning of the experiment by cutting along the midrib and then determining the dry weight of this severed portion. After exposure to light for a given period, the other half of the leaf was removed after the same manner and its dry weight determined. The method was later modified by Sachs and others in that only small portions of the leaf were removed from each side, thus enabling more uniform samples to be taken and eliminating errors due to irregular veins and the lack of symmetry in the two halves of the leaf.




FIG. 28.—Diagram to illustrate the "leaf-punch" method for determining the variations in dry matter, water, carbohydrates, or nitrogen during a 24-hr. period. Description in the text.

Ganong (1908) devised a leaf punch which removes a disk of leaf with an area of 1 cm.² by means of which, if proper precautions are used, samples of very uniform weight and structure may be obtained. By beginning toward the tips of the leaves with this instrument, a series of samples may be taken at different periods of the day without seriously disturbing the conducting system of the leaf. Miller (1917) in determining the changes in the dry matter in the leaves of corn and the sorghums during the day and night obtained samples with a Ganong leaf punch after the following manner:

Thirty representative plants were selected and a leaf chosen on each plant for furnishing all the samples for an experiment extending over the desired length of time. Figure 28 shows the manner in which the leaf samples were obtained. The figure shows the appearance of a leaf at the end of a 40-hr. experiment. At 7 a.m. a single sample was taken from each of the 30 selected leaves at *a* toward the tip of the leaf. At 9 a.m. a sample was taken from each of the 30 leaves at *b* directly opposite *a*. At 11 a.m. the samples were collected from the leaves at *c* directly below *a*, and then at the next 2-hr. period at *d*, and so on. The samples for a 40-hr. experiment were thus obtained from a portion of the leaves representing less than 6 in. of their respective lengths. The samples were collected in weighed vials which were then quickly stoppered, weighed, placed in an oven at 100 to 108°C., and dried to constant weight.

The increase in dry weight that is obtained for a given area of leaf in an experiment of this kind does not represent the total weight of the product formed by photosynthesis during that period. Translocation of products from the leaf takes place during the period of photosynthesis, while a certain amount of the product of photosynthesis is utilized in respiration which is proceeding simultaneously with photosynthesis. The increase in dry weight which is thus obtained represents the difference between the total weight of the products formed and the weight of the material that has been moved from the leaf or utilized in respiration. Sachs attempted to correct for the translocation by placing a detached leaf in water as a control, since translocation from the leaf does not occur under such conditions. Brown and Escombe (1905), however, showed that a detached leaf does not utilize CO₂ in the same proportion as an attached leaf, so such a correction is unreliable.

Sachs also considered that the total weight of photosynthate made during the day in a given area of leaf could be determined by adding to the gain during the day the loss in weight of the same area during the night. This should give the total increase in weight due to photosynthesis provided that respiration and translocation

proceed at the same rate during the daylight hours as they do during the night—which, however, is not definitely known to be a fact. The following figures taken from the work of Miller (1917) show how the dry matter varies during the day and night in the leaves of Dwarf Yellow milo.

VARIATION IN DRY MATTER IN THE LEAVES OF DWARF YELLOW MILO DURING A 24-HR. PERIOD AT GARDEN CITY, KANS.

Time	Dry matter per square meter of leaf, grams	Increase or decrease in dry matter per square meter of leaf, grams
5 a.m.....	50.3	
7 a.m.....	50.8	+0.5
9 a.m.....	53.4	+2.6
11 a.m.....	55.7	+2.3
1 p.m.....	58.3	+2.6
3 p.m.....	61.0	+2.7
5 p.m.....	61.5	+0.5
7 p.m.....	60.2	-1.3
9 p.m.....	58.0	-2.2
11 p.m.....	57.8	-0.2
1 a.m.....	55.6	-2.2
3 a.m.....	54.9	-0.7
5 a.m.....	52.1	-2.8

These data show that during the 24-hr. period there was manufactured in the leaf from 5 a.m. to 5 p.m. 11.2 g. of dry matter per square meter of leaf in excess of that which was translocated and used in respiration. From 5 p.m. to 5 a.m., 9.4 g. of dry matter disappeared per square meter of leaf. If the rate of translocation and respiration was the same during the day as during the night, the total amount of photosynthate during the day from 5 a.m. to 5 p.m. was 20.6 g. per square meter of leaf.

As pointed out by Thoday (1910), there are numerous objections to the dry-weight method of determining the rate of photosynthesis other than those above mentioned. The dry weight obtained includes the increase not only of carbohydrates but of proteins and oils as well. Changes in dry weight may consist in part of ash to as much as 5 per cent. The changes in ash content should be determined and a deduction made for the same. Apparent increases in dry weight would result from any shrinking in area of the leaf due to water loss during the day. Thoday (1910) considers that the dry-weight method gives useful results for rates of increase greater than 2 mg. per square decimeter per hour.

(b) *Saccharification*.—This method consists of hydrolyzing the entire carbohydrate content of the leaf to hexoses and estimating the products thus formed as glucose. The method is essentially the same as that recommended by the Association of Official Agricultural Chemists but must be modified to meet the conditions that are peculiar to the material under consideration. In this method a correction must also be made for respiration and translocation if the actual amount of photosynthate is to be determined.

2. The Rate of Photosynthesis.—It is of interest to know the rate at which carbohydrates are manufactured by the plant in the process of

otosynthesis. The average rate of photosynthesis was determined by Miller (1917) for corn, kafir, and milo under the conditions that prevail in the field in Kansas during the growing season. The data for a large number of experiments for three growing seasons are averaged in the table below. These data have been corrected for translocation and transpiration and thus approximate the actual amount of photosynthate manufactured by the leaves during the periods mentioned.

TABLE 1.—AVERAGE RATE OF PHOTOSYNTHESIS FOR EACH SQUARE METER OF LEAF FOR CORN, KAFIR, AND MILO DURING EACH 2-HR. PERIOD OF THE DAY

Plant	a.m.		p.m.		
	7 to 9	9 to 11	11 to 1	1 to 3	3 to 5
Corn.....	3.8	1.9	1.4	1.2	1.4
Kafir.....	3.0	2.1	1.2	2.1	1.2
Milo.....	2.3	2.7	3.8	3.5	1.4

The high rate of photosynthesis in corn and kafir from 7 to 9 a.m. compared with other periods of the day may be due to water relations. During the growing season in the Great Plains, the water content of the leaves, due to a high rate of transpiration, is apparently below the optimum for some of the physiological processes for the majority of plants.

It also has been observed by Miller that the average rate of photosynthesis during a 10-hr. period for pumpkin, cowpeas, and soybeans are respectively 1.8, 0.85, and 0.8 g.m.² hr. under field conditions. It is of interest to note that the rate for pumpkin is approximately that reported by Sachs (1884) for *Helianthus annuus*. The rates of photosynthesis mentioned above are much lower than those obtained by workers who have determined the rate by the amount of CO₂ taken up. They, however, used concentrations of CO₂ that were many times higher than normal. Thus Matthaei and Blackman (1905) using 6.3 per cent concentration of CO₂ obtained a rate of 3.9 g.m.² hr. for *Helianthus annuus* at 30°C. in strong sunlight. Willstätter and Stoll (1918) in a 1 per cent concentration of CO₂ at 25°C. with a light intensity of 48,000 x obtained a rate of 5.5 g.m.² hr. with *Helianthus annuus* and under the same conditions, but with an atmosphere of 4 per cent CO₂ a rate of 4.3 g.m.² hr. for *Cucurbita pepo*. In the ordinary atmosphere, McLean (1920) obtained a maximum absorption of CO₂ by the leaves of sugar cane that was equivalent to only 0.35 g.m.² hr. of carbohydrate.

3. The Total Incident Radiation.—In order to understand the energy relations of the green plant, a general idea must be had of the total incident radiation of the sun. The thermopile, pyroheliometer, radiometer, radiomicrometer, and bolometer are some of the instruments

that have been used to determine the intensity of solar radiation, but a description of these instruments does not belong here.

The intensity of solar radiation has been measured by means of the heat produced when the radiation is absorbed on a black surface at right angles to the rays. The data thus obtained are generally converted into calories per square centimeter per minute (Spoehr, 1926). The intensity of solar radiation is not a constant but will depend upon the height above sea level, the condition of the atmosphere, and the position of the sun. The maximum intensities of solar radiation that have been reported vary from 1.15 to 1.75 cal. per square centimeter per minute depending upon the position and general condition when the observations were made. Spoehr (1926) considers that 1.35 cal. per square centimeter per minute is a conservative estimate of the energy which reaches the earth's surface during the 6 hr. of the most intense solar radiation of the day. Thus there would be received 1.35 by 60 by 6 or 486 cal. per square centimeter during that period. Taking 90 days as a growing season, the total radiation falling upon that surface during that time would be 43,740 cal. Since there are approximately 41,000,000 cm.² per acre, the total energy received in 90 days by that surface would be 1,793,340,000,-000 cal. According to Spoehr (1926), the heat of combustion of 1 kilo of anthracite coal is equal to 8,000 kg. cal., so that the total incident radiation on an acre during a 90-day period during the growing season would be equivalent to the energy derived from the combustion of 224,167 kilos or 246 tons of anthracite coal.

4. The Coefficient of Absorption of Radiant Energy for Leaves.—As stated by Brown and Escombe (1905), the coefficient of absorption of radiant energy by a leaf is the difference between the solar radiant energy falling upon the leaf in full sunshine and the amount transmitted through it. These investigators measured the total radiant energy by means of a radiometer. The leaf was then interposed so that the light passed through it before falling upon the radiometer. The amount of energy absorbed by the leaf was thus determined, but no account was taken of the reflection or radiation from the leaf surface. This error would tend to increase unduly the estimate of the coefficient of absorption. Brown and Escombe found that the coefficient of absorption was fairly constant for mature and healthy leaves of the same species of plant, but there was considerable variation in the leaves of different species. Thus the coefficient of absorption of the leaves of *Helianthus annuus* was 0.686, for *Polygonum Weyrichii* 0.647, for *Verbascum olympicum* 0.758, and for *Archium majus* 0.728. They observed in most cases no significant differences in the absorption coefficient of young and old leaves. Brown and Escombe measured the absorption and transmission of the radiant energy by the white and green portions of the leaf of *Negundo aceroides*. They found that the coefficient of absorption of the green portion of the

leaf was 0.787, while that of the white portion was 0.745. If the transmission through the albino leaf is taken as 100, that of the green leaf would be 83.5, a difference of 16 per cent, which may be regarded as expressing the increase in the absorptive power due to the coloring matter of the leaf. In this regard, Timiriazeff (1904) noted that the chlorophyll of a certain area of leaf absorbed only 27, 29, and 23.5 per cent of the radiant energy in the case of maple, lime, and oak, respectively. Puriewitsch (1914) by means of the bolometer found that the leaves of different plants absorbed only 18 to 27 per cent of the incident solar radiation. Long (1919) by means of a photometer noted the total incident light absorbed by the leaves to be 27.3, 43.4, and 29.2 per cent of the total incident light for dandelion, bean, and sunflower, respectively. These values reported by Puriewitsch and Long are much lower than those reported by Brown and Escombe. The cause for these differences in the absorption coefficients is difficult to determine and only emphasizes the fact that our knowledge concerning even the absorption of energy by the leaves is very limited.

In considering the absorption coefficient of the leaves, the quality of the rays transmitted or absorbed must be taken into consideration. The green leaf is selective in its absorption of the various wave lengths of solar radiation incident upon it, a behavior which would be suspected, to a degree at least, owing to the selective property of chlorophyll. This selective power of the leaf is shown by the quantity of light which is transmitted when leaves are superimposed upon each other. If the leaf possessed no power of selection, it would be expected that the transmitted portion of the radiant energy would diminish in geometric proportion as the number of leaves was increased in arithmetic proportion (Brown and Escombe, 1905). Thus, for example, if the leaf of *Helianthus annuus* having a transmission coefficient of 0.313 is superimposed upon another, the coefficient of transmission should be $(0.313)^2 = 0.098$, with three such leaves $(0.313)^3 = 0.030$, and so on, if the leaf had no power of selective absorption. This, however, is not the case, since Brown and Escombe found that the coefficient of transmission through two leaves of sunflower was 0.174 and through three leaves 0.116, while the radiation which should have been transmitted in the absence of selective absorption would have been 0.098 and 0.030, respectively. A similar observation was made by Timiriazeff with a solution of chlorophyll. He found, for example, that while the chlorophyll which had been dissolved out of a given area of maple leaf arrested 27 per cent of the energy of direct sunlight, this absorption was increased to only 31 per cent by a triple concentration of the solution.

5. The Utilization of Solar Energy in the Leaves.—A portion of the energy that is absorbed by the leaf is utilized in photosynthesis and in transpiration, while a certain portion is lost by thermal emission into

the surrounding air, provided the temperature of the surrounding medium is lower than that of the leaf. The question naturally arises as to what proportions of the absorbed energy are used in photosynthesis and transpiration. Knowledge in this regard is, however, very limited and fragmentary, because experimental evidence on this subject is difficult to obtain. This difficulty is due to the fact that so many factors must be controlled and measured by methods which in many cases are doubtful in their reliability and accuracy. Some of the factors that must be controlled, measured, or taken into account are the total radiation, the coefficient of absorption, the amount of CO_2 used, the amount of water vapor given off, the intensity of respiration, the effect of the accumulation of products on photosynthesis, and the influence of the general factors upon the action of the stomata and the interchange of gases.

a. Determination of the Energy Used in Photosynthesis.—The energy used in photosynthesis has been estimated from the amount of CO_2 absorbed, from the amount of oxygen given off, and from the increase in dry weight. In all cases the determinations are reduced to the actual carbohydrate formed, correction always being made for respiration. In calculating the energy utilized by these methods, however, the difficulty that the proportions of the various carbohydrates formed are unknown is encountered, and, since each differs in its energy value, the energy utilized in producing the total carbohydrate products can be only approximated. Brown and Escombe (1905) determined the weight of CO_2 absorbed and multiplied this by the factor 0.640 to determine the weight of the carbohydrate produced, the factor being based on the carbohydrate content of the leaf as determined by previous investigators. Puriewitsch (1914) measured the increase in dry weight per unit area by the half-leaf method and the heat of combustion per unit area and thus determined the heat of combustion of the products of assimilation. The values obtained by him were higher than the value for glucose, starch, sucrose, or cellulose and suggest the production of fat or protein in the leaf during the period of photosynthesis.

b. The Energy Used in Photosynthesis.—The most extensive work that has been done to determine the energy relations of the leaf is that of Brown and Escombe (1905). A summary of 9 of their 24 experiments in regard to the energy relations of photosynthesis and transpiration is shown in the table on page 480.

The work of Brown and Escombe shows that as little as 0.5 per cent of the total incident radiation in full sunshine may be utilized in the process of photosynthesis but that as much as 4.5 per cent may be utilized when the sunshine approximates only 13 per cent. Puriewitsch (1914) by measuring the incident energy with the bolometer and determining the energy used in photosynthesis by the increase in the heat of combustion per unit of leaf area found the following utilization of the total incident

INCIDENT SOLAR RADIATION USED IN PHOTOSYNTHESIS AND TRANSPIRATION
Adapted from Brown and Escombe, 1905

Species	General conditions	Percentage of sunshine recorded	Percentage of incident radiation used in photosynthesis	Percentage of incident radiation used in transpiration
<i>Polygonum Weyrichii</i>	Leaves exposed to full sunshine under thin canvas screen for 4.75 hr.	80	1.60	53.6
	Same for 4.2 hr.	56	1.66	57.0
<i>Tropaeolum majus</i> ...	Hot cloudless day Leaves under canvas screen	100	0.50	52.7
<i>Petasites albus</i>	Leaves in sunlight under canvas screen	95	0.78	10.2
	Leaves in weak diffuse light under screen	16	1.28	60.0
	Full solar radiation without any screen	87	0.27	53.3
<i>Helianthus annuus</i> ..	A. Received full radiation	90	0.65	69.2
	B. Received one-half of that on A	90	0.94	77.3
	A. Received full radiation	100	0.56	70.1
	B. Received one-half that on A	100	0.72	80.3
	A. Received full radiation	13	2.80	34.3
	B. Received five-eighths full radiation	13	4.48	45.2

energy: *Acer platanoides*, 0.6 to 2.7 per cent; *Polygonum sacchalinese*, 1.1 to 7.7 per cent; *Helianthus annuus*, 4.5 per cent; and *Saxifraga cordifolia*, 5.0 per cent. Some of these percentages are considerably higher than those of Brown and Escombe. This may be due to the fact that the products of photosynthesis had not yet accumulated and thus did not exert a hindering influence on the rate in certain experiments. The figures of both Brown and Escombe and Purfrewitch make it evident that with a high light intensity only a small part of the incident radiation is utilized in photosynthesis. As the light intensity decreases, however, the proportion of the total incident radiation used in photosynthesis increases. This is what would be expected if light was present in excess and not a limiting factor.

The energy relations of photosynthesis in crop plants growing in the field may be approximated and are of some interest. In the case of the

pumpkin plant the rate of photosynthesis is approximately 1.8 g.m.² hr. If this increase in photosynthate is considered as starch and its heat of combustion taken as 4,200 g. cal., the energy used in photosynthesis would be somewhat less than 1 per cent of the total incident radiation if such radiation was considered as 1.35 cal. per square centimeter per minute. In the case of cowpeas and soybeans where the rate of photosynthesis is only about 0.8 g.m.² hr. the energy used in photosynthesis would be only about 0.4 per cent of the total incident radiation.

Miller (1928) observed that the maximum daily increase in the dry weight of corn plants that had reached their full leaf development was 18.3 g. under field conditions in Kansas. Assuming this total increase in weight as starch and its heat of combustion as 4,200 g. cal. and considering 6,000 corn plants per acre, the total energy fixed during the day would be 451,000,000 cal. The total incident radiation on an acre for a 6-hr. day would amount to 19,926,000,000 cal. considering 41,000,000 cm.² to the acre. The energy utilized in photosynthesis would thus be $451 \div 19,926$ or 2.2 per cent of the total incident radiation on the acre of surface. Transeau (1926) estimated that the corn plant utilized in photosynthesis only about 1.6 per cent of the total energy available to it. This, however, does not take into consideration the material utilized in respiration. Pütter, as quoted by Spoehr (1926), estimated that the utilization of the total incident solar energy by the crop plants in the production of organic matter was as follows, allowance being made for the material used in respiration: summer wheat, 3.26 per cent; summer rye, 2.60 per cent; oats, 3.31 per cent; potatoes, 3.02 per cent; and beets, 2.12 per cent.

6. The Economic Importance of Photosynthesis.—The immediate source of the energy supply that is needed continuously by all living organisms, both plant and animal, is food. This food is manufactured from simple inorganic substances by the green plant with the aid of energy derived from the sun. Food thus represents a supply of energy which has been stored by the plant from the rays of the sun. All life on the earth thus depends upon the energy that comes from the sun through the intermediary of the green plant. The green plant is thus the sole agent that has the power to transform the kinetic energy as it comes from the sun into the potential form. This is accomplished through the process of photosynthesis, and sugars, starch, cellulose, lignocellulose, fats and oils, proteins, and the multitude of plant organic compounds are stores of potential energy that has thus been transformed. This storage of the energy of the sun has been going on for millions of years and has always been in excess of that needed for the maintenance of plant and animal life. This fact is evidenced at the present time by the forests which until comparatively recently furnished man with fuel for his bodily warmth and for industrial power. The energy stored up in plant materials in the

past ages became "fossil energy" and is now stored in the form of coal and oil.

The present industrial civilization is a machine-using age which is dependent upon a continuous and abundant supply of stored energy which may be readily released to the kinetic form for the operation of these machines. At present, coal and oil are the two main sources of this stored energy which, as before stated, has been made possible through the process of photosynthesis through millions of years.

The question that is now of considerable concern, to those who are looking to the future, is, what sources can be drawn upon for a supply of energy when the supply of oil especially is greatly depleted? Alcohol derived from grains, cellulose, and other plant products has been the source that is most commonly suggested. Such a substitution, however, is much more involved and difficult than is commonly supposed. The production of alcohol from plant products as a source of power for industry has serious objections. The question of disturbing the equilibrium of the present food supply is not one of the least of these objections. Thus Spoehr (1922) states that the total average annual yield of corn in the United States (2,740,000,000 bu.) if converted into alcohol would produce only 7,500,000,000 gal. of alcohol, which would be equivalent to 5,000,000,000 gal. of gasoline, just about one-half the present yearly consumption. Thus the present production of grain from all sources in this country would scarcely more than supply the present needs for this fuel, without leaving any for a food supply. The industrial age has been made possible because an enormous supply of stored energy is close at hand or immediately available, and climatic changes, diseases, insect pests, and numerous other factors have no influence upon the supply. Such a certain and undisturbed source of energy would not thus be available if the supply of energy were furnished by the crop of the current year.

Although the green plant is the sole converter of solar energy through the process of photosynthesis, it is, as has previously been mentioned, a very inefficient machine, utilizing only from 0.5 to 3 per cent of the total energy falling upon it. It would appear that the solution of the future fuel supply lies in the discovery of the physics and chemistry of photosynthesis and by their application artificially transforming the kinetic energy of the sun rather than by depending upon this transformation by the slow-acting plant. If man can solve the problem of this transformation of energy by the plant and improve it, he will have at hand an almost unlimited and inexhaustible source of energy.

Questions

354. What is meant by the synthetic power of the green plant? What are some of the compounds that it synthesizes? What is the first synthetic compound formed by the plant?

355. What is a carbohydrate? What three main purposes do carbohydrates serve in plants? Upon what six characteristics are carbohydrates classified?

356. Show by a diagram the general classification of the carbohydrates that may occur in plants.

357. What are sugars? Name three physical and chemical reactions of the sugars.

358. What is the specific rotatory power of a sugar? By what symbol is it expressed? What factors influence the degree of rotation of a sugar?

359. What are dextrorotatory sugars? Levorotatory sugars? What is a reducing sugar? Why does it reduce? Why do some sugars not reduce?

360. What reagents are commonly used to determine the reducing qualities of sugars? What is Fehling's solution? Describe how it is prepared? Why is Rochelle salts placed in the solution? Give in detail the action of Fehling's solution when heated with a reducing sugar.

361. What are hydrazones? Osazones? What are the three most important groups of sugars that occur in green plants? What are the characteristics of the monosaccharides?

362. What are pentoses? In what amounts do they occur in plants? In what form? Where? What are the two most common pentoses derived from hydrolysis?

363. What are the hexoses? What are the four most important hexoses? What are the general characteristics of glucose? By what other names is it known? Write the structural formula of d-glucose.

364. Where does glucose occur in plants? In what compounds does it occur in the combined form in plants? What is fructose? By what other names is it known? Write the structural formula for fructose. In what forms is fructose combined in plants?

365. In what carbohydrates do mannose and galactose exist in the combined form in plants? What are the characteristics of these two sugars? What is a disaccharide? Name the four most important disaccharides occurring in plants.

366. Where and in what quantities does sucrose occur in plants? What are its general characteristics? By what other names is it known? What is invert sugar?

367. What is maltose? From what is it mainly derived? Why does it occur in such small quantities in plants? What are trisaccharides? Name some that occur in plants.

368. What are polysaccharides? How are they apparently formed? Name the main polysaccharides that occur in plants.

369. Where does cellulose occur? Name the amyloses or starches found in green plants. In what tissues does starch occur? In what form?

370. How does the size of starch grains vary? The form? The number of grains per cell? What is the general structure of a starch grain? What is the hilum or locus of the grain?

371. What is a simple starch grain? A compound grain? A concentric grain? An eccentric grain?

372. What are the lamellae of the starch grain? Discuss the theories that have been proposed to account for the physical structure of the starch grain.

373. What do studies with X-rays indicate in regard to the structure of the starch grain? What is the spherocrystalline theory of the structure of the grain?

374. In what part of the cell do starch grains always originate and occur? How do the grains found in the chloroplasts differ from those in the leucoplasts? What is temporary starch? Permanent starch? What determines whether a starch grain will be concentric or eccentric?

375. What is the general chemical composition of a starch grain? How does the outer layer of a starch grain differ in solubility and digestibility from the other portions

of the grain? How do the different lamellae differ in density and solubility? What is the effect of dilute mineral acids on starch?

376. What is starch paste? Soluble starch? What are dextrins? Enumerate their general characteristics? Where do they occur in plants? Name the three types of dextrins and state their distinctive characteristics.

377. What is inulin? In what plants does it occur? In what part of the plants? In what part of the cells? What are mannosans and galactans? Pentosans? Where do they occur in plants?

378. What is photosynthesis? Where does it occur? What waste product is formed? Name the four pigments of the chloroplasts. In what proportion do they occur in fresh leaves?

379. What are the general characteristics of chlorophyll *a*? Of chlorophyll *b*? Enumerate the solvents of these two pigments.

380. Discuss the chemical structure of chlorophyll *a* and chlorophyll *b*. What are chlorophyllins? Phytins? What is chlorophyllase? What action does it perform?

381. What is fluorescence? How is it exhibited in chlorophyll? What rays of light does chlorophyll absorb? What length of rays?

382. How many absorption bands are there in the spectrum of chlorophyll? In what portions of the spectrum is the absorption the most intense? What determines the intensity of absorption?

383. What is the state of chlorophyll in the chloroplasts? Explain how its condition in the chloroplasts is indicated by its behavior toward its solvents. How is its condition indicated by the displacement of the absorption bands?

384. Under what conditions is chlorophyll formed? What is protochlorophyll? How is the formation of chlorophyll influenced by light? By temperature? By the absence of Fe, Mg, Ca, S, K, and Mn? How has it been proved that carbohydrates are essential to the formation of chlorophyll?

385. What are the carotinoids? What are the characteristics of carotin? Xanthophyll? Fucoxanthin? Lycopersicin?

386. What did each of the following contribute to the development of our knowledge of photosynthesis: Priestly, Ingen-Housz, Senebier, De Saussure, and Sachs?

387. What are the two end products of photosynthesis? What other gases are emitted with oxygen? Under what conditions are these other gases largest in amount? Why?

388. What is the photosynthetic quotient? Describe three methods by which it may be determined? Why is its determination difficult? What is the numerical value of the photosynthetic quotient? Explain its importance as an indicator of the type of the synthetic products of photosynthesis.

389. Enumerate the carbohydrates that have been found in leaves. Which are the most abundant? What four functions involving carbohydrates are proceeding simultaneously in the leaf?

390. Name some plants that form abundant starch in their leaves. Name some that form little or no starch. What factor seems to determine the formation of starch in leaves? Give examples.

391. What evidence is there that starch is not the first carbohydrate formed in photosynthesis? How does the carbohydrate content of the leaves vary during the day? Discuss the data in this regard for any individual plant.

392. How does the carbohydrate content of the leaves vary during the growing season? How does the carbohydrate content of the different parts of the leaf differ? What does this indicate?

393. What data have been presented to prove that cane sugar is the first sugar of photosynthesis? That hexoses are the first sugars formed?

394. State the chemical equation that is commonly given for the process of photosynthesis. What does this equation show? What do you consider the most striking fact in regard to photosynthesis?

395. Enumerate the functions that have been assigned to the chlorophyll in the process of photosynthesis. What evidence is there that the atomic groups of the chlorophyll enter into the decompositions and combinations that lead to the formation of carbohydrates.

396. How does the rate of absorption of CO_2 by leaves compare with the rate of absorption of this gas by water? Give data in this regard. What reaction has been suggested to account for an accumulation of CO_2 in the leaf cells?

397. What is Baeyer's hypothesis in regard to photosynthesis? Upon what evidence was this theory proposed? By what three general methods has the reduction of CO_2 to formaldehyde been artificially produced?

398. Why does the reduction of CO_2 to formaldehyde by the above methods fail to establish the fact that this procedure occurs in photosynthesis?

399. What is the source of the formaldehyde produced by isolated chlorophyll when exposed to the light? How do certain aniline dyes behave in this regard? What conditions other than light are necessary for the production of formaldehyde by these pigments?

400. What evidence is there that chlorophyll may be photo-oxidized to formaldehyde during photosynthesis? Under what conditions has formaldehyde been condensed artificially to sugar? Do these results indicate that sugar is formed in the leaf after the same manner? Why?

401. What is "activated formaldehyde"? What experiment has been performed that indicates that surface phenomena are concerned in the reduction of CO_2 to sugar?

402. What does the detection of formaldehyde in the leaves indicate? What might be the origin of the formaldehyde thus detected? How has formaldehyde been used in nutritional experiments with green plants? What results have been obtained? What do these results indicate?

403. Enumerate the simple facts that are definitely known concerning the process of photosynthesis. What is the law of the minimum? The law of limiting factors? Illustrate what is meant by the law of limiting factors in the case of the supplies of CO_2 and light in the process of photosynthesis.

404. What can be said concerning the general applicability of the law of limiting factors? What are external factors? Internal factors? Enumerate the external factors that may influence the rate of photosynthesis. What internal factors may play a part in the process?

405. What amount of carbon dioxide is in the air? How does the amount vary at different levels above the soil? How does the CO_2 content of the air of the soil compare with the atmosphere above it? What are the origins of the CO_2 supply of the atmosphere?

406. What percentage of the dry weight of plants is carbon? If a corn plant contains 364 g. of carbon, how much air must be depleted of CO_2 in order to furnish that amount? What evidence is there that plants may obtain some of their carbon supply from the soil?

407. What evidence is there in regard to the ability of the plant to use carbon monoxide? What is the effect on the rate of photosynthesis of increasing the CO_2 content of the air? How does this vary for different plants?

408. What is meant by the internal diffusion of CO_2 ? Illustrate this by naming the media through which CO_2 must pass in going from the exterior of the leaf to the surface of the chloroplasts. What is the general form of the photosynthetic curve when plotted against an increasing CO_2 supply?

409. What results have been obtained in fertilizing plants with CO_2 in agricultural practice? From what sources has this CO_2 been obtained? By what methods has it been distributed to the plants? What precautions must be used in its distribution?

410. Give some data to illustrate the beneficial effects of CO_2 fertilization on crop production. To what is the increased weight of plants under these conditions due?

411. What is the relationship between light intensity and the rate of photosynthesis? What is meant by photochemical induction in photosynthesis?

412. How does the application of intermittent light affect the rate of photosynthesis? How does this effect vary with the frequency of the intermittence? How has this effect of intermittent light upon photosynthesis been explained?

413. What is the compensation point in regard to respiration and photosynthesis in plants? State a general law concerning the rate of photosynthesis of different plants when light is a limiting factor.

414. Enumerate the difficulties that are encountered in determining the relation of the rate of photosynthesis to the different wave lengths of light? Explain the "iodine-starch method" for obtaining the relative efficiency of the different wave lengths in photosynthesis. What does this method indicate as to the efficiency of the various rays in photosynthesis? What are the objections to this method?

415. How does the rate of photosynthesis in the red and blue rays compare when determined by the oxygen-bubbling method? How does the rate of photosynthesis respond to these two kinds of rays in the case of plants adapted to low light intensities? What relationship is there between the efficiency of photosynthesis and the absorption bands of the spectrum?

416. What is the temperature coefficient of photosynthesis? Why is it relatively low? What is the relationship of the chlorophyll content and the temperature coefficient of photosynthesis? Why does the value of the temperature coefficient of photosynthesis throw little light on the nature of the process?

417. What is the threshold temperature for photosynthesis? How does the photosynthetic rate behave at higher temperatures? Illustrate with data. How might the optimum temperature for photosynthesis be defined?

418. What is Tammann's principle? Why is it considered here? What experimental evidence is there to indicate that an enzyme might be concerned in the photosynthetic process?

419. How does the chlorophyll content of light and shade plants compare? Lowland and alpine plants? How do the photosynthetic rates of these plants compare in different light intensities?

420. What is the photosynthetic or assimilation number? Of what value is it in photosynthetic studies? What is the relationship between the chlorophyll content and the rate of photosynthesis?

421. How does the greening of etiolated plants affect the photosynthetic activity? Why? What seedling plants show no lagging of the photosynthetic activity at germination? Which show lagging?

422. What direct rôle does water play in photosynthesis? What indirect rôle? How does the rate of photosynthesis in wilted leaves compare with the rate in turgid leaves? Which tissues of a leaf are the first to lower their transpiration rate when the water supply is diminishing? Why?

423. How are the chlorophyll and protoplasm dependent upon each other in photosynthesis? How does the oxygen supply affect the process of photosynthesis?

424. What is solarisation in regard to photosynthesis? How does the accumulation of photosynthetic products affect the process? Give examples.

425. What are "starch" plants? "Sugar" plants? What is the concentration of sugar necessary for starch production in starch plants? In sugar plants? In what two ways may the lack of K, Ca, Mg, Fe, or P affect the rate of photosynthesis?

426. What is meant by the "reactive surface" of the chloroplast? How do rusts affect the photosynthetic rate? Give examples.

427. By what three general methods has the rate of photosynthesis been measured? Why are conflicting results sometimes obtained by these different methods?

428. In determining the rate of photosynthesis, how may the correction for respiration be obtained? What is the objection to this correction?

429. In what four ways may the liberation of oxygen in photosynthesis be determined? Describe these methods and state the advantages and disadvantages of each.

430. Describe the manner by which the rate of photosynthesis may be obtained by measuring the amount of carbon dioxide absorbed. What details must be considered in the use of this method?

431. How may the increase in starch in leaves be demonstrated by the iodine-starch method? Describe in detail the half-leaf method of Sachs as now used in the determination of the photosynthetic rate.

432. What corrections must be made in the use of this method? How? What errors in this method can not readily be corrected? Describe the saccharification method for determining the rate of photosynthesis.

433. Discuss the rates of photosynthesis of the various plants that have been studied in that regard.

434. How has the total solar radiation been measured? Upon what factors will its intensity depend? What is the value of the solar radiation per unit of surface? What is the value of the solar radiation falling upon an acre over a 90-day period during the growing season? Explain how this is calculated.

435. What is the coefficient of absorption of radiant energy by a leaf? How may this be determined? What portion of the incident radiation is absorbed by leaves?

436. What is meant by the selective absorption of solar energy by the leaf? How is this determined? Name six factors that will determine the amount of incident radiation utilized by the leaf.

437. In what four ways may the energy used in photosynthesis be determined? What are the objections to these methods?

438. What proportion of the total incident radiation is utilized in photosynthesis in diffuse light? In direct light? Formulate an example to determine the proportion of the incident radiation utilized by crop plants in photosynthesis.

439. Of what economic importance is the process of photosynthesis? Why is there considerable interest in the process at the present time?

Bibliography

- ANDREWS, F. M., 1925: Starch formation, *Ind. Acad. Sci. Proc.* **35**: 182-184.
- BAEYER, A., 1870: Ueber die Wasserentziehung und ihre Bedeutung für das Pflanzenleben und die Gährung, *Ber. d. d. Chem. Ges.*, **3**: 63-78.
- BAKER, S. M., 1913: Quantitative experiments on the effects of formaldehyde on living plants, *Ann. Bot.*, **27**: 411-443.
- BALY, E. C., I. M. HEILBRON, and W. F. BARKER, 1921: Photocatalysis. Part I. The synthesis of formaldehyde and carbohydrates from carbon dioxide and water, *Jour. Chem. Soc. Trans.* **119**: 1025-1035.
- , 1922: Photosynthesis, *Nature*, **109**: 344-346.
- , I. M. HEILBRON, and W. F. BARKER, 1923: Photochemical production of formaldehyde, *Nature*, **112**: 323.
- , 1924: Photosynthesis, *Jour. Ind. Eng. Chem.*, **16**: 1016-1018.
- , 1928: Photosynthesis, *Science*, n.s., **68**: 364-367.

- BANAL, R., 1926: Un fertilizzante fondamentale: l'anidride carbonica. Problemi ed esperienze sull' assimilazione del carbonio, *L'Italia agricola*, **63**: 118-121.
- BARNES, C. R., 1893: On the food of green plants, *Bot. Gaz.*, **18**: 403-411.
- , 1898: So-called "assimilation," *Bot. Centrbl.*, **76**: 255-259.
- BERNARD, C., 1878: "Leçons sur les phénomènes de la vie commun aux animaux et aux végétaux," Paris.
- BERTHELOT, D., and H. GAUDECHON, 1910: Synthèse photochimique des hydrates de carbone aux dépens des éléments de l'anhydride carbonique et de la vapeur d'eau, en l'absence de chlorophyll, *Compt. Rend. Acad. Sci. Paris*, **150**: 1690-1693.
- BLACKMAN, F. F., and G. L. C. MATTHAEI, 1905: Experimental researches in vegetable assimilation and respiration. IV, A quantitative study of carbon-dioxide assimilation and leaf-temperature in natural illumination, *Proc. Roy. Soc. B*, **76**: 402-460.
- , 1905: Optima and limiting factors, *Ann. Bot.*, **19**: 281-295.
- , 1910: Experimental researches on vegetable assimilation and respiration. VIII, A new method for estimating the gaseous exchanges of submerged plants, *Proc. Roy. Soc. B*, **83**: 374-388.
- , and A. M. SMITH, 1910: Experimental researches on vegetable assimilation and respiration. IX, On assimilation in submerged water plants and its relation to the concentration of carbon dioxide and other factors, *Proc. Roy. Soc. B*, **83**: 389-412.
- BOEHM, J. A., 1856: Beiträge zur näheren Kenntniss der Chlorophylls, *Sitzungsber. d. k. Akad. d. Wien.*, **22**: 479.
- BÖHM, J., 1883: Ueber Stärkebildung aus Zucker, *Bot. Zeitung*, **41**: 33-38, 49-54.
- BOKORNY, T., 1891: Ueber Stärkebildung aus Formaldehyd, *Ber. d. d. bot. Ges.*, **9**: 103-106.
- , 1892: Ernährung von grünen Pflanzenzellen mit Formaldehyd, *Landw. Jahrb.* **21**: 445-465.
- , 1897: Ueber die organische Ernährung von grünen Pflanzen und ihre Bedeutung in der Natur, *Biol. Centrbl.*, **17**: 1-20, 33-48.
- , 1908: Ueber die Assimilation des Formaldehyds und die Versuche dieses Zwischenproduct bei Kohlensäure-Assimilation nachzuweisen. Assimilation von Glycerin und Zucker, *Archiv. f. ges. Physiol.*, **125**: 467-490.
- , 1909: Weitere Mitterilung über CO₂-Assimilation und Ernährung von Pflanzen mit Formaldehyd, *Archiv. f. ges. Physiol.*, **128**: 565-586.
- , 1910: Die bisherigen Versuche den Formaldehyd direkt in Blättern nachzuweisen, *Chem. Zeits.*, **33**: 1141-1143, 1150-1151.
- , 1911: Ernährung von grünen Pflanzen mit Formaldehyd und formaldehydabspaltenden Substanzen, *Biochem. Zeits.*, **36**: 83-97.
- BOLAS, B. D., and F. Y. HENDERSON, 1928: The effect of increased atmospheric carbon dioxide on the growth of plants. I, *Ann. Bot.*, **42**: 509-523.
- BONNIER, G., and L. MANGIN, 1886: Recherches sur l'action chlorophyllienne séparée de la respiration, *Ann. Sci. Nat. Bot.*, **7**, **3**: 1-44.
- BORNEMANN, O., 1920: Kohlensäure und Pflanzenwachstum, *Mitteil. deut. landw. Ges.*, **35**: 693-695; *Bot. Abst.* **8**: 2 (1921).
- , G. LEMMERMAN and F. RIEDEL, 1921: Zur Kohlenstoffernährung der Kulturpflanzen, *Mitteil. deut. landw. Ges.*, **36**: 481-485, 496-498.
- BOSE, J. C., 1924: "Physiology of Photosynthesis," p. 286, Longmans, Green and Co., New York.
- BOTTOMLEY, W. B., and H. JACKSON, 1903: Some preliminary observations on the assimilation of carbon monoxide by green plants, *Proc. Roy. Soc.*, **72**: 130-131.

- BOUSSINGAULT, J. B., 1864: De la végétation dans l'obscurité, *Ann. Sci. Nat. Bot.*, 5^e, 1: 314-324.
- BOYSEN-JENSEN, P., 1918: Studies on the production of matter in light and shadow plants, *Bot. Tidssk.*, 36: 219-262.
- BREAZEALE, J. F., 1923: The absorption of carbon by the roots of plants, *Jour. Agr. Res.*, 26: 303-313.
- BRIGGS, G. E., 1920: Experimental researches on vegetable assimilation and respiration. XIII, The development of photosynthetic activity during germination, *Proc. Roy. Soc.*, B, 91: 249-268.
- , 1922: Experimental researches on vegetable assimilation and respiration. XV, The development of photosynthetic activity during germination of different types of seeds, *Proc. Roy. Soc.*, B, 94: 12-19.
- , 1922: Experimental researches on vegetable assimilation and respiration. XVI, The characteristics of subnormal photosynthetic activity resulting from deficiency of nutrient salts, *Proc. Roy. Soc.*, B, 94: 20-35.
- BRILLIANT, B., 1924: Le teneur en eau dans les feuilles et l'énergie assimilatrice, *Compt. Rend. Acad. Sci. Paris*, 178: 2122-2125.
- BROWN, H. T., and G. H. MORRIS, 1893: A contribution to the chemistry and physiology of foliage leaves, *Jour. Chem. Soc.*, 63: 604-677.
- , and F. ESCOMBE, 1902: The influence of varying amounts of carbon dioxide in the air on the photosynthetic process of leaves and on the mode of growth of plants, *Proc. Roy. Soc.*, 70: 397-413.
- , and ———, 1905: Researches on some of the physiological processes of green leaves, with special reference to the interchange of energy between the leaf and its surroundings, *Proc. Roy. Soc.*, B, 76: 29-112.
- , and W. E. WILSON, 1905: On the thermal emissivity of a green leaf in still and moving air, *Proc. Roy. Soc.*, B, 76: 122-137.
- BROWN, W. H., and G. W. HEISE, 1917: The application of photochemical temperature coefficients to the velocity of carbon dioxide assimilation, *Phil. Jour. Sci.*, C, 12: 1-24.
- BURK, DEAN, 1927: Photosynthesis with malachite green, *Jour. Amer. Chem. Soc.*, 49: 1819-1825.
- BUTLEROW, A., 1861: Bildung einer zuckerartigen Substanz durch Synthese, *Ann. Chem. Pharm.*, 120: 295-298.
- CAILLETET, M. L., 1911: Sur l'origine du carbone assimilé par les plantes, *Compt. Rend. Acad. Sci. Paris*, 152: 1215-1217.
- CERIGHELLI, RAOUL, 1921: Influence de l'anhydride carbonique sur le développement des plantes—emploi de CO₂ comme en gris atmosphérique, *Ann. Sci. Agron.*, 38: 68-75.
- CLAYSON, D. H. F., and S. B. SCHRYVER, 1923: The hemicelluloses. I, The hemicellulose of wheat flour, *Biochem. Jour.*, 17: 493-496.
- COLIN, M. H., 1914: Sur la saccharogénie dans la betterave, *Compt. Rend. Acad. Sci. Paris*, 159: 687-689.
- , 1916-1917: Le saccharose dans la betterave. Formation et disparition, *Rév. Gén. Bot.*, 28: 289-299, 321-328, 368-380; 29: 21-32, 56-64, 89-96, 113-127, quoted by Stiles (1925).
- , 1918: The origin of inulin in plants, *Compt. Rend. Acad. Sci. Paris*, 166: 224-227, abstr. *Expt. Sta. Rec.* 39: 524.
- , and H. BELVAL, 1922: La genèse des hydrates de carbone dans le blé. Présence de lévulosanes dans la tige, *Compt. Rend. Acad. Sci. Paris*, 175: 1441-1443.
- CROCKER, WILLIAM, 1918: Law of the minimum—a review of Hooker's work, *Bot. Gaz.*, 65: 287-288.

- CUMMINGS, M. B., and C. H. JONES, 1918: The aerial fertilization of plants with carbon dioxide. *Vt. Agr. Expt. Sta. Bull.* 211.
- , and ———, 1920: The aerial fertilization of plants with carbon dioxide, *Jour. Chem. Soc. Abst.*, **118**: 267.
- DASTUR, R. H., 1924: Water content, a factor in photosynthesis, *Ann. Bot.*, **38**: 779-788.
- , 1925: The relation between water content and photosynthesis, *Ann. Bot.*, **39**: 769-786.
- DAVIS, W. A., and A. J. DAISH, 1913: A study of the methods of estimation of carbohydrates, especially in plant extracts. A new method for the estimation of maltose in presence of other sugars, *Jour. Agr. Sci.*, **5**: 437-468.
- , and ———, 1914: Methods of estimating carbohydrates. II, The estimation of starch in plant material. The use of taka-diastrase, *Jour. Agr. Sci.*, **6**: 152-168.
- , and G. C. SAWYER, 1914: The estimation of carbohydrates. IV, The presence of free pentoses in plant extracts and the influence of other sugars on their estimation, *Jour. Agr. Sci.*, **6**: 406-412.
- , 1916: Studies of the formation and translocation of carbohydrates in plants. II, The dextrose-laevulose ratio in the mangold, *Jour. Agr. Sci.*, **7**: 327-351.
- , A. J. DAISH, and G. C. SAWYER, 1916: Studies of the formation and translocation of carbohydrates in plants. I, The carbohydrates of the mangold leaf, *Jour. Agr. Sci.*, **7**: 255-326.
- , and G. C. SAWYER, 1916: Studies of the formation and translocation of carbohydrates in plants. III, The carbohydrates of the leaf and leaf stalks of the potato. The mechanism of the degradation of starch in the leaf. *Jour. Agr. Sci.*, **7**: 352-384.
- DEAN, A. L., 1904: On inulin, *Amer. Chem. Jour.*, **32**: 69-84.
- DEMOUSSY, E., 1903-1904: Sur la végétation dans des atmosphères riches en acide carbonique. *Compt. Rend. Acad. Sci. Paris*, **136**: 325-328; **138**: 291-293 (1904); **139**: 883-885 (1904).
- DEUBER, C. G., 1926: Influence of mineral elements upon the development of chloroplast pigments of soybeans, *Bot. Gaz.*, **82**: 132-152.
- DIXON, H. H., and T. G. MASON, 1916: The primary sugar of photosynthesis, *Nature*, **97**: 160.
- , and H. H. POOLE, 1920: Photosynthesis and the electronic theory, *Sci. Proc. Roy. Dublin Soc.*, **16**: 63-77.
- , and ———, 1920: Photosynthesis and the electronic theory, *Notes Bot. School Trinity Coll. Dublin*, **3**: 90-104.
- , and N. G. BALL, 1922: Photosynthesis and the electronic theory, *Notes Bot. School Trinity Coll. Dublin*, **3**: 199-205.
- DUCLAUX, E., 1899: "Traite de microbiologie." 2, "Diastases, Toxines et Venins," 768 pp., Masson et Cie, Paris.
- EWART, A. J., 1896: On assimilatory inhibition in plants, *Jour. Linn. Soc. Bot.*, **31**: 364-461.
- , 1897: The effect of tropical insolation, *Ann. Bot.*, **11**: 439-480.
- , 1898: The action of cold and of sunlight upon aquatic plants, *Ann. Bot.*, **12**: 363-397.
- , 1898: Can isolated chloroplastids continue to assimilate? *Bot. Centrbl.*, **75**: 33-36.
- , 1907: On the supposed extracellular photosynthesis of carbon dioxide by chlorophyll, *Proc. Roy. Soc.*, B. **80**: 30-36.
- , 1918: On chlorophyll, carotin and xanthophyll and on the production of sugar from formaldehyde, *Proc. Roy. Soc. Victoria*, n.s., **30**: 178-209.

- EWART, A. J., 1919: On the synthesis of sugars from formaldehyde, *Proc. Roy. Soc. Victoria*, n.s., **31**: 378-387.
- , 1920: On the synthesis of sugar from formaldehyde and its polymers, its quantitative relations and its exothermic character, *Proc. Roy. Soc. Victoria*, n.s., **32**: 168-188.
- EYSTER, W. H., 1928: Photochlorophyll, *Science*, **68**: 569-570.
- FENTON, H. J. H., 1907: The reduction of carbon dioxide to formaldehyde in aqueous solution, *Jour. Chem. Soc. Trans.* **91**: 687-694.
- FERNBACH, A., and J. WOLFF, 1904: Nouvelles observations sur la formation diastatique de l'amyloicellulose, *Compt. Rend. Acad. Sci. Paris*, **138**: 819-821.
- , 1912: Sur une nouvelle forme d'amidon soluble, *Compt. Rend. Acad. Sci. Paris*, **155**: 617-618.
- FINCKE, H., 1913: Über den Nachweis von Formaldehyd in Pflanzen, *Biochem. Zeits.*, **52**: 214-225.
- FISCHER, H., 1912: Carbonic-acid gas as a plant nutrient, *Gartenflora*, **61**: 298-307; abst. *Expt. Sta. Rec.* **28**: 837.
- , 1913: The effect of an increased amount of carbonic acid in the air on green plants, *Jahresber. Ver. Angew. Bot.*, **11**: 1-8; abst. *Expt. Sta. Rec.* **31**: 140.
- , 1919: The carbon nutrition of cultivated plants, *Gartenflora*, **68**: 165-168; abst. *Expt. Sta. Rec.* **42**: 137.
- , 1920: Plant growth and carbon dioxide, *Naturwissenschaften*, **8**: 413-417; abst. *Expt. Sta. Rec.* **45**: 218.
- , 1921: Carbon dioxide manuring, *Angew. Bot.*, **3**: 129-144; abst. *Expt. Sta. Rec.* **49**: 522.
- , 1927: Die Kohlensäure-Ernährung der Pflanzen, *Ber. d. d. bot. Ges.*, **45**: 331-339.
- GALWIALO, M. J., 1925: Zur Frage nach der Photosynthese der Kohlehydrate, *Biochem. Zeits.*, **158**: 65-75.
- GANONG, W. F., 1906: Normal apparatus, *Bot. Gaz.*, **41**: 209-213.
- , 1908: "Plant Physiology," pp. 107-109, Henry Holt & Company.
- GAST, W., 1917: Quantitative Untersuchungen über den Kohlenhydratstoffwechsel im Laubblatt, *Zeits. f. physiol. Chem.*, **99**: 1-54.
- GERLACH, P., 1919: Kohlensäuredüngung, *Mitt. deut. landw. Ges.*, **34**: 77-82.
- , 1921: Carbon dioxide nutrition of plants and stable manure, *Mitt. deut. landw. Ges.*, **36**: 147-150; abst. *Expt. Sta. Rec.* **46**: 424.
- , 1926: Ueber Kohlesäuredüngung, *Zeits. f. Pflanzenernährung und Düngung*, **5**: 65-69.
- GIBSON, R. J. H., 1908: A photoelectric theory of photosynthesis, *Ann. Bot.*, **22**: 117-120.
- GIRARD, A., 1883: Recherches sur la saccharogénie dans la betterave, *Compt. Rend. Acad. Sci. Paris*, **97**: 1305-1308
- , 1884: Recherches sur la saccharogénie dans la betterave, *Compt. Rend. Acad. Sci. Paris*, **99**: 808-811.
- GODLEWSKI, E., 1873: Abhängigkeit der Sauerstoffausscheidung der Blätter von dem Kohlensäuregehalt der Luft, *Arb. bot. Inst. Würzburg*, **1**: 343-370.
- GRADENWITZ, A., 1920: Carbonic acid gas to fertilize the air, *Sci. Amer.*, **123**: 549.
- GRAFE, V., and E. VIESEB, 1909-1911: Untersuchungen über das Verhalten grüner Pflanzen zu gasförmigen Formaldehyd. I, II, *Ber. d. d. bot. Ges.*, **27**: 431-446; **29**: 19-26 (1911).
- GRUZIT, O. M., and R. P. HIBBARD, 1916: The influence of an incomplete culture solution on photosynthesis, *Rept. Mich. Acad. Sci.*, **18**: 50-52.
- HAAS, P., and T. G. HILL, 1913: "The Chemistry of Plant Products," pp. 400, Longmans, Green and Co.

- HABERLANDT, G., 1882: Vergleichende Anatomie des assimilatorischen Gewebesystems der Pflanzen, *Jahrb. f. wiss. Bot.*, **13**: 74–188.
- HARDER, R., 1921: Kritische Versuche zu Blackmans Theorie der "begrenzenden Factoren" bei der Kohlensäureassimilation, *Jahrb. f. wiss. Bot.*, **60**: 531–571.
- HARDING, T. S., 1923: History of inulin, its discovery and methods of preparation, *Sugar*, **25**: 636–638; *Expt. Sta. Rec.* **51**: 409.
- HARVEY, E. N., 1928: Photosynthesis in absence of oxygen, *Plant Physiol.*, **3**: 85–89.
- HEILBRON, I. M., 1923: The photosynthesis of plant products, *Nature*, **111**: 502–504; *Bot. Abst.*, **12**: 981.
- HENRICI, MARGUERITE, 1918: Chlorophyllgehalt und Kohlensäureassimilation bei Alpen- und Ebenenpflanzen, *Verhand. Naturforsch. Ges. Basel.*, **30**: 43–136.
- HERLITZKA, A., 1912: Über den Zustand des Chlorophylls in der Pflanze und über kolloidales Chlorophyll, *Biochem. Zeits.*, **38**: 321–330.
- HOOKE, H. D., 1917: Liebig's law of the minimum in relation to general biological problems, *Science*, n.s., **46**: 197–204.
- HORN, TRUDE, 1923: Das gegenseitige Mengenverhältnis der Kohlenhydrate im Laubblatt in seiner Abhängigkeit von Wassergehalt, *Bot. Archiv.*, **3**: 137–172; *Bot. Abst.*, **13**: 1019.
- ILJIN, W. S., 1915: Transpiration and assimilation in steppe plants, *Bull. Acad. Imp. Sci. Petrograd.*, 6 ser., **9**: 346–367; abst. *Expt. Sta. Rec.* **36**: 734.
- , 1923: Der Einfluss des Wassermangels auf die Kohlenstoffassimilation durch die Pflanzen, *Flora*, **116**: 360–378.
- INGEN-HOUSZ, JEAN, 1779: "Experiment upon Vegetables, Discovering Their Great Power of Purifying Common Air in the Sunshine and of Injuring in the Shade and Night," London.
- IRVING, A. A., 1910: The beginning of photosynthesis and the development of chlorophyll, *Ann. Bot.*, **24**: 805–818.
- JACOBY, M., 1919: Über den Formaldehyd als Übergangsstufe zwischen der eigentlichen Assimilation und der Kohlenhydratbildung in der Pflanze, *Biochem. Zeits.*, **101**: 1–6.
- , 1922: Über den Formaldehyd als Übergangsstufe zwischen der eigentlichen Assimilation und der Kohlenhydratbildung in der Pflanze. II, *Biochem. Zeits.*, **128**: 119–121.
- JAMES, W. O., 1928: Experimental researches on vegetable assimilation and respiration. XIX, The effect of variations of carbon dioxide supply upon the rate of assimilation of submerged water plants, *Proc. Roy. Soc.*, B, **103**: 1–42.
- JESS, M., 1921: Carbonic acid gas as a fertilizer, *Jour. Agr. Prat.*, n.s., **35**: 250–252; abst. *Expt. Sta. Rec.* **45**: 344.
- JØRGENSEN, I., and F. KIDD, 1917: Some photochemical experiments with pure chlorophyll and their bearing on theories of carbon assimilation, *Proc. Roy. Soc.*, B, **89**: 342–361.
- and W. STILES, 1917: Carbon assimilation. A review of recent work on the pigments of the green leaf and the processes connected with them, *New Phytol.*, repr. **10**: 1–180.
- KAYSER, R., 1883: Ueber das Vorkommen von Rohrzucker und einigen seiner Umwandlungsproducte im Organismus der Pflanzen, *Landw. Versuchs-Stat.*, **29**: 461–473.
- KEUHL, H. J., 1926: The concentration of carbon dioxide in the air above cultivated areas, *Zeits. f. Pflanzenernährung und Düngung*, **6**: 318–378.
- KIMPLIN, G., 1907: Sur la présence du menthonal dans les végétaux vertes, *Compt. Rend. Acad. Sci. Paris*, **144**: 148–150.
- KJELDHAL, J., 1879: Recherches sur le ferment production du sucre, *Compt. Rend. de travaux du lab. de Carlsberg*.

- KNIEP, H., and F. MINDER, 1909: Ueber den Einfluss verschiedenfarbigen Lichtes auf die Kohlensäureassimilation, *Zeits. f. Bot.*, **1**: 619–650.
- KNY, L., 1897: Die Abhängigkeit der Chlorophyllfunction von den Chromatophoren und von Cytoplasma, *Ber. d. d. bot. Ges.*, **15**: 388–403.
- , 1898: Vermögen isolirter Chlorophyllkörper im Lichte Sauerstoff auszuschenden? *Bot. Centrbl.*, **73**: 426–439.
- KOSTYTSCHEW, S., 1921: Studien über Photosynthese. I, Das Verhältnis CO_2/O_2 bei der Kohlensäureassimilation, *Ber. d. d. bot. Ges.*, **39**: 319–328; *Bot. Abst.*, **12**: 744.
- , 1922: Studien über Photosynthese. IV, Die CO_2 Assimilation der Leguminosen, *Ber. d. d. bot. Ges.*, **40**: 112–119.
- KRAEMER, H., 1902: The structure of the starch grain, *Bot. Gaz.*, **34**: 341–355.
- , 1905: Further observations on the structure of the starch grain, *Bot. Gaz.*, **40**: 305–310.
- , 1923: The starch grains, *Science*, n.s., **57**: 175.
- KRAUS, G., 1869: Einige Beobachtungen über den Einfluss des Lichts und der Wärme auf die Stärkeerzeugung im Chlorophyll, *Jahrb. f. wiss. Bot.*, **7**: 511–531.
- KREUSLER, U., 1885: Ueber eine Methode zur Beobachtung der Assimilation und Athmung der Pflanzen und über einige diese Vorgänge beeinflussende Momente, *Landw. Jahrb.*, **14**: 913–965.
- , 1887: Beobachtungen über die Kohlensäure-Aufnahme und -Ausgabe (Assimilation und Athmung) der Pflanzen. II. Mittheilung. Abhängigkeit von Entwicklungszustand—Einfluss der Temperatur, *Landw. Jahrb.*, **16**: 711–755.
- , 1888: Beobachtung über die Kohlensäure-Aufnahme und -Ausgabe (Assimilation und Athmung) der Pflanzen. III, Mittheilung. Einfluss der Temperatur, *Landw. Jahrb.*, **17**: 161–175.
- , 1890: Beobachtungen über Assimilation und Athmung der Kohlensäureausscheidung seitens getödteter Exemplare; Kohlensäureverbrauch, wenn Ober- und Unterseite der Blätter dem Licht zugewendet, *Landw. Jahrb.*, **19**: 649–668.
- KUIPER, K. J., 1920: Koolsuurbemesting nachtverlichting en andere groeibevorderende factoren in de plantenteelt. (Effects of CO_2 manuring, night illumination and other growth-stimulating factors upon plant culture), *Cultura*, **32**: 332–344, 355–368; *Bot. Abst.*, **8**: 96.
- LEMMERMAN, O., 1920: Ueber die Kohlensäureernährung der Pflanzen, *Mitteil. deuts. landw. Ges.*, **35**: 696–699; *Bot. Abst.*, **8**: 5.
- , 1926: Untersuchungen über die Bedeutung der Bodenkohlensäure für die Ernährung der Pflanzen und über die Wirkung einiger Humus-bezw. Kohlen-säuredünger, *Zeits. f. Pflanzenmahrung und Düngung*, **5**: 70–85.
- LIEBIG, J., 1843: "Chemistry in Its Application to Agriculture and Physiology," 3d ed., Philadelphia, Peterson.
- , 1843: Die Wechselwirthschaft, *Ann. Chem. Pharm.*, **46**: 58–97.
- LINDET, L., and P. NOTTIN, 1923: Evolution des grains de féculé dans le tubercule de la pomme de terre, *Compt. Rend. Acad. Sci. Paris.*, **176**: 149–155.
- LING, A. R., and R. N. DINSHAW, 1923: Studies on starch. Part I, The nature of polymerized amylose and amylopectin, *Jour. Chem. Soc.*, **123**: 2666–2688.
- LIVINGSTON, B. E., 1917: A quarter-century of growth in plant physiology, *Plant World* **20**: 1–15.
- LOEB, W., 1905–1906: Zur Kenntniss der Assimilation der Kohlensäure, *Zeits. f. Elektrochem.*, **11**: 745–752; **12**: 282–312.
- LONG, F. L., 1919: The quantitative determination of photosynthetic activity in plants, *Physiol. Res.*, **2**: 277–300.
- LUBIMENKO, W., 1905: Sur la sensibilité de l'appareil chlorophyllien des plantes ombrophiles et ombrophobes, *Rév. Gén. Bot.*, **17**: 381–415.

- LUBIMENKO, W., 1908: La concentration du pigment vert et l'assimilation chlorophyllienne, *Rév. Gén. Bot.*, **20**: 162-177, 217-238, 253-267, 285-297.
- , 1923: Action spécifique des rayons lumineux de diverses couleurs dans la photosynthèse, *Compt. Rend. Acad. Sci. Paris*, **177**: 606-608; *Bot. Abst.*, **13**: 568.
- LUNDEGÅRDH, H., 1921: Ecological studies in the assimilation of certain forest plants and short plants, *Svensk. Bot. Tidsk.*, **15**: 46-95.
- , 1922: Theoretical and practical basis for carbon dioxide fertilization, *Angew. Bot.*, **4**: 120-151; abst. *Expt. Sta. Rec.* **49**: 421.
- , 1924: "Der Kreislauf der Kohlensäure in der Natur," pp. VIII, 308, Fig. 47. Gustav Fischer, Jena.
- MACDOUGAL, D. T., 1895: Nature and life history of starch grains, *Bot. Gaz.*, **20**: 458-459.
- MAQUENNE, L., 1903: Sur la rétrogradation de l'empois d'amidon, *Compt. Rend. Acad. Sci. Paris*, **137**: 88-90.
- and E. ROUX, 1905: Sur la constitution la saccharification et la rétrogradation des empois de fécula, *Compt. Rend. Acad. Sci. Paris*, **140**: 1303-1308.
- , 1911: À propos d'une communication récente de M. L. Cailletet, *Compt. Rend. Acad. Sci. Paris*, **152**: 1818-1819.
- and E. DEMOUSSY, 1913: Sur la valeur des coefficients chlorophylliens et leurs rapports avec les quotients respiratoires réels, *Compt. Rend. Acad. Sci. Paris*, **156**: 506-512.
- MASKELL, E. J., 1928: Experimental researches on vegetable assimilation and respiration. XVIII, The relation between stomatal opening and assimilation—a critical study of assimilation rates and porometer rates in leaves of cherry laurel, *Proc. Roy. Soc., B*, **102**: 488-533.
- , 1928: Experimental researches on vegetable assimilation and respiration. XVII, The diurnal rhythm of assimilation in leaves of cherry laurel as limiting concentrations of carbon dioxide, *Proc. Roy. Soc., B*, **102**: 467-488.
- MATTHAEI, G. L. C., 1902: The effect of temperature on carbon dioxide assimilation, *Ann. Bot.*, **16**: 591-593.
- , 1905: Experimental researches on vegetable assimilation and respiration. III, On the effect of temperature on carbon-dioxide assimilation, *Phil. Trans. Roy. Soc.*, **197**: 47-105.
- MCLEAN, F. T., 1920: Field studies of the carbon dioxide absorption of coconut leaves, *Ann. Bot.*, **34**: 367-389.
- MELLANBY, JOHN, 1919: The composition of starch. I, Precipitation by colloidal iron. II, Precipitation by iodine and electrolytes, *Biochem. Jour.*, **13**: 28-36.
- MEYER, A., 1881: Ueber die Structur der Stärkekörner, *Bot. Zeitung*, **39**: 841-852, 856-864.
- , 1885: Ueber die Assimilationsproducte der Laubblätter angiospermer Pflanzen, *Bot. Zeitung*, **43**: 417-423, 433-440, 449-458, 465-472, 481-491, 497-507.
- , 1886: Bildung der Stärkekörner in den Laubblättern aus Zuckerarten, Mannit und Glycerin, *Bot. Zeitung*, **44**: 81-88, 105-113, 129-137, 145-151.
- , 1886: Ueber Stärkekörner, welche sich mit Jod roth färben, *Ber. d. d. bot. Ges.*, **4**: 337-362.
- , 1895: "Untersuchungen über die Stärkekörnerwesen und Lebensgeschichte der Stärkekörner der höheren Pflanzen," p. 318, Jena, Gustav Fischer.
- MILLER, E. C., 1917: Daily variation of water and dry matter in the leaves of corn and the sorghums, *Jour. Agr. Res.*, **10**: 11-47.
- , 1924: Daily variation of the carbohydrates in the leaves of corn and the sorghums, *Jour. Agr. Res.*, **27**: 785-808.
- , 1928: Unpub. data, *Kans. Agr. Expt. Sta.*

- MOILLARD, MARIN, 1912: L'humus est-il une source directe de carbone pour les plantes vertes supérieures? *Compt. Rend. Acad. Sci. Paris*, **154**: 291-294.
- MOLISCH, H., 1925: Carbon dioxide assimilation in dead leaves, *Zeits. f. Bot.*, **17**: 577-593; abstr. *Expt. Sta. Rec.* **57**: 118.
- MOLL, J. W., 1878: Ueber die Herkunft des Kohlenstoffs der Pflanzen, *Arb. bot. Inst. Würzburg*, **2**: 105-113.
- MOORE, B., and T. A. WEBSTER, 1918: Action of light rays on organic compounds and the photosynthesis of organic from inorganic compounds in presence of inorganic colloids, *Proc. Roy. Soc., B*, **90**: 168-186.
- MÜLLER, A., 1904: Die Assimilationsgrösse bei Zucker und Stärkeblättern, *Jahrb. f. wiss. Bot.*, **40**: 443-498.
- NÄGELI, CARL, 1858: "Die Stärkeköerner. Morphologische, physiologische, chemisch-physikalische und systematisch-botanische," monographie, p. 625, Zurich.
- NEF, J. U., 1913: Dissociationsvorgänge in der Zuckergruppe, *Ann. d. Chem.*, **403**: 204-383.
- NICHOLAS, E., and G. NICOLAS, 1922: Influence du formol sur les végétaux supérieurs, *Compt. Rend. Acad. Sci. Paris*, **175**: 1437-1439.
- O'SULLIVAN, C., 1872: On the transformation-products of starch, *Jour. Chem. Soc.*, **25**: 579-588.
- OSTERHOUT, W. J. V., 1915: Artificial photosynthesis by means of chlorophyll, *Science*, n.s., **42**: 68.
- , 1918: A simple method of demonstrating the production of aldehyde by chlorophyll and by aniline dyes in the presence of sunlight, *Amer. Jour. Bot.*, **5**: 511-513.
- and A. R. C. HAAS, 1918: On the dynamics of photosynthesis, *Jour. Gen. Phys.*, **1**: 1-16.
- and ———, 1918: Dynamical aspects of photosynthesis, *Proc. Nat. Acad. Sci.*, **4**: 85-91.
- , 1918: A demonstration of photosynthesis, *Amer. Jour. Bot.*, **5**: 105-111.
- and A. R. C. HAAS, 1918: A simple method of measuring photosynthesis, *Science*, n.s., **47**: 420-422.
- , 1919: Apparatus for the study of photosynthesis and respiration, *Bot. Gaz.*, **68**: 60-62.
- OWEN, O., 1923: Carbon dioxide in relation to glasshouse crops, *Ann. App. Biol.*, **10**: 312-317.
- and P. H. WILLIAMS, 1923: The preparation of an atmosphere rich in carbon dioxide, *Ann. App. Biol.*, **10**: 318-325.
- , T. SMALL, and P. H. WILLIAMS, 1926: Carbon dioxide in relation to glasshouse crops. Part III, The effect of enriched atmospheres on tomatoes and cucumbers, *Ann. App. Biol.*, **13**: 560-577.
- PALLADIN, V. I., 1922: "Plant Physiology," Eng. trans. B. E. Livingston, P. Blakiston's Son & Co. Philadelphia.
- PALLADIN, W., 1891: Ergrünen und Wachstum der etiolirten Blätter, *Ber. d. d. bot. Ges.*, **9**: 229-232.
- PANTANELLI, E., 1904: Abhängigkeit der Sauerstoffausscheidung belichteter Pflanzen von äusseren Bedingungen, *Jahrb. f. wiss. Bot.*, **39**: 167-228.
- PARKIN, J., 1912: The carbohydrates of the foliage leaf of the snow drop (*Galanthus nivalis*) and their bearing on the first sugar of photosynthesis, *Biochem. Jour.*, **6**: 1-47.
- , 1925: The first sugar of photosynthesis and the rôle of cane sugar in the plant. A reply to Professor J. H. Priestley, *New Phytol.*, **24**: 57-64.
- PERRY, A., 1882: Sur l'origin des matières sucrées dans la plante, *Compt. Rend. Acad. Sci. Paris*, **94**: 1124-1125.

- PFEFFER, W., 1871: Die Wirkung farbigen Lichtes auf die Zersetzung der Kohlensäure in Pflanzen, *Arb. bot. Inst. Würzburg*, **1**: 1-76.
- , 1900: "The Physiology of Plants," Eng. trans., Vol. I, Clarendon Press.
- PLAETZER, H., 1917: Untersuchungen über die Assimilation und Atmung von Wasserpflanzen, *Verhandl. Phys. med. Ges. Würzburg*, **45**: 31-102.
- PLESTER, W., 1912: Kohlensäureassimilation und Atmung bei varietäten derselben Art, die sich durch ihre Blattfärbung unterscheiden, *Beitr. Biol. Pflanzen*, **11**: 249-304.
- PRIESTLEY, J. H., 1924: The first sugar of photosynthesis and the rôle of cane sugar in the plant, *New Phytol.*, **23**: 255-264.
- PRIESTLEY, JOSEPH, 1774: "Experiments and Observations on Different Kinds of Air," 342 pp.
- POLLACCI, G., 1917: Carbon assimilation in green plants, *Atti. Inst. Bot. Univ. Pavia*, Ser. II, **17**: 29-51.
- , 1920: Sul carbonio delle piante verdi (the carbon of green plants), *Atti. Inst. Bot. Univ. Pavia*, Ser. II, **17**: 29-51; *Bot. Abst.*, **13**: 1212.
- PURIWITSCH, K., 1914: Untersuchungen über Photosynthese, *Jahrb. f. wiss. Bot.*, **53**: 210-254.
- REICHERT, E. T., 1913: The differentiation and specificity of starches in relation to genera, species, etc., *Carnegie Inst. Wash. Pub.* 173.
- , 1919: A biochemic basis for the study of problems of taxonomy, heredity, evolution, etc., with special reference to the starches and tissues of parent-stocks and hybrid-stocks and the starches and hemoglobins of varieties, species and genera, *Carnegie Inst. Wash. Pub.* 270, parts 1 and 2.
- RICHARDS, H. M., and D. T. MACDOUGAL, 1904: The influence of carbon monoxide and other gases upon plants, *Bull. Torrey Bot. Club*, **31**: 57-66.
- RIEDEL, F., 1919: Die Ausnützung der Hochofenabgase zur Kohlensäuredüngung, *Stahl. u. Eisen.*, **39**: 1497-1506.
- , 1921: Importance of carbon dioxide as a fertilizer for vegetables, *Gartenwelt*, **25**: 302-304; **34**: 336-338 (1921); abst. *Expt. Sta. Rec.* **45**: 834.
- RIPPEL, A., 1926: Kohlensäure und Pflanzenerzeugung, *Zeits. f. Pflanzennahrung und Düngung*, **5**: 49-64.
- SABALITSCHKA, T., and H. RIESENBERG, 1924: Über die Ernährung von Pflanzen mit Aldehyden. II, III, IV, *Biochem. Zeits.*, **144**: 545-550, 551-555; **145**: 373-378.
- , and H. WEIDLING, 1926: Polymerisation des Formaldehyds durch *Elodea canadensis* zu höheren Kohlenhydraten, *Biochem. Zeits.*, **172**: 45-57.
- SACHS, J., 1862: Über den Einfluss des Lichtes auf die Bildung des Amylums in den Chlorophyllkörnern, *Bot. Zeitung*, **20**: 365-373.
- , 1864: Über die Auflösung und Wiederbildung des Amylums in den Chlorophyllkörnern bei wechselnder Beleuchtung, *Bot. Zeitung*, **22**: 289-294.
- , 1884: Ein Beitrag zur Kenntniss der Ernährungsthätigkeit der Blätter, *Arbeiten bot. Inst. in Würzburg*, **3**: 1-33.
- SAMEC, M., and H. HAERDTL, 1920: Studien über Pflanzenkolloide. IX, Zur Kenntniss verschiedener Stärkearten, *Kolloid Chem. Beih.*, **12**: 281-300.
- SAPOSCHINKOFF, W., 1890: Bildung und Wanderung der Kohlenhydrate in den Laubblättern, *Ber. d. d. bot. Ges.*, **8**: 233-242.
- , 1891: Ueber die Grenzen der Anhäufung der Kohlenhydrate in den Blättern der Weinrebe und anderer Pflanzen, *Ber. d. d. bot. Ges.*, **9**: 293-300.
- , 1893: Beitrag zur Kenntniss der Grenzen der Anhäufung von Kohlenhydraten in den Blättern, *Ber. d. d. bot. Ges.*, **11**: 391-393.
- SAUSSURE, NICOLAS THÉODORE DE, 1804: "Recherches chimiques sur la végétation," Paris.

- SAYRE, J. D., 1928: The development of chlorophyll in seedlings in different ranges of wave lengths of light, *Plant Physiol.*, **3**: 71-77.
- SCHERTZ, F. M., 1921: A chemical and physiological study of mottling of leaves, *Bot. Gaz.*, **71**: 81-130.
- , 1925: Some physical and chemical properties of carotin and the preparation of the pure pigment, *Jour. Agr. Res.*, **30**: 469-475.
- , 1925: Some physical and chemical properties of xanthophyll and the preparation of the pure pigment, *Jour. Agr. Res.*, **30**: 575-587.
- , 1928: The preparation of chlorophyll, *Plant Physiol.*, **3**: 487-499.
- , 1928: The extraction and separation of chlorophyll (a and b), carotin and xanthophyll in fresh green leaves, preliminary to their quantitative determination, *Plant Physiol.*, **3**: 211-216.
- , 1928: The quantitative determination of chlorophyll, *Plant Physiol.*, **3**: 323-334.
- , 1928: The chloroplast pigments, their functions and the probable relation of chlorophyll to the vitamins, *Quart. Rev. Biol.*, **3**: 459-485.
- SCHIMPER, A. F. W., 1880: Untersuchungen über die Entstehung der Stärkekörner, *Bot. Zeitung* **38**: 881-902.
- , 1881: Untersuchungen über das Wachstum der Stärkekörner, *Bot. Zeitung*, **39**: 185-194, 201-211, 217-227.
- , 1885: Über die Bildung und Wanderung der Kohlenhydrate in den Laubblättern, *Bot. Zeitung*, **43**: 737-743, 753-763, 769-787.
- SCHROEDER, H., and T. HORN, 1922: Das gegenseitige Mengenverhältnis der Kohlenhydrate im Laubblatt in seiner Abhängigkeit vom Wassergehalt, *Biochem. Zeits.*, **130**: 165-198.
- SCHRYVER, L. B., 1909: The photochemical formation of formaldehyde in green plants, *Proc. Roy. Soc.*, B, **82**: 226-232.
- SCHRYVER, S. B., and E. M. THOMAS, 1923: The hemicelluloses. II, The hemicellulose content of starches, *Biochem. Jour.*, **17**: 497-500.
- SENEBIER, JEAN, 1800: "Physiologie végétale," Geneva.
- SHOHL, A. T., 1923: Analysis of the Jerusalem artichoke, *Jour. Amer. Chem. Soc.*, **45**: 2754-2756.
- SIEGFRIED, M., 1905: Über die Bindung von Kohlensäure durch amphotere Amidokörper, *Zeits. f. physiol. Chem.*, **44**: 85-96.
- SMITH, A. M., 1919: The temperature-coefficient of photosynthesis—a reply to a criticism, *Ann. Bot.*, **33**: 517-536.
- SPIRGATIS, P., 1923: The growth factor carbon dioxide, *Bot. Arch.*, **4**: 381-403; *Expt. Sta. Rec.* **52**: 424.
- SPOEHR, H. A., 1913: Photochemische Vorgänge bei der diurnalen Entsäuerung der Succulenten, *Biochem. Zeits.*, **57**: 95-111.
- , 1916: Theories of photosynthesis in the light of some new facts, *Plant World*, **19**: 1-16.
- , 1917: The pentose sugars in plant metabolism, *Plant World*, **20**: 365-379.
- , 1919: The carbohydrate economy of cacti, *Carnegie Inst. Wash. Pub.* **287**.
- , 1919: The development of conceptions of photosynthesis since Ingen-Housz, *Sci. Monthly*, **9**: 32-47.
- , 1922: Photosynthesis and the possible use of solar energy, *Jour. Ind. Eng. Chem.*, **14**: 1142-1145.
- , 1923: The reduction of carbon dioxide by ultraviolet light, *Jour. Amer. Chem. Soc.*, **45**: 1184-1187.
- and J. M. MCGEE, 1923: Studies in plant respiration and photosynthesis, *Carnegie Inst. Wash. Pub.* **325**.

- SPOEHR, H. A., and J. M. MCGEE, 1924: Investigations in photosynthesis. An electrometric method of determining CO₂, *Jour. Ind. Eng. Chem.*, **16**: 128-130.
- and ———, 1924: The effect of fluctuations in the CO₂ content of the atmosphere and the rate of respiration of leaves, *Amer. Jour. Bot.*, **11**: 493-502.
- and ———, 1924: Absorption of carbon dioxide the first step in photosynthesis, *Science*, n.s., **59**: 513-514.
- , 1926: "Photosynthesis," 393 pp., *Chem. Catalog Co.*, New York.
- SPONSLER, O. L., 1922: The structure of the starch grain, *Amer. Jour. Bot.*, **9**: 471-492.
- , 1923: Structural units of starch determined by x-ray crystal structure method, *Jour. Gen. Physiol.*, **5**: 757-777.
- STANESCU, P. P., 1924: Les variations quantitatives de l'amidon dans les feuilles des plantes vertes pendant une journée (24 heures), *Compt. Rend. Acad. Sci. Paris*, **178**: 117-119.
- , 1927: Contributions à l'étude de la photosynthèse, *Ann. Scien. de l'Université de Jassy*, **15**: 161-212.
- , 1927: "Les variations quantitatives des produits de la photosynthèse dans les feuilles des plantes vertes pendant un jour (24 heures)," thèse, Bucarest.
- STILES, WALTER, 1925: "Photosynthesis—The Assimilation of Carbon by Green Plants," 268 pp., Longmans, Green and Co.
- STOCKLASA, J., and W. ZDOBNICKY, 1911: Ueber photochemische Synthese der Kohlenhydrate aus CO₂ und H₂ in Anwesenheit von KOH und in Abwesenheit von Chlorophyll, *Monatsh. f. Chem.*, **32**: 53-75.
- and ———, 1912: Ueber die photochemische Synthese der Kohlenhydrate unter Einwirkung der Ultravioletten Strahlen, *Biochem. Zeits.*, **41**: 333-372.
- TAMMANN, G., 1892: Die Reactionen der ungeformten Fermente, *Zeits. f. physiol. Chem.*, **16**: 271-328.
- , 1895: Zur Wirkung ungeformter Fermente, *Zeits. f. physikal. Chem.*, **18**: 426-442.
- TAYLOR, T. C., and J. M. NELSON, 1920: Fat associated with starch, *Jour. Amer. Chem. Soc.*, **42**: 1726-1738.
- THATCHER, R. W., 1921: "The Chemistry of Plant Life," 268 pp., McGraw Hill Book Company, Inc.
- THODAY, D., 1909: Experimental researches on vegetable assimilation and respiration. V, A critical examination of Sachs-method for using increase of dry weight as a measure of carbon dioxide assimilation in leaves, *Proc. Roy. Soc.*, B, **82**: 1-56.
- , 1910: Experimental researches on vegetable assimilation and respiration. VI, Some experiments on assimilation in the open air, *Proc. Roy. Soc.*, B, **82**: 421-450.
- THOMAS, A. W., 1915: The chemical constitution of starch. A review, *Biochem. Bull.* **4**: 379-397.
- TIMIRIAZEFF, C., 1890: Enregistrement photographique de la fonction chlorophyllienne par la plante vivante, *Compt. Rend. Acad. Sci. Paris*, **110**: 1346-1347.
- , 1905: The cosmical function of the green plant, *Proc. Roy. Soc.*, **72**: 424-461.
- TRANSEAU, E. N., 1926: The accumulation of energy by plants, *Ohio Jour. Sci.*, **26**: 1-11.
- TSWEET, M. S., 1910: "Chromophylls in the Plant and Animal Worlds" (Russian), Warsaw. 379 pp., *Abst. Expt. Sta. Rec.*, **26**: 710.
- , 1911: Eine Hypothese über den Mechanismus der photosynthetischen Energieübertragung, *Zeits. f. phys. Chem.*, **76**: 413-419.
- URSPRUNG, A., 1917: Über die Stärkebildung im Spektrum, *Ber. d. d. bot. Ges.*, **35**: 44-69.

- URSPRUNG, A., 1918: Über die Absorptionskurve des grünen Farbstoffes lebender Blätter, *Ber. d. d. bot. Ges.*, **36**: 73-85.
- , 1918: Ueber die Bedeutung der Wellenlänge für die Stärkebildung, *Ber. d. d. bot. Ges.*, **36**: 86-100.
- USHER, F. L., and J. H. PRIESTLEY, 1906: The mechanism of carbon assimilation in green plants: the photolytic decomposition of carbon dioxide *in vitro*, *Proc. Roy. Soc. B*, **78**: 318-327.
- and ———, 1906: A study of the mechanism of carbon assimilation in green plants, *Proc. Roy. Soc.*, **B**, **77**: 369-376.
- and ———, 1911: The mechanism of carbon assimilation. III, *Proc. Roy. Soc.*, **B**, **84**: 101-112.
- VER HULST, J. H., W. H. PETERSON, and E. B. FRED, 1923: Distribution of pentosans in the corn plant at different stages of growth, *Jour. Agr. Res.*, **23**: 655-665.
- VILLE, G., 1889: Recherches sur les relations qui existent entre la couleur des plantes et la rich esse des terres en agents de fertilité, *Compt. Rend. Acad. Sci. Paris*, **109**: 397-400.
- WAGER, H., 1914: The action of light on chlorophyll, *Proc. Roy. Soc.*, **B**, **87**: 386-407.
- WARBURG, O., 1919: Über die Geschwindigkeit der photochemischen Köhlensäurezer- setzung in lebenden Zellen. I, *Biochem. Zeits.*, **100**: 230-270.
- and E. NEGELEIN, 1923: Über den Einfluss der Wellenlänge auf den Energie- umsatz bei der Kohlensäureassimilation, *Zeits. f. phys. Chem.*, **106**: 191-218.
- , 1925: Versuche über die Assimilation der Kohlensäure, *Biochem. Zeits.*, **166**: 386-406.
- WARNER, C. H., 1914: Formaldehyde as an oxidation product of chlorophyll extracts, *Proc. Roy. Soc.*, **B**, **87**: 378-386.
- WEATHERWAX, PAUL, 1922: A rare carbohydrate in waxy maize, *Genetics*, **7**: 568-572.
- WEBER, C., 1879: Ueber spezifische Assimilationsenergie, *Arb. Bot. Inst. Würzburg*, **2**: 346-352.
- WEEVERS, T., 1923: The first carbohydrates that originate during the assimilatory process. A physiological study with variegated leaves. *Koninklyke Akad. von Wetensch. 6, Amsterdam Proc.* **27**: 1-11, Eng. summary.
- WIESNER, J., 1874: Untersuchungen über die Beziehungen des Lichtes zum Chloro- phyll, *Sitzungsber. d. k. Akad. d. Wiss. Wien*, **69**: 327-385.
- , 1877: "Die Entstehung des Chlorophylls in der Pflanze," Wien.
- WILLAMAN, J. J., 1922: The preparation of inulin, with special reference to artichoke tubers as a source, *Jour. Biol. Chem.*, **51**: 275-285.
- WILLSTÄTTER, R., and A. STOLL, 1918: "Untersuchungen über die Assimilation der Kohlensäure," Berlin, Julius Springer.
- and ———, 1928: "Investigations on Chlorophyll. Methods and Results," Eng. trans. by F. M. Schertz and A. R. Merz, 380 pp., Lancaster, Pa., Science Press.
- WINKLER, H., 1898: Über die Stärkebildung in den verschiedenartigen Chromato- phoren, *Jahrb. f. wiss. Bot.*, **32**: 525.
- WURMSER, RENÉ, 1925: Sur l'activité des diverses radiations dans la photosynthèses. *Compt. Rend. Acad. Sci. Paris*, **181**: 374-376.
- YAP, G. G., 1920: A study of the photosynthesis of sugar cane, *Philippine Agr.*, **8**: 269-276.
- YUNCKER, T. G., 1916: A study of the relation of soil moisture to transpiration and photosynthesis in the corn plant, *Plant World*, **19**: 151-161.
- ZIRKLE, CONWAY, 1926: The structure of the chloroplast in certain higher plants. I, II, *Amer. Jour. Bot.*, **13**: 301-341.

CHAPTER IX

THE NITROGEN METABOLISM OF THE GREEN PLANT

I. OCCURRENCE OF NITROGEN IN THE PLANT

Nitrogen enters into the structure of chlorophyll, the amino acids, alkaloids, protein, and the protoplasm of the plant. It occurs for the most part in organic combination, and, as will be noted in a subsequent heading, ammonia, nitrates, and nitrites are found, as a rule, only in traces if at all. The percentage of nitrogen in the various plant parts will vary with the age, type of tissue, and the kind of plant as well as with the period of the day when the examination is made. In the case of the corn plant at the period of the late milk stage when the grain was glazed and dented (Latshaw and Miller, 1924), the leaves contained 25 per cent of the total nitrogen in the plant, the stem 14 per cent, the grain 46 per cent, the cobs 9 per cent, and the roots 6 per cent. The nitrogen content of the dry weight of the leaves varied from 1.2 to 1.4 per cent, of the stem from 0.5 to 1.0 per cent, and of the grain from 2 to 2.2 per cent. Miller (1929) observed the nitrogen content of various leaves when the plants were in a vigorous vegetative condition previous to blooming. The average nitrogen content for different periods of the day was for soybeans 5.8 per cent, for cowpeas 5.6 per cent, for garden beans 4.5 per cent, for pumpkin 4.5 per cent, for feterita 3.6 to 4.1 per cent, for kafir 3.6 to 4.2 per cent, and for corn 3.2 to 3.8 per cent of the dry weight of these leaves.

In the absence of nitrogen the leaves are stunted in growth, and a yellowing of the foliage takes place. A large amount of nitrogen in the soil produces a rank growth of foliage, giving an inordinate proportion of stem and leaves, but retards the ripening process. If the plants can be grown to maturity, the excess foliage has no apparent effect on the yield. Frequently, however, under such conditions, ripening occurs prematurely due to various causes, so that considerable amounts of food materials are left in the leaves and not transferred to the seed or grain. In such cases, shriveled grain is the result. Plants, as cabbage and lettuce, which are grown solely for their leaves are benefited by an abundant supply of nitrogen, although the tissues do not remain firm (Thatcher, 1921).

II. SOURCES OF NITROGEN SUPPLY OF PLANT

The possible sources of the nitrogen supply of the plant are the various nitrogenous compounds in the soil and the combined and elemental

nitrogen of the atmosphere. The absorption of the nitrogenous compounds of the soil will first be considered.

A. ABSORPTION FROM THE SOIL

The combined nitrogen in the soil exists in the form of inorganic and organic compounds. The former are principally the nitrates, nitrites, and ammonium salts, while the latter include a long list of the decomposition products of the proteins, protoplasm, and other complex nitrogenous substances of plants and animals. A partial list of the various organic nitrogenous compounds that have been found in the soil is given in Chap. III.

1. Inorganic Nitrogen.—Early in the history of plant nutrition it became generally accepted that plants, in general, absorb the combined inorganic nitrogen preferably in the form of nitrates. In some cases, however, plants apparently did equally well when nitrogen was applied to the soil in the form of ammonium salts. Since these experiments were not made under sterile conditions, it is not definitely known whether the ammonium salts were absorbed as such or not. Since 1889, however, a considerable amount of work has been done, apparently under sterile conditions, to determine the relative value of nitrates and ammonium salts in plant nutrition.

Müntz (1889), Pitsch (1887 to 1896), Griffiths (1891), and Gerlach and Vogel (1905) worked with soils under apparently sterile conditions and showed that beans, barley, hemp, and corn were able to grow in the absence of nitrates, but they did not prove conclusively that ammonium salts were the sole source of the nitrogen obtained by the plants. According to Treboux (1904), *Lemna minor*, moss, diatoms, and certain green algae used by him utilized effectively ammonium nitrogen. Krüger (1905) concluded that ammonium salts and nitrates are equally suitable for mustard, oats, and barley and that, if anything, ammonium salts are better than nitrates for potatoes, while for beets nitrates are superior to ammonium salts. It has been shown by Mazé (1898, 1900) and Prianischnikow (1909, 1923) that corn can utilize ammonium salts as readily as nitrates, while Brigham (1917) concluded that ammonium sulphate is a much better source of nitrogen than sodium nitrate. In the case of sugar cane, McGeorge (1923) concluded that this plant will not grow without some nitrate nitrogen. The cane in an ammoniacal nutrient solution sent out strong, vigorous shoots, but practically no root development took place, while an excellent growth of both roots and tops occurred in a solution containing nitrates. Stewart (1925) and others found that the pineapple plant is capable of assimilating all its nitrogen in the form of ammonium salts, although the best growth of plants was made by those growing in solutions in which the nitrogen was present in the form of nitrates. The indications were that both nitrates

and ammoniacal nitrogen can be utilized by these plants. The relative value of ammonium salts and nitrates in the nutrition of wheat and peas was observed by Hutchinson and Miller (1909), who grew these plants in sand and water cultures and found that ammonium sulphate was assimilated by them directly and that in the case of peas there was no difference between the plants supplied with ammonium and those that had sodium nitrate. Wheat plants showed a decided preference for nitrogen in the form of nitrates. It seems to be definitely established that agricultural plants of various kinds can produce normal growth when supplied with nitrogen in the form of ammonium salts under conditions which exclude nitrification. In experiments with wheat, rice, flax, and corn grown in nutrient solutions under conditions which preclude nitrification Pantanelli and Severini (1910, 1911) concluded that ammonium salts have a higher coefficient of utilization than nitrate salts if both ions of the ammonium compound can be utilized by the plant at approximately the same rate.

The nitrogen nutrition of rice has been studied by numerous investigators and they all report that, under some conditions at least, the ammonium salts are superior to the nitrates in the growth of this plant. Kellner (1884) noted that swamp rice, in pots, during its early development grew better with ammonium salts than with nitrates but that during later growth nitrates proved the more effective. He also showed that the formation of nitrates in paddy soils took place slowly, while ammonia was formed in large quantities. Kelley (1911) applied ammonium sulphate to some rice plants and sodium nitrate to others. The application of the former was followed by an increase in the yield of straw and grain, but sodium nitrate was ineffective. In sand cultures unhealthy and stunted plants resulted if nitrates were used as the only source of combined nitrogen, while the use of ammonium salts resulted in vigorous apparently normal plants. The same beneficial returns from ammonium salts in contrast to nitrates have also been obtained by Nagaoka (1904), Daikuhara (1905), Espino (1920), and Trelease and Paulino (1920).

In conclusion, therefore, it may be stated that the evidence indicates that some plants grow equally well with both nitrates and ammonium salts and that others, although assimilating ammonium nitrogen in the absence of nitrates, seem to prefer nitrates.

Numerous explanations have been proposed to explain the fact that many plants respond better to nitrates than to ammonium salts. By some it is considered that the basic ions combined with the nitrates may exert a stimulating effect while the acid ion of the ammonium salt may be injurious to certain plants. It is also considered that nitrates may be more available than the ammonium salts, since the former are very soluble and not fixed, while the latter salts are fixed and held more firmly and do not circulate so freely in the soil. On that account the ammonium salts

do not come in contact with the root hair to the same extent that the nitrates do and hence are not so readily absorbed by the plant. It has been suggested by Willis and Carrero (1923) that the observation that nitrates are less suitable than ammonium salts for the fertilization of young rice plants may be based on the influence on the plants of the residues of the fertilizer used rather than on the inferiority of nitric nitrogen as a nutrient. They considered that under the conditions under which they worked in Porto Rico the injury noted, which has generally been ascribed to the toxic effects of the nitrites derived from nitrates by reduction, was a manifestation of chlorosis caused by the action of the basic residues of the nitrate salts used as nutrients. Furthermore, the nitrogen of calcium nitrate may be equally suitable with that of ammonium sulphate in the physiological processes of the rice plant when it is used under cultural conditions in which the reaction of the unassimilated residue of the nitrate does not interfere with the absorption and utilization of iron.

The few observations concerning the absorption of nitrites might well be mentioned here. It was observed by Schultz (1903) that in dilute solutions, nitrites seemed to be more readily absorbed by plants than the nitrates. In some cases (Stutzer, 1907), a dilute solution of nitrites seems to be beneficial to some plants while it is injurious to others. More concentrated solutions of nitrites are always more toxic to plants than the same strength of solutions of nitrates.

It has been observed by Prianischnikow (1909, 1923) and Shulvo (1912) that plants which take up nitrogen exclusively as ammonium salts generally contain very distinctly higher percentages of nitrogen than when supplied with nitrates. The same fact has also been observed by Perciabosco and Rosso (1909) when nitrite compounds were supplied.

Kinoshita (1894 to 1897) grew seedlings of various plants for short periods in solutions of ammonium salts and sodium nitrate in order to compare the amounts of asparagin produced. He found that the ammonium salts were rapidly converted into asparagin, while nitrates tended to accumulate and during the short time of the experiment generally failed to increase the amount of asparagin. The production of asparagin was promoted by the presence of sugar, and in its absence or that of other suitable material it was found that ammonia accumulated in the plants and eventually caused injury. These observations seem to indicate that the nitrogen in the ammonium compounds is in a form that can be utilized more readily by the plant in the formation of protein compounds than the nitrogen of the nitrates.

2. Organic Nitrogen.—Previous to 1911 considerable experimental work had been done with the nutrition of plants with organic nitrogenous compounds, but the value of much of the data presented is uncertain, since in many cases the plants were not grown under conditions that would prevent bacterial action. More or less satisfactory evidence of the

assimilation of organic nitrogenous compounds by green plants had been obtained for the following compounds: methyl, amyl and allyl amines, acetamide, leucine, urea, aspartic acid, asparagine, glutamine, uric acid, hippuric acid, and tyrosine. The gains of nitrogen, however, were very small, and in many cases negative results were obtained by other investigators. The reader is referred to Hutchinson and Miller (1911) for a thorough and detailed review of the literature on the subject previous to this date. They grew wheat and peas in cultural solutions under sterile conditions. The ordinary nutrient solutions were used with organic substances as a source of nitrogen. They found that these plants could assimilate acetamide, urea, barbaturic acid, alloxan, formamide, glycine, amino propionic acid, oxamide, sodium aspartate, and peptone.

Under sterile conditions where no reduction of nitrogenous compounds to nitrites or nitrates took place, Schreiner and Skinner (1912) reported that the following compounds entered the plant and reacted with the protoplasm in building up plant protein: nucleic acid, hypoxanthine, xanthine, guanine, creatinine, creatine, histidine, arginine, alloxan, asparagin, leucine, glycocoll, and others. Brigham (1917) found that corn could directly assimilate and use some of the nitrogen in asparagine, casein, cottonseed meal, hemoglobin, linseed meal, uric acid, peptone, guanine, alanine, urea, creatine, malt, and glycocoll. Eight of these substances which were directly available to the plant produced better growth when acted upon by *B. subtilis*, probably because of ammonification. These were peptone, guanine, alanine, linseed meal, cottonseed meal, casein, hemoglobin, and urea. Ciamician and Ravenna (1919 to 1920) have reported the effect of a large number of the more uncommon organic nitrogenous compounds on plants. Crowther (1925) found that wheat and white mustard could obtain nitrogen from various organic compounds among which were dried blood, peptone, amino acetic acid, oxamide, and pyridine. Coville (1926) in preliminary experiments noted that buttermilk applied to young blueberry plants increased their height 32 to 37 per cent besides increasing the general appearance of their vigor. Skimmed milk when applied to the soil gave better results than buttermilk, due perhaps to the fact that the sweet milk penetrated the soil more thoroughly. Azaleas also responded to treatment in much the same manner as the blueberry plants. The indications are that casein is the most active fertilizer of any of the derivatives of the buttermilk and skimmed milk used in the experiments.

It has been considered by some that small amounts of organic nitrogenous compounds exert an accelerating action upon the growth of certain plants somewhat after the manner of auximones or vitamins. Thus Bottomley (1917 to 1920) observed that the growth of the water plants *Lemna minor*, *Salvinia natans*, *Azolla filiculoides*, and *Limnobium stoloniferum* in Detmer's solution was greatly accelerated by the addition

of various amounts of extract from partially decayed peat and other vegetable matter. In one case where the addition of this organic material amounted to 368 ppm. after 6 weeks, the treated plants of *Lemna minor* showed a multiplication to twenty times and an increase in weight to sixty-two times that of the plants growing in the water containing mineral salts only. An examination of the pond water in which the plants grew vigorously showed 1,577 ppm. of dissolved solids of which 488 ppm. were organic material. The inference was that in their natural habitat these plants utilize a certain portion of these organic nitrogenous compounds in their metabolism. The extracts from the partially decayed peat were proved to be derivatives of nucleic acid. Bottomley found that the nitrogen-fixing bacteria have the power of elaborating products from carbohydrate and elementary nitrogen which also greatly increase the growth of *Lemna* plants.

Mockeridge (1917, 1924) investigated the effect of varying quantities of nucleic acid derivatives on the growth of plants of *Lemna minor* and found that although the effect obtained was approximately proportional to the quantity of material supplied, it was not directly proportional to it. The growth of these plants was also accelerated by the addition of sterilized cultures of *Azotobacter* to the medium in which they were growing. Since yeast was found to have plant-growth promoting power on *Lemna minor* and since it contains nucleic acid radicals, the *Azotobacter* were examined for traces of these constituents. Purine and pyrimidine bases, phosphoric acid, and a carbohydrate were all shown to be present, and since all the necessary radicals for the formation of nucleic acid were thus isolated, it was concluded that the beneficial action on the growth of *Lemna minor* by sterilized cultures of *Azotobacter* was due to these organic substances.

Clarke and Roller (1924) and Clarke (1924), however, concluded that the growth of *Lemna minor* in mineral solutions depends upon the suitable concentration of salts and that organic matter (auximones) is not essential for growth and reproduction and cannot be classed with vitamins which are necessary for animal growth. Saeger (1925) and Wolfe (1926) in experiments with plants closely related to those used by Bottomley reported that such plants will grow and reproduce in both Detmer's and Knop's solutions which are properly diluted or balanced. In some cases the addition of organic compounds slightly accelerated the growth and in others it depressed it. They considered that the necessity of organic accessories (auximones) in the nutrition of green plants can thus not be accepted as an established fact.

The studies of the effect of organic nitrogenous compounds on the nutrition of green plants seem to indicate that they can supplement but only in a few cases replace the inorganic nitrogenous salts. The experimental work would seem to show at least that green plants growing in a

heavily manured soil in the field or in a rich compost as frequently used in greenhouses can absorb directly and utilize in their metabolism larger or smaller amounts of complex organic nitrogenous compounds. The value of small amounts of organic nitrogen in the rôle of auximones or vitamins, however, is a disputed question and no conclusions can be drawn from the limited experimental data on the subject.

B. ABSORPTION FROM THE AIR

About 80 per cent of the atmosphere is composed of nitrogen in the elemental form. There are also present small quantities of nitrogen in the form of ammonia, nitrates, and nitrites. Rainfall and snow thus contain nitrogen in this form taken up in their passage through the atmosphere. Russell and Richards (1919) over a period of 28 years at Rothamsted found that with an average rainfall of 28.82 in. the ammoniacal content amounted annually to 2.64 lb. per acre, while the nitric nitrogen was about one-half as much or 1.33 lb. per acre. It was observed by Wilson (1921) at Ithaca, N. Y., that with an average yearly rainfall of 29.31 in. from May, 1915, to May, 1920, 12.51 lb. of nitrogen per acre were brought down annually. Of this amount 11.5 lb. was in the form of ammoniacal nitrogen, while 1.01 lb. was in the form of nitrate nitrogen. There is, however, considerable doubt as to what extent the green plant can absorb this free and combined nitrogen of the atmosphere. A historical résumé of the early work in this regard is essential in order to appreciate the general opinion which prevails at this time in regard to the subject.

1. Historical.—De Saussure (1804) considered that the plants with which he worked did not take up appreciable quantities of the nitrogen supplied to them in the free and gaseous form. He believed that the source of the nitrogen of plants is more probably the nitrogenous compounds of the soil and the small amount of ammonia which he demonstrated to exist in the atmosphere. In 1837 Boussingault took up the question of the source of the nitrogen of plants where De Saussure had left it more than 30 years before and for 20 years carried on experiments with a large variety of plants to determine if any of these absorbed free nitrogen. His conclusions were that neither leguminous nor non-leguminous plants were able, either when their supplies of combined nitrogen were limited to that contained in the seed sown or when their vigor of growth was stimulated by artificial supplies of combined nitrogen, to assimilate the free or uncombined nitrogen of the atmosphere. Ville, a French contemporary of Boussingault, however, in his works published from 1849 to 1857, reported results that are exactly the opposite of those obtained by the latter. He found that the plants in his experiments showed a very considerable gain of nitrogen during growth whether they

were subjected to a current of unwashed air or to one of ammonia-free air and also when the plants were grown in free air and their activity of development increased by the use of nitrates or other nitrogenous matters as manure. This gain of nitrogen he considered to be due to the assimilation of free or uncombined nitrogen of the air.

Lawes, Gilbert, and Pugh in 1860 published the results of their experiments at Rothamsted (1857 to 1859) in which they grew grain plants both with and without a supply of combined nitrogen other than that contained in the seed sown. From these experiments, which were conducted over a wide range of conditions, character, and amount of growth and in the amount of combined nitrogen involved, they concluded that in no case was there any evidence of the assimilation of uncombined nitrogen. Their results of similar experiments with leguminous plants indicated that no assimilation of free nitrogen by the plants occurred. They concluded, however, that since in practice leguminous plants assimilate from some source so much more nitrogen than grain plants under equal circumstances of combined nitrogen, it would be desirable if the evidence of further experiments with these plants under conditions of more healthy growth could be obtained. Their inference in this regard was correct, since it was shown later that they had sacrificed in their attempt for accuracy the conditions that are necessary for the symbiotic relationship of bacteria and the roots of the legumes. Finally, in 1888 Hellriegel and Wilfarth published the results of their classical work on the nitrogenous nutrition of legumes. They observed that legumes differ fundamentally from the grains in their nutrition with respect to nitrogen. The latter can satisfy their nitrogen need only by means of assimilable combinations existing in the soil, while the former in addition to the nitrogen of the soil have at their service a second source upon which they draw for nitrogen and this source is the elementary nitrogen of the atmosphere. They further stated that the legumes do not possess by themselves the faculty of assimilating the free nitrogen from the air but that it is necessary that certain microorganisms of the soil enter into a symbiotic relationship with the plants in order to secure this result. Beyerinck (1888) and Prazmowski (1890) were able to secure pure cultures of the tubercle bacteria and gave to it the name of *B. radicolica*. Thus by the work of these four investigators the relationship of the legumes in regard to their nitrogen supply was placed upon a basis that is now universally accepted.

2. Non-leguminous Plants.—Although it is commonly considered that the non-leguminous plants cannot utilize the free nitrogen of the atmosphere, considerable work has recently been done to investigate the validity of this assumption. Recently Lipman and Taylor (1922, 1924) have called attention to the fact that the assumption that non-leguminous plants cannot assimilate free nitrogen is based almost exclusively upon the

work of Boussingault (1854 to 1855) in which he claimed that neither the leguminous nor non-leguminous plants could assimilate free nitrogen. They further pointed out that the work of Ville (1853 to 1857), which indicated that all plants could utilize free nitrogen, has been entirely overlooked.

a. The Algae.—Since numerous blue-green and green algae inhabit the soil and since some of these resemble the bacteria in their morphology or are closely related to the fungi in their structure, it has been thought that they might fix free nitrogen and thus be an important factor in the nitrogen relations of the soil and the higher plants. Accordingly a considerable amount of experimental work has been done to determine whether these plants possess the power to fix free nitrogen.

Frank (1888 to 1889) obtained positive results for the blue-green algae *Nostoc* and *Gloeo capsa*, but his experiments were not performed under sterile conditions. Kossowitch (1894) was the first to use pure cultures of algae in this type of work. He used *Cystococcus* and showed clearly that under sterile conditions this alga could not fix free nitrogen either in the absence or in the presence of glucose. Schramm (1914) worked with seven species of the green algae and found that in the absence of combined nitrogen no growth took place, so he concluded that these algae could not under these conditions assimilate free nitrogen. Similar results were also obtained by Muenscher (1923) for *Chlorella*. Wann (1920 to 1921) obtained experimental results which led him to conclude that seven species of the green algae (*Chlorophyceae*) exhibited the ability to fix free nitrogen when grown in pure cultures on mineral nutrient agar media containing either ammonium nitrate or calcium nitrate as a source of nitrogen and glucose. The work of Wann was repeated by Bristol and Page (1923), who showed that his data were not correct due to the faults of the methods of nitrogen determination that he used.

Moore and others (1920 to 1921) concluded from their observations that in the absence of all other sources of nitrogen save the elemental nitrogen of the atmosphere, but with an abundance of carbon dioxide, fresh-water unicellular algae can fix nitrogen, grow, and form proteins. The rate of growth is greatly accelerated, however, if nitrates or oxides of nitrogen are available. They considered that the green seaweed (*Enteromorpha compressus*) can fix elemental nitrogen from sea water in the presence of sunlight but not in darkness, and thus indirectly from the air. Their results are open to criticism, since they did not work with sterile cultures and depended only on the turbidity of the water as an indicator of the presence of bacteria. The results of all the experimental work thus indicate that the algae examined cannot fix free nitrogen, and we must conclude, in the words of Bristol and Paige (1923): "It is conceivable that green algae might assimilate atmospheric nitrogen under certain conditions, as yet unknown, but at present there is no trustworthy evidence that they can do so."

b. The Higher Non-leguminous Plants.—The ability of the higher green non-leguminous plants to fix atmospheric nitrogen has been investigated recently by several investigators.

Mameli de Calvino and Pollacci (1911 to 1923) worked with a wide range of plants in relation to their source of nitrogen. The plants used included lichens, mosses, and aquatic and terrestrial phanerogams and were grown under the best known conditions to overcome incomplete sterilization of culture, error due to presence of nitrogen compounds in the air, and incomplete development of the plants. Their data showed that all the plants tested had taken up nitrogen in greater or lesser quantities from the air in which respiration and assimilation took place and that more free nitrogen was taken from the air when the culture medium was supplied with small quantities of

nitrogen compounds. Some of the species of the higher plants which they claim can assimilate some free nitrogen directly from the air without the aid of symbiotic microorganisms are *Raphanus sativus*, *Acer negundo*, *Cucurbita pepo*, and *Polygonum fagopyrum*.

Lipman and Taylor (1922, 1924) claim to have secured conclusive evidence from experiments carried on with wheat and barley in culture solutions with and without nitrate nitrogen that the cultures gained nitrogen at the expense of the elementary nitrogen of the atmosphere. They report in the case of wheat plants that there was a gain of nitrogen from the air which varied from 13 to 21 per cent of the total amount of nitrogen found in the plant. The cultures used by these investigators were not sterile, but they concluded that the small number of bacteria present and the low amount of organic matter in the cultures available for them could not account for the gains in nitrogen observed. Lipman and Taylor believed that the fixation of nitrogen occurs in the leaves of the plants. With the dwarf variety of *Pisum sativum*, however, under as nearly sterile conditions as could be obtained in nutrient solutions, Burk (1927) was unable to observe any fixation of nitrogen.

The results reported by Lipman and Taylor have been skeptically received. It would seem that if any nitrogen is fixed by the non-leguminous green plants it is very small in amount and is inconsequential when compared with that absorbed by the roots in the combined form. It has not been proved to the satisfaction of all that the fixation of nitrogen by the non-leguminous green plants so far reported has not been due to the action of bacteria, and according to Fisher (1917) it should be considered that where claims for nitrogen fixation are made a need exists for the proof that the technique was not in error.

The absorption by the aerial parts of the plant of the combined nitrogen in the air is considered by some (Moore, 1924) to be significant in the metabolism of the plant. He considered that nitrites may be absorbed in considerable quantities from rain and dew, since his experiments indicated that nitrite was present in these waters in amounts of 1 part per 10,000,000 to 2 parts in 1,000,000. These concentrations seem at first glance to be so extremely low that the nitrite would be of no nutritional value to the plant, but Moore points out that the demand of a plant for nitrogen is relatively small and that a concentration of nitrites or nitrates in the atmosphere or cell-sap equivalent to 1 part nitrogen to 120,000,000 parts water could supply a sufficient quantity for assimilative purposes.

III. THE PROTEINS OF THE GREEN PLANT

The proteins are complex organic substances composed of carbon, hydrogen, oxygen, and nitrogen, usually sulphur, and sometimes phosphorus and are compounds which, for the most part, yield alpha amino acids upon hydrolysis. The proteins occur in some form or another in every living plant or animal cell and are essential to all life processes, since they are the main constituents of the protoplasm. The proteins occur in plants in the dissolved state in the cell sap, in a semidissolved state in the protoplasm, and are stored in the insoluble form as reserves in the cells of seeds, tubers, bulbs, buds, roots, and other plant parts. The reserve proteins make up the major portion of the proteins found in plants and occur in the cells with non-nitrogenous reserves of carbohydrates and oils. The undissolved protein in plant cells may be in the

form of crystals, in the form of aleurone grains, and in the form of aleurone. Crystalline proteins are found in the seeds of flax, squash, cotton, sunflower, rape, mustard, peanuts, and in the potato tuber. The term "aleurone grain" is used in a broad sense to denote all non-crystalline protein bodies of a more or less definite shape, and Osborne (1924) states that the aleurone grain may be irregular, semicrystalline with faces and angles on a part of the surface or distorted spheres. The aleurone grains may be rather complicated in their structure, as in the case of those in the castor bean. These grains consist of an amorphous protein matrix in which is embedded a protein crystalloid and a globoid consisting of a




FIG. 29.—Section of a cell from the endosperm of the castor bean (*Ricinus communis*) showing the aleurone grains. *ag*, aleurone grain. *c*, crystal of protein. *a*, amorphous protein. *g*, globoid.

double phosphate of calcium and magnesium. The matrix and its inclusions are surrounded by an outer layer of protein which is not so readily soluble as the matrix (Fig. 29). The protein which occurs in plant cells in an amorphous, finely granular form is generally designated as "aleurone."

In the seeds of the grains and grasses the outermost layer of cells of the endosperm is termed the "aleurone layer." This layer is composed of short, prismatic, rather thin-walled cells and receives its name from the fact that these cells contain, for the most part, protein either as aleurone grains or in the amorphous form regardless of storage materials in the rest of the endosperm (Fig. 33).

A. PHYSICAL PROPERTIES

The proteins have no definite melting points or boiling points but carbonize on heating and give off gases. They are colloidal in character and thus when in solution do not pass through parchment, collodion, or other membranes. All the solutions of plant proteins are optically active, rotating the plane of polarized light to the left. The proteins differ widely as to their solubility in water and in salt solutions, and these differences in solubility are used as a basis for their classification. The proteins are insoluble in strong salt solutions and are precipitated out of their solutions without change in their composition by saturating the solution with various neutral salts as sodium chloride, ammonium sulphate, and magnesium sulphate. Dilution of such saturated solutions will cause the precipitated protein to redissolve. All of the natural proteins when in a colloidal solution may be coagulated by heat, alcohol, or enzymes, forming a semisolid gel which cannot again be rendered soluble except by decomposition.

B. CHEMICAL PROPERTIES

The average percentage of the elements which compose plant proteins is approximately as follows: carbon 52 per cent, oxygen 22 per cent, hydrogen 7 per cent, nitrogen 17 per cent, and sulphur about 0.6 per cent. Phosphorus is also present in certain proteins in small amounts. The percentages of carbon, hydrogen, and oxygen vary within comparatively narrow limits, but the sulphur content varies to a greater extent in the different proteins than any other of their constituent elements. Thus in legumin it amounts to only 0.385 per cent of the dry weight of the protein. Since it has been shown that many plant proteins yield cystine on hydrolysis, it is considered that in proteins much of the sulphur is in that form. By the present methods of determining cystine sulphur, however, the amount of sulphur in the proteins which cannot be accounted for by the cystine determinations ranges from 24 to 80 per cent.

The amount of nitrogen is very similar in many proteins. Thus from Osborne (1924) it is noted that the globulin from squash seed contains 18.5 per cent nitrogen, edestin from the hemp seed 18.7, excelsin from the Brazil nut 18.3, globulin from the cotton seed 18.6, and legumin from peas 18.0 per cent. Of the more than 20 plant proteins mentioned by Osborne (1924) the nitrogen content ranges from 15.9 per cent for the legumin of the horse bean to 19.0 per cent for corylin of the hazelnut. In general, it may be stated that the proteins from plants contain from 2 to 3 per cent more nitrogen than the animal proteins.

The molecule even of the most simple protein is very large. The molecular weights of some of the proteins have been estimated by various

methods, but exact data are still lacking in this regard. The complexity of the protein molecule is shown by the calculated formula of zein and gliadin as given by Thatcher (1921):

Zein from corn $C_{736}H_{1,161}N_{184}O_{208}S_3$

Gliadin from wheat $C_{685}H_{1,063}N_{196}O_{211}S_5$

1. The Amino Acids.—The proteins are apparently compounds formed by the union of amino acids, since their products of hydrolysis are all acids of this type. Since these acids are the units out of which the protein molecule is built and since the characteristics of the proteins are due in part to the characteristics of the amino acids, a few general statements in regard to their nature should be made. An amino acid may be regarded as an organic acid in which one or more hydrogens of the non-carboxyl group is replaced by the amino group NH_2 , or, viewed from another standpoint, an amino acid may be considered as a substituted ammonia, one hydrogen of ammonia being replaced by an organic acid.

$$\begin{array}{c} NH_2 \\ | \\ H-C-COOH \\ | \\ H \end{array}$$

Thus amino-acetic acid or glycine, $H-C-COOH$, is derived from acetic

$$\begin{array}{c} H \\ | \\ H-C-COOH \\ | \\ H \end{array}$$

acid, $H-C-COOH$. From propionic acid, $H-C-C-COOH$, two

amino acids may be derived: α -amino propionic acid or alanine,

$$\begin{array}{c} H \quad NH_2 \\ | \quad | \\ H-C-C-COOH \\ | \quad | \\ H \quad H \end{array}$$

or β -amino propionic acid, $H-C-C-COOH$.

The amino acids which result from the hydrolysis of protein and out of which proteins are supposed to be built are all α -amino acids, which means that the NH_2 group, or one of the NH_2 groups, is attached to the carbon atom nearest to the $COOH$ group. Since the amino acids contain both the basic NH_2 group and the acid $COOH$ group, they easily unite together to form larger molecules, the linkage taking place between the NH_2 group of one amino acid and the $COOH$ group of the other with the elimination of water. A compound thus formed will contain a free NH_2 group and a free $COOH$ group, so that another amino acid may be attached, further to increase the size and complexity of the molecule, and so on. In the laboratory as many as 18 of these acids have been caused to unite in this manner, forming compounds which exhibit some of the characteristics of the natural proteins (Fischer, 1899 to 1906, quoted by Thatcher, 1921). The following amino acids have been obtained

by the hydrolysis of plant proteins or have been found in the free form in different plant tissues especially in germinating seeds and in growing buds:

Amino acids	Derivative name	Formula
Glycine.....	α -aminoacetic acid	$\text{CH}_2\text{NH}_2\text{COOH}$
Alanine.....	α -aminopropionic acid	$\text{CH}_3\text{CHNH}_2\text{COOH}$
Valine	α -aminoisovaleric acid	$\begin{array}{l} \text{CH}_3 \\ \diagdown \\ \text{CH} \cdot \text{CHNH}_2\text{COOH} \\ \diagup \\ \text{CH}_3 \end{array}$
Leucine.....	α -aminoisocaproic acid	$\begin{array}{l} \text{CH}_3 \\ \diagdown \\ \text{CH} \cdot \text{CH}_2\text{CHNH}_2\text{COOH} \\ \diagup \\ \text{CH}_3 \end{array}$
Serine.....	α -amino β -hydroxypropionic acid	$\text{CH}_2\text{OHCHNH}_2\text{COOH}$
Aspartic acid....	α -aminosuccinic acid	$\text{COOH} \cdot \text{CH}_2 \cdot \text{CHNH}_2\text{COOH}$
Glutamic acid .	α -aminoglutaric acid	$\text{COOH} \cdot \text{CH}_2 \cdot \text{CH}_2 \cdot \text{CHNH}_2\text{COOH}$
Arginine.....	α -amino δ -guanidine valeric acid	$\begin{array}{l} \text{NH}_2 \\ \\ \text{HN} \cdots \text{C} \\ \\ \text{NH} \cdot \text{CH}_2 \cdot \text{CH}_2 \cdot \text{CH}_2 \cdot \text{CHNH}_2\text{COOH} \end{array}$
Lysine.....	α - ϵ -di-amino caproic acid	$\text{NH}_2 \cdot \text{CH}_2 \cdot \text{CH}_2 \cdot \text{CH}_2 \cdot \text{CH}_2 \cdot \text{CHNH}_2\text{COOH}$
Cystine.....	di-(α -amino β -thio propionic acid)	$\text{HOOC} \cdot \text{CH}(\text{NH}_2) \cdot \text{CH}_2 \cdot \text{SSH} \cdot \text{C} \cdot \text{CHNH}_2\text{COOH}$
Phenyl alanine .	α -amino β -phenyl propionic acid	$\text{C}_6\text{H}_5 \cdot \text{CH}_2\text{CHNH}_2\text{COOH}$
Tyrosine.....	α -amino β -parahydroxy phenyl propionic acid	$\begin{array}{l} \text{OH} \cdot \text{C}_6\text{H}_4 \cdot \text{CH}_2\text{CHNH}_2\text{COOH} \\ \\ \text{CH}_2 - \text{CH}_2 \end{array}$
Proline.....	α -pyrrolidine carboxylic acid	$\begin{array}{l} \text{CH}_2 \quad \text{CHCOOH} \\ \diagdown \quad \diagup \\ \text{NH} \end{array}$
Histidine.....	α -amino β -imidazol propionic acid	$\begin{array}{l} \text{HC} = \text{C} - \text{CH}_2\text{CHNH}_2\text{COOH} \\ \quad \quad \\ \text{N} \quad \quad \text{NH} \end{array}$
Tryptophane..	α -amino β -indole propionic acid	$\begin{array}{l} \text{CH} \\ \\ \text{C} - \text{CH}_2\text{CHNH}_2\text{COOH} \\ \\ \text{C}_6\text{H}_4 \\ \\ \text{NH} \end{array}$

In a discussion of the amino acids, the group of compounds termed "amides" should be clearly distinguished from them. An amide is a compound resulting from the replacement of one or more atoms of hydro-

gen in ammonia by a univalent acid radical. Thus $\text{H} - \begin{array}{c} \text{H} \quad \text{O} \\ | \quad || \\ \text{C} - \text{C} - \text{NH}_2 \\ | \\ \text{H} \end{array}$ is

acetamide. Two amides that occur in considerable quantities in plants are asparagine, $\text{CONH}_2\text{CH}_2\text{CHNH}_2\text{COOH}$, and glutamine, $\text{CONH}_2\text{CH}_2\text{CH}_2\text{CHNH}_2\text{COOH}$, the amides of aspartic and glutamic acid, respectively. Asparagine occurs in asparagus, beets, peas, beans, and in numerous seeds that have been germinated in the dark. Glutamine is also found in seeds especially in those of the *Cucurbita*. The exact rôle of these two substances in the protein metabolism of the plant is not known.

2. Qualitative Reactions of the Proteins.—Most of the proteins show similar reactions with a large number of reagents. This is due

to the fact that they are complex compounds which are built up in the same general manner from a large number of relatively simple molecules. None of the various chemical reactions of the proteins is characteristic of them alone, but if a substance gives several of these reactions it may be considered to belong to the protein group. Two of the more common reactions of the proteins are the precipitation reactions and the color reactions.

a. Precipitation.—The proteins are precipitated out of solution by the various mineral acids. In this regard, if nitric acid is allowed to flow gently into a protein solution a white ring forms at the junction of the acid and the solution. This is one of the most delicate protein reactions and is known as "Heller's test." The proteins are precipitated from solutions by the reagents which precipitate alkaloids from their solution. Among these reagents are phosphotungstic acid, tannic acid, picric acid, and phosphomolybdic acid.

The proteins are also precipitated from solution by the addition of small amounts of the salts of various heavy metals such as the chlorides, sulphates, and acetates of iron, copper, mercury, and lead. These precipitation reactions which have just been mentioned are due to the fact that a chemical reaction occurs between the protein and the reagents used. The protein is profoundly altered by these reactions and cannot again be dissolved except by treatment with some reagent which will remove the metal or acid radicals that have combined with the protein. With the exception of some of the mineral acids, the protein cannot be recovered in its original form after such precipitation. This type of precipitation is thus entirely different from the precipitation caused by the saturation of a protein solution with the salts of the alkali metals in which the precipitate proteins can again be readily redissolved and recovered in their original form.

b. Color.—The proteins give certain characteristic color reactions with certain reagents. This is due to the fact that certain radicals or groups are present in the protein molecule; accordingly, some proteins may respond with a color reaction to a certain reagent, while others will not. Certain of the decomposition products of proteins also give the color reactions provided that disintegration has not progressed to a point where the reacting groups are destroyed. The following are the five most important color reactions of the proteins:

1. *Biuret Reaction.*—When a protein is treated with a solution of sodium hydroxide and a dilute solution of CuSO_4 is added drop by drop, a reddish-violet or violet-blue color is produced. When the protein has been hydrolyzed to peptone, a red coloration results with this test. This reaction is known as the "biuret test," since biuret, $\text{NH}_2\text{CO.NH.CONH}_2$, gives this characteristic color with the reagents named. This reaction is also given by groups containing two $-\text{CO.NH}-$ radicals connected by a carbon, nitrogen, or sulphur atom. Since most of the proteins contain several such groups, the biuret test is a very general one for proteins.

2. *Xanthoproteic Reaction.*—When proteins are treated with strong nitric acid, a yellow coloration is produced which intensifies upon heating. If an excess of sodium hydroxide or ammonia is added, the color is changed to orange or orange red. The production of this color is apparently associated with the presence of the benzene ring and in protein tests is evidently the effect of nitric acid on tyrosine.

3. *Millon's Reaction.*—When Millon's reagent is added to a solution or suspension of protein in water, there is obtained either in the cold or after boiling a pink coloration of the solution or a pink to brownish-red coloration of the precipitated protein. Millon's reagent is prepared by dissolving one part mercury in two parts concentrated

nitric acid (sp. 1.42), first cold and then warm, and after the complete solution of the mercury, one volume of the solution is diluted with two volumes of water. The Millon reaction is given by all benzene derivatives in which one of the hydrogen atoms has been replaced by a hydroxyl group and is thus a test for proteins containing tyrosine.

4. *Adamkiewicz's or Hopkins-Cole's Reaction.*—If a protein solution is treated with one volume of concentrated sulphuric acid and two volumes of glacial acetic acid, a reddish-violet color is produced. It has been shown that this color is due to the reaction of the glyoxylic acid, which is present in the glacial acetic acid, upon the tryptophane group in the protein. A more intense reaction is obtained if glyoxylic acid is used instead of acetic acid.

5. *Sulphur Reaction.*—If a drop of a solution of lead acetate is added to a solution containing a protein and then sufficient sodium hydroxide added to dissolve the precipitate which is formed, a black or brown coloration will be produced upon heating to boiling, provided that the protein under consideration contains cystine, the amino acid containing sulphur. The reaction depends upon the splitting off of sulphur from the cystine and the subsequent formation of lead sulphide.

3. Amphoteric Nature of Proteins.—The proteins are amphoteric substances, that is, they are substances that may behave either as acids or bases (Loeb, 1924). The amphoteric nature of the proteins is due to the carboxyl ($-\text{COOH}$) and NH_2 —linkages of their constituent amino acids. The behavior of a protein as an acid or as a base will depend upon the reaction of the medium in which it is dispersed, and there is one reaction of this medium at which the protein will behave neither as an acid nor as a base. This reaction is termed the “isoelectric point” of the protein. It is the P_{H} value of the medium in which the protein is dispersed, at which the protein behaves neither as a cation nor an anion, or where the sum of the number of protein anions is equal to the number of protein cations present (Robbins, 1923). Since proteins as well as certain other colloids bear an electric charge when dispersed in water, the isoelectric point may be defined as that P_{H} value of the dispersal medium at which the dispersed protein will behave as uncharged (Pearsall and Priestley, 1923). The isoelectric point may be stated in yet another manner by saying that as amphoteric electrolytes, proteins combine with either acids or bases but that at a particular hydrogen-ion concentration they exist most nearly uncombined. Whether proteins are ionized at all at their isoelectric point or whether they are ionized equally as an acid or a base is a disputed point. The value of this singular point in ionization and its behavior is characteristic of each protein and is its isoelectric point (Cohn, Gross, and Johnson, 1919). If a pure protein is dispersed in a medium containing electrolytes which is more acid than its isoelectric point, the protein bears a positive charge, behaves as a base, combines with anions only, and thus forms a protein-acid salt. If the medium is more alkaline than the isoelectric point, the protein is negatively charged, behaves as an acid radical, combines with cations only, and forms salts of

the base-protein type. The isoelectric points of plant proteins have been determined by Cohn, Gross, and Johnson (1919), Pearsall and Priestley (1923), Robbins (1923), and Pearsall and Ewing (1924). The following values are taken from Pearsall and Ewing (1924):

Protein	Isoelectric point, P_H	Protein	Isoelectric point, P_H
Vicilin.....	3.4	Leucosin.....	4.5
Legumin.....	4.4 to 4.6	Tuberin.....	4.4
Legumelin.....	4.2	Edestin.....	5.6
Glutenin.....	4.4 to 4.5	Globulin (carrot).....	4.1 to 4.4
Gliadin.....	3.5 to 5.5		

Since the cell sap of the parenchymatous tissues in plants is usually only slightly acid (P_H 5.5 to 6.5), Pearsall and Ewing pointed out that the plant proteins are normally on the alkaline side of their isoelectric points and hence would behave as anions.

The position of the isoelectric point is one of the most significant properties of the proteins. At the isoelectric point the proteins are least soluble and exhibit a minimum tendency to swell in water. Thus at its isoelectric point a protein will most readily part with its water, a fact which is of great significance in the synthesis of substances in plants. In solutions of greater acidity or alkalinity than the isoelectric point, the swelling of proteins increases, as do their viscosity, osmotic pressure, and conductivity. Little or nothing is as yet known concerning the significance of the amphoteric nature of the proteins in the life activities of the plant.

C. CLASSIFICATION OF PLANT PROTEINS

The classification of the proteins is based on the little knowledge possessed concerning their chemical nature as derived from their products of hydrolysis and on their solubilities, precipitation by salts, and coagulation by heat. It has been made primarily upon the characteristics of those common to the animal kingdom, since they were the first examined and have been the most thoroughly investigated. Although many of the plant proteins show certain reactions not exactly characteristic of animal proteins, for the most part no separate classification has been made and they have been placed in those general groups to which they most nearly correspond in behavior. The following outline shows the groups of plant proteins that so far have been studied.

Classification of the proteins that have been found in plants	The simple proteins	The albumins	Leucosin in seeds of wheat, rye, and barley Legumelin in seeds of vetch, soybean, lentil, cowpea, and horse bean Phaselin, in seeds of kidney bean Ricin in seeds of castor bean Legumin in seeds of pea, bean, vetch, and lentil Vignin in seeds of cowpea Glycinin in seeds of soybean Phaseolin (crystalline) in the seed of kidney bean (<i>Phaseolus vulgaris</i>) Excelsin (crystalline) in the seed of Brazil nut Edestin (crystalline) in the seed of hemp Avenalin (crystalline) in the seed of oats Cucurbitin (crystalline) in the seed of squash	
		The globulins	Viellin in seed of pea, lentil, horse bean Arachin in seed of peanut Corylin in seed of hazelnut Amandin in seed of peach and almond Juglansin in seed of walnut and butternut Maysin in seed of corn Tuberin in the potato tuber Also globulins in various types from coconut and the seeds of flax, castor bean, cotton, sunflower, radish, rape, mustard, buckwheat, tomato, lima bean, and others	
		The glutelins	Glutenin in seed of wheat Oryzenin in seed of rice Maize glutelin in seed of corn Gliadin in seed of wheat	
		The prolamins	Hordein in seed of rye Zein in seed of corn Kafirin in seed of sorghum (<i>Andropogon sorghum</i>)	
		The conjugated proteins have not been isolated as yet in plants but considered to occur (see discussion in text)		
		The derived proteins occur in plants in relatively small amounts as temporary intermediate products in the digestion or in the synthesis of proteins		

1. Simple Proteins.—The simple proteins are those which yield only amino acids when they are hydrolyzed. They are practically the only plant proteins that have thus far been isolated and studied. There are four main groups of the simple plant proteins: (a) the albumins, (b) the globulins, (c) the glutelins, and (d) the prolamins.

a. Albumins.—The albumins are those proteins which are soluble in pure water and are coagulated by heat. The albumins of animal origin are not precipitated by saturating their neutral solutions with sodium chloride or with magnesium sulphate. The plant proteins which are classified as albumins, however, in many cases are precipitated by saturation with one or the other of these salts but are included in the albumin group on the basis of their solubility in water at the neutral or slightly acid point and their coagulability by heat. The albumins occur in plants in small quantities, and on that account their nature has not been very thoroughly determined. According to Osborne (1924), most seeds and probably the cell sap in most cases contain proteins which belong in the albumin group. The plant albumins that have been isolated and studied are leucosin from the seeds of wheat, rye, and barley; legumelin from the seeds of soybeans, vetch, horse bean, lentil, and cowpea; phaselin from the seeds of kidney bean; and ricin from the castor bean.

b. Globulins.—A typical globulin is a protein that is insoluble in water but soluble in saline solutions (5 to 10 per cent) and is coagulated in solution by heat. The globulins of animal origin are precipitated from solution by saturation with magnesium sulphate or by half saturation with ammonium sulphate. The plant proteins do not always conform to these conditions of solubility. According to Osborne (1924), the plant globulins are precipitated by partial saturation with ammonium sulphate at very different degrees of saturation. Some are precipitated with half saturation, while others are not precipitated until their solutions are nearly saturated with this salt. Most of the seed globulins are only imperfectly coagulated by heating their solutions even to boiling, and some can be heated in this manner for a considerable time without showing any apparent change. Some of the plant globulins including edestin from hemp seed, excelsin from the Brazil nut, and globulins from the squash seed, flax seed, oat kernel, and castor bean can be obtained in the crystalline form. Others are obtained in the form of spheroids which are sometimes mixed with crystals. The globulins include most of the proteins that thus far have been isolated and studied in plants. The names and sources of some of the most common globulins that have been studied are listed in the classification diagram.

c. Glutelins.—The glutelins represent a small group of proteins that are exclusively of plant origin. They are proteins which are not dissolved by neutral aqueous solution, by salt solutions, or by alcohol but dissolve in dilute acid or alkali. The most characteristic protein of this type is the glutenin of wheat. Oryzenin and maize glutelin are two other glutelins that have been isolated from rice and corn, respectively. It is considered by Osborne that other glutelins may be present in the seeds of other cereals, but owing to the difficulty in extracting them no definite products have been obtained.

d. Prolamins.—The prolamins are proteins that are exclusively of plant origin and are known to occur only in the seeds of cereals. The proteins of this group are freely soluble in ethyl alcohol of 70 to 80 per cent, some dissolving in alcohol of 90 to 92 per cent, and the solutions are unaltered by boiling. They are insoluble in water or salt solutions but soluble in dilute acids or alkalis. On hydrolysis they yield a relatively large amount of proline and amide nitrogen and received their name on that account. The principal prolamins thus far isolated and studied are gliadin from the seeds of wheat and rye, hordein in the seed of barley, zein in the seed of corn, and kafirin in the seeds of sorghum (*Andropogon sorghum*). The glutelins and prolamins are collectively termed "glutens."

✓ **2. Conjugated Proteins.**—The conjugated proteins are compounds of proteins with some other non-protein group. They are nucleoproteins, glycoproteins, phosphoproteins, haemoglobins, and lecithoproteins.

They have not been as yet definitely proved to occur in plants. According to Osborne (1924), some of the proteins in spinach and alfalfa leaves show behaviors in extraction which indicate that they may be a type of conjugated protein. It is frequently stated that nucleoproteins occur in abundance in plants, especially in the nuclei. The compounds, however, which occur in the nuclei of plant cells and in the embryos of many seeds are not true nucleoproteins but are salts or esters of protein and nucleic acid. A true nucleoprotein is one which when subjected to peptic digestion or treated with dilute acid gives a protein and a nuclein. This nuclein after treatment with caustic alkali breaks down into a second protein and nucleic acid (Haas and Hill, 1913). No nucleoproteins of this type have been isolated from plants.

3. Derived Proteins.—The term “derived proteins” is given to the decomposition or hydrolytic products of the simple proteins. Three of the most mentioned derived proteins are the proteoses, the peptones, and the peptides. The proteoses are the protein products of hydrolysis that are soluble in water, not coagulated by heat, but precipitated by the saturation of solution with ammonium sulphate. The peptones are products of further hydrolysis which are soluble in water, not coagulated by heat, not precipitate by ammonium sulphate, but give the biuret reaction. The peptides are the simplest products of the hydrolysis of the proteins and include the polypeptides and the individual amino acids. These compounds may or may not give the biuret reaction, depending upon the degree of hydrolysis, since amino acids do not give this test. The above-mentioned derived proteins have been observed in plants yet are not considered as permanent compounds but more as temporary intermediate products of the hydrolysis of proteins or as compounds from which proteins are being synthesized. Extensive work by Jodidi and Markley (1923), Jodidi (1924, 1925), and Jodidi and Wangler (1925) has shown that amino acids and polypeptides are present in considerable amounts in the ungerminated seeds of wheat, oats, corn, and rye. Thus in the case of Kanred, Fultz, Marquis, and Kubanka wheats the polypeptide nitrogen amounted, respectively, to 3.89, 4.67, 4.98, and 5.13 per cent of the total nitrogen of the seed. The ungerminated kernels of these varieties contained free amino acids, the nitrogen contained in these acids amounting to 1.4, 1.8, 1.8, and 2.3 per cent, respectively, of the total nitrogen content of the kernels of Kubanka, Fultz, Marquis, and Kanred.

In considering the kinds of proteins in plants it should be remembered that the investigations in this regard have been relatively few and that they have been confined, for the most part, to the reserve proteins of seeds and other storage organs. The proteins of the physiologically active tissue of the plant as the leaves and growing regions have been but little studied. It is highly probable that when such studies are made,

the present ideas concerning the occurrence of conjugated proteins and derived proteins in plants will be greatly changed.

D. SYNTHESIS OF PROTEINS BY THE GREEN PLANT

The general opinion is that proteins are formed by the linkage of amino acids. The evidence in this regard is that polypeptids have been formed artificially in the laboratory by linking together amino acids and that proteins yield amino acids upon hydrolysis. It has also been observed that in the maturing of seeds the proteins are formed at the expense of the amino acids. The origin of the amino acids, however, is not definitely known. It is known fairly definitely that proteins are not formed in the plant unless a supply of carbohydrates is present, but the manner in which the carbohydrates are changed to amino acids is not known. The formation of amino acids from the fatty acids is apparently a rather simple reaction, but the transformation of carbohydrates into fatty acids is accomplished, artificially at least, only with considerable difficulty. It was observed by Chibnall (1922, 1924) in the case of the leaves of the bean that the nitric nitrogen and monoamino nitrogen varied directly with the protein nitrogen, which indicates that they may be connected with protein synthesis. Baly and Heilbron (1922, 1923) suggest as a theory of the formation of proteins that "activated" formaldehyde $\text{H}-\text{C}-\text{O}-\text{H}$, which they consider is photosynthetically formed in the leaves from CO_2 and water, reacts readily with KNO_2 to give formhydroxamic acid and that this substance at once reacts with more molecules of activated formaldehyde to produce a great variety of the complex substances that are found in the living plant. This reaction they believe takes precedence over the polymerization of the activated formaldehyde to reducing sugars, which they consider is produced only when the activated formaldehyde is produced at a rate greater than that at which it can react with the nitrite and the form-

hydroxamic acid, $\begin{array}{c} \text{N}-\text{O}-\text{H} \\ || \\ \text{H}-\text{C}-\text{OH} \end{array}$, thus formed.

1. Reduction of Nitrates in the Plant.—Since the nitrogen in the protein molecule is generally in the form of NH_2 groups, the nitrogen that has been absorbed by the plant in the form of nitrates must be reduced in order to convert the grouping NO_3 into the necessary NH_2 form. The first step in this reduction is the conversion of the nitrates to nitrites. The transition from nitrate to nitrite is a strongly endothermic reaction and can occur only either by the transformation of other forms of energy such as that of light into chemical energy or by a linked chemical reaction with oxidation of previously formed reduced chemical substances, as, for example, the oxidation of carbohydrates. It is the intention here to mention the occurrence of nitrates in the plant and to

discuss the conditions under which they are reduced both outside and inside the plant.

a. Occurrence.—As has previously been mentioned, a considerable portion of the nitrogen absorbed by plants is in the form of nitrates. The occurrence of nitrates in the plant, however, has for the most part been observed only at random, and the quantitative data in this regard are very limited. Woo (1919) observed in the root, stem, and leaves of *Amaranthus retroflexus* that there was a considerable accumulation of nitrates, especially in the stem and branches. The rate of nitrate absorption increased with the age of the plants until they were 20 in. high and near the blooming stage. At this stage the nitrate nitrogen amounted to 1.01, 1.94, 2.82, and 0.06 per cent of the dry weight of the roots, stem, branches, and leaves, respectively, as compared with 0.42, 0.22, and 0.3 per cent in the roots, stem, and leaves when the plants were only 1 to 4 in. high. Campbell (1924) determined the nitrate content of *Amaranthus retroflexus* and 25 other weeds just before the blooming stage and at maturity. He found that although the nitrate nitrogen was prominent in some of these plants during the young and immature stages, it had completely disappeared at full maturity. In all species grown under normal conditions the highest percentage of nitrate was found in that stage of development designated as "just before blooming." *Amaranthus retroflexus* and *Atriplex patula* grown upon manure piles and heaps of decaying hog hair at early maturity showed more than a trace of nitrate which at full maturity was still present. Anderson (1924) found nitrates in the expressed sap of the shoots of a large number of plants including oats, lupine, wheat, and grasses. He observed that the amount of nitrate found in the plant would depend upon the time of day the examination was made and upon the soil in which the plants were grown. *Solanum dulcamara* showed considerably less nitrate in the morning than later in the day, and *Mercurialis perennis* gave positive nitrate reactions in October and negative in June. The amount of nitrate in the etiolated leaves of wheat, oats, and cabbage was higher than that found in the normal green leaves. In the soybean, Webster (1928) observed that nitrates, as a rule, are much higher in the stem and roots than in the leaves, while the various parts of the plant are lowest in nitrates at about the time of seed maturity. He observed nitrites in the leaves during the earlier stages of growth, but their presence in other parts was doubtful. The addition of nitrates to the soil resulted in a temporary increase in the nitrate storage in all organs of the plant, but this was soon reduced to normal. The percentage of ammonia was very small, but there seems to be reasons for considering that it is one of the intermediate steps in both the synthesis and decomposition of proteins. According to Strowd (1920), there is an increase in the nitrate content of the roots of soybeans growing in the field during arrested photosynthesis. The nitrates in the

cell sap increase to some extent with the increase of the nitrates in the soil, but this increase is not proportional to the increased nitrate supply. Thomas (1927) found that the application of NaNO_3 as a fertilizer to apple trees markedly increased the total nitrogen content of the leaves and growing twigs.

Nitrites have been found in small amounts only if at all in the plant tissues that have been examined (Aso and Sekine, 1914). They were detected by Webster (1928) in the leaves of the soybean in the earlier stages, but their presence in other parts was doubtful. Bonequet (1916) could detect no nitrites in any plant tissue which was normal. In the mosaic tissue of tobacco, however, considerable nitrites were found.

b. Conditions under Which Nitrates Are Reduced.—It was observed by Laurent (1890) that when a sterilized solution of KNO_3 was exposed to sunlight, oxygen and potassium nitrite were formed.

In investigations concerning the reduction of nitrates, Baudisch (1921, 1923) found that glucose solutions do not reduce nitrates or nitrites even when heated under pressure, but the smallest trace of iron salt is sufficient to reduce a large amount of nitrite on warming with glucose in weakly alkaline solution. Under these conditions, nitrates remain entirely unattacked. He found, however, that oxygen in the presence of ferrous salts reduces nitrates instantaneously even in the cold with the formation of nitrites and that there is a direct relation between the amount of oxygen dissolved in the water and the amount of nitrite formed. The reduction of an alkaline solution of nitrate to nitrite can be brought about in sunlight in the summer if the oxygen which is split off is taken care of chemically, a process which may be brought about by the addition of complex ferrous salts such as potassium ferrocyanide. Baudisch considers that the nitrite thus formed from nitrates by light energy or with ferrous hydroxide and oxygen is, in the presence of these same factors reduced to nitrosyl, $\text{R}-\text{NO}$, which will combine readily with

aldehydes and produce formhydroxamic acid,
$$\begin{array}{c} \text{N}-\text{OH} \\ || \\ \text{H}-\text{C}-\text{OH} \end{array}$$

The conditions under which nitrates are reduced in the green plant are not very well defined. Apparently the process goes on in both light and darkness and in any part of the plant, but there is some little evidence that certain conditions are more favorable than others for the reaction. Thus Schimper (1888) found that nitrates were depleted in the green leaves exposed to daylight and were not destroyed in the leaves kept in the dark. He also observed that shade leaves were richer in nitrates than leaves in the sun and that the disappearance of nitrates in the leaves in the light occurred only in green leaves and not in etiolated ones. Moore (1924) also considered that the reduction of nitrates to nitrites occurs in the leaves in the presence of sunlight. Warburg and Negelein (1920)

transferred *Chlorella pyrenoides* from Knop's solution to $N/10$ NaNO_3 and observed that reduction of nitrates took place in the dark but that illumination increased it. The rate of reduction, however, was independent of carbon assimilation. Acqua (1899) and Thomas (1927) obtained evidence that some of the nitrates absorbed by the young roots are utilized directly in or near the root tips. The most complete information that we have concerning the transformation of the nitrates after they enter the plant is afforded by the careful work of Eckerson (1924). This investigator grew tomato plants of the Bonny Best variety in rich soil until they were 8 in. high and then transferred them to quartz sand which was watered with a dilute nutrient solution lacking nitrogen. When the plants thus grown were ready for experimentation, they contained an abundance of glucose, some fructose, and a little sucrose and an abundance of starch in parenchyma cells of the stem and leaves. The tissues gave no reaction for nitrates, nitrites, or ammonia, and no amino acids could be detected. Calcium nitrate was then applied to the sand and the subsequent chemical changes followed by microchemical means. Within 24 hr. after the nitrate was applied, nitrates were present in all parts of the plants. The tops of a few plants gave a slight reaction for nitrites but no reaction for ammonia. At the end of 36 hr. all the plants had considerable nitrite localized in the cortical cells at the tips of the stems, in the cortical cells near the phloem, and in the phloem parenchyma at the nodes of the stem. In all regions there was a trace of ammonia. After 48 hr. there was slightly less nitrite but more ammonia, and a slight decrease in the amount of starch could be detected in the cortical cells at the tips of the plant and in the youngest leaves. Within three to five days there was very much less nitrite, a little ammonia, but a great increase in amino acids. These amino acids were aspartic acid, alanine, leucine, cystine, and histidine and appeared at the nodes and in petioles and blades of young leaves and just behind the stem tips. Succinic acid, malic acid, and asparagin were also present. Eckerson further found that the reduction of nitrates to nitrites and ammonia took place in tomato-plant extract of slightly alkaline reaction, in the presence of fructose or glucose and some free oxygen, in darkness as well as in light and that the reduction was most active in solutions having a P_H value of approximately 7.6.

c. Nitrate-reducing Substances.—Considerable experimental work has been done to determine the presence of nitrate-reducing enzymes in the plant, but the results are somewhat conflicting, especially in regard to the behavior of the extract to heat. Pozzi-Escot (1903) found that the aqueous extracts of the stem of the burdock have the power to reduce nitrates to nitrites and ammonia and concluded that the enzymes that reduce nitrates are very abundant in actively growing plants. Kastle and Elvove (1904) also found that the potato sprouts and eggplant contain

a reducing substance or substances capable of effecting the reduction of nitrates to nitrites. It was found that the reduction takes place most rapidly at 40 to 50°C. and that it is augmented by an increase in the amount of nitrate present and also by an increase in the quantity of the reducing extract. The extracts capable of effecting this reduction lose this property when heated to boiling.

Irving and Haukinson (1908) claimed to have found a nitrate-reducing enzyme in *Elodea*, *Potamogeton*, *Iris*, *Vicia*, and numerous members of the grain family. They considered that the only conditions necessary for nitrate reduction seem to be the presence of the enzyme found in the roots, stem, and leaves and a suitable carbohydrate. Anderson (1924) detected nitrites in the shoots of 25 of the 105 species examined, and in the leafy parts of 23 of these, including sunflower, artichoke, pea, radish, tomato, clover, and wheat, the presence of a nitrate-reducing substance was confirmed. This nitrate-reducing substance was found to be thermolabile and an oxidizable substance rather than an enzyme. Eckerson (1924) reported that tomato-plant juice boiled and brought to a P_{H} value of 7.6 reduced nitrates as rapidly as the unheated juice.

2. Protein Metabolism of the Green Leaf.—The observation of protein changes in the leaf is a difficult task. In the first place, many metabolic processes are continually taking place in the leaf, so that numerous nitrogenous substances are present at the same time. It is impossible to determine which of these substances are synthetic and which are deterioration products. In the second place, the methods for the extraction of proteins and protein products, especially from parenchymatous tissue, are not well developed. Then, too, the amount of protein in leaves is relatively small and it is difficult to differentiate the extracted proteins into those which are uncombined in the cell and those which are constituent parts of the protoplasm.

a. Extraction of Proteins.—Several methods for the general extraction of proteins from leaves have lately been published. Thus Chibnall and Schryver (1920, 1921) treated the macerated leaves of spinach, cabbage, and scarlet runner bean with water saturated with ether and obtained, in such an extract, two-thirds of the total nitrogen of the leaves. Osborne and Wakeman (1920) by grinding the fresh leaves of spinach and centrifuging at high speed obtained solutions containing a certain portion of their protein. These same workers and Leavenworth (1921) found that by grinding and pressing fresh young alfalfa plants it was possible to obtain large quantities of extract suitable for protein determinations. In the case of the leaves of the sugar beet, Tottingham, Schulz, and Lepkovsky (1924) obtained results which indicated the desirability of extracting the macerated tissue with water as a general procedure in separating the nitrogenous constituents of plant cells. The above statements show that the methods for the extraction of proteins and nitrogenous products from leaves vary greatly, and the indications are that for the best results special methods of extraction must be applied to different types of leaves. Thus no one method is equally applicable in any considerable number of cases.

1. *Previous History of Tissue and Nature of Nitrogenous Extract.*—Much of the study that has been made on the nitrogenous changes in the leaves is open to criticism because of the methods used in the preparation of the material for analysis. Thus, for example, many of the results that have been obtained are based on the analysis of materials that were air dried or desiccated at low temperatures. The errors that are likely to occur from such a procedure have been stated by Chibnall (1922), who showed that proteolytic enzymes are present in the leaves of the runner bean which were dried at 40 to 50°C., for 100 to 120 hr. He also observed evidences which indicated the presence of an asparaginase. A comparison of the distribution of the total nitrogen in the aqueous extract of fresh leaves and of leaves which have been dried at 40°C. for 120 hr. will indicate the changes that go on in the nitrogenous compounds of the leaves during the drying process.

COMPARISON OF THE DISTRIBUTION OF THE NITROGEN IN THE AQUEOUS EXTRACT FROM THE FRESH AND DRIED LEAVES OF THE RUNNER BEAN, PERCENTAGE OF TOTAL NITROGEN

Material	Total water-soluble N	Protein-free and proteose-free water-soluble N	Ammonia	Amide N of asparagine	Nitric N	Humin N	Basic N	Amino N	Other N
Fresh ...	21.57	17.22	0.44	0.53	2.73	0.99	2.00	7.76	2.77
Dried, 40°C. .	33.68	29.55	5.32	1.51	1.62	0.82	2.84	13.22	13.22

Chibnall's work shows that when leaves are dried at a low temperature protein autolysis takes place which brings about an increase in the simple water-soluble nitrogenous products consisting, for the most part, of ammonium salts, asparagin, and amino acids. There is a diminution in the amount of leaf proteins during the drying, but they are not appreciably changed in character.

The effect of the method of preparation of material upon the nitrogenous products obtained in extraction was shown by Tottingham, Schulz, and Lepkovsky (1924) in the case of the leaves of the sugar beet as follows:

Substance	Treatment of tissue		
	Extracted fresh, per cent	Extracted after drying at 40°C. without aeration, per cent	Extracted after freezing by ice salt mixture, per cent
Total soluble nitrogen.....	4.0	2.2	3.3
Soluble protein nitrogen....	3.4	0.5	2.3

The nitrogen constituents of the leaves are also markedly affected by disease. Jodidi and others (1918 to 1920) studied the nitrogen metabolism of the healthy leaves of spinach and cabbage and those affected with the mosaic disease. The normal leaves of spinach contained 4.8 to 5 per cent, depending on the sample, of their dry weight in total nitrogen, while the total nitrogen content of the diseased

leaves was only 3.8 to 3.9 per cent of the dry weight, so that the diseased plants had from 21 to 23 per cent less nitrogen than the healthy ones. The diseased leaves had a smaller percentage of total nitrate, acid amide, mono- and diamino nitrogen, but a somewhat larger percentage of ammonia than normal plants, while nitrous acid was present only in the diseased plants. The lower percentage of total nitrogen and of acid amide nitrogen in the diseased material was explained by the assumption that denitrification takes place in those tissues whereby a part of the nitrogen may be lost either as elementary nitrogen or in the form of ammonia.

The reason for the higher proportion of ammoniacal nitrogen in the diseased material than in the corresponding healthy tissues is probably due to the processes of denitrification whereby a part of the nitrites is further reduced to ammonia. The same facts as were mentioned above for spinach were observed in the examination of the healthy and diseased leaves of cabbage. The cause for the dwarfing of plants that are affected with this disease can be attributed to the fact that the acid amides, amino acids, and other nitrogenous substances are partly lost through oxidation so that there is a scarcity of these materials for the formation of protein.

Coons and Klotz (1925) noted the nitrogen constituents of healthy celery plants and those affected with *Cercospora Apii* and *Septoria Apii* and noted that there is a lower percentage of total nitrogen in the necrotic plants than in the healthy ones. Nitrites are present in the diseased material. A comparison of the nitrogenous compounds present, in percentage of total nitrogen, shows greater NH_3 , greater protein nitrogen, less acid amide, less basic, and less non-protein nitrogen in the diseased than in the healthy tissue. The examples just mentioned serve to show that the methods of the preparation of material and the conditions prevailing at the time of sampling must be given first consideration not only in a study of the nitrogen metabolism of the leaf but in the study of all other plant processes as well.

2. *Separation of the Proteins of the Cell.*—The proteins in the cells of the leaf and of other parenchymatous tissue—are those in solution in the vacuole, those held uncombined by the protoplasmic structure, and those combined in the structural material of protoplasm. By the ordinary methods of protein extraction, the proteins from these three sources are obtained in a general mixture. It is evident that before any knowledge can be gained in regard to the nitrogen metabolism of the leaf, methods must be devised to separate the uncombined proteins of the cell from the protoplasm. Chibnall (1923; see also Thomas, 1927) devised a method for extracting protein from leaves which he considered separates the protein of the vacuole of the cell, from the protein of the protoplasm. This method consists of plasmolyzing the cells by means of certain organic agents, as ether or butyl alcohol, and then pressing out the major part of the vacuole content in a press. The remainder of the vacuole content can be washed out by repeatedly allowing the pressed residues to imbibe very dilute acid (0.002*N*) and subsequent pressing. This operation, he considered, does not rupture the leaf cells, and the protoplasm from which some of the water-soluble constituents may have been washed out is retained in them. After the removal of the vacuole contents the protoplasmic material remaining in the residue can be extracted by grinding with water. This material passes into colloidal solution and can be

flocculated by the addition of acid. In the case of spinach leaves, the protein found in the vacuole amounted to from 1 to 2 per cent of the total protein of the leaves and had properties distinct from those proteins of the protoplasm.

Chibnall and Grover (1925) undertook to obtain the proteins of the protoplasm of the cells of the leaf as follows: The leaves were treated with ether, enclosed in filter cloth, and placed under pressure in a hand press, so as to remove the soluble proteins of the vacuole. The leaf residues were then washed free from the remainder of the vacuole material by alternate soaking in water and pressing. The protoplasm from which some water-soluble substances may have been removed was obtained in colloidal solution by grinding with water in a meat chopper and the ground material filtered or strained through fine gauze. The colloidal solution thus contains proteins from the protoplasm of the leaf cells. The proteins thus obtained could be separated into (a) "combined" proteins which are in loose combination with substances soluble in alcohol and (b) "soluble" proteins which are uncombined and which pass fairly readily into solution when the protoplasm is ground with water. These investigators examined these soluble proteins of the protoplasm of the leaves of *Spinacia oleracea*, *Vicia faba*, *Phaseolus multiflorus*, *Medicago sativa*, *Brassica oleracea*, and *Zea mays* and numerous others. It was found that these proteins are glutelins with very similar chemical properties. They have an isoelectric point from P_H 4.0 to 5.0 at which their solubility is at a minimum. The hydrogen-ion concentration of the leaf cell sap was found in all cases to be alkaline with respect to the isoelectric point of the proteins so that they were probably present in the living cells as anions. Chibnall and Grover were, however, unable to obtain any "soluble" protein from the leaves of *Populus tremula*, *Wistaria chinensis*, *Rheum rhaponticum*, *Polygonum cuspidatum*, *Rumex acetosella*, and *Vitis vinifera* among others. In this regard it should be noted that Thomas (1927) found in the case of apple leaves which had been collected at early bud formation, at the stage of active maximum growth, and at the period of chlorophyll degeneration, that the insoluble cytoplasmic proteins showed little or no variation in their nitrogen composition throughout the season.

b. *Diurnal Variation of the Nitrogen in the Leaves.*—In a consideration of the nitrogen metabolism of the leaves, a knowledge of the variation of their nitrogen content both as to quantity and quality during a 24-hr. period is of primary importance, since the changes in these two factors are indicators, at least, of the processes that are occurring.

1. *Methods of Determining.*—The determination of the changes of the nitrogen content of the leaves during a 24-hr. period is attended with considerable difficulty. This is due to the relatively small amount of nitrogen present, to the difficulty of separating the various nitrogenous compounds, and to the wide variation of the other

more abundant constituents of the leaf during the period in question. Four methods, each of which has certain disadvantages, have been used to determine the variation of the nitrogen content of the leaves during the day and night: (a) Estimation of the nitrogen in percentage of the dry weight of the leaves. Most of the data on the diurnal variation of the nitrogen have been obtained by this method. This method is unreliable, since the total dry weight of the leaves changes markedly during the day, so that when the diurnal changes in the nitrogen content of the leaves is estimated in this manner, it is not the absolute amounts of nitrogen in the leaves that are being compared but only the concentrations of nitrogen in terms of total solids. (b) Estimation of the nitrogen by weight in terms of a certain number of leaves. This method is inaccurate, as shown by Chibnall (1924), for the reason that the error in sampling is high. Leaves differ considerably in texture, weight, and general composition, so that when the errors of the determination are taken into consideration, the changes observed in the nitrogen content cannot be considered reliable. (c) Estimation of the nitrogen in percentage of the fresh weight of the leaves. Chibnall (1923) considered that this method gives the most reliable index into the daily fluctuations of the nitrogen in the leaves. It is evident, however, that this method would be of value only under conditions that cause little or no fluctuation in the water content of the leaves. Under the climatic conditions under which Chibnall worked in England the water content of the leaves remained almost constant. Such a constancy of the water content of the leaves is generally not the case, especially in regions of a relatively high evaporation. Miller (1917) observed in Kansas that the minimum amount of water in the leaves of corn and sorghums during the day may be from 88 to 97 per cent of the maximum amount. He also observed that the amount of water in the leaves of pumpkin, soybeans, and cowpeas at 1 p.m. may be only 66, 76, and 86 per cent, respectively, of the water content of the leaves at 8 a.m. It is evident, therefore, that the determination of the percentage of nitrogen on the fresh weight of leaves would in such cases not give a very accurate index into the actual changes of the nitrogen content. (d) Estimation of the nitrogen by weight in terms of a definite leaf area. This method has been used by Miller (1917, 1924) in the determination of the diurnal changes of carbohydrates, dry matter, and water in leaves. Its procedure is as follows: The nitrogen is determined in percentage of the dry weight of the leaves and this value is multiplied by the dry weight of a certain number of leaf areas which have been obtained by means of a calibrated punch (see Chap. VIII, Fig. 28). The two main objections to this method are the shrinkage and expansion of the leaves due to changes in the moisture content and to the errors in sampling due to lack of uniformity in the structure of the leaves. Experience has shown, however, that the errors from these two sources are comparatively small, so that it appears that this method is one of the most accurate of the four that have been mentioned.

2. *Total Nitrogen of the Leaves.*—The total nitrogen content of the leaves was determined by Suzuki (1897) at 6 a.m. and 6 p.m. after they had been exposed respectively to 12 hr. of darkness and 12 hr. of light. The nitrogen was estimated in terms of weight per leaf using a large number of leaves to reduce the error in sampling. His data showed that the total nitrogen content of the leaves of *Wistaria brachybotrys*, *Phaseolus mungo*, *Phaseolus vulgaris*, *Solanum tuberosum*, and *Polygonum fagopyrum* decreased during the night 16.6, 9.9, 10.9, 5.1, and 7.5 per cent, respectively, of the amount found in the leaves at the close of the day. The changes in the total nitrogen of the leaves of *Acer negundo* was determined

by Schulze and Schütz (1909). The data show that at all times of the growing season the absolute amount of nitrogen in the leaves was higher in the evening than in the morning, as shown in the following table:

VARIATION IN THE TOTAL NITROGEN OF THE LEAVES OF *Acer negundo*
After Schulze and Schütz

Date	Per cent of dry substance		Absolute amount in grams, 200 leaves	
	Morning	Evening	Morning	Evening
May 7.....	4.30	4.50	0.734	0.817
June 6.....	3.90	3.98	0.973	1.231
July 5.....	4.06	4.14	1.211	1.306
Aug. 2.....	3.74	3.75	0.864	0.898
Sept. 3 to 6.....	3.16	3.18	0.791	0.971

The total nitrogen of the leaves as expressed in percentage of the dry weight was reported by Kosutany (1897) for the grape and by Pigorini (1914) for the mulberry to be higher in the morning than in the evening. By the same method Frank and Otto (1891) in the case of red clover and alfalfa and Otto and Kooper (1910) in the case of *Aesculus hippocastanum*, *Philadelphus coronarius*, *Syringa vulgaris*, and *Sambucus nigra* found that the total nitrogen was higher in the evening than in the morning. Chibnall (1924) in his investigations of the nitrogen metabolism of the leaves in the scarlet runner bean noted that the fall in the total nitrogen of the leaves expressed in percentage of fresh weight at night amounted to 2.5 per cent with a probable error of only ± 0.2 per cent.

Miller (1926) studied the daily variation of the total nitrogen in the leaves of various crop plants. The nitrogen was determined in percentage of the dry weight, and the results were reduced to the amount of nitrogen per unit of leaf area. A small portion of the data obtained in 1925 for the leaves of soybeans, cowpeas, and garden beans is shown in the table on page 530.

In the case of 18 observations for soybeans in 1925, the total nitrogen content of the leaves expressed as grams per square meter of leaf at 8 p.m. showed fifteen times an increase and four times a decrease over the amount present at 8 a.m. The average nitrogen content of the leaves for these 18 cases at 8 p.m. showed an increase of 5.9 ± 0.9 per cent of the nitrogen content at 8 a.m. For the same year in 17 observations, the nitrogen content of the leaves of cowpeas, expressed in the same manner as above, showed at 8 p.m. an increase in 13 cases and a decrease in 4 cases over the amount of nitrogen present at 8 a.m. The average nitrogen content of the leaves of cowpeas at 8 p.m. for the 17 observations showed an increase of 6.7 ± 0.8 per cent over the amount of nitrogen pres-

DAILY VARIATION OF THE TOTAL NITROGEN OF THE LEAVES OF SOYBEANS, COWPEAS, AND GARDEN BEANS AT MANHATTAN, KANS., 1925

Plant	Time	Water per square meter of leaf, grams	Dry matter per square meter of leaf, grams	Total nitrogen per square meter of leaf, grams	Percentage of total nitrogen	
					Dry basis	Wet basis
July 10-11:						
Soybeans.....	8 a.m.	96.9	32.8	1.863	5.68	1.43
	8 p.m.	108.7	38.6	2.138	5.54	1.45
Cowpeas.....	8 a.m.	107.5	31.8	1.847	5.81	1.32
	8 a.m.	215.0	50.7	2.808	5.54	1.05
Garden beans .	8 p.m.	230.5	55.7	3.002	5.39	1.04
	8 a.m.	228.9	50.1	2.790	5.57	1.00
Garden beans .	8 a.m.	163.9	38.3	1.758	4.59	0.86
	8 p.m.	162.0	43.6	1.979	4.54	0.96
	8 a.m.	167.5	38.7	1.880	4.86	0.91
July 13:						
Soybeans.....	8 a.m.	107.2	32.4	1.918	5.92	1.37
	8 p.m.	108.8	39.0	2.215	5.68	1.49
Cowpeas.....	8 a.m.	207.1	43.4	2.439	5.62	0.97
	8 p.m.	219.7	49.7	2.788	5.61	1.03
Garden beans .	8 a.m.	166.3	42.3	1.941	4.59	0.93
	8 p.m.	175.5	47.7	2.027	4.25	0.90
July 17-18:						
Soybeans.....	8 a.m.	97.9	32.5	1.755	5.40	1.34
	8 p.m.	99.5	36.8	2.013	5.47	1.47
Cowpeas.....	8 a.m.	90.6	31.7	1.962	6.19	1.60
	8 a.m.	209.4	51.5	2.837	5.51	1.08
Garden beans .	8 p.m.	213.5	55.2	3.097	5.61	1.15
	8 a.m.	224.5	49.3	2.746	5.57	1.00
Garden beans .	8 a.m.	172.9	52.2	2.176	4.17	0.96
	8 p.m.	174.2	53.0	2.178	4.11	0.95
	8 a.m.	186.3	50.4	2.192	4.35	0.92
July 24:						
Soybeans.....	8 a.m.	110.7	38.8	2.312	5.96	1.54
	8 p.m.	111.2	39.0	2.215	5.68	1.47
Cowpeas.....	8 a.m.	239.2	54.5	2.992	5.49	1.01
	8 p.m.	239.5	55.3	2.925	5.29	0.99
Garden beans	8 a.m.	199.3	52.5	2.136	4.07	0.84
	8 p.m.	209.8	52.5	2.168	4.13	0.82

ent at 8 a.m. The leaves of garden beans in 16 observations showed eleven times an increase and five times a decrease of their nitrogen content at 8 p.m. as compared to the amount present at 8 a.m. The average nitrogen content at 8 p.m. showed an increase of only 2.9 ± 1.2 per cent over that present in the leaves at 8 a.m. The results in the case of garden beans do not show conclusively that the nitrogen content of the leaves

increases during the day, at least under the conditions under which these observations were made. In 6 observations of the nitrogen changes in the leaves of Dwarf Milo in 4 different years, the amount of nitrogen in the evening showed an increase four times and two times a decrease over the amount present in the morning. The results seem to indicate that in the case of this sorghum that there is little change in the total nitrogen content of the leaves during the day. The same statement can also be made for the nitrogen changes in the leaves of the corn. The observed facts would seem to indicate that the total nitrogen variation in the leaves during the day may be marked in some plants and very little in others. The experimental work that has so far been done indicates that there is an actual increase in the total nitrogen content of the leaves during the day and that this increase disappears during the night. The probable significance of this behavior will be discussed under another heading.

3. *Nitrogenous Compounds of the Leaves.*—The information in this regard is meager and more or less contradictory. Suzuki (1897) reported that in the leaves of *Phaseolus* the asparagin nitrogen decreased during the night to 57 per cent and the amino nitrogen to 91 per cent of what it was during the day. He considered that the reserve proteins in the leaves are decomposed into amino compounds during the night and that they are transferred to other parts of the plant. Schulze and Schütz (1909) in the case of the leaves of *Acer negundo* could observe little change in the amino acid content during the day. They observed, however, a greater amount of protein nitrogen in the evening than in the morning and that the protein nitrogen varied with the total nitrogen.

In the case of *Phaseolus vulgaris* var. *multiflorus*, Chibnall (1924) reported that on the basis of the fresh weight of the leaves there was a fall in the protein nitrogen during the night of 1.8 per cent with a probable error of only ± 0.2 per cent. The non-protein nitrogen showed a definite decrease of 9 per cent with a probable error of only ± 0.6 per cent. Both the ammonia nitrogen and amide nitrogen of asparagine remain unchanged at 0.001 per cent and 0.005 per cent of the fresh weight, respectively. The experimental work all strongly indicates that protein translocation takes place in the leaf cells at night either as unchanged protein or as its decomposition products. This loss of protein is from the cytoplasm and not from the small amounts present in the vacuole. Chibnall (1924), in order to obtain data regarding the process of protein degradation in the leaves, cut leaves with long petioles from *Phaseolus vulgaris* var. *multiflorus* and allowed them to remain with their petioles in water for four or five days. At the same time that the leaves were removed, others were analyzed directly after cutting. It was found that the leaves with their petioles in water showed, in terms of the total leaf nitrogen, a large increase in non-protein nitrogen with a corresponding decrease in the protein nitrogen and that this increase in non-protein

nitrogen is due, in large part, to increases in asparagin and free amino-nitrogen. Thus the amide nitrogen in the freshly plucked leaves constituted only 0.64 per cent of the total leaf nitrogen while the detached leaves with their petioles in water contained 3.78 per cent of amide nitrogen on the same basis. Likewise the free amino nitrogen amounted to only 6 per cent of the total leaf nitrogen in the case of the freshly plucked leaves but to 14.1 per cent in the detached leaves after four days. Chibnall believes that there is a continuous production of asparagin from the reserve proteins of the leaves, that its rôle in the metabolism of the mature plant is that of a translocatory substance, and that it is the chief medium whereby nitrogen in a form suitable for subsequent metabolic processes can be transferred from one part of the plant to another.

c. Formation of Protein in the Leaves.—The formation of protein in the leaves is indicated by the fact that (1) the amount of nitrate in the leaves is relatively small as compared with that in the stem and roots as reported for *Vicia faba* by Emmerling (1880, 1887, 1900), (2) incised leaves with their petioles in nutrient solutions form protein while those with their petioles in distilled water or in solutions lacking nitrogen do not (Chrapowicki, 1889; Sapoznikow, 1895), and (3) leaves can increase their protein content in the dark provided that the petioles are placed in a nutrient solution containing the essential salts and sugar (Zaleski, 1899 to 1907). It has also been observed by Chibnall (1924), as previously mentioned, that the protein nitrogen of the leaves decreases during the night, a fact which indicates that the protein increases during the day and is translocated from the leaves during the night.

Work has been done by Molisch (1916), Lakon (1916), Meyer (1918), and Ullrich (1924) to determine what portion of the green cell is concerned in the formation of protein. All of these workers conclude that the main portion of the protein formed in the leaves is synthesized in the chloroplasts. The general procedure of these workers may be illustrated by the work of Lakon (1916), who studied the variegated leaves of *Acer negundo*, *Acer pseudoplatinus*, *Sambucus nigra*, *Vinca major*, *Tradescantia zebrina*, *Abutilon vexillarium*, and *Aegopodium podagraria* among others to determine the distribution of protein in the differently colored parts. The leaves of these plants contain contrasts in color ranging from stripes of dark green and light green to stripes of dark green and pure white. The leaves were first placed in scalding water and then transferred to warm alcohol until they became colorless, after which they were tested for protein by the xanthoproteic, biuret, or Millon's reaction. In the leaves of *Acer negundo*, all three of the protein tests gave only a very slight reaction in the white portion of the leaf, while the green portion showed a very intense reaction, the contrast between the two portions being so great that it could be observed at a considerable distance. In the case of the leaves of *Acer pseudoplatinus*, which have intense green, bright-green,

and pure white stripes, the white stripes showed only a trace of coloration, the light green an intense coloration, and the dark-green regions a very intense coloration with both the biuret and Millon's reagents. In the pure white part of leaves there is generally no chlorophyll apparatus, since the plastids do not develop or else remain rudimentary. Since the intensity of the protein reaction increases from the white portions of the leaf to the dark green parts, it is assumed that the intensity of the protein reaction depends upon the relative number of the chloroplasts and that the faint protein test observed in the colorless regions of the leaves is due to the reaction of the cytoplasm. Lakon thus concludes that the main part of the protein in the leaves is formed in the chloroplasts. When leaves of *Phaseolus*, *Lactuca*, *Brassica*, *Cucurbita*, *Zea*, and *Tropaecolum* are detached from plants grown without nitrogen and such leaves placed under favorable conditions of light and furnished with a supply of nitrate, they show the formation of nitrogenous material which tests prove to be accumulated in the chloroplasts (Ullrich, 1924).

3. Light and Protein Synthesis.—Evidence has been submitted above to show that protein may be synthesized in the chloroplasts of the cells of the leaves. The question then arises as to whether the leaves are the only portion of the plant in which proteins are manufactured and as to what conditions are necessary for their formation. Suzuki (1897, 1898) grew young barley plants in the dark after the following manner: When the plants had reached a height of 15 cm. they were transferred to a complete nutrient solution which contained the nitrogen in the form of nitrates and allowed to remain for 7 days. One set was then allowed to remain in the nutrient solution while the other was transferred to a 10 per cent sugar solution which was daily renewed. After 7 days the two sets of seedlings were analyzed. It was found that the plants supplied with sugar had been completely exhausted of their nitrates and had greatly increased in their amount of protein and in their dry weight as compared to the plants grown in the solution lacking sugar. Similar results were also obtained in like experiments with beans and potatoes. It was concluded by Suzuki that his results indicated that plants can assimilate nitrates in darkness and form protein provided there is a sufficient supply of sugar present in the cells. This same conclusion was reached by Hansteen (1896) in nutrition experiments with *Lemna minor*, by Prianischnikow (1899) in the study of the regeneration of protein in the onion, and by Muenscher (1923) in a study of protein synthesis in *Chlorella*.

There is considerable experimental evidence which indicates that protein synthesis may occur in any part of the plant regardless of light. Thus Müller-Thurgau (1894) grew plants under such a condition that part of the roots of an individual plant extended into a complete nutrient solution containing assimilable nitrogen and the other part into a nutrient

solution lacking the nitrogen. The roots in the nitrogen solution were profusely branched and showed a thrifty growth, while those growing in the solution lacking nitrogen were very poorly branched and showed lack of vigor. Müller-Thurgau believed that this indicated that nitrogen can be assimilated in the plant without going to the leaves.

Iwanoff (1901) worked with the roots of *Brassica napus*, *Daucus carota*, and *Solanum tuberosum* and concluded that an increase of protein can take place in the roots of these plants in the absence of light only when certain conditions prevail. The conditions necessary are a small amount of protein, a large supply of amides, and a considerable quantity of usable carbohydrates. Bambacioni (1923) made chemical analyses of plants of *Vicia faba*, *Ricinus communis*, and *Cucurbita pepo*, which were grown in a full nutrient solution and in the same solution lacking nitrogen and considered that his data indicated that all parts of the plant may manufacture organic nitrogenous substances. He found that the increase of these was greater in the roots than in the aerial parts and believed that it was probable that protein substances migrate from the roots to the aerial parts, since roots cut off and immersed in complete solutions contain more nitrogen than the roots of the intact plants immersed in such a solution.

The experimental evidence in nearly all cases indicates that protein formation may take place in any of the living cells of the plant provided that a supply of carbohydrates and of the proper nitrogenous compounds and other constituents is present and that light is not directly essential to the process. Protein synthesis may take place to a greater extent in the leaves than in other parts of the plant, due primarily to the abundant supply of carbohydrate in them as a result of photosynthesis. Recent work by Tottingham and Lowsma (1928), however, indicates that the shorter visible light rays may greatly enhance the absorption of nitrate and significantly increase the synthesis of protein as evidenced by the early growth of wheat. Long ultra-violet rays seem to be effective in the absorption of nitrate but gave no evidence of any further rôle.

4. Formation of Protein in Seeds.—Since the greater amount of the protein that occurs in plants is stored as a reserve in seeds, it is of interest to consider the question of its origin. Wassilieff (1908) observed that the disappearance of asparagin at the maturity of seeds is accompanied by an increase in protein material. The production of this amide nitrogen is accompanied by a decrease in amino nitrogen. It was noted by Schulze and Winterstein (1910) and Schulze (1911) in the case of legumes that in the unripe seed there were found along with the proteins small quantities of asparagine, mono-amino acids, arginine, and histidine. They also observed that in the hulls of the unripe seeds tryptophane occurred in appreciable quantities, while in the developing seed but little occurred. In the leaves and stems asparagin occurred in considerable

amounts, while in the maturing seed it occurred in only very small quantities. These investigators considered these data as indicating that the above-mentioned nitrogenous compounds are the materials from which the protein of the seed are synthesized. Zaleski (1911) observed in the maturing seeds of the pea and corn which had been taken from the plant and kept in moist air for varying periods that the protein increased in amount while the other nitrogenous compounds decreased as illustrated in the following data in the case of ripening peas (Raber, 1928):

Time	Protein, per cent	Amino acids, per cent	Nitrogen bases, per cent	Other nitrogen compounds, per cent
Beginning.....	79.2	8.7	10.8	1.4
After 5 days	89.2	4.6	5.6	0.8

Zaleski thus concluded that these nitrogenous compounds furnish the materials from which the proteins are formed.

The development of the wheat grain has been studied more in detail than the development of any other seed and considerable information has been obtained concerning the formation of its protein. It will be necessary to discuss here in detail the development of the wheat grain, since the reactions involving protein formation are closely involved with and cannot be separated from the reactions of other processes. In the formation of the wheat grain, three stages may be distinguished (Brenchley and Hall, 1908 to 1910): (a) a period during which the pericarp is the most prominent feature, (b) a main period during which the endosperm is filled, and (c) the ripening period which is characterized by the desiccation of the grain.

According to Eckerson (1917), at the time of spike formation the largest amount of potassium nitrate is found in the tissues of the root and stem. A continuous stream of sugars and amino acids moves from the leaves of the culms into the young spike. There are present in the vascular elements of the culms fructose, glucose, some arginine, histidine, considerable asparagin, and a large amount of potassium nitrate. The cells of the primordia of the flower contain much fructose and asparagine. The primordia of the stamens, pistils, and glumes are alike chemically, but when the sporogenous tissue is developing, phosphates begin to enter the stamens and pistils while the magnesium oxalate crystals in the spike disappear and magnesium appears in the sporogenous cells. Phosphates continue to move into the sporogenous tissue until the pollen grain and egg are formed. It appears that the greatest absorption of phosphates is during the shooting period. It seems thus that the greatest absorption of phosphates is at the time that they are being assimilated

most actively, while nitrates are absorbed in large quantities by the young plant and are utilized much later in the development.

After the fertilization of the egg there is a continuous stream of nutrient materials moving into the endosperm from the leaves and glumes. These materials include fructose and glucose, asparagin, arginine, histidine, and leucine. As the outer membrane of the nucellus becomes suberized, the current of sugar and amino acids passes from the base of the grain up through the raphe, enters the embryo sac at the chalazal region, and passes down through the endosperm cells to the embryo. Starch is formed in the endosperm cells soon after wall formation. It continues to increase in amount until desiccation begins or as long as the leaves and glumes are green and form an excess of sugar. The nitrogen compounds present, aside from aleurone and protoplasm in the endosperm, just before the ripening of the grain are a large amount of asparagin, considerable arginine, histidine, and some leucine but no glutamine. Thatcher (1913, 1915) found that there was an increase in the actual quantity of all the materials in the kernel with the exception of sugar during each successive period of growth. The decrease in the amount of sugar is due to its condensation into starch. The carbohydrate-protein ratio is at first greater and then becomes less in the developing kernel than in the pericarp material at the beginning of the experiment.

Eckerson (1917) states that in the full-grown, still green wheat kernel containing about 90 per cent moisture there is no storage protein in the endosperm. The aleurone layer and the layer of cells immediately below it contain more protoplasm than the other endosperm cells and give a protein reaction, but this is not storage protein. No storage protein is formed in the endosperm until desiccation begins. The main feature of the ripening process thus is desiccation, during which the condensation of nitrogenous compounds to proteins occurs. The percentage of water in barley was found by Harlan (1920) to be the highest at flowering time, when 80 per cent of the caryopsis was water. From flowering time until maturity the water content gradually decreased until at maturity it amounted to 40 per cent. This percentage decrease is very uniform, and Harlan found in his experiments that it amounted to 2 per cent per day, while Brenchley (1912) found that it averaged about one per cent per day. The maximum dry weight of grain is attained a day or two before the grain should be regarded as ripe in practice. This is in agreement with the observations of Spitzer, Carr, and Epple (1919), who found that the total nitrogen of soft corn is only slightly lower than that of mature corn but that the amide nitrogen is much higher in the former than in the latter. It is also in agreement with the observation of Olson (1917), who states that the nitrogenous compounds of the wheat kernel are at first very simple but change to the more complex forms as the period of desiccation advances.

5. Factors Which Influence the Percentage of Protein in Grains.—

The amount of protein in seeds and grains varies with different species and varieties of plants and with the conditions under which the plants are grown. The factors which influence the percentage of proteins in the cereals have received considerable attention, since the amount of protein in the grain, especially in wheat, determines to a certain degree its market value. A certain amount of protein is necessary in the wheat grain in order to produce a high quality of flour. In certain regions the wheats are especially low in protein so that high-protein wheats must be mixed with them in order to obtain a flour of good baking qualities.

The factors or causes which influence the percentage of protein in grains are apparently numerous and include the general weather conditions prevailing during the growing season, the time of nitrogen application, the available nitrogen, length of the growing season, available water, and certain unknown genetic factors. These factors are all more or less interrelated, so that in any discussion concerning them it is impossible to separate one from the other.

a. Time of Application of Nitrogen.—It is generally agreed that the available nitrogen is a very important and in many cases the greatest factor in determining the yield and quality of wheat (Burke, 1925; Ames, 1910; Whitson, Wells, and Vivian, 1903). As stated by Gericke (1927), however, the peculiarities of the varieties may determine the effect of fertilizer upon the protein content of the grain. The properties of wheat varieties can and do markedly affect the efficiency of any fertilizer treatment.

Davidson and Le Clerc (1917, 1918, 1923) applied nitrogen to wheat plants when they were two inches high, at heading and at the milk stage. They found that the application of nitrogen in any of the inorganic forms used at the early stages of growth was instrumental in producing the highest yields of wheat, while the application of nitrogen in any form at the time of heading produced the highest protein content. When nitrogen was applied at the milk stage, it had no effect either on the yield or upon the composition or quality of the grain. The period between the resumption of growth of wheat in the spring and at the time of heading was divided into three parts (Davidson, 1922), each of three corresponding sets of plots receiving nitrates at one of these subperiods. It was found that the effectiveness of increasing yields decreased consistently as the time of the application of nitrates approached the heading stage, while the reverse was true as regards the effectiveness of the nitrates in increasing the protein content of the grain.

Gericke (1920, 1922) applied nitrogenous fertilizers to the soil at planting time of wheat, oats, and rye in some cases and at different periods thereafter in others. In experiments with spring wheat, nitrogen

was applied at planting time, at 17, 33, 48, 72, and 110 days after planting. The protein content of the grain produced under each of these applications taken in the same order as above was 8.6, 9.3, 10.4, 11.8, 13.2, and 15.2 per cent of the dry weight. The data thus show an increase of 77 per cent in the protein content of the grain obtained from plants that received their nitrogen 110 days after planting over those which were treated with nitrogen at the time of planting. Practically the same results were obtained with oats and rye. Later, as mentioned above, it was found that the response in the protein content of the grain was different for different varieties of plants. The composition of the soil, however, was found by Shaw and Walters (1911), Thatcher (1913), and Le Clerc and Yoder (1914) to have little effect on the protein content of the grain under the conditions of their experiments and with the varieties with which they worked. In this connection it might also be mentioned that Lipman and Blair (1916) found that the liming of the soil increased the percentage of protein in soybeans. Stark (1924) in the case of soybeans noted that the application of limestone and organic matter increased the percentage of protein, while potassium in addition to these compounds gave a decrease in the percentage of protein.

b. Soil Moisture.—In general, it may be said that the protein content of grains varies inversely with the total rainfall. Neidig and Snyder (1922, 1924, 1926) found in the case of Marquis and Palouse blue-stem wheats that under field conditions available nitrogen shows its greatest effect on protein content and yield of wheat when climatic factors are most favorable and that both the climatic factors and available nitrogen play an important part in the quality of the wheat. It is considered that the importance of climate is chiefly due to its effect upon the availability of the nutrients in the soil, which, in turn, affect the nutrition of the plant. Neidig and Snyder (1924) noted that under field conditions a high moisture content properly distributed during the growing season in an average soil will produce a high-yielding wheat with a low protein content. Thatcher (1913) found that the increase in protein content of wheat in eastern Washington decreased with an increase in rainfall. Greaves and Carter (1923) observed a decrease in the nitrogen content of wheat, oats, and barley as the irrigation water used in their growth was increased. The decrease in the nitrogen content of the grain of wheat, oats, and barley amounted to 21, 40, and 19 per cent, respectively. Stewart and Greaves (1909) also observed that wheat grown on arid non-irrigated land contained more protein than was found in wheat on adjoining irrigated land. Greaves and Nelson (1925) showed that corn grown with and without irrigation water and manure gave a decrease in the nitrogen content of the kernel due to irrigation water and an increase due to the manure, the nitrogen content of the grain being a function of the available nitrogen content of the soil.

As a rule, however, the composition of corn is modified little if at all by variations of nutrient treatments or of climatic factors, as is indicated by the fact that the nitrogen content of corn seed from widely separated sections is approximately the same. Tottingham (1924) and Tottingham and Kerr (1926) found in the case of Leaming Yellow Dent corn grown in soil in the greenhouse that variations in the amounts and time of application of sodium nitrate did not modify the nitrogenous content of the cured seed.

These investigators found that the leaves of corn are characterized by low proportions of total soluble nitrogen and soluble protein as contrasted with high values for these factors in wheat and sugar beets, plants whose composition responds readily to changes of climatic conditions. Corn leaves are characterized by low proportions of reducing sugars, while the sugar-beet leaf contains much more reducing sugar than sucrose in the tests that have been made. Tottingham (1924) believed that sucrose and less soluble forms of protein are quite likely to be less altered by the effects of temperature and other climatic factors than are such reactive compounds as glucose, soluble proteins, and other soluble nitrogenous compounds. Tottingham (1923) found that the composition of red clover (*Trifolium pratense*) and buckwheat was greatly altered by changes in the environmental conditions.

6. Yellow Berry in Hard Winter Wheats.—In connection with the protein content of wheat, the nature of yellow berry and the factors that influence it should be taken into consideration. The term "yellow berry" has been defined by Roberts and Freeman (1908) as the appearance in hard, flinty wheats of grains of a light-yellow color, opaque, soft, and starchy. These opaque yellow grains may have this character throughout, or sometimes from a small fraction to half of a grain will be yellow and starchy while the remainder of the kernel will be hard, flinty, and translucent. The difference in color between the flinty grains and the "yellow berries" is due to differences in the structure and content of the cells of the endosperm. Considerable attention has been given to the causes of yellow berry. Lyon and Keyser (1905) concluded that the amount of yellow berry increases with the lateness of ripening and that crops of large yield and low nitrogen content contain more yellow berries than do crops of opposite kinds. Roberts and Freeman (1908) found that there was a diminution in the amount of yellow berry corresponding to the shortening of the fall growing period on account of late planting. They found, in general, that late ripening increased it and that higher mean temperatures three weeks before ripening were found to be correlated with low percentage of yellow berry. Headden (1915) reported that the application of nitrogen in the form of sodium nitrate greatly reduced the amount of yellow berry and in some cases prevented it altogether under the conditions prevailing in Colorado. He found also that yellow

berry could be greatly increased by the application of available potassium. He considered that the occurrence of yellow berry indicates that potassium is present in excess of that necessary to form a potassium-nitrogen ratio favorable to the formation of hard, flinty kernels. Roberts (1919) concluded that the operation of common causes for the production of yellow berry overshadows any differences that may be due to hereditary tendencies and precludes a definite statement concerning the influence of hereditary factors in this regard. Some isolated forms of wheat are, however, apparently freer from the condition of yellow berry than others growing in the same field. Jones and Mitchell (1926) found that thorough tillage of summer fallow in contrast to poor tillage resulted in larger yields and correspondingly less yellow berry. They consider that yellow berry is the manifestation of nutritional disturbances resulting from an insufficiency of nitrogen and other elements for adequately meeting the requirements of a normally developing crop. Since no means appear feasible as yet for protecting dry farmed lands against the gradual depletion of their native supply of nitrogen, high efficiency in the control of yellow berry cannot be maintained indefinitely by tillage.

In conclusion it should be stated that yellow berry is apparently different from ordinary soft wheat, since it is produced under apparently the same conditions as the flinty kernels, not merely in the same field, but on the same plant or in the same head.

IV. NITROGEN BASES IN PLANTS

The nitrogen-containing compounds in plants may, for the most part, be regarded as derived from ammonia by the replacement of one or more of the hydrogen atoms by organic radicles of various types. The nature of these replacements in the formation of amino acids and amides has already been discussed, and it is the intention here to make a statement concerning the general nature of the amines. The replacement of one or more hydrogen ions of ammonia by alkyl groups gives rise to compounds strongly basic in nature and known as "amines." There are three different classes of amines designated as primary, secondary, and tertiary accordingly as one, two, or three of the hydrogen atoms of ammonia have been replaced by the organic radicles above mentioned. The nitrogen bases in plants are amines of these three classes and may be divided into three main groups, (a) the plant amines, (b) the alkaloids, and (c) the purine bases.

A. PLANT AMINES OR NATURAL BASES

These are simple, open, chain amines. Some of the plant amines are trimethyl amine, a volatile compound which occurs in the seeds of *Mercurialis annua* and in the flowers of *Crataegus oxyacantha* and in the leaves of *Chenopodium vulvaria*; and betaine and choline, which occur together frequently in the embryo of *Hordeum sativum*, *Triticum sativum*, *Vicia sativa*, and other plants. Betaine occurs also in the juice of the beet and in the tubers of the Jerusalem artichoke, while choline occurs in the root of *Acorus calamus*, in the endosperm of *Cocos nucifera*, and in many other plants (Haas and Hill, 1913). There is no known physiological use for these simple amines in the plant. They are regarded by some as intermediate products in the synthesis or decomposition of proteins, but there are no data to warrant such a statement.

B. ALKALOIDS

The alkaloids are compounds which for the most part are composed of carbon, hydrogen, oxygen, and nitrogen, but a few, as coniine and nicotine, contain no oxygen. The alkaloids differ widely in structure but are related, for the most part, to heterocyclic compounds, as pyridine, quinoline, and isoquinoline. The term "alkaloid" literally means an alkali-resembling substance, since the compounds of this type have properties similar to those of the alkalis in being able to form salts with acids which are usually soluble in water.

The alkaloids are precipitated from their solutions by the so-called "alkaloid reagents" among which are tannins, phosphomolybdic acid, phosphotungstic acid, picric acid, and potassium mercuric iodide. The majority of the alkaloids are optically active rotating the plane of polarized light to the left, although a few such, as coniine, are dextrorotatory. The alkaloids, in general, are colorless, odorless, crystalline, and have a bitter taste, although there are a number of exceptions in one or more of these regards. They are generally insoluble in water but are easily soluble in organic solvents as chloroform, carbon tetrachloride, and ether. The alkaloids generally do not occur in the plant as such but are combined with acids in the form of a salt. Some of the acids which are combined in this manner are tannic, malic, citric, succinic, and oxalic. The alkaloids are generally set free in extraction by the addition of an alkali as lime or barium, since only the free bases and not their salts are soluble in the solvents above mentioned.

The alkaloids are very limited in their distribution in the plant kingdom, occurring, for the most part, in the *Leguminosae*, *Papaveraceae*, *Ranunculaceae*, *Rubiaceae*, and *Solanaceae*. They may occur in solution in the cell sap in the young parenchyma or may be stored in older tissue in the solid state. They are generally found in the seeds and fruits, but some occur in the leaves, stem, and roots (Haas and Hill, 1913).

Some of the alkaloids are coniine in *Conium maculatum*; nicotine in tobacco; atropine, which is the principal alkaloid in the deadly nightshade; cocaine in cocoa leaves; quinine, which is the most important alkaloid of the 24 found in chinchona bark; strychnine in the seeds of *Strychnos nux vomica*; and morphine, which is the principal alkaloid of the 20 that are found in the juice of the poppy.

The origin of the alkaloids in the plant is not definitely known. Some consider that they arise in the formation of proteins, while others consider that they are formed in the disintegration of the proteins. In general, they are considered as nitrogenous waste products which the plant is incapable of eliminating but which are rendered non-injurious to the plant by being stored in this condition. It would seem, however, that the connection of alkaloids with protein metabolism is not a common relationship, since it is manifested by such a limited number of species.

C. THE PURINE BASES

The purine bases are complex compounds containing a nucleus with four carbon atoms and four nitrogen atoms arranged alternately to form a double-ring group. They are a group of compounds all of which are derivatives of the compound purine, $C_5H_4N_4$. Under this list are included caffeine or theine in coffee and tea; theobromine in the fruit of *Theobroma cacao*; xanthine; hypoxanthine; guanine in sprouting seeds; and adenine, which occurs in the juice of beets. Uric acid, a purine base which does not occur in plants but which is a waste product of the metabolism of animals, is of interest in regard to the nature of the purine bases found in plants. The close relationship between this substance and the purine bases found in plants suggests that the latter might be considered as waste products in the protein metabolism of the plant.

V. LOSS OF NITROGEN FROM PLANTS

One of the most striking differences between the metabolism of animals and plants is that the former continually eliminate nitrogen compounds to the outside world, while plants rarely if ever eliminate nitrogen in any form. The nitrogenous compounds eliminated by animals are chiefly urea, uric acid, ammonia, and others, all of which result from the breaking down of proteins and the protoplasm. These same compounds are apparently formed in the life processes of the plant cell but are again directly utilized in the formation of new protein compounds and not eliminated as in animals.

Fosse (1913) proved that urea is present in the leaves of carrot, spinach, in potato tubers, root of the turnip, and in the seedlings of pumpkin, wheat, rye, clover, beet, pea, and corn. In the resting seed of wheat, corn, and pea it was present in amount equal to one centigram per kilo of weight. Fosse has proved that the urea detected was formed within the plant and was not absorbed directly from the soil where it is known to be present. Chibnall (1922), in working with the changes of protein in the leaves of the runner bean, found that their products of protein disintegration pass into urea derivatives that have a striking analogy to what is found in the animal kingdom.

In the germination of seeds where the processes of metabolism are very intense, the question of the loss of nitrogen in the gaseous form is somewhat in doubt. Schulz (1862) and Atwater and Rockwood (1886) reported appreciable losses of nitrogen during germination, but Boussingault (1838) and Hellriegel (1855) and more recently Davidson (1923) found only negative evidence of nitrogen loss. Davidson (1923) grew cowpeas and two varieties of soft winter wheat under sterile conditions in Kjeldahl flasks so that no transference of seedlings was necessary in the analyses. The seedlings were grown for 15 days and the nitrogen content of the growing seedlings and that of the sterilized seeds was found to be identical. One is thus justified in concluding that no nitrogen in the gaseous form is lost during the early stages of these seedlings. Davidson (1926) found that wheat seedlings floating on distilled water differ in composition from the stock seed from which they were obtained. In 7 days from the time the seeds were set to germinate, or 3 to 4 days after germination, the nitrogen content of the seedlings was approximately 10 per cent higher than the nitrogen content of the stock seeds. This fact seems to be due to the leaching of the nitrogen from the ungerminated seeds and its reabsorption by the growing seedlings. The reserve in these seeds is mostly carbohydrate and it would seem advisable that the loss of nitrogen should be investigated in the germination of seeds in which the major portion of the reserve material is of an oily nature.

Miller (1910) in studying the chemical changes in the germination of the sunflower seed found evidence which indicated that there might be a

loss of nitrogen from these seeds during the first 3 days of their germination. The total nitrogen in 100 seeds before germination amounted to 346 mg. and at the end of the 3-day period, when the hypocotyls were 2.5 to 3.5 cm. in length, the total nitrogen of 100 seedlings amounted to 292 mg.—a loss amounting to approximately 15 per cent of the total nitrogen present in the seed. The total nitrogen in the seedlings at four other more advanced stages showed no loss of nitrogen whatsoever. Newcomb and Miller (1927) determined the nitrogen content of the seeds and seedlings of the sunflower and squash. They obtained data which indicated that a loss of nitrogen occurred during the germination of these seeds, the loss amounting to from 5 to 6 per cent of the nitrogen content of the seed. This loss occurred while the hypocotyl and radicle were attaining a length of 4 to 5 cm. Several sources of error were overlooked, however, and a more careful study of this subject is needed before any definite statements can be made. Although the question of the loss of nitrogen from the germinating seed seems as yet not to be definitely settled, the loss of nitrogen from plants growing in the field seems to be confined wholly to the diffusion outward of nitrogenous salts into the soil, to the leaching of the stems and leaves by rains, and to the falling off of certain parts of the plants.

VI. CARBON/NITROGEN RATIO

Reproduction in plants, as well as their vegetative growth, may be controlled, to some extent at least, by varying their external and internal conditions. Recently it has been found that rather definite carbon and nitrogen relations in the plant influence its response in regard to vegetative growth and reproduction. The relationship of the carbon and nitrogen content of the plant has come to be expressed as the "carbon/nitrogen ratio," a term, however, that has been rather loosely used. To some it is the carbohydrate/nitrogen ratio; to others the carbohydrate/insoluble nitrogen ratio is the important one; others consider the effective ratio to be the starch/nitrogen; while yet others express the relationship as the ratio of the total carbon to the total nitrogen.

In 1916 Fisher reported that the vegetative condition was characterized by a carbohydrate content relatively low in proportion to the nitrogen or, in other words, by a low carbohydrate/nitrogen ratio. He found that the reproductive condition was characterized by a carbohydrate content relatively high in proportion to the nitrogen content, a condition which is designated as a high carbohydrate/nitrogen ratio. Kraus and Kraybill (1918) in their nutrition studies of the tomato plant brought out clearly that the carbohydrate/nitrogen ratio influences its growth and reproduction. They recognized four conditions which had a decided effect upon the behavior of this plant. These may be summarized as follows:

(1) A very high carbohydrate nitrogen ratio accompanying a weakly vegetative condition. Here nitrogen appears to be a limiting factor of growth and the high ratio is apparently due to the small amount of nitrogen present. (2) A high carbohydrate/nitrogen ratio accompanying abundant fruit production. In this type nitrogen compounds are available, but the high ratio is due to an excess of carbohydrates. (3) A low carbohydrate/nitrogen ratio accompanying a vigorous vegetative condition. In this type there appears to be an available supply of both carbohydrate and nitrogen and the balance between them is such as to produce the best vegetative conditions without leaving a residue of carbohydrate. (4) An exceedingly low carbohydrate/nitrogen ratio accompanying a weakly vegetative condition. In this type carbohydrates appear to be the limiting factor of growth and the low ratio is due to the small amount of carbohydrate present while the amount of nitrogen appears to be an indifferent factor.

Nightingale (1922) in experiments with salvia, buckwheat, soybeans, and radish concluded that the carbohydrate/insoluble nitrogen ratio is the effective one in relation to vegetative growth and reproduction in these plants. He considered that nitrates may be stored in the plant until the proper conditions arise for synthesis to other forms of nitrogen and that the presence of nitrates as such in the plant does not appear to affect materially the type of growth of the plant. Gurjar (1920) noted in the case of the tomato that the carbon/nitrogen ratio may be as high as 19 and as low as 2 but that the fruiting took place between the ratios 4 and 6.

Kraus and Kraybill (1918) also found that withholding moisture from plants grown under conditions of relative abundance of available nitrogen results in much the same condition of fruitfulness and carbohydrate storage as the limiting of the supply of available nitrogen. They further concluded that fertilizers containing available nitrogen or that which may be readily made available are mainly effective in producing vegetative response and that they may either increase or decrease fruitfulness according to the relative available carbohydrate supply. They also pointed out that pruning and girdling are largely effective in promoting or retarding fruitfulness by their effects in balancing the carbohydrate supply within the plant or the means for its manufacture with the available moisture and carbohydrate supply. These observations of Kraus and Kraybill have greatly stimulated investigations in regard to the carbohydrate/nitrogen ratio, since it offers a means of outlining methods of practice in regard to fertilizing, pruning, and ringing based upon physiological relations. It is not the intention here, however, to consider any of the methods of agricultural practice but to mention only some of the carbohydrate/nitrogen relationships that so far have been observed.

A. FRUIT-BUD FORMATION

The relationship of the carbohydrate/nitrogen ratio in regard to fruit-bud formation has been extensively studied in the case of the apple by Hooker (1920 to 1924), Roberts (1920), Harvey and Murneek (1921), Harvey (1923), and Kraybill (1923).

Hooker (1920 to 1924) in his investigations of the seasonal changes in the chemical composition of apple spurs found that conditions leading to high starch and low nitrogen content at the time of fruit-bud differentiation appear to be essential for productivity. Fruit-bearing spurs that develop leaf buds have a low starch and a high nitrogen content, and barren spurs, which neither blossom nor produce fruit buds, have a low starch and a low nitrogen content. The starch/nitrogen ratio was more indicative than the total carbohydrate/nitrogen ratio. Starting with an apple spur in the off year, it contains slightly less ash including K and P, less nitrogen, and less starch than a spur at the beginning of the bearing year, but it is higher in dry weight, reducing sugars, and polysaccharoses. During the spring, water is absorbed, the stored starch is hydrolyzed to sugar, and the sugar is utilized along with phosphorus and nitrogen in the production of new growth. During this period of the utilization of reserves and production of new vegetative tissue the acidity, polysaccharoses, and, to some extent, the K content increase. Eventually the supply of available carbohydrates is reduced to a minimum, whereupon terminal bud formation takes place on spurs. After this, growth practically stops and is accompanied by a falling off of acidity and polysaccharose content. By the photosynthetic activity of the newly formed leaves a fresh supply of reducing sugar is formed, some of which is stored in the form of starch and other polysaccharoses, resulting in an increase of dry weight. At the same time, the K and P content increase somewhat while the N content continues to fall off. As a result of this condition, leading to a high starch and a low nitrogen content late in June, fruit-bud differentiation occurs.

Hooker also found that the chief effects of spring applications of nitrogenous fertilizers to healthy apple trees are, on bearing trees, an increased set of fruit associated with a greater nitrogen content in the spurs during the period of fruit setting and, in non-bearing trees, an increased rate of growth. Spring applications of nitrogenous fertilizers do not favor starch accumulation at the period of fruit-bud differentiation, and consequently they could not be expected to favor the process. The later in the season nitrogenous fertilizers are applied the greater is the nitrogen content of the spurs the following spring immediately before growth begins.

It was observed by Roberts (1921), under conditions of low nitrogen nutrition, that the type and appearance of foliage and growth of the

apple tree are more influenced by the composition of the wood as a result of previous treatment than they are by the current seasonal conditions. Thus, for example, trees which were previously poor vegetatively made little growth when maintained in a low nitrogen nutrient, while trees that were previously very vegetative made an excellent growth after being transferred to a low nitrogen nutrient.

Harvey and Murneck (1921) and Harvey (1923) investigated the effects of defoliation and ringing of apple twigs and spurs with especial reference to the carbohydrate/nitrogen ratio. In the case of defoliation, it was found that the defoliated spurs, as compared to the checks, contained more nitrate nitrogen, total nitrogen, and insoluble nitrogen, more reducing sugars, and less total carbohydrates and a smaller value for the carbohydrate/nitrogen ratio. In general, the bearing and sterile spurs showed extreme values, while the non-bearing spurs assumed an intermediate position between them. Howlett (1923 to 1926) considered that the lack of an adequate supply of nitrogen, rather than a lack of carbohydrates, is more often the limiting factor to normal flower development in the case of the apple. Gardner (1923), in the case of the strawberry, reported that when moisture and temperature are not limiting factors, the number of flower clusters, number of flowers, and size of berries are dependent on nutritive conditions within the plant the preceding fall and winter and are practically independent of soil fertility conditions during the spring and at the time of fruiting. Treatments that would increase production through modifying fertility, therefore, should be given during the summer and fall months. He further stated that the maximum production of flower clusters, flowers, and berries was associated with those summer and fall treatments that led to the greatest accumulation of starch and total carbohydrates at the time of fruit-bud differentiation. Gardner also noted that low carbohydrate and low starch content at the time of fruit-bud differentiation led to the production of female flowers in a variety that is normally hermaphroditic. In the case of the strawberry, a low carbohydrate content is apparently associated with the female condition, high carbohydrate content with the male condition, and an intermediate carbohydrate content with hermaphroditism.

B. LENGTH OF DAY

It was observed by Garner and Allard (1920) in their investigations on the effect of the length of day and night upon growth and reproduction, that there are some plants which bloom and produce seed under light conditions of relatively short duration, but which when the length of day is increased become strongly vegetative and unfruitful. Other plants, however, require a long day to be reproductive and become weakly vegetative when the length of day is shortened. These observations led

to the assumption by some that the light requirements might be associated in some manner with the quantity of carbohydrates manufactured during the light period and its relationship to the nitrogen supply. A survey of the light responses, however, indicates that the problem is a complicated one and is difficult to interpret on the basis of photosynthetic activity. Thus, the effects produced are due not to the total quantity of radiation received but rather to the actual length of the exposure period. Plants exposed for long daily periods to sunlight of only one-fourth full intensity behaved similarly to plants exposed to full intensity for the same period and not in the same manner as plants exposed to full intensity for one-fourth the length of time. It is not known, however, whether the difference in total radiation was accompanied by differences in the photosynthetic activity, and other factors might have regulated or influenced the rate of photosynthesis.

The effect of the light period on the fertilizer requirements of plants was studied by Nightingale and Kraus (1924). They found in the case of tomatoes that light, within the limits of a 6-hr. day, did not appear markedly to limit the building up of nitrates to insoluble forms of nitrogen, provided there was present an available supply of carbohydrates. Buckwheat, soybeans, radish, and salvia of the varieties used were limited, however, in the building of nitrates to insoluble forms of nitrogen by a 7-hr. day, as it occurred in the greenhouse, even though there was present an available supply of carbohydrates.

C. DIFFERENT STAGES OF GROWTH

The value of the total carbon/total nitrogen ratio was determined by Hicks (1928) for different stages of growth of Starling winter wheat and of Nevin and Marquis spring wheats. The stages considered were (1) the seedling stage up to the active photosynthetic action of the first leaf and the exhaustion of the seed's store of food, (2) the vegetative cycle up to the heading period, and (3) the fruiting stage.

The seedling stage is characterized by a rapid drop in the carbon and nitrogen percentage. Carbon is lost by respiration, but most of the reserve in the endosperm is taken into the embryo. No nitrogen is lost, but the actual amount is increased by the withdrawal of the reserves from the endosperm, although the percentage is decreased owing to the increased dry weight of the young plant. The carbon/nitrogen ratio in the seedling stage remains low, is constant, and is of practically the same value as that of the ungerminated embryo. The vegetative cycle opens with a low carbon and fairly high nitrogen and with a low carbon/nitrogen balance. After the emergence of the first leaf and the beginning of active photosynthesis, there is a rise in the carbon curve. The carbon/nitrogen ratio shows a marked increase throughout the whole vegetative period. At the time of the highest carbon/nitrogen ratio, flower initials

appear and a general movement in the plant of the carbohydrates and the soluble nitrogen constituents through the stem and into the reproductive parts occurs. After fertilization, the carbon/nitrogen ratio decreases in the developing organs until a very low value is shown by the mature embryo. Hicks further observed that the three strains of wheat showed differences in the rate of carbon accumulation. In winter wheat it accumulates very slowly, the plant maintaining an intermediate carbon/nitrogen ratio. A much higher carbon/nitrogen ratio is required to produce flowers in the winter wheat than in the spring types. Thus a carbon/nitrogen ratio of 14 to 17 covers the range of conditions favorable to flowering in the spring wheats, while a ratio of 31 was required by the winter wheat. Hicks concludes that although each strain examined had its own initial carbon/nitrogen ratio value at which flowers are initiated, it represents in every case the maximum of the ascending carbon/nitrogen ratio curve.

D. VARIATIONS OF RATIO IN DIFFERENT ORGANS OF THE PLANT

The carbon/nitrogen ratio for different parts of the wheat plant was determined by Hicks (1928) at different stages of growth. In the case of a plant in the vegetative phase at the tenth leaf stage, the carbon/nitrogen ratio at the base of the stem was 13.7, at the middle of the stem 12.4, and at the upper portion 11.9. In the case of the tenth leaf, the lower half had a carbon/nitrogen ratio of 8.1 while the upper half had a ratio of 6.5. The carbon content was practically constant throughout the length of the stem, but the nitrogen increased from the base upward. In the case of the roots of plants in the fruiting stage, the carbon/nitrogen ratio of the secondary roots was 19, while that of the root hairs was 15. Hicks concluded from these observations that as a general rule in developing annual plants "the younger the tissue the lower the carbon/nitrogen ratio."

E. EFFECT ON ROOT AND SHOOT GROWTH

Much study has been made on the effect of the relation of nitrogen and carbohydrates to root and shoot growth. Chandler (1919), in the case of peach trees, found that root development is increased less than top growth by the addition of nitrates, while Gericke (1922) states that an abnormally large root development of wheat seedlings, in proportion to that of tops, is primarily associated with a deficiency of nitrogen in the medium in which the plants are rooted. As mentioned in Chap. III, Turner (1922) found that barley and corn showed significant increases in ratios of tops to roots as the nitrate concentration of the solution was increased but that flax plants did not show such an increased ratio. When nitrogen is lacking in the nutrient medium, the plant is able to utilize in new growth the nitrogen that is stored within the plant. It

has been shown by Roberts (1921) that apple trees can absorb nitrogen, store it as a reserve, and later utilize it in growth. An abundant supply of carbohydrates stimulates root development. Thus it has been observed by Dachnowski (1914), Knudson (1916), Curtis (1918), and others that when twigs, cuttings, or plants are grown in sugar solutions an increased root development results.

Starring (1923) studied the effect of the carbohydrate/nitrogen content upon the production of roots on the cuttings of tomato and *Tradescantia* and found that the best production of roots is obtained from those cuttings which have a high content of carbohydrate. When carbohydrates are absent or low in amount, the cuttings develop no roots; and if there is sufficient carbohydrate merely to initiate the growth of roots, they make little or no growth. No wide differences in root development could be secured by varying the nitrogen content.

Reid (1924, 1926) investigated the behavior of cuttings taken from tomato plants that had been grown under conditions to produce the extremes in the carbohydrate/nitrogen ratio. Her results indicated that a high nitrogen supply plus a readily available supply of carbohydrates appears to furnish favorable conditions for shoot growth. A somewhat limited nitrogen supply plus a readily available supply of carbohydrates appears to furnish conditions for root growth, and, in general, the cutting has a tendency to do what the plant, from which it is taken, has been doing. She observed also that shoots are produced in greater number in light than in darkness. A greater quantity of roots is produced in darkness than in light by high carbohydrate cuttings with a moderately high internal nitrogen reserve and grown in solutions lacking nitrates. If, however, high carbohydrate cuttings with a lower nitrogen reserve are grown under the same conditions, a greater quantity of roots is produced in light than in darkness. Hicks (1928) obtained similar results in the case of normal cuttings of *Salix viminalis* and in those injected with KNO_3 and various sugars. She considers that the initiation of growth is due to stimulated respiration giving energy for the withdrawal of N into the bast and its consequent upward translocation, particularly to the buds. The injected sugars hasten this considerably, while KNO_3 in excess prevents the commencement of growth. Hicks concludes that shoots grow at the area of the lowest carbon/nitrogen ratio and roots at the highest. Reid (1926) also found that different kind of seedlings show very different growth responses which are often related to the chemical composition of the seed. Thus the higher the nitrogen in proportion to the carbohydrate content of the seed the higher the shoot/root ratios of the seedlings. The shoot/root ratios in seedlings ranged from 2.01 for low-protein wheat to 8.37 for sunflower. In the case of high-protein corn and high-protein wheat, the shoot/root ratios are higher than the corresponding types that are low in protein. It was

also found that with the exception of cotton seedlings, the shoot/root ratios of all types were increased by the addition of nitrates but that the seedlings of *Leguminosae* were the least responsive in this respect. Reid makes the significant statement that it is apparently inadvisable to draw conclusions as to the effect of mineral nutrients upon the subsequent growth of plants when the observations are based on growth responses during the first three weeks of growth only. Before studying the effect of an element or compound on growth it would therefore seem desirable to conduct experiments in which the storage supply of the element or compound in question has been at least partially exhausted by the seedling.

F. SIGNIFICANCE IN AGRICULTURAL PRACTICE

The investigations of the carbon/nitrogen ratio indicate its importance upon the vegetative growth and reproduction of plants. When, however, an attempt is made to formulate methods of agricultural practice based upon the carbon/nitrogen ratio, the complexity of the problem and the lack of definite information on this subject become evident. Little or nothing is known concerning the question of cumulative and reciprocal influences or the effect of the length of the growing season as influenced by weather upon the relations of carbon to nitrogen. In this regard it is necessary to consider not only the accumulation of reserves but also the relative rates of nitrogen absorption and of carbohydrate synthesis at the critical periods of growth (Knight, 1923). Hooker (1925) enumerates various ways in which the carbohydrate/nitrogen relations may be varied. Thus the carbohydrate content may be increased by girdling, by thinning, and by the application of nitrogen at certain times. It can be decreased by shading, by shortening the daily period of illumination, by defoliation, by heading, and by manuring with nitrogen. The nitrogen content, on the other hand, can be increased by manuring, by shading, by defoliation, and by certain types of pruning. It may be decreased by girdling or defoliation early in the season or by local suppression of growth through pruning, and in some cases the insoluble nitrogen may be increased by shortening the day. The nitrogen content may also be decreased by sod or intercrops.

In conclusion it may be stated that the facts that have been observed concerning the carbon/nitrogen ratio have thrown light only on many established practices, as, for example, manuring, pruning, and girdling, and have thus shown that certain fairly definite physiological processes occur as a result of these practices. The knowledge concerning the carbon/nitrogen ratio is thus at present not sufficient to formulate any methods of agricultural practice other than those which have long been established. The information that has been obtained in regard to the carbon/nitrogen ratio has helped to a certain extent to account for some of the conflicting results that have been obtained from certain agricultural

practices. It is now known that the results obtained from agricultural practices will depend upon both the internal and external conditions that prevail both before and after the plant has been treated.

Questions

440. What functions does nitrogen subserve in the plant? In what form does it occur in plants? In what amounts?

441. What is the general effects on plants of a large amount of nitrogen supply in the soil? Why is an abundant supply of nitrogen frequently the cause of shriveled grain?

442. In what forms does N exist in the soil? Name some plants that can utilize N in the form of ammonium salts. Name some that prefer nitrates. Why are ammonium salts frequently superior to nitrates as nutrients?

443. How effective are nitrites in plant nutrition? How do ammonium salts affect the nitrogen content of the plant as compared with nitrates? Why?

444. Enumerate the organic nitrogenous compounds that can apparently be utilized directly by plants. Discuss the accelerating action of small amounts of organic compounds on growth.

445. How does the balance of the inorganic nutrient solution influence the response of the plant to organic accessories? Of what practical significance is the direct utilization of organic compounds by plants?

446. In what forms and in what amounts does nitrogen occur in the air? What did each of the following contribute in the development of our present knowledge concerning the absorption of N from the air by plants: De Saussure, Ville, Lawes and Gilbert, Hellriegel and Wilfarth, Beijerinck, and Proszowski?

447. Discuss the evidence in regard to the ability of the algae to utilize the free nitrogen of the air. Discuss the evidence in regard to the power of the higher green plants to do this.

448. What are proteins? Where do they occur in the plant? In what three forms do they occur in plants? Where are proteins stored as reserves?

449. What are aleurone grains? What is their composition and structure? What is the aleurone layer?

450. Name the physical properties of the proteins. What is their chemical composition? What is known concerning the protein molecule? Give examples.

451. What are amino acids? Illustrate with examples. Why are the amino acids studied in connection with the proteins?

452. Enumerate the amino acids that have been obtained by protein hydrolysis and state some general facts concerning their composition and structure.

453. What are amides? Name two amides that are common in plants. Why do proteins react with a large number of reagents? Discuss the precipitation reactions of the proteins.

454. Discuss the following protein color reactions in regard to procedure, cause of reaction, and color obtained: biuret reaction, xanthoproteic reaction, Millon's reaction, Adamkiewicz's reaction, sulphur reaction.

455. What are amphoteric substances? To what is the amphoteric nature of the proteins due? What is the isoelectric point of a protein? Give some examples.

456. When does a protein behave as a base? As an acid radical? Why is the position of the isoelectric point a significant property of the proteins?

457. Upon what characteristics are proteins classified? Classify the plant proteins.

458. What are the simple proteins? Name the four main groups of the simple proteins of the plant. What are the albumins? Name four albumins that have been isolated from plants.

459. What are globulins? Name 10 plant globulins. What are the glutelins? Name the three that have so far been isolated. What are the prolamins? Name four prolamins. What are glutens?

460. What are conjugated proteins? How do true nucleoproteins differ from the nucleo compounds that occur in the nuclei of plant cells? What are derived proteins?

461. Distinguish between protooses, peptones, and peptides. Where and under what conditions do these compounds appear in the plant?

462. From what are proteins synthesized in the plant? What is the evidence in this regard? What is the source of the amino acids? Discuss the theory that protein is formed from "activated formaldehyde" and nitrates.

463. Why do nitrates need to be reduced in plants? In what quantity do nitrates occur in plant cells? In what part of the plant are they the most abundant? When are they the most abundant in the plant?

464. Under what conditions may the reduction of nitrates occur *in vitro*? In the plant? State in order the steps in the transformation of nitrates when supplied to tomato plants that have been deprived of nitrogen. What evidence is there that nitrate-reducing substances occur in plants?

465. What two difficulties are encountered in studying the protein metabolism of the leaf? What methods have been used for the extraction of protein from leaves?

466. State examples to show that the method of preparation of the material may influence the nature of the nitrogenous extract. How do plant diseases of the leaves affect their nitrogen constituents?

467. In what three conditions does the protein occur in the cells of the leaf? Discuss the methods by which each of these forms of protein may be obtained.

468. Discuss the four methods that may be used to determine the diurnal variation of the total nitrogen of the leaves and state the advantages and disadvantages of each of these methods.

469. Discuss the data that have been obtained in regard to the daily variation of the total nitrogen of the leaves.

470. What changes do the nitrogen compounds of the leaves undergo during a 24-hr. period? What four facts indicate that protein is formed in the leaves?

471. In what part of the leaf is protein manufactured? How is this determined? Give examples. Is light necessary for protein synthesis? Why? How has this been proved?

472. What protein compounds are found in developing seeds? Describe in detail the development of the wheat grain as determined by Brenchley and Hall and Ecker-son. At what stage of maturity is the protein developed?

473. Why is the protein content of the wheat grain of importance? Name five factors that may influence the protein content of grains.

474. Discuss the effect of the time of application of nitrogen upon the protein content of grain. The effect of the moisture content of the soil.

475. What is "yellow berry"? To what is the difference in color due? Enumerate the causes to which yellow berry has been attributed.

476. What is an amine? What three groups of amines occur in plants? What are the plant amines or natural bases? Name some of these amines and state where they occur in plants. What is their physiological function?

477. What are alkaloids? By what may they be precipitated? What are their general physical characteristics? In what form are they combined in plants? How may they be set free?

478. In what plant families are the alkaloids found? In what plant parts? Name some alkaloids and state the sources from which they are obtained. What is the origin of the alkaloids?

479. What are the purine bases? Name some purine bases found in plants. What appears to be their origin? Discuss the loss of nitrogen from the plant.

480. What is the carbon/nitrogen ratio? What other terms have been used to express this ratio? Name the four general conditions of the carbohydrate/nitrogen ratio that Kraus and Kraybill considered influenced the growth and reproduction of the tomato plant.

481. Discuss the data that have been obtained in regard to the relation between the carbon/nitrogen ratio and fruit-bud formation.

482. What is the relationship between the length of day and the carbon/nitrogen ratio? How does this ratio vary for different stages of growth of the plant?

483. How does the carbon/nitrogen ratio vary in the different organs of the plant? Discuss the effect of the carbon/nitrogen ratio on root and shoot growth.

484. Enumerate the various ways in which the carbon/nitrogen ratio may be attained. What is the significance of the carbon/nitrogen ratio in agricultural practice?

Bibliography

- ACQUA, C., 1910: The place in which nitrates are utilized by plants, *Expt. Sta. Rec.* **24**: 531.
- AMES, J. W., 1910: The composition of wheat. Influence of various factors on the phosphorus, potassium, and nitrogen content of the wheat plant, *Ohio Agr. Expt. Sta. Bull.* 221.
- ANDERSON, V. L., 1924: Some observations on the nitrate-reducing properties of plants, *Ann. Bot.*, **38**: 699-706.
- ASO, K., and T. SEKINE, 1914: Nitrites in plants. *Beih. Bot. Centrbl.*, **32**: 146-147; *Expt. Sta. Rec.* **33**: 627.
- ATWATER, W. O., and E. W. ROCKWOOD, 1886: On the loss of nitrogen by plants during germination and growth, *Amer. Chem. Jour.*, **8**: 327-343.
- BALY, E. C., I. M. HEILBRON, and D. P. HUDSON, 1922: Photocatalysis. II, The photosynthesis of nitrogen compounds from nitrates and carbon dioxide, *Jour. Chem. Soc.* (London), **121**: 1078-1088.
- , ———, and H. J. STERN, 1923: Photocatalysis. III, The photosynthesis of naturally occurring nitrogen compounds from carbon dioxide and ammonia, *Jour. Chem. Soc.* (London), **123**: 185-197.
- BAMBACIONI, V., 1923: Contribuzione alla conoscenza del luogo di formazione del sostanza organiche azotate nei vegetali, *Atti. R. Accad. Lincei Roma Rendiconto Cl. Sci. Mat. e. Nat.*, **32**: 108-110.
- BAUDISCH, OSKAR, 1921: The mechanism of reduction of nitrates and nitrites in process of assimilation, *Jour. Biol. Chem.*, **48**: 489-502.
- , 1923: On the formation of organic compounds from inorganic by the influence of light, *Science*, n.s., **57**: 451-457.
- BEYERINCK, M. W., 1888: Die Bacterien der Papilionaceen-Knöllchen, *Bot. Zeitung*, **46**: 725-735, 741-750, 757-771, 781-790, 797-802.
- BONQUET, P. A., 1916: Presence of nitrites and ammonia in diseased plants, *Jour. Amer. Chem. Soc.*, **38**: 2572-2576.
- BOTTOMLEY, W. B., 1917: Some effects of organic growth promoting substances (auximones) on the growth of *Lemna minor* in mineral culture solutions, *Proc. Roy. Soc. London*, B, **89**: 481-508.
- , 1919: The isolation from peat of certain nucleic acid derivatives, *Proc. Roy. Soc. London*, B, **90**: 39-44.
- , 1920: The effect of nitrogen-fixing organisms and nucleic acid derivatives on plant growth, *Proc. Roy. Soc. London*, B, **91**: 83-95.

- BOTTOMLEY, W. B., 1920: The growth of *Lemna* plants in mineral solutions and in their natural medium, *Ann. Bot.*, **34**: 345-352.
- , 1920: The effect of organic matter on the growth of various water plants in cultural solutions, *Ann. Bot.*, **34**: 353-365.
- BOUSSINGAULT, JEAN, 1854-1855: *Ann. Chim. et Phys.* 3 ser., tomes 41, 43.
- , 1838: Recherches chimiques sur le végétation enterprises dans le but d'examiner si les plantes prennent l'azote á l'atmosphère, *Ann. Chim. et Phys.*, **67**: 5-54.
- BRENCHLEY, W. E., and A. D. HALL, 1908-1910: The development of the grain of wheat, *Jour. Agr. Sci.*, **3**: 193-217.
- , 1912: The development of the grain of barley, *Ann. Bot.*, **26**: 903-928.
- BRIGHT, R. O., 1917: Assimilation of organic nitrogen by *Zea mays* and the influence of *Bacillus subtilis* on such assimilation, *Soil Sci.*, **3**: 155-197.
- BRISTOL, B. M., and H. J. PAGE, 1923: A critical enquiry into the alleged fixation of nitrogen by green algae, *Ann. App. Biol.*, **10**: 378-409.
- BURK, DEAN, 1927: Does the pea plant fix atmospheric nitrogen? *Plant Physiol.*, **2**: 83-90.
- BURKE, E., 1925: The influence of nitrate nitrogen upon the protein content and yield of wheat, *Jour. Agr. Res.*, **31**: 1189-1199.
- CAMPBELL, E. G., 1924: Nitrogen content of weeds, *Bot. Gaz.*, **78**: 103-115.
- CHANDLER, W. H., 1919: Some results as to the response of fruit trees to pruning, *Proc. Amer. Hort. Sci.*, **16**: 88-101.
- CHIBNALL, A. C., and S. B. SCHRYVER, 1920: The isolation of proteins from leaves, *Proc. Physiol. Soc. Jour. Physiol.*, **54**: 1-2.
- and ———, 1921: Isolation of proteins from leaves, *Biochem. Jour.*, **15**: 60-75.
- , 1922: The effect of low-temperature drying on the distribution of nitrogen in the leaves of the runner bean, *Biochem. Jour.* **16**: 599-607.
- , 1922, Distribution of nitrogen in the dead leaves of the runner bean, *Biochem. Jour.*, **16**: 608-610.
- , 1922: The distribution of nitrogen in the leaves of the runner bean, *Biochem. Jour.*, **16**: 344-362.
- , 1923: A new method for the separate extraction of vacuole and protoplasmic material from the leaf cells, *Jour. Biol. Chem.*, **56**: 333-342.
- , 1923: Diurnal variations in the total nitrogen content of foliage leaves, *Ann. Bot.*, **37**: 511-518.
- , 1924: Investigation on the nitrogenous metabolism of the higher plants. V, Diurnal variations in the protein nitrogen of runner bean leaves, *Biochem. Jour.*, **18**: 387-394.
- , 1924: The role of asparagine in the metabolism of the mature plant, *Biochem. Jour.*, **18**: 395-404.
- , 1924: Leaf protein metabolism in normal and abnormal runner bean plants *Biochem. Jour.*, **18**: 405-407.
- and C. E. GROVER, 1926: A chemical study of leaf cell cytoplasm. I, The soluble proteins, *Biochem. Jour.*, **20**: 108-118.
- , 1926: Leaf cytoplasmic proteins, *Jour. Amer. Chem. Soc.*, **48**: 728-732.
- CHRAPOWICKI, W., 1889: Beobachtungen über die Eiweissbildung in dem chlorophyll-führenden Pflanzen, *Arbeiten St. Petersburger Natur. Ges.*, **18**: 1-27.
- CIAMICIAN, G., and C. RAVENNA, 1919 and 1920: Sulla influenza di alcune sostanze organiche sullo sviluppo della piante, *Atti. R. Accad. Lincei Rend.*, **28**: 13-20; **29**: 7-13; *Bot. Abst.*, **6**: 194; **7**: 309.
- and ———, 1919 and 1920: Sul contengo di alcune sostanze organiche nei vegetali, *Gaz. Chim. Italiana*, **49**: 83-126; **50**: 13-46; *Bot. Abst.*, **5**: 292; **7**: 308.

- CLARKE, N. A., 1924: The soil organic matter and growth-promoting accessory substances, *Jour. Ind. Eng. Chem.*, **16**: 249-250.
- and E. M. ROLLER, 1924: "Auximones" and the growth of the green plant, *Soil Sci.*, **17**: 193-199.
- COHN, E. J., J. GROSS, and O. C. JOHNSON, 1919: The isoelectric points of the proteins in certain vegetable juices, *Jour. Gen. Physiol.*, **2**: 145-160.
- COONS, G. H., and L. J. KLOTZ, 1925: The nitrogen constituents of celery plants in health and disease, *Jour. Agr. Res.*, **31**: 287-300.
- COVILLE, F. V., 1926: Buttermilk as a fertilizer for blueberries, *Science*, n.s., **64**: 94-96.
- CROWTHER, E. M., 1925: A note on the availability of organic nitrogen compounds in pot experiments, *Jour. Agr. Sci.*, **15**: 300-302.
- CURTIS, O. F., 1918: Stimulation of root growth in cuttings by treatment with chemical compounds, *N. Y. Agr. Expt. Sta. Mem.* 14.
- DACHNOWSKI, A., 1914: The effects of acid and alkaline solutions upon the water relation and the metabolism of plants, *Amer. Jour. Bot.*, **1**: 412-439.
- DAIKUKARA, G., 1905: On the application of magnesium in the form of magnesium sulphate for the needs of the rice plant, *Bull. Imp. Cent. Agr. Expt. Sta. Japan*, **1**: 24-29.
- DAVIDSON, J., and J. A. LECLEERC, 1917 and 1918: The effect of sodium nitrate applied at different stages of growth on the yield, composition, and quality of wheat. I, II, *Jour. Amer. Soc. Agron.*, **9**: 145-154; **10**: 193-198.
- , 1922: The effect of nitrates applied at different stages of growth on the yield, composition, and quality of wheat, *Jour. Amer. Soc. Agron.*, **14**: 118-122.
- , 1923: Is gaseous nitrogen a product of seedling metabolism? *Bot. Gaz.*, **76**: 95-102.
- and J. A. LECLEERC, 1923: Effect of various inorganic nitrogen compounds, applied at different stages of growth on the yield, composition, and quality of wheat, *Jour. Agr. Res.*, **23**: 55-69.
- , 1926: Changes in nitrogen, potassium, and phosphorus content of wheat seedlings during germination and early stages, *Bot. Gaz.*, **81**: 87-95.
- ECKERSON, SOPHIA, 1917: Microchemical studies in the progressive development of the wheat plant, *Agr. Expt. Sta. State Coll. Wash. Bull.* 139.
- , 1924: Protein synthesis by Plants. • 1, Nitrate reduction, *Bot. Gaz.*, **77**: 377-390.
- EMMERLING, A., 1880: Studien über die Eiweissbildung in der Pflanze. I, *Landw. Versuchs-Stat.*, **24**: 113-160.
- , 1887: Studien über die Eiweissbildung in der Pflanze. VII, *Landw. Versuchs-Stat.*, **34**: 1-91.
- , 1900: Studien über die Eiweissbildung in der Pflanze, *Landw. Versuchs-Stat.*, **54**: 215-281.
- ESPINO, R. B., 1920: Some aspects of the salt requirements of young rice plants, *Phil. Jour. Sci.*, **16**: 455-525.
- FAGAN, T. W., 1925: The variation in the moisture and nitrogen content of the potato during growth and storage, *Welsh. Jour. Agr.*, **1**: 110-115; *Bot. Abst.*, **14**: 1441.
- FEHER, D., and I. VAGI, 1924, 1926: Untersuchungen über die Einwirkung von Nitriten auf das Wachstum der Pflanzen, *Biochem. Zeits.*, **153**: 156-158; **174**: 262-270.
- FISCHER, E., 1899-1906: "Untersuchungen über Aminosäuren, Polypeptide, und Proteine," 770 pp., J. Springer, Berlin, 1906.
- FISHER, H., 1916: Zur Frage der Kohlensäure-Ernährung der Pflanze, *Gartenflora*, **65**: 232-237.
- , 1917: Das Problem der Stickstoffbindung, Festlegung des Luftstickstoffs bei niederen Pflanzen, *Ber. d. d. bot. Ges.*, **35**: 423-454.

- FOSSE, M. R., 1912: Recherches sur l'urée, *Compt. Rend. Acad. Sci. Paris*, **155**: 851-852.
- , 1913: Formation de l'urée par deux moisissures, *Compt. Rend. Acad. Sci. Paris*, **156**: 263-265.
- , 1913: Formation de l'urée par les végétaux supérieurs, *Compt. Rend. Acad. Sci. Paris*, **156**: 567-568.
- , 1913: Recherche de l'urée dans les végétaux, *Compt. Rend. Acad. Sci. Paris*, **156**: 1938-1941.
- , 1914: Présence simultanée de l'urée et de l'uréase dans le même végétal, *Compt. Rend. Acad. Sci. Paris*, **158**: 1374-1376.
- FRANK, B., 1888: Untersuchungen über die Ernährung der Pflanze mit Stickstoff und über den Kreislauf desselben in der Landwirtschaft, *Landw. Jahrb.*, **17**: 421-553.
- , 1889: Ueber den experimentellen Nachweis der Assimilation freien Stickstoffs durch erdbodenbewohnende Algen, *Ber. d. d. bot. Ges.*, **7**: 34-42.
- and R. OTTO, 1891: New experiments concerning the assimilation of nitrogen by plants, *Expt. Sta. Rec.* **3**: 64.
- GARDNER, V. R., 1923: Studies in the nutrition of the strawberry, *Mo. Agr. Expt. Sta. Res. Bull.* **57**.
- GARNER, W. W., and H. A. ALLARD, 1920: Effect of the relative length of day and night and other factors of the environment on growth and reproduction in plants, *Jour. Agr. Res.*, **18**: 553-607.
- GERICKE, W. F., 1920: On the protein content of wheat, *Science*, n.s., **52**: 446-447.
- , 1922: Certain relations between the protein content of wheat and the length of the growing period of the head-bearing stalks, *Soil Sci.*, **13**: 135-139.
- , 1922: Differences effected in the protein content of grain by applications of nitrogen made at different growing periods of the plants, *Soil Sci.*, **14**: 103-109.
- , 1922: Certain relations between root development and tillering in wheat; significance in the production of high-protein wheat, *Amer. Jour. Bot.*, **9**: 366-369.
- , 1927: Why applications of nitrogen to land may cause either increase or decrease in the protein content of wheat, *Jour. Agr. Res.*, **35**: 133-141.
- GERLACH, M., and J. VOGEL, 1905: Ammoniakstickstoff als Pflanzennährstoff, *Centrbl. Bakt. und Parsit.* **11**, **14**: 124-138.
- GREAVES, J. E., and E. G. CARTER, 1923: The influence of irrigation water on the composition of grains and the relationship to nutrition, *Jour. Biol. Chem.*, **58**: 531-541.
- and D. H. NELSON, 1925: The influence of irrigation water and manure on the composition of the corn kernel, *Jour. Agr. Res.*, **31**: 183-191.
- GRIFFITHS, A., 1891: On the direct absorption of ammoniacal salts by certain plants, *Chem. News*, **64**: 147.
- GURJAR, A. M., 1920: Carbon nitrogen ratio in relation to plant metabolism, *Science*, n.s., **51**: 351-352.
- HAAS, P., and T. G. HILL, 1913: "An Introduction to the Chemistry of Plant Products," 401 pp., Longmans, Green and Co.
- HANSTEEN, B., 1896: Beiträge zur Kenntniss der Eiweissbildung und der Bedingungen der Realisirung dieses Processes in phanerogamen Pflanzenkörper, *Ber. d. d. bot. Ges.*, **14**: 362-371.
- HARVEY, E. M., and A. E. MURNEEK, 1921: The relation of carbohydrates and nitrogen to the behavior of apple spurs, *Ore. Agr. Expt. Sta. Bull.* **176**.
- , 1923: A study of growth in summer shoots of the apple with special consideration of the rôle of carbohydrates and nitrogen, *Ore. Agr. Expt. Sta. Bull.* **200**.

- HEADDEN, W. P., 1915: Yellowberry in wheat, its cause and prevention, *Colo. Agr. Expt. Sta. Bull.* 205.
- HELLRIEGEL, H., 1855: Beiträge zur Keimungsgeschichte der ölgebenden Samen, *Jour. Prakt. Chem.*, **64**: 94-107.
- and H. WILFARTH, 1888: Untersuchungen über die Stickstoffnahrung der Gramineen und Leguminosen, *Beilage. Zeits. Rüben zucker-Indust. d. Reich*, 234 pp.
- HICKS, P. A., 1928: The carbohydrate/nitrogen ratio in the wheat plant, *New Phytol.*, **27**: 1-46.
- , 1928: Distribution of carbon/nitrogen ratio in the various organs of the wheat plant at different periods of its life history, *New Phytol.*, **27**: 108-116.
- , 1928: Chemistry of growth as represented by carbon/nitrogen ratio, *Bot. Gaz.*, **86**: 193-209.
- HOOKE, H. D., 1920: Seasonal changes in the chemical composition of apple spurs, *Mo. Agr. Sta. Res. Bull.* 40.
- , 1922: Certain responses of apple trees to nitrogen applications of different kinds and at different seasons, *Mo. Agr. Sta. Res. Bull.* 50.
- , 1922: Some effects of fall application of nitrogen to apple trees, *Proc. Amer. Soc. Hort. Sci.*, **19**: 241-243.
- , 1924: Changes produced in apple trees by various types of pruning, *Mo. Agr. Expt. Sta. Res. Bull.* 72.
- , 1925: A survey of investigations by American horticulturists on carbohydrate-nitrogen relations, *Jour. Pom. Hort. Sci.*, **5**: 34-42.
- HOWLETT, P. S., 1923: Nitrogen and carbohydrate composition of the developing flowers and young fruits of the apple, *Amer. Soc. Hort. Sci. Proc.*, **20**: 31-37; *Cornell Agr. Expt. Sta. Mem.* 99 (1926).
- HUTCHINSON, H. B., and N. H. J. MILLER, 1909: Direct assimilation of ammonium salts by plants, *Jour. Agr. Sci.*, **3**: 179-195.
- and —, 1911: The direct assimilation of inorganic and organic forms of nitrogen by higher plants, *Centrbl. f. Bakt. II, Abt.*, **30**: 513-548.
- IRVING, A. A., and R. HAUKINSON, R., 1908: The presence of a nitrate reducing enzyme in green plants, *Biochem. Jour.*, **3**: 87-96.
- IWANOFF, M., 1901: Versuche über die Frage, ob in den Pflanzen bei Lichtabschluss Eiweissstoffe sich bilden, *Landw. Versuchs-Stat.*, **56**: 78-94.
- JODIDI, S. L., E. H. KELLOGG, and R. H. TRUE, 1918: Nitrogen metabolism in normal and in blighted spinach, *Jour. Agr. Res.*, **15**: 385-404.
- , S. C. MOULTON, and K. S. MARKLEY, 1920: The mosaic disease of spinach as characterized by its nitrogen constituents, *Jour. Amer. Chem. Soc.*, **42**: 1061-1070.
- , 1920: A mosaic disease of cabbage as revealed by its nitrogen constituents, *Jour. Amer. Chem. Soc.*, **42**: 1883-1893.
- and K. S. MARKLEY, 1923: The occurrence of polypeptides and free amino acids in the ungerminated wheat kernel, *Jour. Amer. Chem. Soc.*, **45**: 2137-2144.
- , 1924: Physiological studies on cereals. II, The occurrence of amino acids and polypeptides in the ungerminated oat kernel, *Jour. Franklin Inst.*, **198**: 201-211.
- , 1925: Physiological studies on cereals. III, The occurrence of polypeptides and amino acids in the ungerminated maize kernel, *Jour. Agr. Res.*, **30**: 587-592.
- and J. G. WANGLER, 1925: Physiological and biochemical studies on cereals. IV, On the presence of amino acids and polypeptides in the ungerminated rye kernel, *Jour. Agr. Res.*, **30**: 989-994.
- JONES, J. S., and G. A. MITCHELL, 1926: The cause and control of yellowberry in Turkey wheat grown under dry farming conditions, *Jour. Agr. Res.*, **33**: 281-293.

- KASTLE, J. H., and E. ELVOVE, 1904: On the reduction of nitrates by certain plant extracts and metals, and the accelerating effect of certain substances on the progress of the reduction, *Amer. Chem. Jour.*, **31**: 606-641.
- KELLEY, W. P., 1911: The assimilation of nitrogen by rice, *Hawaii Agr. Expt. Sta. Bull.* 24.
- KELLNER, O., 1884: Agriculturechemische Studien über die Reiscultur, *Landw. Versuchs Stat.*, **30**: 18-41.
- KINOSHITA, Y., 1897: On the assimilation of nitrogen from nitrates and ammonium salts by phanerogams, *Bull. Coll. Agr. Tokyo*, **2**: 200-202.
- KNIGHT, R. C., 1924: The carbohydrate/nitrogen ratio, *Sci. Prog.*, **19**: 34-42.
- KNUDSON, L., 1916: Influence of certain carbohydrates on green plants, *N. Y. Agr. Expt. Sta. Mem.* 9.
- KOSSOWITSCH, P., 1894: Untersuchungen über die Frage ob die Algen freien Stickstoff fixiren, *Bot. Zeitung*, **52**: 97-116.
- KOSUTANY, T., 1897: Untersuchungen über die Entstehung des Pflanzeneiweisses, *Landw. Versuchs-Stat.*, **48**: 13-32.
- KRAUS, E. J., and H. R. KRAYBILL, 1918: Vegetation and reproduction with special reference to the tomato, *Ore. Agr. Expt. Sta. Bull.* 149.
- KRAYBILL, H. R., 1923: Effect of shading and ringing upon the chemical composition of apple and peach trees, *N. H. Agr. Expt. Sta. Tech. Bull.* 23.
- KRÜGER, W., 1905: Ueber die Bedeutung der Nitrifikation für die Kulturpflanzen, *Landw. Jahrb.*, **34**: 761.
- LAKON, G., 1917: Der Eiweissgehalt panachierter Blätter geprüft mittels des makroskopischen Verfahrens von Molisch, *Biochem. Zeits.*, **78**: 145-154.
- LATSHAW, W. L., and E. C. MILLER, 1924: Elemental composition of the corn plant, *Jour. Agr. Res.*, **27**: 845-861.
- LAURENT, E., 1890: Expériences sur la réduction des nitrates par les végétaux, *Ann. Inst. Pasteur*, **4**: 722-744.
- LAWES, J. B., J. H. GILBERT, and E. PUGH, 1860: On the sources of nitrogen of vegetation; with special reference to the question whether plants assimilate free or uncombined nitrogen, *Phil. Trans. Roy. Soc.*, **151**: 431-578.
- LECLERC, J. A., and P. A. YODER, 1914: Environmental influences on the physical and chemical characteristics of wheat, *Jour. Agr. Res.*, **1**: 275-291.
- LIPMAN, C. B., and J. K. TAYLOR, 1922: Proof of the power of the wheat plant to fix atmospheric nitrogen, *Science*, n.s., **56**: 605-606.
- , and ———, 1924: Do green plants have the power of fixing elementary nitrogen from the atmosphere? *Jour. Franklin Inst.*, October, **1924**: 475-506.
- LIPMAN, J. G., and A. W. BLAIR, 1916: Factors influencing the protein content of soybeans, *Soil Sci.*, **1**: 171-178.
- LOEB, J., 1924: "Proteins and the Theory of Colloidal Behavior," 380 pp., McGraw-Hill Book Company, Inc.
- LYON, T. L., and A. KEYSER, 1905: Nature and causes of "yellow-berry" in hard winter wheat, *Nebr. Agr. Expt. Sta. Bull.* **89**: 23-36.
- MAMELI DE CALVINO, E., and G. POLLACCI, 1911: Sull' assimilazione diretta dell' azoto atmosferico libero nei vegetali, *Atti dell' Istituto Botan. di Pavia*, Ser. II, **14**: 159-257.
- , and ———, 1911: Ancora sull' assimilazione diretta dell' azoto atmosferico libero nei vegetali, *Atti. dell' Istituto Botan. di Pavia*. Ser. II., **16**: 197-203.
- , 1923: The direct assimilation of free nitrogen by plants. A review of recent work on the subject, *Torreya*, **23**: 99-104.
- , 1923: Sobre la assimilacion directa del nitrogeno libre por las plantas, *Estoc. Expt. Agron. (Cuba) Circ.* **59**: 3-7.

- MANGEL, C. E., 1927: Pre-harvest factors which affect wheat quality, *Cereal Chem.*, **4**: 376-388.
- MAZÉ, P., 1898: L' assimilation de l' azote nitrique et de l' azote ammoniacal par les végétaux supérieurs, *Compt. Rend. Acad. Sci. Paris*, **127**: 1031-1033.
- , 1900: Recherches sur l'influence de l'azote nitrique et de l'azote ammoniacal sur le développement du maïs, *Ann. Inst. Pasteur*, **14**: 26-45.
- MCGEORGE, W. T., 1923: The assimilation of nitrogen by sugar cane, nitrates vs. ammonium salts, *Planter's Rec.* **27**: 347-352.
- MEYER, ARTHUR, 1918: Eiweissstoffwechsel und Vergilben der Laubblätter von *Tropaeolum majus*, *Flora*, **11-12**: 85-127.
- MILLER, E. C., 1910: A physiological study of the germination of *Helianthus annuus*, *Ann. Bot.*, **24**: 693-726.
- , 1917: Daily variation of water and dry matter in the leaves of corn and the sorghums, *Jour. Agr. Res.*, **10**: 11-47.
- , 1924: Daily variation of the carbohydrates in the leaves of corn and the sorghums, *Jour. Agr. Res.*, **27**: 785-808.
- , 1926: Daily variation of the nitrogen in the leaves, unpub. data, *Kans. Agr. Expt. Sta.*
- , 1929: Nitrogen in the leaves of crop plants, unpub. data, *Kans. Agr. Expt. Sta.*
- MOCKERIDGE, F. A., 1917: Some effects of organic growth-promoting substances (auximones) on the soil organisms concerned in the nitrogen cycle, *Proc. Roy. Soc. B*, **89**: 508-534.
- , 1924: The formation of plant growth-promoting substances by microorganisms, *Ann. Bot.*, **38**: 723-734.
- MOLISCH, H., 1916: Die Eiweissproben makroskopisch angewendet auf Pflanzen, *Zeits. f. Bot.*, **8**: 124-131.
- MOORE, BENJAMIN and T. A. WEBSTER, 1919: The formation of nitrites from nitrates in aqueous solution by the action of sunlight and the assimilation of the nitrites by green leaves in sunlight, *Proc. Roy. Soc. B*, **90**: 158-167.
- , 1920: Studies of photosynthesis in fresh water algae. I, The fixation of both carbon and nitrogen from the atmosphere to form organic tissue by the green plant cell. II, III, *Proc. Roy. Soc.*, **B**, **91**: 201-215.
- , E. WHITLEY, and T. A. WEBSTER, 1921: Studies of photosynthesis in marine algae. I, Fixation of carbon and nitrogen from inorganic sources in sea water. II, *Proc. Roy. Soc.*, **B**, **92**: 51-60.
- MUENSCHER, W. C., 1923: Protein synthesis in *Chlorella*, *Bot. Gaz.*, **75**: 249-268.
- MÜLLER-THURGAU, H. 1894: Einfluss des Stickstoffs auf die Wurzelbildung, *Jahresbericht der Versuchs-Stat. in Wadensweil*, **4**: 48-52.
- MÜNTZ, A., 1889: Sur le rôle de l'ammoniaque dans la nutrition des végétaux supérieurs, *Compt. Rend. Acad. Sci. Paris*, **109**: 646-648.
- NAGAOKA, M., 1904: On the behavior of the rice plant to nitrates and ammonium salts, *Bull. Coll. Agr. Tokyo. Imper. Univ.*, **6**: 285-334; *Expt. Sta. Rec.* **16**: 560.
- NEIDIG, R. E., and R. S. SNYDER, 1922: The effect of available nitrogen on the protein content and yield of wheat, *Idaho Agr. Expt. Sta. Bull.* **1**.
- , and ———, 1924: The relation of moisture and available nitrogen to the yield and protein content of wheat, *Soil Sci.*, **18**: 173-181.
- , ———, 1926: The relation of the yield and protein content of wheat to the nitrogen content of the soil under ten years of different systems of cropping, *Agr. Expt. Sta. Univ. Idaho Res. Bull.* **5**.
- NEWCOMB, M. A., 1927: The loss of nitrogen from oily seeds, unpub. data, Master's thesis, *Kans. Agr. Coll.*

- NIGHTINGALE, G. T., 1922: Light in relation to the growth and chemical composition of some horticultural plants, *Amer. Soc. Hort. Sci. Proc.* **19**: 18-29.
- , and E. J. KRAUS, 1924: Does light affect the fertilizer requirements of plants? *Wis. Sta. Bull.* **352**: 52-54.
- OLSON, G. A., 1917: Gluten formation in the wheat kernel, *Wash. Agr. Expt. Sta. Bull.* **142**.
- , 1923: A study of factors affecting the nitrogen content of wheat and of the changes that occur during the development of wheat, *Jour. Agr. Res.*, **24**: 939-955.
- OSBORNE, T. B., and A. J. WAKEMAN, 1920: The proteins of green leaves. I, Spinach leaves, *Jour. Biol. Chem.*, **42**: 1-26.
- , and C. S. LEAVENWORTH, 1921: The proteins of the alfalfa plant, *Jour. Biol. Chem.*, **49**: 63-91.
- , 1924: "The Vegetable Proteins," mon., 151 pp., Longmans, Green and Co.
- PANTANELLI, E., and G. SEVERINI, 1910-1911: Some experiments on the utilization of ammonium salts by green plants, *Staz. Sper. Agr. Ital.*, **43**: 449-544; **44**: 873-908; *Expt. Sta. Rec.* **25**: 223, **27**: 634.
- PEARSALL, W. H., and J. H. PRIESTLEY, 1923: Meristematic tissues and protein isoelectric points, *New Phytol.*, **22**: 185-191.
- , and JAMES EWING, 1924: The isoelectric points of some plant proteins, *Biochem. Jour.*, **18**: 329-339.
- PERCIABOSCO, F., and V. ROSSO., 1909: L'assorbimento diretto dei nitrato nelle piante, *Staz. Sper. Agrar. Ital.*, **42**: 5-36; *Expt. Sta. Rec.* **23**: 724.
- PIGORINI, L., 1914: Studi sulla foglia di gelso; sulla composizione chimica della foglia al mattino e alla sera, *Atti. dei. Lincei.*, **23**: 433-437.
- PITSCH, O., 1887, 1893, 1896: Versuche zur Entscheidung der Frage, ob salpetersäure Salze für die Entwicklung unserer landwirtschaftlichen Kulturgewächse unentbehrlich sind oder nicht, *Landw. Versuchs-Stat.*, **34**: 217-258; **42**: 1-95; **46**: 357-370.
- POZZI-ESCOT, M-EMM, 1903: The reducing enzymes, *Amer. Chem. Jour.*, **29**: 517-563.
- PRAZMOWSKI, A., 1890: Die Wurzelknöllchen der Erbse. I, Die Actiologie und Entwicklungsgeschichte der Knöllchen, *Landw. Versuchs-Stat.*, **37**: 161-238.
- PRIANISCHNIKOW, D. N., 1899: Die Rückbildung der Eiweissstoffe aus deren Zerfallsprodukten, *Landw. Versuchs-Stat.*, **52**: 347-382.
- , 1908: Zur physiologischen Charakteristik der Ammoniums Salze, *Ber. d. d. bot. Ges.*, **26**: 716-724.
- , 1923: Sur l'assimilation de l'ammoniaque par les plantes supérieures, *Compt. Rend. Acad. Sci. Paris*, **177**: 603-606.
- PRIESTLEY, J. H., 1922: Some recent work on proteins in its relation to physiology, *Sci. Prog.*, **16**: 201-207.
- RABER, O., 1928: "Principles of Plant Physiology," 362 pp., The Macmillan Company.
- REID, MARY E., 1924: Relation of kind of food reserves to regeneration in tomato plants, *Bot. Gaz.*, **77**: 103-111.
- , 1924: Quantitative relations of carbohydrates to nitrogen in determining growth responses in tomato cuttings, *Bot. Gaz.*, **77**: 404-418.
- , 1926: Growth of tomato cuttings in relation to stored carbohydrate and nitrogenous compounds, *Amer. Jour. Bot.*, **13**: 548-575.
- , 1926: Growth of seedlings in relation to composition of seed, *Bot. Gaz.*, **81**: 196-203.
- , 1929: Growth of seedlings in light and in darkness in relation to available nitrogen and carbon, *Bot. Gaz.*, **87**: 81-117.
- ROBBINS, W. J., 1923: An isoelectric point for plant tissue and its significance, *Amer. Jour. Bot.*, **10**: 412-440.

- ROBERTS, H. F., and G. F. FREEMAN, 1908: The yellow berry problem in Kansas hard winter wheats, *Kans. Agr. Expt. Sta. Bull.* 156.
- , 1919: Yellowberry in hard winter wheat, *Jour. Agr. Res.*, **18**: 155–171.
- ROBERTS, R. H., 1920: Off year apple bearing and apple spur growth, *Wis. Agr. Expt. Sta. Bull.* 317.
- , 1921: Nitrogen reserves in apple trees, *Proc. Amer. Soc. Hort. Sci.*, **18**: 143–145.
- , 1923: Effect of defoliation upon blossom bud formation, *Wis. Agr. Expt. Sta. Res. Bull.* 56.
- ROBINSON, M. E., 1929: The protein metabolism of the green plant, *New Phytol.*, **28**: 117–150.
- RUSSELL, E. J., and E. H. RICHARDS, 1919: The amount and composition of rain falling at Rothamsted, *Jour. Agr. Sci.*, **9**: 309–337.
- SAEGER, ALBERT, 1925: The growth of duckweeds in mineral nutrient solutions with and without organic extracts, *Jour. Gen. Physiol.*, **7**: 517–526.
- SAPOZNIKOW, W., 1895: "Eiweisstoffe und Kohlenhydrate der grünen Blätter als Assimilationsproducte," 61 pp., Tomsk (1894); (Russian) *Bot. Centrbl.*, **63**: 246–251.
- SCHRAMM, J. R., 1914: The relation of certain grass-green algae to elementary nitrogen, *Ann. Mo. Bot. Gard.*, **1**: 157–184.
- SCHREINER, OSWALD, and J. J. SKINNER, 1912: Nitrogenous soil constituents and their bearing on soil fertility, *U. S. Dept. Agr. Bur. Soils Bull.* 87.
- SCHULTZ, M., 1903: "Studien über den Einfluss von Nitraten auf die Keimung von Samen und auf das Wachstum von Pflanzen," Inaug.-Diss., Königsberg.
- SCHULZ, M., 1862: Chemische Beiträge zur Kenntniss des Keimprocesses bei einigen Phanerogamen, *Jour. Prakt. Chemie*, **71**: 129–173.
- SCHULZE, B., and J. SCHÜTZ, 1909: Die Stoffwandlungen in den Laubblättern des Baumes, insbesondere in ihren Beziehungen zum herbstlichen Blattfall, *Landw. Versuchs-Stat.*, **71**: 299–352.
- SCHULZE, E., and E. WINTERSTEIN, 1910: Studien über die Proteinbildung in reifenden Pflanzensamen, *Zeits. f. physiol. Chem.*, **66**: 431–476; *Bot. Centrbl.*, **116**: 63.
- , 1911: Studien über die Proteinbildung in reifenden Pflanzensamen, *Zeits. f. physiol. Chem.*, **71**: 31–48.
- SHAW, G. W., and E. H. WALTERS, 1911: A progress report upon soil and climatic factors influencing the composition of wheat, *Calif. Agr. Expt. Sta. Bull.* 216.
- SHULVO, I., 1912: Sterile cultures of higher plants. Assimilation of nitrogen as ammonia and nitrates, *Jour. Expt. Landw.*, **13**: 200–206.
- SPITZER, GEORGE, R. H. CARR, and W. F. EPPLER, 1919: Soft corn, its chemical composition and nitrogen distribution, *Jour. Amer. Chem. Soc.*, **41**: 1212–1221.
- SPOEHR, H. A., 1911: The relation between photosynthesis of CO₂ and nitrate reduction, *Science*, n.s., **34**: 63–64.
- STARK, R. W., 1924: Environmental factors affecting the protein and oil content of soybeans and the iodine number of soybean oil, *Jour. Amer. Soc. Agron.*, **16**: 636–646.
- STARRING, C. C., 1923: Influence of the carbohydrate-nitrate content of cuttings upon the production of roots, *Amer. Soc. Hort. Sci. Proc.* **20**: 288–292.
- STEWART, C. R., E. C. THOMAS, and JOHN HORNER, 1925: The comparative growth of pineapple plants with ammonia and nitrate nitrogen, *Soil Sci.*, **20**: 227–243.
- STEWART, R., and J. E. GREAVES, 1909: A study of the production and movement of nitric nitrogen in an irrigated soil, *Utah. Agr. Expt. Sta. Bull.* 106.
- STROWD, W. H., 1920: The relation of nitrates to nodule production, *Soil Sci.*, **10**: 343–356.
- STUTZER, A., 1906: Die Wirkung von Nitrit auf Pflanzen, *Bot. Centrbl.*, **105**: 569–570.

- SUZUKI, U., 1897: An important function of leaves, *Imp. Univ. Coll. Agr. Tokyo*, **3**: 241-252.
- , 1897: The formation of asparagin in plants under different conditions, *Imp. Univ. Coll. Agr. Tokyo Bull.*, **2**: 409-457.
- , 1898: On the formation of proteids and the assimilation of nitrates by Phanerogams in the absence of light, *Imp. Univ. Coll. Agr. Tokyo Bull.* **4**: 488-587.
- , 1898: Ueber die Assimilation der Nitrate in Dunkelheit durch Phanerogamen, *Bot. Centrbl.*, **75**: 289-292.
- THATCHER, R. W., 1913: A report on the investigations concerning the chemical composition of wheat, 1906 to 1912 inclusive, *Wash. Agr. Expt. Sta. Bull.* 111.
- , 1913: The progressive development of the wheat kernel, *Jour. Amer. Soc. Agron.*, **5**: 203-213.
- , 1915: The progressive development of the wheat kernel. II, *Jour. Amer. Soc. Agron.*, **7**: 273-283.
- , 1921: "The Chemistry of Plant Life," McGraw-Hill Book Company, Inc., 268 pp.
- THOMAS, W., 1927: Nitrogenous metabolism of *Pyrus malus*. I, Influence of temperature of desiccation on water-soluble nitrogenous constituents and separation of water-soluble protein from non-protein constituents, *Plant Physiol.*, **2**: 55-67.
- , 1927: Nitrogenous metabolism of *Pyrus malus*. II, The distribution of nitrogen in the insoluble cytoplasmic proteins, *Plant Physiol.*, **2**: 67-71.
- , 1927: Nitrogenous metabolism of *Pyrus malus*. III, The partition of nitrogen in the leaves, one and two year branch growth and non-bearing spurs throughout a year's cycle, *Plant Physiol.*, **2**: 109-137.
- , 1927: Nitrogenous metabolism of *Pyrus malus*. IV, The effect of sodium nitrate applications on the total nitrogen and its partition products in the leaves, new and one year branch growth throughout a year's cycle, *Plant Physiol.*, **2**: 245-271.
- , 1927: The seat of formation of amino acids in *Pyrus malus* L, *Science*, n.s., **66**: 115-116.
- TOTTINGHAM, W. E., E. R. SCHULZ, and S. LEPKOVSKY, 1924: The extraction of nitrogenous constituents from plant cells, *Jour. Amer. Chem. Soc.*, **46**: 203-208.
- , 1923: Temperature effects in plant metabolism, *Jour. Agr. Res.*, **25**: 13-31.
- , 1924: Physiological stability in maize, *Science*, n.s., **59**: 69-70.
- and H. W. KERR, 1926: Climatic effects in the metabolism of maize, *Plant Physiol.*, **1**: 415-416.
- and H. LOWSMA, 1928: Effects of light upon nitrate assimilation in wheat, *Jour. Amer. Chem. Soc.*, **50**: 2436-2445.
- TREBOUX, O., 1904: Zur Stickstoffernährung der grünen Pflanze, *Ber. d. d. bot. Ges.*, **22**: 570-572.
- TRELEASE, S. F., and P. PAULINO, 1920: The effect on the growth of rice of the addition of ammonium and nitrate salts to soil cultures, *Philippine Agr.*, **8**: 293-313.
- ULLRICH, H., 1924: The role of chloroplasts in protein formation in green plants, *Zeits. f. Bot.*, **16**: 513-562; *Expt. Sta. Rec.* **56**: 814.
- VILLE, M. G., 1853-1857: "Recherches expérimentales sur la végétation," Paris.
- WANN, F. B., 1920: The fixation of free nitrogen by green plants, *Science*, n.s., **51**: 247-248.
- , 1921, The fixation of free nitrogen by green plants, *Amer. Jour. Bot.*, **8**: 1-30.
- WARBURG, O., and E. NEGELEIN, 1920: Über die Reduktion der Salpetersäure in grünen Zellen, *Biochem. Zeits.*, **110**: 66-115.
- WASSILIEFF, N., 1908: Eiweissbildung im reifenden Samen, *Ber. d. d. bot. Ges.*, **26**: 454-467.
- WEBSTER, J. E., 1928: Nitrogen metabolism in the soybean, *Plant Physiol.*, **3**: 31-43.

- WHITSON, A. R., F. J. WELLS, and A. VIVIAN, 1902: Influence of the soil on the protein content of crops, *Wis. Agr. Expt. Sta. 19th Ann. Rept.* **1902**: 192-209.
- WILLIS, L. G., and J. O. CARRERO, 1923: Influence of some nitrogenous fertilizers on the development of chlorosis in rice, *Jour. Agr. Res.*, **24**: 621-640.
- WILSON, B. D., 1921: Nitrogen in the rainwater at Ithaca, N. Y., *Soil Sci.*, **11**: 101-110.
- WOLFE, H. S., 1926: The auximone question, *Bot. Gaz.*, **81**: 228-231.
- WOO, M. L., 1919: Chemical constituents of *Amaranthus retroflexus*, *Bot. Gaz.*, **68**: 313-344.
- ZALESKI, W., 1897: Zur Kenntniss der Eiweissbildung in den Pflanzen, *Ber. d. d. bot. Ges.*, **15**: 536-542.
- , 1901: Die Bedingungen der Eiweissbildung in den Pflanzen, *Bot. Centrbl.*, **87**: 277-282.
- , 1907: Über den Aufbau der Eiweissstoffe in den Pflanzen, *Ber. d. d. bot. Ges.*, **25**: 360-368.
- , 1907: Über die autolytische Ammoniakbildung in den Pflanzen, *Ber. d. d. bot. Ges.*, **25**: 357-360.
- , 1909: Über die Rolle des Lichtes bei der Eiweissbildung in den Pflanzen, *Ber. d. d. bot. Ges.*, **27**: 56-62.
- , 1911: Zur Kenntnis der Stoffwechselprozesse in reifenden Samen, *Beih. Bot. Centrbl.*, **27**: 63-82; *Bot. Centrbl.*, **117**: 57.

CHAPTER X

THE FAT METABOLISM OF THE GREEN PLANT

I. FATTY SUBSTANCES IN PLANTS. CRUDE LIPIDES

When dry plant tissues are extracted with ethyl ether, chloroform, petroleum ether, carbon disulphide, benzene, acetone, or any of the other "fat solvents," a large number of substances are obtained which are designated collectively as the "ether extract," the "chloroform extract," etc., according to the particular solvent that has been used in the extraction. These substances are also frequently termed the "fatty substances" of the plant. Recently Sando (1928) in order to simplify the classification of the fatty substances suggested the name "crude lipides" for the tissue constituents obtained by extraction with the fat solvents and that term will be used in the following discussion.


The crude lipides that have thus been extracted may be divided into two main groups: (a) Those substances which contain in their chemical constitution the fatty acids and which yield these acids upon hydrolysis. This group of substances includes the fats, fatty oils, waxes, sterol esters, phospholipides, and galactolipides. Until 1925, however, there was no comprehensive name to include all of such substances. In that year Bloor proposed the name "lipides" to designate these types of compounds, and this term will be used in the following classification of the fatty substances of plants; (b) those substances which are not compounds of fatty acids. These include the essential oils, hydrocarbons, resins, and coloring matters. Although some of these substances are similar to the lipides in possessing a greasy feel, they have little or no resemblance to them from a chemical standpoint.

The classification of the crude lipides which may occur in plant tissue is given in the outline on page 565.

A. LIPIDES

The lipides are the most abundant, the most widely distributed throughout the plant, and apparently are the most important from a biological standpoint of the fatty substances which occur in plants. As defined by Bloor (1925), they include those substances in plants and animals which are insoluble in water but soluble in ether, chloroform, benzene, or other fat solvents and which have a relationship to the fatty acids as esters either actual or potential. The compounds included under

the term "lipides" form a group which is as strictly defined as either the proteins or carbohydrates and which are practically of the same physiological importance.



1. Composition.—The fatty acids and various types of alcohols are always component parts of the lipides and should be discussed here in some detail, since the reactions of the lipides are due in a large part to the character of these two types of compounds that enter into their composition.

a. Fatty Acids.—According to their position in the scheme of classification, the fatty acids should be considered under the heading of the derived lipides. In order to give the student a clear understanding of the nature of the lipides, however, and the part that the fatty acids play in determining their characteristics, a discussion of the fatty acids is given here. The fatty acids are monobasic and are so named because they occur in natural fats and because in the free state they resemble the fats in physical properties. The lower fatty acids as formic, acetic, and propionic are widely distributed in the various cells throughout the plant,

either in the free or in the combined form. The higher fatty acids with which we are here more particularly concerned occur in the free state to a considerable extent in germinating seeds and perhaps to a limited extent in other plant parts. By far the greater portion which occurs in plants, however, is combined with the alcohols to form the various types of esters which are designated as lipides. The classification and identification of a large proportion of the lipides are based upon the fatty acids which they contain. The fatty acids may be divided into two main series: (1) the saturated and (2) the unsaturated.

1. *Saturated*.—The saturated fatty acids have the general formula $C_nH_{2n}O_2$ and contain the maximum hydrogen possible. A saturated acid is thus saturated with respect to its hydrogen. The more important saturated acids are shown in the following table:

THE SATURATED FATTY ACIDS

Name of the acid	Formula
Formic.....	HCOOH
Acetic.....	CH ₃ COOH
Propionic.....	C ₂ H ₅ COOH
<i>n</i> Butyric.....	C ₃ H ₇ COOH
	CH ₃
	\ CHCOOH
Isobutyric.....	/ CH ₃
<i>n</i> Valeric.....	C ₄ H ₉ COOH
<i>n</i> Caproic.....	C ₅ H ₁₁ COOH
Caprylic.....	C ₇ H ₁₅ COOH
Capric.....	C ₈ H ₁₇ COOH
Lauric.....	C ₁₁ H ₂₃ COOH
Myristic.....	C ₁₃ H ₂₇ COOH
Palmitic.....	C ₁₅ H ₃₁ COOH
Stearic.....	C ₁₇ H ₃₅ COOH
Arachidic.....	C ₁₉ H ₃₉ COOH
Lignoceric.....	C ₂₃ H ₄₇ COOH
Cerotic.....	C ₂₅ H ₅₁ COOH

The acids of this series up to capric acid are liquid at ordinary temperatures, while the members containing ten or more carbon atoms are solids. The lowest members of this saturated series containing four or less carbon atoms are miscible with water in all proportions. As the molecular weight increases beyond this, however, the solubility of the acids in water rapidly diminishes to zero. The acids of this series from capric acid down are easily distilled with steam and are termed the "volatile fatty acids." The acids next above capric pass over in a current of steam only in traces, while the acids higher distill scarcely at all. Practically all these saturated acids above normal valeric occur, for the most part, in the form of glycerides in various plants.

Thus caproic, caprylic, and capric acids occur as glycerides in coconut and palm nut oils. Lauric acid occurs as a glyceride in laurel oil, coconut oil, palm oil, and myrtle wax. Myristic acid occurs as a glyceride in palm kernel oil. Palmitic acid is found as glycerides in barberry wax and in palm oil. Stearic acid occurs in the form of glyceride in shea butter and cacao butter while arachidic acid is found in relatively large amounts as glycerides in peanut oil.

2. *Unsaturated*.—The organic chemist designates these acids as the unsaturated acids, but since the term “unsaturated fatty acids” is used extensively by biologists, it was thought best to designate them by this name in this text. When the fatty acid molecule does not contain the maximum amount of hydrogen possible, the acid is said to be unsaturated. This means that at some point in the chain one or more pairs of carbon atoms are united by a double union. This double union may occur in a number of different positions and the properties of the acid differ with the different positions of the double unions. The unsaturated fatty acids may be made to combine with hydrogen, halogens, or oxygen by chemical means. The greater the degree of unsaturation the more unstable is the acid and the more readily does it combine with the elements above mentioned. The unsaturated acids are liquids at ordinary temperatures. They fall into different series according to their degree of unsaturation. A list of the more important ones is given in the following table:

THE UNSATURATED FATTY ACIDS

Name of the acid	Formula
Oleic series:	$C_nH_{2n-2}O_2$
	or $C_nH_{2n-1}COOH$
Tiglic.....	C_4H_7COOH
Hypogaecic.....	$C_{15}H_{29}COOH$
Oleic.....	$C_{17}H_{33}COOH$
Isomer of oleic:	
Rapic.....	$C_{17}H_{33}COOH$
Erucic.....	$C_{21}H_{41}COOH$
Linolic series:	$C_nH_{2n-4}O_2$
	or $C_nH_{2n-3}COOH$
Linolic.....	$C_{17}H_{31}COOH$
Linolenic series:	$C_nH_{2n-6}O_2$
	or $C_nH_{2n-5}COOH$
Linolenic.....	$C_{17}H_{29}COOH$
Hydroxy series:	$C_nH_{2n-2}O_3$
	or $C_nH_{2n-1}OCOOH$
Ricinoleic acid.....	$C_{17}H_{31}OCOOH$

The oleic series takes its name from oleic acid which occurs as glyceride in most fats and oils. Tiglic acid occurs as a glyceride in croton oil, while hypogaecic acid is found in the form of glyceride in peanut and maize oil. Oleic is the most widespread and most abundant of any

of the fatty acids that occur in the plant. The glyceride of this acid is found in the fats and oils of the coconut, palm kernel, olive, peanut, cotton seed, maize, flax seed, soybean, and many other seeds. Linolic acid occurs in the combined form in linseed oil, cotton-seed oil, olive oil, peanut oil, soybean oil, and maize oil, while linolenic acid and its isomers are found in linseed oil, hemp oil, sunflower oil, soybean oil, and other plant oils.

The hydroxy-fatty acids have one or more hydroxyl groups which replace hydrogen in the chain. One of the common hydroxy-fatty acids is ricinoleic which is unsaturated and forms the glyceride which is the principal constituent of castor oil.

b. Glycerol and Other Alcohols.—Alcohols of various kinds are combined with the fatty acids to form numerous types of lipides. Of these alcohols, the trihydroxyalcohol, glycerol, or glycerine $C_3H_5(OH)_3$ is by far the most abundant and forms esters or glycerides with many different fatty acids. At ordinary temperatures, it is a viscid fluid and mixes with water in all proportions. It is miscible with ethyl alcohol, but only slightly soluble in ether and is insoluble in chloroform, petroleum ether, and carbon bisulphide. It is highly hygroscopic, absorbing more than one-half its weight of water from the air and cannot be completely freed from water *in vacuo* over sulphuric acid. Glycerol is formed in the alcoholic fermentation of sugar. It was discovered during the World War that glycerol can be prepared from sugar by the action of yeast in the presence of large amounts of sodium sulphite and large quantities were obtained in this manner.

The alcohols which are combined with the fatty acids to form waxes or sterol esters are monohydric and are insoluble in water. Some of these which are found in plants are ceryl alcohol, $C_{26}H_{53}OH$, which occurs in the combined state as ceryl palmitate in poppy wax; myricyl alcohol, $C_{30}H_{61}OH$, occurs free and as the ester of cerotic acid in carnauba wax, which is obtained from the leaves of the Brazil palm. Cholesterol, $C_{27}H_{45}OH$, is a cyclic, monohydric alcohol. Such compounds are sometimes termed "sterols." Cholesterol is found in animal tissue, but so far has not been detected in plants. It is of interest here, however, since phytosterol, which is apparently an isomer of cholesterol, is found in practically all the fatty materials of plants, constituting from 0.13 to 0.30 per cent of such materials. The term "phytosterol," however, is now used generically, since phytosterol is considered to be composed of a mixture of two substances: sitosterol, $C_{27}H_{45}OH$, which has been obtained from the oil of wheat, rye, and maize; and stigmasterol, $C_{30}H_{47}OH$, which has been found in the phytosterol of rape oil and cacao butter. Anderson and Moore (1923) found that corn oil contains 2 per cent of unsaponifiable matter, largely of phytosterol which is identical with sitosterol. Both cottonseed oil and linseed oil contain at least two

phytosterols differing in optical properties. The corn pollen of white flint corn contains phytosterol palmitate (Anderson, 1923). The fat extracted from this pollen with absolute alcohol contains 25 per cent unsaponifiable matter, primarily a mixture of optically inactive phytosterols which are free from water of crystallization. Anderson (1924) also found that the unsaponifiable matter derived from the endosperm of corn contained considerable quantities of ordinary sitosterol associated with dihydrositosterol.

2. Classification.—According to Bloor (1925), the lipides may be divided into three main groups: (a) the simple, (b) the compound, and (c) the derived.

a. Simple.—The simple lipides include those compounds which are the esters of the fatty acids with various alcohols. The fats and fatty oils and the waxes are the main groups of the simple lipides.

1. Fats and Fatty Oils.—This group of compounds is composed of esters of the fatty acids with glycerol, termed the "triglycerides" of fatty acids. These compounds are commonly called "oils" if they remain liquid at ordinary temperatures and fats when they are solid at such temperatures. The oils of this type are frequently designated as fatty oils to distinguish them from the volatile oils and others which have no chemical relation to the triglycerides. In this discussion the term "fat" will be used in the general sense as including all the triglycerides. The fats as they occur in nature are practically always mixtures in varying proportions of triglycerides. In some fats one triglyceride predominates, in others another, and in still others several are present in considerable amounts, so that probably no natural fat consists solely of a single triglyceride. Furthermore, the individual fatty-acid radicles of any single glyceride may be different. Thus each of the three fatty-acid radicles may be different, two may be of one type and the third another, or all three may be of the same kind. The type of glyceride which predominates in a given fat gives that fat its more pronounced characteristics. Although a large number of triglycerides occur in nature, those of myristic acid, lauric acid, palmitic acid, stearic acid, oleic acid, linolic acid, and linolenic acid make up the great bulk of the natural fats and oils. This fact, as well as the mixed nature of the fats and oils from plants, is shown in the table on page 570, adapted from Alsberg and Taylor (1928), Baughman and Jamieson (1920, 1921, 1922), and Jamieson, Baughman, and Brauns (1920, 1921).

(a) Physical Properties.—The triglycerides of the higher fatty acids are insoluble in water, while those of the lower are slightly soluble. The triglycerides above those of caprylic acid are lighter than water and all float thereon. They are readily soluble in ether, chloroform, benzene, and other organic solvents in the cold but are much more soluble in these solvents when heated. They are only slightly soluble in ethyl and


PERCENTAGE OF THE MORE IMPORTANT FATTY ACIDS COMBINED IN FATS AND OILS

Fat or oil	Lauric	Myristic	Palmitic	Stearic	Oleic	Linolic	Linolenic
Coconut.....	45	20	5	3	6		
Palm kernel.....	55	12	6	4	10		
Olive.....	14.6	...	75.4	10	
Peanut.....	8.5	6	51.6	26	
Cotton seed.....	23.4	...	31.6	45	
Maize.....	6.0	2	44.0	48	
Linseed.....	..	3	77	17.0
Soybean.....	11.0	2	20.0	64	3.0
Cantaloup seed oil.....	..	0.3	10.2	4.5	27.2	56.6	
Sunflower oil.....	3.5	2.9	33.4	57.5	
Hubbard squash seed oil.....	13.0	6.0	37.0	44.0	

methyl alcohol and acetone, at ordinary temperatures, but readily soluble when heated. Castor oil is an exception, however, and is readily soluble in ethyl alcohol in the cold.

The pure triglycerides are colorless, odorless, and tasteless, the properties of color, odor, and taste, when present, being due entirely to foreign substances mixed with or dissolved in them. The pure triglycerides are for the most part optically inactive. Castor oil is an exception, since it contains an optically active fatty acid. Some of the unpurified triglycerides show optical properties, but these properties are due to such non-fat impurities as resins and sterols.


(b) *Chemical Properties.* (1) *Hydrolysis.*—All the fats and fatty oils, under proper conditions, may be hydrolyzed to glycerine and their component fatty acids. Thus, for example, in the case of tripalmitin, hydrolysis proceeds after the following manner:



The fats may be hydrolyzed (a) by treating them with superheated steam in the presence of a suitable catalytic agent. Four compounds that may be used as catalyzers are sulphuric acid, hydrochloric acid, lime, and magnesia. Sulphuric acid is the most efficient agent since it apparently aids in bringing the fat into a finer emulsion; (b) by

the action of the enzyme lipase. This enzyme may be isolated from plant tissue and be used in the laboratory for hydrolyzing fats. This enzyme hydrolyzes the fats in plants under natural conditions as will be described later. The hydrolysis of fats is apparently the first step in their breaking up for utilization in the metabolism of the plant.

(2) *Saponification*.—When fats are boiled with caustic alkali they are hydrolyzed into glycerol and fatty acids, the alkali combining with the fatty acid to form soap, a process termed “saponification.” The term saponification literally means soapmaking. The process may be illustrated by using the fat tripalmitin as an example:



In the laboratory the saponification of fats is usually carried out by alcoholic alkali solutions, since the reaction is much more rapid with this reagent than with alkali in water. The process is of interest in plant physiology because it is considered to play some part in the translocation and utilization of fats, as will be discussed later.

(3) *Drying of Oils*.—When most of the fatty oils are exposed to the air they tend to thicken or dry. This is due in some cases to polymerization and in others to oxidation. Some oils only thicken while others become dry and form a more or less hard mass or, if spread out sufficiently, a thin elastic film. The drying process is due primarily to the oxidation of the oils and is characteristic of those oils which contain fatty acids with unsaturated carbon unions; the larger the number of these unsaturated unions the more readily do the oils take up oxygen. According to the degree to which they dry, oils are grouped into three classes (Haas and Hill, 1913):

a) *Non-drying*.—The oils in this group only thicken but do not become hard or form films. They are composed, for the most part, of the triglyceride of oleic acid. To this group belong olive oil, peanut oil, almond oil, rice oil, and the oil from the kernels of cherry, plum, peach, and apricot seeds.

b) *Drying*.—The oils of this group are composed principally of the triglycerides of the unsaturated fatty acids of the linolic and linolenic series and contain a relatively small amount of oleic acid. The drying oils absorb oxygen from the air and form an elastic skin or film, a charac-

teristic which is utilized in the manufacture and application of paints. Some of the oils which belong to this group are linseed, hemp seed, sunflower, cedar nut, walnut, and poppy seed.

c) *Semidrying*.—According to the classification of Haas and Hill (1913), the oils of this group have drying properties lying midway between those of the drying and non-drying oils. They differ from the true drying oils in containing acids of the linolic series. Some of the oils which fall in this group are cotton seed, pumpkin seed, soybean, sesame and croton, watermelon seed, barley and rye seed, rape, mustard seed, and radish seed.

(4) *Values for Determining the Character of Fats and Oils*.—There are certain chemical values that are used as measures of certain characteristics of the fats. These values are determined in the technical chemical analyses of fats but are also of importance in determining certain changes which may occur in the metabolism of these compounds in the plant. It is not the intention here to enter into any detailed discussion of the procedure or methods to be used in determining these values, but to discuss them only in so far as they will be an aid in understanding the physiological changes which occur in the fat metabolism of the plant. A detailed discussion may be obtained by consulting Haas and Hill (1913), Leathes and Raper (1925), and "The Methods of Analysis of Official Agricultural Chemists" (1925). The chemical values of the fats which will be mentioned here are (a) the acid, (b) the Hehner, (c) the saponification, (d) the iodine, and (e) the acetyl.

a) *Acid Value*.—By the acid value of a fat is meant the number of milligrams of KOH necessary to neutralize one gram of the fat. It is thus a measure of the amount of free fatty acid present in the fat and indicates the degree of hydrolysis which it has undergone. The acid value, however, indicates nothing as to the nature of the free acids present in the fat. The acid value of a fat may be obtained by dissolving a measured portion in neutral 95 per cent alcohol, heating to boiling, and titrating with tenth-normal alkali, using phenolphthalein as an indicator.

In connection with the acid value of a fat, the total insoluble acids and the total soluble acids should be considered.

b) *Hehner Value*.—By the Hehner value of a fat is meant the percentage of fatty acids insoluble in water that is yielded on the saponification of the fat. The determination then of the insoluble fatty acids of a fat gives some information as to its composition. Thus if the fat contained in a certain plant part shows, during the course of the development of the plant, a decrease in the percentage of insoluble fatty acids, it is an indication that the higher fatty acids are being replaced by those of the lower groups, which are soluble in water. The total soluble acids of a fat represent both the free and the combined acids of the oil which are soluble in water and represent the fatty acids of lower molecular weight. The determination of the soluble acids supplements the results obtained in the estimation of the total insoluble fatty acids.

c) *Saponification Value*.—The saponification equivalent or value of a fat is the amount of KOH in milligrams that is neutralized during the saponification of one gram of the fat by the combined and free fatty acids which it contains. It is in reality an indication of the mean molecular weight of the fatty acids which enter into the composition of the fat. Thus fats which are the glycerides of the higher fatty acids give relatively low saponification values, while those that are glycerides of the lower fatty acids give relatively high saponification values. The saponification values of some of the more common plant fats are as follows:

Fat or oil	Saponification value
Coconut oil.....	246 to 260
Peanut oil.....	190 to 196
Cottonseed oil.....	193 to 195
Linseed oil.....	192 to 195
Soybean oil.....	193
Olive oil.....	185 to 196
Corn oil.....	188 to 193
Rape-seed oil.....	170 to 179

d) *Iodine Value*.—By the iodine value of a fat is meant the amount of iodine that the combined and free unsaturated fatty acids of the fat will take up expressed in percentage of the weight of the oil. Thus if the iodine value of the fat content of a plant decreases during any given period, it indicates that the unsaturated fatty acids of the oil are becoming saturated, probably by the addition of oxygen. The iodine value of some of the more common plant fats is shown in the following table:

IODINE VALUES OF PLANT FATS
(After Alsberg and Taylor, 1928)

Fat or oil	Iodine value	Fat or oil	Iodine value
Linseed oil.....	173 to 201	Peanut oil.....	83 to 100
Soybean oil.....	137 to 143	Palm oil.....	51 to 57
Sunflower oil.....	119 to 135	Cacao butter.....	32 to 41
Corn oil.....	111 to 130	Palm kernel oil.....	13 to 17
Cottonseed oil.....	108 to 110	Coconut oil.....	8 to 10
Rape-seed oil.....	94 to 102		

e) *Acetyl Value*.—The acetyl value of a fat gives the number of milligrams of KOH required to neutralize the acetic acid that is set free when one gram of the acetylated fat is saponified. The acetyl value is really a measure of the amount of the hydroxyl groups which a fat contains. The acetyl values of some of the fats are as follows (after Haas and Hill, 1913):

Linseed oil.....	3.98	Palm oil.....	18.0
Olive oil.....	10.64	Grape-seed oil.....	144.0
Rape-seed oil.....	14.7	Castor oil.....	153.0

2. *Waxes*.—The waxes are generally defined as fatty-acid esters of some alcohol other than glycerol, usually a monohydric alcohol such as ceryl alcohol, cetyl alcohol, myricyl alcohol, and phytosterol. The waxes may also contain acids other than those which have been mentioned in considering the fats and oils. The term "waxes" is used only in the chemical sense and has reference to their composition regardless of their physical condition, so that waxes occur as both solids and liquids. The waxes of the plant kingdom are all solids. Some of the waxes of plant origin are ceryl palmitate in poppy wax, myricyl cerotate and ceryl cerotate in carnauba wax. Some of the waxes of animal origin are beeswax, wool wax, and spermaceti.

Waxes are somewhat less soluble in the ordinary fat solvents than are fats. The waxes, as a general rule, have to be boiled with alcoholic potash much longer than the

glycerides in order to be saponified. This is due in part, apparently, to their low solubility even in hot alcohol. Their saponification value is low because the molecular weights of the alcohols as well as the fatty acids which compose them are high. Waxes are commonly found on fruits and leaves and are generally spread over the cuticle as a wax covering. In the case of fruits this covering is termed the "bloom" when it is noticeable. These wax coverings may consist of grains, small rods, or crusts. The greatest thickness of wax deposit that has been observed is on the leaves of some of the palms where in some cases the coverings are more than 5 mm. in thickness. In the waxlike coating of the apple, Sando (1923) obtained from the ether extract triacontane, $C_{30}H_{62}$, melting at 63.5 to 64°C.; heptacosanol, $C_{27}H_{56}O$, melting at 81 to 81.5°; and malol, a crystalline alcohol.

b. Compound Lipides.—The term "compound lipides" as defined by Bloor (1925) includes the esters of the fatty acids containing groups in addition to an alcohol and a fatty acid. This group of substances has been designated by various authors as "lipins," "lipoids," and "fatlike bodies." MacLean and MacLean (1927) in defining the term "lipins" state that they are substances of a fatlike nature, yielding upon hydrolysis fatty acids or derivatives thereof and containing either nitrogen or phosphorus. The compound lipides are divided into (1) the phospholipides and (2) the galactolipides.

1. *Phospholipides.*—This group has also been called the "phospholipins," "phosphatides," and sometimes "the lecithins." The phospholipides are substituted fats containing phosphoric acid and nitrogen. They thus contain phosphorus, nitrogen, and fatty acids and on hydrolysis yield glycerophosphoric acid, fatty acids, and basic bodies, such as choline and amino ethyl alcohol. The phospholipides are soluble in the majority of the ordinary fat solvents with the exception of acetone. The phospholipides are precipitated from the crude ether or fat solvent extract by the addition of an excess of acetone (MacLean and MacLean, 1927). The two most abundant phospholipides are lecithin and kephalin.

(a) *Lecithin.*—Lecithin is considered the most important plant phospholipide. It may be regarded as a fat in which one of the three fatty acids is replaced by phosphoric acid combined with choline. The type of fatty acids combined in lecithins varies widely. In a lecithin preparation from the soybean, Levene and Rolf (1925) found stearic, palmitic, oleic, linolic, and linolenic acids. Lecithin is very labile and undergoes changes as the result of oxidation. It combines with acids and bases and acts readily as an adsorbent. The occurrence of lecithin in the plant will be mentioned in a subsequent topic.

(b) *Kephalin.*—This compound closely resembles lecithin and is always found closely associated with it. It is distinguished from lecithin by its insolubility in alcohol and is separated in the laboratory from lecithin by the utilization of this property. Kephalin is considered to contain two fatty acids—one of the common fatty acid series and another peculiar to kephalin, termed "kephalic acid." It also contains three

basic bodies, two of choline and one amino ethyl alcohol. The methods for the separation of kephalin have never been very well defined, and it is probable that pure kephalin has never been prepared.

2. *Galactolipides*.—The galactolipides are compounds of the fatty acids with a carbohydrate and contain nitrogen but no phosphoric acid. They have also been designated as glycolipins, cerebrosides, and galactosides. The galactolipides are bodies of a glucoside nature and upon hydrolysis yield galactose, a fatty acid and a base.

c. *Derived Lipides*.—The term "derived lipides" is given those substances which are derived from the simple and compound lipides by hydrolysis and which are soluble in the fat solvents. They include the fatty acids of the various series and the large molecular alcohols which are soluble in the fat solvents and are found in nature combined with the fatty acids. These alcohols include cholesterol, myricyl alcohol, and cetyl alcohol. The derived lipides have been discussed in relation to the compounds of which they are a part and will not be further mentioned here.

3. **Distribution in the Plant Cell**.—Fatty substances occur apparently in every living plant cell in exceedingly variable quantities. They are present in the cells of the apical meristem and were determined by Priestley (1924) to be for the most part phospholipides. Fats, fatty acids, and soaps can be detected in the walls of plant cells at a very early stage and appear to be present as early as the cellulose and pectic substances. Hansteen-Cranner (1924 to 1926) noted the presence of fats and phospholipides in the cell walls of parenchymatous tissues. He considered these of importance in regard to the permeability of these tissues. Priestley (1924) states that the cell walls of the phloem tissues are free from fat, although fat is included in the cell content. The external protective coverings of the plant owe their imperviousness to water to various oxidation and condensation products of fatty acids, especially hydroxy-fatty acids, as mentioned in Chap. I. In the photosynthetic tissues, fats and phospholipides are always present, and the pigments of the green leaf are probably dissolved in colloidal solutions of fatty substances. By far the major portion of the fatty substances in plants is found in the protoplasm, but the physical relation between these substances and the protoplasm is, as yet, not clearly understood. Wakker (1886) considered that the oil substances are distributed evenly in very minute drops in the protoplasm, while Tschirch and Kritzler (1900) believed that the fatty substances of oily seeds are not in drops but are homogeneously mixed with the protoplasm. Czapek (1913) states that in seeds fatty substances are ultramicroscopically divided in the protoplasm and that oil drops cannot be demonstrated. Haberlandt (1914) states that in oily seeds the greater proportion of the oil is contained in the interstices between the delicate meshwork of the proto-

plasm but that when the oil is present in the tissues in small amounts it is suspended in the protoplasm in small drops. Dangeard (1923) by means of intravital staining of living cells of the seeds of *Ricinus* and conifers found the cytoplasm to be alveolar and in the alveoli the aleurone grains and the oil are located. The oil in these alveoli is not a continuous phase but is in the form of spherules, which are thus inclusions in the cytoplasm. In contrast to these observations, Policard and Mangenot (1923) considered that the oil in the ripe seeds of *Ricinus* is in the continuous phase, while the cytoplasm is in the discontinuous phase. They consider that during the germination of the seed the oil passes from the continuous phase into the discontinuous phase, so that the oil containing the cytoplasm becomes transformed into oil droplets in the cytoplasm. In the process of seed formation, the reverse of this process occurs. The dispersion of fatty substances or lipoids in the cells of the embryo and endosperm was studied by Pack (1925) with especial reference to juniper seeds. As after-ripening and germination proceeded at 5°C. the lipid drops gradually became smaller and increased in number. This dispersion was found to proceed and accompany the appearance of sugar and starch in the hypocotyl region. As germination progresses, the lipid drops in the root and shoot axil reach a degree of dispersion equal to the limit of the microscope. During germination there is a decrease in the number of these drops because the lipid material is used in the manufacture of other compounds. The oil reserve observed in the seeds of hawthorne, castor bean, peach, and juniper shows that it is often stored in the form of large drops. At times these drops are collected into masses which fill the meshes of the protoplasm. Resting seeds, with little fatty content, deposit it as fine drops. The lipoids of active cells and tissues are in a very fine state of division. This dispersion of the oily substances increases the oil surface many hundreds of times and is favorable to hydrolysis by enzymes, so that translocation, absorption, and transformation of the oil is favored.

Pack states that in the deposition of fatty materials in storage organs, one first notices fine oil droplets or bodies in the younger cells. These droplets increase in size with the age of the cells, so that in the old cells large masses or drops of oil can be seen. These changes are the reverse of the dispersion of the lipoids during their digestion in the active tissues. Condensation attends the storage of fats while dispersion accompanies their digestion.

Under certain conditions bodies termed "elaioplasts" are formed in certain cells and have been considered by some to be oil formers. According to Beer (1909), they are formed by the aggregation of plastids and their decomposition products, and, although they frequently contain oil, they are in no sense special oil-forming organs. The oil vacuoles sometimes observed in certain cells originate by the coalescence of numer-

ous minute oil droplets secreted by the protoplasm in a manner similar to that in which the ordinary sap vacuole arises. Although these oil vacuoles may be large and project into the sap vacuole, they continue to be surrounded by a thin film of cytoplasm. The oil vacuoles are in no sense plastids, nor are they formed by elaioplasts but are simply accumulations of fatty substances (Rivett, 1918).

4. Occurrence of Fats and Fatty Oils in the Plant.—The fats and fatty oils make up the greater portion of the fatty substances that are found in plants. Although they are widely distributed in the plant world, the commercial supply of these products is obtained for the most part from a comparatively small number of species (approximately 200). The fats and fatty oils are reserve foods and are utilized by the protoplasm in respiration, growth, and repair after the same manner as carbohydrates. When fats and oils are stored in tissues in relatively large amounts, carbohydrates, as a rule, are present in relatively small amounts. When carbohydrates are present in relatively large amounts, fats and oils generally occur only in limited quantity. The fats and oils are found in the greatest abundance in fruits and seeds. While they occur in the root, stem, branches, and leaves of plants, they are rarely present in these organs in quantities large enough to be of much significance. In some seeds, as the cereals, the fats and oils are confined almost entirely to the embryo. In the oil palm, both the embryo and endosperm contain a large amount of fat. In the olive, a large amount of oil is stored in the pulp surrounding the kernel and a smaller amount is in the kernel itself. The oil or fat in these different parts of the seed may have characteristics that are quite different from each other. The table which follows gives the percentages of oil that may occur in various seeds and plant parts. The percentage of oil varies in the same species under different conditions, so that any data in this regard should be considered as more or less relative. The figures that are commonly given for the fat and oil content mean simply the fat-solvent extract and include, thus, numerous substances other than fats and oils.

It is worthy of note that the unsaponifiable matter of the fatty substances extracted from seeds is low, amounting to from 0.2 to 0.8 per cent, while that of the fatty substances obtained from stem and leaves is very high. Thus Chibnall (1927) found that the unsaponifiable matter in the ether extract of the cabbage leaf amounted to from 16.5 to 24.1 per cent. Fats and oils form a considerable portion of the food reserve in trees and shrubs. Under certain conditions, carbohydrates appear to predominate in amount; and under others, fats and oils. In some plants these two reserves are about equal in amount (Sinnott, 1918). It has been observed for a long time that under certain conditions the carbohydrate reserves are transformed into fats and oils and *vice versa*. The conditions under which such changes are brought about are

THE PERCENTAGES OF FATS AND OILS IN THE DRY MATERIAL OF SEEDS AND OTHER
PLANT PARTS

Plant part	Percentage of fat or oil	Plant part	Percentage of fat or oil
Coconut.....	65	<i>Madia sativa</i> seed.....	32
Brazil nut.....	70	Olive pulp.....	50
Castor bean.....	60	Kafir seed.....	2.5
Sunflower seed.....	45-50	Peterita seed.....	2.4
Flax seed.....	30-35	Milo seed.....	2.3
Cotton seed.....	15 20	Corn seed.....	5.0
Peanut.....	40-50	Wheat seed.....	2.1
Hemp.....	30 35	Rye seed.....	1.8
Walnut.....	50 65	Rice seed.....	1.9
Cacao bean.....	40 50	Buckwheat seed.....	2.5
Poppy seed.....	40 50	Field pea.....	1.1
Pumpkin seed.....	41	Bean.....	1.5
Almond.....	40 50	Bluegrass leaves.....	2.8
Soybean.....	15-20	Buffalo grass leaves.....	1.8
Cantaloup seed.....	30	Orchard grass stem and leaves.....	2.9
Spurge seed.....	35-45	Alfalfa stem and leaves.....	2.3
Rape seed.....	33-43	Cowpeas stem and leaves.....	2.6
Sesame seed.....	50-55	Soybeans stem and leaves.....	2.5
Colza seed.....	43-53	Cabbage leaf.....	1.7

still very obscure. In the case of trees growing at Edmonton, Can., a progressive decrease of the sugars from the winter maximum toward the summer was found (Lewis and Tuttle, 1920; Tuttle, 1921). Oils and fats were present in nearly all cells of the phloem, cortex, and the medullary-ray cells. In a majority of cases, starch disappeared during October and early November, while oils and fats were abundant. In case of leaves at about the time of leaf fall, 15 species were characterized by the absence of starch, but all showed a relatively high oil and fat content. Sinnott (1918) considered that starch is more common, in the woody plants, in regions remote from the centers of conduction and in cells with well-lignified and small-pitted walls, while fats and oils were more abundant in and near the phloem, close to vessels, and in cells with thin, unlignified walls with large pits. Where movement of liquids apparently is slow and difficult, the reserve food persists as starch, while where such movement is easy, starch disappears at the beginning of winter and fats and oils are produced. The character of the food reserves thus depends primarily upon the ease with which water or substances carried by it have access to the cells.

5. Occurrence of Compound Lipides in the Plant.—Our knowledge of the compound lipides in plants is very limited, and it is doubtful if

any of them have yet been obtained in the pure form. The methods used for their isolation from animal tissues are apparently not applicable for their extraction from plant tissues. The chief obstacle in investigating the compound lipides in plants is due, according to MacLean and MacLean (1927), to the presence in the plant of a large amount of carbohydrate material which tends to form physical complexes with the compound lipides. It is not known whether the compound lipides of plants are identical or not with those of animal origin. The occurrence of compound lipides has been reported for a wide range of plants and has been especially studied in seeds and seedlings. These compounds have been variously reported as phospholipins, phosphatides, lecithin, lipoids, and lipins. The compound lipides, which have been reported in plants are, for the most part, phospholipides, especially lecithin, but it is probable that kephalin is also present in plants (Levene and Rolf, 1925). According to MacLean and MacLean (1927), the presence of carbohydrates in the compound lipides of plants is almost universal. Although some of this carbohydrate is only in physical association with these substances, there exist bodies of wide occurrence in plants with which the carbohydrates are chemically combined and thus are identical or similar to the galactolipides which are found in animals. The only compound lipides that have been studied to any extent in plants are the phospholipides, and our attention will be devoted entirely to them. The phospholipides are widely distributed in plants, and although occurring in very small amounts are present in practically every living plant cell (Kossel, 1890).

a. Distribution.—Knop (1859) isolated from plant tissue a fatty extract which contained phosphorus and was thus probably the first to observe the presence of phospholipides in plants. Jacobson (1889) showed that one of the decomposition products of the phospholipides occurring in plants is choline, while Schulze and Likiernik (1891) hydrolyzed phospholipides from seeds and obtained fatty acids, glycerophosphoric acid, and choline, thus establishing the similarity of the plant phospholipides to those of animal origin. Winterstein and Hiestand (1908) found phospholipides in the potato and seeds of cereals, vetch, and lupine. Euler and Nordenson (1908) isolated a lecithin-like substance from the carrot, while Winterstein and Stegman (1909) were able to obtain a phospholipide from the leaves of *Ricinus*. It was determined by Winterstein and Smolenski (1909) that wheat flour contains a mixture of phospholipides which differ in their physical and chemical properties, while Smolenski (1909) obtained a phospholipide from the wheat embryo. Njegovan (1911) obtained three phosphatides from the seeds of *Lupinus albus* differing in their content of phosphorus, nitrogen, and fatty acids. Shorey (1898) found that the raw sap of the sugar cane contained a mixture of several lecithins as indicated by the different acids and bases obtained upon hydrolysis.

Hansteen-Cranner (1914-1926) made extensive studies of the distribution of the phospholipides in the protoplasmic membrane and in the cell walls. He considered that the cell wall is permeated with phospholipides which are in intimate connection and relation with those of the plasma membrane. His observations were substantiated by Grafe (1925), Grafe and Horvat (1925), and Grafe and Magistris (1925, 1926),

who prepared water-soluble phospholipides from beets and carrots among other plant tissues. The methods used by these investigators were considered to extract the phospholipides from the cell wall and the plasma membrane without altering the permeability of the general protoplasmic membrane. Steward (1928), however, by the careful extraction of the tissues of potato and beet concluded that leaching experiments do not yield evidence that phospholipides are present in the surface layer of the protoplasm and diffuse from living tissue into distilled water. In a study of the ether-soluble substances of cabbage leaves, Chibnall and Channon (1927) could not detect any true phospholipides. All the phosphorus present was apparently in combination with calcium, glycerol, and fatty acids, while nitrogen was virtually absent. The substance which was isolated was thus apparently the insoluble calcium salts of glycerophosphoric acids in which the choline was replaced by calcium. The phospholipides which have been extracted from plants are no doubt mixtures of similar compounds and vary widely from different sources in regard to their nitrogen and phosphorus content and in the types of their fatty acids. This is illustrated by the work of Webster (1928), who determined the percentage of nitrogen, phosphorus, and iodine value of the phospholipides secured from the seeds of wheat, corn, sorghums, and oats. The results obtained were as follows:

Source of phospholipides	Percentage of nitrogen	Percentage of phosphorus	Iodine value of the fatty acids
Wheat.....	0.99	1.26	81.5
Corn.....	1.14	1.65	65.3
Soybean.....	0.70	0.50	92.5
Oats.....	1.61	0.54	88.8

The amount of the phospholipides which occurs in plant tissue apparently varies with the type of tissue, the kind of plant, and the environmental conditions.

b. Relation of the Amount of Phospholipides to the Protein and Oil Content.—It was considered by Stocklasa (1895 to 1898) that lecithins accompany the proteins in plants, while Schulze and Likiernik (1891), and Schulze, Steiger, and Maxwell (1891) considered that the phospholipides vary directly with the protein content. According to Guerrant (1927), it was considered by Parrozzani (1909) that the ratio between the phospholipides and the amides is more definite than that of proteins and phospholipides. The amount of oils, proteins, and phospholipides in various seeds was determined by Guerrant (1927). Some of his results are shown in the table on page 581.

Guerrant (1927) considered that his results indicated a slight correlation between the phospholipide content and the protein, fat, and phosphorus contents of the various classes of seeds. In general, the highest percentages of phospholipides are found in the seeds having the highest protein and the highest fat content, but this is not always the case.

c. Phospholipides in Developing and Germinating Seeds.—It was considered by Schulze and Frankfurt (1894) that unripe seeds contain less phospholipides than ripe ones, but M'Clenahan (1909) observed just the opposite in the development of the black walnut. Guerrant (1927)

Seed	Number of		Percentage on a dry basis of			
	Samples	Varieties	Protein	Oils	Total phosphorus	Phospholipide phosphorus
Corn.....	6	6	11.5	4.3	0.196	0.0144
Wheat.....	5	4	12.5	2.2	0.289	0.0306
Oats.....	2	2	13.3	4.1	0.262	0.0368
Sorghums.....	26	12	12.1	2.9	0.245	0.0378
Barley.....	1	1	13.1	1.8	0.275	0.0442
Clover.....	1	1	35.2	5.4	0.271	0.0506
Peas.....	5	5	27.0	1.7	0.292	0.0760
Peanut.....	1	1	33.9	48.6	0.332	0.0880
Beans.....	10	8	30.4	12.6	0.387	0.0926
Cotton.....	1	1	23.5	25.22	0.476	0.1456

determined the phospholipide content of seven varieties of sorghum seeds at the milk stage, dough stage, and maturity. He obtained an increase in these compounds as maturity was approached, while the percentage of protein, fats, and total phosphorus also increased. Sufficient data, however, were not obtained to show any definite correlation between the rate of formation of any two of these substances.

It was observed by Schulze and Steiger (1889) that phospholipides decreased when seeds were germinated in the dark. Maxwell (1891), Zalenski (1902), and Iwanoff (1902), in the case of the seeds of corn, bean, and cotton, found an increase of these substances when germinated in the light. Guerrant (1927) germinated two samples of grain sorghum seed in both light and darkness and found that the lipid phosphorus showed a greater increase when germination occurred in the light. Green and Jackson (1905) noted in the germination of the castor bean that the amount of lecithin diminished during the earlier stages of germination, the reserve supply becoming almost exhausted. After the young seedling had begun to develop, there was a gradual increase in the amount, which was maintained during the later stages and remained fairly constant until the endosperm was depleted. They consider that the endosperm of this seed contains the several groups necessary for the formation of lecithin. The decomposition of the oil furnishes the fatty-acid component and the glycerine for the glycerophosphoric acid. The phosphorus is present in the seed, while the nitrogenous body, choline, may arise from the decomposition of the protein.

d. Function of the Compound Lipides.—Since the compound lipides are so widespread in plants and are found especially in those parts of the plant where life activities are very pronounced, it seems evident that they must play an important part in the activities of the protoplasm. In

this regard, however, nothing definite is known, and only theories have been proposed. The compound lipides have been considered by some to exercise an influence on the permeability of the protoplasmic membrane, but their influence in this regard is apparently not of the importance that was once thought. It has been considered by some that the compound lipides play a rôle in the fat metabolism of the plant, but nothing is known concerning their function in this regard. Palladin and Stanewitsch (1910) considered that there is a relationship between the lecithins and respiration, since they found that the respiration intensity of seeds was lower after treatment with those solvents which extracted the most lipins. Korsakow (1910) considered that the lipoids influence the activity of proteolytic enzymes, while Gallagher (1923) believed that the production of peroxidase of potato is intimately associated with the lecithin of the tuber and that the so-called "oxygenase" is in reality an autooxidizable, lecithin-like substance. It has been pointed out by Bang (1911) that the compound lipides are the most labile of the constituents of the protoplasm and that many of the striking properties of protoplasm may be due to these substances, especially the phospholipides, rather than to the proteins. The compound lipides evidently play an important rôle in the activities of the living cell, but, in the words of MacLean and MacLean (1927), it is not yet possible to dissociate these compounds from the other cell constituents and attribute to them alone any specific properties associated with the cell.

6. Synthesis of the Lipides.—The study of the synthesis of the lipides in the plant has been confined almost entirely to the changes occurring in the development of oily seeds. The term "lipides" as here used refers almost without exception to the crude lipides, since the quantity of oily matter has been estimated by determining the ether extract.

a. Relation of the Carbohydrates to the Formation of Fats and Oils.—It was first observed by De Luca (1861, 1862) that as the sugar content of the developing olive diminished progressively, the amount of oil correspondingly increased, so that when the oil content had reached its maximum the sugar had disappeared. The same fact was observed by Leclerc du Sablon (1896) in studying the development of the kernels of the walnut and almond. Some of the data obtained by him are shown on page 583.

Although the disappearance of carbohydrates and the appearance of fats and oils in a developing organ have been considered as evidence that carbohydrates are transformed into fats and oils, this fact in itself is not conclusive evidence that such is the case. In order to obtain more information on this subject, Gerber (1897) studied the respiratory quotient of the developing olive and the seeds of the almond, castor bean, rape, peach, and others. He found that during the period when

PERCENTAGE OF OIL, GLUCOSE, SUCROSE, STARCHES, AND DEXTRINS IN THE DEVELOPING KERNEL OF THE WALNUT AND ALMOND

Date	Oil	Glucose	Sucrose	Starches and dextrins
Walnut				
July 6.....	3	7.6	0.0	21.8
Aug. 1.....	16	2.4	0.5	14.5
Aug. 15.....	42	0.0	0.6	3.2
Sept. 1.....	59	0.0	0.8	2.6
Oct. 4.....	62	0.0	1.6	2.6
Almond				
June 9.....	2	6.0	6.7	21.6
July 4.....	10	4.2	4.9	14.1
Aug. 1.....	37	0.0	2.8	6.2
Sept. 1.....	44	0.0	2.6	5.4
Oct. 4.....	46	0.0	2.5	5.3

the sugar content had reached its maximum and before any fats and oils had yet been formed, the respiratory quotient was less than unity. During the period when the sugar content was diminishing and the oil content was increasing, the respiratory quotient was greater than unity, as, for example, in the olive where it ranged from 1 to 1.46. After the sugar had disappeared from the developing seeds and the oil content had reached its maximum, the respiratory quotient again fell to less than unity. Since citric, tartaric, or malic acid, which give rise to a respiratory quotient greater than unity, were not found in these developing seeds, and since there was no production of alcohol, which is also accompanied by a coefficient greater than unity, Gerber concluded that there is a relationship between the disappearance of carbohydrate and the respiratory quotient. He thus considers that the respiratory quotient of these developing organs indicates that the oil is being produced at the expense of the carbohydrate.

b. Changes in the Fats and Oils during Their Formation.—As an oily seed develops, the percentage of oil gradually increases. Except for the period immediately following blooming and directly preceding maturity, there is throughout the development of the seed a gradual and rather uniform gain in the oil content. There is a very sharp increase in the percentage of oil during the first few weeks after blooming and a slow gain until near the end of the ripening period in the case of the soybean (Garner, Allard, and Foubert, 1914). At this time a decrease in the size of the seed and in the oil content occurs, probably due to an intense respiration at that period. The changes in the oil content during the


development of the seed may be illustrated by the data obtained by Dillman (1928) for the developing flax seed:

Time of sampling, number days after flowering	Percentage of oil in the developing seed	Time of sampling, number days after flowering	Percentage of oil in the developing seed
8	1.8	24	37.5
9	2.3	27	40.2
12	8.5	30	40.7
15	26.0	33	40.7
18	34.6	36	40.6
21	35.5	39	40.7

The factors influencing the percentage of oil in oily seeds have been studied by Garner, Allard, and Foubert (1914) and Stark (1927). By partially defoliating the plants, the number and size of beans produced was decreased, while the percentage of oil was somewhat increased. The general climatic conditions during the growing season seem to have a more marked effect on the oil content than does the length of the season. The difference in the amount of oil per seed may be as much as 100 per cent, while the percentage of oil may vary as much as 7 or 8 per cent. These authors consider that the maximum production of oil in soybeans requires conditions of nutrition favorable to the accumulation of carbohydrates during the vegetative period. Stark (1927) found that the application of limestone and inorganic matter to the soil decreased the percentage of oil in the soybean, while the addition of rock phosphate to the above fertilizer further decreased the oil content of the seed. He observed that by varying the soil conditions, greater differences could be obtained within the variety than generally exist between most varieties.

Ivanow (1911) studied the changes that occur in the carbohydrates and oils in the seeds of flax, hemp, rape, and sunflower during their ripening. His observations indicate that there is a connection between the carbohydrates and the higher fatty acids. The first fatty acids which are developed in these seeds from carbohydrates are the saturated ones and evidently belong to the higher series of the fatty acids, since they are not volatile as indicated from their Reichert-Meissl values. It was observed that the acid values of the ether extract decreases sharply with the ripening of the seed. Thus in the case of flax, in one experiment, the acid value decreased from 15.4 to 5.6, in hemp from 5.8 to 2.7, in rape from 74 to 9.4, and in sunflower from 46 to 8 during their first ripening period. The evidence seemed to indicate that the unsaturated acids are derived from the saturated ones, and Ivanow suggested the

following scheme to illustrate the procedure in the formation of oil from carbohydrates:



The following data taken from his work show the changes that occur in the oil of ripening seeds:

Date	Seed and stage of development	Per cent of oil	Acid value	Iodine value	Saponification value
	Flax:				
July 5	Flowering	2 3	15.4	120 6	38.0
July 18	Seed soft and green	11.0	3.6	151.0	185.7
Aug. 3	Seed unripe	32 5	4.0	168.0	188.7
Aug. 25	Seed ripe	35 0	5.6	175.0	186.8
	Rape:				
July 7	Seed clear and soft	10 0	74.3	210.3
July 25	Seed green and opaque	37.5	16.0	99.8	213.1
Aug. 8	Seed unripe	48 3	13 8	95 3	
Aug. 23	Seed ripe	49.9	9 4	97.5	202.8
	Hemp:				
Aug. 17	Two weeks after bloom	15 3	5.8	152.1	222.7
Aug. 28	Seed unripe	27.0	2.5	155.0	222.7
Sept. 13	Seed unripe	33 5	2.7	154 0	229.0

Priestley (1924) considers that when the fatty acids are finally deposited in the endodermis, cuticle, or cork layers they undergo oxidation and condensation and in so doing lose, for the most part, their power of dissolving in fat solvents. They are thus changed in the same general way as are certain of the vegetable oils in the drying process which they undergo on exposure to the air.

c. General Observations.—Although the fatty oils are quite different chemically from the carbohydrates, there is an intimate and significant physiological relationship between these two classes of compounds in the plant. There is considerable evidence to indicate that fats and oils are formed from carbohydrates and that in germination of oily seeds, as will be mentioned later, the fats give rise to carbohydrates. The fact that the disappearance of the carbohydrate and the increase in the oil content proceeds in unripe seeds detached from the plant is considered as further supporting the evidence that oil is derived from carbohydrate in the plant. Outside the living cell, however, the transformation of carbohydrates into fats and oils or the reverse has been accomplished only in a slight way (Smedley and Lubrzynska, 1913). Smedley (1912) prepared

fatty acids from carbohydrates by breaking the hexoses into three carbon compounds and then oxidizing these into pyruvic acid, $\text{CH}_3\text{CO}\cdot\text{COOH}$, which was then condensed into acids with longer carbon chains. These reactions are accomplished only with great difficulty in the laboratory, and there is no evidence whatsoever that the formation of oil in the plant follows this procedure.

The particular carbohydrate which is transferred directly into the fats and oils, however, is not known (Vallee, 1903). According to Terroine (1920), saccharose is the last sugar to disappear in the maturation of oily seeds and the first to appear upon their germination. This, however, is not sufficient evidence to state that it is the carbohydrate which is transformed directly into the oil.

Some evidence has been obtained that indicates that fats and oils may be formed in plants from other materials than carbohydrates. Thus M'Clenahan (1909) considered that the tannins might afford the material for the formation of the oil in the developing kernel of the walnut. Scurti and Tommasi (1910, 1911) and Scurti and Formaini (1911) observed that the ether-soluble substance of the green olive fruit consists almost entirely of oleanol, a higher alcohol, $\text{C}_{31}\text{H}_{50}\text{O}_3$, and that later in the process of development it is still present but that, in addition, higher fatty acids both saturated and unsaturated are found. When the ripening of the fruit is progressing, the ether extract consists almost entirely of neutral oil. Oleanol occurs in the leaves of the olive, and it was considered by these investigators that this alcohol is produced in the leaf and is transported to the fruit when it is transformed into neutral oil. They examined other fat-containing seeds and fruits, and in all cases an alcohol closely related to oleanol was found in the leaves and fruits, and, as it diminished in amount, neutral oil increased. If a procedure like that above occurs, it is not in accord with the high respiratory quotients reported by Gerber (1897) during the ripening process, since the conversion of oleanol into fatty acids would be accompanied by a respiratory quotient less than unity.

Although oily seeds are generally rich in protein and the accumulation of oil proceeds simultaneously with protein, there is no evidence of any relationship between the two processes. In the case of the soybean, however, Stark (1927) noted that the conditions which produce an increase in the percentage of protein result in a decrease in the oil content, and *vice versa*.

It is not known whether the formation of oil is brought about by the protoplasm itself or results from a set of reactions catalyzed by the plant enzymes which could also be performed by the extracted catalysts. The synthesis of fats from fatty acids and glycerol in the presence of oil-free material from oily seeds was undertaken by Dunlap and Gilbert (1911). They found that flax seed is a good emulsifying

agent, so that when glycerol, oleic acid, and oil-free castor-bean powder are mixed with it and thoroughly ground together an emulsion is formed which persists for many days, and as a result of such a mixture they obtained evidence of the synthesis of oil. The method used for detecting the synthesis of oil in such a mixture was as follows: Equal portions of the mixture were placed in a series of flasks, with the exception that in the control flask the oil-free castor-bean material was replaced by an equal amount of flax seed. The acid content of the flasks was determined at successive periods with the following results:

Period	Milligrams of oleic acid in one gram of the mixture	
	Control, without castor-bean powder	Experiment, with castor-bean powder
At once.....	315.5	337.3
After 2 days.....	319.0	322.0
After 6 days.....	314.8	311.0
After 11 days.....	314.9	248.6

The decrease in the amount of acid present could be accounted for only by the esterification of the oleic acid. The results, however, do not show whether the combination of the oleic acid and the glycerol produces a mon- or diglyceride before the triglyceride is produced.

An interesting observation was made by Abegg (1929) on the effects of the waxy gene in maize on fat metabolism. He noted that the average acid value of the ether-soluble crude oil from non-waxy maize was 13, while that of the waxy was 34. The average saponification number of the crude fats from the non-waxy endosperm was 177 and that from the waxy 200. These marked differences between the non-waxy and waxy types of grain are restricted to the endosperm tissue. The evidence indicates that the waxy gene in maize produces marked effects upon the fat metabolism of the endosperm tissue. It is considered that the activities of this gene are connected with the synthetic and hydrolytic powers of maize endosperm lipase. It appears that the waxy-type lipase does not affect a condensation of fatty acids with glycerol to the same degree as does the non-waxy, hence the waxy endosperm contains a crude fat the acid value of which is higher than that from the non-waxy type.

7. Changes in the Fats and Fatty Oils during Germination. *a. Changes in the Amount of Oil.*—In 1842 it was observed by De Saussure that as the germination of rape and hemp seeds progressed, the amount of oil in the seeds diminished. He undertook this work in order to test the suggestion that the oil in seeds might subserve the same purpose during germination as the starch in the cereal grains. It is now known

that the fats and oils are reserve foods, and all of the numerous investigators who have studied oily seeds, since the time of De Saussure, agree that the oils in seed disappear during the course of germination. This behavior of the oily matter in seeds may be illustrated by the data obtained by Miller (1910, 1912) in the case of sunflower seeds and seedlings, as shown in the following table:

Parts of seeds or seedlings	Seeds	Seedlings				
		4 days	5 days	7 days	10 days	14 days
Percentage of ether extract on dry basis						
Cotyledons.....	55.6	55.9	51.2	33.9	16.7	13.5
Hypocotyls and roots....	47.4	24.2	9.3	9.7	9.8	11.4
Grams of ether extract per 100 seeds and seedlings						
Cotyledons.....	3.786	3.00	2.53	1.298	0.501	0.317
Hypocotyls and roots....	0.219	0.188	0.123	0.214	0.273	0.238

It is noted from the above data that after four days the percentage of oil in the cotyledons is the same as or somewhat higher than that in the cotyledons of the seed, while the actual amount of oil has markedly diminished. This fact has been frequently observed in the germination of oily seeds and may be attributed to one or two causes. In the first place, it may be due to the depletion of the protein and carbohydrate reserve in a relatively greater amount than the oily reserve during that period. On the other hand, it may be due to the combining of oxygen with the unsaturated oils, thus increasing their weight to the same extent as or a greater extent than it has been diminished by depletion during the period under consideration. In most oily seeds, the oily reserve begins to disappear at a very early stage. In the case of the sunflower seed four days after planting, when the hypocotyls and roots have a length of only 2.5 to 3.5 cm., over one-fifth of the oil has already disappeared. In the roots and hypocotyls the actual amount of ether extract remains practically constant (Miller, 1910, 1912; Peters, 1861; and Schmidt, 1891).

b. Chemical Changes in the Oily Reserve.—The changes in the chemical nature of the oily reserve in seeds during germination have been studied for many seeds by numerous investigators. Miller (1912) studied in considerable detail the changes in the oily reserve of the sunflower seed during its germination, and his work is summarized in tabular form as an example of the general changes which the oily reserve undergoes during germination.

CHEMICAL NATURE OF THE ETHER EXTRACT OF THE COTYLEDONS, HYPOCOTYLS, AND ROOTS OF THE SUNFLOWER SEEDS AND SEEDLINGS

Items considered	Seeds	Stage I 3½ days	Stage II 5 days	Stage III 7 days	Stage IV 10 days	Stage V 14 days
Cotyledons						
Dry weight of the cotyledons of 100 seedlings	4 884	3 153	2 785	2 319	2 021	1 621
Ether extract (percentage of dry material)	54 1	52 6	49 2	36 0	16 8	8 7
Grams of ether extract per 100 cotyledons	2 642	1 658	1 370	0 834	0 339	0 141
Percentage of the original oil present		62 7	51 8	31 8	12 8	5 3
Acid value of the ether extract	1 6	1 7	1 5	4 6	27 5	60 8
Percentage of free fatty acid in ether extract ¹	0 008	0 009	0 009	2 3	13 8	33 5
Saponification value of ether extract	189 3	190 9	192 1	184 3	186 1	204 2
Saponification value of the neutral oil	188 4	189 1	190 6	188 2	184 4	226 1
Total insoluble acids of ether extract	95 4	96 0	95 7	93 6	87 6	84 8
Total insoluble acids of the neutral oil	94 6	95 2	94 7	95 9	88 9	
Total soluble acids of ether extract ²	0 005	0 005	0 007	0 005	0 008	4 5
Total soluble acids of the neutral oil ²	0 005	0 003	0 006	0 003	0 002	3 0
Iodine number of the ether extract	125 5	126 4	124 5	125 8	120 1	111 7
Iodine number of the neutral oil	124 9	126 0	124 1	126 0	119 9	111 9
Acetyl saponification value of ether extract	222 7	225 0	225 1	215 0	236 3	263 6
Acetyl value of ether extract	40 1	39 0	40 6	38 2	36 5	37 5
Hypocotyls and roots						
Dry weight of the hypocotyls of 100 seedlings		0 605	0 885	1 21	1 52	2 17
Ether extract (percentage of dry material)		9 9	7 4	3 8	3 1	1 8
Grams of ether extract per 100 hypocotyls		0 060	0 065	0 046	0 017	0 040
Acid value of ether extract		18 2	24 0	27 1	58 3	97 8
Percentage of free fatty acid in ether extract ¹		9 1	12 0	13 4	26 4	49 1
Saponification value of ether extract		190 3	189 2	198 4	236 9	238 3
Total insoluble acids in ether extracts		89 6	85 6	86 5	67 1	57 2
Total soluble acids in ether extract ²		1 0	1 6	1 8	16 1	18 5
Iodine number of ether extract		117 7	118 8	96 1	72 6	48 3
Acetyl saponification value of ether extract		251 4	300 0	274 8		
Acetyl value of ether extract		71 2	114 0	95 1		

¹ Estimated as oleic acid.² Estimated as butyric acid.

1. *Fatty Acids of the Oil.*—It was first observed by Fleury (1865) that non-volatile acids appeared during the germination of oily seeds. Muntz (1871) in the study of the seeds of the rape, poppy, and radish observed for the first time that during germination the oil in the seeds gives rise to free fatty acids. In the case of these particular seeds, the amount of free fatty acids in the oil increased from 10 per cent in the resting seed to as much as 98 per cent in the 10-day seedlings. The increase in the amount of free fatty acid in the germination of oily seeds has since that time been observed by Leclerc du Sablon (1895, 1897), Miller (1911, 1912), Ivanow (1912) and others.

It was suggested by Muntz (1871) that the oil during germination is split up into glycerine and fatty acids. In 1890 Green discovered the

enzyme lipase in the castor-bean seedling and showed that the fats and oils are hydrolyzed into fatty acids and glycerine by its action. Although glycerine is easily obtained by the hydrolysis of fats and oils under artificial conditions, no one has as yet been able to detect it in the germinating seeds and seedlings. The changes that occur in the fatty acids of the oil of seeds and seedlings has for the most part been observed in the ether extract of the entire seedling. In order, however, to understand the significance of the changes in the oily reserve in the metabolism of the seedling, the changes in the oil in the cotyledons or in the endosperm must be considered separately from the oily material of the roots and hypocotyls.

(a) *Fatty Acids of the Cotyledons.*—The changes in the fatty acids of the oil of the sunflower seed during its germination were studied in considerable detail by Miller (1912). In this seed the oily reserve is stored in the cotyledons and amounts to approximately 50 per cent of their dry weight. Miller observed that the ether extract of the cotyledons has an acid value of 1.6 in the resting seed and that this remains constant until one-half of the oil has disappeared. In the 7-day seedlings when the cotyledons are above ground and are spread out perpendicular to the hypocotyl and when the oily reserve has decreased to one-third its original amount, the acid value rises to 4.6. The acid value continues to increase so that when only 5.3 per cent of the original amount of oil remains the acid value amounts to 66.8. The free fatty acids, estimated as oleic, constitute less than 1 per cent of the ether extract of the seed. This remains constant until over two-thirds of the oil has disappeared, after which it increases to 2.3 per cent of the ether extract. This percentage continues to increase until at the end of two weeks the free fatty acids constitute 33.5 per cent of the oily material in the seed. Some of the free fatty acids present in the cotyledons are those of low molecular weight and are soluble in water, but most of them are of higher molecular weight and are insoluble in water.

The iodine value of the oils of seeds at different stages of germination has been studied by Ivanow (1912), Jegorow (1904), and Miller (1912). It has been observed that as the germination of flax, hemp, and rape progressed, the iodine value of the oil decreased. In the sunflower seed, the iodine value of the ether extract is 125. This value remains constant for a considerable period of time and drops to only 120 when the seedlings are 7 days old. After 14 days, when only 5.3 per cent of the original oil remains in the cotyledons, the iodine value falls to 111.8. Miller (1912) considered that this decrease in the iodine value of the oil of the seed during germination indicates that unsaturated fatty acids are becoming saturated. Ivanow (1912), however, considered that this conclusion is erroneous and that the decrease in the iodine value indicates that the unsaturated fatty acids are being utilized. He noted that the unsatu-

rated fatty acids are the first to disappear during germination. Thus in the flax and hemp seedlings the linolenic acids first disappeared, then the linolic, and finally the oleic series.

The saponification value of the oil in the cotyledons of the sunflower seed does not change until the oily reserve has been depleted to 5.3 per cent of the original amount. There is a marked increase in the saponification value at this period, which indicates the presence of glycerides or free fatty acids of lower molecular value than those originally contained in the cotyledons of the seed.

The acetyl value of the ether extract of the sunflower seed is 40.1, a value which remains practically constant during all stages of the germination. There is thus apparently no increase in the number of the hydroxyl groups of the oil during any stage of germination. These observations are in accord with those of Von Fürth (1904) for the sunflower and castor bean.

(b) *Fatty Acids of the Roots and Hypocotyls*.—Miller (1912) observed in the roots and hypocotyls of the sunflower seedlings that the saponification value of the ether extract remained practically constant at 190 until the seventh day when it increased to 198. After that it increased rapidly until at the end of 2 weeks it had risen to 238.

The amount of insoluble fatty acids remains constant during the 7-day period and is about 10 per cent less than the amount of insoluble acid present in the ether extract of the cotyledons at the same stages. After the first week the amount of insoluble acid falls rapidly and amounts to only 57.2 per cent of the oily material present at the end of 14 days, as compared to 90 per cent at the beginning of germination. The amount of soluble fatty acids during the first 7 days of germination changes but little, being about 2 per cent, the amount being somewhat higher than that contained in the oily matter of the cotyledons at these stages. During the second week of germination the amount of soluble fatty acids increases rapidly and amounts to 18.5 per cent of the oily matter present at the end of 14 days. The acid value increases from 18.2 at the first stage of the seedling to 97.8 at the last stage examined. During the first week of germination there is evidence that a considerable portion of the free acid is composed of acids of higher molecular weight which are insoluble in water. During the last week of germination, however, the free acids present seem to be composed entirely of those of low molecular weight which are soluble in water.

The iodine value of the ether extract of the cotyledons and roots remains at 118 until the end of 7 days when it falls to 96 and finally to 48.3 at the end of 2 weeks. The iodine value is thus considerably lower at the earlier stages of germination than it is in the oily material of the cotyledons.

The acetyl value of the ether extract of the hypocotyls and roots is approximately twice as great as that of the ether extract of the cotyledons and increases in value as germination progresses.

The properties of the ether extract of the hypocotyls and roots during the first 7 days of germination bear a striking resemblance to those of the ether extract of the cotyledons during that time. Observations, however, indicate that the changes in the oily material of the hypocotyls and roots during the earlier stages of germination consist in a gradual but evident breaking down of the higher free fatty acids and glycerides into those of lower molecular weight, the saturation of the fatty acids, or the utilization of the unsaturated ones and an increase in the amount of hydroxyl groups present. During the later stages of germination, however, these changes are rapid and very marked, as indicated by the different values determined.

2. Relation of Carbohydrates to the Disappearance of the Fats and Oils.—It was first observed by De Saussure (1842) that as the oily reserve disappeared in the germination of oily seeds, the carbohydrate content of the seeds and seedlings increased. Hellriegel (1855) examined the seedlings of rape at five different stages of growth. He found that the oil decreased from 47 per cent in the seed to 36 per cent in the oldest seedlings and that at the same time the sum of the sugar, organic acids, and tannin increased from 7.7 to 15.4 per cent. He also observed that the seeds contained 3.4 per cent cane sugar and that during the early stages of germination it disappeared. This fact has been noted by other investigators since that time, and it is inferred that the sugar is utilized directly at the beginning of germination before the oily reserve has been transformed or before it has become available.

Sachs (1859, 1863) concluded that the oil in seeds is transformed during germination into starch or sugar, but he did not consider that starch is a transition between oil and sugar or sugar between oil and starch. The fact that sugar increases in the germination of oily seeds as the oily reserve decreases has also been observed by Peters (1861), Laskovsky (1874), Detmer (1875), Green (1890), Leclerc du Sablon (1893 to 1897), Maquenne (1898), Mazé (1900), Kirkwood and Gies (1902), Miller (1910), and others. The changes in the amounts of oil, protein, and carbohydrate in the seedlings of the sunflower as found by Miller (1910) are shown in the table on page 593.

Thus in the case of the sunflower the amount of sugar in the resting seed amounts to 4.1 per cent. Of this amount all but a trace is non-reducing sugar and has been identified as cane sugar. The total weight of sugar in the cotyledons of the seedlings at all stages is comparatively small. At the beginning of germination the non-reducing sugar falls rapidly until the 4-day stage, after which it gradually increases until the cotyledons begin to unfold. Up until that time the only sugar present

Constituents	Seed		4 days		5 days		7 days		10 days		14 days	
	Cot.	Hyp. and roots	Cot.	Hyp. and roots	Cot.	Hyp. and roots	Cot.	Hyp. and roots	Cot.	Hyp. and roots	Cot.	Hyp. and roots

Average percentage of constituents

Ether extract...	55.6	47.4	55.9	24.2	51.2	9.3	33.9	9.7	16.7	9.8	13.5	11.4
Total sugars	4.1	4.1	1.1	9.2	1.8	22.5	3.1	18.6	3.1	12.6	2.1	7.7
Reducing sugar ...	Tr.	Tr.	None	8.7	None	20.5	1.4	17.3	3.1	12.6	1.1	7.7
Protein ...	24.4	25.3	22.0	14.2	21.0	9.4	19.8	9.3	21.0	7.0	20.4	6.5

Grams of constituents per 100 seeds and seedlings

Ether extract...	3.786	0.219	3.00	0.188	2.53	0.123	1.298	0.214	0.501	0.273	0.317	0.238
Total sugar ...	0.279	0.019	0.06	0.071	0.09	0.298	0.12	0.431	0.09	0.351	0.05	0.161
Reducing sugar ...	Tr.	Tr.	None	0.068	None	0.271	0.054	0.382	0.09	0.351	0.025	0.161
Protein ...	1.66	1.17	1.18	0.110	1.03	0.125	0.76	0.205	0.63	0.195	0.48	0.135

in the cotyledons is of the non-reducing type, but when the cotyledons assume the foliage functions, reducing sugars begin to make their appearance, and in the 10-day seedlings it is the only sugar present.

The percentage of total sugar rapidly rises in the hypocotyls and roots, and when they have reached a length of 3 to 4½ in. it amounts to 20 per cent of their dry weight. After that period it decreases, and in the 10-day seedling it amounts to 12.6 per cent. The actual amount of sugar, however, reaches its maximum at the end of the 7-day period when the cotyledons have just spread out, and from that time on it gradually decreases. A small amount of starch appears in the starch sheath of the hypocotyls and roots and in the parenchyma cells of the vascular bundles of the cotyledons during the process of germination.

The marked increase in the amount of carbohydrate in the seedlings of oily seeds raises the question as to its origin. Miller (1910) has shown that in the sunflower the changes in the protein reserve could not account for the increase in carbohydrate. The only other possible source of the sugar, then, is the oil, but how sugar is formed from this is not known. Detmer (1875) considered that when oil is hydrolyzed in the seedling the glycerine formed is changed into unknown bodies and the free fatty acids might be the source of the carbohydrates. Green (1890) considered

that the glycerine formed gives rise directly to sugar and that the free fatty acids give rise to vegetable acids. Leclerc du Sablon (1895) thought that the glycerine with the acids still combined with it goes directly to form carbohydrate, since he found that the amount of free fatty acids as well as sugar increased during the process of germination and since glycerine could not be detected. He thus considered that fatty acids were liberated in such a way that glycerine is not set free. Maquenne (1898) and Ivanow (1912) considered that the unsaturated fatty acids contribute to the formation of sugar. Pirschle (1926) found considerable amounts of acetaldehyde in germinating fatty seeds of several different genera and families and considers that it might possibly be the compound through which the fatty acids pass in being transformed to carbohydrates. A study of the fatty-acid-to-sugar process was made by Rhine (1926). He extracted enzymes from germinating fatty seeds by the methods used in extracting lipase. One part of fatty acid to ten parts of enzyme extract was placed in small flasks and slightly acidified with HCl and kept at 40°C. with frequent agitation for varying periods of time. The results of this simple experiment indicated that a slight decomposition of fatty acids occurred and that a small amount of a water-soluble reducing substance was produced.

In later and more elaborate experiments, higher temperatures, increased acidity, and an abundance of oxygen were substituted for enzyme action upon the mixture of fatty acids and water. In an 800 cc. Kjeldahl flask fitted with a reflux condenser and heated at temperatures varying from 75 to 95°C. were placed 100 cc. of fatty acid and 200 cc. of water. Air from a pressure tank was allowed to bubble through the mixture and served to keep a good emulsion and to furnish an oxygen supply. After varying periods of such treatment, it was found that water-soluble, ether-soluble, non-volatile aldehydes were produced which had more oxygen than that of the ordinary aldehyde or carbonyl group. The actual structure of these substances, however, is not known, but Rhine considered that they approached more nearly the sugars in structure than any products yet reported in the literature. Short-chain acids were also produced which were ether, water, and alcohol soluble and which were fermentable by bread yeast, yielding carbon dioxide and fermenting in about the same time as glucose with the same yeast.

B. FATTY SUBSTANCES NOT COMPOUNDS OF FATTY ACIDS

Two of the more important groups of substances which are not compounds of fatty acids that may be found in the crude lipides are the essential oils and resins. These substances, according to Thatcher (1921), include those compounds to which the characteristic odors of plants are due, along with others similar in structure and possessing characteristic uniformity in composition, and belong to several widely different chemical groups. The essential oils may be divided into two major groups: (1) the hydrocarbon oils or terpenes, some forms of which constitute the main pro-

portions of the oils of turpentine, bergamont, lemon, eucalyptus, fennel, and pennyroyal; (2) the oxygenated and sulphuretted oils. The oxygenated essential oils include alcohols, aldehydes, ketones, acids, and phenols derived from either five-membered or six-membered closed-ring hydrocarbons. These compounds include, among others, menthol, oil of bitter almonds, oil of cinnamon, camphor, and thymol. The two most common sulphuretted oils are oil of mustard and oil of garlic. The latter is present in onions, garlic, radishes, and many other plants. The difference in flavor of these plants is due to the fact that the allyl sulphide is united with other different groups in the glucoside arrangement.

The resins are the oxidation products of the terpenes, but their exact structure is little understood. They are divided into two classes, the balsams and the solid or hard resins. Canada balsam and crude turpentine are examples of the first class and consist of resinous substances dissolved with fluid terpenes. Asafoetida and myrrh are resinous substances which are mixtures of gums and true resins.

The use of the essential oils and resins to the plant is not known. They are formed sometimes normally in healthy tissue and at other times they are the result of injury or disease. They are frequently classed as excretions, since aside from possible protective influences to the plant no biological use of these substances is known.

Questions

485. What are the crude lipides? Into what two main groups may they be divided? Classify the crude lipides that may occur in plant tissue.

486. What are the lipides? What is a fatty acid? Why so called? Where do fatty acids occur in plants? Into what two series may they be divided?

487. What is a saturated fatty acid? What is the general formula for this series? Enumerate the more important saturated fatty acids and state where and in what condition they occur in plants.

488. What are the unsaturated fatty acids? With what may these acids be made to combine? What is the general formula of the oleic series? Of the linolic series? Of the linolenic series?

489. Where and in what form do these acids occur in plants? What are hydroxy-fatty acids? Name the general properties of glycerol. How may it be obtained artificially?

490. What are the following and where do they occur: ceryl alcohol, myricyl alcohol, cholesterol, phytosterol, and sitosterol?

491. Into what three classes may the lipides be grouped? What are the simple lipides? Into what two groups may they be divided? What are the fats and fatty oils?

492. What distinguishes a fat from an oil? What is meant by the statement that the fats and oils are mixtures of triglycerides? Which triglycerides make up the bulk of the natural fats and oils?

493. Give examples to show the percentage of fatty acids in the more common fats and oils. State the general physical characteristics of the fats and oils. What is meant by the hydrolysis of fats and oils? Give an example.

494. By what two means may fats and oils be hydrolyzed? What is the significance of the hydrolysis of fats and oils in the plant? What is meant by the saponification of fats and oils? Give an example. How is this process carried out in the laboratory?

495. What is meant by the drying of oils? What are non-drying oils? Name some oils that belong to this group. What are the drying oils? Name some drying oils. What are semidrying oils? Name some oils of this group.

496. Name five chemical values that are used as measures of characteristics of fats and oils. What is the acid value of a fat or oil? What does it indicate?

497. What is the Hehner value? What does it indicate? What is the saponification value? What does it show in regard to the nature of the fat under consideration? Give the saponification value of some of the more common fats and oils.

498. What is the iodine value? What does it show? State the iodine values of some of the more common fats and oils. What is the acetyl value? What does it measure?

499. What are the waxes? Name some of their more general properties. What are the compound lipides? By what other names have they been designated?

500. What are the phospholipides? By what other names have they been called? What is lecithin? Kephalin? Galactolipides? By what other names have the galactolipides been designated?

501. What are the derived lipides? Name some of them.

502. Enumerate the various cells and cell parts in which lipides have been detected in plants. Discuss in detail the data in regard to the manner of the distribution of the lipides in the protoplasm. How does the dispersion of the fatty substances in the protoplasm change during germination? During the deposition of the oil in the formation of the seed?

503. What are eliaoplasts? What function has been attributed to them? What are oil vacuoles? What function do the reserves of fats and fatty oils serve in the plant?

504. In what plant parts are fats and oils found as storage products? In what parts are they present in the greatest abundance? In what part of seeds and fruits do the fats and oils occur?

505. Give some examples of the amounts of fats and oils contained in seeds and leaves. How does the unsaponifiable matter of the fats and oils from seeds compare with that of the fatty substances from leaves? Discuss the changes that occur in the oil and carbohydrate reserves of woody plants during the autumn and winter.

506. What is the chief obstacle in investigating the compound lipides in plants? Which compound lipides are the most abundant in plants? In what plant parts and in what amounts have the compound lipides been observed?

507. What is the relation of the amount of phospholipides to the protein and oil content of plant parts? Illustrate with examples. How does the phospholipide content of seeds vary with their degree of maturity? How does it vary for light and darkness? For different stages of germination?

508. Enumerate the functions that have been assigned to the compound lipides of the plant. Give data from chemical analysis which indicate that oil is formed in the developing seed at the expense of carbohydrates. Explain how the respiratory quotient of developing oily seeds gives the same indication.

509. Give data to show the changes in the oil content of oily seeds during their development. Enumerate some factors that influence the percentage of oil in seeds. What fatty acids appear to be the first to be formed from carbohydrates in oily seeds?

510. What appears to be the origin of the unsaturated fatty acids in seeds? What changes in acid value, iodine value, and saponification value do the oils of seeds undergo in the formation and maturity of the seeds? What do these changes indicate? What changes do the fatty acids undergo which are deposited in the endodermis, cuticle, or cork layers?

511. Discuss the evidence which indicates that fats and oils are synthesized in the plant from carbohydrates. Can this synthesis be accomplished artificially? Under what conditions? From what other compounds might fats and oils be synthesized in the plant?

512. What relationship is there between protein and oil production in the seed? By what agents is the synthesis of fats and oils brought about? What influence does the waxy gene in corn have upon fat metabolism?

513. What changes occur in the percentage of oil in oily seeds during their germination? The percentage of oil in oily seeds sometimes shows an increase at certain stages of germination. To what might this be due?

514. What is the first change that the reserve fats and oils of seeds undergo in germination? What changes in the acid value, iodine value, saponification value, and acetyl value does the oil of the cotyledons of the sunflower seed undergo during germination? What do these changes indicate?

515. How do the above values vary for the ether extract of the roots and hypocotyls during the germinating period? What do these values of the ether extract indicate as to the changes in the oil of the roots and hypocotyls during germination?

516. What relation is there between the oil and sugar content of the seedlings of oily seeds during the germination period? In what part of the seedling do most of the sugars appear? What sugar predominates in amount?

517. Discuss in detail the methods used in an attempt to synthesize sugar from fatty acids. What results were obtained?

518. What are the essential oils and resins? What are the terpenes? Sulphuretted oils? Name several examples of each of these groups of compounds. Name some resins. Of what use are the resins and essential oils to the plant?

Bibliography

- ABEGG, F. A., 1929: Some effects of the waxy gene in maize on fat metabolism, *Jour. Agr. Res.*, **38**: 183-193.
- ALSBERG, C. L., and A. E. TAYLOR, 1928: The fats and oils. Leland Stanford Junior Univ., *Food Res. Inst.*, 1.
- ANDERSON, R. J., and M. G. MOORE, 1923: A study of the phytosterols of corn oil, cotton seed oil and linseed oil, *Jour. Amer. Chem. Soc.*, **45**, 1944-1953.
- , 1923: Composition of corn pollen. II, Concerning certain lipoids, a hydrocarbon and photosterol occurring in the pollen of white flint corn, *Jour. Biol. Chem.*, **55**: 611-628.
- , 1924: The phytosterols of the endosperm of corn, *Jour. Amer. Chem. Soc.*, **46**: 1450-1460.
- BANG, I., 1911: "Chemie und Biochemie der Lipoide," Wiesbaden. J. F. Bergman, 187 pp.
- BAUGHMAN, W. F., D. BRAUNS and G. S. JAMIESON, 1920: Cantaloup seed oil, *Jour. Amer. Chem. Soc.*, **42**: 2398-2402.
- and G. S. JAMIESON, 1920: The composition of Hubbard squash seed oil, *Jour. Amer. Chem. Soc.*, **42**: 152-157.
- and ———, 1921: The chemical composition of corn oil, *Jour. Amer. Chem. Soc.*, **43**: 2696-2702.
- and ———, 1922: The chemical composition of soy-bean oil, *Jour. Amer. Chem. Soc.*, **44**: 2947-2952.
- BEER, R., 1909: On elaioplasts, *Ann. Bot.*, **23**: 63-72.
- BLOOR, W. R., 1925: Biochemistry of the fats, *Chem. Rev.*, **2**: 243-300.
- CHIBNALL, A. C., and H. J. CHANNON, 1927: The ether-soluble substances of cabbage leaf cytoplasm. I, Preparation and general characters, *Biochem. Jour.*, **21**: 225-232.
- and ———, 1927: The ether-soluble substances of cabbage leaf cytoplasm. II, Calcium salts of glyceridphosphoric acids, *Biochem. Jour.*, **21**: 233-246.
- CZAPEK, F., 1913: "Biochemie der Pflanzen," 1: 710-733, Gustav Fischer.
- DANGEARD, PIERRE, 1923: Remarques sur l'état de l'huile à l'intérieur des graines oléagineuses, *Compt. Rend. Acad. Sci. Paris*, **177**: 67-69; *Bot. Abs.*, **13**: 487.
- DELEANO, N. T., 1909, 1910: Recherche chimique sur la germination *Centrbl. Bakt.* II, **24**: 130-146; *Arch. Sci. Biol.* (St. Petersburg), **15**: 1-24.

- DELUCA, S., 1861, 1862: Recherches sur la formation de la matière grasse dans les olives, *Compt. Rend. Acad. Sci. Paris*, **53**: 380-384, **55**: 470-473, 506-510.
- DESSAUSURE, T., 1842: Ueber das Keimen der Oelsamereien, *Froriep's Notizen*, **24**: 24.
- DETMER, W., 1875: "Phys-chem. Untersuchung über die Keimung ölhaltiger Samen," Gustav Fischer, Leipzig.
- , 1880: "Vergleichende Physiologie des Keimungsprocesses," pp. 336-338, Jena.
- DILLMAN, A. C., 1928: Daily growth and oil content of flaxseeds, *Jour. Agr. Res.*, **37**: 357-377.
- DUNLAP, F. L., and L. O. GILBERT, 1911: The synthesis of fats by the action of enzymes, *Jour. Amer. Chem. Soc.*, **33**: 1787-1791.
- EULER, H., and E. NORDENSON, 1908: Zur Kenntnis des Möhreencarotens und seiner Begleitsubstanzen, *Zeits. f. physiol. Chem.*, **56**: 223-235.
- FLEURY, M., 1865: Recherches chimiques sur la germination, *Ann. Chim. et Phys.*, 4e série, **4**: 38.
- FRANCIS, C. K., and W. G. FRIEDEMANN, 1917: The fats and fatty acids of the grain sorghums, *Okla. Sta. Bull.*, **117**: 3-14.
- GALLAGHER, P. H., 1923: Mechanism of oxidation in the plant. I, The oxygenase of Bach and Chodat: Function of lecithins in respiration. *Biochem. Jour.*, **17**: 515-529.
- GARNER, W. W., H. A. ALLARD, and C. L. FOUBERT, 1914: Oil content of seeds as affected by nutrition of the plant, *Jour. Agr. Res.*, **3**: 227-249.
- GERBER, C., 1897: Étude de la transformation des matières sucrées en huile dans les olives, *Compt. Rend. Acad. Sci. Paris*, **125**: 658-661.
- , 1897: Recherches sur la formation des réserves oléagineuses des graines et des fruits, *Compt. Rend. Acad. Sci. Paris*, **125**: 732-735.
- , 1901: Recherches sur la respiration des olives et sur les relations existant entre les valeurs du quotient respiratoire observé et la formation de l'huile, *Jour. de Bot. Année*, **15**: 9, 88, 121; *Bot. Centrbl.*, **89**: 622.
- GRAFE, V., 1925: Zur Physiologie und Chemie der Pflanzenphosphatide, *Biochem. Zeits.*, **159**: 444-448.
- and V. HORVAT, 1925: Die wasserlöslichen Phosphatide aus der Wurzel der Zuckerrübe. I, *Biochem. Zeits.*, **159**: 449-467.
- and H. MAGISTRIS, 1925: Zur Chemie und Physiologie der Pflanzenphosphatide. II, Die wasserlöslichen Phosphatide aus *Aspergillus oryzae*, *Biochem. Zeits.*, **162**: 366-398.
- and ———, 1926: Über die Phosphatide aus *Daucus carota*, *Zeits. wiss. Biol. Abt. E. Planta.*, **2**: 429-437.
- GUERRANT, N. B., 1927: Some relations of the phospholipins in seeds to other constituents, *Jour. Agr. Res.*, **35**: 1001-1021.
- GREEN, J. REYNOLDS, 1890: On the germination of the seed of the castor oil plant (*Ricinus communis*), *Proc. Roy. Soc.*, **48**: 370-392.
- and H. JACKSON, 1905: Further observations on the germination of the seeds of the castor oil plant, *Proc. Roy. Soc.*, B, **77**: 69-85.
- HABERLANDT, G., 1914: "Physiological Plant Anatomy," English translation, The Macmillan Company.
- HANRIOT, M., 1898: Sur la transformation de la graisse par oxydation directe, *Compt. Rend. Acad. Sci. Paris.*, **127**: 561-563.
- HANSTEEN-CRANNER, B., 1926: Untersuchungen über die Frage, ob in der Zellwand lösliche Phosphatide vorkommen, *Zeits. wiss. Biol. Abt. E. Planta.*, **2**: 438-445; *Bot. Abst.*, **1**: 610, 1927.
- , 1914: Über das Verhalten der Kulturpflanzen zu den Bodensalzen. II, Beiträge zur Biochemie und Physiologie der Zellwand lebender Zellen, *Jahrb. f. wiss. Bot.*, **53**: 536-598.

- HANSTEEN-CRANNER, R., 1926: Untersuchungen über die Frage ob in der Zellwand lösliche Phosphatide vorkommen, *Planta Archiv. f. wiss. Bot.*, **2**: 438-445.
- , 1919: Beiträge zur Biochemie und Physiologie der Zellwand und der plasmatischen Grenzschichten, *Ber. d. d. bot. Ges.*, **37**: 380-391.
- HELLRIEGEL, H., 1855: Beitrag zur Keimungsgeschichte der ölgebenden Samen, *Jour. f. prakt. Chemie*, **64**: 94.
- HICKS, GILBERT, 1895: Oil producing seeds, *Year Book, U. S. Dept. Agr.*, pp. 185-204.
- HILDITCH, THOMAS P., 1928: The chemical composition of vegetable seed fats in relation to the natural orders of plants, *Proc. Roy. Soc., B*, **103**: 111-117.
- IVANOW, S., 1912: Über die Verwandlung des Öls in der Pflanze, *Jahrb. f. wiss. Bot.* **50**: 375-386.
- , 1912: Über den Stoffwechsel beim Reifen ölhaltiger Samen mit besonderer Berücksichtigung der Ölbildungsprozesse, *Beih. Bot. Centrbl.*, **I**, **28**: 159-191.
- , 1911: Ueber Oelsynthese unter Vermittlung der pflanzlichen Lipase, *Ber. d. d. bot. Ges.*, **29**: 595-602.
- IWANOFF, L., 1902: Ueber die Umwandlungen des Phosphors beim Keimen der Wicke, *Ber. d. d. bot. Ges.*, **20**: 366-372.
- JACOBSON, H., 1889: Ueber einige Pflanzenfette, *Zeits. f. physiol. Chem.*, **13**: 32-65.
- JAMIESON, G. S., W. F. BAUGHMAN and D. H. BRAUNS, 1921: The chemical composition of peanut oil, *Jour. Amer. Chem. Soc.*, **43**: 1372-1382.
- and ———, 1922: The chemical composition of sunflower-seed oil, *Jour. Amer. Chem. Soc.*, **44**: 2952-2957.
- JEGOROW, M., 1906: Ueber Stoffmetamorphose bei der Samenkeimung von *Cucurbita maxima*, *Bot. Centrbl.*, **101**: 597-599.
- KNOP, W., 1859: Ueber ein phosphorhaltiges Oel der Erbsen, *Landw. Versuchs-Stat.*, **1**: 26-30.
- KORSAKOW, MARIE, 1910: Ueber den Einfluss der Zellipoide auf die Autolyse der Weizenkeime, *Biochem. Zeits.*, **28**: 121-126.
- KOSSEL, A., 1891: Chemische Zusammensetzung der Zelle, *Arch. Physiol.*, **1891**: 181-186.
- KIRKWOOD, J. E., and W. J. GIES, 1902: Chemical studies of the coconut with some notes on the changes during germination, *Bull. Torrey Bot. Club.*, **29**: 321-359.
- LASKOVSKY, N., 1874: Ueber einige chemische Vorgänge bei der Keimung der Kürbissamen, *Landw. Versuchs-Stat.*, **17**: 219-244.
- LEATHES, J. B., and H. S. RAPER, 1925: "The Fats," a mon., 243 pp., Longmans, Green and Co.
- LECLERC DU SABLON, M. 1893: Sur la germination du Ricin, *Compt. Rend. Acad. Sci. Paris*, **117**: 524-527.
- , 1894: Sur la germination des graines oléagineuses, *Compt. Rend. Acad. Sci. Paris*, **119**: 610-612.
- , 1895: Recherches sur la germination des graines oléagineuses, *Rév. Gén. Bot.*, **7**: 145-165, 205-215, 258-269.
- , 1896: Sur la formation des réserves non azotées de la noix et de l'amande, *Compt. Rend. Acad. Sci. Paris*, **123**: 1084-1086.
- , 1897: Sur la germination des amandes, *Rév. Gén. Bot.*, **9**: 5-16.
- , 1897: Sur les réserves oléagineuses de la noix, *Rév. Gén. Bot.*, **9**: 313-317.
- LEVENE, P. A., and I. P. ROLF, 1925: Plant phosphatides. I, Lecithin and cephalin of the soybean, *Jour. Biol. Chem.*, **62**: 759-766.
- , 1926: Plant phosphatides. II, Lecithin, cephalin and so-called cuorin of the soybean, *Jour. Biol. Chem.*, **68**: 285-293.
- MACDOUGAL, D. T., 1922: The probable action of lipoids in growth. *Proc. Amer. Phil. Soc.*, **61**: 33-53. *Science, n.s.*, **55**: 653-654.

- MACLEAN, H., and IDA MACLEAN, 1927: "Lecithin and Allied Substances," mon., 220 pp., Longmans, Green, and Co.
- M'CLENAHAN, F. M., 1909-1913: The development of fat in the black walnut. I, II, *Jour. Amer. Chem. Soc.*, **31**: 1093-1098; **35**: 485-493.
- MAQUENNE, L., 1898: Sur les changements de composition qu' éprouvent les graines oléagineuses au cours de la germination, *Compt. Rend. Acad. Sci. Paris*, **127**: 625-628.
- MAXWELL, W., 1891: On the behavior of the fatty bodies and the role of the lecithins during normal germination, *Amer. Chem. Jour.*, **13**: 16-24.
- MAZÉ, M., 1900: Recherches sur la digestion des réserves dans les graines, en voie de germination et leur assimilation par les plantules, *Compt. Rend. Acad. Sci. Paris.*, **130**: 424-427.
- MILLER, EDWIN, C., 1910: A physiological study of the germination of *Helianthus annuus*, *Ann. Bot.*, **24**: 693-726.
- , 1912: A physiological study of the germination of *Helianthus annuus*. II, The oily reserve, *Ann. Bot.*, **26**: 889-901.
- MÜNTZ, M., 1871: Sur la germination des graines oléagineuses, *Ann. Chim. et Phys.*, 4e série, **22**: 472.
- NJEGOVAN, V., 1911: Beiträge zur Kenntnis der pflanzlichen Phosphatide, *Zeits. f. physiol. Chem.*, **76**: 1-26.
- PACK, D. A., 1925: Dispersion of lipoids, *Bot. Gaz.*, **79**: 334-338.
- PARROZZANI, A., 1909: Il fosforo organico ed il rapporto fra l'azoto amidico e quello delle altre combinazioni azotate non proteiche nei semi maturi, *Staz. Sper. Agr. Ital.*, **42**: 890-901.
- PALLADIN, W., and E. STANEWITSCH, 1910: Die Abhängigkeit der Pflanzenatmung von den Lipoiden, *Biochem. Zeits.*, **22**: 351-369.
- PIRSCHLE, KARL, 1926: Acetaldehyd als Zwischenprodukt bei der Keimung fetthaltiger Samen, *Biochem. Zeits.*, **169**: 482-489; *Biol. Abst.*, **2**: 463. 1928.
- POLICARD, A., et G. MANGENOT, 1923: Recherches cytologiques sur l'état de l'huile dans les graines oléagineuses. La graine mure, *Compt. Rend. Acad. Sci. Paris*, **176**: 1841-1844.
- and ———, 1923. Sur l'état de l'huile dans la cellule de réserve des graines oléagineuses. La graine en germination, *Compt. Rend. Acad. Sci. Paris*, **177**: 346-348.
- PETERS, E., 1861: Zur Keimungsgeschichte des Kurbissamens, *Landw. Versuchs-Stat.*, **3**: 1-18.
- PRIESTLEY, J. H., 1924: The fundamental fat metabolism of the plant, *New Phytol.*, **23**: 1-20.
- RHINE, J. B., 1926: Studies on the oxidation of certain fatty acids, *Plant Physiol.*, **1**: 349-361.
- RIVETT, M. F., 1918: The structure of the cytoplasm in the cells of *Alicularia scolaris*, *Ann. Bot.*, **32**: 207-214.
- SACHS, J., 1859: Ueber das Auftreten der Stärke bei der Keimung ölhaltiger Samen, *Bot. Zeitung*, **17**, 177-183, 185-188.
- , 1863: Ueber die Keimung des Samens von *Allium Cepa*, *Bot. Zeitung*, **21**: 57-65.
- SANDO, C. E., 1923: Constituents of the wax-like coating on the surface of the apple, *Jour. Biol. Chem.*, **56**: 457-468.
- , 1928: Lipides and their estimation in vegetable tissues, *Plant Physiol.*, **3**: 155-184.
- SCHMIDT, R. H., 1891: Ueber Aufnahme und Verarbeitung von fetten Oelen-Pflanzen, *Flora*, **74**: 300-371.

- SCHULZE, E., and E. STEIGER, 1889: Ueber den Lecithingehalt der Pflanzensamen, *Zeits. f. physiol. Chem.*, **13**: 365-384.
- and W. MAXWELL, 1891: Untersuchungen über die chemische Zusammensetzung einiger Leguminosensamen, *Landw. Versuchs-Stat.*, **39**: 269-326.
- and A. LIKIERNIK, 1891: Ueber das Lecithin der Pflanzensamen, *Zeits. f. physiol. Chem.*, **15**: 405-414.
- and S. FRANKFURT, 1894: Über den Lecithingehalt einiger vegetabilischer Substanzen, *Landw. Versuchs-Stat.*, **43**: 307-318.
- SCURTI, F., and G. TOMMASI, 1909-1910: Sulla formazione del grasso nei frutti oleaginosi; 1910-1911: *Ann. della R. Staz. Chim. Agrar. Sperim. di Roma*, **4**: 253-286 **5**: 103.
- and ———, 1911: Sulla formazione del grasso nei frutti oleaginosi, *Ann. della R. Staz. Chim. Agrar. Sperim. di Roma*, **5**: 223.
- and ———, 1912: In regard to the formation of fatty acid in oleaginous fruits, *Rend. Soc. Chim. Ital.*, **3**: 358-363; *Expt. Sta. Rec.* **26**: 801.
- SHOREY, E. C., 1898: The lecithins of sugar cane, *Jour. Amer. Chem. Soc.*, **20**: 113-118.
- SINNOTT, E. W., 1918: Factors determining character and distribution of food reserve in woody plants, *Bot. Gaz.*, **66**: 162-175.
- SMEDLEY, I., 1912: The biochemical synthesis of fatty acids from carbohydrates, *Jour. Physiol.*, **45**: 25-27.
- and E. LUBRZYNSKA, 1913: The biochemical synthesis of the fatty acids, *Biochem. Jour.*, **7**: 364-374.
- SMOLENSKI, K., 1909: Zur Kenntniss der aus Weizenkeimen darstellbaren Phosphatide, *Zeits. f. physiol. Chem.*, **58**: 522-526.
- STARK, R. W., 1924: Environmental factors affecting the protein and oil content of soybeans and the iodine number of soybean oil, *Jour. Amer. Soc. Agron.*, **16**: 636-646.
- STEWART, F. C., 1928: An experimental examination of the evidence for the presence of phosphatides in the limiting surface of the living protoplast, *British Jour. Exper. Biol.*, **6**, 32-41.
- , 1928: On the evidence for phosphatides in the external surface of the plant protoplast, *Biochem. Jour.*, **22**: 268-275.
- STOCKLASA, J., 1895: Die Assimilation des Lecithins durch die Pflanze, *Sitzungsber. (Math. Naturw., Kl.) K. Akad. d. Wiss. Wien*, **104**: 712-722.
- , 1898: Ueber die Entstehung und Umwandlung der Lecithins in der Pflanze, *Zeits. f. physiol. Chem.*, **25**: 398-405.
- STRASBURGER, Noll, Schrenck and Karstan, 1908: "Textbook of Botany," English translation, p. 101, The Macmillan Company.
- TERROINE, E. F., 1920: Etat actuelle de nos connaissances sur la formation des graisses au cours de la maturation des graines et fruits oléagineux et sur l'utilisation des graisses au cours de la germination, *Ann. Sci. Nat.* **10**, **26**: 1-63; *rev. Bot. Gaz.*, **75**: 224 (1923).
- THATCHER, R. W., 1921: "The Chemistry of Plant Life," McGraw-Hill Book Company, Inc., New York.
- TSCHIRCH, A., and H. KRITZLER, 1900: Microchemische Untersuchungen über die Aleuronekörner, *Ber. deutsch. Pharm.*, **10**: 214-223.
- VALLEE, C., 1903: Sur la présence du saccharose dans les amandes et sur son rôle dans la formation de l'huile, *Compt. Rend. Acad. Sci. Paris.*, **136**: 114-117.
- VON FÜRTH, O., 1904: Ueber das Verhalten des Fettes bei der Keimung ölhaltiger Samen, *Hofmeister's Beiträge zur chem. Physiol. und Path.*, **4**: 430.
- WAKKER, J. H., 1886: Studien über die Inhaltskörper der Pflanzenzelle, *Jahrb. f. wiss. Bot.*, **19**: 423-496.

- WEBSTER, J. E., 1929: Iodine value of fatty acids from plant phosphatides, *Ohio Jour. Sci.*, **29**: 39-42.
- WINTERSTEIN, E., and O. HIESTAND, 1908: Beiträge zur Kenntniss der pflanzlichen Phosphatide. II, *Zeits. f. physiol. Chem.*, **54**: 288-330.
- and L. STEGMANN, 1909: Ueber einen eigenartigen phosphorhaltigen Bestandteil der Blätter von *Ricinus*, *Zeits. f. physiol. Chem.*, **58**: 527-528.
- and K. SMOLENSKI, 1909: Beiträge zur Kenntnis der aus Cerealien darstellbaren Phosphatide, *Zeits. f. physiol. Chem.*, **58**: 506-521.
- ZALENSKI, W., 1902: Beiträge zur Verwandlung des Eiweissphosphors in den Pflanzen, *Ber. d. d. bot. Ges.*, **20**: 426-433.

CHAPTER XI

THE PROCESS OF DIGESTION IN THE GREEN PLANT

I. FOODS OF THE GREEN PLANT

Before considering the process of digestion it will be necessary to discuss the foods of plants in order to understand the significance of this process in their life functions. A food may be defined as any substance that may be used directly, or after hydrolysis, by the protoplasm for growth and repair or as a source of energy. Since this definition applies to animals as well as to plants, it raises the question whether plants and animals use the same kind of foods in their life functions. It is common knowledge that animals are nourished with carbohydrates, fats, and proteins, but the fact that the protoplasm of plants requires for its nourishment and energy the same foods as are used by animals is not so well known. Such, however, is the case, as will be proved in the subsequent discussion.

A. PLANT SOURCES OF ANIMAL FOODS

It is well known that animals obtain their food supply either directly or indirectly from plants, since they live entirely upon plants or prey upon other animals that are dependent upon plants for their food supply. Animals obtain this food supply from the seeds and grains, fruit, stems, roots, and leaves of plants. Seeds and grains are one of the main sources of food for animals, including man. Some of the more important seeds and grains that are a source of food for animals are wheat, corn, rye, oats, barley, rice, peas, beans, sorghum grains, nuts, cotton seed, sunflower seed, buckwheat, millet, and peanuts. Some of the stems that are a source of food to animals are the stems of the grains, grasses, and legumes, Irish potatoes, artichokes, asparagus, sugar cane, and young bamboo, while some of the roots which furnish food are sweet potato, yams, beets, carrots, parsnips, salsify, turnips, rutabagas, and cassava. Some of the leaves that furnish food to animals are those of the grains, grasses and legumes, celery, rhubarb, onion, spinach, lettuce, cabbage, Swiss chard, kale, and rape. The foods that are stored in these plant parts are the proteins, carbohydrates, and fats together with certain minerals and vitamins. These can satisfy all the needs of the animals that feed upon them, in as far as their food supply is concerned. The question then naturally arises concerning the benefits of the foods stored in plants to the plants themselves. Are these foods stored in the organs just mentioned

for the use of the plant or are they placed there primarily for the benefit of the animal kingdom?

B. VALUE TO THE PLANT OF ITS STORED FOODS

Let us first consider the function of the foods stored in seeds. A normal seed contains a young plant which will, if the proper conditions are supplied, begin to grow and develop. The young seedling uses the foods stored in the seed to form new protoplasm and new tissues and from them it also derives the energy to push the stem out of the soil and the roots downward. As the young plant increases in size, the amount of food in the seed continues to decrease until it all disappears. This fact may be illustrated by considering the germination of the sunflower seed. This seed contains protein and oil as stored foods, the former making up 26 per cent and the latter about 50 per cent or more of the dry weight of this seed. This seed does not have an endosperm and these foods are stored in the cotyledons of the embryo. The depletion of these foods as germination progresses is shown in the following table:

GRAMS OF OIL AND PROTEIN IN THE COTYLEDONS OF 100 SEEDS AND SEEDLINGS OF THE SUNFLOWER SEED AT 2, 4, 7, AND 10 DAYS, RESPECTIVELY

Substance	Stage				
	Seed	2 days	4 days	7 days	10 days
Protein.....	1.7	1.2	1.0	0.8	0.6
Oil.....	4.0	3.0	2.5	1.3	0.5

A plant can thus grow to a considerable size without any food except that which is contained in the seed. These foods are transferred to the young plant parts and built into new tissue in much the same manner as this process occurs in animals.

In the aerial stems and branches of plants there is found in the region of the buds a large amount of protein, oil, or carbohydrates stored in the cells. As the buds develop into the new branches and leaves, this stored food is rapidly depleted and used in the formation of these new plant organs. In the case of modified stems like the Irish potato and artichoke, the young sprouts which grow from them when they are planted are nourished until they are above ground and sometime thereafter from the food supply in the old tuber beneath the soil.

The three types of foods are stored in all roots of plants but in especially large quantities in roots of the fleshy type. The use to which the stored foods are put can be best illustrated by considering beets, carrots, parsnips, and other biennial plants. These plants during their first season's growth store up food in the roots and during the second season

develop a new stem which produces a crop of seed. The foods stored in these roots during the first year furnish the food necessary for this development of stem and seeds so that when the seed has matured the roots have been depleted of their stored food and during that time little or no material has been absorbed by the roots or manufactured by the aerial parts. In the majority of cases, the foods that are found in leaves have been manufactured there and are only awaiting transportation to the roots, stem, or seeds of the plant. Certain fleshy leaves, however, as the cabbage and onion, are real storage organs where the foods are stored permanently.

From what has been mentioned above, it is seen that the proteins and carbohydrates, or fats, are stored in all parts of the plant where growth is taking place or is going to take place. When the new organs or parts of the plant are formed, they draw upon these foods and form their tissues from them. We know this to be the case because these parts have no access to any food except that which is stored and also because the translocation of this food from its place of storage to the new parts can readily be detected. Plants thus use for their growth and development the same three types of foods as are used by animals in their growth and development. They differ in regard to the food proposition in that plants can manufacture the proteins, fats, and carbohydrates that they use as foods from the simple materials that they obtain from the air and the soil, while animals have no power to do this but have to depend entirely upon plants to furnish these foods already prepared for them. Thus it may be stated that plants are independent, while animals are dependent in regard to their food supply.

The simple inorganic compounds that plants obtain from the air and soil and from which they manufacture the three types of foods are frequently termed "plant foods." These compounds, however, are not foods in the strict sense of the word, since they cannot be used directly by the protoplasm. They are the crude materials from which foods are formed, in the same fashion as finished walls are formed from bricks, sand, and cement or finished cloth is made from the crude cotton or woolen fibers. The question now arises as to what changes if any the foods found in plants must undergo before they can be utilized by the protoplasm of the plant.

II. NATURE OF DIGESTION

The greater portion of the carbohydrates, proteins, fats, and oils of plants is stored in plants in forms that are insoluble in water. The storage of foods in an insoluble form in the plant cells has several advantages. In the first place, more food can be stored in a given space in the insoluble than in the soluble form. In the second place, foods are more stable in the insoluble form than in the soluble form and are less liable

to be destroyed by decay. In the third place, the conversion of soluble foods to the insoluble form keeps the osmotic value of the cell sap at a level which is not injurious to the cell.

The foods in the insoluble form, however, cannot leave the cells in which they are stored until they are changed to a form that is soluble in water. They must therefore be changed to a soluble form before they can be translocated. Furthermore, all foods must be in a soluble form before they can be utilized for growth or as a source of energy. Even if a food is soluble in water it must in some cases be reduced to a more simple form before the protoplasm can utilize it in its metabolism. With these general facts concerning the foods of plants, we can now understand better what is meant by digestion.

Digestion may be defined as the processes whereby the foods of plants and animals are changed from an insoluble to a soluble form or from a complex to a more simple form. In nearly every case the action on foods in digestion is one of hydrolysis. The food is made to take up water and is then broken down, a fact which will be considered in the discussion of the action of digestive enzymes. As a result of this change, insoluble foods are rendered translocatable and changed to a form that is usable by the protoplasm in growth and development. An example of digestion in which the food is changed from an insoluble to a soluble form is the transformation of starch to sugar. Starch is an insoluble compound and cannot be transferred through the walls of the cells in which it is stored or be directly utilized by the protoplasm. When starch by the process of digestion is changed to maltose or eventually to glucose, we have a carbohydrate that is soluble in water, that can readily move from cell to cell, and one that can be utilized by the protoplasm. Cane sugar is an example of a food that is soluble in water and is easily translocated, but which must be digested into the more simple sugars glucose and fructose before it can be assimilated by the protoplasm of plants and animals.

III. ENZYMES

One of the most striking characteristics of living organisms is the ease with which they are able to split up compounds of a highly stable nature. The oxidation and hydrolysis of compounds in plants and animals occur at ordinary temperatures very rapidly, while in the laboratory these changes are effected in many cases only at higher temperatures and by the use of strong reagents. Little is known, however, concerning the manner in which these reactions are carried out by living organisms. It is well established, however, that the process of digestion in both plants and animals is not brought about directly by the protoplasm itself but by substances secreted by it. These substances behave as catalysts and are called "enzymes." This leads us to a discussion of catalysts in general and of the nature of enzymes in particular.

A. GENERAL NATURE OF CATALYSTS

In regard to the speed with which they are completed, chemical reactions may be placed in two main groups: (1) those reactions that are completed practically instantaneously, as, for example, the neutralization of a base by an acid or the precipitation of copper hydroxide by the addition of a solution of KOH to a solution of CuSO_4 ; (2) those which require a measurable time for their completion, as, for example, the hydrolysis of cane sugar to glucose and fructose by a mineral acid or the saponification of a fat or oil by sodium hydroxide. It is with this latter type of reaction that catalysts are primarily concerned. A catalyst may be defined as a body which alters the speed of a chemical reaction that requires a measurable time to arrive at its final state. This alteration in the speed of a reaction may be either an acceleration or a retardation. Catalysts, however, are generally considered in regard to their acceleration of reactions, and the process of catalysis has been defined as "the acceleration of a chemical change by the presence of some foreign substance" (Bayliss, 1925). It is almost a universal opinion that catalysts cannot in themselves initiate reactions but that they only accelerate or retard reactions that are proceeding in their absence. Some of the general properties of catalysts are: (1) They are not chemically combined with the final products of the reaction but may be recovered at the end of the reaction measurably unchanged in quantity and quality, except where they may be destroyed by subsidiary reactions. (2) A relatively small amount of catalyst produces very large results in the reacting mixture. (3) The effect of a small amount of catalyst is in the end the same as that of a larger quantity if sufficient time is allowed, the only difference being the rate at which the new products appear.

B. GENERAL NATURE OF ENZYMES

In beginning a discussion of this topic, the first step should be to give a definition of the term "enzyme." A definition, however, is difficult of formulation, since so little is known concerning the nature of enzymes. In the light of our present knowledge, perhaps as exact and inclusive a definition as can be formulated is that of Bayliss (1925) who defined an enzyme as "a catalyst produced by living organisms."

Enzymes are colloidal substances and do not readily diffuse through artificial membranes. The rate at which they diffuse through membranes is largely dependent upon the nature of the membrane, but as a rule they will not pass through parchment membranes. This is one important characteristic that distinguishes enzymes from other organic catalysts. Most enzymes, however, will pass through a porcelain filter, and this characteristic is utilized for their separation from the materials with which they are associated. Since enzymes are colloids, they have the

property of carrying down with them by adsorption some of the constituents of the solutions from which they are precipitated. The methods used for the precipitation of enzymes also precipitate most proteins, so that proteins are generally present in an ordinary enzyme preparation. On that account it is difficult to determine the chemical composition of enzymes with any degree of certainty, and so far all attempts to isolate an enzyme as a pure substance of definite chemical composition have been without satisfactory results. In general, the more the enzymes are purified the fewer characteristic reactions do they show, although in some cases their activity, weight for weight, can be greatly increased. On the other hand, in many cases the attempts to purify enzyme preparations by the means at present at our disposal greatly decrease the activity of the enzyme. Since, as will be mentioned later, enzymes are specific in their action, it would seem probable that they differ in their chemical structure. On that account the chemical reactions of the different enzymes will be considered under their individual headings. In general, Willstätter (1922) considered that the experimental evidence indicates that an enzyme consists of a colloidal carrier together with other substances which have an action of a purely chemical nature.

Hogounenq and Loiseleur (1925) considered that an enzyme consists of a colloidal organic complex and a mineral element. The organic complex constitutes a colloidal support upon which the electrolyte is held by adsorption, retaining its crystalloid properties and specific chemical activity. The electrolyte is considered specific for a given enzyme, as, for example, Cl for pepsin and Mn for oxidases. The adsorption of the electrolyte is determined by the electrical sign of the protein micellae, and the sign is determined by the functional grouping in the molecule. Thus pepsin is supposed to consist of a colloidal protein support having predominately acid groups which determine its negative sign. It absorbs such cations as Na, setting free Cl which attacks the NH_2 groups of the proteins digested. Trypsin is a similar colloidal complex in which amidogenic groups predominate, giving the micellae a positive charge.

Enzymes are sensitive to heat. The optimum temperature for most plant enzymes is between 37 and 55°C. In most cases, enzymes are injured at a temperature above 60°C. and all are completely destroyed at a temperature of 100°C. Their resistance to heat differs with different types of enzymes, with the kind of material associated with them, and with the amount of water present, as will be mentioned when the different types of enzymes are considered. The destruction of enzymes by heat is attributed to the alteration of their colloidal nature probably by coagulation. In general, the activity of enzymes is doubled for every rise of 10°C., but this effect is diminished at higher temperatures because of the destruction of the enzymes by heat. The relation of the increased activity of an enzyme to temperature, the effects of the increased tem-

perature on the destruction of the enzyme, and the resultant activity of increases in temperature are shown in Fig. 27. Enzymes are inactivated at lower temperatures but again regain their activity when the temperature is again raised. Enzymes are sensitive to light, especially to the action of the ultra-violet rays and to polarized light, as will be mentioned in the discussion of the different enzymes. On that account experiments upon the activity of enzymes are generally conducted in the dark.

C. GENERAL NATURE OF ENZYME ACTION

Enzymes have two properties that are common to all catalysts in that they are not capable of initiating a new reaction but merely of changing the rate of one already in progress and in that they do not appear combined with the final products of the reactions which they influence. They differ from catalysts in that they do not always carry the process to the same completeness as does an inorganic catalyst which influences the same reaction. Thus the enzyme diastase hydrolyzes starch to malt sugar, while a mineral acid hydrolyzes the starch to glucose. Certain of the proteolytic enzymes also do not carry the digestive process so far as do acids. Thus an acid hydrolyzes the protein to amino acids, while the enzymes frequently leave complex polypeptides that are unattacked. The enzymes are apparently more specific in their action than the acid. Thus an enzyme catalyzes only a single reaction as the hydrolysis of starch to maltose or of maltose to glucose, while the acid catalyzes both reactions. This difference between enzymes and the inorganic catalysts may be more apparent than real, since these reactions which occur under the influence of enzymes might proceed to complete hydrolysis if the appropriate conditions were present. Thus it has been observed, for example, that if malt extract is allowed to act for a long time on starch, the hydrolysis proceeds beyond malt sugar, and glucose is formed. Enzyme action in many cases apparently comes to an end or equilibrium point, owing to the accumulation of the products of the reaction, so that by the dilution or removal of products the reaction can proceed further.

The mechanism by which an enzyme accomplishes its catalytic effects is not definitely known. Two general theories concerning the mode of this catalytic action have been advanced and will be briefly mentioned here, since a full discussion of the nature of enzyme action belongs to the province of advanced biochemistry rather than to the field of plant physiology. The few statements in regard to enzyme action that are given herein are made in order that the student may be familiar with the complexity of the problem and with the meager knowledge available on the subject. The following presentation is based primarily on the discussion by Thatcher (1921).

The earliest and simplest theory of enzyme action that was proposed was that the enzyme simply creates an environment favorable for the particular chemical reaction to take place and does not enter into the combination with the substrate at all. The favorable environment was considered to be brought about by the exposure of large surfaces of the substance under consideration to the action of the active agent of the enzyme by the means of surface adsorption of this substrate on the colloidal material of the enzyme.

The theory which is now most generally accepted is that there is an actual combination between the substrate and the enzyme. This combination is only temporary and breaks down with a resultant change in the substrate and the freeing of the enzyme for recombination with additional substrate. The theory of this mode of enzyme reaction is based on the following: (1) the fact that if an enzyme and its substrate, each of which is filterable through a given filter, are mixed, the active material in the combined solution will not pass through the filter; (2) the interpretation of the curves representing the reaction velocities of typical reactions which are proceeding under the influence of an enzyme; and (3) the fact that the limitation of a given enzyme to a specific substrate is definitely related to the molecular configuration of the molecules of the substrate.

There are two general theories in regard to the nature of the supposed combination of the enzyme and substrate. One is that the combination is molecular and that a definite chemical compound is formed. The other is that the result of the union is purely a physical or colloidal complex. The latter theory is substantiated by the effects of electrolytes and heat on enzyme action and by the appearance of the reacting substances under the microscope.

In many cases the chemical action brought about by enzymes never goes to completion, so that there is some of the substrate remaining intact. This is explained by saying that the action of enzymes is reversible and that the same enzyme will accelerate the velocity of the reaction in either direction, depending upon the environmental conditions of the reacting materials. The synthesis of fats and oils from fatty acids and glycerine in the presence of lipase, as mentioned in Chap. X, is an example of the synthetic action of an enzyme. The synthesis of isomaltose from glucose by maltase is another example of the reversible action of enzymes. It is considered that the synthesis of the various plant products brought about by enzyme action, although the experimental evidence in regard is very meager. Enzyme action under artificial conditions is distinguished from direct protoplasmic action in that it occurs in the presence of an amount of antiseptic that is destructive to the life of protoplasm. Some enzymes, however, are very sensitive to certain antiseptics, as will later be mentioned.

D. NOMENCLATURE

The substance the chemical change of which is catalytically affected by an enzyme is termed the "substrate." The substrate is generally defined as the substance upon which the enzyme acts.

The activity of enzymes is greatly influenced by the presence in the solution of other bodies. Any substance that increases the catalytic activity of an enzyme is termed an "accelerator" or "activator," while one which inhibits or destroys its action is called an "inhibitor" or "paralyzer." The substances which thus influence the rate of enzyme action are generally electrolytes, such as mineral acids, alkalis, and salts, although this is not always the case. The accelerating action of the amino acids on the activity of certain enzymes is an example of these exceptions. All enzymes, however, do not respond alike to the same substance. Thus the activity of some enzymes is greatly increased by the presence of a small amount of mineral acid, while the action of another may be partially or completely inhibited by the same acid in the same concentration. Some of the substances which almost always exercise an inhibitive or toxic action on enzyme activity are hydrogen sulphide, formaldehyde, hydrocyanic acid, chloroform, and the salts of mercury, silver, and copper.

It has been found that many enzymes are inactive unless accompanied by some other substance which is normally present in the protoplasm which produces them. Such substances have been named "coenzymes." This accompanying substance can usually be separated from the enzyme by dialysis, the coenzyme passing through the parchment membrane. After the coenzyme is thus separated, it is not injured by boiling, and the activity of the enzyme may be restored by adding the boiled substance to the liquid which remains behind in the dialyzer. Coenzymes have been studied in connection with the enzymes of animals and in connection with the activity of zymase of yeast cells, but few observations have been made in this regard with the enzyme studies of green plants.

The term "antienzyme" has been applied to a substance occurring naturally in a living organism, or which is produced after the injection of an enzyme, that prevents the action of the specific enzyme upon the tissues. Antienzymes have been considered more particularly in the physiology of animals, but in many cases the evidence of the existence of such substances and their action rests upon theory rather than experimental evidence. The evidence of antienzymes in the green plants is extremely meager. The only work in this regard that is known to the author is that of Czapek (1905), who considered that he obtained evidence of antioxidases in his studies of the reactions occurring during the tropistic movements of plants.

Since enzymes are produced by the protoplasm, it is apparent that at a given stage in their synthesis, they have not yet acquired their


catalytic powers, although possessing, in general, the other properties of enzymes. An enzyme which has reached this stage of its formation is termed a "proenzyme" or "zymogen." These terms are used, however, only when the substance can be obtained free from the cells in which it is formed and can be converted after its extraction into the active enzyme by purely chemical means (Bayliss, 1925). When such a substance has once been activated, it cannot, according to present knowledge, be converted again to the proenzyme or zymogen state. Calcium salts and dilute acids are considered to be the most energetic activators of proenzymes. The activator of a proenzyme has also been termed a "kinase." According to Thatcher (1921), proenzymes are believed to be present in plant cells in the form of definite characteristic granules which may be observed under the microscope and which disappear when the enzyme becomes active. According to him, proinulase has been reported as occurring in artichoke tubers, prolipase in castor beans (Tanka, 1910), and prooxidase in tobacco leaves.

When organic catalysts were first isolated from plant and animal tissues, they were termed "ferments" because of the resemblance of the changes produced to alcoholic fermentation. After it was found that fermentation was due to the presence of living organisms as yeast, these organic catalysts were termed "soluble" or "unorganized ferments" to distinguish them from living organisms producing similar changes, which were termed "insoluble" or "organized ferments." The double use of the word ferment caused much confusion and induced Kühne (1878) to suggest that the name "enzymes" be given to those substances which were then designated as unorganized ferments. The name enzyme comes from the Greek words *en zymos* and literally means "in yeast." Kühne stated that the term was meant to include those unorganized ferments which behave in a manner similar to those substances which occur in yeast. When it was shown in 1897 by Büchner that if yeast cells are crushed and filtered the filtrate is just as active in fermentation as the intact yeast cells, the difference between organized and unorganized ferments disappeared and the term enzyme came into general use. ✓

E. CLASSIFICATION

Enzymes are specific in their action, each one activating a particular chemical change upon one substance, so that there are as many enzymes as there are substances upon which they act. On this account, a system of nomenclature has been adopted which assigns to each enzyme the name of the material upon which it acts, followed by the suffix -ase. Thus sucrase is the enzyme acting upon sucrose, amylase the enzyme acting upon amylum (starch), and cellulase the enzyme acting upon cellulose. This system of nomenclature is now generally followed, although in some cases, where the original name of the enzyme has long been in use, the

older terminology is used, as, for example, pepsin, trypsin, diastase, invertase, and so on. The enzymes that have been the most studied and the ones with which we are primarily concerned in the study of digestion accelerate hydrolytic reactions and may be termed "hydrolases." Certain enzymes which cause coagulation are termed "coagulases" and in some cases apparently play a rôle in the digestive process. The enzymes which are concerned in digestion may be classified after the following manner:



F. OCCURRENCE


Digestive enzymes of one type or another are found in all living plant tissue. A few examples will suffice to illustrate this point. Robertson, Irvine, and Dobson (1904) found diastase, invertase, maltase, inulase, and emulsin in the stem and leaves of the beet. Bailey (1912) found invertase, diastase, proteases, and lipase in the banana, while in the stem, leaves, roots, and seeds of alfalfa, Jacobson and Holmes (1914) detected lipase, diastase, coagulases, emulsin, invertase, pectinase, and certain proteases. The fungi are especially rich in digestive enzymes and are the sources of many of the commercial enzyme preparations. Thus in *Echinodontium tinctorium*, Schmitz (1920) demonstrated the presence of esterase, maltase, lactase, invertase, diastase, inulase, cellulase, rennet, and others.

The abundance of enzymes in a given part of a plant depends apparently on the conditions under which it is placed. There is some evidence that fungi in some cases may secrete an enzyme corresponding to the kind of substrate that is supplied, but no observations in that regard

have been made upon green plants. After enzymes are formed in the plant they may remain active for a long period of time. Thus White (1909) found that the seeds of wheat, oats, corn, barley, and rye which had been stored for 20 years and which had lost their germinating power, contained diastase and erepsins which had retained their activity apparently unimpaired. Mische (1923) examined rye seeds which were at least 112 and probably 280 years old. Although the embryos were disintegrated, the endosperms were intact and the starch contained in them reacted to the iodine test. Enzymes were obtained from these seeds by water extractions which changed starch to sugar and differed from those of fresh rye-seed extracts only in acting more slowly. Maestrini (1923) studied acidulated aqueous extracts of germinating barley which had been kept for 3 or 4 years. Diastase did not appear to be perceptibly modified in its enzymic action by this treatment. The proteases, however, showed a marked reduced hydrolytic capacity, while lipase and emulsin were destroyed in less than 2 years.

We shall now discuss the distribution, general properties, reactions, and methods of preparation of the various digestive enzymes found in the green plant.

1. The Carbohydrases of Plants. *a. The Invertases, Invertins, Saccharases, or Sucrases.*—The enzyme which hydrolyzes sucrose to glucose and levulose has been variously named “invertase,” “invertin,” “saccharase,” or “sucrase.” This hydrolysis is one of the most simple of the enzymic reactions and proceeds after the following manner:



The occurrence of invertase in green plants has been reported by Brown and Morris (1894), Kastle and Clark (1903), Martinand (1907), Vinson (1907), Robertson, Irvine, and Dobson (1909), Colin (1915), McGuire and Falk (1920, 1921), and others. Invertase has been found in the roots and leaves of the radish; in the leaves and tubers of the artichoke; in the leaves, tubers, and sprouts of the potato; in the leaves of the dahlia; in the leaves and roots of the dandelion; in the entire plant of corn and *Sorghum saccharatum*; in the leaf lamina, petioles, and collar of the sugar beet; in all parts of the leaves, stem, and fruit of the grape; in the leaves, stem, and pods of the soybean; in the leaves and roots of the sweet potato; in the fig; in the banana fruit; and in many other plants and plant parts. Knudson (1920) obtained experimental data that indicated that invertase might be secreted by roots under certain conditions. Invertase is thus apparently of almost universal occurrence in green plants. It has not, however, been definitely established whether the invertases from different sources are identical substances (Doby, 1915). Invertase occurs in great abundance in yeast and it is from this source

that the invertase of commerce is mostly obtained. It may also be prepared from cultures of *Aspergillus niger* (Stoward, 1912). Most of the studies on the nature and action of invertase have been made on the invertase of yeast. Invertase is now used rather extensively in the industries. In the hydrolysis of a number of commercial products in which sucrose is the principal saccharine constituent, this enzyme has been found more suitable than an acid as a catalyst. It is used in products which exhibit a marked buffer effect toward added acid and which possess a flavor adversely influenced by the concentration of acid required to effect hydrolysis (Paine, Walton, and Badollet, 1925). According to Paine and Balch (1925), an analytical procedure involving the use of the enzymes invertase and melibiase has been adapted to practical use for the precise determination of the sugars sucrose and raffinose in the chemical control of beet-sugar factories.

1. *Preparation and Study of Invertase.* (a) *Preparation from Yeast.*—Although this text deals only with the physiology of the green plant, the preparation of invertase from yeast is here discussed, since much of our knowledge of the action of this enzyme has been learned from enzyme preparations obtained from this source. Methods for the preparation of invertase from yeast have been given by O'Sullivan and Tompson (1890), Hudson (1910, 1914), and Nelson and Born (1914). The modified method of Nelson and Born as used by Hudson (1914) is as follows: Equal amounts of water and yeast are autolyzed at room temperature for 5 days with toluol as an antiseptic. The material is then filtered and 95 per cent alcohol added in equal volume. After the precipitate settles, the alcohol is decanted and the residue dissolved in water. Alcohol is again added as before and again decanted. After the precipitate is again dissolved in water, a concentrated solution of lead acetate is added until no more precipitate is formed. After filtering off the precipitate, potassium oxalate is added to throw down the excess lead and the precipitate filtered off. The filtrate is then treated with kaolin and stirred constantly for an hour, the treatment being repeated several times. The resulting liquid is then placed in collodion bags with toluol and dialyzed in running water from 3 to 20 days. After this dialysis, a precipitate cannot be obtained by the addition of alcohol until some NaCl, potassium acetate, or acetic acid is added to alter the colloidal nature of the solution. If a precipitate is thus obtained, it is washed with absolute alcohol and dried over H_2SO_4 . The purest preparation of invertase obtained after this manner will give a faint biuret and strong Millon and xanthoproteic reactions as long as the enzyme remains active and there is a rough parallelism between the nitrogen content and activity when the preparation is fairly pure. An active preparation of invertase has a nitrogen content of 2.2 per cent, but when the nitrogen content falls below 1 per cent the enzyme is no longer active (Mathew and Glenn, 1911). The invertase of yeast as ordinarily prepared is considered to be a union of protein with a carbohydrate gum, the protein constituent being the active part of the preparation. Nelson and Born (1914) noted that a 10 per cent solution of invertase prepared from yeast after the above method was not precipitated by any of the ordinary protein precipitants. After the hydrolysis of this solution with 2.5 per cent H_2SO_4 and neutralization with barium carbonate, copious precipitates were obtained with $HgCl_2$, mercuric acetate, phosphomolybdic acid, and phosphotungstic acids. This indicates that in the original invertase preparation, either the protein part is combined with the carbohydrate or the latter acts as a protective colloid.

(b) *Preparation from Green Plants.*—Falk and McGuire (1921) used the following method for the preparation of invertase from bananas: The pulp is ground finely in a food chopper and then mixed in a porcelain mortar with normal NaCl, 100 cc. to each 400 g. of pulp, toluene is added, and the mixture filtered through paper. The filtrate is then dialyzed in collodion bags for 18 to 24 hr. against running water to remove salts, carbohydrates, and other products. The resulting solution will keep for a considerable period of time under toluene and is used for invertase experiments. Invertase in leaves has been studied, for the most part, by drying the leaves at air temperature, pulverizing the dried material to a fine powder, and taking a weighed portion for the study of enzyme action. It should always be remembered that the manner in which an enzyme is obtained may affect not only its activity but its physical properties as well. Thus Falk and McGuire in studying invertase in the banana found a water-soluble, a NaCl-soluble, and another invertase in the extracted residue of the fruit pulp. All three preparations were identical as far as could be observed in their action on cane sugar but were entirely different in their physical behavior.

The general method for the study of the action of invertase is to add 10 to 15 cc. of an invertase solution to 10 to 25 cc. of a 1 to 20 per cent sucrose solution together with sufficient toluene to act as an antiseptic. This mixture is incubated at 35 to 38°C. for varying periods of time, depending upon the activity of the invertase preparation. The periods of incubation vary from 2 to 24 hr. As a rule, the invertase preparations from leaves and fruits are relatively slow in their action as compared to the preparations from yeast. After the incubation, a portion of the mixture is treated with Fehling's solution, heated, and the degree of invertase action determined in terms of the number of milligrams of Cu_2O produced by the action of 1 cc. of the original enzyme solution, correction always being made for the controls. The rate of invertase action may be obtained qualitatively by estimating the amount of reduction of Fehling's solution by the color of the solution or by the relative amount of the precipitate produced.

2. *Nature of the Action of Invertase.*—Invertase has been the best studied of any of the plant enzymes. Since the action of this enzyme is relatively simple, starting with a well-known substance and producing well-known end products, the hydrolysis of cane sugar by it has been chosen by many investigators as the best process with which to study the velocity of enzyme action in relation to different factors.

Invertase is not destroyed or injured by its action on sucrose. O'Sullivan and Tompson (1890) found that a sample of invertase which had induced inversion of one-hundred-thousand times its own weight of cane sugar was still active, so there is apparently no limit to the amount of sugar which may be hydrolyzed by a given amount of this enzyme provided that the proper conditions are maintained for its action.

It should be mentioned here that there is apparently a difference between the action of acids and invertase on cane sugar, although both substances are catalysts and both produce the same end products in the hydrolysis of this sugar. Thus in different concentrations of cane sugar, the same amount of acid gives the same velocity constant. For example, a 5, 10, or 15 per cent sucrose solution will be inverted by a 1 per cent acid solution in the same time to the same extent, say halfway. In the case of invertase, however, the same quantity of enzyme in the different con-

centrations of sucrose invert in the same time, not the same fractions of each solution, but the same absolute amounts.

The velocity of the inversion of cane sugar is directly proportional to the concentration of invertase. The velocity of reaction is nearly independent of the concentration of the sucrose in the more concentrated solutions, while in very dilute sugar solutions, the velocity increases with the increase of concentration of the substrate and finally reaches a maximum (Nelson and Vosburgh, 1917). It was shown by Nelson and Bodansky (1925) that the invert sugar formed in hydrolysis exerts a retarding influence on the velocity of the reaction of invertase. This is due to the fact that invert sugar has a different retarding effect upon hydrolysis according to whether it is in a freshly liberated or in a final mutarotated form. If the invert sugar were mutarotated immediately upon its liberation, the course of reaction would be different from the ordinary observed course of the reaction.

According to Nelson and Griffin (1916), invertase is of a colloidal nature and the reaction between the enzyme and a cane-sugar solution depends on the contact of two phases. They found that the activity of invertase is not affected when it is adsorbed to a solid like charcoal or to a colloid like saponin, serum, or egg albumin distributed uniformly throughout the substrate (Nelson and Hitchcock, 1921). Nelson and Vosburgh (1917) consider that adsorption is one of the controlling factors in the kinetics of invertase action, since the velocity of the inversion curve, where the concentrations of the cane sugar is used as the abscissas, has the same general shape as adsorption curves. There is yet considerable contradiction and uncertainty, however, concerning the nature of the reaction involved in the hydrolysis of cane sugar by invertase. The results obtained by Nelson and Vosburgh (1917) and others indicate that it is a heterogeneous reaction and not a unimolecular homogeneous one.

It was observed by Nelson and Hitchcock (1921) that not all the preparations of yeast invertase are alike in their action but that some are abnormal in allowing the hydrolysis of cane sugar to slow up more than others after the first 20 per cent of the inversion. This abnormality could be rendered normal by the addition of boiled normal invertase or $N/10$ NaCl in some cases, while in others it was not affected by either of these additions. The cause of this abnormal behavior is not known.

It is generally considered that invertase exerts a reversible reaction, and Kohl (1908) states that inversion gives place to the opposite process sooner in darkness than in light. Hudson and Paine (1914), however, conclude that invertase from yeast accomplishes a complete hydrolysis of sucrose to yield invert sugar and that the reaction does not establish mobile equilibrium and is not a reversible or balanced reaction within the limits of detection.

3. *Factors Influencing the Action.*—The method by which invertase is prepared, the age of the preparation, the dilution of the preparation, and the general treatment of the preparation must all be taken into consideration in discussing the influence of various factors on the activity of invertase. Thus Hudson and Paine (1910) noted that alcohol reduces the activity of invertase. This reduction is not noticeable below 20 per cent alcohol at 30°C., is almost instantaneous at 50 per cent, and decreases to zero at 80 per cent. Cane sugar in alcohol has a protective value on the enzyme. Invertase may be precipitated with alcohol without much destruction provided the strength of the alcohol is approximately 90 per cent. A solid preparation obtained in this manner was 78 per cent as active as the original solution. If cane sugar is present, the invertase may be precipitated with 70 per cent alcohol, and the resulting precipitate give 94 to 96 per cent of the original reaction. Vosburgh (1921) found that invertase solutions are subject to loss in activity when diluted, the loss varying with the substances present in the water with which the invertase is diluted. Dilution with distilled water is attended by less loss than by dilution with weak acids. When an invertase solution is added to a solution containing sucrose, the losses in activity due to dilution are less than when the invertase is diluted by similar solutions not containing sucrose. Different preparations of invertase differ in this regard. In studying the action of invertase of banana extracts, McGuire and Falk (1923) showed that under certain conditions this enzyme exhibited apparently spontaneous increases of activity of considerable magnitude. In some cases the original activity was almost doubled, the activity increasing with the aging of the extract. After reaching a maximum value in a certain number of days, the invertase activity decreased. This increase of invertase activity was independent of the composition of the solution used for extraction and was not due to bacterial growth or cell decomposition accompanied by enzyme liberation. The behavior observed might be due to the fact that the extract contained materials which in the absence of life processes form new enzyme. The invertase in the extract may lose its activity steadily and the formation of new enzyme may be at first greater than the destruction and then become less. This theory would account for the increase and subsequent decrease in the activity of the enzyme.

In their classical paper on invertase, O'Sullivan and Tompson (1890) state that small amounts of acid are favorable to the action of this enzyme but that alkalis even in small amounts are very destructive to its action. These observations, in general, have been substantiated by the work of later investigators. Hudson and Paine (1910) found that acids and alkalis in small concentrations influence the activity of the enzyme but do not permanently destroy it. The destruction by acids at 30°C. reaches a barely noticeable rate at a concentration of $N/100$ and increases with the


acidity until it becomes almost instantaneous at a 5*N*/100 concentration. The alkaline destruction of invertase is almost instantaneous at a concentration of 0.045 *N*. The activity of invertase in weak alkaline solutions is zero, rises to a maximum in very weakly acid ones, and decreases with stronger acid solutions. The activity of the enzyme in weak solutions of HCl, HNO₃, H₂SO₄, phosphoric, boric, oxalic, tartaric, citric, and acetic acids depends almost entirely on the concentration of the hydrogen ions, and the acids thus show typical differences which correspond to their degree of dissociation. The optimum activity of invertase according to Nelson and Bloomfield (1924) at 25, 30, and 35°C. is between P_H 4.5 and 5.0. They found that the effect of temperature and hydrogen-ion concentration is independent of the concentration of sucrose, while the sucrose concentration, at which the hydrolysis in the presence of invertase attains a maximum velocity, is independent of temperature and hydrogen-ion concentration. They consider that the hydrolysis of cane sugar in the presence of invertase involves at least two distinct stages. One of these stages is influenced by the concentration of the sucrose but is independent of the temperature and hydrogen-ion concentration, while the other is influenced by both of these factors (Compton, 1921).

O'Sullivan and Tompson (1890) stated that the speed of inversion by invertase increases with the temperature until 55 to 60°C. is reached and that at 65°C. the enzyme is slowly destroyed. The optimum temperature noted by them was about 54°C. Hudson and Paine (1910) found that at 60 to 65°C. the destruction of invertase with hot water was rapid. A dry sample of the enzyme, however, may be heated for some time at 100°C. without any appreciable deterioration. As the temperature is raised, acids and alkalies react more readily on invertase. Hudson and Paine consider that the destruction of this enzyme by acids, alkalies, and hot water is caused by the hydrolysis of the enzyme molecule. The presence of fructose and sucrose protects the destruction of invertase, and O'Sullivan and Tompson state that a solution of invertase in the presence of cane sugar will withstand a temperature 25° higher than in the absence of the sugar. It is assumed that the enzyme forms a combination with the sugar which is more resistant to the destructive action of acids, alkalies, hot water, and alcohol than invertase itself.

The effect of tannin on the solubility of the invertase of the date was noted by Vinson (1908). The invertase of the date remains insoluble in all ordinary solvents throughout its green stages but becomes readily soluble on ripening. This change of the invertase toward solvents coincides very closely in point of time with the passage of the tannin of the date into the insoluble form. Vinson showed experimentally that soluble tannin hinders the solubility of date invertase in water but that

it may be extracted with glycerol provided the glycerol is added at the same time as the tannin.

b. *The Diastases or Amylases*.—The enzyme or aggregate of enzymes that hydrolyze starch to malt sugar is termed “diastase” or “amylase.” The general reaction of this hydrolysis may be represented by the following equation:



This process of digestion proceeds from starch to amyloextrin, to erythroextrin, to achroextrin, to maltose. The substance designated as diastase thus is probably not composed of a single enzyme but of a series of amylases and dextrinases none of which, however, has been isolated in a pure condition.

According to Bayliss (1925), Dubrunfaut (1830) prepared an extract of malt which converted starch into sugar just as strong acids were known to do. This, according to Bayliss, was the first account of an enzyme in solution. Three years later Payen and Persoz precipitated from malt extract by alcohol a substance which could be dried and preserved and which had a hydrolytic action on starch. To this preparation they gave the name “diastase.” Diastase thus was the first plant enzyme to be reported, and due primarily to its importance in the brewing industry it has been the most extensively studied enzyme in the plant kingdom. Its presence in leaves was first proved by Kosman (1877), and since then (Baranetzky, 1878; Krauch, 1879; and Brasse, 1884) it has been found in all green plants or parts thereof that have been examined, so that apparently it is one of the most widespread as well as abundant enzymes of plants. Diastase occurs in many fungi, and the commercial taka diastase, which is used in medicine and in digestion experiments in the laboratory, is derived from the fungus *Aspergillus oryzae*. The diastase produced by this fungus has been known to science since about 1875 but has been in use in Japan empirically for centuries. Commercial taka diastase was introduced by Takamine in 1898 and is prepared by growing the fungus on wheat bran, extracting it with water, and precipitating the enzyme and other substances by the addition of alcohol in such quantity as to give a concentration of 70 per cent (Sherman and Tanberg, 1916).

There are apparently two well-defined types of diastase which have been termed by Brown and Morris (1890) “diastase of secretion” and “diastase of translocation.” The former receives its name because it is secreted by specialized cells, as will be described in a subsequent paragraph. Its distribution is rather limited, being confined for the most part to the germinating seeds of the grains and grasses. Diastase of translocation is so named because it is the type of this enzyme that

digests starch for translocation to various parts of the plant. It is widely distributed and is found in practically all living parenchymatous tissues of green plants and is probably the product of the protoplasm of the cells in which it occurs. In this regard, Neidig (1914) found in the case of alfalfa hay, clover hay, and corn stover that the activity of the diastase therein was roughly proportional to the number of living cells in the parts at the time of cutting. Diastase of translocation is always found in the greatest quantity in the actively growing regions of the plant (Prunet, 1892; Sjöberg, 1922, 1923; and Green, 1894). Diastase of secretion has the power actively to liquefy and saccharify starch paste, while diastase of translocation does not have the power to liquefy starch paste but has the power to saccharify solutions of soluble starch. Diastase of secretion etches and corrodes the starch grains, giving them the notched and irregular markings that are easily observed in the germinating seeds of grains and grasses (Fig. 30). Diastase of translocation dissolves the starch grains gradually over the whole surface so that no markings can be observed. Diastase of secretion is much more rapid in its action on starch than is diastase of translocation. According to Brown and Morris (1893), diastase of secretion is from two to three times more active than the diastase of translocation which was obtained from the leaves of various plants. The amount of diastase in leaves, however, is ample to transform all the starch in them to maltose, and Brown and Morris estimated that the quantity of diastase in the leaves of *Pisum sativum* examined by them was sufficient to hydrolyze twenty-four times their own dry weight of starch in 24 hr.

The diastases obtained from different plants are similar in many respects but are not identical (Effront, 1922). They all digest starch, but the conditions under which their optimum activity occurs vary widely, as will be discussed in detail under another heading. Sherman, Walker, and Caldwell (1919) noted that when similarly purified by washing with very dilute alkali, wheat, corn, and rice starches showed the same digestibility in the sense that under the action of the same amount and kind of diastase, they were all transformed into sugar at the same rate. Their observations were made with malt diastase and taka diastase.




FIG. 30.—Starch grains of the endosperm of the corn kernel showing different stages of digestion by diastase of secretion.

Stone (1896) found that the starches of potato, sweet potato, maize, rice, and wheat varied greatly in their susceptibility to the action of diastase, so that under precisely the same conditions certain of the starches required eighty times as long as others for saccharification. It was found that the order in which the starches were the most easily digested, beginning with the one which was the most readily changed was as follows: For malt extract, the starch of sweet potato, potato, wheat, and corn; for saliva, potato, sweet potato, corn, rice, and wheat; for pancreatic diastase, potato, sweet potato, and corn; while for taka diastase, the potato was more quickly changed than any other.

The diastases from animal sources are, as a rule, more active than those of vegetable origin. Sherman and Schlesinger (1915) made a comparative study of the composition and activity of pancreatic and malt diastase preparations. They found that both preparations were amorphous nitrogenous compounds which were soluble in water or 50 per cent alcohol but insoluble in concentrated alcohol or acetone. Both showed typical protein reactions with Millon's, xanthoproteic, tryptophane, and biuret tests. Both contained 15 to 16 per cent nitrogen with the amino acids in proportion and within the range of variation shown by casein, edestin, and hemoglobin. When allowed to act on soluble starch for 30 min. at 40°C. under optimum conditions of reaction and salt concentration, the pancreatic diastase showed a much higher activity than any yet obtained from malt. Under such conditions the pancreatic diastase formed 10,000 times its weight of maltose, while malt diastase formed about 4,000 times its weight of maltose. For long digestion experiments at 40°C. the malt diastase was observed to form a total of 9,300 times its weight of maltose whereas the pancreatic diastase had formed 1,200,000 times its weight of maltose. Malt diastase is always more stable than pancreatic diastase on standing in water, but both deteriorate on dialysis. Koga (1923) was able to show by means of seriological reactions the difference between animal and plant diastases.

1. *Preparation of Plant Diastase.*—Plant diastase has been prepared, for the most part, from the germinating seeds of the cereals, especially barley (Osborne, 1895; Thatcher and Koch, 1914; Sherman and Schlesinger, 1913, 1915; Glimm and Sommer, 1927). Numerous methods for its preparation have been reported, but those used by Sherman and Schlesinger (1915) and Naylor, Spencer, and House (1925) represent the most improved technique for the preparation of diastase from germinating grains. The general procedure is as follows:

A definite weight of the air-dry germinated grain is ground and soaked for 3 hr. in 2.5 times its weight of cold distilled water. The entire mass is then placed in collodion bags and dialyzed against running tap water for 24 hr. at as nearly ice-box temperature as possible and then filtered. The filtrate is then treated with solid ammonium sulphate 42 g. to 100 cc. of filtrate and the precipitate which contains the active diastase is separated by means of a centrifuge, dissolved in a small quantity of water, and dialyzed in collodion bags against running tap water and finally against distilled water until free from sulphates. At the end of this dialysis the sacks may contain a

deposit of material which has precipitated with the removal of the dialyzable substances from the solution. This insoluble material, which is without diastatic power, is removed from the solution by centrifuging. The solution is placed in fresh collodion bags and concentrated by evaporation through these bags until the volume is reduced one-half. (This evaporation in the case of rye lowers the activity of diastase and in that case is omitted.)

The solution is then treated with an equal volume of cold alcohol, keeping the temperature below 15°C. The material precipitated by this amount of alcohol is separated by means of the centrifuge and rejected. To the liquid sufficient cold alcohol is added to make the alcohol content 70 to 80 per cent by volume. The precipitate thus obtained is separated by means of the centrifuge and dried in a partial vacuum over sulphuric acid in the dark, at a temperature not exceeding 15°C. The end product that is obtained from the above procedure is considered to be as nearly pure diastase as any preparation that has so far been made.

In the preparation of diastase after the above manner the greatest destruction of enzyme usually occurs in the first precipitation with alcohol. The losses in the final precipitation and in drying are less serious. In general, considerable losses of diastatic power also occur during dialysis, but in order to eliminate impurities it has not been possible to omit this part of the preparation. The loss of activity is not due in any large measure to the passage of the enzyme as such through the dialyzing membrane, as shown by the tests of the dialysate. Sherman and Schlesinger (1915) consider that this behavior indicates that the diastase is a compound composed of an albumin with a proteose or peptone, as suggested by Osborne (1895). Since this compound is destroyed apparently through hydrolysis on heating in water, it seems probable that a fraction of the enzyme would be hydrolyzed in water solution even at low temperatures. The removal of the products of hydrolysis by dialysis would result in a further hydrolysis of the enzyme and loss of diastatic power without any accumulation of enzyme in the dialysate. If carried out at ice-box temperature, the loss of diastatic power is much diminished, while the removal of impurities is little retarded.

Diastase may be prepared from leaves or any other plant parts which contain a relatively small amount of diastase after the following method which was used by Bartholomew (1914) in his study of the diastase of red algae:

The fresh material to be studied is immersed in 95 per cent alcohol for 20 min. and after freezing from alcohol is plunged into acetone for 10 min. It is then partially dried *in vacuo* and placed in an oven at 35 to 40°C. until dry. The material is then pulverized and placed in three times its amount of 20 per cent alcohol and left standing 18 to 20 hr. and then filtered through cheesecloth and filter paper if possible. To the filtrate is added two and one-half times its volume of 95 per cent alcohol. The precipitate is then filtered off and washed with equal parts ether and alcohol, dried in a desiccator, and pulverized for use. The amount of diastase material obtained in this manner from ordinary vegetative tissue is very small. Thus, for example, Bartholomew from 51 g. of dried algal material obtained only 0.15 g. of diastase preparation.

The presence of diastase in leaves or other plant parts may be demonstrated by using a water extract of the finely macerated tissues. This water extract should be filtered through cheesecloth or other porous cloth but not through filter paper, since it has been found that if the extract is filtered clear it loses much of its diastatic power (Vines, 1891). Apparently the diastase of the leaves is closely held in the protoplasm (Palladin and Popoff, 1922; Palladin and Popova, 1924) and when freed is adsorbed to a considerable extent by the fine particles of tissue which do not pass through filter paper. The activity of such adsorbed diastase, however, is not impaired by being adsorbed and exerts its full power when in contact with the substrate. In regard to the adsorption of diastase, the work of Ambard (1920, 1921) is worthy of note. He

found that it is possible to adsorb, quantitatively, the amylase present in dilute solutions upon raw commercial rice starch and to remove foreign substances without the loss of enzyme. The adsorption by the raw starch is specific, since it has no power to adsorb invertase. When diastase has been adsorbed by starch after this manner, repeated washings with various solutions do not remove the enzyme. Upon the addition of a neutral salt as NaCl the enzyme is released by the starch and again goes into solution without any loss of activity.

2. *Study of Diastatic Activity.*—Two methods have been used to determine the activity of diastase: (a) liquefaction. This method measures the power of the enzyme to convert completely a known amount of starch paste into products which no longer give the color reaction with iodine; (b) saccharification. By this method is measured by means of Fehling's solution the amount of reducing sugar produced by the enzyme in a given period of time. These two steps in the action of diastase upon starch are more or less independent of each other, since the conditions for their optimum activity are not the same. For quantitative work the saccharification method is now considered the most reliable.

Various methods have been used for preparing starch for the substrate in the study of diastatic activity, but for the most part they may be grouped under two headings: (a) The dispersion of starch in water under different conditions of time, temperature, and pressure but without chemical treatment. A substrate prepared in this manner is commonly called "starch paste." The concentrations that have been used vary from 0.25 to 2 per cent. A common method for the preparation of such a paste is to heat the desired amount of water to boiling and then add the desired amount of starch, thoroughly pulverized and suspended in as small amount of cold water as possible, to the boiling water and continue to boil for 2 to 5 min. with constant stirring. After cooling, the paste is ready for use. Some investigators discard the starch sediment, which settles out when such a paste is allowed to stand, and use for experimental purposes the more or less clear supernatant liquid; (b) Starch which has been subjected to acids or other chemical treatment to render it soluble so that when mixed with water a more or less clear suspension results. Starch treated in this manner may be obtained commercially and is commonly called "soluble starch." The degree of treatment with acids varies greatly, so that while some of the soluble starches react readily with iodine some no longer give that test.

The methods used in determining the activity of diastase are based primarily upon a method devised by Lintner (1884). These methods in general consist in using a series of test tubes each containing from 2 to 10 cc. of a given concentration of raw or soluble starch. To each of the test tubes is added a different amount of diastase extract generally in a series of 0.1, 0.2, 0.3, 0.4 cc., and so on. After standing under toluene for periods of time ranging from 2 to 48 hr. at 37 to 40°C., 5 cc. of Fehling's solution is added to each tube. The tubes are then placed in boiling water for 10 min. and examined at the end of that time to determine the lowest concentration of diastase in which the copper is all reduced. This may be determined qualitatively by noting the absence of blue color or quantitatively by the usual weighing method. The sample of diastase which produces this degree of conversion into maltose under a given set of conditions is taken as the standard and rated as having an activity of 100. To this standard the activity of diastase under different conditions or from different sources is compared.

The method for determining the degree of diastatic activity by means of the iodine method may be illustrated by the procedure used by Appleman (1911) in his work with the potato. One cubic centimeter of a 1 per cent soluble starch solution was placed in each of ten test tubes surrounded by ice. Increasing amounts of the diastase extract were added to the tubes beginning with 1 cc. and increasing the amount 0.1 cc. for each succeeding tube, using toluene as a preservative. The tubes were then

incubated at 40°C. for 48 hr., placed again in ice water, filled nearly full with water, and three drops of iodine solution added to each tube. The first tube in the descending series which showed a blue or violet color was considered the index for comparing diastatic activity.

3. *Factors Influencing the Action.*—The literature in regard to the action of the medium upon the activity of diastase is very confusing and there are almost as many contradictory results as there are investigators. This confusion is doubtless due to two main causes. In the first place, the method by which the diastase is obtained greatly influences its response to its environment (Osborne and Campbell, 1896); and in the second place, the methods for the determination of the diastatic activity also influence the response of the enzyme to its environment. The nature of the antiseptic used also has an influence upon the activity of the enzyme. Thus Sherman and Wayman (1921) found in low concentrations that chloroform did not affect commercial malt extract, but when the enzymes were purified chloroform diminished their action. Toluene had no appreciable effect on either pure or impure diastase preparation, while formaldehyde with a concentration of 0.0000116 *M* gave a 3 per cent reduction of enzymic activity. All diastases studied were retarded in their action by CuSO_4 . It is the intention to discuss here only briefly some of the observations that have been made. A detailed account of the work pertaining to this topic may be found in the literature cited at the end of this chapter.

(a) *Chemicals.*—It was found by Brown and Morris (1893) that tannin exercised an inhibiting action on the diastase of leaves and that when it was present in considerable amounts it was difficult to obtain an extract of the leaf with any marked degree of hydrolyzing power. They demonstrated that tannin prevented the diastase from going into solution. Sherman and Thomas (1915) studied extensively the effect of acetic, propionic, phosphoric, hydrochloric, nitric, and sulphuric acids, the chlorides, nitrates and sulphates, and primary phosphates of Na and K with reference to the concentrations favoring optimum activity of malt diastase. All of the electrolytes above mentioned increased the activity of this enzyme. The activities observed at the optimum concentrations of these activating compounds varied, depending upon the purity of the enzyme preparation and of the starch used, from less than double to more than thirty fold the corresponding activities in the absence of the electrolyte.

The acids showed a greater activating influence than the neutral salts, while the acid phosphates of Na and K gave as high activation as free acids. The acids all showed optimum activation in those concentrations which had essentially the same actual acidity. This optimum hydrogen-ion concentration was in each case between P_H 4.2 and 4.6. Acetic and propionic acids, in quantity ten times the optimum, decreased the activity about one-half, while HCl, HNO_3 , and H_2SO_4 reduced the activity more than one-half when present in concentrations two and one-half times the optimum. Berczeller and Freud (1922) found that malt diastase was permanently inactivated by I_2 , Cl_2 , and Br_2 and that starch exercised a protective action against this inactivation, although the enzyme eventually lost its digestive power. According to Haeln and

Schweigart (1923), the chlorides of Na, Ca, K, Ba, and Mg activated potato diastase under the conditions of their experiment, while diastatic hydrolysis was delayed by salts of Zn, Cd, Pb, and Cu. Salt-free diastase prepared by dialysis and ultrafiltration was entirely inactive, no change occurring during 24 hr. The preparation could be rendered active by the addition of NaCl. Ambard (1923) considered that neutral salts in some way act upon the substrate. The most widely accepted hypothesis is that they accelerate the enzymic activity by increasing the colloidal dispersion of the enzyme.

It was discovered by Sherman and his workers (1919 to 1922) that numerous amino acids including glycine, aspartic acid, arginine, tyrosine, cystine, and lysine increased the activity of certain animal diastases. These amino acids also had the power to restore to full activity diastase which had been partially inactivated by CuSO_4 and to prevent the deterioration of this enzyme in water. Haeln and Schweigart (1923) noted that glycine, alanine, and leucine activated the diastase of the potato.

A large amount of work has been done to determine the optimum hydrogen-ion concentration for diastatic activity. It should be remembered that the apparent optimum reaction may vary to a considerable degree depending upon the temperature (Chrzaszcz and Krause, 1925), the buffer used, the accumulation of products formed, and the source of the enzyme. Sherman and Thomas (1915) found that the optimum hydrogen-ion concentration for malt diastase was P_H 4.2 to 4.6. Sjöberg (1922) found the optimum acidity for a series of plant diastases to be between P_H 5.0 and 5.4. Sherman, Thomas, and Baldwin (1919) found that the optimum P_H value for malt diastase was 4.4 to 4.5, taka diastase 4.8, and pancreatic diastase 7.0. Sherman, Thomas, and Caldwell (1924) found that the isoelectric point of a malt-diastase preparation was P_H 4.3 to 4.5, which coincides with that of its optimum enzymic action upon starch. Maslow and Davidson (1926) found that the optimum reaction for the dextrin-liquefying activity of the dextrinase of taka diastase was P_H 4.0 at 34°C . According to Polak and Tychowski (1928), there are two diastases present in malt extract whose optimum P_H values are different. α -diastase works best at P_H 5.1, while β -diastase reacts best at P_H 4.3. Sjöberg (1922) noted that the optimum P_H for sugar formation by diastase was 5.0 to 5.5, while that for the disappearance of starch was 4.0 to 6.0.

(b) *Temperature*.—The maximum and optimum temperatures for diastatic action will depend upon the source of the enzyme and the nature of and amount of the substrate as well as the presence of the end products. Chrzaszcz (1923) by the use of watery extracts of rye, wheat, oats, corn, buckwheat, barley, broom corn, and millet found that diastases from different sources did not respond to temperature in the same manner at the supposedly optimum hydrogen-ion concentration *i.e.*, P_H 4.9.

The optimum temperatures for barley diastase was 49 to 54°C., for wheat and rye 49 to 55°, for oats 51 to 53°, for buckwheat 50 to 55°, for corn 56 to 57° and for millet 58 to 59°. Barley diastase was completely destroyed at 61 to 62°C., wheat at 63 to 64°, and others at 65 to 66°. Sjöberg (1922) found that the temperature coefficient for sugar formation by diastase decreases between 20 and 40°C., while the temperature coefficient for starch disappearance is constant between those two points.

(c) *Light*.—It was observed by Brown and Morris (1893) that the amount of diastase in leaves increased when they were placed in the dark. They considered that the secretion of diastase is stimulated by the absence of soluble carbohydrates. Sjöberg (1923), however, in experiments with the leaves and blossoms of the tulip concluded that the formation of diastase is independent of light. Pincussen (1923) found that the reaction of light from a quartz light on malt diastase depended on the concentration of the enzymes, on accompanying compounds, and on the reaction of the medium. The greatest injury from light occurred at the optimum reaction for enzyme activity. Green (1894) exposed portions of a preparation of malt diastase to light for periods varying from 2 to 10 days and tested the action of these exposed preparations upon starch paste. He concluded that light, both solar and electric, exercises a destructive influence upon diastase, the deleterious influence being confined to the rays of the violet end of the spectrum, the other rays being slightly favorable instead of destructive. He considered also that the coloring matter of the barley husk acts as a screen in preserving the diastase in that grain from the destructive effects of light. The destruction by light of diastase in the leaves is only 15 to 20 per cent as compared with 68 per cent for malt diastase under the same conditions. Green (1897) considered that either the diastase is more resistant in the leaves or there is some constituent that has the power of screening the enzyme from the deleterious rays. Chlorophyll might serve this purpose, and protein is known to protect the enzyme in this regard. Green considers that when a leaf is illuminated by the whole spectrum, the beneficial rays convert the zymogen into diastase and the latter is speedily destroyed by the deleterious rays. The latter action is the more rapid so that the effect of the whole spectrum is to diminish the amount of diastase in solution.


Baly and Semmens (1924) in experiments with the action of diastase upon the starch of potato, wheat, and corn obtained results which indicate that plane-polarized light exercises a powerful acceleration on the hydrolysis of starch by weak solutions of diastase. Later (1925, 1926) they claimed that starch grains in pure distilled water may be hydrolyzed by a beam of polarized light and that after 2 to 4 days' exposure the etching on the starch grains may be observed. Macht (1925) substantiated their results when he found that polarized light hastened the

conversion of starch into sugar in the presence of diastase. Macht and Hill (1925) noted also that when a suspension of *Saccharomyces cerevisiae* was added to solutions of sucrose the fermentation of sugar proceeded much more rapidly in polarized than in non-polarized light. The work of Baly and Semmens (1924), however, has been adversely criticized by Jones (1925), who considered that the results reported for the action of polarized light on starch grains are doubtful.

c. *The Inulases*.—Inulase is an enzyme which hydrolyzes inulin to levulose or fruit sugar. It was named by Green (1887), who first observed it in the germinating tubers of the Jerusalem artichoke (*Helianthus tuberosus*) and later (1899) found it in the bulbs of *Leucocrium* and *Scilla*. Green could not find inulase in the resting stage of the tubers and bulbs, but if the macerated tissue was kept at 35°C. for awhile, the enzyme was found to be present. It thus appears to occur in the resting tissues in the zymogen form. Inulase may occur with diastase but has no action whatsoever upon starch. Green found that inulase works most advantageously in a neutral or very faintly acid medium, 0.001 per cent HCl being very favorable, but higher concentrations than this were very destructive. An alkali medium was extremely deleterious. These observations in regard to the medium have been confirmed by Kizel (1915). The optimum activity of inulase occurs at 50 to 55°C. but loses its activity when heated to 70 to 75°. Wolff (1916) found in the roots of *Dahlia variabilis* and *Cichorium intybus* a substance which coagulates very actively the juices extracted from these plants and precipitates inulin from the solution.

In 1893 Bourquelot found inulase in the fungi *Aspergillus niger* and *Penicillium glaucum*. It has since been studied in these plants by Dean (1903) and Young (1918). It occurs in abundance in these fungi and most of our knowledge concerning inulase has been derived from these sources. Dean (1903) verified the work of Bourquelot (1893) and found that the enzyme from these fungi reacted in much the same manner as the inulase of the Jerusalem artichoke described by Green (1887).

d. *The Glucases or Maltases*.—The enzyme which hydrolyzes maltose to glucose has been termed "glucase" or "maltase." The reaction occurs after the following manner:



The occurrence of a maltose-splitting enzyme in plants was first suggested by the work of Brasse (1885). He noted when a preparation of malt diastase was allowed to act on starch at 32 to 42°C. that glucose was formed but that when the action occurred at 50 to 57° only maltose was produced. Brasse, however, did not realize that he was working with a

special enzyme capable of digesting maltose. According to Daish (1916), maltase was first observed in corn seeds and seedlings by Cuisinier (1885), who termed it "glucose" and patented a process of converting starch into glucose based on its use. He stated that this enzyme is present in the organs and seeds of a large number of plants, a statement which is now known to be correct, but which could not be substantiated by many subsequent workers for reasons that will be mentioned later in this discussion. Observations by Beyerinck (1895), Huerre (1909), Wierzychowski (1913), and Daish (1916) have substantiated the statement of Cuisinier that maltase is widely distributed in plants. It has been demonstrated in the leaves of a large number of plants and in the resting seeds and seedlings of corn, rice, millet, oats, wheat, barley, rye, buckwheat, and others. Maltase is also present in many of the fungi, and the commercial taka diastase contains this enzyme in larger amounts than does germinating barley.

Maltase has three or four characteristics that are considerably different from other carbohydrate-splitting enzymes and it is due to these characteristics that many investigators failed to detect maltase in the plant material with which they worked. The optimum temperature for activity is from 38 to 40°C., but above that temperature it is rapidly destroyed. Much of the plant material that has been examined for maltase was dried at a temperature of from 40 to 50° so that the enzyme was completely inactivated in the preparation. This also explains the reason for the observation of Brasse (1885) that a malt-diaastase preparation at 32 to 42°C. formed glucose when acting on starch while at 50 to 57° only maltose was formed. The maltase obtained from different sources varies widely in its temperature range, which indicates that there are several varieties of the enzyme (Huerre, 1909). Maltase is practically all destroyed by precipitation by alcohol, a treatment that injures only to a limited degree most of the enzymes. It is very difficult to obtain this enzyme from plant tissue by extraction with water. The enzyme is an endocellular one, and unless the material is extremely well pulverized very little of the enzyme is released. The best action of maltase has been obtained by using the pulverized powder of the seeds or the crushed pulp of the vegetative portions of the plant. It is very sensitive to chloroform and shows only a slight action in the presence of that antiseptic. Toluene has been found to be very satisfactory as a preservative in studying this enzyme.

e. The Cellulases or Cytases.—The enzymes that are capable of dissolving the cellulose walls of plants have been termed "cytases," "cellulases," or "cytohydrolytic enzymes." The existence of cytase was first noted by DeBary in 1886 when he observed that the hyphae of the fungus *Peziza sclerotiorum* were able to penetrate the cell walls of plants. In 1888 a similar enzyme was reported by Ward for a fungus belonging to

the genus *Botrytis*. Since then similar enzymes have been found in numerous green plants and in other fungi. The action of cytase is relatively slow and is confined entirely to normal cellulose and to hemicelluloses. In all the cases that have been observed the cell wall at first becomes hyaline, then gradually becomes more and more transparent, and finally fades away into solution. The cytases are destroyed at a temperature of 60°C. or above.

Brown and Morris (1890, 1898) noted in the early stages of the germination of barley that the parenchymatous cell walls of the endosperm directly under the epithelium cells of the scutellum and the cells of the aleurone layer are disintegrated and ultimately dissolved. This dissolution of the cell walls always precedes any visible action upon the starch grains contained within these cells. This dissolving action they attributed to cytase secreted by the epithelial cells of the scutellum and aleurone layer. They were, however, unable to obtain any action of this enzyme upon the cellulose of the date, asparagus, coffee, or onion seeds, but in the case of the Jerusalem artichoke, potato, carrot, and turnip this enzyme preparation from malt dissolved cell walls. The most thorough work that so far has been done on cytase is that of Newcombe (1899). He prepared a water extract of the seedlings of barley and *Lupinus albus* and the embryos and endosperm of the date seed and prepared cytase by precipitation from the extract after the manner used in the preparation of diastase. He used the following method to determine the action of cytase: Sections were made of the tissues to be examined and were freed from starch if present by treating for 24 hr. with saliva or a pancreatic preparation. The sections were then placed in a solution containing 150 mg. of the enzyme preparation to 10 cc. of water with chloroform as an antiseptic and allowed to stand at 32 to 34°C. The action of the cytase was determined by microscopical examination. In the case of the cell walls of the endosperm of barley, the cytase from various sources dissolved them down to the middle lamella in from 5 to 10 hr., but the cell walls of the aleurone layer were more resistant. In the case of the cell walls of the white lupine, 9 days were required to reduce the cell walls to a hyaline condition, while complete dissolution was not effected even in thin sections until 3 or 4 weeks and then only at the edges of the sections. The enzyme prepared from the embryo and endosperm of the date was capable of digesting the heavy cell walls of the endosperm cells of that seed. After 30 days the whole surface of the section was corroded and the exposed walls frayed out. All the walls became hyaline and the whole section became smaller due to the gradual dissolving action. Newcombe found that the cytase preparations obtained from the seedlings of the date, white lupine, barley, and *Aspergillus oryzae* were apparently not specific so far as could be observed.

f. Other Carbohydrases.—Some of the carbohydrases that have been found in plants, but which in most cases play an unimportant rôle in the life of the green plant, are (1) melibiase, which hydrolyzes melibiose to glucose and galactose; (2) gentianase, which hydrolyzes gentiobiose to glucose; and (3) pectinase, an enzyme capable of hydrolyzing pectose to arabinose.

2. The Glucosidases of Plants.—Before discussing the action of the enzymes of this group, a few statements should be made concerning the compounds upon which they act. The glucosides for the most part are compounds which contain glucose as the characteristic basic group. Upon hydrolysis the glucosides yield glucose together with one or more other substances, usually of an aromatic nature. Some of the organic constituents which may be combined with sugar to form glucosides are phenols, alcohols, aldehydes, acids, and mustard oils. Most of the common glucosides are derived from d-glucose. Some, however, are derivatives of galactose or rhamnose, while in some the exact sugar which is combined in the glucoside is not known. Some of the glucosides are amygdalin found in the almond and other plants of the *Rosaceae*, sinigrin in the *Cruciferae*; silicin in the willow; arbutin in the leaves of bearberry; phlorizdin in the bark of apple, pear, cherry, and plum; populin in the bark of the poplar tree; aesculin in the bark of horse-chestnut; phytin in the coats of seeds; and saponins which occur in more than 400 species of plants.

In this connection some mention should be made of the tannins, although they are not at present classified as glucosides. Tannins are a group of substances that are almost universally distributed in plants. They occur in leaves, wood, bark, unripe fruits, walnut hulls, and many other plant parts. They are especially abundant in the pathological plant growths known as galls and their dry weight may be composed of from 40 to 75 per cent of this group of substances. Tannins make up about 15 per cent of the dry weight of tea leaves and about 40 per cent of the dry weight of oak bark.

The tannins are amorphous, have an astringent taste, give ink colors with ferric salts, precipitate gelatine from solution, and form insoluble compounds with it and are precipitated from solution by copper or lead acetate, stannous chloride, and other metallic salts and by a strong aqueous solution of potassium bichromate. They are readily soluble in hot water and form solutions which are in reality colloidal gels.

Tannins are usually hydrolyzed by acids into a variety of products, one being nearly always d-glucose and the other a hydroxy derivative of the aromatic series. While they usually contain sugar, they do not show the characteristic properties of the true glucosides and are considered as a separate class of substances.

The tannins are generally considered as waste products rather than substances that can be utilized in the nutrition of the plant, for the fol-

Myrosin not only acts on sinigrin but has the power to decompose practically all sulphur containing glucosides that have been examined.

3. The Esterases or Lipases of Plants.—The enzymes of this group accelerate the cleavage of all the simple esters of the trihydroxy alcohols and glycerine as well as many synthetic esters. These enzymes are frequently called “fat splitting” because they hydrolyze the fats and oils to glycerine and fatty acids. The term “lipase” has been almost universally used in a collective sense in speaking of the enzymes of this group. Recent work, however, has shown that the ordinary preparations of lipase contain at least two fat-splitting enzymes which differ in their solubilities and rate of action. It has also been observed that although lipases from different sources show striking similarities in their behavior (Barton, 1920) they at the same time show minor differences which indicate that they are not identical enzymes.

The presence of a fat-splitting enzyme in plants was suggested by the observations of Pelouze (1855) on the seeds of flax, mustard, and rape. Lipase, however, was first proved to exist in plants by Green (1890) in working with the germinating castor bean. Sometime later Sigmund (1890, 1892) found it in both the resting and germinating seeds of the rape, opium, poppy, hemp, flax, and corn. These observations were later confirmed and extended by Connstein, Hoyer, and Wartenberg (1902) and Hoyer (1904) who found that some oily seeds, at least, contain the enzyme whether germinating or not and that an enzyme obtained from a given seed is capable of hydrolyzing fats and oils from other sources.

a. Preparation and Study of Lipase.—Numerous studies have been made concerning the preparation and action of this enzyme, but they have been confined almost entirely to the lipase of the castor bean (*Ricinus communis*). This is probably due to the fact that the enzyme from this source is easily prepared, very stable, and relatively very active. To understand the methods used in the preparation of lipase, a few facts concerning the nature of the enzyme should be considered. Lipase in the castor bean occurs apparently in the zymogen stage. This zymogen appears to be somewhat soluble in fats or in a mixture of fat and ethyl ether but is insoluble in ether alone (Taylor, 1906). The lipase zymogen is activated by acids. According to Haley and Lyman (1921), the active enzyme is unstable and is rapidly destroyed in an acid medium in the absence of fats. In the presence of fats, however, the enzyme shows much greater stability. The lipase found in the seeds of *Chelidonium majus* does not exist in the zymogen state, so that it is not necessary to treat with an acid in order to activate it. The method used by Haley and Lyman (1921) in preparation of the lipase of the castor bean may be taken as an example of the procedure generally followed in the preparation of the enzymes of this group. Fifty grams of hulled castor-bean kernels are ground as finely as possible, mixed with 150 cc. of 1 per cent acetic acid, and allowed to stand for three days at room temperature (the acid treatment varies from 15 min. to several days with other investigators depending on the concentration and types of acid used). The mixture is then filtered, washed with water, and dried at room temperature, after which it is extracted in a Soxhlet apparatus with petroleum ether of a low boiling point. The extracted material is passed through a 40-mesh sieve and again extracted if necessary to completely free it from oil. The

extracted material may then be dried in vacuum or over any drying agent in a desiccator and the light fluffy powder thus obtained may be kept indefinitely in the dry state.

It has been observed by Falk (1913, 1917) and Falk and Sugiura (1915) that two lipases are present in a lipase preparation which has been obtained after the manner mentioned above. One of these is soluble in water and the other insoluble. The former has, comparatively, a greater action toward ethyl butyrate than toward triacetin, while the latter has a greater action toward triacetin than toward ethyl butyrate. The water-soluble portion of such a lipase preparation has been termed "esterase" by Falk, while the other portion has been termed "lipase." He obtained the esterase from a dialyzed and filtered water extract of oil-free castor-bean powder, 0.5 g. to 60 cc. of water. The lipase preparation was obtained by extracting the water-extracted castor-bean powder with a 1.5/*N* NaCl solution, 1.0 g. of material to 100 cc. of solution, and dialyzing until salt free. After such dialysis the lipase is in a suspension in the water. Both the "esterase" and "lipase" preparations act on the higher glycerides, but the latter is somewhat more active than the former. Falk (1915) found that soybeans contain apparently the same lipases as castor beans, the only difference being that the reaction of the castor-bean lipase was somewhat more intense than that obtained from the soybean.

The methods of studying the action of lipases have been numerous and the differences in results obtained by different investigators may be attributed, in part at least, to this cause. Since the action of lipase on fats and oils is relatively slow, many investigators have used ethyl butyrate, triacetin, and other simple esters as a substrate in their study of the action of this enzyme. From the standpoint of plant physiology, however, the study of the hydrolyzing action of the lipases on the fats and oils is more desirable, since these compounds are the ones normally acted upon by these enzymes in the digestive process in plants.

The method used by Haley and Lyman (1921) in studying the action of lipase is as follows: Place 0.1 g. of lipase powder, 1.0 g. olive oil, and 0.6 cc. of HCl, varying in concentration from 0.02 to 0.2 per cent, in a test tube. The contents are thoroughly mixed and placed in the incubator at 38°C. for 24 hr., using toluol as an antiseptic. The order in which the ingredients are added in making up the digestive mixture is of much importance. Thus Haley and Lyman found that if the acid is added to the enzyme material before the oil, complete loss of the lipase is liable to occur. After the period of incubation the mixture is washed from the test tube with 50 per cent alcohol into wide-mouth titration bottles. The resulting mixture is then titrated with *N*/10 NaOH in 50 per cent alcohol using phenolphthalein as an indicator. The degree of hydrolyzation of the oil is determined by the amount of NaOH required for the neutralization of the fatty acids formed in excess of that required to neutralize the controls.

Nicloux (1904 to 1906) made extensive studies concerning the lipolytic activities of the castor bean in a manner quite different from that pursued by other investigators. By mechanical means he separated the cytoplasm of the ground material from the aleurone grains and other cell contents. The cytoplasmic material extracted in this manner had the property of hydrolyzing fats. It acted on the fats in the same manner as enzymes and followed all the laws of enzyme action. He termed the active matter in the cytoplasmic material "lipaseidine" and claimed that it was destroyed by water as soon as it was no longer protected by fats. It seems very probable that Nicloux was working with the lipase of the castor bean which had been obtained in a different manner from that which is generally followed.

b. Factors Influencing the Action.—The influence of the acidity of the medium upon the action of lipase has been extensively studied. The

early investigators on this subject noted in the germination of oily seeds that the hydrolysis of oils took place slowly at first and then increased rapidly. This led to the conclusion that for rapid hydrolysis by lipase a certain amount of free acid is necessary. This conclusion was verified in many cases, since when a small amount of free acid was added at the beginning of an experiment the hydrolysis of the fat was rapid from the first and was soon completed. Considerable contradiction, however, existed in the literature in regard to the effect of acids upon the hydrolysis of fats and oils by lipase. These contradictions are due primarily to the failure of the investigators to take into account the two following facts: (1) that lipase in the seeds in many cases exists in the zymogen condition and (2) that after the zymogen is once activated the enzyme is rapidly inactivated by acids unless oil is present. Armstrong (1905) and Armstrong and Gosney (1913) found that any acid is effective in activating lipase but that the enzyme prepared with a weak acid such as acetic is distinctly superior to that obtained by the use of a stronger acid. They found that aspartic, glutamic, and succinic acids were very efficient in activating lipase preparations. In this regard it is also of interest that Falk and Nelson (1912) found that glycine, phenylalanine, and other amino acids as well as polypeptides aided the hydrolysis of methyl acetate, ethyl butyrate, and olive oil and that this action was to a certain extent selective in character. The above observations are significant, since the compounds mentioned occur in relatively large amounts in germinating seeds at a very early stage.

The effect of various concentrations of HCl on the hydrolysis of olive oil by castor-bean lipase which had been activated in its preparation by one per cent acetic acid is shown by the following data which were taken from the work of Haley and Lyman (1921). In this experiment 0.1 g. of lipase powder, 1.0 g. of olive oil, and 0.6 cc. of HCl were mixed and incubated for 24 hr. at 38°C.

HCl 0.6 cc., per cent	Extent of hydrolysis NaOH used in titration, cubic centimeters	Fat hydrolyzed, per cent
0.00	1.0	3
0.02	2.2	6
0.04	16.5	49
0.06	18.2	54
0.08	24.6	73
0.10	24.6	73
0.12	27.2	79
0.14	30.6	90
0.16	29.7	88
0.18	28.3	84
0.20	27.6	81

They found that the optimum P_H for castor-bean lipase activity was 5.0 and that at P_H 3.0 lipolytic activity ceased entirely. Tanka (1910) considers that the lipase of the castor-oil bean is contained in the resting seed as a zymogen and that the acid, found by some to be necessary for the activity of the extracts, is of use only for the conversion of the zymogen into enzyme which in reality is most active in a neutral medium. In this regard the observations of Falk and Hamlin (1913) in regard to the effect of manganous sulphate on the acceleration of the activity of castor-bean lipase preparation should be noted. They considered that the acceleration of lipase activity is due to the fact that the inactive zymogen of lipase in the castor bean is converted into the active enzyme by an oxidation reaction for which the presence of an "oxygen carrier" or catalytic agent is necessary. Thus manganous sulphate does not accelerate directly the action of the enzyme present, but by aiding the conversion of the inactive zymogen into active enzyme, it increases the total amount of enzyme present or replaces the enzyme which may become inactive on account of hydrolysis. It was shown by Falk (1913) that solutions of methyl and ethyl alcohol and acetone exerted an inhibitory action on the hydrolysis of ethyl butyrate by castor bean lipase preparation, the amount of inhibition increasing with the concentration. Solutions of glucose and glycerol showed no inhibiting effects except in concentrated solutions. As compared with aqueous solutions, decreased activities of lipase were shown in the presence of all the univalent salts of the chlorides and nitrates of Ba, Ca, and Mg, of sodium oxalate, and of dilute solutions of sodium sulphate. Increased activities were shown by lipase in the presence of dilute solutions of the chlorides of barium and calcium, of more concentrated solutions of Na_2SO_4 and $MgSO_4$, and of the chlorides and sulphates of Mn.

Armstrong and Gosney (1913) considered that the fatty acids and glycerol formed in the hydrolysis of oil by lipase inhibit the interaction of enzyme and oil but there are little data in this regard.

In this connection the reverse action of lipase on its substrate—the formation of glycerides from the glycerol and acids—should be considered. Taylor (1906) using triacetin as a substrate considered that this reverse action of castor-bean lipase is one of very low velocity and may be disregarded in ordinary tests. The hydrolytic reaction of lipase, however, is never complete and there is a definite point of equilibrium in the reaction. The synthetic action of lipase has been discussed in Chap. X.

The enzyme lipase when prepared in the powdered form is very resistant to heat and may be heated when dry to $100^\circ C$. without injury. Falk (1917) found when lipase extractions in water were heated to $100^\circ C$. for a few minutes that they were completely inactivated. The same preparations when heated dry at 100 to $110^\circ C$. lost from 50 to 80 per cent

of their activity. The temperature range of lipase activity is about 23 to 42°C. with the optimum temperature in the vicinity of 38°C.

The degree of the emulsification of the fats and fatlike materials is an important one in determining the lipolytic action of lipase. The lipase powder of castor bean and soybean is apparently effective in bringing about emulsification. The addition of ether or petroleum ether to certain fatty mixtures has been found greatly to facilitate the hydrolytic action of lipase, due, evidently, to the solution of the fats. The amount of water present in the digestive mixture is also an important factor. The rate at which interaction takes place is dependent presumably on the conditions at the colloid surfaces, and Armstrong and Gosney (1913) consider that in the case of lipase this interaction must be supposed to take place at or between the surfaces separated, at the most, by a thin film of water. Falk (1917) considers that the inactivation of esterase and lipase preparations by acids, bases, neutral salts, alcohols, acetone, esters, and heat leads to the hypothesis that the active enzyme grouping in these substances possesses the enollactim structure $-\text{C}(\text{OH}) = \text{N}-$ which becomes inactive by tautomerization to the keto-lactam structure, $-\text{CO}-\text{NH}-$.

4. The Proteases of Plants.—The proteases of one type or another are apparently universally distributed in all plants and plant parts. As a general rule, they are more difficult to prepare for study than the carbohydrate enzymes and their action proceeds much more slowly. Even the most active of the proteolytic enzymes require from several hours to several days to produce an appreciable amount of digestion products under laboratory conditions as contrasted with only a few minutes required by diastase or invertase to transform starch into sugar or cane sugar into the invert form. The stage to which the proteolytic action has proceeded as well as the amount of digestion products formed is also difficult to determine, so that much of the work that has been done with plant proteases has been only qualitative in character.

The common qualitative methods that have been the most generally used are to test the enzyme mixture for tryptophane, to examine it for leucine or tyrosine crystals, to test for peptone by the biuret color reaction, or to note the general dissolving action of the enzyme. Some of the quantitative methods that have been used are (a) the determination by weight of the amount of coaguable protein that remains in the solution, (b) the determination of the total nitrogen of the digestion products, (c) the measurement of the increased amino nitrogen by the Van Slyke method, (d) the determination of the increase in the electrical conductivity, (e) the determination of the changes in optical activity, (f) the determination of the extent of protein hydrolysis from the number of free carboxyl groups formed (Sørensen's method, 1908), and (g) the use of the biuret and tryptophane color reactions in a quantitative way

by noting the differences in color intensities. Sherman and Neun (1916) consider that the determination of the total nitrogen or the amino nitrogen of the digestion products is the most accurate and delicate means of measuring proteolysis. Some of the methods for detecting the degree of proteolytic action will be discussed in detail when some of the enzymes are considered.

a. Historical.—Vines (1909) considers that the delivery of Sir Joseph Hooker's presidential address at the British Association in 1874 and the publication of Darwin's book on "Insectivorous Plants" in the following year may be taken as the starting point of the scientific investigations of proteolysis in plants. Hooker found that if cubes of the white of eggs were immersed in the pitchers of *Nepenthes* for 24 hr. their surfaces were more or less dissolved or gelatinized and pieces of fibrin totally dissolved. He was not certain, however, whether this action was due to the juices secreted by the pitchers or to the action of bacteria. Tait (1875), however, considered that digestive enzymes of a peptic nature occurred in these plants and prepared the enzyme in crude form.

Von Gorup-Besanez (1874, 1875, 1876) appears to have been the first to examine seeds for proteolytic enzymes. Using the glycerine method of extraction, he obtained protease preparations from the resting seeds of hemp, flax, and vetch and from germinating barley. He failed to find enzymes of this type in the ungerminated seeds of barley, lupine, and corn. In 1887 Green found a proteolytic enzyme in the seeds of lupine. This enzyme worked in an acid medium and converted fibrin into peptone, leucine, and tyrosine. He considered that it existed in the seed in the form of a zymogen and was transformed into the active state by acid. In 1890 the same author discovered that a tryptic enzyme was developed in the castor bean during germination. This enzyme was capable of splitting fibrin with the formation of peptone and crystal bodies including tyrosine. He considered that this enzyme also existed in zymogen form in the seed. Neumeister (1894) found positive tests for proteases in barley, beet, poppy, corn, and wheat seedlings but negative tests in many others. Fernback and Hubert (1900) and Weis (1900) showed that the germinating barley of malt contained a proteolytic enzyme. Finally, the work of Fermi and Buscalioni (1899), who were the first to make a systematic examination of a large number of plants, showed that proteases occur in a great diversity of plants and plant parts and give strong evidence to the present conception that proteases are of almost universal occurrence in plants.

b. Kinds.—The proteolytic enzymes are generally grouped into three classes: (1) the pepsins, (2) the trypsins, and (3) the erepsins.

1. *The Pepsins or Peptases.*—A pepsin or peptase is a proteolytic enzyme which hydrolyzes protein no further than to the form of proteoses or peptones. It does not act on proteoses or peptones whether they are produced by its own digestion or supplied to it in the artificial form. Enzymes of this type occur in the gastric juice of all normal animals. It was considered by the early investigators that many of the proteolytic enzymes of plants were of the nature of pepsin, but later investigations have proved that they were mistaken and that enzymes of the pepsin type occur only rarely in plants.

The only case in which pepsin has apparently been proved to occur in plants is that of *Drosera*, which was studied by White (1910). She

studied the leaves of the four species of this plant, and, with the best methods so far known for enzyme extraction, the only proteolytic enzyme that could be obtained was one which had the characteristics of a pepsin, since the end product under well-controlled experiments of digestion was always peptone. Her method of procedure is here given because it may be used as a model for the extraction of other plant proteases and the study of their reaction.

The leaves were cut from the plant and all traces of foreign matter removed from them. They were then washed in cold boiled water and again in a strong solution of chloroform, which acts as an antiseptic. The leaves were then chopped into minute pieces with a sterilized knife and the fragments weighed and put into a bottle containing about 100 cc. of luke-warm boiled water and 30 drops of chloroform. The bottle was shaken vigorously for 2 hr., when its contents were filtered. To the filtrate was added half its volume of a saturated solution of ammonium sulphate which was found to be more efficient in the precipitation of this enzyme than alcohol. The precipitate thus obtained was filtered off on a filter paper which had been previously sterilized with boiling water and was dried in a sulphuric acid desiccator. When almost dry the precipitate was scraped off the filter paper with a sterilized knife and dissolved in cold boiled water. A measured quantity of this solution was then placed in test tubes and the material to be tested for digestion added. One of the test tubes was boiled and another left unboiled, about 20 drops of chloroform was then added, and the contents well shaken. The ends of the test tubes were plugged with cotton and placed in an oven at 35°C. After 30 to 50 hr. the tubes were removed from the incubator and tested for the activity of the enzyme.

2. *The Trypsins or Tryptases.*—The term “trypsin” is given to an enzyme which not only hydrolyzes proteins to proteoses and peptones but also further splits these up into amino acids. The protein may be completely hydrolyzed into amino acids by an enzyme of this type or only partly so, since in some cases the hydrolysis is not complete, some polypeptides remaining as a residue. The first enzyme of the trypsin type to be identified in plants was papain, first studied by Wurtz and Bouchut (1879), whose tryptic behavior was first definitely determined by Martin (1884 to 1885). The discovery by Green (1887, 1890) of a tryptic enzyme in the germinating seeds of lupine and the castor bean, the investigations by Chittenden (1894) of bromelin in the pineapple, and the study of the pitcher liquid of *Nepenthes* by Vines (1897, 1898) definitely established that enzymes of the trypsin type are widespread in plants. We shall now consider in detail some of the plant trypsins.

(a) *Papain.*—This enzyme has been studied more than any other protease of the plant kingdom. It is elaborated by the papaw (*Carica papaya*), a plant that is native to the Caribbean, Gulf of Mexico, and

South American regions whence it has spread to many parts of the world. This enzyme is secreted into the milky latex that is characteristic of this plant and is distributed in its roots, stem, leaves, and fruit. The enzyme has been designated variously "papaïn," "papayotin," "papaytin," or "papayacin." It is obtained by collecting the latex from incisions made in the plant parts and drying it in the sun. This dried preparation is reduced to a powder and may be obtained on the drug market.

The proteolytic properties of the latex of this plant have long been known, and Vines (1909) notes that statements concerning its digestive action are recorded as early as 1750. It was observed that if meat was steeped in this liquid for a short time it became very tender. Its digestive action on the mucous membrane of the intestines of swine which had eaten the fruit was also observed. The latex was first scientifically investigated by Wurtz and Bouchut (1879) and Wurtz (1880). They extracted the latex with distilled water and added to this extract ten times its volume of alcohol. The precipitate which was formed by this treatment was collected on a filter and dried. To the white powder thus formed they gave the name "papaïn" and regarded it as the digestive enzyme of the latex. Martin (1884, 1885) proved the formation of leucine and tyrosine in the course of the digestion of fibrin and albumin by papaïn and thus considered that it behaved as a trypsin. Later Chittenden (1892) reported the formation of large proportions of peptone together with small amounts of leucine and tyrosine from the digestion of coagulated egg white, fibrin, and raw and cooked meats by the action of this enzyme. These observations were substantiated by Chittenden, Mendel, and McDermott (1898), who showed that the chief products of digestion in the case of papaïn were albumose and peptone, and later these observations were again confirmed by Mendel and Underhill (1898). In 1902 Vines found by means of the tryptophane test that papaïn actively digests peptone in neutral solution, more actively in the presence of acid (0.5 per cent citric), and less actively in the presence of alkali (0.5 per cent Na_2CO_3). In later experiments Vines (1903, 1905) suggested that papaïn might be a mixture of two proteases, basing his opinion on the behavior of the enzyme toward different antiseptics. He found that chloroform, sodium fluoride, thymol, salicylic acid, toluene, and formalin did not inhibit the peptonizing action of papaïn but that they impeded further proteolysis in the formation of tryptophane. He found that HCN was the only antiseptic in the presence of which papaïn split off any considerable amount of tryptophane. It is of interest to note that several of the earlier workers who observed leucine and tyrosine as digestive products of this enzyme used HCN as an antiseptic. Mendel and Blood (1910) consider that the extreme differences in the rate at which papaïn accomplishes the earlier and later steps in digestion furnish

strong evidence that it is a mixture of at least two enzymes, although conclusive proof that this is the case has not been furnished.

The properties of papain were studied in considerable detail by Mendel and Blood (1910). They observed that the digestion of peptone by papain, in presence of most of the common antiseptics used in digestion experiments, is very slow judged by the production of tryptophane. In the presence of 0.15 per cent HCN, however, hydrolysis is rapid. This accelerated effect is not limited to the hydrolysis of peptone but is also shown in the digestion of raw and coagulated egg white, fibrin, and edestin, whether the measure of digestion is the appearance of tryptophane, leucine, and tyrosine or the rate of solution of insoluble protein. It was also found that hydrogen sulphide in saturation also produces an acceleration of digestion comparable to that effected by HCN. Brill and Brown (1922) found that dilute sodium chloride showed a slightly activating effect followed by an inhibitory effect in more concentrated solutions. Sodium carbonate, sodium bicarbonate, calcium chloride, and magnesium sulphate had no marked influence, potassium chloride and sodium citrate showed marked activating influence, while acetic acid and lactic acid showed strong inhibitory effects.

The behavior of papain at relatively high temperatures has received considerable attention. Chittenden (1892) noted that in acid solution, papain digested more meat protein at 70°C. than at any lower temperature. According to Delezenne and Mouton (1906) and Pozerski (1909), papain digests proteins of egg white and serum so rapidly at 80 to 90°C. that if a suitable mixture of enzyme and uncoagulated protein faintly acidified is heated to boiling over a flame, scarcely any coagulum is obtained. This rapid digestion by papain at high temperatures was verified by Mendel and Blood (1910). Since at 40°C., a temperature which is generally considered favorable for enzyme action, the proteins are not measurably digested by papain, during short periods of time, the question arises as to the cause of the rapid rate of digestion at the higher temperatures. The rapid rate of digestion by papain at these relatively high temperatures is apparently due to the fact that it is not so easily destroyed by heat as other enzymes and that the acceleration of the rate of action by heat more than compensates for the rate of destruction of the enzyme, so that for short periods under favorable conditions, the rate of digestion may be very high. This assumption is strengthened by the observations of Pratt (1915), who states that at 70°C. the activity of the enzyme in the presence of a large amount of the enzyme is not greatly weakened but that with decreasing percentages of the same, the loss in activity becomes more marked. Finally, Platt found if a papain solution is heated rapidly to 100°C., allowed to boil 5 sec., and immediately cooled, that it loses all its proteolytic activities.

Several methods for the determination of the activity of papain are given here in brief in order to give the student a general idea of the procedure that has been followed in studying this enzyme. Details, however, in this regard may be obtained by consulting the literature that has been mentioned in the preceding discussion. Mendel and Blood (1910) in the study of the digestion of peptone by papain used the following method: 3 cc. of 5 per cent peptone in 1 per cent NaCl were mixed with 3 cc. of 1 per cent papain in 1 per cent NaCl solution. Enough HCN was added to make a 0.15 per cent solution. Chloroform, 0.5 per cent; thymol, 0.5 per cent; sodium fluoride, 1 per cent; or several drops of toluene were also used as antiseptics. The mixture was digested in glass-stoppered bottles at 40°C. for 17 hr. It was tested at the end of the experiment for tryptophane by adding saturated bromine water drop by drop to 2 cc. portions of the digest.

The digestion of uncoagulated egg white by this enzyme was studied after the following manner: To 15 cc. of an egg-white solution prepared by diluting slightly beaten white of egg with three volumes of 1 per cent salt solution and filtering was added 1 cc. of 1 per cent papain solution. This was made up to 30 cc. and antiseptics added after the manner above mentioned and the digestion allowed to proceed at 40° for 17 hr. The undigested protein was precipitated by adding 30 cc. of a 10 per cent solution of trichloroacetic acid and heating for 5 min. in a water bath at 100°C. to coagulate the proteins completely and dissolve any albumoses. The mixture was then filtered while hot through a dried weighed filter paper, washed free from acid with water, and dried to constant weight. The amount of protein in the original mixture of egg white and papain was determined in a blank by the trichloroacetic acid method.

Pratt (1915) prepared a papain solution by dissolving 0.75 g. of powdered papain in 150 cc. of distilled water. Although papain is not completely soluble in water, the active principle is dissolved upon being kept for 30 min. at 40°C. so that upon filtering a clear solution is obtained. Pratt used milk as nearly free from butter fat as possible. Into 150 cc. flasks was measured 25 cc. of milk, and to this was added water, varying from 5 to 25 cc., and sufficient papain solution in each case to make the total addition of water and papain solution 25 cc. After the enzyme solution was added, the contents of the flasks were thoroughly mixed by shaking, after which the flask was placed at 40°C. for 30 min. The flasks were then cooled by ice water until their contents could be examined. The contents of each flask were washed into 500 cc. beakers, sufficient water being used to make the volume up to 75 cc. The undigested protein was precipitated by slowly adding 0.5 cc. of copper sulphate solution followed by 5 cc. of glacial acetic acid, the solution being vigorously stirred during the precipitation. After the precipitate had settled it was collected and washed upon weighed ashless paper and dried to constant weight at 100°C. The weight of protein digested by the papain was calculated by subtracting from similar determinations made on blanks to which no enzyme was added. Duplicate analyses in this manner agreed within 2 per cent. No antiseptic was used for such short periods of incubation.

(b) *Bromelin*.—This tryptic enzyme occurs in large quantities in the juice of the pineapple (*Ananas sativa*) and in other plants of the order *Bromeliaceae*. This enzyme was discovered by V. Marcano of Venezuela, according to a brief note published by Russell (1891) in the *Bulletin of Pharmacy*. Russell suggested the name "bromelin" for the enzyme after the natural order to which the plants containing it belong. This enzyme has been studied almost exclusively in the pineapple and was first scientifically investigated by Chittenden and his pupils (1891, 1894). The juice of the pineapple is acid, the acidity being equal to that

of a solution of hydrochloric acid of about 0.45 per cent. The fresh juice is strongly proteolytic and its protein digesting power is manifest in an acid, neutral, or slightly alkaline medium, but in general it acts most energetically in a neutral medium.

When blood fibrin is warmed at 40°C., or thereabouts, with filtered pineapple juice, the fibrin swells up and then quickly disintegrates and in part dissolves. For studying the proteolytic power of pineapple juice under different conditions, Chittenden used the following procedure. About 100 cc. of filtered pineapple juice was warmed at 40°C. for a given period of time with 10 g. of moist, freshly coagulated egg albumin which had been completely freed from all soluble matter by washing with water. When the period of digestion was completed, the undissolved matter was collected in a weighed filter, washed with water, and dried at 110°C. to a constant weight. By subtracting the weight of the insoluble residue so obtained from the weight of dry albumin, equivalent to the moist albumin used in the experiment, the amount of protein matter converted into the soluble form was ascertained. In this manner, it was found, for example, in one experiment that after 3½ hr. 34.5 per cent of the protein was rendered soluble in the juice of natural acidity and 40 per cent in the juice that had been neutralized. This enzyme produces in digestion proteoses, peptones, tyrosine, and leucine which may be detected by proper means.

The temperature relations of bromelin are interesting. Chittenden (1894) observed that neutral pineapple juice was capable of digesting more protein at 60°C. than under like conditions at 40°C. but that warming the enzyme solution alone at 60°C. for 15 min. diminished the proteolytic power of the enzyme 50 per cent. This suggested that the products of digestion protect the enzyme from the destructive action of high temperatures, since when the neutralized juice is heated to 70 to 80°C. for 15 min. in the absence of digestive products, it is rapidly destroyed. It was observed by Pozerski (1909) that at high temperatures the action of bromelin was very rapid, behaving in this regard similarly to papain, the results being due apparently to the same causes as are mentioned under that topic.

Chittenden (1894) precipitated the enzyme from the juice by saturation with NaCl, MgSO₄, and (NH₄)₂SO₄ and he considered the product obtained from NaCl to be superior to that obtained with the other salts. Effront (1917) states that bromelin may be prepared by adding two volumes of alcohol to the pineapple juice and filtering off the precipitate which contains little or no enzyme. To the filtrate thus obtained, five volumes of 95 per cent ethyl alcohol is added, and the precipitate formed, which contains the enzyme, is collected, dried, and pulverized for use.

Impure preparations of bromelin are strongly autodigestive in either an acid or an alkaline medium, such digestion, according to Caldwell

(1905), beginning when the breaking up of protein impurities has been completed and proceeding to the total destruction of the enzyme. Bromelin, however, when prepared in a relatively pure condition is not at all autodigestive, so that the presence of some protein in the juice is apparently a prerequisite for such action. Caldwell (1905) obtained by the following method a preparation of this enzyme which contained only very slight traces of protein: The dialyzed NaCl precipitate was dissolved in a small amount of water and reprecipitated by the addition of 95 per cent alcohol. This precipitate was again dissolved in water and again precipitated by adding crystals of $(\text{NH}_4)_2\text{SO}_4$. A little of the associated protein was left behind at every precipitation, and five repetitions of the process gave a preparation containing only slight traces of protein. Precipitation was much hastened by placing the solutions at 4°C . After being dried upon the water bath at 40°C ., the preparation was completely soluble in water and was not autodigestive in any medium even after prolonged standing.

(c) *Other Plant Trypsins*.—In 1880 Bouchut discovered a tryptic enzyme in the juice of the stem, leaves, and fruit of the common fig (*Ficus carica*) to which Mussi (1890) gave the name "cradina." Green (1887, 1890, 1892) found enzymes of the trypsin type in the germinating seeds of the lupine and castor bean seedlings and in the Kachree gourd (*Cucumis utilissimus*), while Butkewitsch (1900, 1901) observed tryptic enzymes in the germinating seeds of *Lupinus angustifolius* and *Lupinus luteus*. Vines (1902) found the liquid of the pitchers of *Nepenthes* contained a tryptic enzyme and later (1903) found similar enzymes in the juice of the cucumber and melon and in the bulbs of the tulip and hyacinth. The early observations of vegetable trypsins were, with but few exceptions, in seedlings and storage organs. In 1919 Fisher examined the leaves of numerous plants for the presence of trypsins, using finely powdered legumin as a substrate after the following manner: 10 g. of ground fresh leaves were placed with 3 g. of legumin in 250 cc. of water in a flask with a layer of toluene as an antiseptic. The flasks were tightly corked and placed in an incubator at 37°C . for 3 days. The material was filtered and the residue thoroughly washed with water, until the volume was 400 cc. A 40 cc. portion was then transferred to a flask, decolorized by shaking with alumina cream, filtered, and the residue thoroughly washed. The filtrate was then tested by Sorensen's method to determine the extent of protein hydrolysis as follows: To the filtrate was added 15 cc. of a fresh solution consisting of 50 cc. of commercial formaldehyde, 25 cc. of absolute alcohol, and 10 cc. of a thymol phtalein solution. (The thymol phtalein solution consisted of 0.5 g. of thymol phtalein dissolved in 1,000 cc. of 93 per cent alcohol.) Fifth-normal barium hydroxide was then run in until a distinctly green or blue color was obtained which matched that obtained by similar treatment of the control flask. The results show that the leaves of barley, oats, corn, rye, red clover, alfalfa, vetch, beans, peas, buckwheat, white mustard, and others contain enzymes of the trypsin type that are capable of hydrolyzing legumin. The reaction, however, is relatively slow as compared with the hydrolysis of peptone by the same leaf extract. In 3 days the amount of legumin hydrolyzed by the various leaf materials only amounted to from 1.5 to 9.6 per cent. Enzymes of a tryptic nature thus seem to be widely distributed in plants and plant parts. Their action is apparently relatively slow, but this may be due to the fact that the conditions under which they are placed in the laboratory may not be comparable to the conditions which prevail in the cells in which they normally act.

3. *The Erepsins or Ereptases.*—In 1901 Cohnheim described and gave the name “erepsin” to the enzyme formed in the mucous membrane of the small intestine which actively digests peptone, prolamins, polypeptides, and casein to the amino acids but does not act upon the higher proteins. Vines (1903) obtained evidence that various parts of widely different species of plants contain enzymes which resemble erepsin in their reaction. He based his conclusion on his observation that many plant extracts split off tryptophanes rapidly from peptone but entirely fail to hydrolyze fibrin as indicated by any apparent solution or by the formation of tryptophane. Independently of Vines, Javillier (1903) found that *Lolium perenne* contained among other enzymes one which hydrolyzes peptone into products which no longer give the biuret reaction. It has since been shown that erepsins are almost universally distributed in plants and plant parts. They have been found in the embryo of wheat, in green peas, in the expressed juice of the melon, cucumber, and tomato, in the rind of the apple and orange, in the juice of grape, in the leaves of lettuce, cabbage, spinach, barley, oats, corn, rye, clover, alfalfa, vetch, bean, peas, buckwheat, mustard, in the potato tuber and artichoke, in the onion and bulbs of the hyacinth and tulip, and in the roots of turnip, tomato, carrot, and beet, in the leaves of various seedlings, and in many other plants and plant parts.

The erepsin of cabbage was studied in considerable detail by Blood (1910). She prepared the enzyme after the following manner: The leaves were ground and then pressed and the juice so obtained was dialyzed for 40 hr. against running water, with toluene as an antiseptic. The clear juice obtained by filtering the dialysate was saturated with ammonium sulphate and left in the cold room over night. The precipitate was then washed with saturated ammonium sulphate and dissolved in water. This solution was filtered and the filtrate dialyzed against running water, with toluene for an antiseptic, until free from ammonium sulphate, which required 6 days. A preparation of this type can be kept for a considerable period of time without loss of enzymic action.

In the digestive experiments, Blood followed the following procedure: To 5 cc. of 5 per cent peptone in 1 per cent NaCl solution 5 cc. of the enzyme solution was added and made to a volume of 12 cc. This was then digested in the incubator at 40°C. for 17 hr., using toluene as an antiseptic. To test for digestion 2 cc. portions were removed, acidified with acetic acid when necessary, and treated with bromine water drop by drop until a maximum color was obtained.

The erepsin of cabbage obtained and tested in this manner split tryptophane and tyrosine from commercial peptones, clotted milk, and liquefied gelatin. It did not digest fibrin, edestin, or coagulated egg white in neutral, acid, or alkaline solution and was active over a considerable range of acidity and alkalinity.

5. *The Coagulases of Plants.* *a. The Rennets or Rennins.*—Rennet is an enzyme which when introduced into milk causes coagulation, the milk becoming gelatinous and compact. The formation of this milk clot is due to the alteration of the casein of the milk. Rennet is secreted by the gastric glands of animals and is associated in relatively large amounts with animal pepsin.

The enzyme rennet or rennin is apparently widespread in the plant kingdom and is similar to if not identical with that found in the animal body. Experimental evidence indicates that, in the majority of cases at least, it is always closely associated with proteolytic enzymes. The occurrence of rennet in the plant kingdom was known as early as the sixteenth century. It was at that time known by certain tribes of Lapland and by the peasants of the Alps that the leaves of the bitterwort (*Pinguicula vulgaris*) had the power to curdle milk and was used by them for that purpose. It was also known in England about that time, that the stem and leaves of the yellow bedstraw (*Galium verum*) coagulated milk, and until recently, at least, this plant was used in cheese making in certain parts of England.

When the proteases of plants were discovered, it was found that in many cases they possessed the power of curdling milk. Thus papain, bromelin, the trypsin of the castor bean and the ereptase of cabbage all have this power, which is evidently due to rennins accompanying them. The most extensive studies of plant rennins have been made by Gerber (1907 to 1913) and the student is referred to his works for a detailed study of this enzyme.

Rennin has been found in the juice of the stem, leaves, and fruit of the fig, in the juice of the papaw, in the brown algae, and in the seeds of *Datura stramonium*, *Pisum sativum*, *Lupinus hirsutus*, and others. In some of the seeds, it occurs apparently in the zymogen state. This enzyme was found by Gerber to be present in the *Cruciferae*, in the *Ranunculaceae*, in the *Rubiaceae*, in the *Compositae*, in the *Euphorbiaceae*, and others.

As an example of the methods of isolation and study of this enzyme the work of Lea (1883), who studied the rennin of *Withania coagulans*, may be cited. He found that a 5 per cent NaCl solution at 38°C. gave the best extraction of the enzyme from the seeds. The active principle is soluble in glycerine and can be extracted from the seeds by this means. This enzyme loses its activity if boiled in water for a minute or two. Alcohol precipitates the enzyme from its solution and the precipitate after being washed with alcohol may again be dissolved without losing its coagulating power. When a normal clot is formed by this rennin, the reaction of the clot remains neutral or faintly alkaline. The clot is thus a true one and is not due to the action of acid and resembles in appearance the clot formed by animal rennin.

b. The Pectases.—The enzymes of this group coagulate pectic bodies with the formation generally of gelatinous calcium pectate. The presence of calcium salts is apparently necessary for the action of the pectases and it has been found that pectic gels can be formed in the absence of the enzyme provided the necessary conditions are present.

G. THE FORMATION OF ENZYMES IN PLANTS

Two types of enzymes are distinguished in plants, the classification of these two types being based on the relation of their place of origin to the place of their activity. Most of the enzymes of plants function in the cells in which they are formed and are called "intracellular" or "endocellular enzymes." Some plant parts produce enzymes that function outside the cells that produce them and such enzymes are commonly termed "extracellular enzymes." Enzymes of this type are secreted, for the most part, by specialized cells which have a more or less glandular appearance. The study of the formation of extracellular enzymes in plants has been confined almost entirely to the secretion of extracellular enzymes by insectivorous plants and to the germinating seeds of barley, wheat, corn, and other cereal grains.

The secretion of enzymes by certain cells of insectivorous plants received considerable attention from early investigators who demonstrated that these cells excreted enzymes into the liquid in the "pitchers" of *Nepenthes* and similar plants or to the exterior as in the case of *Drosera* or sundew. They found that these enzymes were secreted and digestion of food brought about only when the secreting cells were stimulated in some way or another. ✓

A discussion of the observations of Hepburn (1918) in his studies of the liquid of *Nepenthes* will suffice to show the general status of our present knowledge concerning the secretion of enzymes by insectivorous plants. He examined the liquid in the pitchers of 14 species and hybrids of *Nepenthes*, always studying it prior to the opening of the pitcher. Through an opening he stimulated the glands of the inner wall of the pitcher by stroking with a camel's-hair brush or by placing several round, solid, glass beads therein and shaking the pitcher at intervals during one or more days. After stimulation by the brush or the insertion of the beads, cotton plugs were inserted in the openings of the pitchers and the liquid removed for study the following day. Hepburn studied especially the action of the proteolytic enzymes secreted by the pitchers and found that the liquid from the stimulated pitchers produced a more rapid digestion than did that from the non-stimulated pitchers. The latter exerted proteolytic action only in the presence of acid and failed to produce this action in its absence. The liquid from the stimulated pitchers exerted proteolytic action in either the presence or the absence of an acid. Hepburn concluded that increased proteolytic activity due to stimulation might be caused by one or more of the following results: (1) by changing the H-ion concentration, thus rendering conditions more favorable for the action of proteases already present; (2) by causing the activation of a zymogen already present; (3) by producing an increased secretion of proteases by the glands of the pitcher. Hepburn

showed conclusively that the liquid taken from the young unopened pitchers was sterile and that the proteolytic action of the liquid is due to a protease and not to bacterial action.

In order to discuss the secretion of enzymes by the germinating seeds of the *Gramineae*, it is necessary to have a knowledge of the arrangement and structure of the various seed parts. The structure of the barley grain has been described in detail by Brown and Morris (1890), and that of the corn to some extent by Torrey (1902) and Sargent and Robertson (1905). The general structure of the seeds of the grains and grasses is approximately the same, so that the structure of the corn grain to be herein considered may be taken as representative of this group of seeds.

In Fig. 31 it is seen that a grain of corn consists of an endosperm and embryo surrounded by several coats and the pericarp. The endosperm occupies the greater portion of the seed and partly surrounds the embryo. The endosperm consists for the most part of large cells filled with starch grains, part of which are embedded in a matrix of protein matter. Just beneath the coats of the grain and completely encircling the outer part of the endosperm is a layer of columnar cells filled with protein and termed the "aleurone layer." The embryo is on the furrowed, flattened side of the grain. It is thickest at the end attached to the cob and gradually slopes to a point reached at about three-fourths to four-fifths the length




Fig. 31.—Longitudinal section of a corn grain. *end*, endosperm. *sc*, scutellum. *p*, pericarp. *al*, aleurone layer. *ep*, epithelial layer. *as*, air space. *cl*, coleoptile. *pl*, plumule. *mc*, mesocotyl. *sr*, initials of secondary roots. *r*, radicle. *rc*, root cap. *cr*, coleorhiza. *a*, point of attachment to cob.

of the grain. The embryo consists of the young plant and the scutellum. The young plant or plantlet consists of the plumule and radicle with the connecting hypocotyl. The scutellum is a shield like expansion of the hypocotyl and makes up the greater part of the bulk of the embryo. It is considered by some to be the homologue of the cotyledon and serves as a

special organ for absorbing the food from the endosperm and transferring it to the developing plantlet.

The surface of the scutellum which is in contact with the endosperm consists of a layer of columnar cells which is termed the "epidermal" or "epithelial layer" of the scutellum. In the case of corn, this epithelial layer dips down at regular intervals into the endosperm, thus producing




FIG. 32.—Section through the scutellum, epithelial layer, and endosperm of the corn grain. *s*, scutellum. *epc*, epithelial cells. *c*, flattened cells of the endosperm. *sc*, starch cells of the endosperm.

a greater surface for secretion. These convolutions of the epithelial layer, however, are not present in most of the other members of the grain family (Sargent and Robertson, 1905). These epithelial cells are about three times as long as broad and have one end resting on the scutellar parenchyma and the other in close contact with the endosperm. The protoplasmic contents of the epithelial cells stand in marked contrast to those of the other cells of the scutellum in being finely granulated, semitransparent, and possessing prominent nuclei (Fig. 32).

Within a few hours after the seeds of barley, corn, or other grains are moistened and placed under favorable conditions for germination, the protoplasm of the epithelial cells undergoes marked changes, becoming much coarser in structure, the granulations increasing in size and number and clouding the cell contents so that the nucleus which is conspicuous in the resting stage of the seed cannot readily be observed. This cloudiness reaches its maximum in from 24 to 36 hr. and shows little change in most cases until the endosperm is depleted, after which the cells again become hyaline. In the case of the date seed, however, the epithelial cells clear long before the endosperm is digested (Reed, 1904). The epithelial cells also greatly enlarge at the beginning of germination, so that between the first and third day in the germination of corn they enlarge to three to four times their original size. Soon after the above-mentioned activities appear in the epithelial layer, the cell walls of the cells of the endosperm nearest to the scutellum begin to dissolve and the starch grains therein show evidence of pitting, while temporary starch appears as grains in the parenchymatous tissue of the scutellum bordering upon the epithelial cells.

All investigators are agreed that the epithelial cells are capable of forming *cytase*, *diastase*, and probably *proteases* which are excreted into the adjoining endosperm.

The cytological changes which occur in the cells of the epithelial layer during the formation of enzymes have been studied by Torrey (1902), and Reed (1904). Torrey considered that the nucleus is the seat of this enzyme formation. He noted in the case of corn that at the beginning of germination the nuclei contained dark, staining granules which exuded into the cytoplasm and finally collected at the wall next to the endosperm where they disappeared. Immediately after this dissolution, the first activity of enzymes is noted in the cell walls and starch grains of the endosperm. Torrey thus considered these accumulations at the base of the epithelial cells to be deposits of actual enzyme substance. Reed (1904), however, was unable to confirm the observations of Torrey relative to the extrusion of solid matter from the nucleus but noted that the chromatin of the nuclei increased as germination progressed while the nucleoli diminished in size. In this connection the statements of Horning and Petrie (1927) in regard to the function of mitochondria as mentioned in Chap. I should again be mentioned. They considered that the mitochondria of the epithelial cells migrate into the endosperm, carrying on their surfaces the enzymes which act upon the food reserves contained therein.

The function of the aleurone layer has also received considerable attention (Fig. 33). Beyerinck (1895) considered that this layer secreted maltase; Green (1899), Haberlandt (1890), and Brown and Escombe (1898) concluded that it secreted *cytase* in the case of barley; while

Puriewitsch (1897) and Linz (1896) came to the opposite conclusion. There is much evidence, however, that the aleurone layer has no enzymic secretory powers. The cells which compose it are relatively thick walled and undergo apparently little change in their contents until the endosperm is entirely depleted. No erosion of the starch grains or dissolution of the cell walls occurs next to the aleurone layer except as these changes move out from the scutellum. From thousands of observations on barley grains, Mann and Harlan (1915) concluded that the aleurone layer of that seed exercises no secretory power at all during germination. They consider that all the enzymes formed in the seed during germination are secreted by the epithelial layer. They considered that the aleurone layer may act as a protective layer to the endosperm and embryo and that the nitrogenous material in these cells might serve as a supply of nitrogen for the young plant after it had full power to manufacture its own carbohydrates. The origin of the aleurone layer has been investigated by Jodidi and Peklo (1929) and should be mentioned here in a discussion of its function. From certain cytological and biochemical observations they concluded that symbiotic fungi produce the aleurone layer in the case of English rye grass, wheat, and barley. This is an entirely new line of thought and should be investigated further.

Although all investigators have agreed that the epithelial cells of the scutellum secrete enzymes, there has been much dispute as to the extent to which these cells supply the enzymes concerned in the digestion of the reserves in the endosperm.

It has been found that embryos of many of the *Gramineae* can be grafted onto other endosperms or placed in contact with starch preparations and still develop and function normally by digesting and absorbing their food from the substratum upon which they are placed. On this account and from certain observations on the behavior of endosperms, Brown and Morris (1890), Brown and Escombe (1898), and Pond (1906) conclude that the endosperm has no power at all of self-digestion. On




FIG. 33.—Section through the outer portion of a grain of corn. *pc*, pericarp. *i*, integuments. *al*, aleurone layer. *c*, flattened cells containing some protein. *sc*, starch cells containing mostly starch but also some protein.

the other hand, Krabbe (1890), Grüss (1893 to 1897), Hansteen (1894), Puriewitsch (1897), Paton, Nanji, and Ling (1924), and others have reported observations which contradict these conclusions. The work of Bruschi (1908) showed the cause for the contradictory results that had been obtained in this regard. He found that the starchy endosperm of corn, barley, wheat, and rye can digest itself in the absence of the scutellum though to a very different degree. The vitality of the endosperm cells of various species and varieties differs greatly, so that the enzymic action that would be developed will vary greatly. If an investigator worked with a set of seeds in which the vitality was very low, he would naturally observe little or no digestion of the endosperm. If he happened to study a variety in which the vitality of the endosperm cells remained high, he would observe considerable self-digestion. Bruschi found that some digestion may occur in endosperms that have lost all their vitality. This is apparently due to the fact that the cells contain proenzymes or zymogens which exist after the death of the cells and can form active enzymes after soaking in water at ordinary temperatures.

The effect of the water content and temperature upon the secretion of diastase in the barley grain was studied by Pickler (1919). The grains were placed under certain conditions of temperature and humidity until the absorption of water had reached an equilibrium. A certain portion of each grain sample was then taken, dried and pulverized to a powder, and the action of each sample of powder on a 0.2 per cent solution of starch paste noted. It was found that the temperature changes made little difference in the rate of secretion of the enzyme but that the changes in water content exerted a marked effect. This may be illustrated by the following concrete example: At 10°C. the water content of two samples of seed was 11 and 29.9 per cent, respectively. The former had a diastatic activity of 36.25, while the latter had an activity of 24.25. That is, it required 36.25 hr. for a diastase sample from the seed with a water content of 11 per cent to digest a given amount of starch paste, while it required only 24.25 hr. for a diastase sample from the seed with a water content of 29.9 per cent to digest the same amount of starch paste. At 20°C. with water contents of 11.5 and 30.9 per cent, respectively, the diastatic activities were 36.5 and 23.1. These results show that the water content is a very important factor in determining the rate of formation of diastase by the scutellum of the barley grain.

IV. A COMPARISON OF DIGESTION IN PLANTS AND ANIMALS

The process of digestion in plants and animals is similar in that, for the most part, plants digest the same foods as animals. These foods are digested by similar enzymes and the products of digestion are the same. As a general rule, the process of digestion in animals is more rapid than in plants.

The process of digestion in plants is different from that in animals primarily in regard to its location. In the higher animals digestion occurs in certain definite specialized organs, while in plants, with but few exceptions, it does not occur in any special organs but may take place in any part of the plant body.

Digestion in plants is, for the most part, intracellular, occurring within the cells which produce the enzymes that act upon the food contained therein. The only exceptions are the digestion of some food by insectivorous plants and of the reserve foods in the endosperms of the *Gramineae* and date seed by the enzymes secreted by the epithelial cells of the scutellum and the absorbing portions of the date embryo.

Digestion in animals occurs in practically all cases outside the cells and is termed "extracellular digestion." Thus in the higher animals digestion occurs in the alimentary tract and is brought about by enzymes excreted therein by cells bordering upon it or by special glands connected with it. Also, in the case of unicellular animals as the amoebae, which simply wrap themselves around food particles and digest them, the digestive process is really an extracellular one.

Questions

519. What is a food? What are the plant sources of animal foods? Name the seeds and grains, roots, stems, and leaves that furnish the greater portion of the food for animals.

520. Explain the value to the plant of the foods stored in seeds. Explain the value to the plant of the foods stored in the stem, in the roots, and in the leaves. How are plants and animals alike in regard to the foods they need? How do they differ from each other in regard to the food proposition?

521. In what form are the foods of plants stored in them? Of what advantage is this? What change must insoluble food undergo before it can be utilized by the plant? Why?

522. What is digestion? Give examples. How is the process brought about? Into what two groups may chemical reactions be placed in regard to their speed of completion? Give examples.

523. What is a catalyst? Name three of the general properties of catalysts. What is an enzyme? State some of the general physical properties of enzymes. What is known concerning their composition? What is the optimum temperature for enzyme action? The maximum temperature? How do they behave at the lower temperatures?

524. What properties do enzymes have in common with all catalysts? How do they differ from catalysts in their action? What two theories of enzyme action have been proposed? What three facts suggest that there is a combination between the enzyme and the substrate? Discuss the two general theories in regard to the nature of this supposed combination of enzyme and substrate.

525. What is the substrate? An accelerator or activator? Name some substances that are accelerators to enzyme action. What is an inhibitor or paralyzer? Give examples. What is a coenzyme? Antienzyme?

526. What is a proenzyme or zymogen? A kinase? Give examples. How did the term "enzyme" come into general use? Why are enzymes said to be specific in their action? How are enzymes named? What exceptions are there to this rule?

- 527.** Classify the enzymes that function in the process of digestion in plants.
- 528.** Give some examples to show the widespread occurrence of enzymes in plants and plant parts. Give some examples to illustrate the longevity of enzymes.
- 529.** What is invertase? By what other names is it called? In what plants and plant parts has it been detected? For what is invertase used in the industries?
- 530.** Give in detail the method used in the preparation of invertase from yeast. What are the chemical reactions of the invertase obtained after this manner?
- 531.** Describe the method used in the preparation of invertase from the tissues of green plants. Give examples to show that the method of preparation may influence the physical properties of invertase. Describe the general method used for the study of the quantitative action of invertase. For the qualitative action.
- 532.** Why has the nature of the action of invertase been so extensively studied? How does the action of invertase on cane sugar differ from that of dilute mineral acids?
- 533.** What is the relation of the velocity of inversion of cane sugar by invertase to the concentration of the enzyme? To the concentration of the sugar solution? What reaction does the invert sugar which has been formed by invertase have upon the velocity of the reaction? Why?
- 534.** How is the activity of invertase affected by adsorption compounds? What is known concerning the reversibility of invertase action? How does alcohol affect the activity of invertase? Give data to show that cane sugar in alcohol has a protective action on this enzyme.
- 535.** How is the activity of invertase affected by dilution with water? With weak acids? With a cane-sugar solution? Give an example to show that the activity of invertase preparations may show a spontaneous increase. What might be the cause of this?
- 536.** Discuss in detail the influence of the acidity or alkalinity of the medium upon the activity of invertase. What is the optimum temperature for the action of this enzyme? The maximum temperature? How does the presence of cane sugar affect the maximum temperature? How does the amount of moisture present affect the maximum temperature? How does tannin affect the solubility of invertase?
- 537.** What is diastase? What evidence is there that the ordinary diastase preparation is not a single enzyme? Why has this enzyme been so extensively studied? What is taka diastase?
- 538.** What is "diastase of secretion"? "Diastase of translocation"? Where do each occur? What are the main distinctions between these two types?
- 539.** How is the rapidity of starch digestion influenced by the kind of starch? How do the diastase preparations from plant and animal sources compare in regard to their chemical reactions? In regard to their speed of digestion? How do these two types of enzymes compare in stability?
- 540.** Describe in detail the method used for the preparation of diastase from germinating grain. In this method of preparation when does the greatest loss of diastatic power of the enzyme occur? Why? How may this loss of power be lessened?
- 541.** Describe a method for the preparation of diastase from leaves or other plant parts. How is the activity of diastase affected by adsorption compounds? Give examples.
- 542.** What two methods have been used to determine the activity of diastase? Why may these two methods give different results? Describe fully the method used in preparing starch for a substrate for diastatic activity. What is soluble starch?
- 543.** Describe in detail the manner in which the degree of diastatic activity may be estimated quantitatively or qualitatively by means of Fehling's solution. By means of the iodine method.

544. Name three general factors that must be considered in a study of the influence of the medium upon diastatic activity. How does tannin affect diastatic activity? Mineral acids? Neutral salts? Amino acids?

545. Upon what factors will the optimum H-ion concentration for diastase depend? How does the optimum P_H value vary for different diastases? What relationship is there between the isoelectric point of diastase and the optimum P_H value for the activity of this enzyme?

546. How does the optimum P_H value for sugar formation by diastase compare with the optimum P_H value for the disappearance of starch? Upon what three factors will the influence of temperature on diastatic activity depend? How is the diastase preparations from different sources influenced by temperature? How does the temperature coefficient of sugar formation by diastase differ from that of the disappearance of starch?

547. How is the activity of diastase influenced by light? How does polarized light affect the action of diastase? What is inulase? Where does it occur? Under what conditions does it show the greatest activity?

548. What is maltase or glucase? Where does it occur in plants? How is maltase different from most carbohydrases in regard to (a) temperature, (b) precipitation by alcohol, (c) ease of extraction, and (d) reaction toward antiseptics?

549. What are cellulases or cytases? From what plant sources have they been studied? What substrates have been used? What effect have these enzymes upon these substrates? How rapid is their reaction? What is melibiase? Gentianase? Pectinase?

550. What are glucosides? What constituents may combine with sugar to form glucosides? Name some glucosides and state the plant or portion of the plant in which they occur.

551. What is emulsin? Enumerate the glucosides that it will hydrolyze. What is phytase? Rhamnose? Myrosin?

552. What are lipases or esterases? Where have they been demonstrated in plant tissues? What is known concerning the solubility and stability of the lipase zymogen? Describe the method used by Haley and Lyman for the preparation of lipase from the castor bean.

553. What two fat-splitting enzymes have been separated from the ordinary lipase preparation? How have they been separated? How do they differ in their fat-splitting power? What names have been applied to these two enzymes?

554. Describe in detail a method that may be used in studying the action of lipase. How do acids affect the lipase zymogen? The enzyme lipase? Give data in that regard.

555. What is the optimum P_H value for lipase activity? Why does manganous sulphate increase the activity of lipase? How is the activity of lipase affected by alcohol, glucose, glycerol, chlorides, and nitrates?

556. What is known concerning the reversible action of lipase upon its substrate? What is the temperature range for plant lipase activity? How does the degree of emulsification, the amount of water, or the addition of petroleum ether facilitate the hydrolytic action of lipase?

557. What are the proteases? Why are they more difficult to study than the carbohydrate enzymes? By what means has the action of proteases been determined? What information was gained in regard to proteolytic enzymes during the period 1874 to 1900? What are the three main groups of proteolytic enzymes?

558. What is pepsin or peptase? Where has this enzyme been observed? Give the method used in its preparation.

559. What are the trypsin or tryptases? What is papain? Give something concerning the history of this enzyme. What evidence is there that it is a mixture of two proteases?

560. What is the reaction of papain to its substrate at temperatures from 80 to 90°C? Why? What proof is there for your statement? Describe a method for determining the action of papain upon peptone. Upon uncoagulated egg white. Upon milk.

561. What is bromelin? Why so called? How may this enzyme be prepared? How may its action be measured? How does this enzyme react at higher temperatures? Make a statement concerning the autodigestive properties of bromelin. How may this action be overcome?

562. What is "cradina"? Describe Fisher's method for determining the presence of trypsin in leaves. In what leaves has trypsin been detected?

563. What are erepsins or ereptases? Name the plants and plant parts in which erepsins have been detected. Describe Blood's method for the preparation of erepsin and the procedure to be followed to determine its activity.

564. Discuss the occurrence of rennet in the plant kingdom. With what is it frequently associated? Describe a method that may be used for the isolation and study of plant rennets. What are pectases?

565. Distinguish between intracellular or endocellular enzymes and extracellular enzymes. Which type predominates in plants? What plants or plant parts secrete extracellular enzymes?

566. Describe the methods used in obtaining a secretion of proteolytic enzymes from *Nepenthes*.

567. Diagram a longitudinal section of a corn grain to show its various parts. What is the scutellum? The epithelial layer? Describe in detail the cells of the epithelial layer. What general changes do these epithelial cells undergo during germination? What cytological changes do they undergo?

568. What is the aleurone layer? What evidence is there in regard to its secretory powers? How long does this layer remain intact during germination? What function does it seem to subservise?

569. Why is the endosperm of the cereals capable in some cases and incapable in others of self-digestion? How does the water content affect the secretion of diastase by the barley grain?

570. How is the process of digestion in plants different from animals? How is it similar to this process in animals?

Bibliography

- AMBARD, L., E. PELBOIS, and M. BRICKA, 1920: Similitude de l'hydrolyse du sucre par les acides et de l'hydrolyse de l'amidon par l'amylase. Étude de certaines réactions mono moléculaire, *Bull. Soc. Chim. Biol.*, **2**: 42-63.
- , 1920, 1921: Fixation de l'amylase par l'amidon cru et l'empois d'amidon, *Compt. Rend. Soc. Biol.*, **83**: 1458-1460; **84**: 230-232.
- , 1921: Sur l'amylase. Son dosage, mécanisme de la digestion amylolytique, *Bull. Soc. Chim. Biol.*, **3**: 51-65.
- , 1923: De l'amylase. Liaison du ferment et des substances qu'il digère, *Bull. Soc. Chim. Biol.*, **5**: 693-716.
- APPLEMAN, C. O., 1911: Physiological behavior of enzymes and carbohydrate transformations in after-ripening of the potato tuber, *Bot. Gaz.*, **52**: 306-315.
- ARMSTRONG, H. E., 1905: Studies on enzyme action. Lipase, *Proc. Roy. Soc.*, **B**, **76**: 606-608.
- , and E. ORMEROD, 1906: Studies on enzyme action. Lipase II, *Proc. Roy. Soc.*, **B**, **78**: 376-385.
- , E. F. ARMSTRONG, and E. HORTON, 1908: Studies on enzyme action. XII, The enzymes of emulsin, *Proc. Roy. Soc.*, **B**, **80**: 321-331.

- ARMSTRONG, H. E., and H. W. GOSNEY, 1913: Studies on enzyme action. Lipase III, *Proc. Roy. Soc., B*, **86**: 586-600.
- , and ———, 1915: Studies on enzyme action. Lipase IV, The correlation of synthetic and hydrolytic activity, *Proc. Roy. Soc., B*, **89**: 176-189.
- BAILEY, E. M., 1912: Biochemical and bacteriological studies on the banana, *Jour. Amer. Chem. Soc.*, **34**: 1706-1730.
- BAKER, J. L. and H. F. E. HULTON, 1921: Amylases of the cereal grains. Rye, *Jour. Chem. Soc., London*, **119**: 805-809.
- BALY, E. C. C., and E. S. SEMMENS, 1924: The selective photochemical action of polarised light, *Proc. Roy. Soc., B*, **97**: 250-253.
- and ———, 1925: Selective action of polarized light upon starch grains, *Nature*, **116**: 817.
- BARANETZKY, J., 1878: "Die stärkebildenden Fermente in den Pflanzen," Felix, Leipzig.
- BARENDRECHT, H. P., 1913: Enzyme-action, facts and theory, *Biochem. Jour.*, **7**: 549-561.
- BARTHOLOMEW, E. T., 1914: Concerning the presence of diastase in certain red algae, *Bot. Gaz.*, **57**: 136-147.
- BARTON, A. W., 1920: The lipolytic activity of the castor and soybean, *Jour. Amer. Chem. Soc.*, **42**: 620-632.
- BAYLISS, W. M., 1925: "The Nature of Enzyme Action," mon., pp. 200, Longmans, Green and Co.
- BERCZELLER, L., and J. FREUD, 1922: Über die Wirkung der Halogene auf Diastasen, *Biochem. Zeits.*, **139**: 476-481.
- BEYERINCK, M. W., 1895: Ueber Nachweis und Verbreitung der Glukase, das Enzym der Maltose, *Centrabl. f. Bakt. und Parasitenkunde*, II, **1**: 221-229, 265-271, 329-342.
- BLAGOWESTSCHENSKI, A., 1926: Über die synthetische Wirkung der pflanzlichen Proteasen, *Biochem. Zeits.*, **168**: 1-6.
- BLOOD, ALICE, 1910: The crepsin of the cabbage, *Jour. Biol. Chem.*, **8**: 215-225.
- BOUCHUT, E., 1880: Sur un ferment digestif contenu dans le suc de figuier, *Compt. Rend. Acad. Sci. Paris*, **91**: 67-68.
- BOURQUELOT, E., 1893: Inulose et fermentation alcoolique indirecte de l'inuline, *Compt. Rend. Soc. Biol.*, **5**: 481-483.
- , 1893: Inulase et fermentation alcoolique indirecte de l'inuline, *Compt. Rend. Acad. Sci. Paris*, **116**: 1143-1145.
- , 1893: Remarques sur les ferments solubles sécrétés par l'*Aspergillus niger* et le *Penicillium glaucum*, *Compt. Rend. Soc. Biol.*, **5**: 653-654.
- , 1903: Généralités sur les ferments solubles qui déterminent l'hydrolyse des polysaccharides, *Compt. Rend. Acad. Sci. Paris*, **136**: 762-764.
- BRASSE, L., 1884: Sur la présence de l'amylase dans les feuilles, *Compt. Rend. Acad. Sci. Paris*, **99**: 878-879.
- , 1885: Action de la diastase du malt sur l'amidon cru, *Compt. Rend. Acad. Sci. Paris*, **100**: 454-456.
- BRAUN, K., and E. BEHRENDT, 1903: Beitrag zur fermentative Spaltung der Fette, *Ber. d. d. chem. Ges.*, **36**: 1142-1145, 1900-1911.
- BRILL, H. C., and R. E. BROWN, 1922: The digestive properties of Philippine papain, *Philippine Jour. Sci.*, **20**: 185-191.
- BROWN, H. T., and JOHN HERON, 1879: Contributions to the history of starch and its transformations, *Jour. Chem. Soc. London*, **35**: 596-654.
- and G. H. MORRIS, 1890: Researches on the germination of some of the Gramineae, *Jour. Chem. Soc. London*, **57**: 458-528.

- BROWN, H. T., and JOHN HERON, 1893: A contribution to the chemistry and physiology of foliage leaves, *Jour. Chem. Soc. London*, **63**: 604-677.
- and F. ESCOMBE, 1898: On the depletion of the endosperm of *Hordeum vulgare* during germination, *Proc. Roy. Soc.*, **63**: 3-25.
- BRUSCHI, D., 1908: Researches on the vitality and self digestion of the endosperm of some *Graminaceae*, *Ann. Bot.*, **22**: 449-463.
- BUTKEWITSCH, W., 1900: Ueber das Vorkommen proteolytischer Enzyme in gekeimten Samen und über ihre Wirkung, *Ber. d. d. bot. Ges.*, **18**: 185-189.
- , 1901: Über das Vorkommen eines proteolytischen Enzyms in gekeimten Samen und über seine Wirkung, *Zeits. f. physiol. Chem.*, **32**: 1-53.
- , 1908: Zur Frage über die Umwandlung der Stärke in den Pflanzen und über den Nachweis der amylolytischen Enzyme, *Biochem. Zeits.*, **10**: 314-344.
- CALDWELL, J. S., 1905: The effect of toxic agents upon the action of bromelin, *Bot. Gaz.*, **39**: 409-419.
- CHITTENDEN, R. H., E. P. JOSLIN, and F. S. MEARA, 1891: On the ferments contained in the juice of the pineapple together with some observations on the composition and proteolytic action of the juice, *Trans. Conn. Acad. Arts and Sci.*, **8**: 283-308.
- , 1892: Papoid-digestion, *Trans. Conn. Acad. Arts and Sci.*, **9**: 297-332.
- , 1894: The proteolytic action of bromelin—the ferment of pineapple juice, *Jour. Physiol.*, **15**: 249-310.
- , L. B. MENDEL, and H. E. McDERMOTT, 1898: Papain proteolysis with some observations on the physiological action of the products formed, *Amer. Jour. Physiol.*, **1**: 256-276.
- CHRZASZCZ, T., 1923: Einfluss der Temperatur auf die Wirkung der Amylase. Die Wirkung der verzuckernden Kraft der Amylase, *Biochem. Zeits.*, **142**: 417-439.
- , Z. BIDZINSKI, and A. KRAUSE, 1925: Über den Einfluss der Wasserstoffionkonzentration auf die Dextrinierung der Stärke durch gereinigte Malzamyase, *Biochem. Zeits.*, **160**: 155-171.
- COHNHEIM, OTTO, 1901: Die Umwandlung des Eiweiss durch die Darmwand, *Zeits. f. physiol. Chem.*, **33**: 451-465.
- COLIN, M. H., 1915: Sur la distribution de l'invertine dans les tissus de la Betterave, aux différentes époques de la végétation, *Compt. Rend. Acad. Sci. Paris*, **160**: 777-779.
- COMPTON, ARTHUR, 1921: Studies in the mechanism of enzyme action. I, Role of the reaction of the medium in fixing the optimum temperature of a ferment, *Proc. Roy. Soc.*, B, **92**: 1-6.
- CONNSTEIN, W., E. HOYER, and H. WARTENBERG, 1902: Ueber fermentative Fettspaltung, *Ber. d. d. chem. Ges.*, **35**: 3988-4007.
- CUISINIER, L., 1885: Une nouvelle matière sucrée diastasique la Céréalose et pour sa fabrication, *French Patent* 171958, Oct. 30.
- CZAPEK, F., 1903: Antifermente im Pflanzenorganismus, *Ber. d. d. bot. Ges.*, **21**: 229-242.
- , 1905: The anti-ferment reaction in tropistic movements of plants, *Ann. Bot.*, **19**: 75-98.
- DAISH, A. J., 1916: The distribution of maltase in plants. II, The presence of maltase in foliage leaves, *Biochem. Jour.*, **10**: 49-55.
- , 1916: The distribution of maltase in plants. III, The presence of maltase in germinated barley, *Biochem. Jour.*, **10**: 56-76.
- DAVIS, A. R., 1915: Enzyme action in the marine algae, *Ann. Mo. Bot. Garden*, **2**: 771-836.
- DAVIS, W. A., 1916: The distribution of maltase in plants. I, The function of maltase in starch degradation and its influence on the amyloclastic activity of plant materials, *Biochem. Jour.*, **30**: 31-48.

- DEAN, A. L., 1903: Experimental studies on inulase, *Bot. Gaz.*, **35**: 24-35.
- , 1905: On proteolytic enzymes. I, *Bot. Gaz.*, **39**: 321-339.
- , 1905: On proteolytic enzymes. II, *Bot. Gaz.*, **40**: 121-134.
- DELEZENNE, C., H. MOUTON, and E. POZERSKI, 1906: Sur la digestion brusque de l'ovalbumine et du sérum sanguin par la papaine, *Compt. Rend. Soc. Biol.*, **60**: 309-312.
- and ———, 1906: Sur l'allure anormale de quelques protéolyses produites par la papaine, *Compt. Rend. Soc. Biol.*, **60**: 68-70.
- DOBY, P., 1915: Über Pflanzenzymen. IV, Die Invertase der Kartoffelblätter, *Biochem. Zeits.*, **71**: 495-500.
- DUGGAR, B. M., and A. R. DAVIS, 1914: Enzyme action in *Fucus vesiculosus*, *Ann. Mo. Bot. Gard.*, **1**: 419-426.
- EFFRONT, J., 1905: Sur le développement de l'amylase pendant la germination des graines, *Compt. Rend. Acad. Sci. Paris*, **141**: 626-628.
- , 1917: "Biochemical Catalysts in Life and Industry. Proteolytic Enzymes," Eng. trans. by S. C. Prescott, John Wiley & Sons, Inc.
- , 1922: Sur les propriétés distinctives des amylases de différentes provenances, *Compt. Rend. Acad. Sci. Paris*, **174**: 18-21.
- EMMERLING, O., 1902: Ueber die Eiweisspaltung durch Papayotin, *Ber. d. d. chem. Ges.*, **35**: 695-700.
- FALES, H. A., and J. M. NELSON, 1915: The effect of sodium chloride upon the action of invertase, *Jour. Amer. Chem. Soc.*, **37**: 2769-2786.
- FALK, K. G., and J. M. NELSON, 1912: Studies on enzyme action. I, Some experiments with the castor bean lipase, *Jour. Amer. Chem. Soc.*, **34**: 735-745.
- and ———, 1912: Studies on enzyme action. II, The hydrolytic action of some amino acids and polypeptides of certain esters, *Jour. Amer. Chem. Soc.*, **34**: 828-845.
- and M. L. HAMLIN, 1913: Studies on enzyme action. III, The action of manganous sulfate on castor bean lipase, *Jour. Amer. Chem. Soc.*, **35**: 210-219.
- , 1913: Studies on enzyme action. V, The action of neutral salts on the activity of castor bean lipase, *Jour. Amer. Chem. Soc.*, **35**: 601-616.
- , 1913: Studies on enzyme action. VI, The specificity of lipase action, *Jour. Amer. Chem. Soc.*, **35**: 616-624.
- , 1913: Studies on enzyme action. IX, Extraction experiments with the castor bean lipase, *Jour. Amer. Chem. Soc.*, **35**: 1904-1915.
- and K. SUGIURA, 1915: Studies on enzyme action. XII, The esterase and lipase of castor beans, *Jour. Amer. Chem. Soc.*, **37**: 217-230.
- , 1915: Studies on enzyme action. XIII, The lipase of soybeans, *Jour. Amer. Chem. Soc.*, **37**: 649-653.
- , 1917: Studies on enzyme action. XIV, Further experiments on lipolytic actions, *Jour. Biol. Chem.*, **31**: 97-123.
- , G. MCGUIRE and E. BLOUT, 1919: Studies on enzyme action. XVII, The oxidase, peroxidase, catalase, and amylase of fresh and dehydrated vegetables, *Jour. Biol. Chem.*, **38**: 229-244.
- and ———, 1921: Studies on enzyme action. XIX, The sucrolytic actions of bananas, *Jour. Gen. Physiol.*, **3**: 595-611.
- and ———, 1922: Studies on enzyme action. XXI, Banana gel and banana sucrose, *Jour. Biol. Chem.*, **54**: 655-671.
- FEIST, K., 1908: Die Spaltung des Amygdalin unter den Einfluss von Emulsin, *Archiv. d. Pharm.*, **246**: 206, 509.
- FERMI, C., and DR. BUSCALIONI, 1899: Die proteolytischen Enzyme im Pflanzenreiche, *Centrbl. Bakt.*, II, **5**: 24-27, 63-67, 91-95, 125-135, 146-158.

- FERNBACH, A., and L. HUBERT, 1900: Sur la diastase proteolytique du malt, *Compt. Rend. Acad. Sci. Paris*, **130**: 1783-1785.
- FISHER, E. A., 1919: Contributions to the study of the vegetable proteases. I, Introductory, *Biochem. Jour.*, **13**: 124-134.
- FRANKEL, E. M., 1917: Studies on enzym action. XV, Factors influencing the proteolytic activity of papain, *Jour. Biol. Chem.*, **31**: 201-215.
- GARDINER, W., 1897: The histology of the cell wall with special reference to the mode of connection of cells, *Proc. Roy. Soc.*, **62**: 100-112.
- GERBER, C., 1907: Action du phosphate neutre de sodium sur la coagulation du lait de vache par les présures végétales, *Compt. Rend. Soc. Biol.*, **63**: 640-642.
- , 1907: Action du phosphate neutre de potassium sur la coagulation du lait de vache par les présures végétales, *Compt. Rend. Soc. Biol.*, **63**: 642-644.
- , 1907: La présure des *Crucifères*, *Compt. Rend. Soc. Biol.*, **62**: 1223-1225.
- , 1907: La présure des *Crucifères*, *Compt. Rend. Acad. Sci. Paris*, **145**: 92-94.
- , 1907: La présure des *Rubiaceés*, *Compt. Rend. Acad. Sci. Paris*, **145**: 284-286.
- , 1907: Les agents de la coagulation du lait contenus dans le suc du Mûrier de Chine (*Broussonetia papyrifera*), *Compt. Rend. Acad. Sci. Paris*, **145**: 530-532.
- , 1908: Action des acides sur la coagulation du lait par les présures végétales, *Compt. Rend. Acad. Sci. Paris*, **146**: 1111-1114.
- , 1909: La présure du papayer.—Son action sur le lait bouilli aux diverses températures, *Compt. Rend. Soc. Biol.*, **66**: 227-229.
- , 1908: Suc présurants des *Renonculacées*, *Compt. Rend. Soc. Biol.*, **64**: 522-523.
- , 1909: Action comparée des présures végétales sur la peptone et la caséine. I, Type *Composées*. II, Algues brunes, *Compt. Rend. Soc. Biol.*, **66**: 1122-1125, 1125-1127.
- , 1909: Activité présurante des divers organes des *Composées*, *Compt. Rend. Congr. Soc. Sav. Rennes*, **1909**: 152-155.
- , 1909: Coagulation du lait cru par la présure du Papayer (*Carica papaya*), *Compt. Rend. Acad. Sci. Paris*, **148**: 497-500.
- , 1909: Methode générale de préparation des présures végétales, *Compt. Rend. Soc. Biol. Paris*, **66**: 890-892.
- , 1909: Relations entre les ferments présurants et les ferments proteolytiques végétaux. Leur rôle dans la plante, *Compt. Rend. Soc. Biol. Paris*, **67**: 332-334.
- , 1909: Répartition de la présure dans les membres et tissus végétaux, *Compt. Rend. Acad. Sci. Paris*, **148**: 992-994.
- , 1912: Action des sels neutres sur la caséification du lait par la présure du latex des *Euphorbes*, *Compt. Rend. Soc. Biol.*, **73**: 582-584.
- , 1912: Relations entre l'activité présurante du latex du *Euphorbes* et l'espèce considérée ou la partie du végétal considérée. Résistance de cette présure à la chaleur, *Compt. Rend. Soc. Biol.*, **73**: 578-580.
- GLIMM, E., and W. SOMMER, 1927: Beitrag zur Reinigung der Malzamylose, *Biochem. Zeits.*, **188**: 290-325.
- GORUP-BESANEZ, E. VON, 1874: Ueber das Vorkommen eines diastatischen und peptonisirenden Fermentes in den Wickensamen, *Ber. d. d. chem. Ges.*, **7**: 1478-1480.
- , 1875: Weitere Beobachtungen über diastatische und peptonbildende Fermente im Pflanzenreiche, *Ber. d. d. chem. Ges.*, **8**: 1510-1516.
- and H. WILL, 1876: Fortgesetzte Beobachtungen über peptonbildende Ferment im Pflanzenreiche, *Ber. d. d. chem. Ges.*, **9**: 673-678.
- GREEN, J. R., 1887: On the changes in the proteids in the seed which accompany germination, *Phil. Trans. Roy. Soc., B.*, **178**: 39-61.
- , 1887: On the germination of the tuber of the Jerusalem artichoke (*Helianthus tuberosus*), *Ann. Bot.*, **1**: 223-236.

- GREEN J. R., 1888: Vegetable rennet, *Nature*, **38**: 274-276.
- , 1890: On the germination of the seed of the castor-oil plant, *Proc. Roy. Soc.*, **48**: 370-392.
- , 1892: On the occurrence of vegetable trypsin in the fruit of *Cucumis utilis-simus*, *Ann. Bot.*, **6**: 195-202.
- , 1893: On vegetable ferments, *Ann. Bot.*, **7**: 83-137.
- , 1894: Researches on the germination of the pollen grain and the nutrition of the pollen tube, *Phil. Trans. Roy. Soc.*, B, **185**: 385-409.
- , 1894: The influence of light on diastase, *Ann. Bot.*, **8**: 370-373.
- , 1897: On the action of light on diastase and its biological significance, *Phil. Trans. Roy. Soc.*, B, **188**: 167-190.
- , 1899: "The Soluble Ferments and Fermentation," 480 pp., Cambridge University Press.
- GRIFFIN, E. G., and J. M. NELSON, 1916: The influence of certain substances on the activity of invertase, *Jour. Amer. Chem. Soc.*, **38**: 722-730.
- GRÜSS, J., 1893: Ueber den Eintritt von Diastase in das Endosperm, *Ber. d. d. bot. Ges.*, **11**: 286-292.
- , 1894: Ueber das Verhalten des diastatischen Enzyms in der Keimpflanze, *Jahrb. f. wiss. Bot.*, **26**: 379-437.
- , 1895: Die Diastase im Pflanzenkörper, *Ber. d. d. bot. Ges.*, **13**: 2-13.
- , 1896: Beiträge zur Physiologie der Keimung, *Landw. Jahrb.*, **26**: 385-452.
- , 1897: Ueber die Secretion des Schildechens, *Jahrb. f. wiss. Bot.*, **30**: 645-664.
- HABERLANDT, G., 1890: Die Kleberschicht des Gras-Endosperms als Diastase ausscheidendes Drüsengewebe, *Ber. d. d. bot. Ges.*, **8**: 40-48.
- HAEHN, H., and H. SCHWEIGART, 1923: Zur Kenntnis der Kartoffelamylase, *Biochem. Zeits.*, **143**: 516-526.
- HALEY, D. E., and J. F. LYMAN, 1921: Castor bean lipase, its preparation and some of its properties, *Jour. Amer. Chem. Soc.*, **43**: 2664-2670.
- HANSTEEEN, B., 1895: Ueber die Ursachen der Entleerung der Reservestoffe aus Samen, *Flora*, **79**: 419-429.
- HENRI, V., 1902: Théorie générale de l'action de quelques diastases, *Compt. Rend. Acad. Sci. Paris.*, **135**: 916-919.
- and A. LALOU, 1903: Action de l'émulsine sur la salicine et l'amygdaline. Théorie de l'action de l'émulsine, *Compt. Rend. Acad. Sci. Paris*, **136**: 1693-1694.
- and MAURICE NICLOUX, 1904: Influence des proportions d'huile et d'acide sur la vitesse de saponification par la lipasécidine, *Compt. Rend. Soc. Biol. Paris*, **57**: 175-177.
- HEPBURN, J. S., 1918: Biochemical studies of the pitcher liquor of *Nepenthes*, *Proc. Amer. Phil. Soc.*, **57**: 112-130.
- , E. Q. ST. JOHN, F. M. JONES, and W. F. BAKER, 1922: Studies of the North American *Sarraceniaceae*, *Jour. Biol. Chem.*, **50**: Proc. XLVI.
- HOGOUNENQ, L., and J. LOISELEUR, 1925: Sur la constitution des diastases proteolytique et le mécanisme de leur actions, *Bull. Soc. Chim. Biol.*, **7**: 955-973.
- HORNING, E. S., and A. H. K. PETRIE, 1927: The enzymatic function of mitochondria in the germination of cereals, *Proc. Roy. Soc.*, B, **102**: 188-206.
- HORTON, EDWARD, 1921: On the use of taka-diastase in estimating starch, *Jour. Agr. Sci.*, **11**: 240-257.
- HOYER, E., 1904: Ueber fermentative Fettspaltung, *Ber. d. d. chem. Ges.*, **37**: 1436-1447.
- , 1907: Ueber fermentative Fettspaltung, *Zeits. f. physiol. Chem.*, **50**: 414-435.
- HUDSON, C. S., 1908: The inversion of cane sugar by invertase. I, II, *Jour. Amer. Chem. Soc.*, **30**: 1160-1166, 1564-1583.

- HUDSON, C. S., 1909: The inversion of cane sugar by invertase. III, *Jour. Amer. Chem. Soc.*, **31**: 655-664.
- and H. S. PAINE, 1910: The inversion of cane sugar by invertase. IV, The influence of acids and alkalis on the activity of invertase, *Jour. Amer. Chem. Soc.*, **32**: 774-779.
- and ———, 1910: The inversion of cane sugar by invertase. V, The destruction of invertase by acids, alkalis and hot water, *Jour. Amer. Chem. Soc.*, **32**: 985-989.
- , 1910: The inversion of cane sugar by invertase. VI, A theory of the influence of acids and alkalis on the activity of invertase, *Jour. Amer. Chem. Soc.*, **32**: 1220-1222.
- and H. S. PAINE, 1910: The inversion of cane sugar by invertase. VII, The effect of alcohol on invertase, *Jour. Amer. Chem. Soc.*, **32**: 1350-1357.
- , 1910: The quantitative determination of cane sugar by the use of invertase, *Jour. Ind. Eng. Chem.*, **2**: 143-146.
- , 1914: The inversion of sucrose by invertase. VIII, An improved method for preparing strong invertase solutions from top or bottom yeast, *Jour. Amer. Chem. Soc.*, **36**: 1566-1571.
- and H. S. PAINE, 1914: The inversion of sucrose by invertase. IX, Is the reaction reversible? *Jour. Amer. Chem. Soc.*, **36**: 1571-1581.
- HUERRE, R., 1909: Sur la maltase du sarrasin, *Compt. Rend. Acad. Sci. Paris*, **148**: 1526-1528.
- , 1909: Sur la maltase du maïs, *Compt. Rend. Acad. Sci. Paris*, **148**: 300-302, 505-507.
- , 1909: Influence de la réaction du milieu sur la activité des maltases du maïs, *Compt. Rend. Acad. Sci. Paris*, **148**: 1121-1123.
- JACOBSON, C. A., and A. HOLMES, 1914: Alfalfa investigations. V, Enzymes present in alfalfa, *Jour. Amer. Chem. Soc.*, **36**: 2170-2182.
- JAVILLIER, M., 1903: Sur quelques ferments proteolytiques associés à la présure chez les végétaux, *Compt. Rend. Acad. Sci. Paris*, **136**: 1013-1015.
- JODIDI, S. I., and J. PEKLO, 1929: Symbiotic fungi of cereal seeds and their relation to cereal proteins, *Jour. Agr. Res.*, **38**: 69-93.
- JONES, W. N., 1925: Polarized light and starch grains, *Ann. Bot.*, **39**: 651-653.
- KASTLE, J. H., and MARY CLARK, 1903: On the occurrence of invertase in plants, *Amer. Chem. Jour.*, **30**: 422-427.
- KAYSER, E., 1891: Note sur les ferments de l'ananas, *Ann. Inst. Pasteur*, **5**: 456-463.
- KELLERMAN, K. F., 1903: The effects of various chemical agents upon the starch converting power of taka diastase, *Bull. Torrey Bot. Club*, **30**: 56-70.
- KIZEL, A., 1915: The effect of the reaction of the medium on the activity of inulase of *Aspergillus niger*, *Isv. Imp. Akad. Nauk. (Bull. Acad. Imp. Sci.) Petrograd*, **6**: 1077-1092; *Expt. Sta. Rec.* **37**: 203.
- KNUDSON, L., 1920: The secretion of invertase by plant roots, *Amer. Jour. Bot.*, **7**: 371-380.
- KOGA, T., 1923: Zur Frage der Differenzierung tierischer und pflanzlicher Diastasen, *Biochem. Zeits.*, **142**: 159-164.
- KOHL, F. G., 1908: Über die Reversibilität der Enzymwirkungen und den Einfluss äusserer Faktoren auf die Enzyme (Invertase, Maltase), *Beih. Bot. Centrbl.*, **23**: 64b-64o.
- KOSMANN, M. C., 1877: Recherches chimiques sur les ferments contenus dans les végétaux et sur les effets produits par l'oxydation du fer sur les matières organiques, *Bull. Soc. Chim.*, **27**: 251-256.
- KRABBE, G., 1890: Untersuchungen über das Diastaseferment unter specieller Berücksichtigung seiner Wirkung auf Stärke-körner innerhalb der Pflanzen, *Jahrb. f. wiss. Bot.*, **21**: 521-561.

- KRAUCH, C., 1879: Beiträge zur Kenntniss der ungeformten Fermente im Pflanzenreich, *Landw. Versuchs-Stat.*, **23**: 77-104.
- LEA, SHERIDAN, 1883: On a "Rennet" ferment contained in the seeds of *Withania coagulans*, *Proc. Roy. Soc.*, **36**: 55-58.
- LING, A. R., and D. R. NANJ, 1923: On the presence of maltase in germinated and ungerminated barley, *Biochem. Jour.*, **17**: 593-596.
- LINTNER, C. J., 1886: Studien über Diastase, *Jour. Prak. Chem.*, **34**(2): 378-394.
- LINZ, F., 1896: Beiträge zur Physiologie der Keimung von *Zea mais*, *Jahrb. f. wiss. Bot.*, **29**: 267-319.
- MACHT, D. I., 1928: Effect of polarized light on plants, *Amer. Jour. Bot.*, **15**: 621 (abst.).
- and J. H. HILL, 1925: The influence of polarized light on yeast and bacteria, *Proc. Soc. Exper. Biol. Med.*, **22**: 474-475.
- MAESTRINI, D., 1923: Contributo alla conoscenza degli enzimi. IX, Sulla resistenza all' invecchiamento di alcun enzimi dell'orzo germogliato, *Atti R. Accad. Lincei Roma Rendiconti Cl. Sci. Fis. Mat. e Nat.*, **32**: 397-398; *Bot. Abst.*, **13**: 178.
- MANN, A., and H. V. HARLAN, 1915: Morphology of the barley grain with reference to its enzyme secreting areas, *U. S. Dept. Agr. Bull.*, **183**: 1-32.
- MAQUENNE, L., and E. ROUX, 1906: Recherches sur l'amidon et sa saccharification diastasique, *Ann. de Chemie et de Physique*, 8^e, **9**: 179-220.
- MASLOW, H. L., and W. C. DAVIDSON, 1926: The effect of hydrogen ion concentration upon the starch liquefying activity of the amylase of *Aspergillus oryzae*, *Jour. Biol. Chem.*, **68**: 83-93.
- MARTIN, S. H. C., 1884: Papain-digestion, *Jour. Physiol.*, **5**: 213-230.
- , 1885: The nature of papain and its action on vegetable proteid, *Jour. Physiol.*, **6**: 336-360.
- MARTINAND, V., 1907: Recherche de l'invertine ou sucrase et du saccharose dans les divers organes de la Vigne et dans quelques fruits, *Compt. Rend. Acad. Sci. Paris*, **144**: 1376-1379.
- MATHEW, A. P., and T. H. GLENN, 1911: The composition of invertase, *Jour. Biol. Chem.*, **9**: 29-56.
- MCGUIRE, GRACE, and K. G. FALK, 1919: The saccharogenic actions of potato juice, *Jour. Gen. Physiol.*, **2**: 215-227.
- and —, 1923: Studies on enzyme action. XXIII, The spontaneous increase in sucrase activity of banana extracts, *Jour. Amer. Chem. Soc.*, **45**: 1539-1551.
- MENDEL, L. B., and F. P. UNDERHILL, 1901: Observations on the digestion of proteids with papain, *Trans. Conn. Acad. Arts and Sci.*, **11**: 1-14.
- , 1902: Observations on vegetable proteolytic enzymes, with special reference to papain, *Amer. Jour. Med. Sci.*, **124**: 310-318.
- and A. F. BLOOD, 1910: Some peculiarities of the proteolytic activity of papain, *Jour. Biol. Chem.*, **8**: 177-213.
- MICHAELIS, L., and M. ROTHSTEIN, 1920: Zur Theorie der Invertasewirkung, *Biochem. Zeits.*, **110**: 217-233.
- MIEHE, HUGO, 1923: Über die Lebensdauer der Diastase, *Ber. d. d. bot. Ges.*, **41**: 263-268.
- MUSSI, DR., 1890-1891: Cradina, a proteolytic enzyme in the fig (*Ficus carica*), abst. *Pharm. Jour.*, 3 ser., **21**: 560-561.
- NAYLOR, N. M., M. SPENCER, and M. HOUSE, 1925: The preparation and properties of amylase from germinated wheat and rye, *Jour. Amer. Chem. Soc.*, **47**: 3037-3039.
- NEIDIG, R. E., 1914: The survival of amylase in dried fodders, *Jour. Amer. Chem. Soc.*, **36**: 1312-1314.

- NELSON, J. M., and SIDNEY BORN, 1914: A study of the chemical constitution of invertase, *Jour. Amer. Chem. Soc.*, **36**: 393-403.
- and E. G. GRIFFIN, 1916: Adsorption of invertase, *Jour. Amer. Chem. Soc.* **38**: 1109-1115.
- and W. C. VOSBURGH, 1917: Kinetics of invertase action, *Jour. Amer. Chem. Soc.*, **39**: 790-811.
- and D. I. HITCHCOCK, 1921: The activity of adsorbed invertase, *Jour. Amer. Chem. Soc.*, **43**: 1956-1961.
- and ———, 1921: Uniformity in invertase action, *Jour. Amer. Chem. Soc.*, **43**: 2632-2655.
- and F. HOLLANDER 1923: Uniformity in invertase action, *Jour. Biol. Chem.*, **58**: 291-305.
- and GROVER, BLOOMFIELD, 1924: Some characteristics of invertase action, *Jour. Amer. Chem. Soc.*, **46**: 1025-1043.
- and O. BODANSKY, 1925: Mutarotation as a factor in the kinetics of invertase action, *Jour. Amer. Chem. Soc.*, **47**: 1624-1638.
- NEUMEISTER, R., 1894: Ueber das Vorkommen und die Bedeutung eines eiweisslösenden Enzyms in jugendlichen Pflanzen, *Zeits. f. Biol.*, **30**: 447-463.
- NEWCOMBE, F. C., 1898: Cellulose-enzyme, *Bot. Centrbl.*, **73**: 105-108.
- , 1899: Cellulose-enzymes, *Ann. Bot.*, **13**: 49-81.
- NICLOUX, M., 1904: Étude de l'action lipolytique du cytoplasma de la graine de ricin, *Compt. Rend. Acad. Sci. Paris*, **138**: 1288-1290.
- , 1904: Étude de l'action lipolytique du cytoplasma de la graine de ricin, *Compt. Rend. Soc. Biol.*, **56**: 839-843.
- , 1904: La propriété lipolytique du cytoplasma de la graine de ricin n'est pas due à un ferment soluble, *Compt. Rend. Acad. Sic. Paris*, **138**: 1352-1354.
- , 1904: La propriété lipolytique du cytoplasma de la graine de ricin n'est pas due à un ferment soluble, *Compt. Rend. Soc. Biol.*, **56**: 868-870.
- , 1904: Mécanisme d'action du cytoplasma (lipaseidine) dans la graine en voie de germination: Réalisation synthétique in vitro de ce mécanisme, *Compt. Rend. Acad. Sci. Paris*, **139**: 143-145.
- , 1904: Mécanisme d'action du cytoplasma "lipaseidine" dans la graine en voie de germination réalisation synthétique en vitro de ce mécanisme, *Compt. Rend. Soc. Biol.*, **57**: 84-86.
- , 1904: Sur le pouvoir saponifiant de la graine de ricin, *Compt. Rend. Soc. Biol.*, **56**: 702-704.
- , 1904: Sur le pouvoir saponifiant de la graine de ricin, *Compt. Rend. Acad. Sci. Paris*, **138**: 1175-1177.
- , 1905: La saponification des corps gras, *Rev. Gén. des Sciences*, 16^e année, No. 23, pp. 1029-1037.
- , 1906: Studies on enzyme action—Lipase, *Proc. Roy. Soc.*, B, **77**: 454-455.
- OLSSON, U., 1921: Über Vergiftungserscheinungen an Amylasen, *Zeits. f. physiol. Chem.*, **117**: 91-145.
- OSBORNE, T. B., 1895: The chemical nature of diastase, *Jour. Amer. Chem. Soc.*, **17**: 587-604.
- and G. F. CAMPBELL, 1896: The chemical nature of diastase. II, *Jour. Amer. Chem. Soc.*, **18**: 536-542.
- OSBORNE, W. A., 1898: Beiträge zur Kenntniss des Invertins, *Zeits. f. physiol. Chem.*, **28**: 399-425.
- O'SULLIVAN, C., and F. W. TOMPSON, 1890: Invertase: A contribution to the history of an enzyme or unorganized ferment, *Jour. Chem. Soc.*, **57**: 834-931.
- PAINE, H. S., and R. T. BALCH, 1925: Application of enzymes to beet sugar factory control, *Jour. Ind. Eng. Chem.*, **17**: 240-246.

- PAINE, H. S., C. F. WALTON, and M. S. BADOLLET, 1925: Industrial applications of invertase, *Jour. Ind. Eng. Chem.*, **17**: 445-450.
- PALLADIN, W., and H. POPOFF, 1922: Über die Entstehung der Amylase und Maltase in den Pflanzen, *Biochem. Zeits.*, **128**: 487-494.
- PALLADIN, V. I., and E. M. POPOVA, 1924: On the origin of diastase in plants, *Bull. App. Bot. Plant-breeding*, **13**: 355-369 (Russian); *Bot. Abst.*, **14**: 1448.
- PATON, JAMES, R. DINSHAW, and A. R. LING, 1924: On the hydrolysis of the endosperm of *Phytelephas macrocarpa* by its own enzymes, *Biochem. Jour.*, **18**: 451-454.
- PELOUZE, J., 1855: Mémoire sur la saponification des huiles sous l'influence des matières qui les accompagnent dans les graines, *Compt. Rend. Acad. Sci. Paris*, **40**: 605-611.
- PICKLER, W. E., 1919: Water content and temperature as factors influencing diastase formation in the barley grain, *Plant World*, **22**: 221-238.
- PINCUSSEN, L., 1923: Fermente und Licht. I, II, Diastase. I, *Biochem. Zeits.*, **134**: 459-469, 470-475.
- PRATT, DAVID S., 1915: Papaïn. Its commercial preparation and digestive properties, *Phillipine Jour. Sci.*, **A**, **10**: 1-37.
- POLAK, F., and A. TYCHOWSKI, 1928: Über die Umwandlung der α -Diastase in β -Diastase, *Biochem. Zeits.*, **192**: 463-478.
- POND, R. H., 1906: The incapacity of the date endosperm for self-digestion, *Ann. Bot.*, **20**: 62-78.
- POZERSKI, E., 1909: Contribution à l'étude physiologique de la papaïne, *Ann. Inst. Pasteur*, **23**: 321-359.
- , 1909: Digestion brusque produite par la bromeline. Comparaison avec la papaïne, *Ann. Inst. Pasteur*, **23**: 341-346.
- PRUNET, A., 1892: Sur le mécanisme de la dissolution de l'amidon dans la plante, *Compt. Rend. Acad. Sci. Paris*, **115**: 751-754.
- PURIWITSCH, K., 1897: Physiologische Untersuchungen über die Entleerung der Reservestoffbehälter, *Jahrb. f. wiss. Bot.*, **31**: 1-76.
- REED, H. S., 1904: A study of the enzyme-secreting cells in the seedlings of *Zea mais* and *Phoenix dactylifera*, *Ann. Bot.*, **18**: 267-287.
- RICHAND, ALBERT, 1900: "Recherches physiologique sur l'amilase et sur l'inuline," thèse 8°, 95 pp., Carre et Naud, Paris.
- ROBERTSON, R. A., J. C. IRVINE, and M. E. DOBSON, 1909: A polarimetric study of the sacroclastic enzymes in *Beta vulgaris*, *Biochem. Jour.*, **4**: 258-273.
- RUSSELL, J. B., 1891: Bromelin, *Bull. Pharm.*, **5**: 77.
- SARGANT, E., and A. ROBERTSON, 1905: The anatomy of the scutellum in *Zea mais*, *Ann. Bot.*, **19**: 115-124.
- SCHENKER, ROBERT, 1921: Zur Kenntnis der Lipase von *Aspergillus niger*, *Biochem. Zeits.*, **120**: 164-196.
- SCHMITZ, H., 1920: Enzyme action in *Echinodontium tinctorium*, *Jour. Gen. Physiol.*, **2**: 613-616.
- SEMMENS, E. S., 1926: Hydrolysis of starch grains by light polarized by small particles, *Nature*, **117**: 821-822.
- , 1926: Some further notes on the hydrolysis of starch grains under polarized light, *Plant Physiol.*, **1**: 201-202.
- SHERMAN, H. C., E. C. KENDALL, and E. D. CLARK, 1910: Studies on amylases. I. An examination of methods for the determination of diastatic power, *Jour. Amer. Chem. Soc.*, **32**: 1073-1087.
- , and M. D. SCHLESINGER, 1913: Studies on amylases. V, Experiments upon the purification of the amylase of malt, *Jour. Amer. Chem. Soc.*, **35**: 1617-1624.

- SHERMAN, H. C., and A. O. GETTLER, 1913: Studies on amylases. VII, The forms of nitrogen in amylase preparations from the pancreas and from malt, as shown by the Van Slyke method, *Jour. Amer. Chem. Soc.*, **35**: 1790-1794.
- , and A. W. THOMAS, 1915: Studies on amylases. VIII, The influence of certain acids and salts upon the activity of malt amylase, *Jour. Amer. Chem. Soc.*, **37**: 623-643.
- , and M. D. SCHLESINGER, 1915: Studies on amylases. IX, Further experiments upon the purification of malt amylase, *Jour. Amer. Chem. Soc.*, **37**: 643-648.
- , and ———, 1915: Studies on amylases. X, Comparison of certain properties of pancreatic and malt amylase preparations, *Jour. Amer. Chem. Soc.*, **37**: 1305-1319.
- , and J. C. BAKER, 1916: Experiments upon starch as substrate for enzyme action, *Amer. Jour. Chem. Soc.*, **38**: 1885-1904.
- , and D. E. NEUN, 1916: An examination of certain methods for the study of proteolytic action, *Jour. Amer. Chem. Soc.*, **38**: 2199-2216.
- , and A. P. TANBERG, 1916: Experiments upon the amylase of *Aspergillus oryzae*, *Jour. Amer. Chem. Soc.*, **38**: 1638-1644.
- , and J. A. WALKER, 1917: Influence of certain electrolytes upon the course of the hydrolysis of starch by malt amylase, *Jour. Amer. Chem. Soc.*, **39**: 1476-1493.
- , A. W. THOMAS, and M. E. BALDWIN, 1919: Influence of hydrogen-ion concentration upon enzymic activity of three typical amylases, *Jour. Amer. Chem. Soc.*, **41**: 231-235.
- , F. WALKER, and M. L. CALDWELL, 1919: Action of enzymes upon starches of different origin, *Jour. Amer. Chem. Soc.*, **41**: 1123-1129.
- , and ———, 1919: Influence of aspartic acid and asparagin upon the enzymic hydrolysis of starch, *Jour. Amer. Chem. Soc.*, **41**: 1866-1873.
- , and MARY CALDWELL, 1921: A study of the influence of arginine, histidine, tryptophane and cystine upon the hydrolysis of starch by purified pancreatic amylase, *Jour. Amer. Chem. Soc.*, **43**: 2469-2476.
- , and FLORENCE WALKER, 1921: The influence of certain amino acids upon the enzyme hydrolysis of starch, *Jour. Amer. Chem. Soc.*, **43**: 2461-2469.
- , and M. WAYMAN, 1921: Effect of certain antiseptics upon the activity of amylases, *Jour. Amer. Chem. Soc.*, **43**: 2454-2461.
- , and M. L. CALDWELL, 1922: Influence of amino acid in protecting amylase from inactivation by mercury, *Jour. Amer. Chem. Soc.*, **44**: 2923-2926.
- , and ———, 1922: Influence of lysine upon the hydrolysis of starch by purified pancreatic amylase, *Jour. Amer. Chem. Soc.*, **44**: 2926-2930.
- , and N. M. NAYLOR, 1922: Influence of some organic compounds upon the hydrolysis of starch by salivary and pancreatic amylases, *Jour. Amer. Chem. Soc.*, **44**: 2957-2966.
- , A. W. THOMAS, and M. L. CALDWELL, 1924: The isoelectric point of malt amylase, *Jour. Amer. Chem. Soc.*, **46**: 1711-1717.
- , M. L. CALDWELL, and MILDRED ADAMS, 1927: Establishment of the optimal hydrogen-ion activities for the enzymic hydrolysis of starch by pancreatic and malt amylases under varied conditions of time and temperature, *Jour. Amer. Chem. Soc.*, **49**: 2000-2005.
- SIGMUND, W., 1890: Ueber fettspaltende Fermente im Pflanzenreiche, *Monats. f. Chem. Wien.*, **11**: 272-276.
- , 1892: Beziehungen zwischen fettspaltenden und glycosidspaltenden Ferment, *Sitzungsber. d. k. Akad. d. Wiss. Wien.*, **101**: 549-559.
- SJÖBERG, K., 1922: Beiträge zur Kenntnis der Amylase in Pflanzen. I, Über die Bildung und das Verhalten der Amylase in lebenden Pflanzen, *Biochem. Zeits.*, **133**: 218-294.

- SJÖBERG, K., 1922: Beiträge zur Kenntnis der Amylase in Pflanzen. II, Die Temperaturempfindlichkeit der Amylase von *Phaseolus vulgaris*, *Biochem. Zeits.*, **133**: 294-330.
- , 1923: Beiträge zur Kenntnis der Amylase in Pflanzen. III, *Biochem. Zeits.*, **142**: 274-279.
- SORENSEN, S. P. L., 1908: Enzymstudien, *Biochem. Zeits.*, **7**: 45-101.
- STONE, W. E., 1896: The carbohydrates of wheat, maize, flour and bread and the action of enzymic ferments upon starches of different origin. *U. S. Dept. Agr. Off. Expt. Sta. Bull.* **34**.
- STOWARD, F., 1912: On the influence exercised by certain acids on the inversion of saccharose by sucrase, *Biochem. Jour.*, **6**: 131-140.
- SWANSON, C. O., and J. W. CALVIN, 1913: A preliminary study of the conditions which affect the activity of the amylolytic enzymes in wheat flour, *Jour. Amer. Chem. Soc.*, **35**: 1635-1640.
- TAIT, L., 1875: Insectivorous plants, *Nature*, **12**: 251-252.
- TAKAMINE, JOKICHI, and OSHIMA KOKICHI, 1920: The properties of a specially prepared enzymic extract, polyzime, comparing its starch liquefying power with malt diastase, *Jour. Amer. Chem. Soc.*, **42**: 1261-1265.
- TANKA, YOSHIO, 1910: The action of acids in the enzymic decomposition of oil by castor seeds, *Jour. Coll. Eng. Tokyo*, **5**: 25-42 (quoted by Bayliss, 1925).
- , 1912: The preparation of lipase-powder acting in neutral medium, *Jour. Coll. Eng. Tokyo*, **5**: 125-136.
- TAYLOR, A. E., 1906: On the action of lipase, *Jour. Biol. Chem.*, **2**: 87-105.
- THATCHER, R. W., and G. P. KOCH, 1914: The quantitative extraction of diastases from plant tissues, *Jour. Amer. Chem. Soc.*, **36**: 759-770.
- , 1921: "The Chemistry of Plant Life," 268 pp., McGraw-Hill Book Company, Inc.
- THOMAS, A. W., 1917: A noteworthy effect of bromides upon the action of malt amylase, *Jour. Amer. Chem. Soc.*, **39**: 1501-1503.
- TORREY, J. C., 1902: Cytological changes accompanying the secretion of diastase, *Bull. Torr. Bot. Club.*, **29**: 421-
- VINES, S. H., 1891: On the presence of a diastatic ferment in green leaves, *Ann. Bot.*, **5**: 409-412.
- , 1897, 1898, 1901: The proteolytic enzyme of *Nepenthes*. I, II, III, *Ann. Bot.*, **11**: 563-584; **12**: 545-555; **15**: 563-573.
- , 1902: Tryptophane in proteolysis, *Ann. Bot.*, **16**: 1-22.
- , 1903: Proteolytic enzymes in plants. I, II, *Ann. Bot.*, **17**: 237-264, 597-616.
- , 1904-1906, 1908-1910: The proteases of plants, I, II, III, IV, V, VI, VII, *Ann. Bot.*, **18**: 289-317; **19**: 149-162, 171-187; **20**: 113-122; **22**: 103-113; **23**: 1-18; **24**: 213-222.
- VINSON, A. E., 1907: The function of invertase in the formation of cane and invert sugar dates, *Bot. Gaz.*, **43**: 393-407.
- , 1908: The endo- and ektoinvertase of the date, *Jour. Amer. Chem. Soc.*, **30**: 1005-1020.
- VOSBURGH, W. C., 1921: Some errors in the study of invertase action, *Jour. Amer. Chem. Soc.*, **43**: 1693-1705.
- WAKSMAN, S. A., 1920: A method of testing the amylolytic action of the diastase of *Aspergillus oryzae*, *Jour. Amer. Chem. Soc.*, **42**: 293-299.
- WARD, MARSHALL, 1888: A lily disease, *Ann. Bot.*, **2**: 319-383.
- WEIS, F., 1900: Ueber das proteolytische und ein eiweisscoagulirendes Enzym in keimender Gerste (Malz.), *Zeits. f. physiol. Chem.*, **31**: 79-97.
- WHITE, JEAN, 1909: The ferments and latent life of resting seeds, *Proc. Roy. Soc., B*, **81**: 417-442.

- WHITE, JEAN, 1910: The proteolytic enzyme of *Drosera*, *Proc. Roy. Soc.*, **B**, **83**: 134-139.
- WIERZCHOWSKI, Z., 1913: Studien über die Einwirkung von Maltase auf Stärke, *Biochem. Zeits.*, **56**: 209-219.
- , 1913: Über das Auftreten der Maltase in Getreidearten, *Biochem. Zeits.*, **57**: 125-131.
- WILLSTATTER, R., 1922: Über Isolierung von Enzymen, *Ber. d. d. chem. Ges.*, **55**: 3601-3623.
- WOLFF, J., 1916: Sur une substance coagulant l'inuline et l'accompagnant dans les tissus végétaux, *Compt. Rend. Acad. Sci. Paris.*, **162**: 514-516.
- WURTZ, A., 1879: "Recherches cliniques et chimiques sur la papaine," Paris.
- and E. BOUCHUT, 1879: Sur le ferment digestif du *Carica papaya*, *Compt. Rend. Acad. Sci. Paris*, **89**: 425-429.
- , 1880: Sur la papaine. Nouvelle contribution à l'histoire des ferments solubles, *Compt. Rend. Acad. Sci. Paris*, **91**: 787-791.
- YOUNG, V. H., 1918: Some factors affecting inulase formation in *Aspergillus niger*, *Plant World*, **21**: 75-87, 114-133.

CHAPTER XII

THE TRANSLOCATION OF MATERIALS IN PLANTS

I. NEED OF TRANSLOCATION

Most of the green plants are highly specialized organisms. They are thus composed of numerous interdependent parts or organs which perform special functions. Each organ must be supplied by other organs with the materials necessary for its functions, while it in turn furnishes other organs with certain materials needed by them. Thus the epidermal cells of the roots absorb the compounds that enter the plant from the soil. These substances are for the most part not used entirely or directly by these cells that absorb them but are moved to other parts of the plant where they are utilized in the various life functions. For example, only a very small portion of the water that is absorbed by the epidermal cells of the roots is utilized by these cells. The greater portion of it is moved through the roots and stem to supply the needs of their cells and then on to the leaves to replace the water lost by transpiration. The movement of sugar is another striking example of translocation. This carbohydrate is manufactured only in the green cells of the leaf but is needed by every living cell of the plant for the manufacture of other foods, for respiration, for osmotic effects, and for other purposes. Sugar thus must be moved from the leaves to every living cell in the plant. The reserve foods of plants are practically all stored in places that are some distance removed from the regions in which they will eventually be utilized. Thus when the demand for them arises, they must be translocated to those parts of the plant in which they are needed.

II. TISSUES CONCERNED

In the broadest sense, all the living cells and certain of the non-living cells play a rôle in the movement of materials in plants. In the lower plants where materials need to be moved for only short distances, no specialization of cells for translocation occurs and all cells are equally concerned in the process. Also, if, in the higher plants, materials are moved for relatively short distances only, the cells show no special adaptations for translocation. Thus the materials taken from the soil by the epidermal cells of the root are moved to the endodermis across the parenchyma cells of the cortex. Likewise, the raw materials needed by the chlorenchyma cells of the leaf, as well as their manufactured products, are moved across them to and from the fibrovascular bundles. These

parenchyma cells, as well as those of the pith and cortex of the stem, show no special adaptations for translocation other than that they are possessed of thin cell walls which are readily permeable to solvent and solutes.

The tissues of the green plant that are specialized for the translocation of materials are the xylem and the phloem.

A. THE XYLEM

The cells of the xylem especially concerned in translocation are the tracheids, the vessels or tracheae, the wood parenchyma, or xylem parenchyma, and the xylem medullary rays. The tracheids are elongated cells with tapering ends. They may have relatively thin walls which are strengthened by spiral or annular thickenings, or the walls may be thick, lignified, and possessed of numerous pits generally of the bordered type. The tracheids are living cells for varying periods after their formation but eventually lose their protoplasmic contents so that they consist only of their cell walls. The vessels or tracheae, according to Eames and MacDaniels (1925), include those xylem elements which have a large lumen and marked perforations, especially in the end cell walls. The development of these perforations in the end walls brings a series of cells into a definite tubelike system. The conduction in the vessels is thus direct and is in contrast with the indirect lines of conduction in a group of tracheids. The vessels frequently have thin walls which are strengthened by annular or spiral thickenings. In other cases, the walls are thickened but generally not to the degree of the walls of the tracheids, and the vessels then are possessed of pits in their lateral walls. These pits are usually more numerous and smaller than those of the tracheids. The vessels also lose their protoplasmic contents at an early period after their development. The "wood" or "xylem parenchyma" is the name given to those living cells which are associated with the tracheids and vessels. These cells may be thin walled or thick walled and supplied with simple pits. They retain their protoplasmic contents and remain alive for a long period of time.

The xylem rays, or wood rays, are ribbon-like strips of tissue which extend radially into the xylem. These strips are composed of parenchyma cells which have their long axes at right angles to the long axes of the tracheids, vessels, and wood parenchyma. These cells are living cells and contain their protoplasmic contents for a long period of time, and, as mentioned in Chap. I, they remain alive longer than any other known plant cells. The ray cells have cell walls of varying degrees of thickness and have numerous simple pits on all their walls. According to Eames and MacDaniels (1925), the xylem rays may be one, two, or several cells in width, and in height they may range from one cell to many and thus may vary in height from a fraction of a millimeter to

8 to 10 mm. in extreme cases. In a given stem some of the xylem rays may extend from the cambium to the pith, while others extend from the cambium to varying distances in the xylem.

In this general description of the conducting elements of the xylem, it should be noted that those tracheids and vessels which have lost their protoplasmic contents and are yet concerned in conduction are in contact with some parts of their wall surface with one or more living cells. Abundant pits are also present in these contact areas. The living cells with which these non-living elements are in contact may be either the xylem parenchyma or xylem rays, or both these elements.

B. THE PHLOEM

The phloem is composed of the sieve tubes, companion cells, phloem parenchyma, and phloem rays. A sieve tube is an elongated living cell with a thin cellulose wall. It has a large vacuole, and the cytoplasm forms a thin peripheral layer. No nucleus is present in a sieve tube. The sieve tubes are joined end to end and are arranged more or less definitely in longitudinal rows. Their protoplasmic contents are connected through pores or perforations in their end and lateral walls. These pores are located in more or less definite areas which are termed "sieve plates." Although these sieve plates may occur over the end and side walls, they are limited to a considerable extent to the end walls (Fig. 34). The cell sap of many of the sieve tubes contains a relatively large amount of protein compounds of a slimy nature (Hill, 1901, 1908). The outstanding characteristics of the sieve tubes are thus the pores in their walls which are perforated with conspicuous cytoplasmic




FIG. 34.—Sieve tubes and a companion cell from the pumpkin vine. *spl*, sectional view of sieve plates. *s'pl'*, surface view of sieve plates. *sc*, protoplasmic contents of sieve tube, here contracted to the center of the cell. *stc*, cell cavity caused by the contraction of the protoplasmic contents. *s*, cell wall of sieve tube. *cp*, companion cell.

strands, the absence of a nucleus, and the relatively large amount of protein compounds in their vacuoles.

The companion cells are elongated, slender, parenchymatous cells which have a small vacuole and dense protoplasmic contents with a prominent nucleus. One companion cell is associated with each sieve tube, but it is often difficult to determine the sieve tube with which a given companion cell is associated (Fig. 34). A companion cell has numerous simple pits connecting with the sieve tube with which it is associated.

The phloem parenchyma cells have dense protoplasmic contents and possess simple pits in both their longitudinal and end walls. The relative amount of phloem parenchyma varies greatly with different types of phloem and with different plants. In some cases it makes up the greater portion of the phloem, while in others it is entirely absent. The phloem rays have the same general structure and arrangement as the xylem rays. It should be noted in this connection that the elements which compose the phloem are all living cells, which is in marked contrast with the elements of the xylem tissue.

III. MOVEMENT OF MATERIALS

A. Translocation of Water

The movement of water from the roots to the leaves, especially in the case of trees, has been of much general interest for several centuries. One of the most common questions asked by the general public of those individuals whom they know to be interested in the functions of plants concerns the manner in which the sap is moved through the stems of plants. It should be stated here that at present no answer that is entirely satisfactory can be given to this question. Although a large amount of experimental work has been undertaken to demonstrate the manner of water movement in plants, the evidence which has been obtained is in no way conclusive in many respects. In the following topics it is the intention to relate not only those facts which have been definitely established in regard to the translocation of water through the plant but also some of the theories concerning certain phases of this process which as yet have not been satisfactorily explained by the experimental evidence at hand.

1. Pathway of Water Movement.—The pathway through which most of the water travels from its entrance into the root until it is lost from the leaves into the atmosphere has been definitely established. The water enters the epidermal cells of the root, crosses the cells of the cortex, and enters the endodermis whence it moves into the lumina of the tracheids and vessels of the xylem of the root. It moves upward in these elements in the roots and thence through the same unit structures in the stem to the fibrovascular bundles of the leaf. From the xylem elements of the fibrovascular bundles of the leaf, it moves through the various

chlorenchyma cells to those bordering on the intercellular air spaces or on the substomatal air cavities. Here it is lost from the cell walls in the form of vapor and escapes through the stomata to the external atmosphere. Some water may travel upward through the pith and cortex of the root and stem of certain plants, but apparently the amount moved in these regions is relatively small, except in young plants, compared with that moved through the channels which have just been mentioned. The lateral movement of water apparently takes place for the most part through the xylem rays and phloem rays in the case of young dicotyledons and through the general parenchymatous tissue of the stem in the case of the monocotyledons.

The pathway of water in the xylem has been determined directly by the use of colored liquids (see Peirce, 1929) and has been proved in an indirect manner by noting the lack of sufficient water to supply the leaves when the xylem elements are blocked or severed. The portion of the xylem concerned in water conduction has, however, in the case of woody plants been in considerable dispute. The work of Overton (1925), Overton and Smith (1926) and MacDougal, Overton, and Smith (1929) has thrown much light upon this controversy. Their work indicates that the portion of the xylem concerned in water translocation varies markedly in different plants. Thus by using acid fuchsin it was found for the willow (*Salix lasiolepis*) that the colored liquid rose in every annual layer in stems that were 11 or more years of age. It was also found that the liquid passed only through the summer wood of each layer. The colored zones were less than 1 mm. in thickness, while the unstained zones were from 2.5 to 4.5 mm. wide. In the alder (*Alnus oregona*) the same concentric zonation of water conduction is shown, but the movement of water in this stem does not take place through the late summer wood but is confined exclusively to the early formed spring wood. In the walnut where heart- and sapwood are present all the conduction is in the sapwood through the late summer and early spring wood. In the pine (*Pinus radiata*) there is no localization of conduction in the xylem and the water moves through practically all parts of each annual ring.

2. Water-conducting Cells.—The absorbing power of the epidermal cells of the root for water is always greater than that of the soil solution under the general conditions of plant growth. There is an increasing gradient in the absorbing power of the cortical cells for water from the epidermal cells of the root toward the endodermis. The absorbing power of the endodermis, however, in all the cases that have been investigated, drops considerably below that of the cortical cells bordering on it.

The cells concerned in the absorption and translocation of water across the root to the xylem elements of the central cylinder are all living cells. The tracheids and vessels of the root and stem with the exception

of those which have been recently formed are however devoid of protoplasmic contents. The amount of water contained in these non-living water conducting elements has long been a matter of dispute. The observation of the contents of the tracheids and vessels under natural conditions is a difficult task, and in many of the observations the tissues examined were placed under abnormal conditions. It is thus impossible to determine whether the conditions of the cell contents observed were those normally prevailing or the result of the conditions imposed by the experiment. It has long been known that certain of the elements of the xylem contain gas bubbles with the liquid therein contained. At one time it was supposed that the presence of these bubbles lessened the total weight of a theoretical column of water and thus facilitated the ascent of sap in stems containing these so-called "Jaminian chains." It is now, however, almost universally recognized that the presence of a gas bubble in a tracheid or vessel at once eliminates that element from the conducting system. Those xylem elements which no longer function in the translocation of water are filled with gases, or the gases are intermingled as bubbles with the liquids yet remaining in them. The condition and composition of the gaseous mixture which fills these woody elements have been studied in detail by MacDougal (1925, 1926, 1927). He found that the gases of the central cylinder in the walnut may include CO_2 at a partial pressure six hundred times as great as in the atmosphere, but with an oxygen pressure of only one-half that of the atmosphere. The gases in the central cylinder of the Monterey pine included CO_2 at a pressure two hundred times as great as the atmosphere with the oxygen pressure reduced to one-fourth of that normally present in the air. The amounts of these gases vary during the season of year. Thus the CO_2 content of the oak was 3 per cent in October and 9 per cent in June. In the case of the willow the CO_2 content was 13.2 per cent in June and 8.4 per cent in August. The oxygen content of the walnut stem varied from 8.8 per cent in June to 12 to 13 per cent in July.

According to MacDougal, Overton, and Smith (1929), pressures and suction on the gaseous system within the trunk of a tree are readily transmitted vertically for distances many times the length of the vessels. Tangential transmission, however, of suction and pressures is at a very slow rate and even slower in a radial direction. The internal gaseous system of the tree is, however, in communication with the atmosphere radially through the cambium and vertically through the ends of the branches. The tensions in the air system have been shown to vary from less than one-half an atmosphere to not to exceed two atmospheres. The relative volumes of the water and air systems within a tree are subject to variations during the season, so that specific conducting elements may at one time be partially or wholly filled with gas and at another time entirely filled with water.

According to MacDougal, Overton, and Smith (1929), it has been observed by Holle (1915) that when leaves were completely wilted the water columns remained intact in the conducting elements. These authors also state that Bode (1923) in observations of the wilted plants of *Tradescantia*, *Cucurbita*, *Impatiens*, *Helianthus*, *Sambucus*, and *Phaseolus* noted that gas bubbles entered the conducting elements of these parts only when living cells in contact with them were touched or wounded. Bode thus concluded that bubbles may appear in conducting elements containing water only by being drawn in or by wounding. MacDougal, Overton, and Smith (1929) state that in the stems examined by them the elements which are operative in conduction contain exclusively water, while those that are inoperative in conduction may contain gas exclusively or water and gas bubbles in the form of chains.

It is thus apparently well established that the elements of the xylem concerned in conduction are completely filled with water and that on that account there is a continuous column of water through them from the endodermis to the chlorenchyma cells of the leaf. As mentioned in Chap. II, it has been shown that there is an increasing gradient of absorbing power for water in the chlorenchyma cells of the leaf from the fibrovascular bundles of the leaf toward its margins.

The evidence thus indicates that water columns are continuous in the plant from the soil particles through the epidermal cells, cortex, and endodermis of the root; through the conducting xylem of the root and stem to the veins of the leaves; and thence through the cell walls and vacuoles of the chlorenchyma cells to the surfaces of the menisci formed in the submicroscopical cavities of the cell walls bordering on the intercellular spaces in the leaf. These water connections extending throughout the plant have been termed by MacDougal (1925 to 1926) the "hydrostatic system" of the plant.

3. Ascent of Water.—In attempting to determine the forces that are concerned in the ascent of water in plants, the investigator is handicapped because of the relatively small number of the external manifestations of the action of these forces as well as the difficulty encountered in measuring and correctly interpreting these manifestations. The external manifestations by which the action of the hydrostatic system of plants in elevating water may be estimated are, according to MacDougal (1925), (a) the amount of the intake of water, (b) the amount of transpiration, (c) the amount of water forced from the plant in the form of liquid, and (d) the registration of the daily reversible variations in stems as a result of the altered cohesive tensions in the ascending column of water. Some of these manifestations are more evident under conditions of low evaporation, while others are more evident under conditions of high evaporation. The forces that are concerned in the ascent of water in plants are apparently active all the time but are more manifest under one of the above-

mentioned conditions than under the other. On that account, it is convenient in discussing the ascent of water to consider (a) the ascent of water in plants under conditions of low evaporation and (b) the ascent of water in plants under the conditions of high evaporation.

a. *Low Evaporation.*—Under conditions that are favorable for both low transpiration and the absorption of water from the soil, water is forced into and up through the xylem elements under considerable pressure. This fact is made manifest by the exudation of water from the stem and leaves of intact plants, the water so exuded being designated as “water of guttation.” This action is also shown when bore holes are made into the stems and branches, or when they are severed, since under these conditions water is forced out or exuded from the hole or stump apparently by some pressure within the stem or root. This exudation of water may also occur from perforations in the stem or from the stump of stems or branches under conditions of high transpiration, although a considerable period of time must elapse before the exudation develops. The force or pressure with which water is exuded from holes made in the stem or from the fresh stumps of stems or branches has been termed “root pressure,” “sap pressure,” “endodermal pressure,” “bleeding pressure,” or “exudation pressure.” These terms have also been applied to the forces causing the exudation of water of guttation. The term root pressure has been the one most commonly used to designate not only the force with which water is being pushed up through the stem of the intact plant but also the force with which water is being exuded from some injured part. The term has been used since it has generally been considered that the force under consideration is generated in certain of the root cells. In some cases, however, as will later be mentioned, the exudation of water from cut or injured stems is brought about by forces generated in the living cells contiguous to the exudating region. In such cases “root pressure” is not the appropriate term to use. When water is exuded in considerable quantities from the stumps of cut stems or branches or from bore holes in the stem, as in the case of the grape vine, sugar maple, *Begonia*, or *Fuchsia*, the process has been termed “bleeding.” Some cut stems exude only a relatively small quantity of water, but there is no correlation between the amount of water exuded and the pressure with which it is being forced out of the stem.

The exudation pressures have been measured by manometers fitted to a bore hole in the side of large stems or to the stump, as in the case of the smaller stems or branches. Although many studies have been made of exudation pressures, the data concerning their value are very meager. Boehm (1892) found exudation pressures as high as 9 atmospheres in *Aesculus hippocastanum*, and Molisch (1902) reported pressures of over 6 atmospheres in the native trees of Austria. Clark (1874) reported root pressures of 2 to 2.5 atmospheres for *Betula lenta*, about 1 atmosphere for

the sugar maple and 1.25 atmospheres for the grape vine. Eckerson (1908) studied the exudation pressures of the stumps of over 20 herbaceous plants growing under greenhouse conditions and found that they ranged from 0.43 to 1.4 atmospheres. MacDougal (1925) found that pressures of from 2 to 4 atmospheres developed in bore holes in the side of the trunk of Monterey pine. The pressures observed will depend to a considerable degree, however, upon the general conditions prevailing at the time the observations are made.

It has generally been assumed that the exudation of water from cut stems and branches is due to the action of the cells of the root. There is considerable evidence, however, that exudation pressures are due, in many cases at least, to the action of cell masses contiguous to the cut surfaces (Molisch, 1902). It was considered by MacDougal (1925, 1926) that his work on the exudation pressures of the Monterey pine and the cactus *Carnegiea gigantea* indicated that the pressures developed were due to the local action of the living cells. Thus in the pine no root pressure could be observed, but exudation pressures as high as 4 atmospheres were observed in the stem. In the case of the cactus, exudation pressures as high as 2 atmospheres could be developed when no roots were present, and root pressure was thereby entirely absent. In the cases of guttation from epithem hydathodes, or in the case of continuous loss of water from a cut stem for a considerable period, as in the grape vine, the exudation is apparently caused by the action of certain cells of the root or stem other than those contiguous to the regions of water loss.

In this connection the sap flow of the sugar maple should be mentioned. As is well known, large quantities of sap will escape from this tree during late winter and early spring through tap holes made in the lower part of the trunk. The causes for this escape of sap have long been a subject of discussion and are as yet little understood. Jones, Edson, and Morse (1903) found that the root pressure was very infrequent and that when it was observable it did not exceed 1.5 atmospheres. On the other hand, negative pressures were frequent during the time of flow and reached values as high as 6 atmospheres. They thus consider that the flow of sap cannot be attributed to root pressure, since the small positive pressure thus developed is too infrequent and slight to be the main causative factor. Gas expansion in the conducting elements occurs during the time of flow, but the force thus generated is considered to be inadequate to account for the results obtained. Jones, Edson, and Morse considered that the activities of the protoplasm of the living cells of the xylem are the dominant factors in causing this sap flow. They consider that the changes in temperature and the changes in gas pressure within the trunk are the stimuli which cause the protoplasm to become active.

Since the gradient of absorbing power for water increases from the epidermal cells of the root through the cortex to the endodermis, the migration of water from the epidermis to the endodermis can be attributed to osmotic and imbibitional forces provided that a saturation deficit is maintained at the endodermis. In the leaves in the cases that have been examined, there is an increasing gradient of the absorbing power of the cells for water from the xylem elements of the veins across the chlorenchyma cells to the intercellular spaces. Here the movement of water from the veins toward the intercellular spaces may be explained on the basis of osmotic and imbibitional forces provided a saturation deficit is maintained at the cell surfaces bordering upon the intercellular spaces.

The manner in which the water is transferred from the cortical cells of the root to the xylem elements and then forced upward is not known. The theories which have been proposed to account for root pressure are purely speculative or at the best are based upon very meager evidence. Little or nothing is known concerning the osmotic conditions of the parenchyma cells and xylem elements within the central cylinder of the root and in the conducting tissues of the stem. In the few studies that have been made, the suction force of the parenchyma cells of the central cylinder as well as the surrounding endodermal cells was found to be lower than that of the cortical cells. Whether this osmotic relationship is of common occurrence in plants, however, is not known. If it were, the entrance of water into the central cylinder by the ordinary methods of diffusion would not occur.

The structure of the endodermis suggests that it plays an important part in the entrance of water. The term "endodermal pressure," which is sometimes applied to the force which causes the exudation of water from cut stems, was so named because it was assumed that the endodermal cells force the water into the central cylinder of the root. If the endodermis is designated as the organ that forces water into the central cylinder and thence up through the stem, the nature of its action, according to our present knowledge of osmotic relationships, can be expressed only by saying that it is a process of "secretion" or "excretion." The use of these terms, however, is only an indirect way of stating that we know nothing concerning the manner in which the endodermis functions in the entrance of water into the central cylinder of the root.

Priestley (1920) and Priestley and Armstead (1922) formulated a theory of the mechanism by which exudation pressures might be developed. They considered that the solute concentration of the xylem, in certain regions at least, is maintained at a higher level than that of the adjoining cells and that this supply of solutes is maintained by the endodermis which prevents their outward leakage. They obtained evidence which indicated that the parenchyma cells around the xylem but within

the central cylinder have specially permeable protoplasmic membranes that permit the exchange of organic substances between their cell sap and the solution in the xylem tubes. This exchange of solutes appears to involve both physical adsorption and physiological absorption. If the concentration of solutes in the xylem elements is greater than that in the cells adjoining them, it is easy to explain the entrance of water into them and the development of an exudation pressure.

Priestley and Armstead (1922) noted that the solutes which are present in the xylem sap of the grapevine are both organic and inorganic. It was observed that as the organic solutes fell in quantity in the sap of a cut vine, the exudation pressure began to fall while the supply of inorganic solutes still remained approximately constant. The organic solutes were thus considered to be more directly responsible for the osmotic pressure effective in causing the flow of sap. In the case of the grapevine, the organic solutes are principally the disaccharose and monosaccharose sugars.

Priestley and Armstead were able under suitable conditions to produce exudation pressures in stem and leaves as well as in the roots. In some instances, however, these pressures in the stem and leaves were only temporary, since the absence of a functional endodermis permits too rapid a leakage of the necessary solutes from the xylem for these pressures to be long maintained. In order to account for the fact that the water of guttation contains only a relatively small amount of solutes, these authors assumed that the solutes are absorbed from the xylem by the bordering cells during the upward passage of the sap. They thus assume that in one region the sap in the xylem vessels may be receiving solutes from the surrounding cells, while in another region the same solute may be diffusing away from the xylem into the neighboring tissue.

b. High Evaporation.—As is well known, the greater portion of the water lost from plants is lost under conditions of relatively high evaporation. Under such conditions the water in the conducting elements of the xylem is under tension due to negative pressure, so that if a branch or stem is severed, water will be drawn into the cut ends instead of being forced outward. On that account, it has long been recognized that under conditions of high evaporation, root pressure or endodermal pressure is not the main force in causing the movement of water through the stem to the leaves. It has been almost universally considered that the forces which are operative in causing the upward movement of water reside in the stem and leaves, but the nature of these forces and even the cells concerned in the process have not, as a rule, been established with any degree of certainty.

The ascent of water in trees has especially attracted the attention of investigators, since the large quantity of water which is lost from them, the great distances that it has to be moved, and the great amount of

energy that must be expended to bring this about are striking. On that account, most of the studies on the ascent of water have been confined to woody plants and most of the theories proposed to account for this phenomenon have been based upon the conditions which are known to prevail or considered to prevail in woody stems. It is beyond the scope of this work to discuss in detail all the theories that have been proposed to account for the ascent of water in plants. Many of these theories are at present only of passing interest, since they were based upon conditions that are now known not to exist in the plants. A thorough and critical review of the literature on this subject may be obtained by consulting Copeland (1902) and Dixon (1910, 1914), and the student who is interested in this regard is referred to these sources for detailed information. It is the intention here to mention only briefly the earlier theories that have been proposed to explain the ascent of water in stems and to confine the discussion principally to the ideas that dominate the field in this regard at the present time.

The theories that have been proposed to explain the ascent of water in plants under conditions of high evaporation may be divided into two main classes: (1) vital and (2) physical. The authors of the vital theories assume that the forces that are active in raising water in plants are manifested, for the most part, by the living cells of the root, stem, and leaves, although most of them consider that purely physical factors may assume a definite, although a minor, part. Those who propose the physical theories contend that the major forces concerned in the elevation of water are purely physical in their nature and consider that their manifestation by the plant is identical or very similar to that which would occur in a purely physical apparatus under like conditions. Most of those who favor the physical explanation of the ascent of sap agree that the living cells of the plant play their part in the process, although their action is classed as of only minor importance. The matter of contention between the advocates of these two theories is thus apparently a question of whether vital or purely physical forces are the dominant ones in the process. It would seem that the forces which are dominant might depend upon the conditions surrounding the plant. Thus under some conditions, as, for example, low evaporation, vital forces might be the dominant ones while physical forces might be exerting only a slight influence. Under another set of conditions, as for example, under conditions of high evaporation, physical factors might dominate the process and thus overshadow the activity of the living cells.

1. *Vital Theories*.—Westermaier (1883 to 1884) formulated one of the first vital theories in regard to the ascent of water. He considered that the upward passage of water in the stem was effected in the wood parenchyma, while the tracheids and vessels acted as water reservoirs rather than conducting elements. Godlewski (1884) assumed a periodic change

in the permeability of the protoplasmic membranes of the cells of the medullary rays of the xylem on which account water was taken up on one side from the bordering xylem elements and then released into the xylem elements bordering upon the upper part of the opposite side. This was considered possible since it was assumed that the air pressure in the conducting xylem at the upper portion of the medullary ray was lower than the pressure inside those xylem elements in contact with the lower part of this ray. Janse (1887) supported the idea of Godlewski and was one of the first to note that if the lower portion of a branch be killed, the leaves above are affected within a few days. These theories, however, were proposed upon little or no experimental evidence and upon the assumption of certain conditions in the stem that are now known not to exist.

The later advocates of the vital theory of water ascent have been Ursprung (1905 to 1907), Ewart (1905, 1906, 1908), Schwendener (1892, 1909), Leclere du Sablon (1910), Bose (1923) and Molisch (1928 to 1929). These advocates, however, base their assumptions upon a considerable amount of experimental evidence which, while convincing them of the nature of the forces involved in the ascent of water in plants, has not so appealed to many other workers in this field. Ursprung and Ewart, while agreeing that certain physical forces play a prominent part in the ascent of water, consider that the process is dependent to a certain extent upon the living cells of the stem. They consider that their experimental evidence indicates that the continuous ascent of water in the xylem is possible only in the presence of its living cells. The exact functions, however, that these living cells perform are not clearly set forth. Bose and Molisch, however, attribute the ascent of water practically entirely to the physiological activity of the living cells of the plant. The work of Bose (1923) has attracted much attention and on that account will be mentioned here in considerable detail, together with some of the adverse criticisms of the methods used and of the conclusions that he has deduced from his experimental evidence.

Bose observed by means of special apparatus that the cells of the lower and upper halves of the pulvinules of the lateral leaflets of the telegraph plant (*Desmodium gyrans*) execute alternate contractions, the period of a complete pulsation varying according to the circumstances from one minute to four minutes. Bose also claimed that by means of proper apparatus pulsating activities are noticeable in growing regions of the plant. These growth pulsations consist of a series of alternate expansions and contractions. It was ascertained that these pulsating activities can be modified in very definite directions by changing the physiological conditions. Thus pulsatory activity is depressed or arrested under diminished internal pressure. A rise of temperature stimulates it while a fall in temperature depresses it. A small amount of an anesthetic increases this rhythmic activity, while it is completely stopped by poisons.

Bose observed that the ascent of sap is modified by the same conditions that so strikingly affect the pulsatory activity. Thus, diminished internal hydrostatic

pressure causes a depression in the ascent of sap, a rise of temperature increases the rate, and a fall in temperature depresses it. Small doses of an anesthetic increase the ascent of sap, while larger doses arrest it. Poisons also arrest the ascent of sap. From these observations Bose concluded that he had "proved conclusively that it is the pulsatory activity of living cells which maintains the ascent of sap in plants." He considered also that the response of transpiration to various factors indicates that it is "not a physical process but a physiological one carried on by a rhythmic tissue forming part of a rhythmic system continuous throughout the plant for the absorption and distribution of water." Thus he considered that transpiration is a physiological excretion of water by the leaf cells, the excreted water being removed by the physical process of evaporation. He also considered that the excretion of water can be shown when the leaves are covered with vaseline and considered that this is a further proof that transpiration is an active physiological process.

By electrical methods Bose considered that he demonstrated that a definite layer of tissue, the innermost layer of the cortex in dicotyledonous plants, is in a state of active pulsation which consists of alternate contraction and expansion. He thus concludes that these are the cells that carry the water upward. Since there is no such pulsatory activity to be observed in the wood, Bose considered that the xylem is by no means essential for the conduction of water and that it acts only as a reservoir, the water being pumped into or withdrawn from it according to different circumstances.

Molisch (1928, 1929) reported that he successfully repeated some of the experiments of Bose. In one experiment he employed a cut piece of stem of *Antirrhinum* which was held at the cut end by a piece of sponge. When the water supply was low the leaves on this stem became badly wilted. A few drops of a dilute solution of camphor applied on the sponge, however, caused the leaves to revive quickly and become fully erect in the course of 2 or 3 min. The results of this experiment are thought to be indicative of the fact that the movement of water in a plant is a physiological rather than a physical process. By means of one of the instruments of Bose, Molisch reported that the flow of sap along the stem was observed to consist of a series of pulsations. These pulsatory activities were greatly increased by drugs which enhance cardiac activity in the animal. Molisch states: "There is an inherent activity in the stem itself, independent of those in the leaves and roots which cause the movement of sap. The sap can be made to flow either upward or downward according to different stimulation. The law of directing movement of sap is that it moves from the stimulated to unstimulated or depressed regions. A local depression or stimulation starts the machinery into action and makes the sap proceed toward the depressed or away from the overstimulated region."

Dixon and his workers (1924) repeated certain phases of Bose's work but were unable to verify his results. The work and conclusions of Bose have been adversely criticised by Shull (1923), MacDougal and Overton (1927, 1929), and Benedict (1927). One of the chief criticisms is that the relationship of the pulsations or rhythmic activity reported by Bose and Molisch to the ascent of sap has not been definitely established. It does not follow that because pulsation activities and the ascent of sap respond in a like manner to the same factors, one is the cause of the other. The method of determining the rate of water ascent by noting the time it took a wilted leaf to show signs of recovery when the stem is supplied with water is considered to be untenable. The fact that the leaf shows signs of recovery does not indicate that the water which has entered the stem has ascended to the leaf in that time any more than water which comes from the nozzle of a full garden hose is the identical water which at that instant has entered the distal end of the hose (MacDougal and Overton, 1927). It has been estimated that the pulsatory movement of sap claimed by Bose (1923) and Molisch (1928 to 1929) would imply a transfer through 200 to 400 living cells

per second. Benedict (1927) measured the cross-section area of the living cells in the tree trunks of 10 different species and computed the maximum pumping capacity of the most rapid pulsating rates found by Bose. The actual rate of sap flow under maximum conditions of transpiration proved to be from eight thousand to thirty thousand times as rapid as would be possible under the theory proposed by Bose.

It appears evident under the conditions of high evaporation that all the forces which function in the ascent of water in plants cannot be attributed to the direct action of living cells. The living cells, however, evidently play an important part, especially those of the roots and leaves. Whether those in the conducting tissue play any part is evidently not definitely known. Dixon (1924) states that the facts that water rises in stems of plants even when surrounded by a saturated atmosphere and that dead leaves inadequately draw up water indicate that the living cells play some part in the ascent of sap. It would be safe to state that the living cells of the roots and leaves at least maintain good contact and thus keep intact the passageways across them for the movement of water even if they do not in themselves exert any vital force in the ascent of water in the stem.

2. *Physical Theories.*—Under this heading are grouped those theories which assume that the ascent of water is for the most part due to purely physical forces and that the living cells of the stem play only a minor part in the process. Before discussing the physical theories of the ascent of sap, however, some of the experimental evidence which has been presented to show that the living cells are unessential in the ascent of water should be mentioned.

(a) *Absence of Living Cells.*—The general method of procedure that has been followed to demonstrate that the living cells of the stem are not concerned in the ascent of sap has been to kill a portion of the stem by exposing it to hot water, steam, or chemicals or to place the cut end of a branch into a solution of a chemical which is known to kill protoplasm when in contact with it. These methods, however, are subject to criticism, as will later be mentioned.

Boucherie (1840, 1841), while injecting timber with various compounds in order to test their effects upon its preservation, found that if a tree were cut across at its base and supplied with a poisonous solution, it drew this liquid up to its highest leaves. It would also draw up a second solution if supplied. The significance of this experiment in the ascent of sap, however, was apparently not recognized by this investigator or by contemporary botanists. Boehm (1889) noted that if a portion of a stem were killed, water would still ascend to the leaves, but the classical work of Strasburger (1891 to 1893) gave the first conclusive evidence that the living cells of the stem are at most of only minor importance in the ascent of water. He placed the base of cut stems in poisonous solutions among which were copper sulphate and picric acid. In the case of branches set in a 5 to 15 per cent solution of copper sulphate, the liquid rose to a height of from 6 to 20 m. in from 16 to 20 days. In another experiment he killed the branches for a distance of 10 to 12 m. at the basal end with boiling water and observed that eosin rose in them from the cut end to a height of almost 17 m.

The leaves at the uninjured end of the stem, however, remained alive for only a few days when they dried up and fell off. In another experiment Strasburger used a young oak tree 22 m. in height. This was sawed off near the ground and kept upright with the lower end in a solution of picric acid. After 8.5 days it was found that the highest branch was completely impregnated with picric acid, while fuchsin which had been added 3 days later than the picric acid was also found in the same regions. Roshardt (1910) performed experiments on 131 species of plants, including shrubs and herbaceous plants of 59 families, by killing portions of the stem, branches, or petioles by steam, ether, low temperatures, or other means and then determined the effect of this treatment upon the sap flow. A considerable number of his experiments were made upon grasses among which were *Poa pratensis*, *Bromus sterilis*, *Bromus hordeaceus*, *Agropyrum repens*, and *Secale cereale*. He noted that water ascended the stem for a considerable time after certain portions of the lower part had been killed but that the leaves dried up after from 8 to 17 days. There was no distinct wilting, but the leaves began to dry at the tips.

Overton (1911) in experiments with the umbrella plant (*Cyperus alternifolius*) found that when 5 to 10 cm. of the stem was killed by treatment with picric acid, 95 per cent alcohol, or copper sulphate for 36 to 48 hr., sufficient water ascended through the poisoned portions to supply the transpiration needs for 90 days and to allow the development of new branches.

MacDougal, Overton, and Smith (1929) sawed off a willow tree 11 cm. in diameter and about 8 m. high and placed it upright with the basal end in a concentrated solution of picric acid. It was allowed to transpire for 4 days, after which it was transferred to acid fuchsin. In 4 days the tree absorbed 10 l. of the picric acid solution and about the same amount of acid fuchsin in the succeeding 4 days, both solutions being drawn up the tree for a distance of 6 m. This experiment was repeated with a walnut tree 10 cm. in diameter with results very similar to those observed for the willow.

The results obtained from the experiments which have just been mentioned indicate that the living cells of the stem play no important rôle in the ascent of sap. There has, however, been some question of the conclusions drawn from these experiments. It is pointed out that the killing of the cells in a given length of the stem does not show that those living cells above or below the injured portion are not concerned in the process. Some suggest that even though poisonous solutions are drawn up the stem, some of the living cells may not be injured. In the experiments in which the stems have been immersed in poisonous liquids, the leaves remain alive for only a relatively short period of time after the treatment. It has been contended that the leaves should remain alive for a long period of time after such treatments if the death of the living cells of the stem has no influence on the ascent of water. In the cases where a portion of the stem has been killed by the various means, Dixon (1905, 1909, 1915) and Overton (1911) considered that the leaves are not injured because of a lack of water being moved to them through the dead stem but by the transportation to them in the water stream of poisonous or plasmolytic substances which have been formed by the decomposition of the cells in the treated region. Both of these investigators noted that the leaves showed injury in proportion to

the length of the stem that was killed. This opinion was further substantiated by Dixon, who forced water through a steamed portion of the stem and found that it was tinged with a brown substance, while the water which was forced through an untreated stem emerged a clear liquid. Some of the investigators are of the opinion that the treatments of the stem cause the formation of substances which clog the lumina of the xylem elements and thus prevent the normal ascent of water. It has also been suggested that these treatments of stems might rupture the water columns and thus bring about a decrease in water movement. Roshardt (1910) considered that the decrease in water content under such treatment is due to the lack of energy which is normally furnished by the living cells and which the dead cells are unable to supply. It appears evident that the methods which have been used to render the living cells of the stems inactive in the study of the ascent of water bring about other changes in the stem which cannot be ignored.

(b) *Imbibition and Capillary Theories.*—The imbibition theory was proposed by Unger (1868) and championed by Sachs (1878, 1879), who became its chief exponent. This theory assumed that the water moved upward in the stem entirely in the walls of the xylem elements by the process of imbibition. It was considered that the creation of a saturation deficit in the cell walls at the top of a plant would cause a flow of water toward the point of loss from the adjoining portions of the cell wall and that this demand for water would thus be transmitted downward through the walls to the roots where it would be satisfied. The forces of imbibition are known to be sufficient to elevate the water in this manner much beyond the height of the tallest trees. The imbibition theory of the ascent of sap after the manner above mentioned, however, became obsolete when it was demonstrated beyond doubt that practically all the water moves upward in the lumina of the xylem elements. This fact, proved by numerous investigators among whom are Elfving (1882), Vesque (1884), Darwin and Phillips (1885), Errea (1886), Strasburger (1891), Dixon and Joly (1895), and Smith (1896), shows that if the lumina are blocked by gelatin, paraffin, ice, water vapor, or by compressing the stems until the lumina are closed, the supply of water to the upper portion of the plant is checked to the extent that severe wilting results. The ascent of water in the lumina is also demonstrated by means of dyes. There is no doubt that some water ascends in the walls of the xylem elements, but the amount is insignificant in comparison with that which moves upward through the lumina of the tracheids and vessels (Vines, 1896).

The elevation of water has been ascribed by some writers to the force of capillarity in the lumina of the xylem elements. The lifting power of a capillary is determined by the form and size of the meniscus of the liquid therein contained. The form of the meniscus is, in turn, influenced by the nature of the walls of the capillary. It was early recognized that the

lumina of the xylem elements are of such a size that their lifting power of capillarity is not very large and cannot account for a rise of water, according to Strasburger (1891), to distances exceeding 3 m. The terms "imbibition" and "capillarity" have been used more or less interchangeably by some writers. As here interpreted, however, capillarity is confined to small but well-defined lumina or tubes, while imbibition is confined to the submicroscopical pores or interstices of the cell wall.

(c) *Cohesion Theory*.—In 1894 Dixon and Joly published their cohesion theory of the ascent of water in plants. Askenasy (1895, 1896) independently developed a similar theory which was published shortly after the abstract of Dixon and Joly had appeared. This theory has been further elaborated by Dixon, and much work has been undertaken to substantiate it. It is so much in accord with the general conditions known to prevail in the plant and has been so well substantiated by experimental evidence that it has been almost universally accepted as the best explanation of the ascent of water in stems under conditions of high evaporation.

The cohesion theory of the ascent of water is based essentially upon the two following facts: (a) the cohesive force of water or the quality which water possesses of resisting tensile stress and (b) the imbibitional force of the evaporating cell walls of the leaf or the tractional force exerted by the water menisci of the submicroscopical cavities of these cell walls.

The cohesion theory of the ascent of water assumes that the water in the conducting tracts of the xylem exists in the form of unbroken columns and that these columns are continuous with each other both vertically and laterally through the cell walls. A continuous meshwork of water thus exists throughout the whole length of the stem, roots, and leaves. The terminals of this water meshwork are the menisci of the water in the submicroscopical cavities of the cell walls of the epidermal cells of the root and of the cells bordering upon the intercellular spaces of the leaf or of the epidermal cells. This theory also assumes that the water in the conducting tracts is brought into a state of tension by the imbibitional forces in the evaporating cell walls of the leaf and that these water columns are able to withstand the tensile pull which is thus exerted upon them.

Thus in the process of transpiration, water particles are set free from the menisci of the submicroscopical cavities of the cell walls of the evaporating cells of the leaf. This loss of water particles produces incipient drying or a saturation deficit, the menisci become more concave, and their surface tension is increased. As a result of this, water is abstracted from the protoplasm of the cells which the evaporating walls enclose. The protoplasm in turn abstracts water from the vacuole, so, on account of this disturbance in water equilibrium, osmotic and imbibitional forces are set in motion which abstract water from adjoining

cells or cell parts. This disturbance in equilibrium is transmitted eventually to the water of the xylem elements of the leaf. A pull is thus set up on the water in this conducting element, which, in turn, is carried down the petiole to the conducting xylem elements of the stem and root and then to the soil. Due to the weight of the water columns and to their adhesion to the walls of the conducting tracts, the water is, under the conditions above mentioned, thrown into a state of tension which may in some cases be as great as 200 atmospheres (MacDougal, Overton, and Smith, 1929). As a result of this pull exerted by the water menisci of the evaporating cell walls of the leaf, water is moved upward through the root and stem to the leaves.

Under conditions of high transpiration the tensile stress of the water in the stem and roots must be transmitted across the cortex of the root to the submicroscopical cavities of the outer cell walls of the epidermal cells of the root. On this account, as the menisci of the evaporating cell walls of the leaf become more concave, the menisci of the exterior cell walls of the epidermal cells behave in a similar manner. The rendering of the menisci of the evaporating cell walls of the leaf more concave tends to bring them in equilibrium with a lower vapor pressure and consequently reduces evaporation, while the increased concavity of the menisci in the epidermal cells of the root renders them more ready to condense water vapor. The menisci of the cell walls of the epidermal cells of the root entrap the more active molecules of water, while the menisci of the evaporating cell walls of the leaf retain the less active ones. Dixon (1910) states:

Thus we may regard the flow of water up the highest tree as due to the evaporation and condensation produced by the difference between the vapor pressure at the surface of the epidermal cells and that which obtains in the cell walls of the evaporating cells of the leaf.

There is some dispute as to what part the osmotic forces of the cells of the mesophyll of the leaves and the cortex of the roots play in the ascent of water. It is considered that these forces at least keep these cells turgid and thus prevent them from collapsing under the tension which pulls the water across them. The osmotic pressure of these cells, however, must equal or exceed the tension in the water which crosses them (Dixon, 1896).

Dixon (1914) considered that the loss of water by a plant under conditions of very low evaporation might be a process of secretion by the mesophyll cells of the leaves. If this is true, the energy which is necessary for the lifting of the water is considered to be supplied by respiration. Dixon estimated that the energy necessary to raise a cubic centimeter of water 100 m. in a tree and to overcome the resistance would amount to only 0.5 cal. To evaporate a cubic centimeter of water at 20°C. requires

592.5 cal.; hence, in order to obtain the energy needed to raise the water in a 100-m. tree the amount evaporated would be diminished by only one-thousandth part. Even taking the highest and most excessive estimate of the resistance in the highest trees, the amount of water evaporated would be reduced by only one-hundredth to one-thirtieth if, in addition to evaporation, the energy absorbed by the leaf had to do the work of transporting the water from the roots. If under conditions of extremely low evaporation water is excreted from the leaf cells, ample energy can be derived from respiration to lift the water to the tops of the tallest trees.

In a discussion of the cohesion theory of the ascent of water, the experimental evidence which has been obtained in an attempt to prove or disprove its validity should be briefly reviewed.

The cohesive force of water has been known since about 1850, and, according to Copeland (1902), Nägeli (1866) first suspected its importance in the ascent of water. The publication of the cohesion theory of the ascent of water greatly stimulated interest in the cohesive properties of water, and studies in that regard have been reported by Dixon (1910, 1915), Ursprung (1913, 1915, 1916), and Renner (1915). These investigators all found that water has great cohesive power and demonstrated that the tensile strength of water containing dissolved air is at least 300 atmospheres. It has been shown that the xylem sap has a greater tensile strength than pure water and that when it is in position in the conducting xylem it may withstand tensions greater than 300 atmospheres without separating from the walls of these conducting elements.

It has been shown by Dixon (1914) that the resistance of a current of water moving through wood at the velocity of the transpiration stream is equivalent to a head of water equal in length to the wood traversed. In a tree 100 m. in height, the tension of the ascending water would be approximately 20 atmospheres, a force which would in no way tax its cohesive powers.

The force of imbibition in the evaporating cell walls of the leaves is enormous and is much more than ample to lift a column of water to the height of the tallest trees. It has been estimated that a saturation deficit in these evaporating cell walls of the leaf of one-tenth of one per cent would exert a pull sufficient to lift water to the top of the ordinary annual plants. Ursprung (1925) proved that the suction power of the vacuoles of the leaf cells would furnish ample force to move the column of water in stems at an adequate rate to replace the water evaporated from the leaves provided osmotic forces play a determining part in the lifting of the water in the stem.

It was calculated by Dixon (1897) that it would require a pressure of 100 atmospheres to tax the cell walls of the mesophyll cells of the leaf to their breaking point. Thus it is apparent that the osmotic pres-

tures of the leaves never seriously tax the tensile strength of these cell walls.

Renner (1911 to 1912) measured the suction force of transpiring twigs and found under the conditions of his experiment that it amounted to 10 to 20 atmospheres. He considered that the saturation deficit in the leaves was the cause of the water movement in the stem. By applying artificial suction to the leaves at a time when no saturation deficit existed, he determined the rate of flow produced by a given suction force. The rate of flow through the stem was then determined when rapid transpiration was proceeding, and the suction that was being exerted by the leaves was calculated from these data, since it was considered that the rate of flow through the stem was proportional to the suction forces exerted by the leaves. Nordhausen (1916, 1919, 1921) showed that suction forces exist in the leaves, although by his methods he did not obtain so high values as did Renner. In this connection it should be mentioned that Thut (1928) devised an apparatus which shows definitely the lifting power of evaporation under ordinary laboratory conditions.

If the water in the xylem elements is thrown into a state of tension by the suction forces of the leaves, these elements should show a contraction when transpiration is proceeding and should again expand when transpiration decreases or ceases entirely. MacDougal (1921, 1925 to 1926) and MacDougal and Shreve (1924) have observed that the trunks and branches of trees show daily alterations in diameter. This swelling and shrinking was attributed to changes in the wood due to changes in the transpiration rate. It was found that variations in diameter depended directly upon the depletion and repletion of the water supply of the wood, and the effect of increasing tension in the water upon the diameter of the conducting elements was noted. Bode (1923) made a direct microscopical examination of the vessels of wilted plants and found that they would shrink with increased transpirational pull and that they would expand again when the transpiring surfaces were removed from the plant. The experimental evidence that has been obtained relative to the cohesion theory of the ascent of sap has thus, for the most part, tended to substantiate it. ✓

4. Downward Movement of Water.—It has been known since the time of Hales (1727) that under certain conditions there may be a downward as well as an upward movement of water through the xylem. A few examples of this downward movement selected from the literature are cited herewith. Hales (1727) among other observations noted that a forked branch cut from a tree will remain fresh and continue to transpire for many days provided that one limb of the fork with its leaves is immersed in water. Dixon (1924) states that if the tip of an upper leaf of a potato plant is cut under an eosin solution, the colored liquid is quickly drawn back into the conducting elements of the xylem of the

leaf and thence into the same tissue in the petiole. From there it not only makes its way into the upper branches and leaves but also passes down the stem supporting these parts and into the xylem tissue of the tuber.

Mason and Maskell (1928) found in the case of the cotton plant that an eosin solution taken in through cuts in the leaf blades was in 6 hr. found to have penetrated both upward and downward in the xylem. The stain passed in with the foliar trace and occupied a medium position in the wood, the peripheral region of the wood being unstained.

Arndt (1928) studied the movement of solutions through the xylem of the coffee tree. In one case the terminal internode was cut and an eosin solution applied through a funnel and rubber tube. In 15 hr., 50 cc. of the solution was absorbed and the corollas of flowers in lateral branches 80 cm. from the cut internode were stained. In 23 hr. after the beginning of the experiment all the leaves of the trees were stained and the total distance of eosin movement exceeded 200 cm. In one the stain descended 125 cm., passed horizontally 60 cm., and then ascended 100 cm. In none of the experiments did the eosin solution in moving either up or down the stem pass through the cambium into the phloem, and the cut surface of the phloem in contact with the dye did not conduct it. MacDougal (1925) noted that the outermost wood of the Monterey pine is not the path of an upward-moving current in the normal tree, but he could not, however, demonstrate a downward moving current in that part of the xylem. The path of reverse currents has been traced by Birch-Hirschfeld (1920) by means of lithium nitrate and eosin.

The examples that have been cited above leave no doubt in regard to a downward current of water in the xylem. The cause of this movement, however, is not definitely known. Dixon (1924) considers that these reversals in the current of water are readily explained by the cohesion theory of the ascent of water. He argues that since transpiration causes the water in the conducting xylem to pass into a state of tension, this tension determines a flow from any source wherever situated and the continuous transpiration from the leaves draws the supply through the plant along the channels of least resistance. This path of least resistance, however, is not always the shortest path in the wood. Transverse motion across several xylem-conducting elements seldom occurs and the separate linear series of conducting elements are practically isolated from each other laterally. On that account, Dixon considered that this enables the tension developed by the transpiring cells of the leaves, while it raises a water column in one series of the conducting xylem, to draw a solution in a neighboring filament of xylem elements terminating above in some local supply.

Arndt (1929) noted that during the daytime when the leaves are actively transpiring, the eosin solution moved upward more rapidly than downward but that at late evening, at night, and in early morning

the downward movement was not greatly reduced, while the upward movement was so greatly reduced that the downward movement exceeded it. Arndt considered, since only slightly reduced downward movement occurs at night and since topping a plant affects this movement but little, that it is independent of transpiration. If the postulation of Dixon (1924) that there are separate conduits for transportation in each direction is correct, Arndt considers that in the case of the coffee tree these conduits are so close together that a microscopical examination after short-interval experiments does not show stained and unstained areas as would be expected. He considers that the observations indicate that living cells other than the leaf must play an important rôle in sap conduction, since it does not seem probable that there could be simultaneously ascending and descending streams unless there are conduits which are hydrostatically isolated from each other by an impermeable partition of living cells.

5. Lateral Movement of Water.—The data concerning the lateral transfer of water in stems are very limited and the observations in that regard have been confined almost entirely to woody stems. It is known that the lateral transfer is very slow and that translocation in a radial direction usually takes place more slowly than it does in a tangential direction. In many cases, the location of pits in the conducting xylem elements is such as to facilitate translocation in a tangential direction while the medullary rays offer passageways for radial transfer. MacDougal, Overton, and Smith (1929) consider, however, that the movements which take place through the medullary rays are largely or wholly osmotic and that mass movements in a radial direction do not occur except possibly in some cases in the pines where the medullary-ray cells are of a tracheid nature.

Experimenting with a 13-year-old willow, they found that there was no radial transfer from one annual layer to another. Thus when dye was injected into the oldest 10 annual layers of this tree in such a manner as to exclude the dye from the outermost 3 layers, they found that to the height of the 10-year level there was no dye in the outer three annual layers. There was, however, a tangential movement of the dye in those annual layers to which the dye had access, and at a considerable distance above the bore hole the tangential movement in the summer wood was completely around the annual layer. The number of annual layers in which there was no dye remained constant from the bore hole to the 10-year level. The number of annual layers toward the center of the tree which contained the dye became progressively smaller until at the 10-year-old level only the innermost of the terminal portions of the wood of the tenth year showed the dye. These investigators considered that this experiment demonstrates that there is not a radial mass movement nor a radial transfer of the forces concerned in sap flow from one annual layer to another, through the living cells of the medullary rays or through abutting xylem elements. They consider, however, that the possibility exists for an osmotic transfer of water through these structures.

It was noted by MacDougal, Overton, and Smith (1929) that, although the injection experiments showed no mass movement in a radial direction from the inner to

the outer annual layers, the leaves at the tips of all branches above the bore hole showed the presence of the dye. Since these leaves are connected only with the wood of the current year and since there was no dye in this layer at the level of the bore hole, the question arises as to what path is followed by the transpiration stream in moving from the innermost layer of the xylem to the outmost one if there is no radial mass movement.

These authors explain this point by using as an example a 2-year-old unbranched stem. A stem of this type consists of a central column of xylem of the first year's growth whose terminal end is bluntly conical. This central column is surrounded by a thimble-shaped mass of wood whose upper half, which is the longitudinal growth of the present season, is solid. The lower portion, which is the lateral formation to the previous year's wood, is a hollow cylinder enclosing the last year's xylem. The leaves attached to the upper portion of the current year's growth exert a pull on the water in the xylem elements, and this is transmitted through the dome-shaped portion of the preceding year's growth to its conducting xylem. The transpiration stream thus moves from the xylem of the first year to that of the second year in a more or less vertical direction. The transpiration pull on the water columns of the first year may thus be transmitted to the columns in the xylem of the second year and thence to the xylem of the third year and so on to all the columns present in any annual layer.

It was noted by Arndt (1929), using a coffee tree, when a single lateral root was cut under an eosin solution, that a one-sided staining was evident to the top of the tree after a period of 20 hr. In another case, this one-sided staining was still evident after 72 hr., the staining of the leaves of the laterals corresponding to the stained sector of the xylem. As the top of the tree was approached, the dye gradually diffused tangentially so that all the branches tended to become stained. In some experiments it was noted that as the dye passed upward it tended to diffuse laterally, but in all cases the radial and tangential diffusion was slow.

Auchter (1923) obtained evidence which suggested that water may move laterally in the peach tree. When the roots were removed from one side of the tree, the total water content of the whole plant was reduced and the growth checked to some extent. The moisture contents on the two sides of the tree, however, were identical and the leaves on the cut side did not wilt on bright, clear days. Apparently in these trees water moved through and around the stem without much difficulty.

B. TRANSLOCATION OF INORGANIC COMPOUNDS

1. Upward Transfer.—It has been commonly stated in the literature since the time of Sachs that the water and inorganic materials are carried upward for the most part through the xylem. While it is apparently established beyond a doubt that the xylem is the pathway of the upward movement of water, the statements concerning the movement of solutes are apparently based upon very inconclusive evidence.

The xylem has been considered as the pathway of the movement of the inorganic solutes on account of the following evidence: (1) It has been assumed that since the inorganic salts are dissolved in the water of the soil and since the pathway of the water is in the xylem, these

inorganic materials would be absorbed and carried with it. (2) The inorganic salts have actually been found in the water-conducting elements and in the sap that has been obtained therefrom. (3) When cut stems are placed in solutions of dyes or salts, the solutes move for considerable distances in the xylem tissues. (4) Experiments in which the movement of dyes and salts has been studied in rooted and uninjured plants give indications that translocation of the solutes occurs in the xylem.

This evidence has been critically considered by Curtis (1923). He points out, as has been discussed in Chap. V, that it has apparently been definitely established that there is no direct relation between the absorption of water and the absorption of inorganic salts. He also considers that the fact that inorganic salts have been found in the sap of the xylem is not conclusive evidence that they are translocated in this tissue. He states that unless it is known that the water moves by mass flow through open tubes and not by diffusion or through occasional membranes, or unless it is known that neighboring cells do not remove solutes from a passing stream perhaps transferring them and reintroducing them at a lower level, the mere presence of these solutes in the xylem sap is no proof that they are being moved therein.

The methods by which the samples of xylem sap have been obtained may be open to question. Curtis considered that sap obtained from a cut or bleeding stem may be different from that in a normal uninjured stem, since the movement of water through a series of cell membranes may be different from the flow that would occur if the membranes were cut open. Some of the methods for obtaining sap may, however, be free from this objection (Bennett, Anderssen, and Milad, 1927). Objections may also be made to the method of placing cut stems in dyes and salt solutions, since normally the water-conducting system may be considered as a closed system with no actual openings. Curtis considered that numerous sources of error have been overlooked in the experiments in which the translocation of salts and dyes has been studied in intact plants so that the results obtained have given no clear indications of the tissues concerned in the movement of the inorganic salts.

Curtis (1923 to 1925) conducted experiments to determine if the phloem is concerned in the translocation of the inorganic salts. The general method used by him was to ring twigs or branches by a complete or partial removal of the bark or to remove a portion of the xylem and to study the effect of this ringing upon the upward movement of nitrogen, ash, and carbohydrates. In these experiments all the ring wounds were covered with warm paraffin to prevent the entrance of bacteria and to prevent the tissue from drying out.

In the experiments with privet, peach, and lilac, the branches were selected in pairs, so the ringed and control branches were similar in size and position. Immediately after ringing, nitrogen as NaNO_3 was added

to the soil. In some cases, CaCl_2 and NaCl were also added. Observations were made upon the leaves above the ringed portions for area, dry weight, ash, and nitrogen content, and these quantities compared with those of the leaves from similar regions of the control branches. In the case of the peach, the total amount of nitrogen moving up the unringed stem was evidently much greater than that moving up the ringed stem, since there were from 10 to 20 times as many leaves on the control stem and they were from 30 to 70 per cent larger than those upon the ringed twig. With the lilac the control leaves contained 1.8 to 2.2 times as much nitrogen per unit of dry weight as those from the ringed stem. The ash analysis also indicated that ringing hinders the movement of inorganic salts, since the check leaves contained from 1.5 to 2.0 times more ash than did those from the ringed stems.

In one series of experiments, Curtis (1925), by technique which need not be described here, completely severed the xylem in one portion of a split stem, leaving the phloem intact. In another series, the xylem on one portion of the stem was left intact and the phloem severed by ringing. By the use of such divided stems where water was supplied by one set of roots and nitrogen by others, data were obtained which indicated that if the roots supplied with nitrogen were connected with the top by the xylem only, there was little transfer of nitrogen to the tops, while if they were connected by a strip of phloem only, considerable transfer of that element occurred.

Curtis also found that if a narrow band or strip of phloem containing from one-tenth to one-fourth of the normal amount was left intact in ringing, the transfer of solutes was normal. It has been shown many times that a small portion of the xylem cylinder will carry sufficient water to keep the leaves apparently normal. Curtis (1925) considers that since a small amount of the phloem is sufficient to allow for an approximately normal solute transfer while its complete severance causes a marked reduction and since a small part of the xylem is sufficient to allow for approximately normal water conduction, while its complete severance practically stops water movement, it would appear that water moves chiefly in the xylem and solute movement occurs chiefly in the phloem.

The observations of Anderssen (1929) in regard to the tracheal sap of the pear tree, however, indicate that the xylem functions in part in the translocation of the inorganic solutes. Thus he found that the individual inorganic constituents of the tracheal sap showed a large increase in concentration from early winter until early spring. From Nov. 10 to May 10 the calcium increased from 16.6 to 84.7 ppm., magnesium from 0.8 to 23.5 ppm., potassium from 23.6 to 59.6 ppm., and PO_4 from 10.6 to 25.2 ppm. On May 10 the calcium, magnesium, and PO_4 ions far exceeded their concentration in the soil extract. The total

electrolytes were almost twice as concentrated in the outer annual ring as in the inner rings.

Maskell and Mason (1930) noted in the cotton plant that the absolute amount of nitrogen in the wood of the lower part of the stem was about equal to that in the bark but that the variation in the wood in response to variation in supply and demand was about twice that in the bark. They considered that these data were in accord with the view that the bulk of the mineral nitrogen absorbed by the roots is carried in the transpiration current to the leaves where it is elaborated to amino acids and other nitrogenous compounds and then moved downward in the plant through the sieve tubes.

The most serious objections that have been offered to ringing experiments is that the xylem may be altered by the ringing. Numerous authors have reported that tyloses or gums may plug the xylem elements in the region of a ring or other wound. In many of the cases, however, that have thus been reported, no precautions were taken to protect the exposed xylem. Even when the ringed portion is protected by wax, vaseline, or paraffin, the xylem is in some way affected by the ringing, since it has been noted that under these conditions there is an increased resistance to the flow of water through it. The xylem, however, at the most, in well-managed experiments is only partially plugged, and this partial plugging cannot fully account for the hindrance in solute movement when the phloem is severed.

There seems to be strong evidence which indicates that the inorganic solutes move upward in considerable amounts through the phloem. The cases of translocation, however, which have been studied are relatively few and have been confined to only a few species of plants. On that account, a much greater number and variety of plants must be studied before any general conclusion can be drawn.

2. Lateral Transfer.—The lateral transfer of inorganic solutes has received some attention. The most thorough work in this regard was done by Auchter (1923), who studied the lateral transfer of nitrates in 10-year-old peach trees, 5-year-old apple trees, 3-year-old privet bushes, and 5-year-old oak trees. In these experiments some plants received nitrates about all their roots, some had nitrates applied to only one-half of their roots, while others had all their roots removed from one side and nitrates applied evenly under both sides. In practically all cases, the leaves increased in nitrogen content per unit of dry weight, per unit of green weight, and per unit of area on the nitrated sides. The leaves on those halves which had not received nitrate actually lost nitrogen in the cases where analyses were made before and after treatments. The check halves of the trees acted much the same as full-check trees, while the nitrated halves responded approximately the same as fully nitrated trees. In one experiment with Grimes Golden apple trees, the soil was

cultivated on one side for 2 years, while the other side was not. The average terminal growth of the branches on the side that had been cultivated was 12 to 14 in., while that on the uncultivated side was only 3 to 4 in. It was considered that the additional nitrates in the cultivated soil were responsible for this difference in growth and that it indicated that they were used by the halves of the trees which were directly above the cultivated areas. Similar results in regard to fertilization and cultivation have been obtained by Blake (1921) for peach trees and by Knowlton (1921) for Roman Beauty apple trees.

In the case of dormant privet cuttings transplanted so that one-half of their roots were in quartz sand and the other half in fertile soil plus nitrate, Auchter (1923) found that the two halves of these stems broke their rest period unevenly. The sides above the fertile soil started to grow 3 weeks sooner and had made twice the amount of growth after a period of 5 weeks. Since nitrates are known to break the rest period of plants, it was considered that they had moved upward in the stem only on the side to which they were presented to the roots and that there was little or no lateral transfer.

From these studies of woody plants it appears that the mineral nutrients absorbed by the roots on one side of a plant are, in a large measure, translocated to and used by the trunk, limbs, and leaves directly above them and that there is very little cross-transfer of such nutrients in the plant. Since there are some indications of the cross-transfer of water in stems, the mineral nutrients evidently travel independently of the water movement.

In the case of the corn plant, Gile and Carrero (1921) distributed the roots in three different flasks containing different nutrients. In one flask was a solution of potassium salts, in another the phosphorus salts, and in a third the nitrogen salts. There was a diminished assimilation of these nutrients under these conditions as compared with the plants growing in a solution which contained all of these salts. It was considered that this diminished assimilation was not due to the inability of the roots to absorb the ions with sufficient rapidity but to the slowness with which the three ions were translocated to the cells where they were needed. These three ions thus each accumulated in different parts of the plant as a result of having been absorbed by different roots.

C. INJECTION EXPERIMENTS

A considerable number of injection experiments have been undertaken in an attempt to supplement the supply of water and nutrients to plants and to control fungous diseases and insect pests. These experiments should be mentioned here, as the factors involved are primarily those of translocation.

The injection of iron salts into the trunks of trees in order to overcome chlorosis has recently received considerable attention. Bennett (1927) introduced iron salts

directly into the trunk of pear trees which were affected with chlorosis. Over 6,000 trees were treated and a cure was effected in 90 per cent of the cases at a cost of 1.5 to 15 cents per tree, depending upon the size of the trees. Beneficial results were observed on those trees which did not fully recover from the chlorotic condition. Wann (1929) found that dry iron salts placed in an ordinary uncapped medicine capsule and inserted in holes bored in the stem of the plant proved effective in overcoming chlorosis of grapevines and of peach and apple trees. The iron salts used were ferric citrate, ferric phosphate, and ferric ammonium citrate, but the best response was obtained with the ferric phosphate. The leaves above the point of injection were the first to recover, after which the recovery spread gradually over the whole plant. Thomas and Haas (1928) were able to improve the chlorotic orange trees temporarily by the injection of iron salts. Subsequent injections, however, were necessary and in a new place, since the wood was injured for some distance around the point of injection.

Goff (1897) undertook to supply water in an artificial way to the roots of young transplanted trees. He placed a supply of water at a height equal to or greater than that of the tree and connected this with the cut end of a root. He reported that the buds on the treated plants developed more quickly than on the control plants and that the effects of this treatment were noticeable within 48 hr.

The injection of chemicals into plants for the control of fungous diseases has been undertaken by a considerable number of investigators. Bolley (1903 to 1906) found that trees would take up water solutions in large quantities when applied through a bore hole with an attached feeder. Chemical substances were carried to the most distal parts of the trees in a few hours. Thus in 10 hr. substances could be detected microscopically in the tops of cottonwood trees 30 to 45 ft. high. He was unable, however, to prevent fungous diseases by any injection experiments, but he considered that in some cases he held them in check. Mangin (1898), Morkrjetsky (1903), and Simon (1907) also considered that they obtained some control over fungous diseases by the injection of trees, potatoes, cauliflower, cabbage, and other plants. Injection experiments by Rankin 1917 and Rumbold (1915, 1920) using 80 or more chemicals with chestnut trees all gave negative results in the control of the chestnut-blight fungus. Scherer (1927) in injection experiments with white birch, gray birch, American elm, American chestnut, and apple trees obtained negative results in the control of fungous diseases and insect pests with the exception of apple trees which were injected with thymol. These seemed to show definite resistance to the progress of *Bacillus amylovorus*.

Injection experiments with potassium ferrocyanide have been tried for the control of insect pests, especially those in woody plants. The results that have been reported are extremely conflicting. Sanford (1914, 1915) and Shattuck (1915) have reported favorable results, while Surface (1914) and Flint (1915) could obtain no control whatsoever.

The conduction and behavior of the potassium cyanide when introduced into plants have been studied by Moore and Ruggles (1915) and Elliot (1917). Elliot found in smaller plants that the injury due to this chemical was very marked. On a hot, dry day the wilting of the leaves of herbaceous plants and small woody plants was noticeable under conditions of high evaporation within 10 min., and the fumes due to the potassium cyanide were readily detected coming from the leaves. Plants treated on cool, damp days showed little injury within 24 hr. The injury to these plants was also less extensive than to those treated on hot, dry days. The diffusion of potassium cyanide laterally is greatest when conduction is the slowest, and in woody stems Moore and Ruggles (1915) found that hydrocyanic acid passed through a particular area which had its point of departure on the upper side of the injection hole and that the chemical diffused but little in a lateral direction. The efficiency of

the control of fungous diseases and injurious insects is limited apparently by the fact that a solution of any chemical which will injure the protoplasm of the cells of the fungus or insect will also injure the protoplasm of the host cells. The control of insect pests in woody stems by injections is further handicapped because the lateral conduction of solutions is very limited and the injected materials will come in contact for the most part only with those insects which are directly above the point of injection.

D. TRANSLOCATION OF ORGANIC COMPOUNDS

1. Storage of Reserves.—Before discussing the translocation of organic compounds, a few facts should be stated in regard to their occurrence, storage, and depletion in the plant. The principal organic materials stored in plants are the proteins, carbohydrates, fats, and oils. The cells that are concerned in their storage are the medullary-ray cells, the parenchyma cells of the xylem and phloem, the parenchyma cells of the cortex, and the cells of seeds, bulbs, tubers, and rhizomes. The place of the origin of these organic materials is an important point to consider in a discussion of their translocation. Are they manufactured at places other than that of their occurrence and then translocated to where they are found or are they manufactured in the cells in which they are stored?

Sugar is apparently the only organic compound for whose formation light is directly essential, although, as mentioned in Chap. VIII, the kind of sugar that is first formed is not known. From this primary sugar, all the other carbohydrates may be formed in any living cells regardless of light. The indications are that the proteins, fats, oils, and other organic compounds may also be formed in any living cell independently of light, provided that sugar of one type or another and the necessary inorganic materials are present. If such is the case, it is conceivable in the formation and storage of organic compounds that sugar of one kind or another is the only organic compound that needs to be translocated for long distances in the plant. Since it is formed, for the most part, only in the leaves and since it is found either in the free or combined form in every living cell, there is no doubt that it is moved farther and in greater abundance in the plant than any other organic compound.

There is evidence, however, in some cases that there is a movement of organic materials, other than the freshly manufactured sugars, from the vegetative part of the plant to the seeds and fruits in their formative stage. Thus Trowbridge, Haigh, and Moulton (1915) noted that the dry matter of the roots and stubble of wheat increased up to the milk stage, after which it decreased in amount, being moved to the parts of the plant above ground. The stalks and leaves contained their maximum amount of dry matter at blooming time, after which it decreased until the ripening of the grain. The protein in the stems and leaves

decreased from 240 lb. per acre at blooming to 120 lb. at the maturity of the grain. The most rapid depletion during that period was from the milk stage to ripening. During that time the total carbohydrates decreased from 1,700 to 1,400 lb. per acre in the leaves and stems. Data quoted by Jones and Huston (1903) from German experiments showed during a 22-day period of grain formation that the nitrogen in the straw decreased from 83.5 to 25.0 lb. per acre, while the nitrogen content of the head increased from 23.4 to 60.8 lb. per acre. The dry matter in the straw decreased from 77.9 to 60.1 lb. per acre, while it increased in the head from 11.9 to 32.6 lb. per acre. In the case of the developing apple, Murneek (1928) states that after flowering, the direction of movement of most organic compounds seems to be primarily, if not exclusively, to the fruits that have set. The work of Jones and Huston (1914) with maize indicates that there is little depletion of the organic materials in the vegetative parts of this plant during the formation of the grain. Thus they found that the dry matter, fats, and carbohydrates in the stalk and blades remained practically constant while they rapidly increased in the ear. Although the carbohydrates remained constant in amount in the vegetative parts, they increased from 4 to 40 lb. per acre during a 40-day period of grain formation. There was evidence, however, that the stem and leaves were being depleted of inorganic materials in order to supply the crude materials for the synthesis of organic compounds in the developing grain. Thus the nitrogen in the stalks after the ears began to form decreased from 53.5 lb. per acre in August to 31.8 lb. in October, although the nitrogen content of the whole plant was increasing. The phosphorus decreased in the stalks from 15 to 6.3 lb. per acre during this same period, while it increased in the head from 6.0 to 35.5 lb. per acre. The migration of potassium apparently was not so marked, since in the stalk it decreased only from 73.5 to 70 lb. per acre, while it increased in the ear from 10 to 25 lb. per acre.

The time of the storage of organic compounds as well as the tissues in which they are laid down should be noted, since considerable work has been done in order to determine the relation of the amount of these reserves to fruit formation, to the amount and quality of vegetative growth, to the conservation of plants, or to their eradication.

In timothy (Trowbridge, Haigh, and Moulton, 1915) the dry matter in the bulbs increased throughout the growing period, but the amount became constant before the ripening of the seed.

Working with alfalfa, Graber and his coworkers (1927) did not find any exact period of growth when the storage of organic food reserves began in the roots but noted that such storage was greatly accelerated during the periods of blooming and seed formation, as shown in the following table:

DISTRIBUTION OF ORGANIC MATERIALS IN THE TOPS AND ROOTS OF ALFALFA AT DIFFERENT PERIODS DURING THE GROWING SEASON
Adapted from Graber, Nelson, Leukel, and Albert, 1927

Stage of growth	Per cent of moist weight		Per cent of dry weight									
	Dry matter		Total sugars		Soluble starches dextrins		True starch		Hemi-cellulose		Total nitrogen	
	Roots	Tops	Roots	Tops	Roots	Tops	Roots	Tops	Roots	Tops	Roots	Tops
Early-spring stage, $\frac{4}{13}$	26.8	20.5	11.2	6.1	2.8	1.9	6.0	1.9	11.3	10.9	2.1	3.8
Flower-bud stage, $\frac{6}{21}$	28.0	20.1	5.3	3.9	5.5	1.5	17.8	2.1	12.1	12.0	2.3	2.5
Full-bloom stage, $\frac{7}{10}$	36.9	24.6	5.1	3.1	14.4	2.2	17.6	1.9	12.5	14.5	2.2	2.2
Seed-pod stage, $\frac{8}{7}$	56.0	43.0	5.0	1.6	6.7	1.4	20.0	2.0	9.6	12.6	2.7	2.6
Fall dormancy, $\frac{1}{2}$	44.8	26.8	4.6	6.1	4.7	1.6	24.9	3.1	8.2	11.9	2.5	2.9

Aldous (1929) found that in the stems of the sumac (*Rhus glabra*) and buckbrush (*Symphoricarpos vulgaris*) the largest amount of reserve materials was reached about Aug. 15 in both cases. In the former the minimum amount of stored materials was present about June 10, while in the latter the minimum was reached as early as May 10. The location of the food reserves in the two plants is of interest. In the sumac the major portion is stored in the parenchyma cells of the bark, while in the buckbrush practically all of it is stored in the medullary rays and parenchyma cells of the xylem.

In the 2- to 3-year-old portions of apple twigs, Traub (1927) found that the total reserve carbohydrate of the xylem tissues was higher than that of the cortex phloem at all times of the year and that this reserve reached its maximum after leaf fall. The pentosan content formed a relatively large proportion of the total reserve carbohydrates. They made up from 45 to 68 per cent of the total carbohydrates of the cortex phloem, from 65 to 93 per cent of the carbohydrates of the outer xylem, and from 58 to 83 per cent of those of the inner xylem. The acid hydrolyzable hexosans made up from 2.3 to 26.5 per cent of the carbohydrates of the cortex phloem and from 10.1 to 31.8 per cent of those of the outer xylem.

During the summer this hexosan content increased, but with the approach of cold weather there was a change of hexosans into sugar beginning about October. The total sugars in these parts also increased at this time, owing to translocation from the leaves. During the winter the hexosans disappeared almost entirely from the cortex phloem and

were reduced more than 50 per cent in the xylem tissues. There was a general depletion of hexosans in May in all the tissues, owing to the translocation of sugar used in growth. The total sugar content of the phloem cortex was always markedly higher than that of the xylem tissues.

The nitrogen maximum in all parts was reached in March and April preceding growth in length. After a decline during the growth in length, the nitrogen content was relatively constant during the summer. From the fall of leaves through the winter it remained practically constant. The amino nitrogen was highest during the growing season, decreased as the rest period approached, and reached a minimum during the dormant period. The protein nitrogen was highest during the dormant season, decreased as the active growing season approached, and reached a minimum in June. The protein nitrogen was consistently higher in the cortex phloem than in the xylem tissues. Gardner (1925) observed that starch deposition in the shoots of the Bartlett pear begins very shortly after the cessation of length growth. Starch is deposited first at the tip of the shoot and then progressively downward toward the base. In the various tissues of the current season's growth, starch appears in the following order: medullary rays, wood parenchyma, and bark. Microchemical tests for sugar showed that the bark is much higher in sugar content than is the wood. The cortical parenchyma contains the largest amount of sugar.

These reserve organic compounds are used by the plant in respiration and in the formation of new plant parts, after a rest period as in the case of renewed growth in the spring or for the production of new organs and parts when these have been removed. Thus it has been found by Salmon, Swanson, and McCampbell (1925), Nelson (1925), Graber (1927), Albert (1927), and Leukel (1927) that in alfalfa new top growth is initiated in a large measure at the expense of previously deposited root reserves and that unless such reserves are sufficiently replenished during the period of successive cuttings, a reduction in the reserve contents of the root occurs which diminishes the amount of new top and root growth, following each cutting. The effects of too frequent cutting at immature stages are to prevent the plants from forming organic food reserves in sufficient quantities for storage in the roots for their future development, as well as that of the tops. When alfalfa is cut too frequently, the vigor of succeeding growths decreases rapidly, and many plants may die during the growing season. It has also been observed that the amount of winter injury to these plants may be correlated with the time and number of the cuttings during the summer. The vigor of blue grass, redtop, and timothy is also influenced by the number of cuttings during their growing season.

In the case of kudzu (Pierre and Bertram, 1929), the fewer the number of cuttings the greater is the production of food reserves. The roots

of plants receiving six cuttings per season decreased in weight during a period of 2 years. Those receiving four cuttings increased in weight 150 per cent, those receiving two cuttings increased about 400 per cent, while those from plants receiving only one cutting increased in weight about 1,250 per cent. The percentage of reserve starch and nitrogen was found to be less than one-half as much in the roots from plants receiving six cuttings as in the roots of those receiving four or a fewer number of cuttings.

In practice it has long been contended that if obnoxious brush and briars are cut at certain seasons of the year, few if any sprouts will arise from the roots and stump and that thus the plants would be eradicated. If, however, these were cut at other seasons of the year, numerous and vigorous sprouts would be developed, so that within a year or two the growth would be as heavy as or heavier than before. It seems very probable that this growth of sprouts is correlated with the amount of organic reserves stored in the stump and roots. If the cutting is done when the reserves are almost depleted, few sprouts develop; while if an abundant supply is present, new growth is very vigorous.

2. Utilization of Reserves.—Although it is definitely known that the reserve organic materials are utilized by the plant, the question arises as to how far these materials are moved from their place of storage to their regions of utilization. This question is of special interest in the case of woody plants where the distances between the various plant organs are relatively great. Since foods are stored in large amounts in stems and roots in late summer and autumn and since these disappear when growth is renewed in the spring, the general conclusion was early formed that foods are translocated from the roots and lower parts of the stem to the developing shoots and leaves.

It has been stated by Hartig (1858), Leclerc du Sablon (1906), and Butler, Smith, and Carey (1917) that the percentage of carbohydrates in the roots of various woody plants may be higher than that of the stem. This has been considered to indicate that the roots might act as storage organs for foods to be supplied to the developing parts of the stem. Curtis (1920), however, points out that the actual amount of carbohydrate and other reserves present in the roots may be less than that in the stem, since the total mass of stem is much greater than that of the roots, as shown by Chandler (1917), who calculated from the percentage concentrations given by Butler the relative amounts of foods available in the roots and tops of the apple tree.

Curtis (1920) ringed stems of *Acer saccharum* in early spring at different distances from the tips. In one series the rings were in the first-year wood, in another in the second- and third-year wood, and in another in wood ranging from 5 to 15 years of age. Of the 15 twigs ringed in the 1-year-old wood, the average growth in length during the following month

was 0.84 cm., while that of the check stems was 2.22 cm. The terminal growth of those stems which were ringed in the second and third year's growth was 2.03 cm. as compared with 2.25 cm. for the corresponding checks. Those twigs ringed in the 5- to 15-year-old wood showed no difference in growth from the controls. Similar results were also obtained for the pear tree.

In the case of apple twigs it was found that shoot growth was fairly vigorous when no food farther back than that obtained from a branch about one centimeter in diameter was available. When the ring was no farther back than the 5- to 10-year-old wood, the growth of the shoots above the ring approached that of the unringed twigs. Soon after the shoots have started, much or all the food necessary for continuing growth is apparently produced by the leaves of the same shoot, so that in some cases the growth of ringed twigs with leaves was fully as great as that of twigs not ringed. Using the Bartlett pear, Gardner (1925) found that when the growth of twigs began in the spring, the stored starch disappears first from the tip and then from the lower regions of the shoot successively. In the various tissues of the shoot, the stored starch disappears in the following order as growth begins: bark, medullary rays, wood parenchyma, and pith. In some cases, at least, root growth occurs before shoot growth begins in the spring, as shown by Goff (1898) for a large number of woody plants. The observations of Jones, Edson, and Morse (1903) on the amount of water in the trunk of the sugar maple would also indicate that root growth precedes stem growth. They found that the amount of water in the stem increased from 36.5 per cent on Mar. 1 to 47 per cent on Apr. 28 at which time the buds opened and the water content of the stems fell off. Crider (1928) and Rogers (1929) have noted that roots of weeds grow under conditions which are unfavorable for the development of the aerial portions. Since apparently the roots of woody plants begin to grow earlier in the spring and continue later in the autumn than the twigs, it would seem probable that they would utilize a considerable portion of their stored foods. Since a twig ringed in that part of a stem from 5 to 15 or more years old produces a growth above the ring which approximates that of a normal stem, the indications are that the upward movement of food from points below the ring is not essential for the development of the twig. This statement is made on the assumption that the major portion of the organic materials are translocated through the phloem. Curtis considered that the distance from which food is withdrawn back of the tip to be used in shoot growth may depend upon the different species, individual plants, and the conditions of the present and previous seasons. The indications are that there is normally no movement upward to the tips of the branches from the roots and little or none from the main trunk.

3. Tissues Concerned.—No uniformity of opinion regarding the tissues that are concerned in the translocation of organic materials in plants has been reached by investigators. Some claim that the major movement is through the xylem and consider that the phloem is totally inadequate for that purpose. Others consider that the phloem carries the major portion of these compounds. Both sides present considerable experimental evidence which is worthy of brief consideration here.

a. The Xylem.—Those who consider the xylem as the main pathway for the translocation of organic materials base their opinion upon two general observations: (1) the physical unsuitability of the phloem for their translocation; (2) the composition and amount of the organic substances in the tracheal sap.

1. *Physical Unsuitability of the Phloem.*—Dixon and Ball (1922) and Dixon (1922 to 1924) presented theoretical evidence to show that the phloem is unsuitable for the translocation of organic substances. They mentioned that the phloem tissue is always relatively small in cross-sections; that it is formed of short cells and comparatively short, narrow tubes with many cross-partitions which must be traversed by the stream carrying the organic substances if this tissue is used as a pathway for their translocation. They considered that the resistance to a translocation stream must be high due to the fact that a large proportion of the cross-section of the phloem is occupied by viscous contents of protoplasm and proteins. They stated that the velocities of transport comparable with diffusion alone could be maintained only under such conditions and that such velocities could not account for the quantity of material that is moved through the stem and roots.

To illustrate these points they cited as an example the translocation of carbohydrates from the leaves of the potato to its tubers. They selected a branch connecting the stem with a tuber which contained 50 g. of carbohydrate that had been deposited during a period of 100 days and determined that the area of the cross-section of the phloem tissue of this branch amounted to 0.422 mm.² not allowing for the cell walls and non-functional elements. Assuming that all the carbohydrates in the tuber passed through the phloem tissue and that they were carried in a solution whose concentration was 10 per cent, 500 cc. of this solution would have passed in 100 days.

The velocity of the solution in its passage would thus have been $\frac{500}{0.0042 \times 100 \times 24}$ or approximately 50 cm. per hour. The concentration of the solution, however, probably never exceeds 5 per cent; hence the rate of translocation must have approximated 100 cm. per hour. In the case of the yam, Mason and Lewin (1924) believe that higher values than those for the rate of diffusion would have to be assumed. Dixon and Ball assumed that if a 10 per cent sugar solution were supplied by the leaves to the phloem elements and this were converted into an insoluble carbohydrate in the tuber 50 cm. distant as soon as it reached this destination, then a rate of transport by diffusion alone of only 0.2 mm. per day would be expected. They therefore considered that the observed rate of translocation of carbohydrates is so high that it cannot be accounted for by diffusion alone through the phloem elements, even though protoplasmic streaming is taken into account. They considered that these facts

force one to conclude that the phloem elements are not adequate to transmit the amounts of carbohydrates actually known to travel downward in the stems and petioles of plants. Dixon and his students maintained that the major portion of the organic compounds are moved upward and downward through the conducting elements of the xylem in the xylem sap. Dixon considered that his observations on the seedlings of *Vicia* strengthens this view. He noted (1923) that the tracheal elements in these seedlings are differentiated in the petioles of the cotyledons much earlier than are the sieve tubes, so that before the latter are formed, considerable transport of organic substances to the embryo takes place. He believed that this is evidence that the tracheae and not the sieve tubes carry the organic substances.

Dixon and his pupils believed that the phloem is a means for the transmission of organic substance in a radial direction and consider that the medullary rays receive their organic materials from it. The phloem elements with the medullary rays and wood parenchyma present a large surface to the conducting xylem which thus facilitates the interchange of the organic substances between the living cells and these non-living conducting elements.

Curtis (1925), however, calculated the cross-sectional areas of the conducting tissues of potato rhizomes and found that the xylem in this case has an even smaller cross-sectional area than the phloem. The small area of the cross-section of the phloem cannot thus be considered as evidence that the sugar travels in the xylem. Furthermore, according to Curtis, sugars have never been demonstrated to be present in the conducting elements of the potato xylem. It should be noted in this regard that the relative areas of the conducting xylem elements and the living cells of the stem differ widely for different plants, as shown by Dixon and Marshall (1923).

2. *Composition and Amount of Organic Compounds in Tracheal Sap.*—Hartig (1858) ringed a number of trees and noted after a time that the starch below the ring had disappeared. He concluded from this that the reserve food products must have moved up through the xylem. As pointed out by Curtis (1920), however, he overlooked the fact that the foods stored below the ring might have been used locally for growth or have been moved downward through the phloem and used in root growth. Hartig considered that the materials formed in the leaves are passed down in the bark and stored in the wood parenchyma and medullary rays and in the spring are brought into solution and passed upward through the conducting elements of the xylem.

Schroeder (1871) made some observations on the sap of *Acer platanoides* and *Betula*. He noted that the sugar content of the sap from the birch decreased from early to late spring. The sugar concentration of the maple sap was greater in the upper part of the stem than in the lower, while the opposite condition prevailed in the birch.

Fischer (1888, 1890) by microchemical means demonstrated the presence of reducing substances in the conducting xylem elements of

numerous trees and found that they were less in amount in the summer and autumn than in the spring. Dixon and Atkins (1915, 1916) examined the tracheal sap of a number of deciduous woody plants and found that the concentration of the soluble carbohydrates in the transpiration stream was greater than that of the electrolytes. The sugars were both the reducing and non-reducing types, and estimated as glucose their concentration ranged from 0.3 to 2 per cent depending upon the date of examination. The greatest concentration of sugar occurred in the early spring. This was followed by a rapid dilution in spring and early summer with a minimum occurring in the summer or autumn. A rise in concentration took place during the winter, culminating in a spring maximum just prior to the opening of the buds. These authors concluded that the conveyance upward of sugars is a continual and primary function of the xylem. The sheath of wood parenchyma around the vessels functions as a storage place from which sugars pass into the rising transpiration stream. They believed that the medullary rays convey carbohydrates from the bark to these sheaths.

The sap of the sugar maple has a sugar concentration of between 2 and 3 per cent. This flow of sap is considered good evidence that the conducting elements of the wood are able to carry this sugar both upward and downward at a comparatively rapid rate. No sap in this case comes from the bark (Adams, 1923). MacDougal (1926) found considerable amounts of reducing substances in the sap of the xylem of Monterey pine, the more concentrated solutions being in the outer rings.

Anderssen (1929) in the case of the tracheal sap of the pear found that the free reducing substances and sucrose showed a high concentration in late winter and early spring, a rapid decrease in late spring, and a very low amount during the summer. These substances were found to be limited to the outer annual ring in 3-year-old pear branches during the late winter and spring. He thought this showed that the starch in the inner rings when hydrolyzed does not pass into the adjacent tracheae but is transferred along the medullary rays toward the outer tracheae into which it passes.

The nitrogen in the tracheal sap of the pear was found to consist almost entirely of organic nitrogen, and no nitrates could be detected until after the sap had been concentrated. On Nov. 10 the sap contained 60 ppm. of total nitrogen and on May 10, 163 ppm. of which 110 ppm. were present as amino nitrogen and 49 ppm. as amide nitrogen.

Some evidence has been presented that indicates that the living cells of stems and petioles are not necessary for the translocation of organic materials. This has been taken as proof that the organic matter moves through the xylem rather than through the phloem. The work of Deleano (1911) has been the most frequently quoted in proof of this. He chloroformed the petioles of grape leaves and found that the transloca-

tion of organic materials from the leaves continued although at a reduced rate. Some movement of organic materials from the leaves also took place after the petioles had been killed by heat.

b. *The Phloem.*—The view that the phloem elements are the channels for the movement upward and downward of organic compounds in the plant rests mainly upon the results obtained from ringing experiments in which the phloem portion of the stems have been severed by removing a ring of bark extending to the cambium. Experiments of this type were some of the earliest performed in plant physiology, and in general they have indicated that the downward passage of organic material is prevented or greatly hindered by the ringing. The death of a tree due to girdling is attributed to the fact that the downward movement of organic materials manufactured in the leaves is prevented to the extent that the roots die from starvation.

It has generally been assumed that the removal of the phloem in no way injured or affected the functioning of the xylem, but recent observations indicate that it does so unless special precautions are taken. On that account, the evidence obtained in the earlier ringing experiments cannot be taken as conclusive proof that the results obtained were due alone to the severance of the phloem tissue. It would be well now to review some of the more recent ringing experiments and consider the evidence thus obtained in regard to the part played by the phloem in the movement of organic material.

Curtis (1920) by ringing the twigs of *Philadelphus pubescens*, *Acer saccharum*, *Crataegus* sp., *Pyrus malus*, and others found that the defoliated stems did not continue to grow after the starch supply above a ring was depleted. If the stem above a ring, however, was not defoliated, the leaves were able to furnish a sufficient supply of material to allow for considerable growth. The carbohydrates stored in the xylem below the ring can apparently not be removed through the xylem but may be transferred radially to the phloem, where they may be carried downward if there is no second ring below.

Mason (1922) in the case of the bitter cassava (*Manihot utilissima*) found that the final weight of the tuberous roots of the ringed plants was only about one-fourth that of the unringed stems. Gardner (1925) in a study of the conductive tissues in the shoots of Bartlett pear concluded that the phloem is the tissue largely concerned in the longitudinal movement of foods. By using potassium hydroxide a ring was made which did not injure the xylem, yet it did not conduct the food stored between two rings past them, while the starch above and below the rings was removed. Both old and new tracheal tubes of excised pear branches allowed water and solutions of glucose and asparagin to pass through under pressure. In his opinion there is little reason to believe that the outer and inner xylem act differentially in the conduction of foods

and water, because only the outer xylem conducts foods, while the whole cross-section is used for water transport. He found that ringing did not induce the formation of tyloses within the tracheae of the pear shoots but that it did affect the xylem by actual mechanical injury by clogging and by drying the outer vessels. The inner xylem, comprising 75 to 80 per cent of the ringed shoots, was uninjured and was available for carbohydrate conduction but was evidently not used for that function. In *Robinia pseudacacia*, tyloses effectively blocked the passage of water and solutes of glucose and asparagin through the innermost xylem. The conduction of foods in this species is thus apparently limited to the phloem or to the outermost xylem.

Extensive and thorough experiments by Mason and Maskell (1928) with the cotton plant give conclusive proof that the transport of sugar from the leaves to the bolls and down the stems occurs in the phloem tissue. These experiments will be discussed in detail when the translocation of carbohydrates is considered.

The position taken by certain aphids on the vascular bundles of leaves has been considered an indicator of the tissue in which the organic materials travel. Thus Davidson (1921) by fixing the aphids *in situ* found that they seek the phloem part of the vascular bundle when tapping the plant for nutrients. The observation of Schneider-Orelli (1909) on the influence of a leaf miner upon translocation is worthy of note. He found that when it had bored through veins, the storage of starch in the tissues was affected. It was observed that the destruction of the xylem and the greater portion of the bundle sheath could be brought about without causing an accumulation of starch in the distal part of the leaf but that an injury of phloem resulted in an accumulation of starch proportional to the extent of the injury.

It has previously been mentioned in this chapter that the sieve tubes, companion cells, and phloem parenchyma are living cells and have a high colloidal content compared with the vessels and tracheids of the xylem. It has also been mentioned that the presence of the contents of these cells has been considered by some to prevent the translocation of organic matter in sufficient amount by simple diffusion to account for the total quantity that is actually moved. Some, on the other hand, consider that the protoplasm plays some rôle in this translocation, and considerable experimental work has been done to determine if it is actually concerned in this process.

De Vries (1885) pointed out that diffusion alone is apparently too slow to account for the movement of organic compounds which actually occurs. He suggested that the rotation and circulation of the protoplasm might aid in the translocation process, since he and others had noted protoplasmic streaming in the phloem tissue. Curtis (1929) observed streaming in the companion cells and phloem parenchyma in numerous

plants but in no sieve tubes except those of *Elodea*. He considered that injury in preparing sections might account for the failure to observe streaming in the mature sieve tubes and believed that it is very likely that rotation and streaming of some sort does actually occur in them under normal conditions.

Czapek (1897) and Deleano (1911) found that chloroforming the petioles without killing the cells delayed starch removal from the leaves. Czapek did not consider the streaming of the protoplasm as essential but seemed to favor some secretive action by the protoplasm. Steward (1928), however, believed that streaming of the protoplasm might be the cause which facilitates the diffusion of the organic compounds across protoplasmic membranes.

Curtis (1928 to 1929) studied the effects of chilling upon the translocation of carbohydrates. In the case of leaves, he encased the petioles with rubber tubing through which water of a desired temperature could be run. He found that the total carbohydrate content in the leaves with the chilled petioles was always higher than that in the controls, the ratio of the total carbohydrate of the chilled leaves to the checks being 1.37. The ratio of the sugar content of the chilled leaves to the checks was 1.49. The chilling of the petioles to 2 to 3°C. clearly interfered with the removal of sugar from the leaf, but chilling to 7 to 9° did not cause a significant retardation. Using plants grown in sand and watered with known chemicals and treating the stems as above mentioned, Curtis found that chilling interfered with the upward movement of inorganic nutrients. Thus the gain in total ash of the unchilled plants was 58.3 per cent of that at the beginning, while that of the chilled stems was only 35 per cent.

The temperatures at which chilling interferes with the translocation of materials is approximately that at which streaming in protoplasm ceases. The evidence indicates that living cells take an active part in both the upward and downward movement of materials and that this movement is probably facilitated by the streaming of the protoplasm. It should be noted that chilling apparently has little or no effect upon water movement, since plants bled as freely from the cut ends of chilled stems as they did from the unchilled.

4. Lateral Translocation.—The lateral transfer of organic materials in plants is for the most part in a radial direction. This movement takes place principally through the medullary rays but is never so marked as the longitudinal movement. Translocation around the stem is apparently almost negligible. It has long been observed that the annual rings of trees on the side directly under the larger limbs or on the sunny side of trees bordering on a forest are much larger than those on the opposite side. Czapek (1897) in ringing experiments found that ringing could be nullified only by vertical bridges connecting the upper and lower

portion of the bark. Oblique and zigzag bridges were ineffective in the transference of organic materials across the ring. This indicates that there is little lateral translocation. Auchter (1923) obtained evidence in the case of fruit trees which indicates that the foods manufactured on one side of these are used and stored mainly in that side or are translocated, for the most part, to the roots directly beneath.

5. Translocation of Carbohydrates.—It has previously been mentioned that sugars are translocated farther and in greater quantities than any other organic compound and are almost without exception the form in which carbohydrates are moved. Mason and Maskell (1928) in their thorough and detailed study of the transport of carbohydrates in the cotton plant have given us the most extensive information concerning carbohydrate translocation that is at present available. On that account their results will be reviewed here in considerable detail.

They found that the concentration of the total sugars in the cell sap of the bark was greatly in excess of that of the wood or leaf. Thus in one 24-hr. period the sugar content of the xylem varied from 0.05 to 0.07 per cent, of the bark from 3.0 to 3.5 per cent, and of the leaf from 1.5 to 1.8 per cent. In another observation it was found that the total sugar concentration in the boll was approximately 0.5 per cent higher than that of the bark, the concentration ranging from 5 to 6 per cent in both. Under the same conditions the sugar concentration of the leaves varied from 1.5 to 2.5 per cent. The concentration curves of these three plant parts, however, ran parallel, for the most part, but those for the bark and boll lagged behind that of the leaf. The sugar concentration rose in all three of these parts during the day and fell during the night, but the concentration in the wood was not appreciably affected by the change from day to night. The diurnal variations in the concentration of total sugars in the leaf were more highly correlated with variations of the concentrations in the bark than in the wood. In two experiments in which samples of the bark were taken from different levels on the stem it was shown that the concentration of the total sugars in the upper part of the stem was higher than that in the lower portion.

Reducing sugars were present in the leaves greatly in excess of sucrose. In the boll, the excess of reducing sugars over sucrose was especially marked. In the stem, however, sucrose was in excess of the reducing sugar, the concentration of sucrose in the bark increasing during the day and decreasing during the night, while the reducing sugars remained relatively constant.

Mason and Maskell believed their chemical analyses suggest that in the cotton plant the translocation of sugar occurs in the bark. As the major part of the fluctuations in the total sugars of the bark was found to be due to changes in the sucrose, they believed that the bulk of the carbohydrate translocated through this stem travels in that form.

They considered that sugar moves from the leaf to the bark by a process similar to physical diffusion in that concentration changes in the leaf are followed by similar changes in the bark. They assumed that even though the exchange of the solute may take place against a concentration gradient, the possibility of a definite causal relationship between concentration changes in the leaf and bark is not excluded. Since a concentration gradient exists in the bark down the stem, the movement of sugars down the stem toward the roots resembles movement by simple diffusion in that the direction of movement is from a region of high to one of low concentration.

Since the sucrose concentration of the bark was found to be on an average 2 per cent higher than that of the boll and since the rate of transport of sugar into the boll tended to increase as the sucrose gradient from bark to boll increased, it was concluded that the sucrose gradient between bark and boll is probably an important factor in determining variations in the rate of carbohydrate transport through the pedicel to the boll. It was also shown that the rate of transport of sugar into the boll was approximately four times greater by day than by night, a fact which is in harmony with the above conclusions, since the variation in the sucrose concentration in the bark follows closely in the changes in sugar concentration in the assimilating organs due to alternations of day and night.

By well-controlled ringing experiments Mason and Maskell obtained further evidence that the transport of carbohydrates in the cotton plant occurs in the bark. (1) Ringing caused an accumulation of carbohydrates, not only in the bark and wood just above the ring but also in the leaves 2 ft. distant from it. (2) Ringing interrupted the downward transport of carbohydrate in the stem but did not interrupt the downward movement of a dye in the wood. It was thus concluded that the movements in these two parts are fundamentally different. (3) When the wood and bark were completely separated from each other, the movement of sugar took place through the bark at nearly a normal rate, but no movement of sugar through the wood could be detected. In order to determine what portion of the bark is concerned in the translocation of sugar, Mason and Maskell subdivided the bark into three zones—outer, middle, and inner of approximately equal cross-sectional area—and analyzed each of these portions. They found that sucrose increased in concentration from outside to inside, while reducing sugars increased in the reverse direction. The radial gradient of reducing sugars was relatively stable, but the gradient in sucrose fluctuated markedly, increasing or decreasing as the sugar supply in the bark increased or decreased. There was a high positive correlation between the percentage of sieve tubes in any zone of bark and the sucrose concentration in that zone, and a high negative correlation between the percentage of sieve tubes

The sugars, in particular the sucrose, in the sieve tubes fluctuated markedly with changes in the sugar supply to the bark. The changes in the sugars of the parenchyma were, however, very small. The gradient in sugar concentration from sieve tubes to bark parenchyma was found in some cases to be five-hundred times as steep as the vertical gradient in the sieve tubes. There was a high correlation between the concentration of total sugars in the whole bark and the concentration in the sieve tubes, so that the gradient in the whole bark could be used as an estimate of the gradient in the sieve tubes. These observations appear to offer conclusive proof that the longitudinal translocation of sugars for the most part takes place through the sieve tubes.

It has been noted by Jost (1907), Mangham (1910 to 1922), Dixon and Ball (1922), and others that physical diffusion alone seems much too slow to account for the large quantities of carbohydrates that are moved longitudinally in plants. Mangham (1917) proposed a theory to account for the translocation of carbohydrates through the phloem elements that does not involve the physical diffusion of sugars through the protoplasmic membranes. He assumed that in the plant protoplasm there are present constituents capable of adsorbing sugars from solution; that for any given concentration of sugar present in the liquid phase of the protoplasm and the cell sap continuous with it there would be a definite concentration of sugar present at the adsorbing surface; and that any alteration of concentration in any region would lead to a readjustment of concentration equilibrium which would be transmitted or propagated as a wave through the system of these adsorbing particles and the solution immediately in contact with them. The connecting threads of the sieve tubes are assumed to provide a continuous protoplasmic pathway so the sieve plates would cause little if any obstruction to the progress of the wave of readjustment of concentration equilibrium. He considered that the sieve tubes would thus permit the passage of the waves with more effect than would be possible in any other type of cell except laticiferous cells.

The work of Mason and Maskell (1928), however, indicates that sugars move through the sieve tubes by a process similar to diffusion. Thus if sugars move in this tissue by diffusion, it would seem possible that the rate of movement of sugar at any point would be proportional to the concentration gradient in the channels of transport and to the cross-sectional area of the channels. Mason and Maskell investigated this point by examining the changes in rate produced by reducing the area of the channels of transport. It was found that a reduction by ringing in a cross-sectional area of the bark of approximately 45 per cent caused a reduction in the rate of sugar translocation of only 22.4 per cent. Thus the rate of transport across unit cross-sectional area of the bark in the constricted area was increased by reducing the area available for trans-

port. This increase in rate was accompanied by and could be explained in terms of an increase in the gradient of sugar concentration across the constricted region.

The rate of sugar movement through the sieve tubes is, however, much higher than that which ordinarily occurs in purely physical diffusion. Mason and Maskell (1928) state in the case of the cotton plant that the observed diffusion constant of sugar in the sieve tubes is about forty thousand times as great as the diffusion constant for sugar in a 2 per cent solution of sucrose in water and that it is almost identical with the diffusion constant for molecules of the size of the sucrose molecule diffusing in air. Although there seems to be good evidence that the carbohydrates travel as sugars in the sieve tubes, no satisfactory explanation has been given of the manner in which these products are moved with adequate speed in the required amount (MacDougal, 1926). The rate of movement of sugar from bark to wood appears, on the other hand, not very much greater than would be accounted for by purely physical diffusion.

The translocation of carbohydrates in germinating seeds and in seedling plants has been extensively studied by Sachs (1862), Detmer (1880), LeClerc and Breazeale (1911), Boysen-Jensen (1915), Choate (1921), Toole (1924), Yocum (1925), and others. Only a few of these observations will be discussed here, as detailed information may be obtained by consulting the references above mentioned. It should be kept in mind that the transformation of carbohydrates from one form to another is very frequent and rapid in plants, especially in seedlings, so that any given molecule of sugar passes no considerable distance without changing into other sugars or into insoluble carbohydrates for temporary storage.

In the wheat seedling, Choate (1921) detected reducing sugars in the coleorhiza, root, endosperm, coleoptile, plumule, and scutellum after 12, 18, 24, 36, 48 and 96 hr., respectively, while starch appeared in the root cap in 12 hr. after the beginning of germination. In the endosperm, reducing sugar is first found near the basal end of the embryo but is eventually found throughout the whole tissue. At the end of 7 days, starch was still present in the endosperm, although all the grains were corroded. Yocum (1925) noted that the greatest amount of reducing sugar in the plumules and roots was present at the ninth day. There was no evidence of sucrose formation taking place in the seed. When the starch showed a rapid loss the dextrins increased and then dropped off at about the same rate as the total sugars, but at no time were there sufficient dextrins in the roots and plumules to indicate that translocation of dextrins occurs. The starch content of the seed and seedling dropped off rapidly the first 7 days, the decline being extreme from the third to the sixth day. The amount of sugar was highest at 6 days. The proportional increase of plumule and roots in dry weight was greatest at this period, so the greatest starch hydrolysis and the greatest sugar

content accompanied the greatest growth. Starch was found in the plumules and roots at all stages. It appears that if the seedling has good growing conditions, it will store temporary starch in all its tissues. The seedlings of wheat depend entirely upon the endosperm for their carbohydrate supply for 6 days. From the sixth to the twelfth day they depend only partially on this source, after which they depend entirely upon photosynthesis for this supply. Toole (1924) in the case of germinating corn could find no reducing sugars in the cells of the scutellum, although sucrose was present in about the same amount as in the dry embryo. He thought that sucrose might represent the translocation form of carbohydrates in the corn seedling.

6. Translocation of Fats and Oils.—Our knowledge concerning the translocation of fats and oils is very meager and is confined almost entirely to observations of the germination of fatty seeds. The known facts may perhaps be best presented by reviewing the results that have been reported.

Sachs, as early as 1859, observed considerable quantities of oil in the hypocotyls of seeds and concluded that it had moved out from the seed in that form. He believed, however, that the greater portion of the reserve oil in seeds is transformed to carbohydrates for transport and use.

Schmidt (1891) reported extensive experiments on the translocation of oil in seedlings. He believed that in many cases oils are transported as such to the different regions of the seedling where it is broken up into the necessary products for growth. His conclusions were based on the following experiments: Pea seedlings were grown in the dark until the stored foods of the cotyledons were exhausted. A longitudinal incision was made just above the ground and a strip of filter paper saturated with oil was inserted in the incision. By using colored oils, their presence in the intercellular spaces and in the cytoplasm could be detected. When almond oil mixed with oleic acid was used, he observed that the rise of the oil was increased as the amount of fatty acid was increased. He reported that the neutral oil with which he worked did not enter the cell unless there was present at least 10 per cent free acid. When pure fatty acid was used, its presence could be detected in the cytoplasm within a few hours. Schmidt explained these results by assuming that soaplike compounds were formed with the free acid and that the emulsification of the neutral fat by these soapy substances occurred. He thus assumed that the neutral oil passed through the cell walls from cell to cell as a fine emulsion.

Rhine (1926) repeated the work of Schmidt. He found that the movement of oil in plants treated after the manner of Schmidt was through the intercellular spaces of the outer region of the cortex. Contrary to the observations of Schmidt, however, he found that a fatty acid in

the pure state did not rise so rapidly as did the neutral fats of these acids. Thus linseed oil rose at the rate of 2 cm. per hour, while the fatty acids of this oil rose at the rate of only 1 cm. per hour. The fatty acids entered the cytoplasm of the cells from the intercellular spaces and appeared in the cytoplasm in the form of small droplets. Linseed oil, however, with a free acid content of less than 2 per cent penetrated the cell walls as well as the free acid.

Rhine believed that since the oil in the cells during translocation is in the emulsified state, while the oil on the outside of the cells in these experiments was pure and homogeneous, the cases could not be considered comparable. He believed that the movement of oils through the cell walls must be demonstrated from the emulsion state with water if the continuous phase of the experimental results is to be taken as an indication of what actually occurs in the plant. When pea seedlings were placed in an emulsion of linseed fatty acids, no intake whatsoever of the oils took place.

Since the seedlings that had been used in the foregoing experiments were starved and etiolated, it was considered that an abnormal condition might prevail in the walls bordering on the intercellular spaces. In order to investigate this point, two sets of seedlings were treated. One set was well supplied with water and the other partially desiccated by drying with a fan. In the seedlings which had an abundance of water, the rise of the oil in most cases was zero and no penetration of the cell walls occurred. The increased drying effects of air currents increased the rate of the ascent of the oil and facilitated its penetration. It was thus definitely shown that the observed intake of oil by plants was due to an unnatural drying out of the cell walls—a condition which does not prevail in the cells of germinating fatty seed through which oil has been supposed to pass.

It was suggested by Schmidt (1891) that soaps formed from the fatty acids might facilitate the movement of oils through the cells. If soaps are found to function in that manner, the tissues must be alkaline in order that they may not decompose. Rhine (1926) determined the P_H value of the hypocotyls of a number of seedlings of fatty seeds with the following results:

Hypocotyls of	Range of P_H
Peanut.....	5.4 to 5.8
Sunflower.....	5.2 to 5.6
Castor bean.....	5.2 to 5.6
Hemp.....	6.2 to 6.6

The phloem of these tissues was examined with special care, since it has been reported to be alkaline, but its acidity was found to be the same as that of the adjoining tissues. Under the conditions of acidity

which were found it would be difficult to conceive of the existence and movement of soaps through the tissues.

The respiratory quotient of the hypocotyls or other growing parts of the seedling should serve as an index to the nature of the food that is being translocated through them. If oil is being translocated as such and moved into the hypocotyls, it would be expected that oil would be used in respiration, and in that case the respiratory quotient would be relatively low, approximately 0.6. If the hypocotyl is receiving sugar, it would be used in respiration, and the respiratory quotient of the hypocotyl would be approximately 1.00. Rhine found that the respiratory quotient of the hypocotyls of the seedlings of sunflower and cotton averaged 0.770, while that of the pea, wheat, barley, and buckwheat averaged 0.775. The respiratory quotient of the hypocotyl of these germinating oily seeds was thus almost the same as that of starchy seeds. This indicates that the food supplied to the hypocotyls by the storage region of fatty seeds reaches them in a form which yields the same value for the respiratory quotient as the food supplied by the typical carbohydrate storage seeds. This food is commonly supposed to be sugar.

Rhine studied the oil gradient from the source of supply to the growing tip in the case of the seedlings of cotton, sunflower, squash, cocklebur, castor bean, peanut, and flax. In no case did he find a gradient from the storage region to the growing tip, but in every case there was a distinct gradient in the other direction; that is, the amount of fat increased with the approach toward the tip of the hypocotyl, as shown in the following table:

Seedling	Percentage of ether extract on wet basis		
	Tips	Middles	Bases
Cotton.....	5.75	2.24	1.33
Sunflower.....	5.31	1.34	0.66
Squash.....	2.59	0.60	0.22

If oils are moved as such from cell to cell, some would be expected to be present in the cell walls. Rhine, however, was unable to observe either in cross- or longitudinal sections any evidence of its passing through the walls.

Rhine concluded that from a physical standpoint, the movement of oils as such through the cells is improbable. In moving downward into the hypocotyls, the oil must pass through the cytoplasm whose specific gravity is 1.00 or greater. The various extracts of the hypocotyls made by Rhine showed in all cases a specific gravity lower than that of

water. Oil movement downward if it occurs would thus have to take place against the pressure of a denser medium, a procedure which would seem rather improbable.

The presence of oil in the hypocotyls of seedlings is no proof that it has been moved there as such. Starch is present in most cases in the growing regions of plants, yet no one considers that it has been moved from its place of storage in that form.

The evidence thus indicates that oils, especially in seedlings, are converted into sugars at their place of storage and translocated to the different parts of the plant in that form. After the arrival of sugar at these regions, a portion of it at least may be converted into oil as a temporary storage product. It seems to be proved that oil as such is rarely if ever moved from cell to cell or from one region of the plant to another.

7. Translocation of Proteins.—There is apparently little or no movement of proteins as such through cell membranes or through the special conducting elements of the plant. Only a few proteins are soluble in water, and since they are slowly diffusing substances, their movement must necessarily be very slow. The contents of the sieve tubes give the protein reactions and have been considered on that account to be the elements in which proteins are moved longitudinally in the plant. These elements are rich in protoplasm and colloidal material, but how much of this if any is protein in transit cannot be determined.

The proteins can apparently be formed in any region of the plant, provided that a supply of sugar and the necessary inorganic materials are present. It seems probable, therefore, that proteins are not, as a rule, manufactured in superabundance in any special portion of the plant and then translocated for considerable distances for utilization or storage but that they are formed in the immediate region in which they are found. The frequently observed fact that when a nitrogen supply is abundant in the tops of plants the carbohydrates are used for top growth in larger proportions than when the nitrogen is more limited is indicative that protein formation proceeds wherever the necessary materials are present and that they are utilized more or less locally (Chandler, 1919). It was mentioned in Chap. IX that proteins are manufactured in the leaves in considerable amounts during the day and moved from them especially at night, but to what distances they are moved is not known. Amino acids and amides have been detected in both the xylem and phloem elements, but whether they are of local origin or are in transit from regions more remote has not been definitely determined.

The movement of protein from their place of storage to their point of utilization has been studied for the most part in seedlings. The richest stores of proteins occur in seeds and are rapidly broken down and moved to the growing portions of the seedling during germination.

The general procedure has been to study the kind and quantity of the hydrolytic products in the original storage parts and in the newly formed organs of the seedlings. A few of the observations that have thus been made will now be reviewed.

Schulze (1900) and Schulze and Castoro (1903) found in the seedlings of *Lupinus albus* and other leguminous seedlings that amino acids appeared as leucine, tyrosine, and hexone bases. In the seedlings of the Alaska pea, Thompson (1915) noted that the amount of the total nitrogen in the amino form increased from 6.58 per cent of the total nitrogen in the 1-day-old seedlings to 28.27 per cent in those 7 days old. The distribution of the nitrogen in the 7-day seedlings was as follows:

Part of seedling	Percentage on a dry basis of		Percentage of total nitrogen in the amino form
	Total N	Amino N	
Plumule	7.02	0.254	36.18
Cotyledons.....	3.36	0.421	12.53
Root	5.33	1.705	32.00

Stark (1927) found in the seedlings of Manchu soybeans grown at 20°C. that the alpha amino nitrogen increased from 1.86 per cent of the total nitrogen at the age of 1 day to 23.2 per cent at the end of 39 days. In the case of the Midwest variety, the increase was from 2.1 to 17.8 per cent.

These data indicate that the proteins in the seed are broken down into amino acids which are translocated as rapidly as they are formed to the plumules and roots. In corn seedlings (Pettibone and Kennedy, 1916) the total nitrogen in the seed decreased from 75.0 mg. per 20 seedlings when the plumules were $\frac{1}{2}$ in. in length to 23.1 mg. when they had reached a length of 10 in. The total nitrogen in the plumules during the period increased from 12.3 to 57.5 mg., while in the roots it had increased from 8.2 to 307 mg. Amino acids were present in considerable amounts in all three parts. An analysis of the sap exuded from the stumps of several seedlings showed that amino acids and other protein decomposition products resembling proteoses and peptones were present. Observations similar to these have been observed by Choate (1921) working with wheat seedlings.

Jodidi (1925 to 1927) observed also in etiolated corn seedlings that 48 per cent of the proteins present in the seed are converted into water-soluble diffusing nitrogen compounds within 8 days. During this period there is a rise in the amino nitrogen and a diminution in the peptide nitrogen. This is taken to mean that amino acids increase at the expense of polypeptides which along with proteoses are among the first degradation products of proteins.

Since nitrogen increases in the plumules and roots as it disappears from the seed, and since amino acids are present in these parts and in the flowing sap, it seems evident that the reserve proteins of the seeds are transported to their points of utilization in the seedling in the form of amino acids.

Questions

571. Why is the translocation of materials in plants necessary? Give two examples of materials that are widely translocated in plants.

572. What unspecialized tissues in the plant are concerned in translocation? What specialized tissues? Of what cells is the xylem composed? What are the characteristics of the tracheids? The vessels? The xylem parenchyma? The xylem medullary rays?

573. What cells compose the phloem? What are the characteristics of the sieve tubes? Of the companion cells? Of the phloem parenchyma?

574. Trace the pathway of water from its entrance in the root until it evaporates from the leaves. How has the pathway of water in the xylem been demonstrated? What portion of the xylem functions in the translocation of water? How does this vary for different plants? Give examples.

575. How does the absorbing power of the epidermal cells of the root for water compare with that of the cortical cells? With that of the endodermis? How does the absorbing power of the chlorenchyma cells of the leaf compare with that of the fibrovascular bundles?

576. How does the presence of gas bubbles in a conducting xylem element affect conduction of water across it? What is the origin of these gas bubbles? State some facts that have been observed in regard to the gases present in woody stems.

577. Explain how water is continuous from the soil through the root and stem to the intercellular spaces of the leaves. What is the condition of the water in the conducting elements at wilting? What is meant by the hydrostatic system of the plant?

578. Why is it difficult to determine the forces concerned in the ascent of water in plants? By what external manifestations may the forces concerned in the elevation of water in the plant be estimated?

579. What evidence is there that water is forced up from the roots under conditions of low evaporation? What terms have been used to designate the force with which water is exuded from plants? Which term has been the most universally used? Why?

580. What is bleeding? How are exudation pressures measured? What values for these pressures have been reported? What evidence is there that exudation pressures are not always developed in the roots?

581. How may water be transferred from the epidermis of the root to the endodermis? From the endodermis to the xylem elements? Discuss the theory of exudation pressure formulated by Priestley and Armstead.

582. What is the condition of the water in the conducting elements under conditions of high evaporation? Under such conditions where do the main forces causing the upward movement of water reside? What are the main differences between the vital and physical theories of water ascent in plants?

583. What is Bose's theory of the ascent of water? Upon what evidence is it based? What objections are there to it? What part may living cells play in the conduction of water through the plant?

584. Describe the experiments that have been performed to show that the living cells are not necessary for the ascent of water through stems. What are the objections to these experiments?

585. What is the imbibition theory of the ascent of water? How has it been disproved? What is the objection to the assumption that the force of capillarity is an important factor? Distinguish between imbibitional and capillary forces.

586. Who formulated the cohesive theory of the ascent of water? Upon what two facts is it based? Describe in detail the behavior of the forces involved, according to this theory, in the ascent of water under conditions of high evaporation.

587. How much force is required to raise water to a height of 100 m. in a tree? To evaporate a cubic centimeter of water? What would be the source of the required energy under conditions of low evaporation?

588. How great is the tensile strength of water? Of the xylem sap? How much resistance must be overcome in the passage of water through wood? How great is the force of imbibition in the evaporating cells of the leaves?

589. How has the suction force of transpiring twigs been measured? How has a state of tension in the conducting elements been demonstrated? How has the downward movement of water through the xylem been shown? What is the cause of this movement?

590. Discuss the observations that have been made in regard to the lateral transfer of water in plants. What evidence is there that no radial transfer of water occurs from one annual layer to another? Describe by means of a 2-year-old unbranched stem the path followed by the transpiration stream in moving from the innermost layer of the xylem to the outermost layer if there is no radial mass movement of water.

591. Why has the xylem generally been considered as the pathway of the upward transfer of the inorganic solutes? Discuss the evidence which has been obtained in this regard by means of ringing experiments. What are the objections to ringing experiments?

592. Discuss the evidence in regard to the lateral transfer of inorganic solutes in plants. How successful have injection experiments been in overcoming chlorosis? In controlling fungous diseases? Insect pests? Why?

593. Enumerate the chief reserve organic compounds of plants. In what cells are these reserves stored? Which organic compound appears to be the most extensively transferred? Why?

594. Discuss the evidence pro and con in regard to the movement of the organic compounds from the vegetative parts of plants to the seeds, fruits, and tubers during their formation. What evidence is there that the vegetative parts are depleted of their inorganic materials at this stage?

595. When are the reserve materials laid down in roots and stems as evidenced by observations on alfalfa and apple and pear twigs? For what are these organic reserves used by the plant? How is this shown by the number and time of cuttings of the tops?

596. What do ringing experiments indicate in regard to the distance of translocation of organic compounds in stems? Give examples.

597. Discuss the evidence submitted by Dixon and his pupils to prove the physical unsuitability of the phloem for the translocation of organic materials. How does the cross-sectional area of the phloem of the potato rhizome compare with the like dimensions of the xylem?

598. What organic compounds have been demonstrated in the cell sap of the xylem? In what amounts do they occur? How do they vary in amount during the year?

599. In what manner has the function of the phloem in the translocation of organic materials been studied? What objection is there to this method? Discuss some of the results that have thus been obtained. What indirect evidence indicates that the phloem is the pathway of the movement of organic materials?

600. In what manner is the protoplasm of the phloem considered to influence translocation. Describe the experiments which have been performed to demonstrate that protoplasm plays a part in translocation in the phloem. Discuss the lateral translocation of organic substances in stems.

601. What evidence is there from chemical analysis that the translocation of sugar occurs in the bark of the cotton plant? What evidence is there from ringing experiments that such is the case?

602. How does the concentration of cane sugar vary from the outside to the inside of the bark in this plant? The concentration of reducing sugars? How does the concentration of sucrose and reducing sugars in the bark correlate with the percentage of sieve tubes? What does this indicate?

603. What evidence from ringing experiments indicates that sugars move through the sieve tubes by a process similar to diffusion? How does the rate of movement correspond to that of purely physical diffusion? Discuss the transformation and translocation of the carbohydrates in a developing wheat seedling.

604. What evidence suggested that oils are moved as such in plants? Describe the experiments of Schmidt on the translocation of oils. What theory of their translocation did he propose? What evidence was obtained by Rhine that contradicts that theory?

605. What does the respiratory quotient of the growing parts of the seedling indicate in regard to the translocation of oil? What does the gradient of oil from the source of storage to the growing parts indicate? What objection is there from the physical standpoint in considering the movement of oil as such through cells?

606. Where and under what conditions are proteins formed in plants? Evidence? In what form are proteins translocated? Illustrate this by examples of data which have been reported from analyses of seedlings.

Bibliography

- ADAMS, J., 1923: The translocation of carbohydrates in the sugar maple, *Nature*, **112**: 207.
- ALBERT, W. B., 1927: Studies on the growth of alfalfa and some perennial grasses, *Jour. Amer. Soc. Agron.*, **19**: 624-655.
- ALDOUS, A. E., 1929: The eradication of brush and weeds from pasture lands, *Jour. Amer. Soc. Agron.*, **21**: 660-666.
- ANDERSSON, F. G., 1929: Some seasonal changes in the tracheal sap of pear and apricot trees, *Plant Physiol.*, **4**: 459-477.
- ARNDT, C. H., 1929: The movement of sap in *Coffea Arabica*, *Amer. Jour. Bot.*, **16**: 179-190.
- ASKENASY, E., 1895: Ueber das Saftsteigen, *Verh. naturh.-med. Ver. Heidelberg*, n.f., **5**: 325-345; *Bot. Centrbl.*, **62**: 237-238.
- , 1896: Beiträge zur Erklärung des Saftsteigens, *Verh. naturh.-med. Ver. Heidelberg*, n.f., **5**: 429-448.
- ATKINS, W. R. G., 1916: "Some Recent Researches in Plant Physiology," Chap. XI, The Function of the Wood, pp. 186-215.
- AUCHTER, E. C., 1923: Is there normally a cross transfer of foods, water, and mineral nutrients in woody plants? *Maryland Sta. Bull.* 257.
- BENEDICT, H. M., 1927: Application of Bose's theory of sap rise to ten species of trees, *Amer. Jour. Bot.*, **14**: 623.
- BENNETT, J. P., 1927: Chlorosis studies, *Calif. Sta. Rept.*, **1927**: 85-87.
- , F. G., ANDERSSON, and Y. MILAD, 1927: Methods of obtaining tracheal sap from woody plants, *New Phytol.*, **26**: 316-323.

- BIRCH-HIRSCHFELD, LOUISE, 1920: Untersuchungen über die Ausbreitungsgeschwindigkeit gelöster Stoffe in der Pflanze, *Jahrb. f. wiss. Bot.*, **59**: 171-262.
- BLAKE, M. A., 1921: Effect of an early application of nitrogen on peach trees deficient in vigor, *Proc. Amer. Soc. Hort. Sci.*, **18**: 139-145.
- BODE, H. R., 1923: Beiträge zur Dynamik der Wasserbewegung in den Gefäßpflanzen, *Jahrb. f. wiss. Bot.*, **62**: 92-127.
- BOEHM, J., 1889: Ursache des Saftsteigens, *Ber. d. d. bot. Ges.*, **II**, **7**: 46-56.
- , 1890: Ueber Ursache der Wasserbewegung in transpirirenden Pflanzen, *Verh. Zool.-Bot. Ges. Wien.*, **40**: 149-159.
- , 1892: Ueber einen eigenthümlichen Stammdruck, *Ber. d. d. bot. Ges.*, **10**: 539-544.
- , 1893: Capillarität und Saftsteigen, *Ber. d. d. bot. Ges.*, **11**: 203-212.
- BOLLEY, H. L., 1903: Tree feeding and tree medication, *N. Dak. Expt. Sta. Ann. Rept.* **14**: 55-58 (1904) **15**: 56 (1906) **17**: 35.
- BOSE, J. C., 1923: "Physiology of the Ascent of Sap," p. 277, Longmans, Green and Co., New York and London.
- BOUCHERIE, A., 1840: Rapport sur un Mémoire relatif à la conservation des bois, *Compt. Rend. Acad. Sci. Paris*, **11**: 894-898.
- , 1841: Nouvelles recherches sur la conservation des bois, *Compt. Rend. Acad. Sci. Paris*, **12**: 337-339.
- BOYSEN-JENSEN, P., 1915: Über synthetische Vorgänge im pflanzlichen Organismus. II, Vorkommen, Bedeutung und Bildung des Rohrzuckers bei der Keimung von *Pisum sativum*, *Jahrb. f. wiss. Bot.*, **56**: 431-446.
- BUTLER, O. R., T. O. SMITH, and B. E. CAREY, 1917: Physiology of the apple. Distribution of food materials in the tree at different periods of vegetation, *N. H. Agr. Expt. Sta. Tech. Bull.* **13**.
- CHANDLER, W. II., 1914: Sap studies with horticultural plants, *Mo. Agr. Expt. Sta. Res. Bull.* **14**.
- , 1919: Some results as to the response of fruit trees to pruning, *Proc. Amer. Soc. Hort. Sci.*, **16**: 88-101.
- CHOATE, H. A., 1921: Chemical changes in wheat during germination, *Bot. Gaz.*, **71**: 409-426.
- CLARK, W. S., 1874: The circulation of sap in plants, *Mass. Board Agr. Ann. Rept. Sec.*, **21**: 159-204.
- COPELAND, E. B., 1902: The rise of the transpiration stream: an historical and critical discussion, *Bot. Gaz.*, **34**: 161-193, 260-283.
- CRIDER, F. J., 1928: Winter root growth of plants, *Science*, n.s., **68**: 403-404.
- CURTIS, O. F., 1920: The upward translocation of foods in woody plants. I, Tissues concerned in translocation, *Amer. Jour. Bot.*, **7**: 101-124.
- , 1920: The upward translocation of foods in woody plants. II, Is there normally an upward transfer of storage foods from the roots or trunk to the growing shoots? *Amer. Jour. Bot.*, **7**: 286-296.
- , 1923: The effect of ringing a stem on the upward transfer of nitrogen and ash constituents, *Amer. Jour. Bot.*, **10**: 361-383.
- , 1925: Studies on the tissues concerned in the transfer of solutes in plants. The effect on the upward transfer of solutes of cutting the xylem as compared with that of cutting the phloem, *Ann. Bot.*, **39**: 573-585.
- , 1928: Studies indicating that translocation is dependent on the activity of living cells and the possible bearing of this on solute distribution, *Amer. Jour. Bot.*, **15**: 630-631.
- , 1929: Studies on solute translocation in plants. Experiments indicating that translocation is dependent on the activity of living cells, *Amer. Jour. Bot.*, **16**: 154-168.

- CZAPEK, F., 1897: Über die Leitungswege der organischen Baustoffe im Pflanzenkörper, *Sitzungsber. d. k. Akad. d. Wiss. Wien.*, **106**: 117-170.
- DARWIN, F., and R. W. PHILLIPS, 1885: On the transpiration stream in cut branches, *Proc. Cambridge Phil. Soc.*, **5**: 330-367.
- , S. H., VINES, and J. JOLY, 1896: A discussion on the ascent of water in trees, *Ann. Bot.*, **10**: 630-661.
- DAVIDSON, J., 1921: Biological studies of *Aphis rumicis*, *Ann. App. Biol.*, **8**: 51-65.
- DELEANO, N. T., 1911: Über die Ableitung der Assimilate durch die intakten, die chloroformierten und die plasmolysierten Blattstiele der Laubblätter, *Jahrb. f. wiss. Bot.*, **49**: 129-186.
- DETMER, W., 1880: "Vergleichende Physiologie des Keimungsprocesses der Samen," Fischer, Jena.
- DEVRIES, H., 1885: Ueber die Bedeutung der Circulation und der Rotation des Protoplasma für den Stofftransport in der Pflanze, *Bot. Zeitung*, **43**: 2-6, 17-26.
- DIXON, H. H., and J. JOLY, 1894: On the ascent of sap, *Proc. Roy. Soc.*, **57**: 3-5.
- and ———, 1894: On the ascent of sap, *Ann. Bot.*, **8**: 468-470.
- and ———, 1895: On the ascent of sap, *Phil. Trans. Roy. Soc.*, 186 B, I, 563-576.
- and ———, 1895: The path of the transpiration-current, *Ann. Bot.*, **9**: 403-420.
- , 1896: Note on the role of osmosis in transpiration, *Proc. Roy. Irish Acad.*, **3**: 767-775.
- , 1897: The tensile strength of cell walls, *Ann. Bot.*, **11**: 585-588.
- , 1903: The cohesion theory of the ascent of sap, *Sci. Proc. Roy. Dublin Soc.*, n.s., 10, No. 4.
- , 1905: Note on the supply of water to leaves on a dead branch, *Sci. Proc. Roy. Dublin Soc.*, n.s., **11**: 7-12.
- , 1906: On the transpiration current in plants, *Proc. Roy. Soc.*, B, **79**: 41-57.
- , 1909: Vitality and the transmission of water through the stems of plants, *Notes Bot. School Trinity Coll. Dublin*, **2**: 5-18; *Sci. Proc. Roy. Dublin Soc.*, n.s., **12**: 21-34.
- , 1910: Transpiration and the ascent of sap, *Progressus rei botanicae*, **3**: 1-66.
- , 1910: Transpiration and the ascent of sap, *Ann. Rept. Smithsonian Inst.*, **1910**: 407-425.
- , 1914: "Transpiration and the Ascent of Sap in Plants," 216 pp., Macmillan and Co., Limited.
- and E. S. MARSHALL, 1915: A quantitative examination of the elements of the wood of trees in relation to the supposed function of the cells in the ascent of sap, *Proc. Roy. Dub. Soc.*, n.s., **16**: 358; *Notes Bot. School Trinity Coll. Dublin*, **2**: 264.
- , 1915: Note on the spread of morbid changes through plants from branches killed by heat, *Notes Bot. School Trinity Coll. Dublin*, **2**: 221-224.
- , 1915: Changes produced in the sap by the heating of branches, *Notes Bot. School Trinity Coll. Dublin*, **2**: 225-229.
- , 1915: On the tensile strength of sap, *Notes Bot. School Trinity Coll. Dublin*, **2**: 230-235.
- , and W. R. G. ATKINS, 1915: On the constituents and concentration of the sap in the conducting tracts and on the circulation of carbohydrates in plants, *Sci. Proc. Roy. Dublin Soc.*, n.s., **14**: 374-392.
- , and ———, 1916: Osmotic pressure in plants. IV, On the constituents and concentration of the sap in the conducting tracts, and on the circulation of carbohydrates in plants, *Notes Bot. School Trinity Coll. Dublin*, **2**: 275-293.

- DIXON, H. H., and J. JOLY, 1916: On the composition of the sap in the conducting tracts of trees at different levels and at different seasons of the year, *Sci. Proc. Roy. Dublin Soc.*, n.s., **15**: 51.
- , 1922: Transport of organic substances in plants, *Nature*, **110**: 547-551.
- , and N. G. BALL, 1922: Transport of organic substances in plants, *Nature*, **109**: 236-237.
- , and ———, 1923: On the channels of transport from the storage organs of the seedlings of *Lodoicea*, *Phoenix* and *Vicia*, *Sci. Proc. Roy. Dublin Soc.*, **17**: 185-196.
- , 1923: Transport of organic substances in plants, *Notes Bot. School Trinity Coll. Dublin*, **3**: 207-215.
- , 1924: "The Transpiration Stream," 80 pp., University of London Press.
- EAMES, A. J., and L. H. MACDANIELS, 1925: "An Introduction to Plant Anatomy," 363 pp., McGraw-Hill Book Company, Inc.
- ELFVING, F., 1883: Ueber die Wasserleitung im Holz, *Bot. Zeitung*, **40**: 707-723.
- ELLIOT, J. A., 1917: The conduction of potassium cyanide in plants, *Phytopath.*, **7**: 443-448.
- ERRERA, L., 1886: Ein Transpirationsversuch, *Ber. d. d. bot. Ges.*, **4**: 16-18.
- EWART, A. J., 1904: The ascent of water in trees, *Proc. Roy. Soc.*, **74**: 554-556.
- , 1906, 1908: The ascent of water in trees, *Phil. Trans. Roy. Soc.*, B, **198**: 41-85; **199**: 341-392.
- FISCHER, A., 1888: Glycose als Reservestoff der Laubhölzer, *Bot. Zeitung*, **46**: 405-417.
- , 1890: Beiträge zur Physiologie der Holzgewächse, *Jahrb. f. wiss. Bot.*, **22**: 73-160.
- FLINT, W. P., 1915: The effect of cyanide on the locust-borer and the locust tree, *Science*, n.s., **42**: 726-727.
- GARDNER, F. E., 1925: A study of the conductive tissues in shoots of the Bartlett pear and the relationship of food movement to dominance of the apical buds, *Calif. Agr. Expt. Sta. Tech. Paper* 20.
- GILE, P. L., and J. O. CARRERO, 1921: Assimilation of nitrogen, phosphorus and potassium by corn when nutrient salts are confined to different roots, *Jour. Agr. Res.*, **21**: 545-573.
- GODLEWSKI, E., 1884: Zur Theorie der Wasserbewegung in den Pflanzen, *Jahrb. f. wiss. Bot.*, **15**: 569-630.
- GOFF, E. S., 1897: The application of artificial root pressure to recently transplanted trees, *Wis. Agr. Expt. Sta. Ann. Rept.*, **14**: 272-282.
- , 1898: The resumption of root growth in the spring, *Wis. Agr. Expt. Sta. Ann. Rept.* **15**: 220-228.
- GRABER, L. F., N. T. NELSON, W. A. LEUKEL, and W. B. ALBERT, 1927: Organic food reserves in relation to the growth of alfalfa and other perennial herbaceous plants, *Agr. Expt. Sta. Univ. Wis. Res. Bull.* 80.
- HARTIG, T., 1858: Über die Bewegung des Saftes in den Holzpflanzen, *Bot. Zeitung*, **16**: 329-335, 337-342.
- HILL, A. W., 1901: The histology of the sieve-tubes of *Pinus*, *Ann. Bot.*, **15**: 575-613.
- , 1908: The histology of the sieve-tubes of angiosperms, *Ann. Bot.*, **22**: 245-291.
- HOLLE, H., 1915: Untersuchungen über Welken, Vertrocknen und Wiederertraffwerden, *Flora*, **108**: 73-126.
- JANSE, J. M., 1887: Die Mitwirkung der Markstrahlen bei der Wasserbewegung im Holz, *Jahrb. f. wiss. Bot.*, **18**: 1-69.
- JODIDI, S. L., 1925: Nitrogen metabolism in etiolated corn seedlings, *Jour. Agr. Res.*, **31**: 1149-1164.
- , 1927: Isolation and identification of some organic nitrogenous compounds occurring in etiolated corn seedlings, *Jour. Agr. Res.*, **34**: 649-656.

- JONES, C. H., A. W. EDSON, and W. J. MORSE, 1903: The maple sap flow, *Vt. Agr. Expt. Sta. Bull.* 103.
- JONES, W. J., and H. A. HUSTON, 1914: Composition of maize at various stages of its growth, *Ind. Agr. Expt. Sta. Bull.* 175.
- JOST, L., 1907: "Lectures on Plant Physiology," Eng. trans., pp. 167-172, Clarendon Press.
- KNIGHT, R. C., 1920: Storage and translocation, *Sci. Prog.*, **15**: 200-206.
- KNOWLTON, H. E., 1921: A preliminary experiment on half tree fertilization, *Proc. Amer. Soc. Hort. Sci.*, **18**: 148-149.
- LECLERC DU SABLON, M., 1904: 1906: Recherches physiologiques sur les matières des réserves des arbres, *Rev. Gén. Bot.*, **16**: 341-368; **18**: 5-25, 82-96.
- , 1910: Sur le mécanisme de la circulation de l'eau dans les plantes. *Rev. Gén. Bot.*, **22**: 125-136; *Bot. Centrbl.*, **116**: 87.
- LECLERC, J. A., and J. F. BREAZEALE, 1911: Translocation of plant food and elaboration of organic plant material in wheat seedlings, *Bur. Chem. U. S. Dept. Agr. Bull.* 138.
- LEUKEL, W. A., 1927: Deposition and utilization of reserve foods in alfalfa plants, *Jour. Amer. Soc. Agron.*, **19**: 596-624.
- MACDOUGAL, D. T., 1921: Growth in trees, *Carnegie Inst. Wash. Pub.* 307.
- , and FORREST SHREVE, 1924: Growth in trees and massive organs of plants, *Carnegie Inst. Wash. Pub.* 350.
- , 1925: Absorption and exudation pressures in plants, *Proc. Amer. Phil. Soc.*, **64**: 102-130.
- , 1925: Reversible variations in volume, pressure and movements of sap in trees, *Carnegie Inst. Wash. Pub.* 365.
- , 1926: The hydrostatic system of trees, *Carnegie Inst. Wash. Pub.* 373.
- , 1925-26, 1926-27: Composition of gases in tree trunks, *Carnegie Inst. Wash. Year Book* **25**: 160-162; **26**: 162-163.
- , and J. B. OVERTON, 1927: Sap flow and pressure in trees, *Science*, n.s., **65**: 189-190.
- , ———, and G. M. SMITH, 1929: The hydrostatic-pneumatic system of certain trees: movements of liquids and gases, *Carnegie Inst. Wash. Pub.* 397.
- MANGHAM, S., 1910-1911: The translocation of carbohydrates in plants, *Sci. Prog.*, **5**: 256-285, 457-479.
- , 1915: Observations on the osazone method of locating sugars in plant tissues, *Ann. Bot.*, **29**: 369-391.
- , 1917: On the mechanism of translocation in plant tissues. An hypothesis, with special reference to sugar conduction in sieve-tubes, *Ann. Bot.*, **31**: 293-311.
- , 1922: Transport of organic substances in plants, *Nature*, **109**: 476-477.
- MANGIN, L., 1898: Sur la nutrition et la defense de la vigne par injection, *Jour. Agr. Prak.*, **1898**: 918-920.
- MASKELL, E. J., and T. G. MASON, 1930: Studies on the transport of nitrogenous substances in the cotton plant. I, II, III; *Mem. Cotton Res. Sta. Trinidad*, **2**; *Ann. Bot.*, **43**: 205-231, 615-652 (1929); **44**: 1-29 (1930).
- MASON, T. G., 1922: A note on the growth and the transport of organic substances in bitter cassava (*Manihot utilisima*), *Sci. Proc. Roy. Dublin Soc.*, **17**: 105-112; *Bot. Abst.*, **12**: 759.
- , and C. J. LEWIN, 1924: On the rate of carbohydrate transport in the greater yam, *Dioscorea alata*, *Sci. Proc. Roy. Dublin Soc.*, **18**: 203-205.
- , and E. J. MASKELL, 1928: Studies on the transport of carbohydrates in the cotton plant. I, A study of diurnal variation in the carbohydrates of leaf, bark and wood, and of the effects of ringing, *Ann. Bot.*, **42**: 189-253.

- MASON, T. G., and E. J. MASKELL, 1928: Studies on the transport of carbohydrates in the cotton plant. II, The factors determining the rate and the direction of movement of sugars, *Ann. Bot.*, **42**: 571-636.
- , and ———, 1928: Studies on the transport of carbohydrates in the cotton plant. I, II; *Mem. Cotton Res. Sta. Trinidad*, Ser. B, *Physiology*.
- MOLISCH, H., 1902: Ueber lokalen Blütungsdruck und seine Ursachen, *Bot. Zeitung*, **60**: 45-63.
- , 1928, 1929: The movement of sap in plants, *Nature*, **122**: 168-169; *Science*, n.s., **69**: 217-218.
- MOORE, WILLIAM, and A. G. RUGGLES, 1915: The action of potassium cyanide when introduced into the tissues of a plant, *Science*, n.s., **42**: 33-36.
- MORKKJETSKY, A., 1903: Über die innere Therapie der Pflanzen, *Zeits. f. Pflanzenkr.*, **13**: 251-265 (quoted by Rumbold, 1920).
- MURNEEK, A. E., 1928: Nitrogen and carbohydrate distribution in organs of bearing apple spurs, *Mo. Agr. Expt. Sta. Res. Bull.* 119.
- NÄGELI, C., 1866: Die Theorie der Capillarität, *Bot. Mith.*, **2**: 471-501 (quoted by Copeland, 1902).
- NELSON, N. T., 1925: The effect of frequent cutting on the production, root reserves and behavior of alfalfa, *Jour. Amer. Soc. Agron.*, **17**: 100-113.
- NORDHAUSEN, M., 1916: Ueber die Saugkraft transpirierender Sprosse, *Ber. d. d. bot. Ges.*, **34**: 619-639.
- , 1919: Zur Kenntniss der Saugkraft und der Wasserversorgung transpirierender Sprosse, *Jahrb. f. wiss. Bot.*, **58**: 295-335.
- , 1921: Weitere Beiträge zum Saftsteigeproblem, *Jahrb. f. wiss. Bot.*, **60**: 307-353.
- OVERTON, J. B., 1911: Studies on the relation of the living cells to transpiration and sap flow in *Cyperus*. I, II, *Bot. Gaz.*, **51**: 28-63, 102-120.
- , 1925-1926: Stem anatomy and sap conduction, *Carnegie Inst. Wash. Year Book*, **25**: 155-158.
- and J. B. SMITH, 1926-1927: Additional observations on stem anatomy and sap conduction, *Carnegie Inst. Wash. Year Book*, **26**: 159-160.
- PEIRCE, G. J., 1929: To demonstrate the course of sap ascent in plants, *Science*, n.s., **69**: 186-187.
- PETTIBONE, C. J. V., and C. KENNEDY, 1916: Translocation of seed protein reserves in the growing corn seedling, *Jour. Biol. Chem.*, **26**: 519-525.
- PIERRE, W. H., and F. E. BERTRAM, 1929: Kudzu production with special reference to influence of frequency of cutting on yields and formation of root reserves, *Jour. Amer. Soc. Agron.*, **21**: 1079-1101.
- PRIESTLEY, J. H., 1920: The mechanism of root pressure, *New Phytol.*, **19**: 189-200.
- and DOROTHY ARMSTEAD, 1922: Physiological studies in plant anatomy. II, The physiological relation of the surrounding tissue to the xylem and its contents, *New Phytol.*, **21**: 62-80.
- RANKIN, W. H., 1917: The penetration of foreign substances introduced into trees, *Phytopath.*, **7**: 5-14.
- RENNER, O., 1911: Experimentelle Beiträge zur Kenntnis der Wasserbewegung, *Flora*, **103**: 175-247.
- , 1911: Zur Physik der Transpiration. I, *Ber. d. d. bot. Ges.*, **29**: 125-132.
- , 1912: Zur Physik der Transpiration. II, *Ber. d. d. bot. Ges.*, **30**: 572-575.
- , 1912: Versuche zur Mechanik der Wasserversorgung. I, Der Druck in den Leitungsbahnen von Freilandpflanzen. II, Über Wurzeltätigkeit, *Ber. d. d. bot. Ges.*, **30**: 576-580, 642-648.
- , 1915: Theoretisches und Experimentelles zur Kohäsionstheorie der Wasserbewegung, *Jahrb. f. wiss. Bot.*, **56**: 617-667.

- RENNER, O., 1918: Versuche zur Mechanik der Wasserversorgung, *Ber. d. d. bot. Ges.*, **36**: 172-179.
- RHINE, J. B., 1926: Translocation of fats as such in germinating fatty seeds, *Bot. Gaz.*, **82**: 154-170.
- ROGERS, C. F., 1929: Winter activity of the roots of perennial weeds, *Science*, n.s., **69**: 299-300.
- ROSHARDT, P. A., 1910: Ueber die Beteiligung lebender Zellen am Saftsteigen bei Pflanzen von niedrigen Wuchs, *Beih. Bot. Centrbl.*, I, **25**: 243-357.
- RUHLAND, W., 1911: Untersuchungen über den Kohlenhydratstoffwechsel von *Beta vulgaris*, *Jahrb. f. wiss. Bot.*, **50**: 200-257.
- RUMBOLD, C., 1915: Methods of injecting trees, *Phytopath.*, **5**: 225-229.
- , 1920: The injection of chemicals into chestnut trees, *Amer. Jour. Bot.*, **7**: 1-21.
- , 1920: Effect on chestnuts of substances injected into their trunks, *Amer. Jour. Bot.*, **7**: 45-57.
- SACHS, J., 1862: Zur Keimungsgeschichte der Gräser, *Bot. Zeitung*, **20**: 145-150.
- , 1862: Microchemische Untersuchungen, *Flora*, **45**: 289-301, 313-320, 325-336.
- , 1878: Ein Beitrag zur Kenntniss des aufsteigenden Saftstroms in transpirierenden Pflanzen, *Arb. Bot. Inst. Würzburg*, **2**: 148-184.
- , 1879: Ueber die Porosität des Holzes, *Arb. Bot. Inst. Würzburg*, **2**: 291-332.
- SALMON, S. C., C. O. SWANSON, and C. W. McCAMPBELL, 1925: Experiments relating to the time of cutting of alfalfa, *Kans. Agr. Expt. Sta. Tech. Bull.* 15.
- SANFORD, F., 1914: An experiment on killing tree scale by poisoning the sap of the tree, *Science*, n.s., **40**: 519-520.
- , 1915: In regard to the poisoning of trees by potassic cyanide, *Science*, n.s., **41**: 213-214.
- SCHERER, C. M., 1927: Tree injection for control of fungous diseases and insect pests, abst. *Phytopath.*, **17**: 51.
- SCHMIDT, R. H., 1891: Ueber Aufnahme und Verarbeitung von fetten Ölen durch Pflanzen, *Flora*, **74**: 300-370.
- SCHNEIDER-ORELLI, O., 1909: Die Miniergänge von *Lyonetia clerkella* und die Stoffwanderung in Apfelblättern, *Centrbl. f. Bact.*, II, **24**: 158-181.
- SCHROEDER, J., 1871: Die Frühjahrsperiode der Birke (*Betula alba*) und des Ahorn (*Acer platanoides*), *Landw. Versuchs-stat.*, **14**: 118-146.
- SCHULZE, E., 1900: Über den Umsatz der Eiweissstoffe in der lebenden Pflanze. II, *Zeits. f. physiol. Chem.*, **30**: 241-312.
- and N. CASTORO, 1903: Beiträge zur Kenntnis der Zusammensetzung und des Stoffwechsels der Keimpflanzen, *Zeits. f. physiol. Chem.*, **38**: 199-258.
- SCHWENDENER, S., 1892, 1893: Zur Kritik der neuesten Untersuchungen über das Saftsteigen, *Sitzungsber. d. k. Akad. d. Wiss. Wien.*, **44**: 911-946; *Bot. Centrbl.*, **53**: 290.
- , 1909: "Vorlesungen über mechanische Probleme der Botanik," W. Engelmann, Leipzig.
- SHATTUCK, C. H., 1915: Effect of cyanide of potassium on trees, *Science*, n.s., **41**: 324.
- SHULL, C. A., 1923: Review of physiology of the ascent of sap by Bose, *Bot. Gaz.*, **76**: 316-317.
- SIMON, W. J. M., 1906: Recherches sur l'alimentation artificielle des plantes, *Jour. Soc. Nat. Hort. France*, III, **7**: 678-686; *Gard. Chron.*, 3 ser., **41**: 8 (1907).
- SMITH, E. F., 1896: The path of the water current in cucumber plants, *Amer. Nat.*, **30**: 372-378, 451-457, 554-562.
- SNOW, R., 1925: The transport of organic foodstuffs in plants, *Nature*, **116**: 360.
- STARK, O. K., 1927: The protein metabolism of the soybean, *Amer. Jour. Bot.*, **14**: 532-548.

- STEWART, F. C., 1928: A preliminary study of the diffusion of sugars through membranes of living plant tissue, *abst. Amer. Jour. Bot.*, **15**: 629-630.
- STRASBURGER, E., 1891: Ueber den Bau und die Verrichtungen der Leitungsbahnen in den Pflanzen, *Histol. Beitr. Jena*, **3**: 609.
- , 1893: Ueber das Saftsteigen, *Histol. Beitr. Jena*, **5**: 1-94; *abst. Bot. Centrbl.*, **60**: 270-272.
- SURFACE, H. A., 1914: Cyanide of potassium in trees, *Science*, n.s., **40**: 852-853.
- THOMAS, E. E., and A. R. C. HAAS, 1928: Injection method as a means of improving chlorotic orange trees, *Bot. Gaz.*, **86**: 355-362.
- THOMPSON, T. G., 1915: The total amino nitrogen in the seedlings of the Alaska pea, *Jour. Amer. Chem. Soc.*, **37**: 230-235.
- THUT, H. F., 1928: Demonstration of the lifting power of evaporation, *Ohio Jour. Sci.*, **28**: 292-298.
- TOOLE, E. H., 1924: The transformations and course of development of germinating maize, *Amer. Jour. Bot.*, **11**: 325-350.
- TRAUB, H. P., 1927: Regional and seasonal distribution of moisture, carbohydrates, nitrogen, and ash in 2-3 year portions of apple twigs, *Univ. Minn. Agr. Expt. Sta. Tech. Bull.* 53.
- TROWBRIDGE, P. F., L. D. HAIGH, and C. R. MOULTON, 1915: Studies of the timothy plant. II, The changes in the chemical composition of the timothy plant during growth and ripening with a comparative study of the wheat plant, *Univ. Mo. Agr. Expt. Sta. Tech. Bull.* 20.
- UNGER, F., 1868: Weitere Untersuchungen über die Bewegung des Pflanzensaftes, *Sitzungsber. d. k. Akad. d. Wiss. Wien.*, **58**: 392-418.
- URSPRUNG, A., 1905: Untersuchungen über die Beteiligung lebender Zellen am Saftsteigen, *Beih. bot. Centrbl.*, **1**, **18**: 147-158.
- , 1906: Die Beteiligung lebender Zellen am Saftsteigen, *Jahrb. f. wiss. Bot.*, **42**: 503-544.
- , 1907: Ueber die Ursache des Welkens, *Beih. bot. Centrbl.*, **1**, **21**: 67-75.
- , 1907: Studien über die Wasserversorgung der Pflanzen, *Biolog. Centrbl.*, **27**: 33-60.
- , 1907: Abtötungs- und Ringelversuche an einigen Holzpflanzen, *Jahrb. f. wiss. Bot.*, **44**: 287-349.
- , 1913: Ueber die Bedeutung der Kohäsion für das Saftsteigen, *Ber. d. d. bot. Ges.*, **31**: 401-412.
- , 1913: Zur Demonstration der Flüssigkeitskohäsion, *Ber. d. d. bot. Ges.*, **31**: 388-400.
- , 1915: Ueber die Kohäsion des Wassers im Farnannulus, *Ber. d. d. bot. Ges.*, **33**: 153-163.
- , 1915: Zweiter Beitrag zur Demonstration der Flüssigkeitskohäsion, *Ber. d. d. bot. Ges.*, **33**: 253-265.
- , 1916: Dritter Beitrag zur Demonstration der Flüssigkeitskohäsion, *Ber. d. d. bot. Ges.*, **34**: 475-487.
- , 1925: Einige Resultate der neuesten Saugkraftstudien, *Flora*, **18-19**: 566-599.
- VESQUE, J., 1884: Recherche sur le mouvement de la sève ascendante, *Ann. Sci. Nat. Bot.*, **VI**, **19**: 159-199.
- VINES, S. H., 1896: The suction force of transpiring branches, *Ann. Bot.*, **10**: 429-444.
- WANN, F. B., 1929: Experiments on the treatment of chlorosis in Utah. *Abst. Amer. Jour. Bot.*, **16**: 844.
- WESTERMAIER, M., 1883: Zur Kenntniss der osmotischen Leistungen des lebenden Parenchym's, *Ber. d. d. bot. Ges.*, **1**: 371-383.
- , 1884: Bedeutung tochter Röhren und lebender Zellen für die Wasserbewegung, *Sitzb. preuss. Akad. Wiss.*, **48**: 1105-1117.
- YOCUM, L. E., 1925: The translocation of the food materials of the wheat seedling, *Jour. Agr. Res.*, **31**: 727-744.

CHAPTER XIII

THE PROCESS OF RESPIRATION IN PLANTS

1. Energy Relations of the Plant.—The various processes that go on in a green plant involve the execution of work. Some of these processes are the formation of carbohydrates, fats, proteins, and other organic compounds from the simple materials obtained from the soil and the air; the evaporation of water from the stem and leaves; the penetration of the roots through the soil; the elevation of the stem into the air; and the movements and activities of the protoplasm not included in the processes mentioned above. To accomplish these various kinds of work, a supply of kinetic energy must be furnished continually to the different plant parts concerned in the performance of these various functions. Let us now inquire into the source of the energy of the plant and its distribution, transference, and general availability in the various activities of plant life.

The sun is the source of the energy that is necessary for all life and this energy is transmitted in the form of heat, light, and chemical rays. About 70 per cent of this energy which falls upon the plant is absorbed by it, while the remainder is either reflected or transmitted. It has been mentioned in Chap. VIII that slightly over 70 per cent of this absorbed energy is utilized in the evaporation of water in transpiration. From 1.5 to 4.5 per cent of it is utilized in the synthesis of carbohydrates, fats, proteins, and other organic compounds and is thus transformed into potential or stored energy. Another portion of the absorbed energy may be used directly in the various processes of the parts by which it is absorbed and in raising the temperature of the plant, while the remainder is lost by radiation into the surrounding air.

Although the rays of the sun are the original source of the energy supply of the plant, the structure of the plant and the conditions under which it grows prevent it from utilizing this energy directly in all its parts. The structure of the plant is such that its interior portions are not exposed to the rays of the sun, so that they cannot utilize directly the energy of the sunshine. Also the living cells must be furnished with a continuous supply of energy during darkness as well as light. It is evident, therefore, that some supply of energy must be available for immediate use in all the cells of the plant under conditions of both light and darkness. In every living plant cell there is present a supply of proteins, carbohydrates, fats, and other organic compounds in varying

amounts. Every living plant cell thus has in the form of these compounds, a supply of potential energy which, if changed into the kinetic form, would be available for the life processes of the cell. The living cell has the power so to transform this stored energy whenever the proper conditions exist. The processes associated with the transformation of potential energy in the living cell into the kinetic form are primarily chemical decompositions in which the stored foods and the protoplasm of the cell are involved. The most important process concerned in the liberation of stored energy in the cells is termed "respiration" and it is this subject that will now be considered.

2. Nature of Respiration.—Respiration may be defined as a process that goes on in every living cell whereby energy is released. The term "energenesis" has been suggested (Barnes, 1905) as a name for the processes involved in energy release, but this has never come into general use. In the process of respiration under ordinary conditions oxygen is absorbed, organic compounds, especially carbohydrates and fats, disappear, while carbon dioxide and water are formed as end products. The materials used and the waste products formed in the process are well defined, but the changes which occur in the cell whereby the organic compounds are utilized and the waste products produced are not clearly understood. We can thus observe the beginning and end of the process but know little or nothing of the intermediate changes that occur.

Respiration is generally considered as an oxidation process because the final products—carbon dioxide, water, and kinetic energy—are the same as those derived from the combustion of organic substances in the air. The oxidation of organic substances in respiration, however, is striking in that it occurs at ordinary temperatures generally below 35°C., while oxidation of the same substances outside the living organism is accomplished only by the aid of very high temperatures or of powerful reagents. The oxidation of organic substances in respiration apparently occurs in the protoplasm itself or in close proximity to it and it is considered that the oxidation is accomplished by the action of oxidizing enzymes which are secreted by the protoplasm. Herzfeld and Klinger (1919) stresses the possibility that certain molecular structures may weaken the union of the oxygen atoms in the oxygen molecule so that "activation" (increased oxidizing power) results, whereby loose chemical combinations are made with H₂O, with OH ions, and with O₂ absorbing surfaces. Such organic compounds as the lower fatty acids or their salts might thus be oxidized to CO₂ and H₂O, fulfilling the conditions for oxidation processes in the living organism, namely active O₂ and easily oxidizable simpler metabolic products, thereby rendering the assumption of certain oxidases unnecessary. It should, however, be remembered that in no case has it been definitely proved that the carbohydrates, fats, or proteins are directly attacked outside the protoplasm,

and it will also be shown in the discussion of the oxidizing enzymes that they are incapable, as prepared by present methods, of oxidizing under laboratory conditions any of the carbohydrates or fats which are apparently used in respiration.

It is believed by some that the facts of respiration may be explained more satisfactorily by assuming that the process is concerned in the decomposition of the living matter itself. Barnes (1905) assumed that in the labile protein components of the protoplasm there occurs a shifting of atomic groups within the molecule as a result of the addition of hydroxyl groups from the water present. Dissociation of these components follows this procedure, the rate depending upon the prevailing conditions. The groups or radicals of the protoplasm that have thus been dissociated may contain structural components which have been derived from sugars, fats, or proteins. The portion of the protoplasm that has been dissociated is then rebuilt at the expense of the sugars, fats, or proteins present in the cell, and as a consequence they disappear during the process of respiration. An attempt was made by Palladin (1896) to determine the relationship of the amount of protoplasm to the rate of carbon dioxide production. He determined the amount of carbon dioxide given off by wheat seedlings in the dark, and in parallel experiments he determined the amount of protein present which was indigestible in gastric juice. It was assumed that such proteins represented those that were components of the protoplasm. Palladin found that with an adequate supply of carbohydrate, the elimination of carbon dioxide was proportional to the amounts of indigestible proteins present in the seedlings. Although this method is far from exact, it nevertheless gives some indication of the relationship between the protoplasm and the process of respiration. The part of the protoplasm, however, which is the most actively concerned in respiration has received but little attention. The leaf cells of the Indian pipe (*Monotropa uniflora*) contain a colorless chromogen which oxidizes very easily if the proper conditions are provided. Osterhout (1917) determined that the oxidation of this chromogen in the cell is much more rapid in the nucleus than in the cytoplasm. From that he inferred that respiration is much more rapid in the nucleus than in the other parts of the protoplasm. It is not known, however, whether the nuclei of other plant cells show a similar behavior.

3. Organic Materials Used in Respiration.—One of the striking results of respiration is the loss in weight of the organism, which, however, is not ordinarily noticed in plants on account of the manufactured food equaling or exceeding the amount lost. If food is withheld from an animal, or if a plant is prevented from manufacturing food, the loss in weight due to respiration is very apparent. The most striking examples of the loss in weight from respiration are shown in the case of germinating seeds. The seedling plant always weighs less in dry matter than the seed from

which it originated. Thus corn seedlings, including the residues of the seeds 2 weeks after planting, contain from 5 to 10 per cent less dry matter than the original seeds. Miller (1910) noted in sunflower seedlings 10 days old that the dry weight of 100 seedlings was 5.7 g. as compared with 7.3 g. which was the dry weight of an equal number of seeds. This was a loss in weight of 1.6 g. or approximately 20 per cent of the original dry weight of the seeds. Thus, one-fifth of the foods stored in the seeds was consumed in respiration in order to generate sufficient energy to push the plant roots into the soil, to raise the stem or cotyledons above ground, and to carry on the various life activities of the seedling.

The materials which disappear in the process of respiration are, for the most part, the carbohydrates and fats. It is well established that the carbohydrates furnish the greater portion of the materials that are used in respiration. Even when fats are the only source of oxidizable material, it is very probable that they are transformed into sugars before they are ultimately utilized in respiration.

The relationship of the supply of carbohydrates, especially of the sugars, to the intensity of respiration has received considerable consideration. Palladin (1896) and Palladin and Komleff (1902) found that etiolated bean leaves floated on a solution of sucrose or with their petioles immersed therein respired much more rapidly when transferred to distilled water than did the controls. In one case, 100 g. of leaves low in carbohydrate gave off at room temperature 89.6 mg. of carbon dioxide per hour for a given period. After the same leaves were floated upon a solution of cane sugar in darkness for 2 days they gave off carbon dioxide at the rate of 147.8 mg. per hour. Maige and Nicolas (1910) showed that, in general, respiration increased as the concentration of the sugar in the medium increased until the concentrations were sufficient to produce plasmolysis when the intensity of respiration declined. In ripening bananas, Gore (1914) found that the graph of the rate of respiration paralleled that of the rate of starch hydrolysis in the fruit, while there were only slight changes in the amounts of fats and proteins. His results were substantiated by Olney (1926), who found that the value of the respiratory quotient during the ripening of this fruit was approximately unity, which indicated that the oxidation in this case consisted solely of the combustion of carbohydrates. It was noted by Knudson (1916) that there was an increased respiration in plants when sugars were added to the nutrient solutions in which they were growing. According to Hopkins (1927), the sugar content of wounded potatoes increased from 53 to 68 per cent of the original sugar present. The rate of respiration was also increased after the wounding, and he assumed that the basis of this augmentation of the intensity of respiration was the increase in the sugar content of the cells. The curves of the sugar content and of the rate of respiration, however, did not exactly parallel.

• The hexoses are apparently the sugars utilized in respiration. Thus Hasselbring and Hawkins (1915) could observe no correlation between the total sugars in the sweet potato and respiratory activity. A simultaneous decrease, however, in the reducing sugars and the respiratory intensity was observed which indicated that they were the immediate source of the materials used in respiration. In plants d-glucose is apparently the most easily oxidizable sugar. The amount of d-levulose has been found to be in excess of d-glucose in the leaves, which is taken to indicate that the former is the more stable and is thus used to a lesser degree in respiration. Spoehr and McGee (1922) found that the intensity of respiration in the excised leaves of *Helianthus annuus* was not increased when levulose was fed to them, while the presentation of d-glucose, sucrose, and mannose stimulated respiration. As will be mentioned later, the addition of amino compounds with these sugars stimulated the rate of respiration in all cases except with levulose.

.When the carbohydrate content of plants is low, the rate of the emission of carbon dioxide increases with the increasing supply of sugars. This may be conceived of as a matter of mass action in that as the concentration of the available material to be oxidized becomes greater, the rate of reaction is increased. This is true, however, only within the limits of the capacity of the protoplasm present to carry on respiration. Thus, the intensity of respiration in etiolated leaves of the bean was greatly accelerated by floating them for a 2-day period upon a sugar solution. A further increase in respiration, however, could not be obtained by extending the period of sugar feeding to 40 days, although the concentration of the sugar in the leaf cells was greatly increased. During a 2-day period upon the sugar solution sufficient sugar was absorbed for the maximum rate of respiration for the quantity of protoplasm present so that the further addition of sugar was without influence upon the process. The total quantity of carbohydrate in the cell will thus not influence the rate of respiration except to determine the length of time that the process may continue therein.

It was formerly considered that proteins were also directly utilized in respiration, but experiments have shown that under normal conditions they are not utilized to any appreciable extent in this regard. In the absence of an adequate supply of carbohydrates, however, the proteins are apparently utilized in the process. Thus, Palladin (1888) found that if wheat plants were left in the dark until they were deprived of their carbohydrate reserves, they lost a portion of their protein. Deleano (1912) found that excised leaves of the grape during the first 100 hr. used only carbohydrates in respiration, while the protein remained intact. After the carbohydrate supply was depleted, however, the process of respiration was strikingly altered and the protein was split up into soluble products. Meyer (1918) made the same observation with leaves and

noted that the protein supplied only the carbon chains for respiration and that no loss of nitrogen from the leaves could be observed.


It is evident that the amount of energy which could be obtained by the decomposition of proteins under normal conditions would be very small, for this decomposition is only a cleavage into the amino acids. Furthermore, the plant is capable of re-forming these amino acids again into proteins without the direct utilization of energy save that which is derived from the oxidation of carbohydrates. Spoehr and McGee (1922) believed, therefore, that the total gain in energy for the plant from protein decomposition would be nothing and that unless the proteins yield energy of a certain form or at a particular rate, which is necessary for the proper functioning of certain processes, it is difficult to see what advantage would result or what the mode would be of deriving energy by continual decomposition and subsequent resynthesis of the proteins. It may safely be assumed that the rate of energy release from protein decomposition is much slower than that from carbohydrates, but of the possible different forms of energy liberated in the decomposition of these two types of compounds little or nothing is known.

Since it is known that amino acids have a marked influence upon the action of certain enzymes, Spoehr and McGee suggested that the decomposition of proteins may provide materials essential to the proper functioning of these agents. As the amino acids are amphoteric electrolytes, they may also function in maintaining the hydrogen-ion concentration of the cell contents within definite limits. Spoehr and McGee investigated the effects of glycocoll and asparagin upon the intensity of respiration in excised leaves of *Helianthus annuus* and found that the leaves which were fed glycocoll respired more actively than those which had not thus been treated. The rate of respiration was increased by feeding the leaves with d-glucose, but this rate was further increased by feeding in addition glycocoll or asparagin. When the leaves were given sucrose there was an initial drop in the rate of carbon dioxide emission, which probably represented the time required for the sugar to migrate into the leaves, after which there was an irregular rise which became prominent after 35 hr. When glycocoll was added in addition to the sucrose, there was a marked rise in the rate of respiration immediately after the initial drop. Hafenrichter (1928), however, in his study of the germination of the soybean concluded that there was no evidence under the conditions of his experiments to support the theory that amino acids stimulate respiration.


Hafenrichter (1928) pointed out that since the stored food materials of seeds undergo a series of changes during the germination and development of the seedlings, there would be qualitative and quantitative differences in the materials available for respiration. The manner in which these qualitative and quantitative differences may affect respiration

under various conditions has not, however, been investigated to any extent and it is not known whether or not the required amount of energy under any set of conditions is always supplied by a definite metabolic process. It has been demonstrated for animals that it is possible to maintain the same energy relations by substituting foods that are qualitatively different provided that the caloric values remain constant. It has been observed, as has been previously mentioned, that plants apparently prefer one of two closely related carbohydrates for respiration and it has also been found that some plants may utilize different amounts of one food in the presence of different quantities of another. This indicates that external as well as internal conditions determine the kind of materials that may be utilized in respiration. From a study of the respiration of the seedlings of two varieties of soybean, Hafenrichter concluded that the difference in the respiration of different plants cannot be explained on the basis of quantitative differences in the reserve food materials. He obtained evidence, however, which suggested that plants exhibit a selection of organic compounds in their metabolism and that this is reflected in their respiration.

4. Aerobic and Anaerobic Respiration.—Under the conditions of a normal supply of free oxygen, the process of respiration is marked by an absorption of oxygen, by a consumption of organic compounds, especially of carbohydrates, and by the appearance of water and carbon dioxide as end products. When respiration proceeds after this manner, it is termed “normal,” “aerobic,” or “oxygen respiration.” If carbohydrates are the compounds concerned, the chemical procedure in the process is represented by the equation




If ethyl alcohol is the compound concerned, the equation is written:



In some cases, carbon monoxide appears to be a product of respiration. Thus Langdon and Gailey (1920) reported from 1 to 12 per cent of this gas but no carbon dioxide in the hollow pneumatocysts of *Nereocystis luetkeana*.

When plants are placed in an atmosphere devoid of free oxygen, the process of normal respiration is greatly modified so that the end products are carbon dioxide and a number of more or less complex compounds including ethyl alcohol, acetic, formic, oxalic, propionic, other organic acids, and probably molecular hydrogen instead of simply carbon dioxide and water. Under this condition, however, the evolution of carbon dioxide, as a rule, is at a much lower rate than during aerobic respiration. When respiration proceeds after this fashion it is termed “intramolecular”

or "anaerobic respiration," or "fermentation." Under the conditions of anaerobic respiration, the decomposition of the organic compounds may be accomplished in some instances by the rearrangement of the atoms within the molecule without the presence of any oxygen supply. Alcoholic fermentation is one of the best examples of this type of procedure. The process is represented by the equation



The partial oxidation of organic compounds under anaerobic conditions may also occur under the influence of oxygen which has been derived from the breaking down of other organic compounds. It is therefore conceivable that the oxygen thus derived from one part of a complex molecule may oxidize even another part of the same molecule. In no case, however, in anaerobic respiration is the oxidation of complex compounds entirely completed to carbon dioxide and water.

5. Relationship of Anaerobic and Aerobic Respiration.—According to Kidd (1916), Rollo as early as 1798 noted that plant tissues produced carbon dioxide in the absence of free oxygen as a vital process, but his statement was not accepted for many years afterward. Pfeffer (1881 to 1885) termed this anaerobic production of carbon dioxide "intra-molecular respiration," as he believed that it was a normal process in respiration and genetically connected with a subsequent oxidation by the oxygen of the atmosphere under ordinary conditions. An impetus was given to this manner of considering anaerobic respiration when Stocklase and Czerny (1903) reported the extraction of an enzyme from beet roots, potatoes, peas, and other plant tissues and also from animal tissues which appeared very similar in its action to the enzyme zymase from yeast which has the power of converting sugar into ethyl alcohol and carbon dioxide. It was through the extensive studies of Palladin and Kostytschew, however, from 1888 to 1920, and through the suggestions of Barnes (1905) and Peirce (1909, 1912) that the theory of the direct relationship between anaerobic and aerobic respiration came to be generally accepted. The student is referred to Kostytschew (1927) for a detailed review of the literature pertaining to this subject.

It is now generally believed that anaerobic and aerobic respiration are intimately connected in the vital activities of the plant. The present theories of respiration generally assume that anaerobic respiration constitutes a preliminary step in the process. This initial decomposition of the organic materials in the process of respiration is believed to be independent of free oxygen. This may be brought about by a rearrangement of the atoms within the molecule or by the intervention of oxygen derived from other compounds. The end products derived from this initial decomposition are believed to be ethyl alcohol (Palladin and Kostytschew, 1906), organic acids, and carbon dioxide. It is believed by

some that ethyl alcohol and carbon dioxide are the principal compounds formed in this initial step (Genevois, 1927; Blackman, 1928). Under normal conditions, however, plants and animals utilize free oxygen to oxidize to carbon dioxide and water, the products produced in anaerobic respiration. If this is true, then anaerobic respiration is proceeding under the conditions of aerobic respiration, but it is not discernible, because its end products are almost immediately oxidized.

Most organisms, however, can live for only a short time by the process of anaerobic respiration and must be supplied with free oxygen if they continue to function normally. The inability to survive may be due to one or both of the following causes: In the first place, the products of anaerobic respiration may be toxic to the protoplasm, so that unless they are oxidized by the free oxygen their accumulation will render the protoplasm completely inactive. The production of black heart in Irish potatoes is a good example of the detrimental effects that may be initiated by anaerobic conditions (Bennett and Bartholomew, 1924). In the second place, if sufficient free oxygen is not present, the decomposition processes in the anaerobic stage may reach an equilibrium due to the accumulation of the products thus formed. There may be needed in the process some substance to disturb constantly in one direction or another the equilibrium that tends to be reached, and oxygen appears to be the agent in this regard.

The initial decomposition of the compounds which occur in anaerobic respiration is considered by some to be the process which liberates the energy necessary for the vital activities of the cell. The energy derived from the oxidation of the end products of anaerobic respiration is assumed to be greatly in excess of what is actually needed and is lost by radiation, conduction, and convection into the surrounding medium (Peirce, 1909 to 1912). The amount of energy liberated, however, in anaerobic respiration is small compared with that released in aerobic respiration. Thus in the transformation of a gram molecule of glucose to alcohol and carbon dioxide, 57 kg. cal. of heat would be liberated. The oxidation of the alcohol thus produced to water and carbon dioxide would liberate 652 kg. cal. of heat. The complete oxidation of a gram molecule of glucose would consequently give 709 kg. cal. In order to liberate a given amount of energy, more than twelve times as much glucose must be used in fermentation or anaerobic respiration as would be required in aerobic respiration (see also McGinnis and Taylor, 1923).

The following observations are generally presented as evidence to substantiate the assumption that anaerobic respiration is a normal process of the organism under conditions of a free oxygen supply and that it is intimately connected with oxygen respiration:

a. All the plants which have thus far been examined are able to produce carbon dioxide in the absence of free oxygen. This behavior is

believed to be so general that it cannot be considered simply a biological adaptation to abnormal conditions but must be classed as a vital process of all cells.

b. When plants are transferred from an anaerobic condition to one which has a normal supply of free oxygen, the production of carbon dioxide is markedly increased over that which normally prevails under aerobic conditions. This excess carbon dioxide production is assumed to be due to the oxidation of the accumulated end products of anaerobic respiration.

c. Any changes that are made in the external conditions, excepting the oxygen supply, do not modify the value of the ratio of the carbon dioxide output of anaerobic respiration to that of aerobic respiration. This indicates that the intensity of both types of respiration are influenced by the same factors and to the same extent. Thus Palladin (1894) showed that etiolated bean leaves which were artificially supplied with carbohydrates increased the formation of carbon dioxide in the absence of oxygen in the same proportion as did leaves which were similarly treated and placed under conditions of a normal supply of oxygen. Karlsson (1925) found that the effects of the vapors of ether, benzene, and alcohol upon aerobic and anaerobic production of carbon dioxide by wheat seedlings were closely similar.

d. The oxidizing enzymes of plants are unable to attack sugar directly, but according to Kostytschew (1927) they are able to oxidize to carbon dioxide and water the substances contained in fermented solutions.

e. It has been demonstrated by Zaleski (1915), Kostytschew (1904, 1927), and others that green plants can oxidize ethyl alcohol. This is assumed to account for the failure to detect alcohol in the tissues under normal conditions, a fact which has been used as an argument against the theory that anaerobic respiration occurs normally. It was also found by Kostytschew (1908) that sugar solutions fermented by yeast stimulated the aerobic respiration in plants.

Some investigators, however, including Maquenne and Demoussy (1921), believe that anaerobic and aerobic respiration do not have a common origin but that they proceed from different causes and should both be regarded as autonomous functions as truly in their intimate mechanism as in the influence they exert upon the life of the green plant. A direct proof that anaerobic respiration is the initial step in normal respiration and is thus intimately associated with aerobic respiration is difficult and could be supplied only if it were possible to demonstrate which products of anaerobic metabolism are oxidized in the presence of oxygen. In the oxidation of organic compounds in respiration there are a great many steps between the original compound and the formation of carbon dioxide and water, and the most important products and reactions

in the process cannot be measured or detected by the chemical methods at present available.

A few facts should here be mentioned in regard to the relative intensity of anaerobic and aerobic respiration as measured by the production of carbon dioxide. As a general rule, the production of carbon dioxide in anaerobic respiration is less than that under aerobic conditions ranging from 18 to 85 per cent of the latter. The production of carbon dioxide in anaerobic respiration is greater, however, than that which would be produced by the formation of ethyl alcohol and carbon dioxide by fermentation alone, so that some of the carbon dioxide evolved must have its origin from other sources than from the activity of zymase. Some cases have been reported in which the intensity of anaerobic respiration is measured by the evolution of carbon dioxide equalled or exceeded its production in aerobic respiration. Thus Hill (1913) found that the production of carbon dioxide by ripe cherries, blackberries, and grapes for a considerable period of time was as rapid as the aerobic production. The fruits which showed this, however, had apparently finished their growth and were ripe. He found, however, that green peaches and germinating wheat respired more than twice as intensely under aerobic as under anaerobic conditions.

6. Aerobic Respiration and Photosynthesis Contrasted.—Jean Ingen-Housz (1774) noted that green plants in darkness rendered the air impure just as did animals and that in daylight the fruits, flowers, and roots acted in the same manner. He was thus apparently the first to define in this general manner the conditions under which plants carry on respiration, although he did not recognize the significance of his observations. It remained for De Saussure (1804) to show that this absorption of oxygen and the formation of carbon dioxide were stages in the respiration of plants and that the respiration of plants was identical with the respiration of animals. He also recognized the formation of water in the process and was one of the first to explain the relation of respiration in growth and the other vital activities of the plant.

For a long time, however, the processes of respiration and photosynthesis were not clearly defined, and it was considered that they did not occur concurrently in the same cells. It was argued that it was impossible that two processes which were directly the opposites could occur in the cells at the same time. This erroneous idea still persists, and it is frequently stated that one of the marked differences between green plants and animals is that the plants take up carbon dioxide and give off oxygen while animals absorb oxygen and eliminate carbon dioxide. This statement is only partially correct and leaves the general impression that green plants do not carry on respiration. The best way in which to differentiate clearly between photosynthesis and respiration is to contrast them in regard to the time and place of their occurrence,

the compounds used, the end products formed, and the relation of these two processes to the energy supply of the plant. These points may be contrasted after the following manner:

Photosynthesis	Respiration
1. Photosynthesis occurs only in the chlorophyllous cells of plants.	1. Respiration occurs in every living cell regardless of its color and regardless of whether it is of plant or animal nature.
2. Photosynthesis occurs only in the sunlight or under artificial illumination.	2. Respiration occurs all the time. It occurs in darkness as well as in light.
3. In the process of photosynthesis water and carbon dioxide are used.	3. In the process of respiration water and carbon dioxide are the end or waste products.
4. In the process of photosynthesis oxygen is given off as a waste product.	4. In the process of respiration oxygen is used.
5. Food is built up in the process of photosynthesis.	5. Food is destroyed in the process of respiration.
6. Photosynthesis increases the weight of a plant.	6. Respiration decreases the weight of a plant.
7. Energy is stored in the process of photosynthesis.	7. Energy is released in the process of respiration.
8. The chemical equation of photosynthesis is written: $6\text{CO}_2 + 6\text{H}_2\text{O} \rightarrow \text{C}_6\text{H}_{12}\text{O}_6 + 6\text{O}_2$	8. The chemical equation of respiration is written: $\text{C}_6\text{H}_{12}\text{O}_6 + 6\text{O}_2 \rightarrow 6\text{CO}_2 + 6\text{H}_2\text{O}$

7. Respiration and Breathing.—In the preceding topics, the process of respiration in plants has been discussed in regard to the place of its occurrence, the materials used, and the waste products produced. It is the intention here to describe the means by which the oxygen is supplied to the cells for use in respiration and the manner in which the waste products are eliminated from the plant body. In discussing these processes, it is necessary to distinguish between the terms “respiration” and “breathing.” These two terms are commonly used synonymously, but from a biological standpoint each has a distinct meaning and the difference between them should be clearly fixed. Breathing is the forcible inhaling and exhaling of air by the animal body, while respiration is an energy-releasing process that occurs in every living cell. In the higher animals there are special organs—the nose, windpipe, lungs, and certain muscles—that are employed to draw the air into the body and to force it out again. The air entering the body contains the oxygen supply needed in respiration, while the air leaving the body contains the carbon dioxide and water which are the waste products of the process. After the air has entered the lungs, a portion of its oxygen is taken up by the blood stream and carried to the cells of the body. This oxygen is taken up by the cells while the carbon dioxide and water formed in the cells as a result of respiration diffuse into the blood stream and are carried primarily to the lungs where they are eliminated with the exhaled air.

Plants, in contrast with animals, do not have any special organs for drawing air into the body and forcing it out again. The air simply diffuses in and out through the stomata, lenticels, and cuticle of the younger plant parts. After entering the plant, it circulates through the intercellular spaces in the plant and possibly to a considerable degree in solution in the water movements of the plant. As the air thus comes in contact with the cells of the plant, they absorb the oxygen therefrom and give up the carbon dioxide thereto that has been formed in respiration. The entrance and exit of these gases from the cells is due primarily to the difference in gradient which exists between the respective gases in the cells and in the surrounding air. The oxygen exterior to the plant diffuses inwardly through the lenticels, stomata, and intercellular spaces to restore the oxygen equilibrium which has been disturbed by the absorption of oxygen by the cells. Likewise, the carbon dioxide diffuses outwardly through these openings, since its concentration within the intercellular spaces is higher than that of the surrounding air. Plants thus differ markedly from animals in regard to the manner in which they obtain their air supply and by which they eliminate the end products of respiration into the external atmosphere. The general statement can thus be made that animals breathe but plants do not. The student should keep clearly in mind that respiration is a chemical process which goes on continuously in every living cell whether of plant or animal nature, while breathing is a mechanical process that supplies air to and eliminates it from the animal body but does not occur in plants at all.

8. Methods of Measuring the Intensity of Aerobic Respiration.—The intensity of aerobic respiration in plants may be measured by the loss in weight, the amount of oxygen absorbed, or the amount of carbon dioxide produced by the plant or plant part concerned. A detailed description of the various methods is beyond the scope of this work and the student is referred to Harrington and Crocker (1923) and Kostytshew (1927) for references and more complete information. It is the intention here to describe in detail only two of these methods and to describe only the general procedure to be followed in others. Most of the methods that have been devised for determining the rate of respiration are based on the measurement of the carbon dioxide which is produced. These methods may be grouped as follows according to the principles involved in their manipulation:

a. One of the oldest and most generally used types of procedure is to allow the carbon dioxide which is respired to diffuse into a stream of carbon dioxide free air, which is constantly being drawn through the apparatus containing the respiring material. This air then passes through a solution of alkali which depletes it of the carbon dioxide that it thus acquires. The amount of carbon dioxide may then be determined by titration, by the increased weight of the absorbent, or by the weight of the precipitate provided an insoluble carbonate is formed. Apparatus of this type have been devised or modified by Pfeffer (1885), Kostytshew (1908), Gurjar (1917), Ginsburg (1925), and Beaumont, Willaman, and DeLong (1927). For relatively large amounts of actively respiring materials, methods of this type are excellent for measuring the carbon dioxide produced. They have the advantage in that the air is constantly renewed over the respiring material so the disturbing effects of the changes in

the partial pressures of carbon dioxide and oxygen which occur in closed containers are avoided. The methods of this type, however, neglect entirely the question of the absorption of oxygen, which is not always proportional to the amount of carbon dioxide given off. They are not adapted for use with limited quantities of small or inactive material, as the experimental error is relatively large so the amount of carbon dioxide given off in a reasonable time may fall within the limit of error.

One of the most common methods of the above type which can easily be used by students in the laboratory is conducted after the following manner: The apparatus, which consists of a connected series of closed containers, U-shaped calcium chloride tubes, and potash tubes, is attached at one end to a filter pump by means of which a continuous stream of air is drawn through the apparatus. As the air enters, it is drawn through a concentrated solution of sodium or potassium hydroxide and thence through a solution of barium hydroxide, which will indicate whether or not the entering air has been deprived of its carbon dioxide. The carbon-dioxide-free air now passes over the respiring material which is in a closed container and thence through calcium chloride tubes, which depletes it of moisture. The moisture-free air thence is drawn into weighed potash bulbs containing a concentrated solution of sodium or potassium hydroxide where the carbon dioxide is absorbed. The air which has absorbed moisture from the alkali solution next passes through weighed calcium chloride tubes where this moisture is again absorbed. After the experiment has proceeded the required time, the alkali tubes and the last two calcium chloride tubes are weighed. The initial weight of the alkali tubes is subtracted from their final weight plus the increased weight of the two calcium chloride tubes. This difference in weight represents the weight of the carbon dioxide which has been eliminated by the respiring material during the period of the experiment.

b. Numerous types of microrespirometers have been devised for the detection of very slight changes in the composition of the gases under consideration. Instruments of this type have been devised and used by Tashiro (1913), Osterhout and Haas (1917), Lund (1919), and others. Some of these methods are too complicated for general use and are limited in regard to the quantity of material that may be used. None of them provides for the simultaneous determination of both sides of the respiratory exchange in the same material.

c. An indicator method has been perfected by Haas (1916) and Osterhout (1918) for the detection of small quantities of carbon dioxide respired. The method has the advantage of sufficient sensitiveness so that the experimental period can be very short. The method is also useful for the rapid and simultaneous determination in several different experiments. By a special arrangement the apparatus can be used to determine approximately the amounts of oxygen absorbed. Indicator methods for the determination of the oxygen absorbed by respiring material have been described by Osterhout (1918). The use of the indicator method requires care to avoid errors due to buffer effects or to the production of acid reacting substances other than carbon dioxide or of alkaline-reacting substances (Harrington and Crocker, 1923).

d. A method which has been used to a considerable extent is to place the respiring material in a closed container and occasionally sample the air for analysis in some form of micro-apparatus. This method is described in detail by Thoday (1913) by whom it was used with success.

e. The absorption by a solution of alkali of the carbon dioxide respired in a closed container with manometric measurement of the oxygen absorbed has been used by Stich (1891) and others. This type of apparatus gives both the oxygen consumption and the carbon dioxide produced. The method, however, has a disadvantage, since the carbon dioxide is absorbed as rapidly as it is produced and thus does not compensate for the oxygen absorbed by the respiring material. This fact causes relatively

large changes in pressure within the apparatus which might affect the behavior of the plant in the experiment.

An apparatus for the measurement of the gaseous exchange in the respiration of seeds and small parts of plants, devised by Harrington and Crocker (1923) and later modified by Davis (1925), is shown in Fig. 35. This instrument, based upon the principle of the respirometer of Ganong (1908), is one of the most accurate and easy to operate of the many respirometers that have been devised. With this apparatus, the oxygen consumption and the carbon dioxide evolved are determined in the same apparatus and for the same period of time, using the whole volume of air instead of a sample. This apparatus also has an advantage in that the carbon dioxide given off by the respiring material accumulates and tends to compensate for the oxygen absorbed so no large changes in pressure occur during the experimental period.

This apparatus consists of a cylindrical glass tube *c* in the form of a bottle with an extension *c'* which serves as a receptacle for the seeds or material to be studied. Into the mouth of this cylinder is fitted a ground-glass stopper *s* upon which are mounted a short open manometer *m* with a 2-mm. bore and an inlet tube provided with a stop cock *sc* and a small chamber *ch*. The stopper fits deep into the neck of the cylinder so that a mercury seal *mc* can be made. The apparatus has been used in three sizes of about 20, 40, and 80 cc. capacity. Before conducting an experiment, the combined capacity of the corked cylinder *c* including the seed chamber *c'* and the pores of the manometer to the level of the mercury and of the intake tube to the stop cock *sc* must be determined. This is found by measuring the volume of water necessary to fill these parts of the apparatus.

After the volume of the instrument has been determined, the soaked seeds *s'* whose volume and weight have been obtained are placed in the seed chamber *c'*. The glass stopper is then inserted in the cylinder, the stop cock *sc* and cork of the intake tube being left open to equalize the pressure, and the mercury seal made. The apparatus is then placed in any convenient thermostat, preferably a water bath, and as soon as the instrument has come to the desired temperature the stop cock *sc* in the intake tube is closed and the chamber *ch* stoppered. Care must be taken that the respirometer stands vertically and that the mercury in the manometer *m* is at the same level in the two arms. The experiment is now ready to proceed and the temperature of the medium surrounding the respirometer is taken and the barometric pressure is recorded.

After the experiment has proceeded for the desired period, which is generally from 24 to 48 hr., from 1 to 3 cc., as required, of 20 per cent sodium hydroxide is measured into the chamber *ch* of the intake tube, which is then left unstoppered. The manometer reading is then taken by holding a millimeter scale behind the arm of the manometer. The stop cock *sc* is now opened and the alkali carefully admitted




FIG. 35.—Diagram of respirometer. *c*, chamber of respirometer. *c'*, seed chamber. *s'*, seeds. *s*, ground-glass stopper with attached manometer and supply tube provided with a small chamber *ch* and a stop cock, *sc*. *mc*, mercury seal. *m*, mercury. (After Davis, 1925.)

into the respiratory cylinder *c*, care being taken that no air escapes from the cylinder. The temperature of the medium surrounding the respirometer and the reading of the barometer are recorded. After absorption is completed, the manometer reading is again determined.

From the manometer and barometric readings, the temperature, and the volume of the apparatus corrected for the volumes of the respiratory material and of the alkali admitted, the three significant volumes of air under standard conditions (0°C., 760 mm.) can be determined. From these three volumes, the volume of oxygen absorbed and the volume of carbon dioxide given off may be calculated after the following manner (Sherman, 1921; Harrington and Crocker, 1923):

V_r = volume of the respirometer
 V_s = volume of the imbibed seeds
 V_a = volume of the absorbent alkali
 T_1 = initial absolute temperature
 T_2 = final absolute temperature
 B_1 = initial barometric pressure
 B_2 = final barometric pressure
 m_1 = initial manometer reading
 m_2 = final manometer reading

$$A. (V_r - V_s) \frac{273}{T_1} \cdot \frac{B_1}{760}$$

$$B. (V_r - V_s) \frac{273}{T_2} \cdot \frac{B_2 \pm m_1}{760}$$

$$C. (V_r - V_s - V_a) \frac{273}{T_2} \cdot \frac{B_2 \pm m_2}{760}$$


$B - C$ = the volume of carbon dioxide eliminated

$A - C$ = the volume of oxygen absorbed

From this the respiratory quotient CO_2/O_2 is easily calculated. The number of milligrams of carbon dioxide eliminated and of oxygen absorbed per gram of imbibed weight for any given period can also be determined; 1 cc. of carbon dioxide weighs 1.96 mg. and 1 cc. of oxygen weighs 1.428 mg. at 0°C. and 760 mm. barometric pressure.

9. The Respiratory Quotient.—The ratio of the volume of carbon dioxide given off to the volume of oxygen absorbed during respiration is termed the “respiratory quotient” and is written CO_2/O_2 . Great diversity of opinion, however, exists as to the importance to be attached to the value of this ratio as an index to the reactions occurring in respiration. A discussion of the factors which may cause the fluctuation of this ratio will serve to show some of the conditions prevailing in the tissues that may be indicated by its changes in value.

a. The types of materials consumed in respiration will influence the value of the respiratory quotient. Thus under the ordinary aerobic conditions of respiration, if carbohydrates are the compounds utilized in the process and if all the oxygen absorbed by the plant is consumed in their combustion, the volume of oxygen absorbed would be equal to the volume of carbon dioxide given off according to the equation and the



respiratory quotient would be unity. If organic acids which are relatively rich in oxygen were the materials utilized, the respiratory quotient would be greater than unity. Thus the respiratory quotient for the complete oxidation of tartaric acid would be 1.6, while that of oxalic acid would be 4.0. If fats are the materials utilized in respiration, the respiratory quotient is less than unity, since most of these compounds are relatively low in oxygen.

b. A portion of the oxygen which is absorbed by the plant may be utilized for purposes other than that of respiration. This extra oxygen may be used in the formation of organic acids. The depression of the value of CO_2/O_2 due to this factor is noticed in the storage of organic acids in ripening fruits and in succulents (Richards, 1915). The fats are relatively low in oxygen and generally absorb oxygen to satisfy their unsaturated condition before their disintegration is initiated in the process of respiration. If the fats are converted into sugar before they are ultimately used in respiration, this transformation requires a quantity of oxygen which is not indicated by the quantity of carbon dioxide produced when the sugar thus formed is oxidized. This accounts for the low respiratory quotient of plant parts which contain fats as reserve foods.

c. Carbon dioxide may be formed without the absorption of oxygen. This occurs under anaerobic conditions, as has been mentioned previously. The same effects may occur, but to a lesser degree if the supply of oxygen is rather limited. Under these conditions the respiratory quotient is greater than unity. During the ripening of oily seeds the respiratory quotient is also greater than 1. As mentioned in Chap. X, the fats in oily seeds are formed at the expense of carbohydrates. In the transformation of carbohydrates to fats a certain amount of oxygen is set free. The oxygen which has thus been freed is utilized directly in respiration, and consequently a smaller amount is absorbed from the exterior than would otherwise occur. Consequently the volume of carbon dioxide produced is greater than the volume of oxygen absorbed, and the respiratory quotient is greater than unity.

d. The respiratory quotient may also vary according to the temperature at which the observations are made. This has been explained by the fact that both the absorption of oxygen and the exhalation of carbon dioxide vary with differences of temperature, but they vary in different degrees. Harrington (1923) noted in respiratory studies of dormant apple seeds that the respiratory quotient increased with an increase in temperature. He believed that this was due to an impoverishment in easily oxidizable substances and might also be indicative of an oxygen deficiency in the respiring tissues. The respiratory quotient decreased with a decreasing temperature. This indicated a storage of oxygen which became very considerable at 10 and 0°C. In the respiration of these seeds the temperature coefficient was affected by the previous treat-

ment. It was higher after treatments which tended toward after-ripening and lower after treatments which induced deeper dormancy. The influence of external and internal conditions upon the respiratory quotient is, however, but little understood, and no definite statements can be made in that regard. Some of the observations that have been made upon the value of the respiratory quotient should be mentioned here. Godlewski (1882), as quoted by Harrington (1923), found that the respiratory quotient of oily seeds during swelling was only a little less than 1 but that its value decreased as soon as the roots appeared and remained approximately constant at a value of 0.55 to 0.65 during the period of the greatest respiratory activity, after which it rose again to approximately unity. Similar observations were made by Bonnier and Mangin (1884), who found that with both oily and starchy seeds during germination, the respiratory quotient was at first approximately unity but fell gradually as germination progressed to a minimum, which varied with the type of seed, and then rose again to its initial value. These fluctuations in the value of the respiratory quotient may be explained, in part at least, upon the basis of the nature of the food available for respiration. Practically all seeds whether of a starchy or an oily nature contain a small reserve of sugars which serve the seedling in the initial stage of germination, so that while this is being utilized the respiratory quotient would be approximately unity. Even starchy seeds contain more or less oil which is generally concentrated in the embryo. If, as would be expected, this oil is drawn upon during very early germination, the large use of oxygen in its conversion to sugar would give a temporarily low value to the respiratory quotient of such seeds. Gerber (1900) considered that in the germination of oily seeds, the value of the respiratory quotient will be near that for complete oxidation (approximately 0.70) provided that the stored fats are easily oxidized. If these fats, however, are difficult of oxidation, the respiratory quotient will be low and near to that for the conversion of fats to sugar.

Harrington (1923) observed that the respiratory quotient of dormant apple seeds at 19°C. was 0.70, a value which corresponds to the complete oxidation of fats. At the beginning of germination there was a rise in the respiratory quotient to 1.2, which indicated the breaking up of oxygen-rich bodies much more rapidly than they were replaced, being thus associated with a temporary deficiency of oxygen in the ripening tissues. In a study of the respiration of the dormant seeds of *Amaranthus retroflexus*, *Chenopodium album*, *Rumex crispus*, and *Crataegus coccinea*, Sherman (1921) observed that the value of CO_2/O_2 varied within wide limits but that in all cases except *Rumex* the respiratory quotient was less than unity. Cerighelli (1924) reported that the respiratory quotient of the roots of wheat, sunflower, corn, peas, buckwheat, rhubarb, and others at the beginning of development was always less than unity. In annuals

low in stored foods, it remained less than unity during growth, while in those which accumulated reserve foods it became greater than unity.

10. Respiration and the Production of Heat.—It is a familiar fact that respiration produces heat in the animal body, but that this occurs in plants is not known so generally. The heat produced by respiration in plants is quickly dissipated into the surrounding air, primarily because they have no means of controlling its loss and because they have a large surface in proportion to their mass. Fleshy fruits, bulbs, and tubers may, however, retain sufficient heat to raise their temperature slightly above their surroundings. Thus ripening bananas maintain themselves at temperatures distinctly above that of their surroundings, while Richards (1897) states that the temperature of the Irish potato was 0.17°C . and that of the onion 0.5°C . higher than the surrounding air. The production of heat by respiration in plants, however, cannot readily be observed unless the proper precautions are taken to prevent its loss.

The method which is now the most commonly used for demonstrations in laboratory studies was developed and perfected independently by Ganong (1908) and Peirce (1908). The general procedure is to place the plant parts to be studied in Dewar flasks or thermos bottles, insert a thermometer, carefully plug with cotton, insulate the containers as thoroughly as possible, and note the changes in temperature as indicated by the thermometer. This experiment, however, is not so easily performed as it would at first appear, since to obtain reliable results, certain conditions of which some are difficult to obtain, must be satisfied. According to Potter (1917), some of these conditions are (*a*) a sufficiently large amount of material, (*b*) a supply of oxygen, (*c*) a means for the disposal of the carbon dioxide produced, and (*d*) efficient control for the prevention of putrefaction and fungal growth. This last condition is the most difficult to obtain in this experiment. The heat equivalent of the material under consideration, of the water used, and of the container must also be known and taken into consideration if accurate results are to be obtained.

The results obtained by Peirce (1912) with peas are commonly cited as illustrations of the liberation of heat by plants in respiration. He placed 75 g. of air-dry peas which had been rinsed with a solution of mercuric chloride in a Dewar flask, added 100 cc. of sterilized distilled water, and noted the changes in temperature. The temperature of the flask rose from 18°C . at the beginning of the experiment to 38°C . at the end of 5 days, after which it remained constant. In the 7 days this quantity of peas liberated 2,593 cal. or an average of 370 cal. per day. In similar experiments Darsie, Elliott, and Peirce (1914) determined the average daily increase in temperature of several kinds of seeds due to respiration when infection from bacteria and fungi was prevented. They found that the increase in temperature to be expected from 10 g. of viable

seeds was 1.82°C . for hemp, 0.80° for barley, 0.75° for clover, 0.73° for wheat, 0.55° for oats, and 0.49° for corn. Their experiments indicated that the quantity of heat liberated in respiration when they were placed under conditions favorable for germination gave some indication of the quality of the seeds, of their viability, and of the vigor of their growth immediately following germination.

The question arises as to the value of the heat liberated in respiration to the plant. Peirce (1909, 1912) was of the opinion that while the essential product of respiration is energy, it is the energy which is immediately converted into work that is utilized by the plant in its vital activities. If the aerobic phase of respiration is merely considered a process of purification whereby useless or injurious substances are converted into forms which can be eliminated, then the heat thus liberated may be considered as of no special benefit to the plant. It may be considered as a waste product of respiration just as carbon dioxide and water.

The heating of moist grain when placed in storage is due primarily to the heat generated in the respiration of the cells of the seeds. A high temperature and moisture content are two factors which especially stimulate respiration, as will be discussed in subsequent topics. In this self-heating of grains, respiration may raise the temperature to a point where other chemical reactions may occur (Gore, 1911). Bacterial action may also play a part under these conditions. When grain with a high moisture content is stored, the heat generated from respiration cannot readily be dissipated into the atmosphere, so that it accumulates and raises the temperature to a point where it is injurious to the seed and where it may even cause the disintegration of the tissues. Hot weather accelerates the heating of stored moist grain in two ways. It affects it biochemically by increasing the rate of enzyme action and physically by reducing the rate of conduction of heat into the atmosphere. Bailey (1918) found that all the normally plump spring wheat that heated contained over 14.3 per cent of moisture. He observed that sound, plump, hard wheat containing less than 14.5 per cent of moisture would keep without heating in storage in a temperate climate. A lower moisture content must be employed, however, in storing shriveled or frosted wheat and possibly also with plump wheat in a mild climate.

11. Factors Affecting Respiration. *a. Temperature.*—It is apparently well established that the rate of respiration increases with the temperature until the latter begins to injure the tissues. Clausen (1890) found the temperature coefficient for the respiration of germinating wheat to be 2.86 between 0 and 10°C ., 1.09 between 30 and 40°C ., with an average value of 2.71 between 0 and 40°C . Matthaei (1905) observed that at 5.8°C . 2 g. of leaves respired 0.1 mg. of CO_2 per hour, while at 35.1°C .

the rate was 1.35 mg. per hour. Gore (1911) obtained an average temperature coefficient of 2.38 in 49 respiration experiments with 40 different fruits. Olney (1926) noted that the rate of respiration in ripening bananas at 12°C. was only one-third of that at 20°C. Bigelow, Gore, and Howard (1905) noted that the respiration of apples was twice as high in cellar storage as in cold storage. Morse (1908) studied the intensity of respiration of apples at different temperatures by determining the amount of carbon dioxide evolved. Some of his results are shown in the following table:

MILLIGRAMS OF CARBON DIOXIDE EXHALED PER KILO OF APPLES PER HOUR

Experiment	0°C.	5° to 10°C.	18 to 25°C.	Experiment	0°C.	5 to 10°C.	18 to 25°C.
1	2.3	8.0	16.4	4	2.8	8.8	18.2
2	2.6	7.3	18.7	5	2.2	7.9	18.0
3	3.8	8.7	12.6	6	5.2	13.2	21.9

The effect of the temperature upon the rate of respiration of Wagener apples directly after picking was determined by Burroughs (1922). At 0°C. the carbon dioxide eliminated amounted to only 3.1 mg. per kilo of apples per hour as compared with 7.5, 12, and 24.4 mg. per kilo per hour, respectively, for temperatures of 9, 20, and 30°C. Hopkins (1924) noted that the carbon dioxide eliminated by Cobbler potatoes at 0, 4.4, 7.2, and 10.0°C. was, respectively, 5.0, 5.1, 6.0, and 8.0 mg. per kilo of weight per hour. It was observed by Drain (1926) that apples of different varieties showed marked differences in their response in the respiration rate to temperature changes. Thus 6 days after picking, the carbon dioxide produced by Maiden Blush apples was 280 mg. per kilo per hour at 25°C. as compared with 46.8 mg. produced by those at 0°C. Apples of the Oldenburg variety, however, produced 55.8 mg. of carbon dioxide per kilo of weight at 25°C. as compared with 39.3 mg. at 0°C. The localization of the oxidase activity in the different varieties is of interest in regard to the intensity of respiration. The Maiden Blush variety shows this localization in the periphery, which suggests that the localization may be influenced by gas exchange. Many apple varieties show greater oxidase activity near the core, which suggests that they have a gas exchange through the calyx tube and core.

The composition of the air contained in the intercellular spaces of apples, potatoes, and carrots stored at different temperatures was determined by Magness (1920). Some of his results are shown in the following table:

Storage temperature, degrees Centigrade	Percentage of		
	Carbon dioxide	Oxygen	Nitrogen
Apples			
2	6.7	14.2	79.1
6	8.4	12.9	78.7
11	12.2	10.7	77.1
20	17.2	5.5	77.3
30	21.4	3.2	75.4
Potatoes			
11	19.6	10.9	
22	34.4	5.7	
Carrots			
11	12.2	13.1	
24	28.6	5.2	

These figures show that marked variations may occur in the composition of the gaseous content in tissues under varying conditions of temperature. It is to be noted that at the lower temperatures the sum of the percentages of oxygen and carbon dioxide closely approximates their total percentage in normal air. As the temperature increases, however, the sum of these gases increases, which indicates that at higher temperatures more than one molecule of carbon dioxide is liberated for each molecule of oxygen absorbed. At the higher temperatures it is probable that some anaerobic respiration occurred due to the relatively small amount of oxygen present. In the tissues of ripening Bartlett pears, Magness and Ballard (1926) also found that the concentration of carbon dioxide was higher and that of oxygen lower in the fruit which was held at higher temperatures than in that held in cold storage. The high concentration of carbon dioxide and the correspondingly low oxygen content in this fruit ripening at a temperature of about 15°C. appear to be associated with the development of high aroma and flavor. The main factors determining the amount of carbon dioxide and oxygen in the intercellular spaces are (1) the rate of oxidation or the rate at which oxygen is taken up from and carbon dioxide given off into the intercellular spaces, (2) the permeability of the skin or epidermal coverings to carbon dioxide and oxygen, and (3) the difference in the pressure of carbon dioxide and oxygen within the tissue which determines the rate of gaseous exchange when the permeability factor is a constant.

Besides the direct effect of temperature upon respiration, there is evidence to indicate that there is a stimulating effect upon the process

caused by temperature changes. Thus Müller-Thurgau (1882) noted that respiration was much more intense in potatoes which had been kept at 0°C. for some time and then returned to the original temperature than in those tubers which had not been so treated. Similar results were observed by Palladin (1899) with bean seedlings and by Burroughs (1922) for freshly picked apples. The latter investigator noted that this stimulation in respiration was more marked for immaturity than for maturely picked fruit.

Kimbrough (1924) determined the respiration rate of potato tubers that had been stored at 32, 40, and 72°F. and found that the lower the temperature of storage the higher was the initial intensity of respiration when they were exposed to warmer temperatures. It was also observed that the initial respiration rate was higher the longer the tubers had been in storage up to 3 weeks, after which longer storage did not further increase the rate. It was noted by Hopkins (1924) in studying the respiration of potatoes at low temperatures that there was a marked acceleration in the rate at 0°C., so that for a considerable period the intensity was greater than at 4.5°C. The curve of respiration for temperatures from 0.8 to 11.5°C. showed a minimum point at 3.0°C., and as the temperature increased it showed an increase at 0° and then a decline. Carrick (1928) found that Winesap apples frozen from 3 to 6 hr. at temperatures of from -7.5 to -8.5°C. increased their respiration at 0°C. as much as 85 per cent above their previously normal performance at that temperature. This acceleration lasted for several days, gradually declining so that slight effects were to be noted 1 month after the treatment. When the respiration rate was measured at 20°C., the treated fruit showed an increase in the rate, although generally with a smaller gain than when measured at 0°C. When the fruit was frozen sufficiently to kill 80 per cent of the cells, the excretion of carbon dioxide at 0°C. was only one-third that which was normally produced at that temperature.

These changes in the rate of respiration can apparently be explained, in some cases at least, by the changes in the sugar content which accompany the changes in temperature. Thus it was noted by Müller-Thurgau (1882), Appleman (1911), and Hopkins (1924) that sugar accumulated in the tubers of the potato at 0°C. Appleman also found that after 2 to 3 weeks at this temperature the diastatic activity had greatly increased over that of the tubers stored at room temperatures. The causes of this accumulation of sugar are not definitely known. It has been suggested that the lower temperatures are unfavorable for respiration, while the activity of diastase is not affected to so great a degree, so that sugar is thus formed in excess of its consumption by respiration and as a consequence accumulates. It is thus assumed that the increased respiration of tubers and fruits following their exposure to low temperatures

is caused by the increased sugar supply available for the process (Butler, 1913). This assumption has been strengthened by the observations of Hopkins (1924), who noted, as previously mentioned, that the respiration of potatoes at lower temperatures showed a marked acceleration at 0°C. over that occurring at 4.5°C. It was found that sugar accumulated in these tubers at 0°C. but began to disappear rapidly when stored at 4.5°C. The respiration curve and that of the change in sugar content thus approximately paralleled each other.

b. Moisture.—The amount of moisture in the tissues, within certain limits, is one of the determining factors in the intensity of respiration. This fact has been especially observed in the case of seeds and grains. In air-dry seeds respiration is proceeding at a relatively low rate, but directly following an increase in their moisture content the intensity of respiration increases. Thus Kolkwitz (1901) found that barley kernels containing 10 to 11 per cent of moisture liberated only 0.33 to 1.5 mg. of carbon dioxide per kilo per hour, while after they had absorbed 33 per cent of moisture, 2,000 mg. of this gas were liberated in a similar period. White (1909) reported that the respiration rate of air-dry seeds of wheat with a moisture content of 12 per cent was 0.03 part of what it was in active seedlings, while the intensity in air-dry seeds of *Acacia melanoxylon* amounted to only 0.0001 of that from the germinating seeds. The coefficient of increase in the respiration rate due to changes in the moisture content was observed in wheat by Bailey and Gurjar (1918) to be as follows:

Increase in moisture, per cent	Acceleration in respiration, per cent
12 to 13	0.16
13 to 14	0.17
15 to 16	1.41
16 to 17	3.02

In corn seed, Bailey (1921) observed that respiration became marked when the moisture content exceeded 13 per cent and that when the moisture content was raised to 15 to 16 per cent an increase in the respiration rate of 400 per cent was obtained. Coleman, Rothgeb, and Fellows (1928) in a study of the respiration rate of the seeds of the sorghums noted the following response in yellow milo and feterita seeds to changes in moisture content at a temperature of 37.8°C. (see table p. 753).

Observations similar to those which have been mentioned in regard to the relation of the moisture content and respiration have been made by Duvel (1904), Babcock (1912), and others.

The length of time the excess moisture is present in seeds bears a relation to the rate of respiration, as may be observed from data mentioned by Bailey and Gurjar (1918) for wheat. The quantity of carbon

Percentage of moisture in the grain	Milligrams of carbon dioxide evolved per 24 hr. per 100 g. of dry matter	
	Yellow milo	Feterita
11	0.53	1.00
12	0.70	1.10
13	1.00	1.58
14	1.56	3.00
15	3.27	5.80
16	7.58	11.80

dioxide respired by a sample of wheat containing 15.2 per cent moisture which was stored 55 days after it was dampened was approximately four times as great as that respired by freshly dampened wheat of the same moisture content. The carbon dioxide evolved from a sample containing 15.7 per cent of moisture which was stored for 108 days was about eight times as great as the wheat of the same moisture content which had just been moistened. It is considered that the dampened grain is favorable for the formation of sugar which tends to accumulate as times goes on so that there is a supply sufficient for a relatively high rate of respiration.

It is worthy of note here that the humidity of the atmosphere may affect the rate of respiration in stored grain by increasing its water content. Thus Bailey (1921) noted that at 35 per cent humidity the moisture content of corn was 8.5 per cent, while at 85 per cent humidity it was 17.8 per cent.

The effect of moisture upon the rate of respiration varies to a considerable degree for different plants or plant parts. Thus Jacquot and Mayer (1927) in the case of the seeds of corn and the peanut found that the rate of carbon dioxide production per unit of moist weight increased with increased water content up to 30 to 35 per cent when the rate began to fall off, while in the bean the respiration rate increased up to 60 per cent before it began to decline. When the carbon dioxide production, however, was determined per unit of dry matter, it was found to increase up to the complete imbibition of the bean seeds (117 per cent) and up to 58 to 60 per cent in peanuts. The respiratory quotient was greater than unity in all of the seeds at low water content and as complete saturation was approached. Fraymouth (1928) studied the relationship of respiration to the moisture content of certain terrestrial algae and other lower plants. In the algae the respiration rate increased rapidly on the addition of water to the air-dry material until the amount of water had reached 100 per cent. There was then a gradual rise in rate until a water content of 600 per cent was reached, when gaseous exchange was apparently seriously impaired. After prolonged drought respiration in these algae was practically zero, but immediately after the addition of water,

it was found to be almost as intense as for fresh material of a similar water content. In the lichen (*Parmelia*) the respiration rate showed no great increase until a water content of 60 per cent was reached, after which it rapidly increased until a water content of 200 per cent was attained. In *Hypnum* sp. there was a gradual rise in the respiratory rate with increasing amounts of associated water until 250 per cent was reached, after which the tissues were saturated with water and gaseous exchange was apparently impaired. The effects of desiccation upon respiration and certain organic constituents of the cacti have been reported by MacDougal, Long, and Brown (1915) and Long (1917).

Several experiments have been reported, however, which show some striking variations from the majority of the observations in regard to the relationship between the moisture content of the tissues and respiration. Smith (1915) by means of a vacuum desiccator diminished the water content of the leaves of the snowdrop and the stem tips of nasturtium and young asparagus and found that the respiratory rate increased with a diminishing water content until about 30 per cent of the water had been withdrawn. The rate of respiration then remained about the same until the water was diminished to about 50 per cent of that originally present. Below this limit to complete dryness, respiration decreased proportionately to the amount of water lost. Palladin and Sheloumova (1918) used potato tubers and exposed a part of the material for drying in the air at room temperature, with the result that during the first few days, in spite of a great loss of water, the intensity of respiration was gradually increased, but after further loss of water there was a distinct lowering of the respiratory rate. When the same tubers were immersed in water, the respiratory intensity was again stimulated for a few days, after which it fell to the normal rate. They thus could not establish any definite correlation between the amount of water lost and the intensity of respiration. Luthra (1924) in experiments with pears kept in moist and in dry air noted that both transpiration and respiration of some varieties were increased in the dry air.

The question naturally arises as to why respiration is accelerated by an increased moisture content. Bailey and Gurjar (1918) assume in the case of grains that the colloids of the cells imbibe water and form elastic gels and that if sufficient water is supplied the gels become more and more dilute. Diffusion through the stronger gels is relatively slow, while through the dilute gels it is relatively rapid. Increasing the moisture content thus results in progressively less viscous gels and a corresponding increase in the rate of diffusion. It is assumed that the rate of respiration depends upon the rate of diffusion between the various cells of the tissues, so that the less viscous the gels of these cells the more rapid the rate of respiration.

c. *Injury*.—It has been known for a considerable time that wounded plant parts respire more intensely than those which are intact. One of the first to observe this fact was Boehm (1887), who called attention to the abnormal production of carbon dioxide by potatoes which had been injured by cuttings. Richards (1896) by using potatoes and carrots cut in four pieces, slit leaves, split hypocotyls, and decapitated roots of seedlings demonstrated increases of as much as 100 per cent in the intensity of respiration when measured by the output of carbon dioxide. In the case of the potatoes and carrots he noted a very marked and sudden increase during the first 2 hr., which again fell rapidly, although to a point still considerably above the normal respiration, and then rose more slowly later to the maximum production of carbon dioxide. The respiratory activity reached its maximum 24 to 30 hr. after the injury had been inflicted. Lutman (1926) found an increased respiration in potatoes during the second and third days after cutting which was followed by a gradual fall until the normal rate of the uninjured tuber was attained. If the cutting was repeated in 5 to 7 days, the respiration curve did not rise so high as after the first cutting, but a similar intensity could be attained by increasing the cut surface. Repeated cuttings lowered the respiration curve until finally the tubers would not respond. By lengthening the intervals between cuttings to 11 to 12 days, the respiration curve more nearly approximated the one obtained after the first cutting. Johnstone (1925) by means of a cork borer removed cylindrical plugs from sweet potatoes and noted that from one lot of roots with an injured area of 7,385 mm.² the evolution of carbon dioxide increased from 64.3 mg. per kilo per hour before wounding to 126.8 mg. during the same time after wounding. It was noted by Coleman, Rothgeb, and Fellows (1928) that cracked grains of the sorghums showed a higher intensity of respiration than did the intact grains.

It was noted by Richards (1897) that the temperature of injured parts of plants was materially higher than that of the surrounding tissues. In the potato no increase in temperature was observed until 24 hr. after injury or at the time of maximum respiratory activity due to injury. This increase in temperature was only 0.4 per cent and was very local, since 2 cm. back of the wound no perceptible differences in temperature could be noted. Similar reactions were also observed in the radish and carrot. Onion bulbs showed the most marked changes in temperature due to injury of any of the material used. The rise in temperature due to injury was as much as 3.3°C. and in contrast with the potato the temperature effect extended a considerable distance into the surrounding tissue.

The probable causes of this increased respiratory activity of tissues following their injury will now be considered. One cause is apparently the facilitation of the gaseous exchange. Thus when Stich (1891) sealed

together the cut ends of a potato with neutral gelatin, no carbon dioxide was evolved. Johnstone (1925) noted in injured sweet potatoes that the rate of respiration increased 97.3 per cent when the injured area was exposed, while it increased only 17.1 per cent when this area was not directly exposed to the air. The sudden and marked increase in the output of carbon dioxide directly following injury is probably due to the escape of this gas which has accumulated in the intercellular spaces of the tissues. This assumption is strengthened by the fact that only bulky tissues show this marked increase in the evolution of carbon dioxide directly following injury. The absorption of oxygen is also rendered more favorable by the freer access of air across the tissues due to injury. This facilitation of gaseous exchange is indicated by the composition of the air taken from the intercellular spaces of uninjured and injured apples, as shown in the following table (Magness, 1920):

State of apple	Storage, temperature degrees centigrade	Percentage of	
		Carbon dioxide	Oxygen
Whole apple.....	1	6.6	14.6
Ends peeled.....	1	1.7	15.8
Whole apple.....	20	17.8	7.0
Ends peeled.....	20	7.4	9.9
Whole apple.....	30	23.9	1.8
Ends peeled.....	30	12.6	8.9

It has been noted by Drain (1926) for apples and Lutman (1926) for potatoes that an injury which is not accompanied by the rupture of the skin does not increase the respiratory rate. This indicates also that the increase in respiration rate due to injury is due primarily to an acceleration of the gaseous exchange between the tissues and the surrounding air.

Lutman (1926) believed that the increased respiration due to injury in the potato may be regarded, in the main, as an irritable response of the protoplasm to the stimulus of the contact of the tuber cells with the oxygen of the air which under ordinary conditions are protected from such a contact by the external layer of cork cells. He was able to remove a large part of the effect of injury on respiration by washing the cut surfaces in running water for 1 to 3 hr. The activators of respiration or the substances upon which they act are apparently soluble in water.

The chemical changes which occur in the injured regions of tissues has also been observed to a limited degree. Thus Grüss (1907) found in the cells around wounded potatoes an accumulation of sugar in the subphellogen and an increase in the oxidizing enzymes and in the diastatic activity. Friedrich (1908) in potatoes noted in the cells bordering the cut surfaces an increase in the total nitrogen and acidity and a

decrease in total carbohydrates but an increase in reducing sugars. He considered that the sugars increased the intensity of respiration while the acids were waste products of this process. Lutman (1926), however, did not consider this increase in sugar content to have any effect upon the respiratory rate. It was observed by Hopkins (1927) that the sugar content of wounded potatoes increased from 53 to 68 per cent of the original amount present. This sugar content began to increase after injury, reached a maximum after several days, and then fell off. He believed that this increase in sugar was brought about by activities leading to callus formation.

d. Kind and Age of Tissues.—The intensity of respiration varies markedly with the kind and age of the tissues. This variation of the rate of respiration of different tissues may be illustrated by the observations of Benoy (1929), who determined the rate of respiration of a number of different vegetables at 30°C. for a 30-hr. period following their harvesting. With respect to the amount of carbon dioxide evolved for equal weights of dry matter, they stood in the following order: asparagus, lettuce, green bean, okra, green onion, carrot, tomato, beet, green mango, and red pimento. It should be noted here that the amount of glucose which accumulated per 100 g. of material was the highest (13.68 g.) in asparagus and the lowest (1.29 g.) in the red pimento. Beaumont and Willaman (1924) found that the output of carbon dioxide from the buds and twigs of a hardy variety of apple as Charlamoff at temperatures of 5.3 and 12.4°C. was greater than that from the Delicious variety which is considered non-hardy. This difference in carbon dioxide evolution held on the basis of the number of milligram per unit of length of twig, weight, volume, or number of buds. This difference in the intensity of respiration was not due to any differences in the extent of the rest period or dormancy.

The difference in the rate of respiration of different tissues has been especially studied in seeds and seedlings by determining the relative respiratory intensity of the embryo and endosperm. In this regard, Burlakow (1898) stated that the respiratory activity in the embryo of wheat was twenty times that of the endosperm. Kolkwitz (1901) found that when wheat kernels were divided transversely into equal portions, the embryo end respired three times as much carbon dioxide as the opposite end when equal weights of material were compared, while Karchevski (1903) reported the aerobic respiration of the embryo of wheat to be twelve times as great as that of the endosperm. The embryo of the rice seed, according to Bailey and Gurjar (1920), also shows a higher rate of respiration than does the endosperm. These same authors also noted (1918) that shriveled wheat respired at a rate two to three times greater than did the plump grains. They attributed this to the higher ratio of embryo weight to endosperm in the shriveled grain as compared

with that of the plump wheat. In many of the studies of the relative rate of respiration in the embryo and endosperm, the embryos have been removed. As the tissues are more or less injured by this operation, this method is open to criticism. The production of embryoless seeds of wheat in certain instances furnished Lyon (1928) an opportunity to compare the respiration rate of these seeds with the normal ones without inflicting any injury upon their tissues. It was found that when these two types of seeds were placed under conditions favorable to germination, the seeds devoid of embryos respired 22.1 mg. of carbon dioxide per gram of seed in 6 days, while the normal seeds gave off 26.5 mg. for the same unit weight. As the embryo made up only 3 per cent of the entire seed by weight, its rate of respiration was decidedly greater than that of the endosperm.

The age of the tissues has a marked influence upon the intensity of respiration. Thus Nicolas (1908) noted that the respiratory intensity of young leaves and stems was from three to seven times greater than that of corresponding fully developed organs taken from the older parts of the plant. Bezagu (1919) observed that respiration was relatively weak in young leaves and increased to a maximum at the time the leaf reached its full development, after which it decreased as the leaf became older. Bergman (1925) and Wakabayashi (1925) found the rate of respiration of the flowers of cranberries much less than that of buds. The shoots of the current year's growth respired two to three times as rapidly as those of the previous year and at about the same rate as the flowers. The young fruits for a period of 1 to 3 days after the petals fell respired very rapidly, the rate exceeding that of the buds, but decreased rapidly with the development of the fruit. Hover and Gustafson (1926) in observations on the respiratory activity of the leaves of corn, oats, sorghum, and wheat noted a decreased activity with increasing age until middle age and thereafter a gradual increase as determined per unit of dry weight. They assumed that this increase was due to the decrease of the dry matter in the leaves after middle age. Maige and Nicolas (1910) considered that both the respiratory intensity and the respiratory quotient increased with the increased turgidity of the cells. An increase in turgidity, however, may be only an indicator of favorable conditions for growth and vital activity and thus not a direct causative factor in increasing respiration.

Kidd, West, and Briggs (1921) determined the respiratory index for *Helianthus annuus* at different stages of growth. They defined the respiratory index as the milligrams of carbon dioxide liberated per gram of dry weight per hour at 10°C. when the amount of respiratory material is not limited and when the external concentration of the oxygen is that of the atmosphere. This index is consequently a measure of the effective amount of respiring cell matter per gram of dry weight.

These observed respiratory indices for the sunflower plant and its parts at different ages are shown in the following table:

RESPIRATORY INDICES OF SUNFLOWER PLANTS AND PLANT PARTS AT DIFFERENT STAGES OF GROWTH

Days from germination	Number of plants used	Dry weight of a single plant, grams	Respiratory index			
			Entire plant	Stem	Leaves	Stem apex
1	30	0.0225	2.90			
2	25	0.0223	3.00			
4	25	0.0242	3.00			
13	10	0.1009	2.80			
22	8	0.630	3.00			
29	2	4.065	2.30			
36	1	12.850	1.21	0.81	1.56	
43	1	22.050	1.03	0.69	1.38	
50	1	45.150	0.94	0.46	1.52	2.56
59	1	93.200	0.66	0.33	1.32	1.72
89	1	294.700	0.48	0.31	0.90	1.13
99	1	377.400	0.37	0.25	0.45	0.89
112	1	818.300	0.26	0.098	0.38	0.75

It is to be observed from this table that the respiratory index of the entire plant falls off continuously from 3 to about one-tenth of this value at the end of the life cycle. The respiratory index of the stem, of individual leaves, and of the flowers, respectively, decreased with the age of the organ. The initial respiratory index of successive leaves decreases with the age of the plant, indicating that the respiratory index of the meristematic tissue decreases with age. The fall in the respiratory index of the meristematic tissue and young leaves indicated that the fall in the respiratory index of the whole plant was not due entirely to the increase in proportion of mechanical tissue. The fall in the value of the respiratory index with age followed closely that of the value of the relative growth rate, indicating a close connection between the "internal" factor for respiration and the "internal" factor for growth.

Gustafson (1929) found a decrease in the production of carbon dioxide during growth in the John Baer variety of tomato fruits until a minimum point was reached at about the time increase in size stopped. This was followed by an increase in carbon dioxide production which reached its maximum when the fruits were orange red in color, after which there was a final decrease in respiration. Gustafson attributed the increase in respiration to a lowering of the H-ion concentration in the cell sap, while the final decrease was thought to be due to a slowing down of all life activities as the fruit approached its maturity. Hafenrichter

(1928) found, however, in the germination of the soybean that if the growth rate of the entire plant was considered instead of its parts, the maximum rate of respiration was reached earlier in the development of these plants than was the maximum rate of growth.

e. Anesthetics.—It was observed by Irving (1912) that very small doses of chloroform applied as vapor to leaves increased their respiration. This increased rate could be maintained if the chloroform was applied continuously, but when it was withdrawn the respiration rate dropped to normal. When medium doses were applied, an initial outburst of carbon dioxide resulted which was followed by a decline much below normal, the rate and extent of this decline increasing with the amount of chloroform used. When strong doses were applied, there was no initial increase of carbon dioxide, and its production rapidly dropped to zero. Thoday (1913) substantiated the observations of Irving in regard to the production of carbon dioxide and noted further that in the stimulation of respiration due to small doses of chloroform the absorption of oxygen and carbon dioxide increased in like proportion but that when the doses of chloroform were large, the absorption of oxygen was no longer closely correlated with the production of carbon dioxide. The behavior of different leaves in this regard is of interest. Thus in the leaves of *Tropaeolum*, which contained no tannin, the absorption of oxygen was depressed more than the production of carbon dioxide. In leaves of cherry laurel and *Helianthus*, however, which contained tannins, the oxidation of which imparted a brown or black color to the disorganized leaves, the absorption of oxygen was very rapid for a short time and, though quickly falling, remained at a much higher level than the production of carbon dioxide.

With wheat seeds soaked in 7.3 and 3.6 per cent ether solutions, Thomas (1918) obtained an increase in the rate of respiration which was followed by a decrease. Smith (1921) treated the seedlings of wheat when the roots were 1 to 1.5 in. in length with 1, 3.65, and 7.3 per cent of ether in water and found that the first effect was an increase in the rate of respiration, which in turn was followed by a decrease. With all these concentrations the rate of respiration was ultimately reduced to approximately the same level, the stronger the concentration the more rapid the fall. When respiration was reduced below normal, recovery was possible on the removal of the ether and appeared to be complete if sufficient time was allowed. If respiration was too far depressed, however, no recovery was possible. Haas (1919) exposed *Laminaria* to 0.3 per cent chloroform, 0.8 per cent formaldehyde, and 10 per cent ethyl alcohol and observed that the rate of respiration was respectively 1.4 to 2.8, 2.7, and 6.2 times that of the controls. Upon the exposure of the alga to these compounds, the initial effect was an increase in respiration which was followed by a decrease if they were sufficiently toxic. No decrease in respiration, however, was observed when the concentration was too low to be toxic.

The probable action of anesthetics upon the oxidative mechanism of the cells is indicated by the observations of Ray (1923). He found that when *Uva* was killed in such a manner as to destroy the oxidizing enzymes no carbon dioxide was produced unless hydrogen peroxide and $\text{Fe}_2(\text{SO}_4)_3$, which acts like a peroxidase, were present. If the concentration of the iron was low, there was an increase of the carbon dioxide production when chloroform was added. If the concentration of iron was high, the rate of carbon dioxide production appeared to decrease from the start. It was also observed that if oleic, tannic, succinic, or malic acid were treated with hydrogen peroxide and $\text{Fe}_2(\text{SO}_4)_3$, carbon dioxide was produced at a rate which could be measured by the indicator method. In the case of acids with a double bond, the rate of production of carbon dioxide could be varied by the addition of an anesthetic. The changes in the rate of production of carbon dioxide under the influence of an anesthetic, as chloroform, showed a striking resemblance to the reaction of an organism. Ray considered that there is a definite relation between the rate of production of carbon dioxide and the ability of the compounds to absorb iodine. An analysis of the effects of chloroform on the production of carbon dioxide by the living and killed cells of *Uva* and unsaturated organic acids indicates that the same process is taking place in all three cases. The conclusion of Ray was that the action of chloroform on the oxidative mechanism of the cell was chemical in nature and that it acted either by catalysis or by the formation of a loose compound with some portion of the system.

The effects of ethylene, which is now extensively used in the ripening of fruits, upon respiration might well be noted under this topic. Denny (1924) found that concentrations of this gas of 1 part in 1,000; 1 part in 10,000; 1 part in 100,000; and even 1 part in 1,000,000 of air increased the respiration of green lemons. The increase in carbon dioxide output ranged from 100 to 250 per cent and appeared to be greatest at the intermediate concentrations. After the discontinuance of the application the rate of respiration decreased. Regeimbal, Vacha, and Harvey (1927) treated ripening bananas with 1 part ethylene to 1,000 parts air for 15 to 20 min. and then determined their rate of respiration. In all cases the rate of respiration expressed in milligrams of carbon dioxide per hour was doubled or trebled within a few minutes, after which the rate fell off to a value lower than normal. It was assumed that the high initial increase might have been due either to the increase of oxidation or to the increase in the permeability of the membranes, allowing the diffusion outward of the carbon dioxide already in the cells. The rise in the respiratory rate after a second dose of the ethylene seemed to indicate that the oxidation rate rather than the permeability rate was increased. This stimulation wears off in less than an hour. It should be noted in this regard that the treated bananas had one-fifth to one-fourth more sugar in them than

the untreated ones, while the starch content was proportionately decreased. The activity of diastatic enzymes as well as respiratory enzymes was apparently increased by the treatment with ethylene. It is not known, however, whether permeability changes indicated by the gas allow the enzyme and substrate to come together, activate the enzymes, or actually increase the amount of enzymes present.

It should be noted here also that Haas (1919) found that when *Laminaria* was killed by alcohol, acetone, formaldehyde, or ethyl bromide, as well as by drying, the rate of respiration was even greater than under normal conditions. This rate, however, was not long maintained but gradually fell off and eventually became negligible.

f. Concentration of Oxygen and Carbon Dioxide.—The effects of the concentration of oxygen upon the rate of respiration will depend not only upon the plant or plant part under consideration but also upon their condition when the observation is made. When the supply of oxygen is sufficient for the normal respiration of the plant, the presence of a surplus produces in most cases no perceptible effects. The intensity of respiration in many plants is not markedly modified when the oxygen supply is reduced to one-half that normally present in the air or when it is increased to five to ten times that which normally occurs. According to Stich (1891), the absorption of oxygen becomes insufficient for most plants when the supply in the air falls below 5 to 8 per cent. If a plant is confined in a container, it can generally absorb the last trace of oxygen from the medium. When the oxygen supply is increased, the plant may continue to respire normally for a period of time even when the partial pressure of oxygen has been increased to twenty or thirty times the normal amount. In a few hours or days under such conditions, respiration declines and death ultimately ensues.

The variation of plants in their oxygen needs under different conditions of their development is illustrated by the embryo of *Alisma*, as reported by Crocker and Davis (1914). They found that the hypocotyl was capable of elongating 1.2 times its original length in the total absence of free oxygen. For greening and branching, however, it required an air pressure of at least 5 mm. to supply the minimum amount of oxygen, while for the development of the primary root a yet greater amount was required. The amount of oxygen which must be supplied to produce a certain intensity of respiration or rate of growth will depend in many cases upon the permeability of the membranes which it must penetrate in reaching the seat of its utilization. This is illustrated by the coats of seeds through which oxygen diffuses with difficulty. When such coats are present, a higher supply of oxygen is required to produce a certain rate of respiration or growth than when they are removed. Thus Shull (1914) found with *Xanthium* seeds that when the oxygen supply was increased, it brought about, in some manner, an immediate and rapid

increase in the rate of oxygen absorption resulting in an immediate germination of the seeds. Shull considered that it was difficult to say what function or functions were affected by this treatment. It is certain that oxygen acted as a limiting factor on some function, but whether it was by limiting the process of respiration, by limiting enzyme formation, or by limiting the action of oxygen carriers could not be stated. Becker (1912) suggested that in some instances oxygen may act as a stimulus for certain functions without being directly concerned in respiration.

The quantity of oxygen in the intercellular spaces of fruits and other plant parts due primarily to poor gaseous exchange is frequently considerably below that of the air and may thus in some cases be a limiting factor in the respiration of these parts. Injury to plants due to an inadequate supply of oxygen is shown by the effects upon cranberry plants which have been submerged by flooding (Bergman, 1921, 1925). This injury was more pronounced on cloudy than on clear days, due to the difference in the amount of oxygen released in photosynthesis. Shading the flooded plants had the same effect as clouds in this regard. Low temperatures operated to reduce the amount of injury by lowering the respiration rate and thus decreasing the need for oxygen while at the same time increasing the capacity of the water to absorb this gas. The flowers and tips of the shoots were the parts of the plants most seriously affected by flooding, due to their high respiration rate.

The amount of carbon dioxide in the atmosphere surrounding the plant may have some effect upon the respiration rate. Kidd (1916) noted that the rate of respiration was lowered by the accumulation of carbon dioxide and that this effect was more marked upon the process of aerobic respiration. These depressing effects were evidently not due to permanent disorganization, as they always passed away as soon as the depressing concentrations of carbon dioxide were removed. In their study of the respiration of apple twigs at 0°C., potato tubers at 22°C., and wheat at 40°C., Willaman and Beaumont (1928) found that if carbon dioxide was allowed to accumulate in the respiratory chamber, the rate of carbon dioxide production continuously decreased with time. When aspiration of the atmosphere surrounding the tissues was commenced after 30 or 40 hr. of accumulating carbon dioxide, the respiration rate as measured by the output of carbon dioxide immediately assumed a much higher value than it had during the accumulation period. The work of Spoehr and McGee (1924) indicates that under such conditions, the establishment of an equilibrium between the carbon dioxide in the air surrounding the tissues and that which is dissolved in them is the result that is being observed. Thus they found that when the carbon dioxide content of the air surrounding a leaf was changed from a lower to a higher concentration, the leaf showed a reduced rate of carbon dioxide emission

for a period following the change and then finally again attained the same rate as before the change in carbon dioxide content was made. When the carbon dioxide of the air surrounding the leaf was changed from a higher to a lower concentration, the leaf showed a primary increased rate of carbon dioxide emission and a subsequent decrease to the original rate.

The accumulation of carbon dioxide in some cases, however, apparently has no marked effect upon certain activities. Thus Newcombe and Bowerman (1918) in observations upon 2,000 seedlings of 12 different species reported that ventilation was of no effect in producing better seedlings in small or large chambers in the dark and that this had no visible effect on the sensitive reactions of these plants to gravity and light.

g. Various Salt Solutions.—The effects of sodium chloride and calcium chloride upon respiration have been studied by Lyon (1921) and Inman (1921). It was observed in the case of *Elodea* that solutions of NaCl caused an increase in respiration which was followed by a decrease, while solutions of CaCl₂ caused only a decrease. In a mixture containing 99.65 mols of NaCl and 0.35 mols of CaCl₂ the rate remained normal, while a mixture of 98.6 mols of NaCl and 1.38 mols of CaCl₂ caused a great increase in respiration. In highly hypertonic solutions of sea water, the rate of respiration of *Laminaria agardhii* was rapidly reduced, while in hypotonic solutions it was reduced somewhat less rapidly. Hypertonic solutions of NaCl, CaCl₂, and mixtures of NaCl and CaCl₂ in the proportion of 50 to 1 all caused a decrease in the respiration of wheat seedlings.

The stimulating action of phosphates upon oxidation reactions has been reported by Spoehr (1924) and Lyon (1924, 1927). The former investigator noted that glucose and other hexoses were oxidized by air in solutions containing disodium phosphate and methylene blue with the formation of carbon dioxide. This reaction was greatly accelerated by small quantities of iron salt. Sodium ferropyrophosphate was a more active catalyst than methylene blue in causing the oxidation of carbohydrates with air. Lyon (1924, 1927) reported that phosphates exerted a promoter action upon potato oxidase so that carbon dioxide was produced by an oxidation of some component in a solution of glucose. He also states that phosphate catalyzes the slow oxidation of pyrogallol by atmospheric oxygen. He assumed that phosphate increases the rate of production of carbon dioxide by anaerobic processes because of its rôle in the early stages of alcoholic fermentation and that it effects an increase in the production of carbon dioxide by the aerobic phase of respiration through its action as a catalyst toward oxidases. In *Elodea canadensis* and wheat seedlings Lyon was able by the application of phosphate to obtain an increase in the production of carbon dioxide

amounting to 55 per cent for the former and 35 per cent for the latter plant. Lyon also observed that arsenates exerted a catalytic effect on the oxidation of pyrogallol by atmospheric oxygen and by metallic iron and on the production of carbon dioxide by *Elodea*. Warburg (1921, 1925, 1928) believed that iron is the oxygen-carrying component of the respiration ferment. He stated that if respiration is considered as an oxidation, the respiration ferment is the sum of all the catalytically active iron compounds which occur in the cell. The respiration ferment is thus considered a substance which takes up the atmospheric oxygen and transfers it to the organic substance and in its chemical constitution is related to the hemoglobin or red pigment of the blood.

It was observed by Smith (1921) that the respiratory rate of wheat roots which had attained a length of about 2 in. was greatly accelerated and then depressed after they were placed in a 0.0025 *M* solution of lactic acid. As the concentration of the acid was increased, this preliminary rise in respiratory intensity became less marked until a concentration was reached where the rate began to fall at once. Recovery was complete even when the respiratory rate was reduced to 25 per cent of normal by a 2 *M* solution of the acid. These results were apparently not due to acidity or osmotic pressure but to some specific action of the lactic acid. They also indicate that in the case of wheat, lactic acid is not an important intermediate product of the respiratory process.

Hutchinson (1922) reported that when radish seedlings were placed in 0.003 and 0.002 per cent solution of adrenalin, they showed a falling off of 20 per cent in carbon dioxide production at the end of 15 min. and then a gradual rise. More dilute solutions of 0.0005 and 0.0002 per cent gave a much smaller decrease, with a final rise to normal in about 1 hr.

h. Light and Electricity.—Spoehr (1915) found respiration in the sunlight higher than in the dark. He believed that the air may possess higher oxidative power during the hours of illumination than during darkness due to the ionizing power of the sun's rays. He assumed that deionization of the air has its influence on oxidation. In wheat seedlings the ratio of the day rate of respiration to the rate at night in ordinary air during two experiments was 1.042 and 1.091, while in deionized air these ratios were 1.010 and 1.014, respectively. The rate of respiration in deionized air thus was approximately the same during the day and night. For the autoxidative process the dissociation or liberating of free valences in the oxygen molecule is necessary, and by this is explained the accelerating influence of light and heat upon oxidative processes.

Middleton (1927) found that when the air passing over barley seedlings was artificially ionized by means of polonium, the rate of respiration was increased by as much as 29.1 ± 5.6 per cent. In the case of the leaves

of *Pelargonium zonale* with air ionized to a degree varying from 7.28×10^2 to 3.64×10^2 that of normal air, Whimster (1927) observed a percentage increase of 85.7 ± 7.1 in the respiration rate. After the removal of the polonium there was a definite after effect, the succeeding 2 hr. showing a percentage increase of 28.0 ± 7.3 over the control period. This effect of ionized air on respiration is apparently due to the ions themselves and not to the gaseous products produced by the action of the ionizing agent.

In 1914 Knight and Priestely reported some observations on the effects of electricity on respiration. Direct currents of a density 10^{-6} to 10^{-4} amp. had no effect on the respiration of peas other than that due to accompanying changes of temperature. The proportion of the currents actually traversing the peas, however, was small, the greater portion being taken by the water films of the seeds. Overhead discharges producing a current of density less than 3×10^{-6} amp. had no effect upon respiration. When higher currents were employed, a definite increase of the carbon dioxide output was observed. This increase, however, could be wholly attributed to the rise of temperature caused by the discharge. In the field where the currents are too small to produce any appreciable rise in temperature, electrification will have no effect on respiration, and explanations of the acceleration of growth due to electricity must be sought in other functions of the plant.

12. Substances or Enzymes Concerned in or Associated with Oxidation in Plants.—It was demonstrated by Schönbein as early as 1856 that there are present in plants and animal juices substances which act as oxidizing agents for certain compounds. Traube (1877) termed these substances "oxidizing ferments," and Bertrand (1896) proposed the term "oxydases" as a group or class name. This term has come into general use, although in England and America it is now commonly written "oxidases." As the behavior of these substances was more thoroughly studied it was found that they varied widely in their composition and in the nature of their reactions. As a result, numerous terms have been introduced into the literature so that the nomenclature in regard to substances concerned in or accompanying oxidation by plant and animal tissues has become rather confusing. Before beginning a detailed discussion of the nature and action of the oxidizing substances of the plant it would perhaps be best, for clearness, to define four terms which have been the most generally used. These are "oxidases," "oxygenases," "peroxidases," and "catalases."

An *oxidase* is a complex of substances which has the power at ordinary temperatures to bring about the oxidation of certain compounds in the presence of gaseous or dissolved free oxygen.

An *oxygenase* is a substance which is capable of causing the formation of organic peroxides. By some authors an oxygenase is defined as a

performed organic peroxide resulting from auto-oxidation. Some consider that the oxygenase itself takes up oxygen and thus becomes a peroxide, while others believe that it acts only as a catalyzer in the production of peroxides. An oxygenase is sometimes called a "peroxide-forming enzyme."

A *peroxidase* is a substance that is capable of rendering active the oxygen of peroxides. The oxygen is freed from the peroxides in the atomic or active form and is thus capable of causing the oxidation of certain compounds.

A *catalase* is a substance which is capable of decomposing hydrogen peroxide into water and molecular oxygen without being able apparently to activate the oxygen thus liberated toward oxidizable substances.

a. *The Oxidases*.—When the juice or watery extract of a plant tissue causes the oxidation of compounds which cannot be brought about by oxygen alone to any appreciable extent at ordinary temperatures, it is said to contain a direct oxidizing enzyme or oxidase. Some of these oxidation reactions are manifest by the bluing of guaiacum, the conversion of hydroquinone into quinone, the liberation of I from KI, and the formation of phenolphthalein from phenolphthalin by the liberation of two atoms of hydrogen. The action of oxidases is manifest by the blackening of cut potatoes, the staining of lumber (Bailey, 1910), and the blackening of tea leaves upon curing. Since the oxidases are in most cases destroyed by heat, mineral acids, and poisons and since they apparently act in a catalytic manner, they have been termed "oxidizing enzymes," although they possess certain characteristics which are different from those of enzymes. Thus in most cases they do not behave as true catalysts, as they are unable to accomplish the oxidation of unlimited amounts of oxidizable materials.

It was stated by Bach (1897), Kastle and Lovenhart (1901), and Bach and Chodat (1903) that the action of the oxidases indicated that they have the power to produce peroxides, and they believed that an oxidase is composed of two substances—an oxygenase and a peroxidase. They suggested that the oxygenase has the power of fixing the atmospheric oxygen in such a manner as to produce a peroxide, but the manner in which this occurs is not clear. Some suggest that the oxygenase catalyzes the formation of organic peroxides from auto-oxidizable substances in the cells, while others believe that the oxygenase itself combines with the atmospheric oxygen and thus becomes a substituted organic peroxide of a very unstable nature (Moore and Whitley, 1909).

Gallagher (1923) found evidence that the production of peroxide in the potato is intimately associated with the lecithin of the tuber. He believed that the substance from which the peroxide is derived may either be the lecithin itself or a compound intimately associated with it. Gallagher isolated from fresh potatoes a substance which bore a

close relation to the lipins. In contact with air or oxygen a solution of this substance acquired the property of causing the immediate oxidation of guaiacum in the presence of peroxidase. He thought this indicated that the so-called "oxygenase" of the potato is really an auto-oxidizable lecithin-like substance. He believed this evidence substantiates the view that there is a relationship between lecithins and plant respiration. Onslow (1919) believed that the peroxides are formed under the influence of oxygenase from aromatic substances having the dihydroxy grouping of catechol. The peroxidase is considered to catalyze the decomposition of the peroxide which is formed by the oxygenase, with the liberation of active oxygen. This active oxygen then combines with the oxidizable substances with which it comes in contact. This theory of the nature and reaction of oxidases has been generally accepted and has largely dominated the field of thought in that regard.

The two constituents of the oxidases have been separated by Bach and Chodat (1903) and Reed (1916) in a fairly satisfactory manner. Reed found that the filtrate from finely ground potato peel in 55 per cent alcohol contained a peroxidase, while the residue after washing with alcohol gave a water extraction containing oxygenase. When these two preparations were mixed, the oxidation increased in the case of pyrogallol about six times over that where oxygenase alone was used.

1. *Classification of Oxidases.*—The oxidases of plants that have been studied have been grouped into two main classes according to the substances upon which they act. These are the laccases or phenolases and the tyrosinases.

(a) *The Laccases or Phenolases.*—It has long been known that a blue coloring matter is produced when a tincture of gum guaiacum is treated with certain oxidizing agents, and the first knowledge of oxidases is closely associated with this fact (Kastle, 1910). The laccases or phenolases include those oxidases which are capable of reacting directly, in the presence of free oxygen, with a fresh alcoholic solution of gum guaiacum with the production of its characteristic blue oxidation product (Gallagher, 1923). Each of the oxidases in this group is capable of oxidizing one or more of the phenol compounds. Some of the compounds which can be oxidized under the influence of the phenolases are pyrogallol, benzidin, *a*-naphthol, phloroglucin, pyrocatechol, hydroquinone, phlorizidin, resorcin, guaiacol, *o*-cresol, *m*-cresol, *p*-cresol, *o*-toluidin, *m*-toluidin, *p*-toluidin, phenolphthalin, tannins, guaiac tincture, and others.

In 1883, Yoshida reported that the hardening of the milk sap of the lac tree (*Rhus vermicifera*) was apparently an oxidation process which was catalyzed under the influence of a nitrogenous substance having the characteristics of an enzyme. In 1894 and 1895 Bertrand confirmed these results and called the oxidizable substances present

in the sap "laccol" and the compound which catalyzed the oxidation "laccase." On account of the resemblance of "laccol" to the phenols, Bertrand studied the effects of laccase upon a number of them and found that they were oxidized under its influence. He found guaiacum to be a useful reagent for laccase and detected its presence by this means in many plants and plant parts. Laccase has been found to be not a specific enzyme in the narrow sense, because it will bring about the oxidation of many phenols and phenol derivatives. It is not able, however, to oxidize tyrosin or any of its derivatives. It thus apparently acts only upon substances containing a certain grouping in their structure.

Substances which give the same or similar reactions as laccase toward the phenol compounds are widely distributed in the plant kingdom and have been named collectively the "laccases," the "phenol oxidases," or the "phenolases." Most of the oxidases which have been studied in plants belong to this group, but practically no progress has been made toward their further classification. Some idea of the widespread distribution of the laccases may be had from the work of Onslow (1920, 1921), who examined 320 species of angiosperms representing more than 180 natural orders and 309 genera and found that 62 per cent of the orders examined contained oxidases of the laccase type. She found the laccases or phenolases in the fruit of the apple, pear, quince, plum, cherry, peach, apricot, strawberry, grape, fig, and mulberry. They have also been found in apple bark and leaves, in alfalfa, clover, turnips, potatoes, peas, cabbage, silks of green corn, asparagus, and in many other plants and plant parts. Bunzel (1913, 1914) noted that the seeds of the beet had the highest phenolase activity of any of the plant parts, while the leaves stood next in order. In the normally developing leaves of the potato plant the phenolase activity was greatest in the early stages of development. It fell off with the growth of the plants and again rose when growth was completed. Bunzel (1916) noted in the case of the onion, potato plant, and sugar beet that the relative activity of the phenolases, as manifest toward the reagents which he used, varied only in intensity for the different parts of the same plant but found that the enzyme from each plant was markedly different from those of the other plants.

Drain (1923) in tests made at various periods during the time of fruit development, at harvest and late in the storage season of apples, found that the majority of them fell in that class where the greatest phenolase activity was noted in the vicinity of the core and core line. He believed that oxygen may enter this fruit largely through the fibrovascular bundles which connect the calyx tube and the core cavity.

(b) *The Tyrosinases*.—It has long been noted that when certain fungi were exposed to the air they turned pink or red and finally black while other species became blue due, as we now know, to the activities of the laccases. Bertrand (1896) proved that the former colorations were due

to the oxidation of tyrosin by the absorption of oxygen under the influence of a specific oxidizing enzyme which he named "tyrosinase." He proved that this enzyme also occurs in the roots of the beet and in the tubers of the potato and dahlia, and it has since been demonstrated to be rather widely distributed in the plant and animal kingdoms. It is especially abundant in wheat bran.

Tyrosinase exhibits two general reactions. It oxidizes tyrosin, with the production finally of the black pigment melanin and the oxidation of *p*-cresol with the formation of a deep orange color. The former is the most common reaction shown by this enzyme. When tyrosinase is added to a solution containing tyrosin, the solution passes through a series of color changes ranging from pink to rose, to red, to violet, to blue black, and finally to the formation of a black precipitate. The tyrosinases are non-dializable and are destroyed by heat. They are apparently more or less specific, since they act upon a group of compounds which are closely associated in structure.

2. *Methods of Determining Activity.*—The presence and activity of oxidases in plant extracts and tissues have been studied by color reactions and by the determination of the quantity of oxygen absorbed.

(a) *Color Methods.*—Much of the knowledge of the oxidases has been obtained from the study of their action upon compounds which undergo a change of color upon oxidation. The compounds generally employed for this purpose are those which do not oxidize spontaneously, or do so only very slowly, when exposed to the air in very dilute solutions, but which when brought into contact with living tissues or their extracts show a change in color.

The color reactions have been especially useful in determining the distribution of oxidases, and their behavior toward various indicators has also shown that these enzymes vary in the type of reactions that they catalyze. The color methods, however, give no quantitative indication of the amount of oxidation which has taken place, although it has been so assumed in many experiments. The amount of oxidation necessary to produce the colored appearance is, in most cases, very small, so that after the color appears, the oxidation may continue without necessarily changing the intensity of the color. There is also no definite means of determining the amount of oxidation which a particular color reaction represents. It should also be noted in this connection that the amount of oxidation necessary to produce a color in the various reagents varies over a wide range (Reed, 1916). Some of the more common preparations used in the color determinations of oxidase activity and their method of application are given below.

(1) *Guaiacum Reaction.*—Two grams of gum guaiacum are dissolved in 100 cc. of 95 per cent ethyl alcohol. To 5 cc. of plant extract is added 10 drops of this solution. If oxidases of the laccase type are present, a blue color develops.

(2) *Benzidine Reaction.*—One gram of benzidine is dissolved in 100 cc. of 50 per cent ethyl alcohol. To 5 cc. of plant extract is added 10 drops of this solution. This is allowed to stand for $\frac{1}{2}$ hr., and if oxidases are present, a blue color develops.

(3) *α -Naphthol Reaction.*—A 1 per cent solution of α -naphthol in 50 per cent ethyl alcohol is prepared. When a few drops of this reagent is added to plant extracts, a lilac or lavender color results if oxidation occurs.

(4) *Phenolphthalin Reaction.*—The phenolphthalin solution is prepared after the following manner: To 1 cc. of tenth-normal sodium hydroxide solution is added

0.1 g. of phenolphthalin. This is dissolved as thoroughly as possible, after which it is diluted with 25 cc. of water, filtered, and made up to 100 cc.

To 10 cc. of plant extract is added 5 cc. of the phenolphthalin solution and the mixture allowed to stand for 15 min., after which it is made alkaline with twentieth*




FIG. 36.—Bunzel apparatus for determining oxidase activity. Description in the text. (Courtesy of Emil-Greiner Co.)

normal sodium hydroxide. If oxidase activity has occurred, the solution acquires a pink or red color due to the formation of phenolphthalein by the oxidation of the colorless phenolphthalin.

(5) *Röhmman-Spitzer Reaction*.—Equal parts of the α -naphthol solution and of a 1 per cent solution of *p*-phenylenediamine hydrochloride in distilled water are mixed

just before the oxidase test is made. Five drops of this mixture is added to 2 cc. of plant extract. If oxidases are present, the colors developed within 15 min. vary from pink to deep reddish purple. This is one of the most delicate of the oxidation tests.

(b) *Measurement of Oxygen Absorbed.*—The measurement of the oxygen used in oxidation offers a means of determining quantitatively the intensity of oxidase activity. Apparatus for this purpose has been devised by Bunzel (1912, 1914) and Harvey (1920). The simplified apparatus of Bunzel is shown in Fig. 36. This consists of two parts—a manometer *m* and a basal part *b* which has two compartments *e* and *f*. The two parts of the apparatus are connected by a ground glass junction *j*. The total volume of the apparatus minus the vial *v* up to the zero point on the manometer is 76.1 cc. In preparing for an experiment the manometer *m* is detached at the ground joint *j* and a measured quantity of the plant juice is run into the compartment *e* and the solution containing the oxidizable substance into compartment *f*. Enough water is then added to make the total volume of the liquid in the apparatus 18 cc. Rose (1915) used the materials in the following proportions: 3 cc. of plant extract, 3 cc. of water, and 12 cc. of a 1 per cent solution of pyrogallol. The vial *v* with 1 cc. of concentrated alkali is next inserted in the basal portion of the apparatus. The volume of this vial and contents is 3.5 cc. The manometer is replaced in such a manner that the two openings *o* and *o'* in the ground joint coincide and the apparatus is brought to the temperature at which the experiment is to be carried out. The apparatus is then closed by turning the manometer in the ground joint through an angle of 90 deg. The plant extract and the oxidizable material are mixed by shaking the apparatus. The basal portion of the apparatus may be immersed in a water bath of the desired temperature, and continuous shaking by mechanical means may be carried on for the duration of the experiment. After 18 cc. of liquid and the vial and contents are added, the volume of air in the apparatus is 54.1 cc., so that every change in pressure of 1 cm. of mercury corresponds to the absorption of 0.71 cc. of oxygen.

3. *Factors Influencing Oxidase Activity.*—The oxidases, as a rule, increase in oxidizing power with an increase in temperature up to 42 to 45°C., but above that they become less and less active and are completely inactivated at 100°C. They are very sensitive to acids and apparently are the most active in a neutral or slightly alkaline medium. Reed (1916) found that potato oxidase was completely inactivated by 0.0005 *N* to 0.007 *N* acids. Bunzel (1916) found that the inhibiting range of hydrogen-ion concentration for oxidase activity in the case of the potato tuber was P_{H} 3.55 to 3.70. In the case of the buds and leaves of the tulip it was P_{H} 2.30 to 2.80, and for the buds and leaves of magnolia P_{H} 2.45 to 3.05. The indications are that they are destroyed by the higher concentrations of acids, since neutralization fails to revive them. Rose, Kraybill, and Rose (1920) studied the effects of various salts upon the rate of oxidation of pyrogallol by apple bark. They found that tenth-normal solutions of the chlorides of K, Na, Li, Cs, NH_4 , Ca, Mn, and ferric Fe decreased oxidation, while it was slightly increased by solutions of the same concentration of the sulphates of these cations. The nitrates of K, Na, and Mg in tenth-normal concentration had no effect on oxidation, while the nitrates of C, Ba, Mn, and ferric Fe decreased it. Oxidation was increased in the presence of the tartrates, oxalates, citrates, acetates, and carbonates.

In their experiments the increased oxidation seemed to be due, in part at least, to the low acidity of the mixture of bark, pyrogallol, and salt, but marked decreases in oxidase activity were not necessarily accompanied by high acidity of the mixture. They believed that ions other than hydrogen and hydroxyl may be important in influencing oxidase activity so that in neutralizing these ions in the study of oxidases the possible effects of the salts formed should be considered.

The relative oxidase activity of healthy and diseased tissues has received considerable attention. Woods (1902) found a greater oxidase activity in the spotted leaves of tobacco affected with mosaic than in the normal ones. Bunzel (1913) noted that the juice from the leaves of beets affected with curly top had an oxidase content two to three times greater than the healthy and normally developing ones. An abnormally high oxidase activity was also shown in those plants whose growth had been retarded. Bunzel (1914) also found that the juice of the tubers and foliage of potato plants affected with curly dwarf showed a greater oxidase activity than the juice from these parts of healthy plants. The oxidase activity of tumor tissue in the beet caused either by freezing or by *Bacterium tumefaciens* was observed by Harvey (1920) to be greater than in the adjacent healthy tissue. Rose (1915) found that the extracts of apple-tree bark affected with Illinois canker caused greater and more rapid oxidation of pyrogallol than did the extract of healthy bark. The diseased bark extract was less acid than the healthy bark extract, hence he concluded that oxidase activity was in approximately inverse ratio to the acidity of the extract in the range of concentrations used by him. His conclusions were substantiated by the fact that the addition of acid to the solution in the apparatus decreased oxidation, while the addition of alkali increased it. Rose (1919) found in later work that apple bark attacked by the blister canker caused about twice as much oxidation with pyrocatechin, guaiacol, and benzidine as did the healthy bark. He considered that the lower tannin content of the diseased bark might have some influence on the oxidase activity.

4. *The Relation of the Oxidases to Physiological Functions.*—The phenomena of oxidation in plants are good examples of the ability of living organisms to carry out changes at ordinary temperatures without the presence of chemical agents. Thus the living plant is continually oxidizing materials in the process of respiration under conditions under which oxidation cannot be accomplished in the laboratory. In an attempt to explain the mechanism of respiration, the oxidases have generally been assigned a rôle in the process, although their relationship to it is almost entirely hypothetical. The activity of oxidases has been studied, for the most part, by the action of plant juices upon phenol compounds under the conditions of the laboratory. In one instance, however, Kastle and Buckner (1917) injected phenolphthalin into the

stalks of corn and obtained evidence that the phenolphthalin had been oxidized to phenolphthalein in the cells into which it had penetrated. They thus considered that oxidation similar to that obtained by oxidases under laboratory conditions prevails in the plant.

It is, however, difficult to assign a function to the oxidases in respiration, since by the present known methods of measuring their activity, they have no direct action at all upon the ordinary substances consumed in respiration. The decomposition products of respiration are also incapable of being oxidized directly by the oxidases under the laboratory conditions that have so far been tried. Appleman (1916) found no correlation between oxidase activity and the rate of respiration in potato tubers. He stated that while oxidases may play some rôle in the process they are certainly not the controlling factor in regulating the rate of respiration.

Crocker and Harrington (1918) observed in the case of the seeds of Johnson grass and *Amaranthus* that the intensity of oxidase activity decreased markedly with age. One-year-old seeds of Johnson grass showed only two-thirds the oxidase activity of fresh seeds, while three-year-old seed had only one-third the activity of one-year-old seeds. Two-year-old *Amaranthus* seeds were only about one-half as active as fresh seed. The oxidase activity of the dry seeds of Johnson grass showed no difference in intensity from that of germinating seeds. It was also observed that the oxidase activity of the non-living bracts which enclose the mature caryopses of Sudan and Johnson grass was as high as or higher than that of the caryopses.

It was reported by True and Stockberger (1916) that the intensity of oxidase activity roughly paralleled the distribution of the latex in the poppy (*Papaver somniferum*). With the exception of the roots, the oxidase activity ran roughly parallel with the alkaloid content. The alkaloids appear not to exist as such in the poppy plant but appear as products of the action of the oxidases on constituents present in the latex in the presence of oxygen. Annett (1922) noted that the latex of the Indian poppy has a powerful oxidizing action on guaiacum tincture, pyrogallol, benzidine, and tyrosin in the absence of hydrogen peroxide. He found that opium stored for 3 years possessed an oxidizing enzyme which acted on benzidine and suggested that the loss of morphine from opium on storage might be due to the action of oxidizing enzymes.

There appears to be some connection between the occurrence of oxidases and certain sap pigments in the stems, leaves, and flowers. A vast amount of work has been reported in this regard by Wheldale (1910), Keeble and Jones (1912), Keeble, Armstrong, and Jones (1913), Combes (1913), Everest (1914), Atkins (1915), and many others. A fine review of the literature in this field is given by Atkins (1916). The

discussion of this relationship of oxidases, however, is beyond the scope of this work.

b. The Peroxidases.—When the juices or watery extracts of tissues produce oxidation only after the addition of hydrogen peroxide, they are said to contain an indirect oxidizing enzyme which was called “peroxidase” by Linossier (1898). The usual test for a peroxidase is to note if the juice or extract gives a blue color with a solution of guaiacum after the addition of hydrogen peroxide. A peroxidase is a peroxide-activating enzyme activating both hydrogen peroxide and organic peroxides (Bach and Chodat, 1903). A peroxidase apparently combines with the oxygen from the peroxides to form an intermediate compound which is a more energetic oxidizing agent than the original source of the oxygen. The final stage of oxidation is then effected by the intermediate compound.

The peroxidases are probably more widely distributed in plants than any other enzyme with the exception of catalase. Of the 320 species examined by Onslow (1921), 95 per cent gave the peroxidase reaction with hydrogen peroxide and guaiacum. Clark (1911) reported that 75 per cent of the plants examined by him contained peroxidase. It is especially abundant in the root of the horseradish, in the tuber of the potato, and in the beet. Onslow (1920) found peroxidase in the blackberry, red and black currants, gooseberry, grape fruit, pineapple, melon, and tomato. McHargue (1920) and Coupin (1925) found that peroxidase predominates in the seeds of most species of plants.

Peroxidase is apparently the most stable of the enzymes associated with oxidation in plant tissues. According to Onslow (1919), it may be obtained from the pear or potato as follows:

Thin slices of the material are rapidly pounded in a mortar after sufficient 95 per cent alcohol has been added to prevent exposure to the air. After filtering off the alcohol with a filter pump, the residue is again ground with more alcohol and again filtered. This process should be repeated two or three times and the grinding should be very thorough. The insoluble residue or white powder which is finally obtained upon drying contains the peroxidase. A cold-water extract is then made of this residue and filtered. This filtered extract does not darken on exposure to air, and in the presence of hydrogen peroxide it oxidizes guaiacum, guaiacol, benzidine, and other phenol compounds. In the absence of hydrogen peroxide it is without action on these substances.

c. The Catalases.—It was noted by Schoenbein (1863) that all the animal and plant tissues with which he worked had the power to decompose hydrogen peroxide with the evolution of molecular oxygen. A further study of this phenomenon by him and others led to the general conclusion that it was a property possessed by all the various enzymes in plant and animal tissues. In 1901, however, Loew isolated from tobacco leaves a body capable of decomposing hydrogen peroxide into

molecular oxygen but possessing no other enzymic properties. This body he called "catalase," and with but few exceptions (Reed, 1916; Harvey, 1924) it has been found in the cells of all living tissues that have been examined and is thus apparently the most widely distributed of any of the enzymes. Catalase is classified as an enzyme upon its sensitiveness toward heat, acids, and various poisons, but, as will be discussed later, it exhibits certain behaviors that are not characteristic of enzymes.

1. *Preparation and Study.*—Any description of a method for the preparation and study of catalase must necessarily be general, since the details will depend upon the type of material used, upon the amount of catalase present, and upon other conditions under which the experiment is conducted. For details concerning the preparation and study of various plant tissues, the experiments of Appleman (1910 to 1916), Heinicke (1923, 1924), Rhine (1924), Davis (1925), Lantz (1927), Knott (1927), and Overholser (1928) should be consulted.

The material to be studied is generally ground or macerated in a small quantity of water with an excess of calcium carbonate, since catalase is very sensitive to acids. Quartz sand is sometimes used in the grinding in order more thoroughly to pulverize the tissue. The pulverizing process is usually limited to 2 to 5 min., since in some cases it has been found that the activity of catalase is sensitive to agitation. In some cases the pulverized material is forced through bolting cloth or a sieve to obtain a uniform sample. The fineness to which the material must be reduced to give the best results must be determined by actual experiment, as it has been observed in some cases that the activity of the enzyme may be decreased by pulverizing the tissue too finely. In the case of the seeds of Johnson grass, Crocker and Harrington (1918) found that the maximum activity was obtained when the material was forced through a 70- to 80-mesh screen. They considered that the best results were obtained when the average diameter of the sieve mesh was several times the diameter of the cells.

As soon as maceration is completed, water is added to the mixture—the amount added being determined by the activity of the catalase in the material under consideration. In the case of apple bark and leaves, Heinicke (1923, 1924) added sufficient water to give a dilution of 1 to 50. In working with seeds, Crocker and Harrington (1918) used from 0.5 to 0.025 g. of material for each determination but found 0.14 g. the most desirable. This preparation should not stand for longer than an hour or two, since in most cases the activity of catalase deteriorates very rapidly on aging. This enzyme, as a rule, also loses its activity very rapidly when powdered material is stored in the desiccator. On that account, it is best to grind the material and prepare the mixture just previous to making the catalase determination.

The methods that have been employed in making catalase determinations have been, for the most part, modifications of the method described by Appleman (1910). A description of the apparatus and procedure used by Davis (1926) will serve to illustrate, in general, the methods that are followed (Fig. 37). The apparatus consists of a buret *a* with a two-way stop cock *g* at the upper end and a connection with a leveling bulb *b* at the lower end. An ordinary pinch-cock buret may be used with a T-tube inserted in the upper end and connected directly at the bottom with the leveling tube (Heinicke, 1924). A wide-mouthed bottle *c* of approximately 100 cc. capacity is fitted with a three-holed stopper *h*. Through one of these openings a small separatory funnel *d* with a stop cock *t* is inserted, the top of the funnel being connected with the bottle by the rubber tube *e* and a glass tube inserted through a hole in the stopper. The bottle is connected through its third hole with the opening *r* at the top of the buret by means of the rubber tube *f*.

found that there was a gradual accumulation of catalase in corn germinating at 10°C., so that ultimately the catalase content was nearly equal to that at 20 to 30°C. At 42°C. the catalase content was markedly reduced. The point of total destruction of catalase for most of the cases reported, however, ranges from 65 to 80°C.

The relation of the catalase of air-dry seeds to temperature is worthy of note. Crocker and Harrington (1918) found that the air-dry seeds of Johnson grass were all killed and their catalase completely destroyed by heating at 100°C. for 5 hr. Heating at 81° for ½ hr. reduced the catalase activity by 30 per cent but improved the germination of the seeds. Heating at 81°C. for 17 hr. reduced the catalase activity approximately 90 per cent of its original value and killed all the seeds. The heating of the seeds of *Amaranthus retroflexus* at 81° from 4 to 48 hr. reduced the catalase activity but little, while the power of germination was destroyed. The catalase in the air-dry seeds of *Amaranthus* is thus comparatively heat stable, while the substances essential to vitality are comparatively thermolabile.

The effect of drying the material upon catalase activity has been observed in numerous cases. Crocker and Harrington (1918) noted that drying the seeds of peach and Johnson grass after they had been in the germinator reduced the catalase activity. Lantz (1927), however, found that the drying of corn seedlings at room temperature *in vacuo* over H₂SO₄ did not affect their catalase content. Heinicke (1924) reported that the maceration of dry tissue of apple bark resulted in a marked retardation of its catalase activity but that maceration of wet tissue had little influence on its activity. The longer the tissue is ground, however, the greater is the reduction in its catalase activity. The addition of water in grinding may tend to neutralize the medium, or it may reduce the heat generated in grinding. Knott (1925) found that catalase preparations deteriorate rapidly at 10 to 20°C. and that placing the bottles on ice immediately after maceration and dilution appears to be the best method of keeping preparations of spinach and celery. Tomato catalase, however, lost its activity in 24 hr. even when on ice.

Loew (1901) and Appleman (1910) pointed out that catalase is very sensitive to acids and that the maximum activity and minimum destruction occur in a neutral or slightly alkaline medium. The ground-plant tissues either contain or develop sufficient acid to injure greatly the catalase activity. This injury to the enzyme is avoided by grinding the tissue with CaCO₃. The effect of the hydrogen-ion concentration upon the activity of catalase apparently varies with different tissues. Thus Harvey (1920) found that the juice expressed from overgrowths on *Ricinus*, *Bryophyllum*, and beets had a hydrogen-ion concentration consistently lower than that obtained from the healthy tissues regardless of whether these overgrowths were caused by freezing or by *B. tumefaciens*.

The tumor juice in all cases showed a catalase activity much greater than that of the healthy tissue. In the case of the mosaic leaves of tobacco, however, the catalase activity was greatly increased over that of the normal leaves, while the P_{H} values of the diseased and healthy leaves were approximately the same. Weiss and Harvey (1921) found that the hydrogen-ion concentration of potato tubers affected with the wart disease was consistently higher than that of healthy tubers from the same plant, the values being represented by P_{H} 6.00 and P_{H} 6.49, respectively. The catalase activity, however, was much greater in the wart tissue, the values being represented by 17.9 cc. of oxygen for diseased and 7.8 cc. for the healthy tissue. Overholser (1928) noted that when the P_{H} value of the pulp of pears was reduced to 3.55 by the addition of $N/10$ HCl the catalase was almost completely checked. As the P_{H} value was raised by the addition of $N/10$ NaOH the catalase activity increased to a maximum with a P_{H} of from 6.00 to 6.50.†

3. *Relation to Physiological Activity.*—Since catalase occurs in practically all living cells, the question naturally arises as to what function it performs. Loew (1901) thought that hydrogen peroxide might be produced in the cell as a result of the respiratory process and that its accumulation would be harmful. He believed that its destruction is brought about by the catalase which would thus not only prevent injury but the oxygen thus liberated could be again used in respiration. The formation of hydrogen peroxide in respiration, however, has not been proved, and even if it were formed it is probable that it would not be injurious to the plant, as indicated by the work of Bach and Chodat (1903), who were able to cultivate plants in a medium containing 0.68 per cent hydrogen peroxide. Catalase, however, acts only on hydrogen peroxide and not on organic peroxides. These compounds rather than hydrogen peroxide are concerned in respiration, and Reed (1916) considered that the function of catalase in protecting the organism against hydrogen peroxide is very limited if it exists at all. The relation of catalase activity to respiration and to the general metabolic activity or vitality of plants has been extensively studied and will be considered in the discussion of those phenomena.

(a) *Respiration.*—The great majority of workers have found some connection between catalase activity and respiration, although the data show some contradictions, but the exact nature of this connection is not known. The catalase activity and the intensity of respiration have been found to parallel each other in many cases, and on that account it has been concluded that the one is the cause of the other. †

Appleman (1910, 1916, 1918) found that the catalase activity in the potato tuber and in fresh sweet corn showed a striking correlation with respiratory activity. Thus respiration was very high when the corn was first pulled, but this rate fell off rapidly with storage. The catalase

activity in a collateral set of ears showed a decline with storage which was almost directly proportional to the decline in respiratory intensity. Crocker and Harrington (1918) found that the catalase activity of the embryo of Stoner wheat was approximately twenty-eight times that of the endosperm. Since it has been found by Burlakow (1898) that the respiratory intensity of the wheat embryo is about twenty times that of the endosperm, it would appear that here also catalase activity parallels high respiratory intensity. In *Spirogyra* Burge and Burge (1924) also found a parallelism between respiration and catalase activity. Rosenberg (1910) and Zaleski and Rosenberg (1912) likewise considered that catalase stands in a direct relationship with the respiratory process.

Sherman (1921) found in the germination of *Crataegus* seeds that the catalase activity increased continuously up to the twelfth day, while the respiratory activity increased only to the sixth day. In the germination of *Amaranthus* the fluctuations of catalase activity and respiratory activity were frequently in opposite directions.

It was found by Morinaga (1925) that the catalase of germinating rice increased under aerobic conditions with a reduced quantity of oxygen but did not increase in the course of anaerobic germination. He concluded that in the case of rice the ratio of increase of catalase activity is a function of the free oxygen in the medium. Magness and Ballard (1926) found that there was an increase in catalase activity in Bartlett pears as they were held in storage after picking, followed by a decrease as the fruit approached prime eating conditions. The decrease in catalase, however, came much earlier in the life of the fruit than did the decrease in CO₂ output.

Rhine (1924) noted in the germination of the seeds of wheat, feterita, clover, mustard, radish, and buckwheat that there was always a drop in catalase at the onset of germination, the low point being reached in from ½ hr. to several days depending upon the type of seeds. This decrease in catalase activity was nevertheless followed by a sharp rise. The intensity of respiration, however, increased rapidly from the first hour of germination. The early curve of respiration thus diverged widely from the curve of catalase. Similar observations were made by Lantz (1927) in germinating corn. He found some correlation between catalase activity and respiration at 20°C., but at 10 and 30°C. this correlation was not apparent, and he concluded that there is, in this case at least, no evidence to assume that catalase is the enzyme chiefly concerned in physiological oxidation.

Since the catalase activity drops markedly at the beginning of germination and then increases while respiration increases from the first, Rhine (1924) believed that the most plausible theory of catalase formation in the plant seems to be that it is formed as an enzyme according to the theory of need—the presence of the substance which it attacks acting

as a stimulus for the production of the enzyme. The decrease of catalase with germination could thus be explained by supposing the catalase reserve to be used up in attacking the respiratory products faster than it is produced. The high stimulation of the suddenly increased quantity of by-products would thus lead in a short time to the increased production of catalase observed. If this is the case, the catalase curve would follow but never precede the respiration curve.

(b) *Vitality*.—It has been shown in some cases that catalase activity parallels the general metabolic activity of the organism, and numerous experiments have been conducted to determine if the catalase activity can be used as an indicator of the vitality and vigor of the plant or plant parts. The relation of catalase activity to the maturity, dormancy, and vitality of seeds has been especially studied. Crocker and Harrington (1918) found in the seeds of Johnson grass and Sudan grass that the fall in catalase began with harvest and continued for an indefinite period. It was found in these seeds that a considerable fall in catalase occurred with little or no fall in vitality. Thus in 9-year-old seeds of Sudan grass the percentage of germination was 98 per cent, although the catalase activity had fallen to less than one-half that of the 1-year-old seeds. In the case of the seeds of Johnson grass and Sudan grass, the catalase activity seemed to be an indicator of age rather than of vitality. In the seeds of *Amaranthus retroflexus*, however, there was no regular fall of catalase activity with the age or vitality of the seed. In maple seed, Jones (1920) noted that after 8 months of storage under laboratory conditions the catalase activity had declined to only one-half that of the fresh seeds. In the seeds of various varieties of lettuce 20 years old, Davis (1925) found that the relation of catalase to vitality was not such as to give reliable data on the viability of seeds, as the catalase content of dead seeds frequently was sufficiently high to indicate fair germination. He found, however, if seeds were soaked for a time in warm water at a temperature not sufficiently high to affect their viability that the catalase of dead seeds disorganized very rapidly, while that of the viable seeds was not affected. These observations are contrary to those reported by Nemeč and Duchon (1921, 1922, 1923) in their work with seeds of oats and peas. They considered that the viability of seeds could be determined by means of the catalase content of these seeds, since they found that the ratio of catalase of poor seeds to that of viable seeds also expressed very closely the percentage germination of the seeds. The disappearance of catalase from seeds during and after death no doubt bears a close relation to such factors as temperature, moisture, and aeration to which the seeds have been subjected during that time (Davis, 1925).

The catalase activity as a rule increases markedly during germination and in the seeds of Sudan grass and Johnson grass it doubled during that time (Crocker and Harrington, 1918). As is well known, the lower seeds

of *Xanthium* under natural conditions germinate much more readily than the upper ones. It was found by Shull and Davis (1923) that in the field during the germination season, the lower seeds increased in catalase activity while the upper lagged behind, showing practically no increase. They concluded that the catalase differences in *Xanthium* seeds are in harmony with the physiological differences which operate to bring about delayed germination of upper seeds with intact coats. Davis (1930) noted in the seeds of *Xanthium* and *Ambrosia* that during the period in which the embryo became dormant both the respiration and catalase activity were reduced. In the case of *Xanthium* during the period of after-ripening or the removal of dormancy at low temperature there was a rise in the catalase activity and also in the respiratory activity of the seed. Sherman (1921) noted in the seeds of *Acer saccharum* and *Juniperus virginiana* that catalase activity increased as dormancy ended and germination began.

The relation of catalase activity to the general vigor and response of the plant has been studied in the apple tree by Heinicke (1922, 1923, 1924). He found that the catalase activity in apple-leaf tissue was influenced by the factors that affected the nutritive or physiological conditions of it. Thus the wilting of leaves reduced the catalase activity. Leaves from trees growing in sod showed less catalase activity than did those from trees under cultivation, while nitrogenous fertilizers increased the catalase activity in leaves from trees in sod. Ringing reduced the activity of catalase. The catalase activity was less in those leaves grown in the shade as compared with those having good exposure to light. Heinicke found that the catalase activity of the phloem was greater than that of the xylem. The activity of young phloem and xylem was greater than the old phloem and xylem, respectively. Catalase in dormant vegetative buds was greater in amount than in dormant flower buds. Ezell and Crist (1927), however, in studying the effect of nutritive conditions upon the oxidase and catalase activity found in the case of radish, lettuce, and spinach plants that the correlation between the activity of catalase and growth or size of the plants was better than with oxidase and was significantly negative. Heinicke (1923) believed that the activity of catalase is a more sensitive measure of the metabolic status of the tissues than the usual chemical analysis and that it may serve, along with other measures, as an indicator of the physiological responses of plants to various cultural conditions or treatments. If it could so be used, it would be a convenient indicator. The determinations are quickly and easily made, and numerous samples can be taken at frequent intervals from the same source without serious injury to the experimental subject. The effect of disturbances in physiological functions upon the action of catalase was observed by Moore and Willaman (1917) in tomato plants which had been fumigated with hydrocyanic acid. There was a reduction in the

activity of catalase and oxidase, but within a few hours after the fumigation the oxidase activity had returned to normal, while the catalase and respiratory activities exceeded the normal.

Questions

607. Why is a supply of kinetic energy necessary for plant life? What portion of the solar energy falling on the plant is absorbed? What percentage of this absorbed energy is utilized in photosynthesis? In transpiration? What prevents the direct use of the absorbed energy by all the cells of the plant?

608. What sources of energy are available in every living cell? How may this energy be released? What is respiration? What materials are used in the process? What end products are formed?

609. Why is respiration considered an oxidation process? How does it differ from ordinary oxidation? How may respiration be explained upon the basis of the decomposition of the protoplasm? What relationship is there between the amount of protoplasm and the intensity of respiration? What parts of the protoplasm are concerned in respiration?

610. How does respiration affect the weight of an organism? Why? Give examples. What relationship is there between the carbohydrate supply and the intensity of respiration? How has this been demonstrated? What carbohydrates seem to be the most utilized in the process? Give examples.

611. What observations have been made in regard to the utilization of proteins in respiration? Why is the energy released by the proteins generally small in amount? What rôles may the amino acids play in the metabolism of the plant? What effect do amino acids have on respiration?

612. What is known concerning the effects of the qualitative and quantitative differences of foods upon respiration? What is meant by aerobic respiration? What are the end products? Write the equation for aerobic respiration if glucose is utilized. If ethyl alcohol is used.

613. What is meant by anaerobic respiration? What are the end products of this process? In what manner is the decomposition of the compounds accomplished? Give examples.

614. Discuss in detail the general conception concerning the relationship between aerobic and anaerobic respiration under conditions of a normal oxygen supply. Name five observations that are commonly presented as proofs that anaerobic respiration is a normal process which is intimately connected with aerobic respiration.

615. Why are most organisms unable to live for only a short time by the process of anaerobic respiration? How does the amount of energy released in anaerobic respiration compare with that set free in aerobic respiration? Why is it difficult to demonstrate the relationship of anaerobic to aerobic respiration?

616. How does the output of carbon dioxide compare in the two types of respiration? Why? Give examples.

617. Contrast in as many ways as you can the processes of aerobic respiration and photosynthesis. Describe the means by which oxygen is supplied to and carbon dioxide eliminated from the cells of plants and animals. Distinguish between respiration and breathing. Which occurs in plants? Which in animals?

618. By the measurement of what three quantities may the intensity of aerobic respiration be determined? Which quantity is the most frequently determined? Why? Name five general methods that have been used for the determination of the carbon dioxide evolved in respiration and state some of the advantages and disadvantages of each type of apparatus.

619. Outline in detail one of the most commonly used methods for the determination of the carbon dioxide evolved in respiration. Describe in detail the respirometer devised by Harrington, Crocker, and Davis. What are the advantages of this instrument? Describe the procedure to be followed in its use to determine the quantity of oxygen absorbed and the carbon dioxide released in respiration.

620. What is the respiratory quotient? What may its value indicate? Name and discuss four factors that may influence its value?

621. Why is the heat produced in respiration not ordinarily observed in plants? What method is commonly used to demonstrate the production of heat by plants? What precautions must be observed in an experiment of this kind?

622. What is the value to the plant of the heat liberated in respiration? Why does moist grain heat when stored? Why does hot weather accelerate this self-heating of grain?

623. What is the value of the temperature coefficient of respiration in plants? Give some examples illustrating the effects of temperature upon the output of carbon dioxide. What three factors may determine the amount of carbon dioxide and oxygen in the intercellular spaces of fruits and vegetables? Give examples.

624. How do changes in temperature affect the sugar content of tubers and fruits? The rate of respiration? Cite examples.

625. How does the respiration rate of air-dry seeds compare with that of germinating ones? Give some concrete examples to illustrate this. How does the length of time the excess moisture is present affect the intensity of respiration? Why?

626. Cite some examples to show the variations of the effects of moisture upon the respiration of different plants. Why is the rate of respiration accelerated by an increased moisture content?

627. How does wounding affect the intensity of respiration? The temperature of the tissues? What is the cause of these effects? Proof? What chemical changes occur in the injured regions?

628. Give some examples to illustrate the difference in the rate of respiration of different plants. How does the intensity of respiration in the embryo and endosperm compare in germinating seeds? Why? Give examples.

629. How does the respiratory intensity of young and old leaves compare? Of young and old fruits? What is the respiratory index? How does its value change with the age of the plant or plant parts? Why? What is the relationship of the value of the respiratory index to the growth rate?

630. Discuss the influence of chloroform and ether upon the intensity of respiration in plants. What do the observations of Ray indicate as to the probable nature of the effect of chloroform on the oxidative mechanism of the cell?

631. Give examples to show how ethylene gas affects the rate of respiration of ripening fruits. To what may this effect be due? How is the carbohydrate content of the fruit affected by the treatment?

632. How do changes in the concentration of oxygen affect the rate of respiration? What determines the concentration of oxygen necessary for the needs of the plant or plant part? Give some examples.

633. How does the amount of carbon dioxide surrounding the plant influence the rate of respiration? Why? Give some examples.

634. How do solutions of NaCl, CaCl₂, and mixtures of these two salts affect respiration? Why? What proof is there that phosphate accelerates respiration? How does lactic acid affect respiration? What does this indicate?

635. What effect has light on respiration? Why? How is the rate of respiration affected by direct electrical currents? By overhead discharge?

636. Distinguish between the terms "oxidase," "oxygenase," "peroxidase," and "catalase."

637. When is plant or animal tissue said to contain an oxidase? Give some examples. What are the two main components of an oxidase? Proof?

638. What are the characteristics of the laccases or phenolases of plants? What compounds may they oxidize? Discuss the origin of the term laccase. Make a statement concerning the distribution of laccases in different plants. In different plant parts.

639. What are the characteristics of the tyrosinases of plants? What two general methods have been used to determine the activity of oxidases? What are the objections to the color methods?

640. Describe the five color reactions that are used for determining the presence and activity of laccases. Which is most universally used? Which is the most sensitive?

641. Describe the simplified Bunzel apparatus and state in detail how to determine by it the amount of oxygen used by oxidases.

642. How is the activity of oxidases influenced by temperature? By acids? P_H value? Chlorides? Nitrates? How does the oxidase activity of diseased and healthy tissue compare? Why?

643. Discuss the relation of the oxidases to the physiological functions of the plant. How is the presence of peroxidases commonly determined? Make a statement concerning the distribution of peroxidases. Outline a method for the preparation of peroxidase.

644. Describe a method for the determination of catalase activity. How is catalase different in its behavior from most enzymes? How like? In what two forms does catalase exist? How may they be separated? How is the activity of catalase affected by temperature?

645. How is the action of a catalase affected by the drying of the material? By acidity? How does its activity compare in healthy and in diseased tissues? Cite examples.

646. What is the function of catalase in the organism? Discuss the relation of catalase activity to respiration.

647. What is the relationship of catalase activity to vitality? Age? General vigor? Give some examples in which catalase is an indicator of the condition of the organism.

Bibliography

- ANNETT, H. E., 1922: The enzymes of the latex of the Indian poppy (*Papaver somniferum*), *Biochem. Jour.*, **16**: 765-770.
- APPLEMAN, C. O., 1910: Some observations on catalase, *Bot. Gaz.*, **50**: 182-192.
- , 1911: Physiological behavior of enzymes and carbohydrate transformation in after-ripening of the potato tuber, *Bot. Gaz.*, **52**: 306-315.
- , 1915: Relation of catalase and oxidases to respiration in plants, *Md. Agr. Expt. Sta. Bull.* 191.
- , 1916: Relation of oxidases and catalase to respiration in plants, *Amer. Jour. Bot.*, **3**: 223-234.
- , 1918: Respiration and catalase activity in sweet corn, *Amer. Jour. Bot.*, **5**: 207-209.
- ASO, K., 1903: On the chemical nature of the oxydases, *Bull. Coll. Agr. Tokyo*, **5**: 481-491; *Bot. Centrbl.*, **96**: 106 (1904).
- , 1905: On the nature of oxidases, *Beih. bot. Centrbl.*, I, **18**: 319-326.
- ATKINS, W. R. G., 1915: The oxidases and their inhibitors in plant tissues. II, The flowers and leaves of the Iris, *Notes Bot. School Trinity Coll. Dublin*, **2**: 201-212.
- , 1915: Oxidases and their inhibitors in plant tissues. IV, The flowers of Iris, *Notes Bot. School Trinity Coll. Dublin*, **2**: 236-246.

- ATKINS, W. R. G., 1916: "Some Recent Researches in Plant Physiology," Chap. 13, The Oxidases in Relation to Pigmentation and the Anthocyanin Pigments, pp. 250-292, Whittaker and Co., London.
- BABCOCK, S. M., 1912: Metabolic water: Its production and role in vital phenomena, *Univ. Wis. Agr. Expt. Sta. Tech. Bull.* 22.
- BACH, A., 1897: Du rôle des peroxydes dans les phénomènes d'oxydation lente, *Compt. Rend. Acad. Sci. Paris*, **124**: 951-954.
- and R. CHODAT, 1903: Ueber den gegenwärtigen Stand der Lehre pflanzlicher Oxydations-fermente, *Biochem. Centrbl.*, **1**: 417-421.
- and ———, 1903: Untersuchungen über die Rolle der Peroxyde in der Chemie der lebenden Zelle. IV, Ueber Peroxydase, *Ber. d. d. chem. Ges.*, **36**: 600-605.
- and ———, 1903: Untersuchungen über die Rolle der Peroxyde in der Chemie der lebenden Zelle. V, Zerlegung der sogenannten Oxydasen in Oxygenasen und Peroxydasen, *Ber. d. d. chem. Ges.*, **36**: 606-609.
- BAILEY, C. H., 1917: The catalase activity of American wheat flours, *Jour. Biol. Chem.*, **32**: 539-545.
- , 1917: The moisture content of heating wheat, *Jour. Amer. Soc. Agron.*, **9**: 248-252.
- and A. M. GURJAR, 1918: Respiration of stored wheat, *Jour. Agr. Res.*, **12**: 685-713.
- , 1919, 1920: The storage of wheat, *Operative Miller*, **24**: 352, 381-382; **25**: 5-6.
- and A. M. GURJAR, 1920: Respiration of cereal plants and grains. II, Respiration of sprouted wheat. III, Respiration of rice paddy and milled rice. IV, The respiration of frosted wheat plants, *Jour. Biol. Chem.*, **44**: 5-7, 9-12, 13-15.
- , 1921: Respiration of shelled corn, *Univ. Minn. Agr. Expt. Sta. Tech. Bull.* 3.
- BAILEY, E. M., 1912: Biochemical and bacteriological studies on the banana, *Jour. Amer. Chem. Soc.*, **34**: 1706-1730.
- BAILEY, I. W., 1910: Oxidizing enzymes and their relation to sap stain in lumber, *Bot. Gaz.*, **50**: 142-147.
- BARNES, C. R., 1905: The theory of respiration, *Bot. Gaz.*, **39**: 81-98.
- BARTLETT, A. W., 1920: Note on an improved method for demonstrating the absorption of oxygen in respiration, *New Phytol.*, **19**: 151-152.
- BEAUMONT, J. H., and J. J. WILLAMAN, 1924: Preliminary report on the respiration of apple twigs during the winter, *Proc. Amer. Soc. Hort. Sci.*, **21**: 99-104.
- , ———, and W. A. DELONG, 1927: Notes on apparatus for low temperature respiration studies, *Plant Physiol.*, **2**: 487-495.
- BECKER, H., 1912: Über die Kiemung verschiedenartiger Früchte und Samen bei derselben Spezies, *Beih. Bot. Centrbl.*, **1**, **29**: 21-143.
- BECKING, L. G. M. B., and H. C. HAMPTON, 1920: Measurement of the catalytic power of catalase, *Amer. Jour. Bot.*, **7**: 261-275.
- BENNETT, J. P., and E. T. BARTHOLOMEW, 1924: The respiration of potato tubers in relation to the occurrence of black heart, *Calif. Agr. Expt. Sta. Tech. Paper* 14.
- BENOY, M. J., 1929: The respiration factor in the deterioration of fresh vegetables at room temperature, *Jour. Agr. Res.*, **39**: 75-80.
- BERGMAN, H. F., 1921: The effect of cloudiness on the oxygen content of water and its significance in cranberry culture, *Amer. Jour. Bot.*, **8**: 50-58.
- , 1925: The respiratory activity of various parts of the cranberry plant in relation to flooding injury, *Amer. Jour. Bot.*, **12**: 641-660.
- BERTRAND, G., 1894: Sur la latex de l'arbre à laque, *Compt. Rend. Acad. Sci. Paris*, **118**: 1215-1218.
- , 1895: Sur la laccase et le pouvoir oxydant de cette diastase, *Compt. Rend. Acad. Sci. Paris*, **120**: 266-269.

- BERTRAND, G., 1896: Sur les rapports qui existent entre la constitution chimique des composés organiques et leur oxydabilité sous l'influence de la laccase, *Compt. Rend. Acad. Sci. Paris*, **122**: 1132-1134.
- , 1896: Sur les rapports qui existent entre la constitution chimique des composés organiques et leur oxydabilité sous l'influence de la laccase, *Bull. Soc. Chim. Paris*, **15**: 793 (quoted by Appleman, 1916).
- , 1896: Sur une nouvelle oxydase, ou ferment soluble oxydant, d'origine végétale, *Compt. Rend. Acad. Sci. Paris*, **122**: 1215-1217.
- BEZAGU, MAURICE, 1919: Variations de la respiration des cellules de feuille avec l'âge, *Compt. Rend. Acad. Sci. Paris*, **169**: 701-702.
- BIGELOW, W. D., H. C. GORE, and B. J. HOWARD, 1905: Studies on apples. I, Storage, respiration and growth, *U. S. Dept. Agr. Bur. Chem. Bull.* 94.
- BLACKMAN, F. F., and P. PARIJA, 1928: Analytic studies in plant respiration. I, Respiration of a population of senescent ripening apples, *Proc. Roy. Soc., B*, **103**: 412-446.
- , 1928: Analytic studies in plant respiration. III, Formation of a catalytic system for the respiration of apples and its relation to oxygen, *Proc. Roy. Soc., B*, **103**: 491-523.
- BOEHM, J., 1887: Ueber die Respiration der Kartoffel, *Bot. Zeitung*, **45**: 671-675, 680-691.
- BONNIER, G., and L. MANGIN, 1884: Sur les variations de la respiration des graines germantes avec le développement, *Bull. Soc. Bot. France*, **31**: 306-309.
- BUNZEL, H. H., 1912: The measurement of the oxidase content of plant juices. *U. S. Dept. Agr. Bur. Plant Ind. Bull.* 238.
- , 1913: A biochemical study of the curly-top of sugar beets, *U. S. Dept. Agr. Bur. Plant Ind. Bull.* 277.
- , 1914: A simplified and inexpensive oxidase apparatus, *Jour. Biol. Chem.*, **17**: 409-411.
- , 1914: Oxidases in healthy and in curly-dwarf potatoes, *Jour. Agr. Res.*, **2**: 373-404.
- , 1915: On alfalfa laccase, *Jour. Biol. Chem.*, **20**: 697-706.
- , 1916: The mode of action of the oxidases, *Jour. Biol. Chem.*, **24**: 91-102.
- , 1917: The relationship existing between the oxidase activity of plant juices and their hydrogen ion concentrations with a note on the cause of oxidase activity in plant tissues, *Jour. Biol. Chem.*, **28**: 315-333.
- , 1916: The relative oxidase activity of different organs of the same plant, *Jour. Biol. Chem.*, **24**: 103-110.
- and H. HASSELBRING, 1917: The supposed action of potassium permanganate with plant peroxidases, *Bot. Gaz.*, **63**: 225-228.
- BURGE, W. E., and E. L. BURGE, 1924: Effect of temperature and light on catalase content of *Spirogyra*, *Bot. Gaz.*, **77**: 220-224.
- BURLAKOW, G., 1898: Ueber Athmung des Keimes des Weizens, *Triticum vulgare*, abst. *Bot. Centrbl.*, **74**: 323-324.
- BURROUGHS, A. M., 1922: Changes in the respiration rate of ripening apples, *Proc. Amer. Soc. Hort. Sci.*, **19**: 225-235.
- BUTLER, O., 1913: A note on the significance of sugar in the tubers of *Solanum tuberosum*, *Bull. Torrey Bot. Club.*, **40**: 110-118.
- CARRICK, D. B., 1928: The effect of freezing on the respiration of the apple, *Cornell Univ. Agr. Expt. Sta. Mem.* 110.
- CERIGHELLI, R., 1924: Sur le quotient respiratoire de la racine et ses variations au cours du développement de la plante, *Compt. Rend. Acad. Sci. Paris*, **178**: 645-647.

- CLARK, E. D., 1910: "The Plant Oxidases," thesis, Columbia Univ., New York.
- , 1911: The nature and function of the plant oxidases, *Torreya*, **11**: 23–31, 55–61, 84–92, 101–110.
- CLAUSEN, H., 1890: Beiträge zur Kenntniss der Athmung der Gewächse, *Landw. Jahrb.*, **19**: 893–930.
- COLEMAN, D. A., B. E. ROTHGEB, and C. H. FELLOWS, 1928: Respiration of sorghum grains, *U. S. Dept. Agr. Tech. Bull.* 100.
- COMBES, R., 1913: Production expérimentale d'une anthocyane identique à celle qui se forme dans les feuilles rouges et automne, en partant d'un composé extrait des feuilles vertes, *Compt. Rend. Acad. Sci. Paris*, **157**: 1002–1005.
- COUPIN, HENRI, 1925: Sur les peroxydases dans les graines sèches, *Compt. Rend. Acad. Sci. Paris*, **180**: 685–687.
- CROCKER, W., and G. T. HARRINGTON, 1918: Catalase and oxidase content of seeds in relation to their dormancy, age, vitality and respiration, *Jour. Agr. Res.*, **15**: 137–174.
- DARSIE, M. L., CHARLOTTE ELLIOTT, and G. J. PEIRCE, 1914: A study of the germinating power of seeds, *Bot. Gaz.*, **58**: 101–137.
- DAVIS, W. E., and R. C. ROSE, 1912: The effect of external conditions upon the after-ripening of the seeds of *Crataegus mollis*, *Bot. Gaz.*, **54**: 49–62.
- , 1925: The use of catalase as a means of determining the viability of seeds, *Proc. 18th Ann. Meeting Assoc. Off. Seed Analysts N.A.*, 6–12.
- , 1925: Unpub. data, *Kans. State Agr. Coll.*
- , 1930: Primary dormancy, after-ripening and the development of secondary dormancy in embryos of *Ambrosia trifida*, *Amer. Jour. Bot.*, **17**: 58–76.
- , 1930: The development of dormancy in seeds of cocklebur (*Xanthium*), *Amer. Jour. Bot.*, **17**: 77–87.
- DELEANO, N. T., 1912: Studien über den Atmungsstoffwechsel abgeschnittener Laubblätter, *Jahrb. f. wiss. Bot.*, **51**: 541–592.
- , 1912: Untersuchungen über die in Weinblättern enthaltenen Kohlenhydrate und stickstoffhaltigen Körper, *Zeits. physiol. Chem.*, **80**: 79–94.
- DENNY, F. E., 1924: Effect of ethylene upon respiration of lemons, *Bot. Gaz.*, **77**: 322–330.
- DRAIN, B. D., 1923: Oxidase activity in varieties of apples, *Amer. Soc. Hort. Sci. Proc.*, **20**: 25–30.
- , 1926: Temperature and respiratory enzymes of apples, *Bot. Gaz.*, **82**: 183–195.
- DUVEL, J. W. T., 1904: The vitality and germination of seeds, *U. S. Dept. Agr. Bur. Plant Ind. Bull.* 58.
- EULER, H., and IVAN BOLIN, 1909: Zur Kenntniss biologisch wichtige Oxydation, *Zeit. physiol. Chem.*, **61**: 72–92; *Bot. Gaz.*, **49**: 395 (1910).
- EVEREST, A. E., 1914: The production of anthocyanins and anthocyanidins, I, II, *Proc. Roy. Soc., B*, **88**: 326–332; **87**: 444–452.
- EWART, A. J., 1915: A comparative study of oxidation by catalysts of organic and inorganic origin, *Proc. Roy. Soc., B*, **88**: 284–320.
- EZELL, B. D., and J. W. CRIST, 1927: Effect of certain nutrient conditions on activity of oxidase and catalase, *Agr. Expt. Sta. Mich. Tech. Bull.* 78.
- FALK, K. G., GRACE MCGUIRE, and E. BLOUT, 1919: Studies on enzyme action. XVII, The oxidase, peroxidase, catalase and amylase of fresh and dehydrated vegetables, *Jour. Biol. Chem.*, **38**: 229–244.
- FONG, M. Y., and M. V. CRUESS, 1929: The effect of P_H value on the inactivation temperature of fruit oxidase, *Plant Physiol.*, **4**: 537–543.
- FRAYMOUTH, JOAN, 1928: The moisture relations of terrestrial algae. III, The respiration of certain lower plants, including terrestrial algae with special reference to the influence of drought, *Ann. Bot.*, **42**: 75–100.

- FRIEDRICH, R., 1908: Ueber die Stoffwechselvorgänge infolge der Verletzung von Pflanzen, *Centrbl. Bakt.*, **11**: 330-349.
- GALLAGHER, P. H., 1923: Mechanism of oxidation in the plant. I, The oxygenase of Bach and Chodat: Function of lecithins in respiration, *Biochem. Jour.*, **17**: 515-529.
- , 1924: Mechanism of oxidation in the plant. II, An investigation of substances which are capable of behaving as peroxydases, *Biochem. Jour.*, **18**: 29-38.
- , 1924: Mechanism of oxidation in the plant. III, Peroxydase. Observations on the thermostability of the peroxydase of the mangold, *Biochem. Jour.*, **18**: 39-46.
- GANONG, W. F., 1908: "A Laboratory Course in Plant Physiology," p. 129. Henry Holt and Co., New York.
- GENEVOIS, L., 1927: Über Atmung und Gärung in grünen Pflanzen, *Biochem. Zeits.*, **186**: 461-473.
- , 1928: Über Atmung und Gärung in grünen Pflanzen. II, Der Stoffwechsel der Phanerogamen, *Biochem. Zeits.*, **191**: 147-158.
- GERBER, C., 1900: Étude comparée de la respiration des graines oléagineuses pendant leur développement et pendant leur germination, *Actes 1st Cong. Internat. Bot. Paris*, **1900**: 59-101.
- GINSBURG, J. M., 1925: A modified respiration apparatus for plant and soil studies, *Soil Sci.*, **19**: 411-417.
- GODLEWSKI, E., 1882: Beiträge zur Kenntniss der Pflanzenathmung, *Jahrb. f. wiss. Bot.*, **13**: 491-543.
- GORE, H. C., 1911: Studies on fruit respiration, *U. S. Dept. Agr. Bur. Chem. Bull.* **142**.
- , 1915: Changes in composition of peel and pulp of ripening bananas, *Jour. Agr. Res.*, **3**: 187-205.
- GORTNER, R. A., 1910: A contribution to the study of oxidases, *Jour. Chem. Soc. London*, **97**: 110-120.
- GRÜSS, J., 1907: Enzymwirkungen aus Wundrand der Kartoffelknolle, *Zeits. Pflanz-enkrankh.*, **17**: 69-70.
- GURJAR, A. M., 1917: The adaptation of Truog's method for the determination of carbon dioxide to plant respiration studies, *Plant World*, **20**: 288-293.
- GUSTAFSON, F. G., 1929: Respiration of tomato fruits, *Plant Physiol.*, **4**: 349-357.
- HAAS, A. R. C., 1916: A simple and rapid method of studying respiration by the detection of exceedingly minute quantities of carbon dioxide, *Science*, n.s., **44**: 105-108.
- , 1917: Rapid respiration after death, *Proc. Nat. Acad. Sci.*, **3**: 688-691.
- , 1917: Anesthesia and respiration, *Science*, n.s., **46**: 462-464.
- , 1919: Effect of anesthetics upon respiration, *Bot. Gaz.*, **67**: 377-405.
- , 1919: Respiration after death, *Bot. Gaz.*, **67**: 347-366.
- HAFENRICHTER, A. L., 1928: Respiration of the soybean, *Bot. Gaz.*, **85**: 271-299.
- HARRINGTON, G. T., 1923: Respiration of apple seeds, *Jour. Agr. Res.*, **23**: 117-130.
- , and WILLIAM CROCKER, 1923: A new and efficient respirometer for seeds and other small objects: Directions for its use, *Jour. Agr. Res.*, **23**: 101-115.
- HARVEY, R. B., 1919: Apparatus for the measurement of oxidase and catalase activity, *Jour. Gen. Physiol.*, **2**: 253-254.
- , 1920: Hydrogen ion changes in the mosaic disease of tobacco plants and their relation to catalase, *Jour. Biol. Chem.*, **42**: 397-400.
- , 1920: Relation of catalase, oxidase and H concentrations to the formation of overgrowths, *Amer. Jour. Bot.*, **7**: 211-223.
- , 1924: Enzymes of thermal algae, *Science*, n.s., **60**: 481-482.
- HASSELBRING, H. and L. ALSBERG, 1910: Studies upon oxidases, *Science*, n.s., **31**: 637.

- HASSELBRING, H., and L. A. HAWKINS, 1915: Respiration experiments with sweet potatoes, *Jour. Agr. Res.*, **5**: 509-519.
- HEINICKE, A. J., 1922: Catalase activity as an indicator of nutritive condition of fruit tree tissues, *Amer. Soc. Hort. Sci. Proc.* **19**: 209-214.
- , 1923: Factors influencing catalase activity in apple leaf tissue, *Cornell Univ. Agr. Expt. Sta. Mem.* **62**.
- , 1924: Catalase, activity in dormant apple twigs: its relation to the condition of the tissue, respiration and other factors, *Cornell Univ. Agr. Expt. Sta. Mem.* **74**.
- HERZFELD, E., and R. KLINGER, 1919: Chemische Studien zur Physiologie und Pathologie VI, Zur Biochemie der Oxydationen (Zellatmung, Oxydations-fermente; zur Theorie der Narkose), *Biochem. Zeits.*, **93**: 324-352; *Bot. Abst.*, **8**: 95 (1921).
- HILL, G. R., 1913: Respiration of fruits and growing plant tissues in certain gases, with reference to ventilation and fruit storage. *N. Y. Cornell Agr. Expt. Sta. Bull.* **330**.
- HOPKINS, E. F., 1924: Relation of low temperatures to respiration and carbohydrate changes in potato tubers, *Bot. Gaz.*, **78**: 311-326.
- , 1927: Variations in sugar content in potato tubers caused by wounding and its possible relation to respiration, *Bot. Gaz.*, **84**: 75-88.
- HOVER, J. M., and F. G. GUSTAFSON, 1926: Rate of respiration as related to age, *Jour. Gen. Physiol.*, **10**: 33-39.
- HUTCHINSON, D. M., 1922: Comparative studies on respiration. XXIII, The effect of adrenalin on the production of CO₂ by animals and by plants, *Amer. Jour. Physiol.*, **62**: 192-196.
- ILJIN, W. S., 1923: Einfluss des Welkens auf die Atmung des Pflanzen, *Flora*, **116**: 379-403.
- INMAN, O. L., 1921: Comparative studies on respiration. XVI, Effects of hypotonic and hypertonic solutions upon respiration, *Jour. Gen. Physiol.*, **3**: 533-539.
- , 1921: Comparative studies on respiration. XVII, Decreased respiration and recovery, *Jour. Gen. Physiol.*, **3**: 663-667.
- IRVING, A. A., 1911: The effect of chloroform upon respiration and assimilation, *Ann. Bot.*, **25**: 1077-1099.
- IVANOW, S. L., 1913: Der Einfluss von Oelvorräten der Samen und der Temperatur auf den Respirationcoefficient CO₂/O₂, *Russ. Jour. Exp. Landw.*, **14**: 75-87.
- JACQUOT, R., and A. MAYER, 1926: Hydration et respiration des graines, *Ann. Physiol. Physiochem. Biol.*, **2**: 408-425; *Biol. Abst.*, **1**: 611-612.
- JOHNSTONE, G. R., 1925: Effect of wounding on respiration and the exchange of gases, *Bot. Gaz.*, **79**: 339-340.
- , 1925: Physiological studies of two varieties of *Ipomoea batatas*, *Bot. Gaz.*, **80**: 145-167.
- JONES, H. A., 1920: Physiological study of maple seeds, *Bot. Gaz.*, **69**: 127-152.
- KARCHEVSKI, M., 1903: Influence of the fluctuation of temperature on the respiration of seeds and embryos of wheat, *Expt. Sta. Rec.* **14**: 839.
- KARLSON, A., 1925: Comparative studies on respiration. XXVIII, The effects of anesthetics on the production of carbon dioxide by wheat under aerobic and anaerobic conditions, *Amer. Jour. Bot.*, **12**: 619-624.
- KASTLE, J. H., and A. S. LOVENHART, 1901: On the nature of certain of the oxidizing ferments, *Amer. Chem. Jour.*, **26**: 539-566.
- , 1910: The oxidases and other oxygen-catalysts concerned in biological oxidations, *Public Health and Marine Hospital Service Hygienic Lab. Bull.* **59**.
- and G. D. BUCKNER, 1917: Evidence of the action of oxidases within the growing plant, *Jour. Amer. Chem. Soc.*, **39**: 478-482.
- KEEBLE, F., and E. F. ARMSTRONG, 1912: The distribution of oxidases in plants and their role in the formation of pigments, *Proc. Roy. Soc. B*, **85**: 214-218.

- KEEBLE, F., and E. F. ARMSTRONG, and W. N. JONES, 1913: The formation of anthocyan pigments of plants. IV, The chromogens, *Proc. Roy. Soc., B*, **86**: 308-317.
- , ———, and ———, 1914: The formation of anthocyan pigments of plants. VI, *Proc. Roy. Soc., B*, **87**: 113-131.
- KIDD, FRANKLAND, 1917: The controlling influence of carbon dioxide. III, The retarding effect of carbon dioxide on respiration, *Proc. Roy. Soc., B*, **39**: 136-157.
- , C. WEST, and G. E. BRIGGS, 1921: A quantitative analysis of the growth of *Helianthus annuus*. I, The respiration of the plant and of its parts throughout the life cycle, *Proc. Roy. Soc., B*, **92**: 368-384.
- KIMBROUGH, W. D., 1924: The relation of respiration to storage and transportation of potatoes, *Proc. Ann. Meeting Potato Assoc. Amer.*, **11**: 53-54.
- KNIGHT, R. C., and J. H. PRIESTLEY, 1914: The respiration of plants under various electrical conditions, *Ann. Bot.*, **28**: 135-163.
- KNOTT, J. E., 1925: Some conditions influencing the determination of catalase activity in plant tissue, *Proc. Amer. Soc. Hort. Sci.*, **22**: 398-407.
- , 1927: Catalase in relation to growth and to other changes in plant tissue, *Cornell Univ. Agr. Expt. Sta. Mem.* 106.
- KNUDSON, LEWIS, 1916: Influence of certain carbohydrates on green plants, *Cornell Univ. Agr. Sta. Mem.* 9.
- KOLKOWITZ, R., 1901: Ueber die Athmung ruhender Samen, *Ber. d. d. bot. Ges.*, **19**: 285-287.
- KOSTYTSCHEW, S., 1909: Über die Anteilnahme der Zymase am Atmungsprozesse der Samenpflanzen, *Biochem. Zeits.*, **15**: 164-195.
- , 1910: Über den Vorgang der Zuckeroxydation bei der Pflanzenatmung. *Zeit. f. physiol. Chem.*, **67**: 116-137.
- , 1927: "Plant Respiration," Eng. trans. by C. J. Lyons, P. Blakiston's Son & Co.
- LANGDON, S. C., and W. R. GAILLEY, 1920: Carbon monoxide a respiration product of *Nereocystis leutkeana*, *Bot. Gaz.*, **70**: 230-239.
- LANTZ, C. W., 1927: Respiration in corn with special reference to catalase, *Amer. Jour. Bot.*, **14**: 85-105.
- LINOSSIER, M. G., 1898: Contribution a l'étude des ferments oxydants. Sur la peroxydase du pus, *Compt. Rend. Soc. Biol.*, **50**: 373-375.
- LOEW, O., 1901: Catalase, a new enzyme of general occurrence, with special reference to the tobacco plant, *U. S. Dept. Agr. Rept.* 68.
- LONG, E. R., 1917: Desiccation and respiration in succulent plants. *Carnegie Inst. Wash. Year Book*, **16**: 80-82.
- , 1918: Further results in desiccation and respiration of *Echinocactus*, *Bot. Gaz.*, **65**: 354-358.
- LUND, E. J., 1919: A simple method for measuring carbon dioxide produced by small organisms, *Biol. Bull.* **36**: 105-114.
- LUTHRA, J. C., 1924: Some experiments on the effects of dry and moist air on the rate of respiration and breakdown of ripe pears, *New Phytol.*, **23**: 131-142.
- LUTMAN, B. F., 1926: Respiration of potato tubers after injury, *Bull. Torrey Bot. Club*, **53**: 429-457.
- LYON, C. J., 1921: Comparative studies on respiration. XVIII, Respiration and antagonism in *Elodea*, *Amer. Jour. Bot.*, **8**: 458-464.
- , 1923: The effect of phosphates on respiration, *Jour. Gen. Physiol.*, **6**: 299-306.
- , 1927: Arsenate as a catalyst of oxidation, *Jour. Gen. Physiol.*, **10**: 617-622.
- , 1927: Phosphate ion as a promoter catalyst of respiration, *Jour. Gen. Physiol.*, **10**: 599-615.

- LYON, C. J., 1927: The role of phosphate in plant respiration, *Amer. Jour. Bot.*, **14**: 274-284.
- LYON, MILDRED E., 1928: The occurrence and behavior of embryoless wheat seeds, *Jour. Agr. Res.*, **36**: 631-637.
- MACDOUGAL, D. T., E. R. LONG, and J. G. BROWN, 1915: End results of desiccation and respiration in succulent plants, *Physiol. Res.*, **1**: 289-327.
- MAIGE, A., and G. NICOLAS, 1910: Recherches sur l'influence des variations de la turgescence sur la respiration de la cellule, *Rév. Gén. Bot.*, **22**: 409-422.
- and ———, 1910: Recherches sur l'influence des solutions sucrées de divers degrés de concentration sur la respiration, la turgescence et la croissance de la cellule, *Ann. Sci. Nat. Bot.*, 9^e ser., **12**: 315-368.
- MAGNESS, J. R., 1920: Composition of gases in intercellular spaces of apples and potatoes, *Bot. Gaz.*, **70**: 308-316.
- and H. C. DIEHL, 1924: Physiological studies on apples in storage, *Jour. Agr. Res.*, **27**: 1-38.
- and W. S. BALLARD, 1926: The respiration of Bartlett pears, *Jour. Agr. Res.*, **32**: 801-833.
- MANGENOT, G., 1928: Sur la localisation cytotologique des peroxydases et des oxydases, *Compt. Rend. Acad. Sci. Paris*, **186**: 710-712.
- MAQUENNE, L., and E. DEMOUSSY, 1921: Sur la respiration des feuilles dans le vide ou des atmosphères pauvres en oxygène, *Compt. Rend. Acad. Sci. Paris*, **173**: 373-377.
- MATTHAEI, G. L. C., 1905: Experimental researches on vegetable assimilation and respiration. III, The effect of temperature on carbon dioxide assimilation, *Phil. Trans. Roy. Soc.*, B, **197**: 47-86.
- MCGINNIS, F. W., and G. S. TAYLOR, 1923: The effect of respiration upon the protein percentage of wheat, oats and barley, *Jour. Agr. Res.*, **24**: 1041-1048.
- McHARGUE, J. S., 1920: The significance of the peroxidase reaction with reference to the viability of seeds, *Jour. Amer. Chem. Soc.*, **42**: 612-615.
- MEYER, A., 1918: Eiweissstoffwechsel und Vergilben der Laubblätter von *Tropaeolum majus*, *Flora*, **11-12**: 85-127.
- MIDDLETON, N. I., 1927: The effect of ionized air on the rate of respiration of barley seedlings, *Ann. Bot.*, **41**: 345-356.
- MILLER, E. C., 1910: A physiological study of the germination of *Helianthus annuus*, *Ann. Bot.*, **24**: 693-726.
- MOORE, B., and E. WHITLEY, 1909: The properties and classification of the oxidizing enzymes and analogies between enzymic activity and the effects of immune bodies and complements, *Biochem. Jour.*, **4**: 136-168.
- MOORE, WILLIAM, and J. J. WILLAMAN, 1917: Studies in greenhouse fumigation with hydrocyanic acid: physiological effects on the plant, *Jour. Agr. Res.*, **11**: 319-338.
- MORINAGA, T., 1925: Catalase activity and the aerobic and anaerobic germination of rice, *Bot. Gaz.*, **79**: 73-85.
- MORSE, F. W., 1908: The effect of temperature on the respiration of apples, *Jour. Amer. Chem. Soc.*, **30**: 876-881.
- MORGULIS, S., M. BEBER, and I. RABKIN, 1926: Studies on the effect of temperature on the catalase reaction. I, Effect of different hydrogen peroxide concentrations. II, Loss of catalase activity. III, Temperature effects at different hydrogen ion concentrations. IV, A theory of catalase reaction, *Jour. Biol. Chem.*, **68**: 521-563.
- MÜLLER-THURGAU, H., 1882: Ueber Zuckerrückbildung in Pflanzentheilen in Folge niederer Temperatur, *Landw. Jahrb.*, **11**: 751-828.

- NEMEC, A., and F. DUCHON, 1921: Peut-on déterminer la valeur des semences par voie biochimique? *Compt. Rend. Acad. Sci. Paris*, **173**: 933-935.
- and ———, 1922: Sur une méthode indicatrice permettant d'évaluer la vitalité des semences par voie biochimique, *Compt. Rend. Acad. Sci. Paris*, **174**: 632-634.
- and ———, 1923: Sur une nouvelle méthode biochimique pour le détermination de la force vitale des semences, *Ann. Sci. Agron., Franc., et Etrangère*, **40**: 121-150.
- NEWCOMBE, F. C., and E. A. BOWERMAN, 1918: Behavior of plants in unventilated chambers, *Amer. Jour. Bot.*, **5**: 284-295.
- NICOLAS, G., 1918: Contribution à l'étude des variations de la respiration des végétaux avec l'âge, *Rév. Gén. Bot.*, **30**: 214-225.
- OLNEY, A. J., 1926: Temperature and respiration of ripening of bananas, *Bot. Gaz.*, **82**: 415-462.
- ONSLow, M. W., 1919: Oxidizing enzymes. I, The nature of the "peroxid" naturally associated with certain direct oxidizing systems in plants, *Biochem. Jour.*, **13**: 1-9.
- , 1920: Oxidising enzymes. II, The nature of the enzymes associated with certain direct oxidising systems in plants, *Biochem. Jour.*, **14**: 535-540.
- , 1920: Oxidising enzymes. III, The oxidising enzymes of some common fruits, *Biochem. Jour.*, **14**: 541-547.
- , 1921: Oxidising enzymes. IV, The distribution of oxidising enzymes among the higher plants, *Biochem. Jour.*, **15**: 107-113.
- , 1921: Oxidising enzymes. V, Further observations on the oxidising enzymes of fruits, *Biochem. Jour.*, **15**: 113-118.
- , 1923: Oxidising enzymes. VI, A note on tyrosinase, *Biochem. Jour.*, **17**: 216-220.
- , 1924: The oxidising enzymes. VII, The oxygenase of the higher plants, *Biochem. Jour.*, **18**: 549.
- and M. E. ROBINSON, 1925: Oxidising enzymes. VIII, The oxidation of certain parahydroxy-compounds by plant enzymes and its connection with "tyrosinase," *Biochem. Jour.*, **19**: 420-423.
- and ———, 1928: Oxidizing enzymes. X, The relationship of oxygenase to tryosinase, *Biochem. Jour.*, **22**: 1327-1332.
- OPPENHEIMER, C., 1913: Die Fermente, **11**: 754.
- OSTERHOUT, W. J. V., and A. R. C. HAAS, 1917: An adaptation of Winkler's method to biological work, *Jour. Biol. Chem.*, **32**: 141-146.
- , 1917: The rôle of the nucleus in oxidation, *Science*, n.s., **46**: 367-369.
- , 1918: A method of studying respiration, *Jour. Gen. Physiol.*, **1**: 17-22.
- , 1918: An indicator method of measuring the consumption of oxygen, *Jour. Gen. Physiol.*, **1**: 167-171.
- , 1918: Comparative studies on respiration. I, Introduction, *Jour. Gen. Physiol.*, **1**: 171-181.
- OTA, JUNJI, 1925: Continuous respiration studies of dormant seeds of *Xanthium*, *Bot. Gaz.*, **80**: 288-299.
- OVERHOLSER, E. L., and W. V. CRUESS, 1923: A study of the darkening of apple tissue, *Calif. Agr. Expt. Sta. Tech. Paper* 7.
- , 1928: A study of the catalase of the fruits of pear varieties, *Amer. Jour. Bot.*, **15**: 285-307.
- PALLADIN, W., 1888: Ueber Eiweisszersetzung in den Pflanzen bei Abwesenheit von freiem Sauerstoff, *Ber. d. d. bot. Ges.*, **6**: 205-212.
- , 1888: Ueber Zersetzungsproducte der Eiweissstoffe in den Pflanzen bei Abwesenheit von freiem Sauerstoff, *Ber. d. d. bot. Ges.*, **6**: 296-304.

- PALLADIN, W., 1893: Recherches sur la respiration des feuilles vertes et des feuilles étiolées, *Rév. Gén. Bot.*, **5**: 449-473.
- , 1894: Sur le rôle des hydrates de carbone dans la résistance à l'asphyxie chez les plantes supérieures, *Rév. Gén. Bot.*, **6**: 201-209.
- , 1896: Recherches sur la corrélation entre la respiration des plantes et les substances azotées actives, *Rév. Gén. Bot.*, **8**: 225-248.
- , 1899: Influence de la lumière sur la formation des matières protéiques actives et sur l'énergie de la respiration des parties vertes des végétaux, *Rév. Gén. Bot.*, **11**: 81-105.
- , 1899: L'influence des changements de température sur la respiration des plantes, *Rév. Gén. Bot.*, **11**: 241-247.
- and A. KOMLEFF, 1902: Influence de la concentration des solutions sur l'énergie respiratoire et sur la transformation des substance dans les plantes, *Rév. Gén. Bot.*, **14**: 497-516.
- and S. KOSTYTSCHEW, 1906: Anaerobe Athmung, Alkoholgärung und Acetonbildung bei den Samenpflanzen, *Zeits. f. physiol. Chem.*, **48**: 214-239.
- , 1909: The theory of respiration of plants, *Biochem. Zeits.*, **18**: 151-206; *Expt. Sta. Rec.* **21**: 532 (1910).
- and A. M. SHELOUMOVA, 1918: Effect of loss of water on respiration of plants, *Bull. Acad. Sci. Russ.*, 6 ser., No. 8, pp. 801-808; *Expt. Sta. Rec.* **39**: 731 (1918).
- , 1922: "Plant Physiology," Eng. trans. by Livingston, P. Blakiston's Son & Co.
- PARIJA, P., 1928: Analytic studies in plant respiration. II, The respiration of apples in nitrogen and its relation to respiration in air, *Proc. Roy. Soc.*, B, **103**: 446-491.
- PEIRCE, G. J., 1908: A new respiration calorimeter, *Bot. Gaz.*, **46**: 193-202.
- , 1909: What is the use of respiration? *Plant World*, **12**: 193-198.
- , 1912: The liberation of heat in respiration, *Bot. Gaz.*, **53**: 89-112.
- PFEFFER, W., 1881-1885: Ueber intramoleculare Athmung, *Untersuch. Bot. Inst. Tübingen*, **1**: 636-685.
- POTTER, M. C., 1917: Note on a method of demonstrating the heat of respiration, *Ann. Bot.*, **31**: 435-438.
- RAY, G. B., 1923: Comparative studies on respiration. XXV, The action of chloroform on the oxidation of some organic acids, *Jour. Gen. Physiol.*, **5**: 611-623.
- , 1923: Comparative studies on respiration. XXVI, The production of CO₂ from organic acids in relation to their iodine absorption, *Jour. Gen. Physiol.*, **5**: 623-629.
- , 1923: Comparative studies on respiration. XXIV, The effects of chloroform on the respiration of dead and living tissue, *Jour. Gen. Physiol.*, **5**: 469-477.
- , 1923: Comparative studies on respiration. XXVII, The mechanism of oxidation in relation to chloroform anesthesia, *Jour. Gen. Physiol.*, **5**: 741-749.
- REED, G. B., 1914: The oxidases of acid tissue, *Bot. Gaz.*, **57**: 528-530.
- , 1915: Evidence for the general distribution of oxidases in plants, *Bot. Gaz.*, **59**: 407-409.
- , 1916: On the mechanism of oxidase action, *Bot. Gaz.*, **62**: 53-64.
- , 1916: The measurement of oxidation potential and its significance in the study of oxidases, *Bot. Gaz.*, **61**: 523-527.
- , 1916: The mode of action of plant peroxidases, *Bot. Gaz.*, **62**: 233-238.
- , 1916: The relation between oxidase and catalase in plant tissues, *Bot. Gaz.*, **62**: 409-412.
- , 1916: The relation of oxidase reactions to changes in hydrogen ion concentration, *Jour. Biol. Chem.*, **27**: 299-302.
- , 1916: The separation of oxidase reactions from the catalase reaction, *Bot. Gaz.*, **62**: 303-310.

- REED, G. B., 1916: The significance of color changes in oxidase reagents, *Bot. Gaz.*, **61**: 430-432.
- REGEIMBAL, L. O., G. A. VACHA, and R. B. HARVEY, 1927: The effect of ethylene on the respiration of bananas during ripening, *Plant Physiol.*, **2**: 357-359.
- RHINE, LOUISA E., 1924: Divergence of catalase and respiration in germination, *Bot. Gaz.*, **78**: 46-67.
- RICHARDS, H. M., 1896: The respiration of wounded plants, *Ann. Bot.*, **10**: 531-582.
- , 1897: The evolution of heat by wounded plants, *Ann. Bot.*, **11**: 29-63.
- , 1915: Acidity and gas interchange in cacti, *Carnegie Inst. Wash. Pub.* 209.
- RISCHAWI, L., 1876: Einige Versuche über die Athmung der Pflanzen, *Landw. Versuchs-Stat.*, **19**: 321-340.
- ROBINSON, M. E., 1924: A comparison of certain oxidizing enzymes of the higher and lower plants, *Biochem. Jour.*, **18**: 543-548.
- ROHMANN, E., and W. SPITZER, 1895: Ueber Oxydationswirkungen thierischer Gewebe, *Ber. d. d. chem. Ges.*, **28**: 567-572.
- ROSE, D. H., 1915: Oxidation in healthy and diseased apple bark, *Bot. Gaz.*, **60**: 55-65.
- , 1919: Blister canker of apple trees: A physiological and chemical study, *Bot. Gaz.*, **67**: 105-146.
- , H. R. KRAYBILL, and R. C. ROSE, 1920: Effect of salts upon oxidase activity of apple bark, *Bot. Gaz.*, **69**: 218-236.
- ROSENBERG, ANNA, 1910: Über die Rolle der Katalase in den Pflanzen, *Ber. d. d. bot. Ges.*, **28**: 280-288.
- DE SAUSSURE, THEODORE, 1804: "Recherches chimiques sur la végétation."
- SCHOENBEIN, C. F., 1863: Ueber die katalytische Wirksamkeit organischer Materien und deren Verbreitung in der Pflanzen- und Thierwelt, *Jour. Prakt. Chem.*, **89**: 323-344.
- SHERMAN, HOPE, 1921: Respiration of dormant seeds, *Bot. Gaz.*, **72**: 1-30.
- SHULL, C. A., 1911: The oxygen minimum and the germination of *Xanthium* seeds, *Bot. Gaz.*, **52**: 453-477.
- , 1914: The role of oxygen in germination, *Bot. Gaz.*, **57**: 64-69.
- , and W. B. DAVIS, 1923: Delayed germination and catalase activity in *Xanthium*, *Bot. Gaz.*, **75**: 268-281.
- SMITH, A. M., 1915: The respiration of partly dried plant organs, abs. in *Rept. Brit. Assoc. Adv. Sci.*, **85**: 725; *Expt. Sta. Rec.* **36**: 824.
- SMITH, EDITH P., 1921: Comparative studies on respiration. XIX, A preliminary stage in the process of ether anesthesia, *Jour. Gen. Physiol.*, **4**: 157-163.
- , 1922: Comparative studies on respiration. XXII, The effect of lactic acid on the respiration of wheat, *Amer. Jour. Bot.*, **9**: 307-311.
- SPOEHR, H. A., 1915: Variations in respiratory activity in relation to sunlight, *Bot. Gaz.*, **59**: 366-387.
- , and J. M. MCGEE, 1923: Studies in plant respiration and photosynthesis, *Carnegie Inst. Wash. Pub.* 325.
- , and ———, 1924: The effect of fluctuations in the CO₂ content on the atmosphere on the rate of respiration of leaves, *Amer. Jour. Bot.*, **11**: 493-502.
- , 1924: The oxidation of carbohydrates with air, *Jour. Amer. Chem. Soc.*, **46**: 1494-1503.
- STICH, C., 1891: Die Athmung der Pflanzen bei verminderter Sauerstoffspannung und bei Verletzungen, *Flora*, **74**: 1-57.
- STOCKLASA, J., and F. CZERNY, 1903: Isolirung des die anaerobe Athmung der Zelle der höher organisirten Pflanzen und Thiere bewirkenden Enzyms, *Ber. d. d. chem. Ges.*, **36**: 622-634.
- STOWARD, F., 1908: On endospermic respiration in certain seeds, *Ann. Bot.*, **22**: 415-448.

- TASHIRO, S., 1913: A new method and apparatus for the estimation of exceedingly minute quantities of carbon dioxide, *Amer. Jour. Physiol.*, **32**: 137-145.
- TERRIGINE, E. F., R. BONNET, et P. H. JOËSSEL, 1923: Influence de la température sur le rendement énergétique dans la germination, *Compt. Rend. Acad. Sci. Paris*, **177**: 212-214.
- THODAY, D., 1913: On the capillary eudiometric apparatus of Bonnier and Mangin for the analysis of air in investigating the gaseous exchanges of plants, *Ann. Bot.*, **27**: 565-573.
- , 1913: The effect of chloroform on the respiratory exchanges of leaves, *Ann. Bot.*, **27**: 697-717.
- THOMAS, H. S., 1918: Comparative studies on respiration. IV, The effect of ether on the respiration of wheat, *Jour. Gen. Physiol.*, **1**: 203-209.
- THOMAS, M., 1925: The controlling influence of carbon dioxide. V, A quantitative study of the production of ethyl alcohol and acetaldehyde by cells of the higher plants in relation to concentration of oxygen and CO₂, *Biochem. Jour.*, **19**: 927-947.
- TRAUBE, M., 1877: Die chemische Theorie der Fermentwirkungen und der Chemismus der Respiration, *Ber. d. d. chem. Ges.*, **10**: 1984-1992.
- TRUE, R. H., and W. W. STOCKBERGER, 1916: Physiological observations on alkaloids, latex and oxidases in *Papaver somniferum*, *Amer. Jour. Bot.*, **3**: 1-11.
- WAKABAYASHI, S., 1925: The injurious effect of submergence on the cranberry plant, *N. J. Expt. Sta. Bull.* 420.
- WARBURG, O., 1921: Physikalische Chemie der Zellatmung, *Biochem. Zeits.*, **119**: 134-166.
- , 1925: Iron, the oxygen-carrier of respiration ferment, *Science*, n.s., **61**: 575-582.
- , 1928: The chemical constitution of respiration ferment, *Science*, n.s., **68**: 437-443.
- WEISS, F., and R. B. HARVEY, 1921: Catalase, hydrogen-ion concentration, and growth in the potato wart disease. *Jour. Agr. Res.*, **21**: 589-592.
- WHELDALE, M., 1910: Plant oxidases and the chemical interrelationships of color varieties, *Prog. rei. Bot.*, **3**: 457.
- WHIMSTER, K., 1927: The effect of ionized air on the assimilation and respiration of green leaves, *Ann. Bot.*, **41**: 357-374.
- WHITE, JEAN, 1909: The ferments and latent life of resting seeds, *Proc. Roy. Soc., B*, **81**: 417-442.
- WILLAMAN, J. J., and J. H. BEAUMONT, 1928: The effect of accumulated carbon dioxide on plant respiration, *Plant Physiol.*, **3**: 45-61.
- WOODS, A. F., 1902: Observations on the mosaic disease of tobacco, *U. S. Dept. Agr. Bureau Plant Ind. Bull.* 18.
- YOSHIDA, H., 1883: Chemistry of lacquer, *Jour. Chem. Soc. London*, **43**: 472-486.
- ZALESKI, W., and A. ROSENBERG, 1911: Zur Kenntnis der Rolle der Katalase in den Pflanzen, *Biochem. Zeits.*, **33**: 1-15; *Bot. Centrbl.*, **119**: 431. 1912.
- , 1915: Über die Alkoholoxydation durch die Samenpflanzen, *Biochem. Zeits.*, **69**: 289-293.
- ZERBAN, F. W., 1918: The role of oxidases and of iron in the color changes of sugar cane juice, *Jour. Ind. Eng. Chem.*, **10**: 814-817.

CHAPTER XIV

THE PROCESS OF GROWTH IN PLANTS

I. NATURE OF GROWTH

Growth is one of the outstanding characteristics of living matter, but at the same time it is a process which is very difficult to define. In discussing the nature of growth, it should be remembered that it may be considered from the standpoint of the entire organism or from that of its individual parts. Thus growth may refer to the changes which occur in the protoplasm, in the cell wall, in the cell considered as a unit, in the organs or parts of organs, or in the entire plant considered as a whole. Any statements, therefore, concerning growth will be modified somewhat by the viewpoint from which they are considered.

Regardless of the standpoint from which growth is considered, the first step in the process is, with but few exceptions, the formation of new protoplasm. This step has been termed the "fundamental stage of growth." This formation of new living matter is always accompanied or immediately followed by a permanent increase in the amount of the non-living materials which are always closely associated with the protoplasm. This increase in the amount of non-living matter is plainly evident through the enlargement of the plant part and by an increase in its weight. These changes are due chiefly to an increased water content and to the deposition of materials in the cell walls. Since this stage in growth is readily observed, it has been termed the "evident stage of growth." This increase in the size and weight of the plant part under consideration is permanent as long as that part remains alive. In the light of these facts, growth has been defined by some authors as a permanent increase in weight, attended by a permanent change in form, these changes having been induced primarily by an increase in the quantity of protoplasm.

While there are instances where this definition of growth does not strictly describe the changes which occur, it is applicable in most cases. Two of the examples which have frequently been cited as cases where this definition does not apply are the sprouting potato tuber and germinating seeds. Thus the total dry weight of the tuber and sprout will be less than that of the original tuber due to loss in weight through respiration. The sprouts, however, have greatly increased in weight and changed markedly in form from the buds which produced them. The same relation exists in germinating seeds where the seedling and seed combined

for several weeks contain less dry matter than the original seed. The plumule and radicle of the embryo, however, have increased their weight and have changed in form, although the seed as a whole has decreased in dry matter.

To some, however, growth implies more than simply an increase in weight and size. They believe that differentiation and development should also be included in the term. The development of a plant from the fertilized egg is not simply an increase in the weight and size of the fertilized egg; otherwise a mature plant would be only an enlarged egg and not a highly specialized individual. It is evident that if the differentiation of a plant or plant part is not considered as a phase of growth, it must at least be regarded as intimately associated with it.

The growth of an organism consists primarily of the formation of new cells, of their enlargement and specialization. In order, therefore, to understand growth in plants, we must consider in detail the manner in which a plant cell grows.

II. STAGES IN THE GROWTH OF A PLANT CELL

In the formation and development of a plant cell, three more or less distinct stages or types of activity are to be observed. The transition from one stage to another is not sudden and complete, but the different stages can readily be distinguished and can be seen to be differently affected by the immediate environment of the cells (Priestley, 1929). The different stages of growth which may be distinguished are (a) the embryonic or formative stage, (b) the stage of elongation, and (c) the stage of differentiation.

A. EMBRYONIC OR FORMATIVE

This stage includes that period in which the cell is formed from a preexisting cell. In the vascular plants, the formation of new cells is localized in more or less definite regions known as "meristems." These regions are fairly definitely confined to the tip of branches, near to the tips of roots, to the cambium, to the base of the internodes especially in the monocotyledons, and to the bases of the growing sheaths and leaves of monocotyledons.

The cells of the meristem which thus give rise to new cells are small with dense protoplasmic contents and prominent nuclei. The nuclei are of the normal size of other plant cells, but in such small cells they bulk large in proportion to the rest of the protoplasm. The protoplasm is especially free from vacuoles and characteristic inclusions, no granular food reserves being evident, while the plastids are very minute or invisible. The cells may be 12 to 14 sided but frequently are cubical and are closely packed together with no intercellular spaces. The cell walls are the thinnest of any in the plant body, and according to Priestley (1929)

they frequently take stains, which indicates that they are impregnated with protoplasm. He considered that the walls of these cells are the channels of transport for the food supplies of this tissue. It should be mentioned here that certain of the characteristics of the meristematic cells which have been mentioned are not applicable to the cambium.

In the meristematic cells protein synthesis is dominant, while carbohydrate formation is at a minimum. In this formative stage, therefore, the protoplasm is primarily engaged in protoplasmic synthesis. According to Priestley (1929), this is maintained only when the liquid surrounding the cell has a hydrogen-ion concentration near the isoelectric point of the main constituent protein of the cell. When the mass of a meristematic cell has increased to a certain point, cell division follows, and the narrow range of cell size in these regions indicates that the division follows the attainment of a certain upward limit of the cell mass. MacDougal (1916 to 1921) came to the conclusion from his extensive experiments with growth that the first step in the process is an increase in the volume of the protoplasm by hydration. This increase in volume is usually but not always accompanied by the incorporation of materials other than water to the colloids of the protoplasm with the entailed additional capacity for absorbing water. The actual manner in which this incorporation occurs, however, is not known. MacDougal believed that the protoplasm of plants consists of a comparatively inert base of a polysaccharose character in colloidal combination with proteins, amino acids, lipins, and salts. The enlargement of protoplasmic mass due to hydration is therefore determined by the character of this colloidal mixture as well as by the quantity and type of salts and by the acidity or alkalinity of the medium. These factors might all be altered by the action of the metabolic products of the meristematic cells. The retardation of growth of an organ may be directly connected with the lessening of the water capacity of the colloidal masses. This theory of the rôle of colloidal hydration in growth has been substantiated by the work of MacDougal (1920, 1921) and MacDougal and Spoehr (1917) with artificially prepared mixtures consisting largely of amorphous, condensed carbohydrates such as agar to which had been added a small proportion of albumen or amino acid. These mixtures were found to respond to the action of acids, alkalies, and salts in a manner similar to that of the plant.

Instances of growth are known in which water only has been added to the colloids of the protoplasm, but in these cases in all probability the solid particles are variously rearranged. MacDougal (1919) found no increase in dry matter in the leaves of *Crassulaceae*, in the joints of cacti, and in fruits, although growth as measured by the change in form was taking place. The proportion of water and solid matter thus underwent but little change, their incorporation being at a rate which kept them near the initial proportion.

B. ELONGATING

After a new cell has been formed, the protoplasm tends toward carbohydrate synthesis rather than protein synthesis. The increased carbohydrate synthesis is indicated by the increase in the thickness of the cell walls and by the inclusion of starch grains in the protoplasm (Priestley, 1928). The amount of protoplasm increases little if at all during this stage of cell development.

The protoplasm of the new cell now exhibits syneresis similar to that shown by many colloids in which cavities or canals are formed throughout the colloidal mass. These syneretic cavities enlarge by the absorption of water to form the "vacuoles," by which name they are generally called. These vacuoles continue to expand by the absorption of water and eventually coalesce to form the vacuole of the cell. The expansion of these vacuoles and the consequent increase in volume of the cell takes place primarily by the force of osmotic action. The vacuole continues to hold some of the colloidal material and in addition the various solutes which enter the cell or are formed therein (MacDougal, 1919).

During the elongating period, the newly formed cell increases in size, especially in length (Fig. 3). When this elongation takes place, the protoplasm, which has increased but little in amount over that of the newly formed cell, spreads out in a thin film along the cell wall. The volume of a plant cell may thus increase several hundred times and yet contain very little more protoplasm than before expansion began. In this respect, the plant cell differs from the animal cell, for in the latter no such increase in volume takes place without a corresponding increase in the amount of protoplasm. By this expansion of cells due to the absorption of water very rapid growth occurs without the expenditure of the energy necessary to manufacture relatively large quantities of protoplasm. This ability to grow rapidly is a distinct advantage to an organism where there is a time limit to its period of growth. The total period during which the elongation of the plant cell occurs is termed the "grand period of growth."

C. DIFFERENTIATING

About the time a cell reaches its maximum enlargement, it begins to undergo changes which will transform it into a specialized cell. It may become a sclerenchyma cell, a sieve tube, a tracheid, or any other of the numerous types of cells that compose a plant, depending upon its location and the resultant of internal and external factors. When a cell has once become specialized, it seldom if ever reverts to another form but remains the same type of cell as long as it exists. After a cell is differentiated, it functions solely in aiding other cells to grow and develop.

III. GROWTH OF PLANT ORGANS

In the great majority of plants the regions of cell expansion are strictly localized. Thus the following are the regions in the higher plants where increase in the size of the cells occurs: (*a*) near the root tip. The elongating region is restricted to a portion of the root not over 10 mm. in extent. The region of maximum elongation generally occurs only about 3 mm. back of the root tip; (*b*) at the tips of stems. The stem, as a rule, has a longer elongating region than the root; (*c*) at the cambium; (*d*) at the base of the internodes in the monocotyledons; and (*e*) at the base of the sheaths and leaves of monocotyledons. In the leaves of dicotyledons growth is rather evenly distributed throughout the entire surface but with slightly more activity at the basal region than at the apical one. In general, growth is more localized in a mature plant than in a younger one and more so in a perennial than in an annual plant.

Since each cell of a plant passes through the three more or less distinct stages in its growth and development, each plant part or organ in its development passes through the same stages. Thus each organ or plant part has its formative stage, its elongative stage or grand period of growth, and its stage of differentiation or maturation. The enlargement of any plant part begins at a slow rate which gradually increases to a maximum, after which the rate progressively decreases until enlargement ceases. This behavior of growth is illustrated by the rate of elongation of the growing zone of a root of *Vicia faba*, as quoted by Raber (1928).

Day	Growth, millimeter	Day	Growth, millimeter
1	2	6	14
2	4	7	7
3	18	8	4
4	18	9	0
5	17		

From these data it is seen that elongation during the first 2 days is relatively slow but reaches a maximum during the next 3 days, after which it rapidly declines to zero.

The higher plants, as a rule, continue to develop new organs as long as they live, forming stems, leaves, roots, flowers, and seeds in a somewhat indefinite repetition. Even in an annual plant no definite number of organs are developed. This is in marked contrast to most animals, which develop a single set of organs which serve them throughout their life. Although growth in an annual plant is limited to one season, this process in perennial plants continues as long as the plant lives. Thus a tree that is several thousand years old will continue to produce organs and increase in height and thickness of stem.

IV. NATURE OF GROWTH CURVES

The rate of growth of plants or plant parts is commonly measured by their increase in extent or by their increase in weight. As has been previously mentioned, the rate of growth of a plant or any portion of it is relatively slow at first, increases rapidly to a maximum, and finally decreases until it ceases. This behavior is especially noticeable when the elongation of plant parts is considered. When the rate of growth is plotted against time, a typical S curve is obtained.




FIG. 38.—Graphs showing the weekly gain in dry weight of Reid Yellow Dent corn grown at Manhattan, Kans., in 1925, together with the weekly averages of the maximum and minimum temperatures.

There are various ways in which the growth increment may be expressed, but there is no concensus of opinion as to which is the best. Hackenberg (1908) and others used the term “substance quotient” in expressing the increment of growth. The substance quotient is the ratio of the dry weight at any given period to the dry weight of the preceding period. The rate may also be expressed as the percentage increase of dry weight or of extent for a given period over that of the preceding one. The increase in leaf surface or in leaf weight is also considered by some to be a good indicator of growth increment.

In the table on page 804 are given data obtained by Miller (1925) in the growth of the corn plant at Manhattan, Kans. The weekly increments of growth are therein expressed by the increase in dry weight, the percentage increase in dry weight during each period over that of the succeeding period, the increase in the leaf surface, and the increase in the height of the plant for each period. The rate of transpiration per plant and the weather conditions in regard to temperature are also included. A portion of this data is plotted in Fig. 38. The increments in growth in this case are somewhat irregular due, in part at least, to a considerable degree to rather wide fluctuations in temperature during several periods.

Numerous attempts have been made to give mathematical expression to the growth curves of plants. Some of the investigators who have worked with this problem are Robertson (1907 to 1908, 1923), Blackman (1919, 1920), Brenchley (1919, 1920), Reed and Holland (1919), Reed (1919 to 1923), Kidd, West, and Briggs (1919 to 1928), Fisher (1920), Priestley and Evershed (1922), Priestley and Pearsall (1922), Rippel (1922), Hooker (1925), Inamdar, Singh, and Pande (1925), Sande-Bakhuizen (1926), Pearsall (1927), Gregory (1928), Copeman (1928) and Porterfield (1928). A complete discussion of the contributions of these authors is beyond the scope of this book, and it is the intention here to summarize as briefly as possible the opinions concerning this subject. The student who is interested is referred to these citations for detailed information.

Robertson (1907 to 1908) advanced the view that growth is of the nature of a monomolecular autocatalytic reaction. An autocatalytic reaction is one which is capable of self-catalysis, one of the products of the reaction acting as a catalytic reagent. A reaction of this type proceeds slowly at first, rapidly increases to a maximum, and then declines in its rate. The curve for such a reaction is thus typically S shaped.

Since the curve of growth is very similar to that of an autocatalytic reaction, Robertson proposed that growth is of this nature and that some special catalyst of the nature of an enzyme governs the growth rate of an organism. He considered that the growth curve could be expressed by the formula

$$\log \frac{x}{A - x} = K(t - t_1)$$

where A is the maximum dry weight of the plant, x the dry weight of the plant at any time, t the time at which the weight of the plant is one-half the final dry weight, and K a constant. Robertson considered that the greatest increase in volume or weight in any unit of time in any growth cycle takes place when the total growth due to the cycle is one-half accomplished. Reed and Holland (1919) and Reed (1919 to 1923) from their observations on the elongation of the sunflower, apricot, and other

WEEKLY GROWTH CHANGES OF REID YELLOW DENT CORN AT MANHATTAN, KANS. DURING GROWING SEASON OF 1925
Averages of Five Plants

Date	Average dry weight per plant, grams		Weekly gain in dry weight per plant		Total leaf surface per plant, grams	Weekly increase in leaf surface per plant		Rate of growth in height, inches	Transpiration per plant, cc.	Average weekly minimum temperature, °F.	
	grams	per plant	Grams	Per cent		Grams	Per cent			maximum	minimum
May 11.....	0.16		0.14 ¹	47.0 ¹	70.5	3.5	59		
11-25.....	0.65		0.49	306.2	348.1	277.6	393.7	2.5	102		
25-June 1.....	4.66		4.01	617.0	1,554.8	1,206.7	346.9	5.0	1,079	88.8	68.7
June 1-8.....	15.74		11.08	237.7	4,260.7	2,705.9	174.0	6.0	2,874	88.4	65.1
8-15.....	49.30		33.56	213.2	9,891.5	5,620.8	131.9	14.0	4,110	92.7	69.6
15-22.....	123.70		74.40	151.0	17,069.2	7,277.7	73.5	17.0	8,290	90.4	64.8
22-29.....	195.00		71.30	57.6	21,585.8	4,516.6	26.4	17.0	22,610	95.8	72.9
29-July 6.....	297.00		102.02	52.3	26,699.2	5,113.4	23.6	18.0	27,220	99.4	73.6
July 6-13.....	385.50		88.48	29.8	28,629.4	1,930.2	7.2	33.0 ²	30,420	95.3	67.9
13-20.....	499.70		114.20	29.6	Full leaf development						
20-27.....	570.80		71.10	14.2					22,190	90.1	67.6
27-Aug. 3.....	679.00		108.20	18.9					15,530	83.1	58.7
Aug. 3-10.....	807.50		128.50	18.9					21,610	90.7	66.3
10-17.....	895.90		88.40	10.9					15,890	91.0	67.4
17-24.....									17,130	93.9	66.3

¹ Loss
² Tasseling.

plants and Murneek (1925) from observations on the tomato and cotton plants concluded that the growth rate approximated the course of an autocatalytic reaction. A close similarity between the observed and calculated growth values led them to the conclusion that the growth rate is governed by constant internal factors rather than by external factors. They obtained no strong correlation of growth either with temperature or with transpiration summation. In the case of apricot, Reed (1919) considered that an organism grows at a definite rate which is at any moment proportional to the amount of growth yet to be made.

Blackman (1919, 1920) suggested that the growth of an annual plant can be treated as a process following the compound-interest law expressed by the formula

$$W_1 = W_0 e^{rt} \text{ or, written in another manner, } \log_e \frac{W_1}{W_0} = rt$$

In this formula W_1 is the dry weight of the plant at the end of the time t , W_0 the initial seedling or seed rate, e the base of the natural logarithms, and r the rate of interest or increase. Blackman termed this rate of increase in dry matter the "efficiency index of production," since it represents the efficiency of the plant as a producer of new material and gives a measurement of the plant's economy. It may also be termed the "economy constant" of the plant and is comparable to the velocity constant of a chemical reaction. The rate of increase of dry material increases during daylight according to external conditions and during the night becomes a negative quantity. On that account, Blackman (1920) states that the efficiency index when applied to plants growing under natural conditions is only an average measure of the activity of the plant in the production of new material. He also states that caution must be exercised in making deductions as to a plant's general economy from the efficiency index calculated over periods. The efficiency index nevertheless gives a measure of the plant's average efficiency during any particular period.

Kidd, West, and Briggs (1920) and Briggs, Kidd, and West (1920) calculated the growth rate by means of the formula

$$\frac{R}{100} = \frac{W_2 - W_1}{W_1}$$

where W_1 and W_2 are the dry weights, respectively, of the plants at the beginning and end of the period under consideration. This formula gives the rate of increase in dry weight for the period as a percentage of the dry weight at the beginning of the period. It was adversely criticised by Fisher (1920), who believed that the growth rate should be calculated as a percentage of the mean value for the period.

In a consideration of growth formulae it should be noted that the rate of change at any time is conditioned by the state of the system at that

time; that the rate of change of the system is conditioned by its previous history as well as by the state of the general environment (Gregory, 1928).

V. PERIODIC ELONGATION

According to Friesner (1920), it was first observed by Sachs (1874) that plants exhibit a rhythm of elongation. He found that plants exposed to the alteration of light and darkness showed a maximum elongation shortly after sunrise and the minimum shortly after sunset. Prantl (1873) found a similar behavior in the increase in width of leaves and under normal conditions the maximum was reached in the morning from six to nine and the minimum in the evening from six to nine. He observed that by shifting the hours of illumination and darkness he could alter the time of maximum and minimum expansion, since for each change in the time of illumination and darkness there was a corresponding change in the times of maximum and minimum expansion. These investigators could find no evidence of periodicity when the plants were grown in the dark from the beginning, and Baranetzky (1879) observed that plants which exhibit this regular periodicity lose this when placed in darkness. The time for its complete loss varied from 2 to 3 days and in one case to 14 days. He also observed that plants grown from the beginning in darkness did not exhibit this periodicity except in the case of the shoots of *Brassica rapa* where it continued to exist.

MacMillan (1891), however, noted that the increase in the diameter of the potato tuber developing in continuous darkness is not regular but rhythmic. The maxima of growth may occur from one to four times during a 24-hr. period. These are not of long duration and are followed by periods of slower growth or entire cessation of growth. The maxima of some days were greater absolute maxima than those of other days, which indicates a grand period of growth for the tuber. MacMillan believed that there is some connection between the periodic growth of the tuber and the periodic growth of the aerial stem but that there is also an independent periodicity in the growth of the tuber which is obscured and modified by the secondary induced periodicity which is related to the aerial stem and its mode of growth.

It was observed by Lewis (1901) that the roots of *Allium cepa* showed two waves in their rate of cell division, the maxima coming at midnight and noon and the minima at 4 a. m. and 4 p. m. His work was substantiated by Kellicot (1904), who also observed that the periods of rapid cell division coincided with a low rate of elongation and that during rapid elongation the rate of cell division was the lowest.

Friesner (1920) in the study of the rate of elongation of the radicles of *Cucurbita pepo*, *Lupinus albus*, *Pisum sativum*, *Vicia faba*, and *Allium cepa* showed that elongation in all these plants proceeded in a wavelike fashion, two to four waves being exhibited in a 24-hr. period. He also

found that the curve of cell division in these plants exhibited a number of oscillations and that the maxima of elongation were near the minima of cell division, and *vice versa*. He made the important discovery that the exact time of the occurrence of the maximum and minimum cell division is dependent upon the time of the initiation of activity and not upon the time of day.

The question now arises as to what are the causes of the rhythm found both in the elongation and the cell division of plants. It apparently is not due to external influences of changes in illumination and temperature, since this occurs in darkness under conditions of constant temperature. It is apparently not due to heredity, since it is generally lost when the plants are placed in continuous darkness and uniform temperatures. Friesner (1920) considered that when a large number of cells are undergoing mitosis, the total energy available within the tip is directed more to mitosis than toward elongation, so that the one process will be near to its maximum when the other is near to its minimum. These processes alternate with each other in the individual cell and in the root as a whole. The fact that these rhythms have a definite interval and that the maxima and minima in the different curves depend for the time of their appearance upon the time when activity begins indicates that this alternation between mitosis and elongation is entirely an internal cause and is not related to external conditions. Friesner suggested that a distinction should be made between the terms "periodicity" and rhythm." He considered that the term periodicity as used by the earlier writers means a regular oscillation which is caused by the alternation of day and night or by other external changes and which is lost when the environmental conditions are rendered constant. The term rhythm he would restrict to mean any oscillation in activity which is definite and regular and not related to any external influence.

VI. GROWTH-PROMOTING AND GROWTH-INHIBITING SUBSTANCES

Before discussing the literature on this topic, it should be emphasized that the evidence concerning the existence of these substances is very limited and almost entirely indirect and that practically all that has been written on the subject belongs to the realm of theory rather than fact.

It was assumed by Sachs that specific organ-forming substances are needed for growth and that the exhaustion of these substances in the growing regions is the cause of the inhibition of growth of dormant buds. Pfeffer (1900) also considered that regulatory influences exerted by enzymes and other chemical substances play a rôle in growth. Armstrong and Armstrong (1911) stressed the function of substances resembling hormones in the metabolism of plants, and Gericke (1924) concluded from nutritional studies of wheat that plants have a physiology which is subject to growth-inhibiting and growth-stimulating agencies.

It has thus come to be generally considered that the growth of plants or plant parts is promoted or inhibited by certain substances other than the inorganic and organic compounds that have been shown to be necessary for plant life. It is considered that some of these substances are manufactured by the plant, while others may be obtained from the soil. The chemical composition of these substances, however, has never been determined. They have been variously termed "vitamins," "hormones," "growth-promoting," or "growth-inhibiting substances."

A. GROWTH-PROMOTING SUBSTANCES

Although the plant manufactures the vitamins that are so essential to the growth and development of animals, there is little evidence to indicate the rôle that they play in the plant body. The fact that they are frequently present in the largest amounts in those parts of the plant where the metabolic processes are the most active has been considered to indicate that they play a rôle in the nutrition of the plant (Tschirch, 1921). The presence of hormones in plants has not been proved to any degree of certainty. The evidence of their occurrence is mostly indirect. For example, blooming occurs in certain orchids until pollination occurs. If, however, pollen extracts are made and injected into the pistil, flowering ceases just as if pollination had occurred. Tschirch (1921) considered that this influence is due to a hormone-like substance in the pollen. Swingle (1928) noted that pollination had a direct effect upon the pericarp of the date. This influence was shown on the size, shape, character, and time of ripening of the fruit. These changes cannot be explained by xenia. Swingle believed that the simplest and most probable explanation is that the embryo or endosperm or both of them secrete hormones or soluble substances analogous to them. These diffuse out into the tissues that constitute the fruit and there exert a specific effect on these tissues varying according to the particular male parent used to fecundate the embryo and endosperm.

The fact that small amounts of organic extracts appear to stimulate plant growth to a marked degree has been taken to mean that substances other than those used directly in food building are necessary for the proper functioning of the plant. Thus the application of animal manure to the soil greatly increases the development of the plant. It has generally been assumed that this stimulation was due to the compounds of nitrogen, phosphorus, and potassium which it contained. Breazeale (1927), however, found that this stimulating property rests largely in the water-soluble organic matter and not in the inorganic compounds which it contains. He believed that the beneficial effects of manure and crop rotation are due in large part to the fact that their vegetative matter decomposing develops or sets free certain organic compounds that are essential to the growth of plants.

The cause of the dominance of the apical bud on stems and tubers and of the polarity of stems has always been a question of great interest, and much of the literature on growth-promoting and growth-inhibiting substances has been devoted to theories which attempt to explain such behavior. In extensive studies concerning the development of roots, buds, and shoots in *Bryophyllum calycinum*, Loeb (1915 to 1924) proposed several theories to account for the growth of certain plant organs and for the inhibition of others. One of these theories assumes that the growth of the bud depends upon the flow of certain substances from the leaf to the bud. The bud which receives these substances first will grow out first and thereby prevent the flow to the other buds whose growth is thereby inhibited. The apparent inhibition of growth in certain regions is thus due simply to the fact that under certain conditions the substances required for growth flow to some other place and are retained there. The removal of this inhibition consists in creating conditions which force the substances to flow to other places at which growth will then occur.

Appleman (1918) obtained evidence from sprouting potato tubers which indicates the presence of growth-promoting substances therein. Thus the vigor of potato sprouts bears a direct relation to the size of the seed piece or, in other words, to the amount of tissue surrounding the eye. When a certain minimum is reached, the vigor of the sprout decreases as the size of the seed piece is reduced, the plant resulting therefrom remaining weak during its vegetative period and yielding a small crop of tubers. The weak sprouts are not due to the lack of ordinary food materials, since a sufficient quantity of these for future growth remains in the tuber piece. It has also been shown that the ordinary inorganic nutrients are not the materials that are lacking under these conditions. Appleman concluded that the potato tuber contains a limited amount of a special growth-promoting substance and that if the amount of tissue surrounding the growing bud is too small, there is not enough of this substance available for normal growth.

Some investigators, however, do not consider that it is necessary to assume the existence of special growth-controlling substances to explain growth behavior. Gustafson (1927) believed that growth, especially in fruits, is influenced mainly by nutrition. As the cells begin rapidly to divide, rapid growth ensues provided that food is supplied; and when the supply of food becomes limited, cell formation ceases and the fruit begins to mature. He considered that the growth of shoots and roots can be explained in the same manner. Thus in the tomato when the nutrients were not diverted to fruit formation, the rate of growth of the shoot continued at approximately a uniform rate in contrast with an increasingly lower rate when fruiting was taking place. Pearsall (1923) states that while there appears to be some evidence in plants of the effect of specific substances it is not known whether we are dealing with specific

substances which are products of cell metabolism or are dealing simply with combinations of direct effects.

B. GROWTH-INHIBITING SUBSTANCES

The absorption by the plant of compounds for the soil which inhibit plant growth has been discussed in detail in Chap. III. The discussion here will deal especially with the inhibitors which retard the development of stems and roots. Loeb (1915 to 1924) proposed a theory to account for the dominance of the apical stem upon the basis of the formation of growth-inhibiting substances by the plant. He assumed that the growing apex of a stem might form a definite substance which is antagonistic to bud growth and which migrating toward the base would impede or inhibit the growth of the lower buds. The apical buds are the first to be freed from this substance and begin to grow out, producing at the same time fresh supplies of the inhibitor the concentration of which increases gradually toward the base of the stem. The subapical buds are therefore retarded in growth increasingly in this direction, until finally the point is reached where the concentration is great enough to inhibit lateral shoot growth completely.

Appleman (1918) obtained evidence that the terminal buds of the potato tuber inhibit the development of the lateral ones. Thus when all the eyes of a tuber are subjected to the same external conditions, the buds on the terminal or seed end will grow out first, the number of such buds developing depending upon the variety, size of the tuber, and the vigor of the terminal sprouts. The number of eyes on the tuber, however, bears no direct relation to the number of sprouts which will grow out from the terminal end. If the terminal buds grow normally, they inhibit the growth of the more basal ones. If, however, the terminal sprouts are destroyed or otherwise retarded, sprouts will appear on the stem half of the tuber which otherwise would have remained dormant. If the tubers are cut transversely into halves, the suppressing influence of the terminal eyes is thus removed and the eyes on the stem end show an equal if not greater capacity for the production of vigorous sprouts as the terminal bud.

Reed and Halma (1919) believed that the manner of growth of the young shoots of pear and Chinese lemon observed by them afforded evidence for the hypothesis that a growth-inhibiting substance is produced in the apical portion of the shoot and that it travels downward toward the base, causing a condition of dormancy in the subapical buds. It was observed by Priestley and Evershed (1922) and Priestley and Pearsall (1922) that the growth curve of the roots formed from cuttings of tomato and *Tradescantia* showed a progressive series of S curves. In all cases the first curve ended just before the secondary root formation and the second reached its low level at the appearance of the tertiary roots.

They attributed these phases of retardation to the operation of inhibiting factors such as accumulated end products which were left over from the previous growth.

VII. DORMANT OR RESTING PERIODS

The rest or dormant period in plants is a period when the plant or plant parts to all appearances do not grow. Woody plants especially exhibit this characteristic, while it is very common in seeds, bulbs, tubers, buds, and spores. Plants and plant parts vary greatly in the extent of this dormant period. In some instances it may last for only a few days, while in some seeds it may last to 100 years or more. Woody plants go into the dormant condition in the temperate zone at the close of the summer, while crocus, hyacinth, spring beauty, and tulip die to the ground in the spring and their bulbs become dormant by early summer and almost never begin to grow again before fall, no matter what sort of weather prevails. The majority of seeds will not germinate at once when placed under the conditions which ordinarily produce germination. Howard (1915) found that if 2 weeks is sufficient time to allow seeds for making immediate germination, fully 75 per cent of the species of Missouri exhibit dormancy. Of the 76 species of seed examined by him 23.6 per cent grew in less than 3 weeks, 39.4 per cent in the fall or following spring, while 37 per cent did not germinate at all during the time of his experiments.

Duvel (1905) and Goss (1924) found that of the 107 species of seeds buried by them, 50 species grew after a period of 20 years, the germination ranging from 1 to almost 100 per cent. Ohga (1923) found that seeds of *Nelumbo nucifera* taken from strata of soil in a railroad cut and estimated to be from 120 to 400 years old still retained their vitality and readily germinated after their coats were filed to allow the intake of water. The rest or dormant period in the seeds of wild plants is more general and more persistent than in the cultivated ones.

A. CAUSES OF DORMANCY IN PLANTS AND PLANT PARTS

According to Crocker (1916), dormancy is brought about by factors inhibitory to general processes preceding or accompanying growth. The rest period is considered by some to be a direct response to the changing external conditions, while others consider it to be the result of fixed heredity. It seems reasonable to consider it a result of a combination of these two factors. Thus, for example, the structure of a seed which possesses impermeable seed coats or an immature embryo which causes it to be dormant is apparently due primarily to hereditary factors. The environmental conditions under which the seed develops, however, will serve to alter to a considerable degree the nature of the seed structures. The conditions under which such a seed is placed after its separa-

tion from the plant will also determine to a marked degree the extent of its resting period.

The work of Howard (1910) indicates that in many cases dormancy is induced primarily by changes in the environment. Thus, of 283 species of woody plants brought into the greenhouse in November and January more than one-half grew easily inside 2 weeks without any treatment. In some species the winter rest is a habit induced by unfavorable outward circumstances, and if these conditions are removed some species can be induced to grow readily. The peach tree apparently belongs to this type of plants. It has a comparatively short dormant period and frequently becomes active during the warmer days of winter, with the result that the fruit buds are killed.

The causes of dormancy in seeds have been studied extensively. According to Crocker (1916), their dormancy is due to one or a combination of the following causes: (1) the possession of thick or hard coats which prevents the intake of water and probably also of oxygen. Some of the seeds which possess such coats are those of the legumes except peanut, several species of *Nelumbo*, velvet leaf, Kentucky coffee bean, asparagus, morning glory, and okra. The possession of coats which are hard or impermeable to water is one of the most common causes of dormancy in seeds. In some species all the seeds are hard but more frequently only a portion and these are of varying degrees of hardness. This in nature insures the distribution of germination of a single crop over a number of years. Most of the long-lived seeds have hard, impermeable coats.

In some cases, the seed coats are readily permeable to water but are so firm that they prevent the expansion of the embryo. The seeds of *Alisma plantago* and *Amaranthus retroflexus* are apparently inhibited in their germination on this account. Crocker and Davis (1914) reported that when the seeds of *Alisma plantago* lie in water, the embryo itself does not much more than one-fourth consummate its possible imbibitional and osmotic swelling. The embryo thus lives in water for years restrained in its swelling by the seed coat against which it must exert a pressure of approximately 100 atmospheres. When the carpel wall is removed, the seed swells rapidly and increases 40 per cent of its air-dry weight in the course of 2 hr. The elongation of the embryo when the seed coat is removed was 30 per cent of its length in 5 hr. (2) The possession of coats which interfere with the absorption of oxygen. The classical example of this type is the seed coats of the cocklebur (*Xanthium*). This character appears in both the upper and lower seeds of the bur but is more marked in the former. It is considered that the germination of many other seeds is greatly influenced by the rate of the diffusion of oxygen through the seed coats. (3) The possession of immature embryos. When some seeds are separated from the parent plant, the young plant in the seed

has not yet reached its full embryonic development. This development is reached after the seed has fallen off, and several weeks or months must elapse before it becomes sufficiently developed to germinate. The seeds of *Ginkgo biloba*, *Gnetum gnemon*, *Erythronium denscanis*, and *Ranunculus ficaria* are some of those whose dormancy is due to an undeveloped embryo. (4) The possession of an embryo which, although to all appearances is mature, must undergo certain changes before it will germinate. Most of the seeds of the *Rosaceae*, including peach, apple, cherry, plum, and hawthorne, are of this type. Before these seeds will germinate they must "after-ripen," as will subsequently be discussed.

B. OVERCOMING DORMANCY

1. Stems, Tubers, and Bulbs.—The principal methods that have been used in breaking the dormant period of these plant parts are (a) the raising of the temperature, (b) the lowering of the temperature, (c) treatment with gases and vapors, (d) immersion in chemical solutions, and (e) desiccation. Howard (1915) found that the most effective treatments for overcoming the dormancy of 65 species of herbaceous perennials with which he worked were freezing, desiccation, and ether vapors. With woody stems, freezing for 8 days followed by treatment with ether caused the quickest growth. Coville (1920) showed that the blueberry and other woody plants which have become dormant will not resume normal growth in the spring unless they have been subjected to chilling. Dormant plants which have not been chilled do not resume growth until long after those which have been exposed to winter weather. It was found by Denny and Stanton (1928) that the vapors of ethylene dichlorid and ethylene chlorhydrin were very effective in breaking the rest period of the lilac, crab apple, flowering almond, *Azalea*, and others. A treatment of 24 to 48 hr. was usually sufficient. The gain in time varied from 2 weeks in the flowering almond to 2 months in the crab apple. Other chemicals which gave favorable results were prophylene chlorhydrin, furfurol, and acetylene tetrachlorid.

The effect of various treatments is apparently limited to that portion of the plant which has been treated. Thus when a branch of blueberry was placed through a hole in the window and exposed to winter weather, it leafed out in the spring, while the portion which remained inside and was unchilled did not do so (Coville, 1920). By applying the various chemical treatments to individual buds of the lilac, Denny and Stanton (1928) showed that dormancy in this plant is not systemic but is localized in the buds. Thus of the pair of buds at the tip of a twig, one could be made to start growth by treating without breaking the dormancy of the other member of the pair.

The treatment of potato tubers for the overcoming of dormancy has received considerable attention. According to Appleman (1918), treat-

ment of the buds with ether or chloroform forces them to open 3 to 6 weeks ahead of normal. Treatments which furnish a better oxygen supply to the tissues also shorten the dormant period. Thus wounding of the tuber and the removal of the skin shorten the dormant period. If the tubers are wrapped in cotton saturated with hydrogen peroxide, the rest period is shortened. The hydrogen peroxide is absorbed by the tuber, and oxygen is released through the catalase which it contains.

Denny (1926, 1928) tested the value of a large number of chemicals for the hastening of germination in potatoes. The vapors of ethylene chlorhydrin and solutions of sodium and potassium thiocyanate gave excellent results. The treated tubers showed 100 per cent germination and in 2 months the plants were 2 ft. high and tubers were forming, while the check tubers had not yet appeared above the ground. Favorable results were also obtained from trichlorethylene, dichlorethylene, carbon bisulphid, ethylene dichlorid, and ethyl bromid. According to Vacha and Harvey (1927), ethylene also breaks dormancy in the potato.

2. Seeds.—The treatments which have been used to hasten the germination of seeds are scarification, treatment with chemicals, alternation of temperatures, freezing and thawing, storage, and placing under conditions favorable to after-ripening. Dormancy which is due to hard or thickened coats is overcome by scratching or filing the coats or by dissolving them with strong sulphuric acid so that water may be absorbed. The dormancy of hard-coated seeds is also overcome by placing them in the soil to be subjected to freezing and thawing during the winter season. Rose (1915) found that the hard-coated seeds of legumes, lettuce, mustard, okra, and snapdragon could be made to germinate more quickly by being blown against needle points. It was found by Jones (1928) that the seed coats of *Nelumbo lutea* do not absorb water after soaking in water for 18 months at room temperatures but that when the seed coats were broken without injury to the embryo, the seeds quickly germinated. These seeds may be prepared for germination by treatment for 5 hr. with concentrated sulphuric acid, followed by washing in tap water and drying on a screen to eliminate immediate germination. The threshing machine acts as an effective abrasive agent on hard seeds and hastens their germination. Thus certain legume seeds when hulled by hand have as high as 90 per cent of hard seeds which will not immediately germinate, while there are only 20 per cent of such hard seeds when hulled by machine. The longevity of some seeds, however, is lessened by being scarified (Wolfe and Kipps, 1912).

It was found by Harrington (1923) that seeds of redtop, parsnip, celery, orchard grass, blue grass, Bermuda grass, and Johnson grass germinate much better with favorable alternations of temperature than at constant temperatures, the exact alternation depending on the kind of seed. In alternating the temperatures, the upper temperature should be

maintained only a small part of the day, never more than 8 and usually not more than 6 hr., and the change to the lower temperature should be fairly rapid. The best germination of the seeds of Johnson grass was obtained after being subjected to a temperature of 30°C. for 18 to 22 hr. and at 45°C. for 2 to 6 hr. each day. The best results were obtained for parsnip, celery, redtop, and orchard-grass seeds when placed at 20°C. for 16 to 18 hr. and at 30°C. for 6 to 8 hr. Morinaga (1926) reported that alternating temperatures were necessary to germinate the intact seeds of Bermuda grass and *Typha latifolia* but that breaking the seed coats or treating with sulphuric acid allowed germination at constant temperatures.

The supply of oxygen is an important factor in germination, and it is generally considered that the increased germination due to various treatments is in many cases caused by the favorable effect the treatment has upon the diffusion of oxygen through the membranes of the seed. The exact changes in the oxygen relations are, however, not understood. Morinaga (1926) noted that the seeds of cat-tail (*Typha latifolia*), which germinated poorly or not at all in air, germinated promptly when the oxygen supply was decreased by diluting the air with 48 to 80 per cent hydrogen or nitrogen. When 20 per cent oxygen was added to the air, germination was only 1.3 per cent. Some oxygen, however, is necessary for germination, since when all of it is removed the seeds will not germinate. Morinaga also found that Bermuda grass germinates better with a reduced oxygen supply, but the effects are not so marked as in the case of the seeds of *Typha latifolia*. The breaking of the seed coats of *Typha latifolia* removes the necessity of reducing the oxygen supply, and they germinate equally well with from 1 to 90 per cent of full atmospheric oxygen.

Light has an effect upon the germination of certain seeds. Thus Gardner (1921) reported that the seeds of *Rumex crispus*, *Datura stramonium*, and *Phoradendron flavescens* are light sensitive. The germination of the first and last were promoted by light, while that of *Datura stramonium* was hindered by light. It was noted by Morinaga (1926) that light, nitrate, and nitrite with alternating temperatures increased the germination of the seeds of Bermuda grass. The highest germination of the seeds of blue grass was obtained with these three factors in combination. Light was found to be effective in the germination of celery seeds only when unfavorably high temperatures were used.

C. AFTER-RIPENING

The term "after-ripening" refers to the series of chemical or physical changes occurring within the plant or plant parts which bring to a close the dormant period and make growth again possible (Jones, 1920). It is evident that these changes will vary for different plants and for

different treatments, so that no prediction can be made with certainty concerning the changes that will occur. Howard (1915) believed that the specific effect of all rest-period breaking agents on dormant woody tissue is due to the stimulation of enzymes. He thought that the diastatic, proteolytic, fat-splitting, and oxidizing enzymes are stimulated into greater activity by the treatment with the various reagents. He considered that the rest period sets in on account of the inhibition of enzyme activity due to the overaccumulation of the products of their action.

In the potato tuber, Appleman (1914, 1916) could observe no changes in the amount of diastase and invertase under normal growing conditions until sprouting had occurred. The protein, lipoid and organic extractives, and the inorganic phosphorus also remained constant until that time. The abrupt changes in regard to these substances was concurrent with sprouting. The juices from the tubers at the end of the rest period caused a greater acceleration of the oxidation of pyrogallol than the juice from new immature tubers of the same varieties. It was observed by Appleman and Miller (1926) that the ripening and maturing process in immature potatoes may continue during storage, so that by the end of the rest period, immature potatoes large enough for seed have practically the same percentage composition and respiratory response as potatoes allowed to mature on the vine provided that they are stored under the same conditions.

The stimulating effect produced by chilling in overcoming dormancy in woody plants is believed by Coville (1920) to be intimately associated with the transformation of starch into sugar, since tests for starch and sugar showed a decrease of starch and an increase of sugar as winter progressed. The theory offered in explanation of this is that the starch grains are at first separated by living cell membranes from the diastatic enzymes but that when the plant is chilled, the vital activity of these membranes is weakened, the enzymes are allowed to pass through, and the starch is changed to sugar. This change is regarded as the mechanism for creating high osmotic pressures to start the plants into growth.

The changes accompanying after-ripening have been especially studied in seeds. The period of after-ripening may be greatly shortened by proper treatment; thus the seeds of the hawthorne (*Crataegus mollis*) has a latent period of 1 year or more. Davis and Rose (1912) showed that if these seeds are removed from the carpels and kept very moist at a temperature of 5 to 6°C., the latent period may be shortened to 2.5 to 3 months. If the testas are removed and the embryo treated as mentioned, the dormant period may be reduced to 30 days. Eckerson (1913) studied microchemically the changes accompanying the after-ripening of these seeds and observed that the first initial change in the embryo was an increase in acidity which was correlated with an increased

water-holding capacity and an increase in the activity of catalase and peroxidase. Near the end of the after-ripening period there was a sudden increase in acidity and in the water content, while oxidase made its first appearance. The enzymes, acidity, and water absorption all increased in amount until the hypocotyl was 3 to 5 cm. in length. At that time the fats decreased and sugar appeared. Eckerson found that after-ripening in this case could be greatly shortened by treating the embryos with dilute hydrochloric, acetic, or butyric acid. The water-holding capacity, acidity, and amount of peroxidase increased much more rapidly and oxidase much earlier in the embryos thus treated than in the untreated ones. This increase in acidity, water-holding capacity, and catalase and oxidase activity during after-ripening was also observed by Rose (1919) in the seeds of *Tilia* and by Jones (1920) in the seeds of the sugar maple.

Pack (1921) in the study of the embryo of *Juniperus* has reported the most extensive data in regard to the changes accompanying after-ripening. The following changes were observed: (1) rapid or complete imbibition followed by a steady slow decrease in water content until germination; (2) increased hydrogen-ion concentration in the embryo and an increment of titratable acid; (3) a steady and enormous increase in the degree of dispersion of stored fats; (4) a decrease in the amount of stored fat and protein with an increase of sugar; (5) the translocation of food in the form of fat or fatty acids from the endosperm to the embryo; (6) a sevenfold increase in the amino acid content; (7) an increase of the soluble proteins with a marked hydrolysis of the stored proteins; (8) a slight increase in the respiratory rate; (9) an increase in the respiratory quotient; (10) a decrease in intramolecular respiration; (11) a twofold increase in catalase activity; (12) a slight growth of the embryo; and (13) a rise in the vigor of the seeds as indicated by their resistance to fungal attacks. The changes which accompany after-ripening in the seeds of *Juniperus* are thus represented by the accumulation of cell-building materials and enzymes. This accumulation of plastic cell materials coupled with minimum respiration and combustion probably forces the dormant organs to activity. If these changes are not the basis of the after-ripening process, they accompany it.

The artificial ripening of fruits and vegetables might well be mentioned under this topic. The artificial ripening and coloring of fruits has apparently been practiced for a long time, but during the past 20 years renewed interest has been taken in this problem and methods have been devised for artificial ripening on a large scale of citrus fruits, bananas, dates, persimmons, pineapples, cantaloupes, tomatoes, celery, and others. The first method consisted in placing kerosene stoves in the car or bin, and it was thought for some time that heat was the effective agent in the process. Later, however, it was found that the gases generated by the stoves were effective when distributed by pipes among the fruits and

vegetables to be treated. Denny (1924) determined that the change in color in lemons was due to some unsaturated hydrocarbon compound. He tried ethylene and found that the coloring was very effectively and quickly done. Ethylene is now extensively employed in the ripening process. According to Harvey (1928), it has distinct advantages over the older methods of ripening. The time is shorter; there is less chance for spoiling, since a lower temperature is maintained; and a better color and flavor result. The best temperature for treatment is 65 to 70°F. and the concentration 1 cu. ft. of gas to 1,000 cu. ft. of air. The time of treatment varies, but 48 hr. is generally sufficient to ripen the greenest fruits.

Harvey considers that the effect of the ethylene is to activate the enzymes which digest starch to sugar and oxidize acids and tannins. He found that the treated stalks of celery increased their sugar content 20 to 30 per cent over the checks. Increases in the sugar content were also observed in treated tomatoes and bananas. Regeimbal and Harvey (1927) noted that treated pineapples were sweeter and the activity of the proteolytic enzymes more marked than in the controls. It was demonstrated by Babb (1928) that the blanching of celery with ethylene does not affect its vitamin-B content. Other investigators, including Chace and Church (1927) and Hibbard (1930), however, could not observe an increased carbohydrate content in the fruits and vegetables treated with ethylene. Harvey (1928) suggests that the strength of the gas used in the treatment might have its influence upon the changes in the sugar content.

The changes which fruits undergo in their natural ripening on the tree or in storage is of great interest, but a consideration of this subject belongs to horticulture rather than to plant physiology, so it will not be discussed in this text.

VIII. FACTORS AFFECTING GROWTH OF PLANTS

According to Reed (1919), growth may be considered a function of two variables. The first is the genetic constitution of the individual, and the second is the resultant of all those factors which make up what is commonly called the "environment" of the organism. The factors of the first group are essentially internal, while those of the second are essentially external.

A. INTERNAL FACTORS

In the fertilized egg there are certain genetic tendencies which when expressed later during the life of the growing plant tend to produce under any set of external conditions a certain definite form of growth (Hanna, 1925). Thus a plant of a dwarf variety, although it may be made to vary

slightly in its size and composition by its environment, cannot be made to attain any considerable size by any known cultural methods. The effect of inherent factors on growth is also illustrated by the similar growth rates of green and albino corn seedlings which were observed by Kempton (1924). That sister plants differing so greatly in a major physiological characteristic should have such similar growth rates is a very striking fact. This behavior of growth of these two types of plants is believed to be controlled by inherent factors which are not associated with chlorophyll and photosynthesis.

Some of the conditions which are classified as internal factors other than the inherent nature of the protoplasm are the concentration of the cell sap, the number and size of the growing points, and the accessibility of manufactured food. Although these factors are classified as internal, they may be altered to a marked degree by the external environment. The growth rate of a plant is thus a function of the internal factors which at present are indefinitely defined and the various conditions of the external environment. The external conditions merely accelerate or retard the manner in which the internal factors tend to express themselves (Briggs, 1928; Gregory, 1928). Changes of environment thus need not always have the same effect on the rate of growth. Even though two organisms have the same rate of growth under a given set of conditions, the internal conditions in the two cases may be different and may be differently affected by the changes in the environment.

In a discussion of the influence of internal factors upon growth, the effect of the size of the seed upon plant production could well be considered. The size of the seed, although governed by genetic tendencies, is influenced to some degree by its position on the parent plant and by the general environmental conditions. The reports of the experiments on the effect of the size of the seed upon the vigor and productivity of the plants derived from them are conflicting. This is apparently due to the fact that the comparative results vary greatly with the manner of testing (Kiesselbach, 1924). Kidd and West (1918) and Rotunno (1924) in reviewing the literature on the subject found that the evidence was in favor of the conclusion that larger seeds give rise to more vigorous plants and a better yield. Rotunno in his experiments with small, medium, and large seeds of the radish found that the percentage germination of all three sizes of seeds average the same within the limits of error. The medium seeds averaged the heaviest roots and produced with but one exception the highest percentage of salable roots.

Rudolfs (1923) working with bean seedlings from large and small seeds in the dark found that those from large seeds showed the better growth and that temperature acting as an accelerating factor increased this advantage. Thus at 10°C. large and small seeds required 9.8 days to attain a growth of 140 mm. At 15° the large seeds required 7.8 days

and small seeds 8.8 days. At 20° the large seeds required only 3.1 days, while the small seeds required 8.5 days. In the case of the large seeds a normal temperature coefficient for growth was shown, while in the case of the small seeds the temperature coefficient was abnormally small. This seems to suggest that the amount of food stored in the seeds is of major importance for early growth.

Kiesselbach (1924) in reviewing the literature concerning the yields from seed grades of cereal crops summarized the published data as follows: (1) When the space planting was such as to permit maximum development, the individual plant grain yield was 19 per cent less for the small than for the large seed. This difference is apparently due to the immediate advantage of a greater reserve food supply in the larger seed which results in a more vigorous initial growth.

(2) When planted in equal number at a rate optimum for the large seeds, the small seeds yielded 11 per cent less grain per acre than the large. (3) When planted in equal weights at a rate optimum for the large seed, the small seed yielded 3 per cent less and the unselected seed 2 per cent more per acre than the large seed. The relatively low yield of plants from small seeds was largely overcome by planting a greater number of seeds. The results of experiments by Kiesselbach with winter and spring wheats and oats are very comparable to the results reported above, and he concluded that there is no material or practical gain in the grain yield under farm conditions from the practice of grading small grain seed provided that it is free from inert matter.

B. EXTERNAL FACTORS

Some of the external factors which may influence growth are temperature, light, moisture, electricity, and the amount and composition of the materials in the soil.

1. Temperature.—It has long been known that the growth of plants is closely correlated with temperature, since the rising temperature of the environment is attended within certain limits by an increased rate of growth.

a. Growth Curve in Relation to Temperature.—In general, the growth curve in relation to temperature shows three cardinal points: the minimum, the lowest temperature at which growth is exhibited; the optimum, the temperature at which growth is the greatest; and the maximum, the highest temperature at which growth will occur. The position of these three points, especially the optimum temperature, has varied rather widely in the reports of different investigators. Some of these differences may be attributed to the fact that the growth rate varies for different plants, for the different organs, and for different ages of the same plant or plant part (Newcombe, 1923). Thus for a 12-hr. period the optimum

temperature for the growth of the coleoptile for oats was 30°, for bluegrass 27°, and for *Sorghum vulgare* 31°C. It has also been shown that the length of the time of exposure is an important factor in determining the position of the optimum, minimum, and maximum temperatures for growth.

Lehenbauer (1914) in the case of corn seedlings found that the optimum temperature for growth for a 12-hr. period was 32°C. but that this was not the optimum when the length of the period of exposure was altered. At temperatures above 31°C. the initial rate of growth was not maintained and there was a marked falling off of this rate during prolonged periods of exposure. Similar observations were made by Leitch (1916) in the growth of *Pisum sativum*. The minimum temperature for growth in this plant was -2°, the maximum 44.5°, and the optimum 28 to 30°C. In this instance, the relation of growth to temperature could be expressed as a uniform curve from -2 to 29°C., the curve showing a very close resemblance to that of respiration. Above 29°C., however, for each higher temperature a different curve had to be constructed to express the rate of growth in successive time intervals. This falling off of the growth rate with time is similar to the decrease in rate of enzyme action and photosynthesis under the influence of high temperatures during prolonged periods.

No definition of optimum temperature in regard to growth is thus of value unless it involves a consideration of time. The optimum temperature for growth has been defined by some as the highest temperature which will allow growth for some specified time period without decrease in rate. Lehenbauer believed it should be defined as the temperature which for a specified time period of exposure produces the greatest growth. He observed in corn seedlings that when the experiments were made over a 3-hr. period, the optimum temperature was 29°C. If the observations were over a 6-hr. period, the optimum temperature was 30°; and if the periods were from 9 to 27 hr., the optimum was 32°C. Above 27 hr. the optimum shifted to 31°C.

A definition of the maximum temperature for growth must also involve a consideration of time. The maximum temperature might thus be defined as the highest temperature at which growth ceases after a specific time exposure. With corn, Lehenbauer noted that a temperature of 40°C. allowed growth in all the plants tested for a period of at least 21 hours. With a temperature of 41°C., five of the six plants exhibited no growth after 15 hr., while the other plant ceased to grow after 18 hr. At 42°C., three plants ceased to grow after 15 hr. and three after 18 hr. At 43°C. three grew no more after 9 hr., two ceased to grow after 12 hr., and the sixth stopped growth after 15 hr. It may thus be stated that 43°C. is the maximum temperature for growth of these seedlings for an exposure period of 15 hr., and 42°C. for an 18-hr. period. It was observed that

plants kept at 41 to 43°C. for 6 hr. after growth had ceased were not killed, since when the temperature was gradually lowered growth was again resumed.

MacDougal (1917) noted that a retardation in the growth of wheat and corn seedlings occurred at more than one place in the temperature scale and at different times of the day. In some instances this was attributed to direct temperature effect, while in others this explanation was not deemed adequate and the cause was attributed to varying imbibition capacity coincident with alternations of acidity or alkalinity.

Since growth is intimately associated with hydration and imbibition, it is of interest to note the effect of temperature upon these processes under different conditions of the medium. Sections of petioles of *Solanum* were placed in distilled water and in 4.2 and 2.6 per cent citric acid at temperatures ranging from 18 to 38°C. The swelling in distilled water was nearly three times as great at the higher temperature, while in the acid solution a retardation took place which limited the total at the higher temperature to something over a half that possible at the lower temperature. The total swelling in the acid at the lower temperature occupied an hour, while at the higher temperature it was a matter of 10 to 15 min. The total imbibitional capacity of the lower temperature was not reached for 8 to 10 hr., while at the higher temperature it was reached under 2 hr. The effect of temperature on growth is thus apparently determined to a marked degree by the chemical reactions of the tissues under observation.

It has been assumed by many in studying the effect of temperature on growth that the process is a unified one or a series of successive reactions. MacDougal (1920) emphasizes the statement that growth is a group or "constellation" of activities and that the rate of one of these dependent on temperature may be the determining one when the particular process forms either the retarding or leading agency. On that account, he asserts that the relation of growth to temperature between 10 to 50°C. cannot be expressed by any simple formula. At times, however, the rates of metabolism, respiration, hydration, diffusion, and other processes may coincide in such a manner as to make possible the application of a simple formula for the effects of temperature within a limited range.

b. Resistance of Plants to Low Temperatures.—The large economic losses caused by the injury or death of plants during the autumn, winter, or spring by low temperatures has stimulated a considerable amount of research to determine the cause of this injury, the characteristics which retard it, methods for its prevention, and to acquire plants which are inherently resistant to the effects of such temperatures. A thorough review of the literature pertaining to the effects of low temperatures on plants may be found in Abbe (1895), Salmon (1917), Rosa (1921),

and West (1924), and the student is referred to these references for detailed information on the subject.

The cause of injury by freezing has been assumed to be due primarily to the withdrawal of water from the cell. Upon freezing, water is usually withdrawn from the cell and freezes in the intercellular spaces. As the temperature falls, more water is frozen on the outer walls and more is drawn from the cell by imbibition. Since the force with which the remaining water is held increases rapidly with the progressive loss of water by virtue of the increasing concentration of the cell sap, the amount of water frozen at each successive degree is smaller and smaller. If plants are warmed slowly in many cases after freezing, the water is withdrawn from the intercellular spaces into the cells, and little injury results. The killing by cold depends apparently in some cases on ice formation rather than on the direct effect of low temperature. The withdrawal of water from the cell by freezing may bring about death by the following causes: (1) the desiccation of the protoplasm; (2) the mechanical injury to the protoplasmic membrane; (3) the precipitation of proteins by salting out due to the greater concentration of salts in the sap or to its increase in acidity as water is withdrawn. It should be noted here that chilling above the freezing point has an injurious effect upon some plants. Thus Sellschop and Salmon (1928) found that an exposure of 24 to 36 hr. at 0.5 to 5°C. was fatal to rice, velvet beans, and cotton, while with the same exposure cowpeas were completely defoliated. Peanuts and Sudan grass exposed to these temperatures for 48 hr. were apparently uninjured at first but died in about 2 weeks. Soybeans, potato, buckwheat, tomatoes, and flax were exceedingly hardy, showing no injury when exposed at these temperatures for 84 to 96 hr.

Since certain varieties of plants are known to be hardy under conditions of low temperature, the question naturally arises as to what characteristics enable them to survive while others perish. Strausbaugh (1921) stated that the dormant condition reached by hardy forms of plums appeared to involve fundamental changes in the colloidal condition of the protoplasm whereby there was a marked retention of water against the force of dehydration. According to Newton (1924), the imbibition pressure of fresh leaves in the winter hardened condition is in most cases directly related to hardiness. The imbibitional pressure of hardened leaves appears to depend on the physical state of the cell colloids of the living tissue, since this property was lost when the tissues were killed. The quantity of hydrophilic colloids contained in the pressed juice was found proportional to winter hardiness. Ackerman (1917) observed a high correlation between the sugar content of the hardened leaves and hardiness. Although the concentration of the cell sap may play some rôle in winter hardiness, it does not always show a relationship in that regard (Salmon and Fleming, 1918). According to Martin (1927),

the hardy wheats are characterized by a low moisture content of the tissues, a high percentage of total solids in the cell sap, a high osmotic concentration of the cell sap, a high percentage of bound water, and a low rate of respiration at low temperature. Zacharowa (1925) in the freezing of roots found a positive correlation between cold resistance and alkaline reaction and a negative correlation between acid reaction and cold resistance. The water content of the soil may exert a marked influence on injury of plants by freezing. Thus Hill and Salmon (1927) noted that plants grown in a dry soil were injured more severely by freezing than similar plants in a wet soil. The specific heat of the water in the wet soil prevents a rapid change in temperature.

Plants in many instances may be made to endure low temperatures without serious injury by hardening. They may be hardened by being exposed to gradually decreasing temperatures, scantily supplied with water, severely pruned, or watered with various salt solutions. Apparently any treatment that checks the growth of the plant increases its resistance to cold. Harvey (1918) reported that cabbage plants became resistant to $\frac{1}{2}$ hr. of freezing at -3°C . by exposure to 3°C . for 5 days. He considered that the principal hardening process in cabbage was to change the proteins to forms less easily precipitated, which was indicated by an increase in the amino acid content. Hardened plants contain a larger amount of bound water than the unhardened ones. The percentage of moisture frozen in hardened cabbage leaves at -3 and -4°C . was only two-thirds of that frozen in tender cabbage. That is, the actual amount of water remaining unfrozen at a given temperature was greater in hardened than in tender leaves, although the total moisture content was less. Martin (1927) states that during the hardening of wheats there is a decrease in the moisture content, an increase in the total solids in the sap, and an increased osmotic pressure and imbibition pressure of colloids as measured by the ability of the tissues to hold the sap against the forces of freezing and pressure. Hardened plants possess a larger amount of hydrophilic colloids, probably pentosans (Hooker, 1920), than the untreated ones. They lose less moisture by transpiration per unit of leaf surface than do tender plants (Rosa, 1921). Weimer (1929) found a correlation between the amount of bound water and cold resistance of hardened and unhardened alfalfa plants but could not show a similar correlation between varieties shown to differ in hardiness.

2. Light.—In addition to its influence on the formation of chlorophyll and the process of photosynthesis, light exerts a formative effect upon plants. When a plant is grown in darkness, striking structural and morphological changes result. It is greatly elongated, the tip of the stem has a characteristic hooked form, and the leaves remain very narrow and scalelike. A plant grown under such conditions and with such an appearance is said to be "etiolated." According to Priestley (1926),

the main morphological and structural features of etiolation are determined by a redistribution of meristematic growth at the shoot apex which results from the greater difficulty experienced by the meristem in drawing nourishment from the vascular supply, because when grown in the dark the walls between the vascular strands and meristem are rendered relatively impermeable by the retention in them of the protein and fatty substances that form the surface of the protoplast. The preponderance of growth in length over superficial growth in the shoot in etiolated plants suggests that the superficial layers of meristem are making less growth, while new tissues are being added to the stem as the result of the activity of the more deeply situated meristematic cells. Priestley obtained evidence from micro- and macrochemical data which indicated that the fatty substances released from the differentiating cells are only slowly removed from the walls between these protoplasts under conditions of etiolation. This slow removal of fatty substances from the walls is obviously in close correlation with the deep-seated meristematic activities. Trumpf (1924) found that exposing etiolated plants to light for only 1 to 2 min. and then returning them to darkness produced marked changes in the appearance of the plant. The most striking results were the marked expansion of the leaf lamina and the disappearance of the plumular hook. Priestley (1925) by the exposure to light of the etiolated plants of *Vicia faba* and *Pisum sativum* produced the changes observed by Trumpf and also greatly shortened the stems so that the etiolated plants had much the same appearance as normal ones except that they lacked the green color. It appears that the light action in these cases is photocatalytic.

a. *Rate of Growth in Light and Darkness.*—If stem elongation is taken as the measure of growth, it will be found that in most instances the rate of growth during the night will exceed that during the day provided that the temperature does not fall too low during the night. Thus Omaston (1918) noted that the increase in height of the bamboo was 9.65 ft. in 14 days of which 3.7 ft. occurred by day and 5.95 ft. by night. Porterfield (1928) reported that the ratio of the night growth of bamboo to that of daylight was 1.8 to 2.8 as reported by investigators in Java, Ceylon, and India. In Algiers, however, the growth of this plant was greater during the day than during the night. Porterfield found the ratio of day growth to night growth to be 1.6. Brown and Trelease (1918) found that the shoots of *Cestrum nocturnum*, which is one of the most rapidly growing plants around Manila, P. I., wilted during the day and decreased in length but that later in the afternoon they returned to their original length and increased it during the night. Prescott (1921), according to Hanna (1925), found that the growth rate of corn in Egypt as measured by increase in height showed two maxima during the 24 hr., one a short time after sunrise and the other in the late afternoon about sunset. The total

growth, however, during the 12 hr. of night from 8 p.m. to 8 a.m. was generally greater than that during the remaining 12 hr. of the daytime. Miller (1925) observed at Manhattan, Kans., that corn plants which were about 4 ft. high increased in height 6 cm. from 7 a.m. to 7 p.m. and 8 cm. from 7 p.m. to 7 a.m.

Mason (1925) reported that in the date palm, normal growth, which is manifest by the pushing up of the leaves from the growth center, is made chiefly in the time between sunset and sunrise but also at a reduced rate in the daytime when direct sunlight is cut off by the clouds. In full sunlight elongation of the date palm ceases entirely. Leaf growth in this plant, however, may be induced in darkness obtained by enclosing the plant in a dark chamber at any hour of the day. Partial growth may also be obtained by screening the plant from direct sunlight, exposing it to reflected light, or placing it with a north exposure.

The question arises as to what is the cause of the greater elongation of stems during the night. In many cases it is apparently due to a better water supply for growth. The demands for water by transpiration are so great during the day that there is not a sufficient amount available in the growing regions for the maximum elongation rate of the cells. Brown and Trelease (1918) believed that the absence of growth and even shrinkage of *Cestrum nocturnum* during the day is connected with excessive transpiration. This plant grows better when exposed to the sun than it does in the shade. During the daytime a sufficient amount of water is apparently available in the leaf for photosynthesis and the plant accumulates food to be used in elongation at night. Mason (1925) believed that in the desert it is the action of the rays of a wave length of $570\mu\mu$ in the yellow to $405\mu\mu$ in the violet and probably, also, the ultra-violet rays that inhibit the growth of the palm leaf. In the absence of direct sunlight, the growth of these leaves was apparently synchronous with the closing of the stomata, the checking of transpiration, and increased turgescence in the meristematic tissue. In some succulents the rate of growth varies during the day and night according to the acidity of the tissue. Thus, according to Long (1915), MacDougal noted in *Opuntia Blakeana* that the growth increase in diffuse light was 6.9 per cent, while in bright light it was 12.4 per cent. In the daylight in this instance the acidity decreased, while at night acids were accumulated.

Increased rate of growth is not always due to an increase in the osmotic pressure, since Borowikow (1912) has found in the sunflower that the most rapidly growing seedling is not always the most turgescient one. Vogt (1915) in observations on the growth of the coleoptile of barley obtained evidence that the greater growth in darkness is due largely to the stimulating effect of the previous illumination. He believed that a knowledge of the effects of light on the hydration of

colloids will be necessary to explain the behavior of growth in light and darkness.

b. Different Rays.—Schanz (1919) mentions the fact that in Holland many growers prefer crude glass to regular window glass for forcing. The former cuts out more of all rays than the latter and is especially effective in screening out the ultra-violet. On this account, Schanz carried on some experiments to determine the effect of the different rays of the spectrum upon plant growth. He states that cucumber, *Fuchsia*, *Begonia*, beet, and potato became taller the more the short rays of light were eliminated. The maximum height was obtained under red light and the minimum under the blue-violet light. He concluded, in general, that light of short wave lengths, particularly the ultra-violet was, detrimental to the growth of plants and recommended the use of glass for greenhouses which eliminates these rays. He believed also that the ultra-violet rays have an important relation to the development of anthocyanin in the epidermal layer, since this pigment failed to develop in red-leaved lettuce and other plants when these rays were excluded.

When plants were grown in daylight from which all wave lengths shorter than $529\mu\mu$ were eliminated, Popp (1926) found that they developed the following characteristics as compared with plants grown in the entire spectrum of daylight: a greater final height in soybeans, tomatoes, and *Coleus* but a decided decrease in height in sunflowers, petunia, buckwheat, and Sudan grass. There was a considerable decrease in the thickness of stems and a reduction in the number of branches and side shoots. There was a good development of chlorophyll but a reduction in the amount of anthocyanin of the leaves and flowers. The number of flowers was reduced and there was a delay in their time of appearance. There was also a very weak development of seeds, fruits, and general storage organs. The decrease in starch and total carbohydrates was considerable, but usually there was an increase in total nitrogen. When all wave lengths shorter than $472\mu\mu$ were removed, the same effects were produced but to a somewhat lesser degree. When only ultra-violet rays were eliminated, none of the foregoing results was obtained with any of the plants used, although there was a small increase in the length of stems in all the plants except buckwheat. In general, there was very little difference between plants that received all the rays of the spectrum of daylight and those from which all ultra-violet rays were eliminated. The results of the work of Popp indicate that while the ultra-violet rays are not indispensable, the blue-violet end of the spectrum is necessary for the normal vigorous growth of plants. This conclusion is substantiated by the work of Shirley (1928), who grew plants under five different light qualities with three intensities and found that the plants produced more dry matter per unit of light intensity under the complete solar spectrum than under any portion of it.

Eltinge (1928) found that raying with an unscreened quartz mercury light caused injury to all the plants used. This ultra-violet radiation had little if any effect upon the decomposition of the chlorophyll or upon the hydrogen-ion concentration of the plants. Raying with a lamp screened by Vita glass, which allowed the passage of the rays 578 to 289 $\mu\mu$, was beneficial to some plants, while it produced little visible effects in others. Raying with a lamp screened by quartzlite glass (578 to 313 $\mu\mu$) injured none and benefited many of the plants. Eltinge believed that her results emphasize the fact that each plant has its own ultra-violet requirement for its best growth which can be determined only by experiment. Tincker (1930), in using various types of commercial glass which allow the ultra-violet rays to pass, found that a heavier crop of radishes and carrots was produced under them than under ordinary glass but that the rate of growth of lettuce was not affected.

The effect of X-rays upon plants might well be mentioned under this topic. Johnson (1926) found that the catalase activity was depressed in the young seedlings of *Helianthus annuus* whose seeds had been exposed to medium doses of X-rays but that in older seedlings little change could be noted. When stunted growth accompanied heavy irradiation, the rate of respiration was decreased. Cells from the root tip of seedlings whose growth had been inhibited by irradiation showed elongation, large vacuoles, and the absence of a nucleus. Potatoes irradiated before sprouting with a slight dose of X-rays produced 27 per cent more tubers per hill, but the average weight was 18 per cent less than the controls, thus making the average total weight per hill practically the same (Johnson, 1928). When the seeds of sunflower were irradiated with medium doses of X-rays, an inhibiting effect proportional to the dosage was noted in the growth of the seedlings for about 3 weeks. After that, however, the plants grew rapidly until at maturity, when there was little difference in height or time of blossoming between the controls and the plants from treated seeds. Williams (1923, 1925) noted that the cells of *Saxifraga umbrosa* and *Elodea* after a short exposure to the β - and γ -rays from radium showed an increase in the rate of circulation of the protoplasm and an increase in the permeability of the protoplasmic membrane as indicated by the exosmosis of solutes. Large doses produced shrinkage and vacuolation effects which were irreversible. Extensive experiments have been conducted by Stadler (1930) on the genetic effect of X-rays on barley and corn. A discussion of these effects, however, belongs primarily to the province of genetics and will not be considered here.

The effect of polarized light on growth was noted by Macht (1926, 1928). Plants of *Lupinus albus* exposed to polarized light grew much better than did the controls. The growth of wheat and sunflowers was also hastened, although not to such a marked degree. It was also found,

as mentioned in Chap. XI, that polarized light hastened the conversion of starch to sugar.

c. Intensity of Light.—Under artificial light, Harvey (1922) found that some plants grew and bloomed over a wide range of light intensities, while others bloomed only in a very limited range. Thus, with the light intensity measured in foot candles, the range of corn was 500 to 3,000; tobacco, 800 to 10,000; *Amaranthus retroflexus*, 500 to 10,000; squash, 500 to 750; and wheat, 650 to 800. Popp (1926) grew four varieties of soybeans for 7 days at a temperature of 19 to 23°C. under light intensities of 4,285, 1,536, 560, 390, 250, and 26 ft. cp., respectively. He observed that the lower the light intensity the more rapid was the rate of stem elongation during the period of initial growth. The greatest general height was attained by plants under a light intensity averaging 560 ft. cp. and the lowest under 26 ft. cp. The thickness of the stem was directly proportional to the light intensity and there was a gradual decrease in vigor with decreasing light intensity. Adams (1924) believed that light of lower intensity but more prolonged will produce the same result as light of higher intensity but of shorter duration. Observations as regards height, weight, and time of flowering on numerous plants grown in the greenhouse and in the open showed that the results were as satisfactory under 2 hr. exposure to light at midday as under 3 hr. exposure during the morning and afternoon.

d. Length of Exposure to Light.—Although it has been known for a long time that the duration of exposure to light markedly effects the growth of plants, it is only within the past decade that the subject has been extensively investigated. The striking results obtained by Garner and Allard (1920) in their extensive investigations on the effect of the relative length of day and night upon growth and reproduction in plants created a great amount of interest and stimulated research in this field. These investigators suggest the term "photoperiodism" to designate the response of organisms to the relative length of day and night and "photo-period," to designate the favorable length of day for each organism.

In general, it may be stated that the plants which are exposed longest to daylight attain the greatest production of dry matter. This subject has been especially studied by Adams (1920 to 1925). In latitude 45.5° N. during June and July, plants of corn, wheat, soybean, white mustard, wax bean, flax, tomato, and sunflower were darkened from 1 to 5 hr. each day. In almost all cases, the plants exposed longest to the action of light gave the greatest average weight and the greatest average height. Wheat, rye, flax, hemp, soybeans, tomatoes, buckwheat, and sunflowers were grown in darkness, in different periods of daylight ranging from 3 to 15 hr., and in artificial light in addition to full daylight, bringing the total exposure of light up to 18 to 20 hr. In the case of the tomato, soybean, buckwheat, and hemp, there appears to be an upper limit to

the amount of light which a plant can utilize and above which it makes no additional growth.

1. *Reproduction.*—The work of Garner and Allard (1920, 1923) and of Tincker (1925, 1928, 1929) showed that plants, in their behavior toward the length of light exposure, arrange themselves into three general groups according to the effect of the treatment upon the time of flowering: (a) those species and varieties which are apparently little affected in their time of blooming by the duration of the exposure to light; (b) those plants which are caused to flower by the action of short days. Such plants are commonly called "short-day" plants; (c) those plants which are forced into flowering through the action of long days. These have been designated "long-day" plants.

Harvey (1922) grew a large number of plants under continuous artificial illumination with electric lights. These lights were mounted with ordinary enameled reflectors at a distance of 5 ft. from the plants and gave about 457 lumens per square foot. Under these conditions, wheat, oats, barley, rye, flax, buckwheat, white clover, peas, beans, and a number of weeds grew from seed to maturity and set good seed. Potatoes, tomatoes, red and alsike clover, and squash bloomed but set no seed. Adams (1925) grew the castor bean from seed to seed under artificial light, while Tjebbes and Uphoff (1920) and Hostermann (1922) obtained increased yields from greenhouse crops by the use of artificial light. Harrington (1926) grew cereals in the greenhouse during the winter through the use of artificial light to supplement the natural daylight. By this means he was able to grow to maturity three successive generations of wheat in one year.

Some of the plants which have been found to require short days to produce flowering are Maryland Mammoth tobacco, Biloxi soybeans, ragweed, *Aster linariifolius*, *Phaseolus vulgaris*, *Phaseolus multiflorus*, *Cosmos*, and *Chrysanthemum*. Some of those which require a long day for the production of flowers are Mandarin soybeans, *Hibiscus*, goldenrod, climbing hempweed, timothy, radish, and perennial rye grass. The plants which are placed in the short-day group are those which can bloom only under a daily light period of 12 hr. or less, while those which are placed in the long-day group require a length of daylight of more than 12 hr. (Kellerman, 1926).

The influence of the relative length of day upon the date of flowering can be illustrated by considering certain varieties of soybeans. If the Biloxi variety is planted about the middle of April in the latitude of Washington, D. C., approximately 125 days elapse between germination and the time of blooming. If, however, these plants are exposed to daylight for only 7 to 12 hr. the time elapsing between germination and blooming is only 28 days. The fact that certain varieties of plants are early or late maturing is apparently connected with the different responses

of these plants to the relative length of day and night. Thus for plantings in the field through the month of May, the average number of days from germination to blossoming for the Mandarin, Peking, Tokyo, and Biloxi varieties of soybeans was approximately 27, 56, 70, and 105 days, respectively. When these plants are placed in the daylight for only 7 to 12 hr. daily, they all bloom in approximately 28 days and thus all become early maturing. On the other hand, the late-maturing varieties may be maintained in the active vegetative condition for a prolonged period of time by continued exposure to a relatively long daily period of illumination.

Supplementing the daily period of sunlight with electric lights of approximately one-thousandth of the intensity of sunlight turned on at sunset and turned off at midnight is sufficient to bring about the flowering response of long-day plants. Under such conditions, short-day plants continue vigorous vegetative growth and are unable to bloom.

The work of Gilbert (1926) and Adams (1925) suggests that the phenomena of response to relative length of day may be influenced by the temperature and humidity conditions to which the plant may be subjected during the growth period. Gilbert observed in soybeans and cotton that there was a definite retardation of flowering with the lower temperatures and higher humidity, while *Cosmos* flowered much earlier and more normally under lower temperatures and higher humidity. *Salvia* and buckwheat exhibited no reaction to temperature and humidity conditions. In the case of *Xanthium pennsylvanicum* grown under known conditions of temperature and relative daylight, it was found that temperature was the determining factor in influencing the time of flower primordia formation but was associated with the response to the length of day. Adams (1925) observed in numerous experiments carried out at different times of the year that a large number of plants showed as good growth under an average exposure to daylight of 569 hr. at a mean temperature of 60.8°F. as they did with an average exposure to light of 500 hr. at a temperature of 68.2°F. The temperature must always be taken into account in experiments dealing with the relation of plants to light.

The work of Schaffner (1923, 1927) on the influence of the relative length of day upon the reversal of sex in hemp and corn should be noted here. When hemp is planted in the latitude of Colorado or Ohio between May 10 and Aug. 10 in the greenhouse or in the open it develops the typical dioecious state. If, however, the planting is done in the greenhouse between Aug. 20 and May 1, sex reversal is almost sure to take place in inverse proportion to the length of daylight and the time of planting and the subsequent period of growth. This reversal of the sexual state is in both directions. In the staminate plants the reversal is from maleness to femaleness and in the carpellate plants from female-

ness to maleness. In corn planted on Nov. 1 in the greenhouse all individuals showed some degree of female expression in the tassel, whereas if planted in the spring or summer, they showed only purely staminate tassels.

2. *Development of Storage Organs.*—The duration of the daily illumination period not only influences the quantity of photosynthetic material that is formed but also may determine the use which the plant can make of it. The changes in the character of vegetative growth due to the alteration of the period of light exposure are frequently as clear and striking as the change from the vegetative to the flower behavior. The Globe spring radish when exposed to a 7-hr. day enlarged its root for at least a year. The Irish potato and the Jerusalem artichoke developed tubers only under relatively short days. Carrots did not produce a bulbous root under a very short day but under a 14-hr. day developed a typical carrot root. In no case did the light period best adapted to the formation of bulbs, tubers, or storage roots coincide with the best daylight period adapted for the upward or top growth of the particular plant under consideration (Kellerman, 1926).

In Porto Rico, McClelland (1928) found that onions were very sensitive to the duration of the daily light period and that different varieties varied in their response. Short days favored leaf growth but inhibited bulb formation for which longer days are necessary. The variety Bermuda white showed itself to be adapted for growing in such latitudes as have a maximum day length only slightly in excess of 13 hr. The Prize Taker and other varieties were found to be wholly unsuited for growing under such day lengths, the plants remaining in the spring-onion stage rather than forming bulbs. Under daily light exposures of a little more than 15 hr., normal bulb formation was rapid for all the varieties tried. The longer exposures favored growth of tops in potatoes, while the shorter exposures favored tuberization.

It was observed by Zimmerman and Hitchcock (1929) that the length of day markedly affects the type of root system formed by dahlia cuttings. The long-day exposure gave rise to a fibrous root system, while short-day illumination resulted in a heavy root storage. Weaver and Himmel (1929) found in investigating both short- and long-day plants that the development of the root system for different exposures was in all cases in direct correlation with the development of tops.

3. *Chemical Changes.*—According to Garner, Bacon, and Allard (1924) the light period influences the acidity relations, the form of carbohydrates present in the plant, and probably the water content of the tissues.

In the case of short-day plants, a relatively long daily illumination period was associated with a progressive increase in the actual acidity, particularly in the regions of the growing points. This increase continued

until the upper portion of the plant became more acid than the lower portion. Exposure to a relatively short daily light period was followed by only a moderate increase until a level was approached at which flowering was initiated. Under the short-day exposure the upper portions of the plant were less acid than the lower portions. After flowering had been initiated, there was a progressive increase in acidity in the vegetative parts of the plant. An abrupt transfer from a long day to a short day caused a sudden and sharp decrease in acidity in the region of the growing point which usually occurred about 3 to 5 days after the transfer had been made. This drop in acidity, which was believed to indicate definite transition from the vegetative to the flowering condition, was only temporary and rapidly rose to the original level.

In the case of *Cosmos* a transfer from a long to a short day resulted in a material increase in reducing sugar in the upper portion of the stem within 48 hr. after the transfer had been made. Two days later this increase in sugar content was found to be in the form of polysaccharides and was accompanied by a slight decrease in the water content. Twelve days later after flowering buds had appeared, the increased carbohydrate was in the form of monosaccharoses, while a considerable increase in the water content had occurred. In the summer radish, the elongation of the stem resulting from an exposure to a long day was associated with an increased content of reducing sugar in the tissues with the maximum concentration in the upper portion of the stem.

Deats (1925) found that the cell-sap concentration in the leaves was greatest in those plants exposed to a long day, while it was more concentrated in the fruit of the tomato which had been exposed to a short day. He suggests that the differences in the relative length of day and night might influence the form of plant development by a change in the nitrogen carbohydrate ratio.

4. *Localization of Response.*—Garner and Allard (1925) found that when two coordinate branches of *Cosmos bipinnatus* were exposed to light for daily periods of different length each branch responded in a characteristic manner to its particular light period, more or less independently of the other. With *Cosmos sulphureus* when the upper portion of the plant was exposed to the full length of the day of summer and the lower portion received only 10 hr. of light daily, the latter promptly flowered, while the former remained vegetative. Knott (1926, 1927) noted that the catalase activity of the apical portion of the stem of spinach decreased as the spinach plant changed from a vegetative to a reproductive type of growth. If elongation ceased and vegetative growth was resumed, the high catalase activity returned. In the bud leaves of the *Cosmos* there was the same marked change in the catalase activity as was found in the stem apex of the spinach. No such change, however, could be noticed in the leaves immediately adjacent to the apex or bud

leaves. Knott believed that these facts suggest a highly localized response in the plant to the changed length of day.

3. Electricity.—During the past decade a number of experiments have been undertaken to study the effect of electricity upon growth and crop production. Blackman, Legg, and Gregory (1923) exposed the coleoptile of the barley seedling for periods of 1 to 3 hr. to an electric discharge from a point charged positively to about 10,000 volts and placed 2 cm. above the coleoptile so that a current of the order of 0.5×10^{-10} amp. passed through it.

The increase in the rate of growth reached 4 per cent of the normal rate in the first hour, and if the current was continued for another 2 hr., the effect went on increasing, so that at the end of the third hour an increase of 5 per cent of the normal occurred. When the current was stopped there was a striking after-effect, the rate of growth continuing to rise for at least 4 hr. after the cessation of the discharge. The after-effect was greater than the direct effect and resulted in the fifth hour in an increase of 12.6 per cent of the actual rate of the control plants. This after-effect as measured by the increase in the rate of growth in the fifth hour from the start of the discharge was greater with the short discharge of 1 hr. than with the longer discharge period of 3 hr.

When the point was negatively charged and a current of the same intensity passed through the seedling for 3 hr., the rate of growth increased during the first hour, but the increase instead of becoming greater with time as with a current in the other direction became less, so that at the end of the third hour the rate was little if at all above the normal. When after 3 hr. the current was stopped, a stimulating after-effect occurred, but not so marked as with the positively charged point. These results were treated statistically by Gregory and Batten (1926) and were found to provide significant evidence of the physiological effect of the discharge.

The significance of electrical discharges on field crops was pointed out by Jorgensen and Priestley (1914) and by Jorgensen and Stiles (1917). The most extensive field work in this regard, however, was performed by Blackman (1924) in experiments with spring-sown oats and barley, winter wheat, and clover. A discharge was given at the rate of 0.5 to 1.0 milliamp. per acre from three insulated wires stretched above the crop at a height of about 7 ft. and charged to a voltage of 40,000 to 80,000. The discharge was usually given for 6 hr. a day in two periods, 3 hr. in the morning and 3 hr. in the afternoon. In the case of the 18 experiments with oats and barley, 14 gave positive results in favor of the electrified plots, while 4 showed decreased yields compared with the controls. The increased yield ranged from 10 to 50 per cent, while none of the negative results was so much as 10 per cent. The beneficial effects on winter wheat and clover, however, were uncertain. Blackman and Legg (1924) ran pot cultures of young cereals concurrently with the above

field experiments. Networks charged to a high voltage were suspended over the plants by insulating supports and so arranged that they could be raised or lowered and thus vary the strength of the current passing to the plant. The plants showed marked sensitiveness to currents of very low intensity, definite increases in dry weight being obtained with currents as low as 1×10^{-10} amp. per plant. The optimum intensity of current appeared to be below 1×10^{-8} amp.

Briggs, Campbell, Heald, and Flint (1926) in electrocultural experiments extending over 8 years at the Arlington Experimental Farms found no well-defined increase in yield due to electrical treatment, as the results obtained were well within the limit of experimental error. Collins, Flint, and McLane (1929) found that treatment with a current intensity of 10^{-9} amp. was slightly positive for corn seedlings under laboratory conditions.

The knowledge concerning the proper conditions under which electrical treatments should be given is very meager, and much more experimental work is needed before any definite statements can be made concerning the effects of electricity on growth and crop production.

The mode of the action of an electrical current in those cases where increased yields have been reported is not known. Blackman (1924) noted that in some cases the treated crops had a deeper green than those of the controls. The effect of the discharge is apparently of the nature of a stimulus, since the additional energy in most of the experiments was less than one-thousandth of the energy which the plant was receiving from the sun. Dixon and Bennett-Clark (1927) found that a moderate electrical current in a tissue caused a fall in electrical resistance which became less and less rapid. After a few minutes the resistance began to rise and reached the normal in about an hour. They suggested that the ability of a current to stimulate a cell is determined by the potential difference across the membrane of the cell.

It should be mentioned here that the atmosphere becomes heavily charged with electricity during the dust storms which occur in the Great Plains area, and it is believed by some that this causes the marked injury to cereals which has been observed after such storms.

Some of the observations concerning electric currents within the plant might well be mentioned here. Waller (1900) and Waller (1924, 1925) reported that when light falls upon a plant tissue, electricity is produced by the tissue under certain conditions. This photoelectric current is of interest on account of the distinct significance which it appears to possess in reference to plant metabolism. It was believed that the nature of the photochemical reactions in the plant may be indicated by this electrical response. This photoelectric response is shown mainly by the green parts of plants and is apparently dependent upon the metabolic activity of the chlorophyll, although it may occur

in the absence of chlorophyll, as shown in the cases of *Hydrangea* petals and in blanched celery. The direction of the current is apparently determined by the kind of leaf and by the conditions to which it is subjected.

Lund (1929) reported that the cells of the onion root, of the leaf of *Bryophyllum*, and of Douglas fir generate electric currents continuously. The orientation of the electric polarities is such that they act in series and parallel and sometimes may be observed to oppose one another's electromotive forces like electric batteries. In the Douglas fir the unstimulated stem and each lateral branch exhibit an electric polarity. The apex is electropositive to the basal parts of the stem, while the unstimulated apex of the main stem is electropositive to the apex of each lateral branch. This positive electric dominance of the main apex corresponds to its dominance in growth. Lund believed that electric currents continually flow along certain circuits in the tree, thus correlating the living parts of the whole tree and making it a definite and continual electrified system.

4. Hydrogen-ion Concentration.—The effects of the hydrogen-ion concentration on the various activities of the plant have been stated in the discussion of these activities in the text, so that little remains to be said in regard to its direct effect upon growth. McCall (1923) emphasized the fact that the intensity of the acidity of the soil in many instances is of greater significance in biochemical processes than is the quantity of acid present. Kurz (1923) reported that the H-ion concentration *per se* was not the main factor in determining the distribution of the species which he considered. Reed and Haas (1924) noted that the injury to walnut seedlings in the absence of calcium was due to the lack of this element rather than to the high concentration of hydroxyl ions. Knudson (1925) states that the H-ion concentration may effect many factors in plants other than the alteration of their growth.

Powers (1927) reported that alfalfa, Hungarian vetch, mint, and alsike clover grew best in a slightly acid medium. The maximum development of alfalfa was secured at P_H 5.6 to 6.0, Hungarian vetch at P_H 5.3, spearmint at P_H 6.0, and alsike at 5.5 to 6.0.

The relation of the H-ion concentration to the growth of the cell is discussed by Pearsall (1925). He suggests that one of the conditions for the development of dividing cells in normal non-growing tissue is the development of a gradient of H-ion concentration such that the protoplasm or its principal proteins can be reduced to an isoelectric condition. It is at this point that the proteins show minimum swelling, minimum osmotic pressure, maximum precipitation, and least viscosity. If the protoplasm and principal proteins were made approximately isoelectric by an alteration in the H-ion concentration, they would tend to lose water to adjacent media of higher osmotic potential, and as a result the condition in the protoplasmic or protein aggregate would favor synthesis.

In stems there is a superficial layer of growing cells next to the cuticle which is usually markedly acid (P_H 3.5 to 4.5), while the ground tissue usually has a P_H value between 5 and 6. When lateral roots develop, they do so outside the xylem with its markedly acid reaction and not opposite the phloem which is relatively alkaline. The surroundings of the dividing cells usually have a reaction of about P_H 4.5 to 5.0 as against the normal tissue reaction of P_H 5.5 to 6.5.

5. Gases.—In 1908 Crocker and Knight found that the flowers of carnation are extremely sensitive to traces of illuminating gas. They observed that concentrations of 1 part in 40,000 parts of air killed the young buds and prevented the opening of those already showing the petals. A concentration of 1 part of gas to 80,000 parts of air caused the closing of the open flowers after 12 hr. exposure. Since 1 part of ethylene to 1,000,000 parts of air prevented the opening of buds and concentrations of 1 part to 2,000,000 caused closure of the flowers after 12 hr. exposure, they concluded that the toxic effect of the illuminating gas was due to the ethylene that it contained. Harvey (1913) found that the castor bean is a very delicate indicator of the presence of ethylene, since it responded by a nastic drooping of 15 to 30° when exposed to as little as 1 part ethylene to 10,000,000 parts of air. Knight and Crocker (1913) showed that tobacco smoke of a concentration of 1,000 ppm. caused a reduction in the rate of elongation of the sweet pea, while 5,000 ppm. completely stopped elongation. They determined that ethylene was the component that thus affected growth and that the sweet pea was a more delicate indicator of the presence of this gas than any chemical test.

Harvey and Rose (1915) believed that ethylene is the most harmful constituent of illuminating gas except in extremely high concentrations of gas when other substances may play a part. Harvey (1915) investigated the changes in the metabolism of the sweet pea which were caused by the action of ethylene. In the treated plants the simple soluble substances increased at the expense of the higher soluble and insoluble forms. Thus the sugars, amino acids, amids, polypeptids, and lipoids increased by 8 per cent while the insoluble substances as proteins, starch, and cellulose correspondingly diminished. The water content of the treated and untreated plants, however, remained the same. The osmotic pressure of the treated plants increased as did also the permeability of the protoplasmic membrane. Doubt (1917) reported that the following plants were found to be well adapted for use in detecting illuminating gas in greenhouses: *Lycopersicum esculentum*, *Salvia splendens*, *Mimosa pudica*, *Ricinus communis*, and *Datura stramonium*. Traces of gas 50 ppm. caused epinastic growth of the petals of all of these plants. This amount of gas is far below the limit of odor. The following plants were not injured by gas unless there was enough present to be detected by

odor: *Caladium esculentum*, *Lupinus perennis*, *Eriobotrya japonica*, *Phoenix canariensis*, and others.

Priestley (1922) suggested that the effect of the injurious components of illuminating gas on the stems and roots of etiolated plants is due to their inhibition of the formation of an unbroken primary endodermis normally present in these structures. The unsaturated hydrocarbons prevent the formation of a functional endodermis by preventing the normal accumulation of unsaturated acids in the region of the future Casparian strip. Woffenden and Priestley (1924) traced the effect of coal gas upon the stem of *Sambucus* to its action upon cork and lenticel formation. When the cork cells are cut off from the phellogen, they are very susceptible to the presence of coal gas. The fatty acids diffusing from the protoplasm fail to remain in and on the walls, so that no suberin lamella can be formed. This is due apparently to the greater mobility of unsaturated fatty acids in the presence of the gaseous unsaturated hydrocarbons present in the coal gas. They believed that coal gas will not be toxic to cork enveloped tissue except in the case of leakage from buried gas mains around the roots.

6. Moisture and Nutrients.—The effects of these two factors upon growth have been discussed in detail under various headings in the preceding chapters and will on that account not be considered here.

Questions

648. From what standpoints may growth be considered? What is the fundamental stage of growth? The evident stage of growth? Formulate a definition for growth.

649. What is the embryonic stage of growth of a plant cell? Where does the formation of new cells occur in a plant? What are the outstanding characteristics of embryonic cells? What peculiarities do their cell walls possess in regard to composition and function?

650. Explain how the first step in growth might be a process of hydration. What factors might influence this process? How might growth occur without the addition of any solid particles?

651. Explain the manner in which the vacuole of a plant cell is formed. In what way does the enlargement of a plant cell differ from that of an animal cell? What is the grand period of growth of a cell? Of an organ?

652. What is the differentiating stage of growth? What is the main function of a differentiated cell? In what regions of the plant is growth localized? How does the rate of growth of a plant cell or of a plant organ progress with time? Give an illustration.

653. How may the rate of growth in plants be expressed? What type of curve results from plotting the rate of growth against time? What is an autocatalytic reaction? Why is growth considered to be of the nature of this type of reaction?

654. Discuss Robertson's formula for the expression of the growth curve of plants. Discuss Blackman's compound interest law of growth. What is the "substance quotient"? The efficiency index? What are some of the facts that should be noted in considering growth formulae?

655. State some of the observations that have been made in regard to the periodic elongation of plant parts and in regard to the periodic rates of cell division. What determines the time at which the maxima and minima rates of these two processes will occur? Give some examples.

656. What evidence is there that vitamins may play a rôle in plant metabolism? Hormones? What evidence is there of growth promoting substances in manures and decayed organic matter?

657. How may the dominance in growth of the apical bud be explained by the action of growth promoting substances? What evidence is there that the potato tuber contains a growth promoting substance? How may growth behavior be explained as a result of the abundance and distribution of nutritive materials?

658. How may the dominance of the growth of the apical bud be explained by the theory of growth inhibiting substances? Describe experiments which show the dominance of the apical buds of the potato tuber. How has the presence of growth inhibiting substances been indicated in the growth of the shoots of pear? In the production of secondary and tertiary roots?

659. What is the dormant or rest period in plants? Name some examples. What factors are instrumental in causing dormancy? Give illustrations.

660. Enumerate the causes of dormancy in seeds and give examples of seeds which are apparently dormant on account of these causes. Classify the methods that have been used to overcome dormancy in plants or plant parts.

661. Discuss in detail the various treatments that have been used to overcome dormancy in stems, tubers, and seeds.

662. What is meant by "after-ripening"? What changes have been observed to occur in stems and seeds during after-ripening? How is the hastening of the ripening of fruits and vegetables brought about? What changes occur in the fruits and vegetables which are thus ripened?

663. What internal factors may affect the rate of growth? What effect does the size of the seed have upon the vigor and production of the plant produced from it? How does this effect vary with the temperature? With the thickness of the stand?

665. Enumerate the external factors that may affect growth. In general how does the growth curve vary with temperature? How does the rate of growth behave with time at the higher temperatures? Why?

666. How would you define the optimum temperature for growth? The maximum temperature? The minimum temperature? Give examples.

667. How is the temperature effect upon the hydration of plant colloids altered by the acidity of the medium. Give an illustration. Why is it difficult to express the relation of growth to temperature by a simple formula?

668. What changes occur in the water relations of a plant cell when the tissues are exposed to freezing temperatures? What reactions may occur in the cell as the result of the withdrawal of water therefrom? What characteristics are especially marked in winter hardy plants? Give examples.

669. Name some plants which are injured by chilling above the freezing point. What is meant by hardening plants? In what ways may this be accomplished? How does hardening affect the physical and chemical properties of the tissues? Give some examples.

670. What is an etiolated plant? How does it differ in its general appearance from a plant grown in the light? In its structure? Why? What evidence is there that light acts as a photocatalyst in growth?

671. How does the rate of elongation of plant stems compare during the day and night? Give three examples. What appear to be some of the reasons for this difference in growth rate?

672. How is the rate of growth affected by the different rays of the spectrum? What effect do ultraviolet rays have upon plant growth? The X-rays? Polarized light?

673. Give some examples to illustrate the effect of light intensity on the growth of plants. What is meant by photoperiodism? Photoperiod? Name some plants that have been grown from seed to seed in continuous artificial light.

674. What are "short-day" plants? "Long-day" plants? Give examples of each type. How is the character of early maturing and late maturing varieties of plants related to photoperiodism? How may this be shown?

675. How does the influence of the length of day affect the reversal of sex in plants? Give examples. How is photoperiodism influenced by temperature and relative humidity? Give examples.

676. How does the length of day affect tuber, bulb, and storage root formation? Give examples. Enumerate the chemical changes which occur when plants are exposed to long and short day periods.

677. Cite experiments to show that the response of plants to differences in light exposure is localized. How does electrical treatment affect plant growth and crop production? Describe some of the experiments that have been conducted to determine the effect of electricity on plant growth. What evidence is there that electric currents exist within the plant?

678. What is the relationship of the H-ion concentration to growth in plant tissues. How is this shown by the difference in acidity of the cells of the growing regions.

679. Discuss the investigations that have been made concerning the effects of illuminating gas on plants. What general changes in chemical composition occur on exposure to gas? How do these gases affect the formation of cork? Why?

Bibliography

- ABBE, C., 1895: Influence of cold on plants,—a resumé, *Expt. Sta. Rec.* **6**: 777-781.
- ABBOTT, O., 1923: Chemical changes at beginning and ending of rest period in apple and peach, *Bot. Gaz.*, **76**: 167-184.
- ACKERMAN, A., 1917: Beiträge zur Kenntniss der Kältresistenz des Winterweizen, *Zeitschr. Pflanzenzucht.*, **5**: 349-359.
- ADAMS, J., 1920: Relation of flax to varying amounts of light, *Bot. Gaz.*, **70**: 153-156.
- , 1923: The effect on certain plants of altering the daily period of light, *Ann. Bot.*, **37**: 72-94.
- , 1924: Does light determine the date of heading out in winter wheat and winter rye? *Amer. Jour. Bot.*, **11**: 535-539.
- , 1924: Duration of light and growth, *Ann. Bot.*, **38**: 510-523.
- , 1924: The effect on tomato, soybean, and other plants of altering the daily period of light, *Amer. Jour. Bot.*, **11**: 229-233.
- , 1925: Some further experiments on the relation of light to growth, *Amer. Jour. Bot.*, **12**: 398-413.
- APPLEMAN, C. O., 1911: Physiological behavior of enzymes and carbohydrate transformations in after-ripening of the potato tuber, *Bot. Gaz.*, **52**: 306-315.
- , 1912: Changes in Irish potatoes during storage, *Md. Agr. Expt. Sta. Bull.* **167**.
- , 1914: Biochemical and physiological study of the rest period in the tubers of *Solanum tuberosum*, *Md. Agr. Expt. Sta. Bull.* **183**.
- , 1916: Biochemical and physiological study of the rest period in the tubers of *Solanum tuberosum*, *Bot. Gaz.*, **61**: 265-294.
- , 1918: Physiological basis for the preparation of potatoes for seed, *Md. State Coll. Agr. Expt. Sta. Bull.* **212**.
- , 1918: Special growth-promoting substances and correlation, *Science*, n.s., **48**: 319-320.

- APPLEMAN, C. O., and E. V. MILLER, 1926: A chemical and physiological study of maturity in potatoes, *Jour. Agr. Res.*, **33**: 569-579.
- ARMSTRONG, H. E., and E. F. ARMSTRONG, 1911: The function of hormones in regulating metabolism, *Ann. Bot.*, **25**: 507-519.
- AUCHTER, E. C., and C. P. HARLEY, 1924: Effect of various lengths of day on development and chemical composition of some horticultural plants, *Amer. Soc. Hort. Sci. Proc.* **21**: 199-214.
- BABB, M. F., 1928: The effect of ethylene upon the vitamin B content of celery, *Science*, n.s., **68**: 231.
- DEBEER, G. R., 1924: "Growth," 120 pp., Edward Arnold & Co., London.
- BLACKMAN, V. H., 1919: The compound interest law and plant growth, *Ann. Bot.*, **33**: 353-360.
- , 1920: The significance of the efficiency index of plant growth, *New Phytol.*, **19**: 97-100.
- , A. T. LEGG, and F. G. GREGORY, 1923: The effect of a direct electric current of very low intensity on the rate of growth of the coleoptile of barley, *Proc. Roy. Soc., B.*, **95**: 214-228.
- , 1924: Field experiments in electroculture, *Jour. Agr. Sci.*, **14**: 240-267.
- and A. T. LEGG, 1924: Pot culture experiments with an electric charge, *Jour. Agri. Sci.*, **14**: 268-287.
- BOROWIKOW, G. A., 1912: Über die Ursachen des Wachstums der Pflanzen, *Biochem. Zeits.*, **48**: 230-246; **50**: 119-128; *Plant World*, **16**: 347-349 (1913).
- BREAZEALE, J. F., 1927: Vitamin-like substances in plant nutrition, *Univ. Ariz. Tech. Bull.* 16.
- BRENCHLEY, W. E., 1919: Some factors in plant competition, *Ann. App. Biol.*, **6**: 142-170.
- , 1920: On the relations between growth and the environmental conditions of temperature and bright sunshine, *Ann. App. Biol.*, **6**: 211-244.
- BRIGGS, G. E., F. KIDD, and C. WEST, 1920: A quantitative analysis of plant growth. I, II, *Ann. App. Biol.*, **7**: 103-123, 202-223.
- , ———, and ———, 1920: Methods in the quantitative analysis of plant growth. A reply to criticism, *Ann. App. Biol.*, **7**: 403-406.
- , 1925: Plant yield and the intensity of external factors.—Mitscherlich's Wirkungsgesetz, *Ann. Bot.*, **39**: 475-502.
- , 1928: A consideration of some attempts to analyse growth curves, *Proc. Roy. Soc., B.*, **102**: 280-285.
- BRIGGS, L. J., A. B. CAMPBELL, R. H. HEALD, and L. H. FLINT, 1926: Electroculture, *U. S. Dept. Agr. Dept. Bull.* 1379.
- BROWN, W. H., and S. F. TRELEASE, 1918: Alternate shrinkage and elongation of growing stems of *Cestrum nocturnum*, *Phil. Jour. Sci., C*, **13**: 353-360.
- CHACE, E. M., and E. G. CHURCH, 1927: Effect of ethylene on the composition and color of fruits, *Jour. Ind. Eng. Chem.*, **19**: 1135-1139.
- CHILD, C. M., and A. W. BELLAMY, 1920: Physiological isolation by low temperature in *Bryophyllum*, *Bot. Gaz.*, **70**: 249-267.
- CLARK, N. A., 1926: Plant growth promoting substances, hydrogen-ion concentration and the reproduction of *Lemna*, *Plant Physiol.*, **1**: 273-279.
- COLLINS, G. N., L. H. FLINT, and J. W. MCLANE, 1929: Electrical stimulation of plant growth, *Jour. Agr. Res.*, **38**: 585-600.
- COPEMAN, P. R., 1928: Autocatalysis and growth, *Ann. App. Biol.*, **15**: 613-622.
- COVILLE, F. V., 1920: The influence of cold in stimulating the growth of plants, *Jour. Agr. Res.*, **20**: 151-160.
- CROCKER, WILLIAM and L. I. KNIGHT, 1908: Effect of illuminating gas and ethylene upon flowering carnations, *Bot. Gaz.*, **46**: 259-276.

- CROCKER, WILLIAM and W. E. DAVIS, 1914: Delayed germination in seeds of *Alisma plantago*, *Bot. Gaz.*, **57**: 285-322.
- , 1916: Mechanics of dormancy in seeds, *Amer. Jour. Bot.*, **3**: 99-121.
- DEATS, M. E., 1925: The effect on plants of the increase and decrease of the period of illumination over that of the normal day period, *Amer. Jour. Bot.*, **12**: 384-393.
- DENNY, F. E., 1924: Hastening the coloration of lemons, *Jour. Agr. Res.*, **27**: 757-771.
- , 1926: Hastening the sprouting of dormant potato tubers, *Amer. Jour. Bot.*, **13**: 118-126.
- , 1926: Second report on the use of chemicals for hastening the sprouting of dormant potato tubers, *Amer. Jour. Bot.*, **13**: 386-396.
- , 1928: Chemical treatments for controlling the growth of buds of plants, *Jour. Ind. Eng. Chem.*, **20**: 578-581.
- and E. N. STANTON, 1928: Chemical treatments for shortening the rest period of pot-grown woody plants, *Amer. Jour. Bot.*, **15**: 327-337.
- and ———, 1928: Localization of response of woody tissues to chemical treatments that break the rest period, *Amer. Jour. Bot.*, **15**: 337-344.
- , 1928: The importance of temperature in the use of chemicals for hastening the sprouting of dormant potato tubers, *Amer. Jour. Bot.*, **15**: 395-404.
- , 1929: Role of mother tuber in growth of potato plant, *Bot. Gaz.*, **87**: 157-194.
- DIXON, H. H., and T. A. BENNETT-CLARK, 1927: Response of plant tissue to electric currents, *Notes, Bot. School Trinity Coll. Dublin*, **4**: 33-54.
- DOUBT, S. L., 1917: The response of plants to illuminating gas, *Bot. Gaz.*, **63**: 209-224.
- DUVEL, J., 1905: The vitality of buried seeds, *U. S. Dept. Agr. Bur. Plant. Ind. Bull.* 83.
- EATON, F. M., 1924: Assimilation-respiration balance as related to length of day reactions of soybeans, *Bot. Gaz.*, **77**: 311-321.
- ECKERSON, S. H., 1913: A physiological and chemical study of after-ripening, *Bot. Gaz.*, **55**: 286-299.
- ELTINGE, ETHEL T., 1928: The effect of ultra-violet radiation upon higher plants, *Ann. Mo. Bot. Gard.*, **15**: 169-240.
- EWART, A. J., 1908: On the longevity of seeds, *Proc. Roy. Soc. Victoria*, **21**: 1-210.
- FERNALD, E. I., 1925: The inhibition of bud development as correlated with the osmotic concentration of sap, *Amer. Jour. Bot.*, **12**: 287-305.
- FISHER, R. A., 1920: Some remarks on the methods formulated in a recent article on the quantitative analysis of plant growth, *Ann. App. Biol.*, **7**: 367-372.
- FRIESNER, R. C., 1920: Daily rhythms of elongation and cell division in certain roots, *Amer. Jour. Bot.*, **7**: 380-406.
- GARDNER, W. A., 1921: Effect of light on germination of light-sensitive seeds, *Bot. Gaz.*, **71**: 249-288.
- GARNER, W. W., and H. A. ALLARD, 1920: Effect of the relative length of day and night and other factors of the environment on growth and reproduction in plants, *Jour. Agr. Res.*, **18**: 553-607.
- and ———, 1923: Further studies in photoperiodism, the response of the plant to relative length of day and night, *Jour. Agr. Res.*, **23**: 871-921.
- , C. W. BACON, and H. A. ALLARD, 1924: Photoperiodism in relation to hydrogen-ion concentration of the cell sap and the carbohydrate content of the plant, *Jour. Agr. Res.*, **27**: 119-157.
- and H. A. ALLARD, 1925: Localization of the response in plants to relative length of day and night, *Jour. Agr. Res.*, **31**: 555-567.
- GERICKE, W. F., 1918: Effects of rest and no-rest periods upon growth of *Solanum*, *Bot. Gaz.*, **65**: 344-353.
- , 1924: Growth-inhibiting and growth-stimulating substances, *Bot. Gaz.*, **78**: 440-455.

- GILBERT, B. E., 1926: Interrelation of relative day length and temperature, *Bot. Gaz.*, **81**: 1-25.
- , 1926: The response of certain photoperiodic plants to differing temperature and humidity conditions, *Ann. Bot.*, **40**: 315-321.
- Goss, W. L., 1924: The vitality of buried seeds, *Jour. Agr. Res.*, **29**: 349-362.
- GREGORY, F. G., 1926: The effect of climatic conditions on the growth of barley, *Ann. Bot.*, **40**: 1-27.
- , and L. BATTEN, 1926: A critical statistical study of experimental data on the effect of minute electric currents on the growth rate of the coleoptile of barley, *Proc. Roy. Soc.*, B, **99**: 122-130.
- , 1928: Studies in the energy relations of plants. I, The effect of temperature on the increase in area of leaf surface. II, The effect of temperature on increase in area of leaf surface and in dry weight of *Cucumis sativus*, *Ann. Bot.*, **42**: 469-507.
- , 1928: The analysis of growth curves.—A reply to criticism, *Ann. Bot.*, **42**: 531-541.
- GROVES, J. F., 1917: Temperature and life duration of seeds, *Bot. Gaz.*, **63**: 169-189.
- GUSTAFSON, F. G., 1926: Growth studies on fruits, *Plant Physiol.*, **1**: 265-272.
- , 1927: Growth studies on fruits. An explanation of the shape of the growth curve, *Plant Physiol.*, **2**: 153-161.
- HABERLANDT, G., 1922: Cell-division hormones and their relation to wound repair, fertilization, parthenogenesis, and adventive embryogeny, *Biol. Zentbl.*, **42**: 145-172; *Expt. Sta. Rec.* **49**: 219.
- HACKENBERG, H., 1909: Ueber die Substanzquotienten von *Cannabis sativa* und *Cannabis gigantea*, *Beihfte bot. Centrbl.*, I, **24**: 45-67.
- HANNA, W. F., 1924: Growth of corn and sunflowers in relation to climatic conditions, *Bot. Gaz.*, **78**: 200-215.
- , 1925: The nature of the growth rate in plants, *Sci. Agr.*, **5**: 133-138.
- HARRINGTON, G. T., 1916: Agricultural value of impermeable seeds, *Jour. Agr. Res.*, **6**: 761-796.
- , 1923: Use of alternating temperatures in the germination of seeds, *Jour. Agr. Res.*, **23**: 295-333.
- HARRINGTON, J. B., 1926: Growing wheat and barley hybrids in winter by means of artificial light, *Sci. Agr.*, **7**: 125-130.
- HARVEY, E. M., 1915: Some effects of ethylene on the metabolism of plants, *Bot. Gaz.*, **60**: 193-214.
- , 1913: The castor bean plant and laboratory air, *Bot. Gaz.*, **56**: 439-442.
- , and R. C. ROSE, 1915: The effects of illuminating gas on root systems, *Bot. Gaz.*, **60**: 27-45.
- HARVEY, R. B., 1918: Hardening process in plants and developments from frost injury, *Jour. Agr. Res.*, **15**: 83-113.
- , 1922: Growth of plants in artificial light, *Bot. Gaz.*, **74**: 447-451.
- , 1922: Growth of plants in artificial light from seed to seed, *Science*, n.s., **56**: 366-367.
- , 1928: Artificial ripening of fruits and vegetables, *Univ. Minn. Agr. Expt. Sta. Bull.* **247**.
- , 1928: Ethylene as a ripener of fruits and vegetables, *Science*, n.s., **67**: 421-422.
- HEDRICKS, E., and R. B. HARVEY, 1924: Growth of plants in artificial light. II, Intensities of continuous light required for blooming, *Bot. Gaz.*, **77**: 330-334.
- HIBBARD, R. P., 1930: The physiological effect of ethylene gas upon celery, tomatoes and certain fruits, *Mich. Agr. Expt. Sta. Tech. Bull.* **104**.
- HILL, D. D., and S. C. SALMON, 1927: The resistance of certain varieties of winter wheat to artificially produced low temperatures, *Jour. Agr. Res.*, **35**: 933-939.

- HOOKER, H. D., 1920: Pentosan content in relation to winter hardiness, *Proc. Amer. Soc. Hort. Sci.*, **17**: 204-207.
- , 1925: Plant growth, *Proc. Nat. Acad. Sci.*, **11**: 710-713.
- HOSTERMANN, G., 1922: Kulturversuche mit elektrischen Licht, *Gartenwelt*, **26**: 74-75; *Bot. Abst.*, **11**: 383.
- HOWARD, W. L., 1910: An experimental study of the rest period in plants. The winter rest, *Univ. Mo. Coll. Agr. Expt. Sta. Res. Bull.* 1.
- , 1915: An experimental study of the rest period in plants. The summer rest of bulbs and herbaceous perennials, *Univ. Mo. Coll. Agr. Expt. Sta. Res. Bull.* 15.
- , 1915: An experimental study of the rest period in plants. Pot grown woody plants, *Univ. Mo. Coll. Agr. Expt. Sta. Res. Bull.* 16.
- , 1915: An experimental study of the rest period in plants. Seeds. *Univ. Mo. Coll. Agr. Expt. Sta. Res. Bull.* 17.
- , 1915: An experimental study of the rest period in plants. Physiological changes accompanying breaking of the rest period. *Univ. Mo. Coll. Agr. Expt. Sta. Res. Bull.* 21.
- INAMDAR, R. S., S. B. SINGH, and T. D. PANDE, 1925: The growth of the cotton plant in India. I. The relative growth rates during successive periods of growth and the relation between growth rate and respiratory index throughout the life cycle, *Ann. Bot.*, **39**: 281-311.
- JENSEN, I. J., 1925: Winter wheat studies in Montana with special reference to winter killing, *Jour. Amer. Soc. Agron.*, **17**: 630-631.
- JOHNSON, E. L., 1926: Effect of X-rays upon growth, development, and oxidizing enzymes of *Helianthus annuus*, *Bot. Gaz.*, **82**: 373-403.
- , 1928: Growth and germination of sunflowers as influenced by X-rays, *Amer. Jour. Bot.*, **15**: 65-77.
- , 1928: Tuberization of potatoes increased by X-rays, *Science*, n.s., **68**: 231.
- JONES, J. A., 1920: Physiological study of maple seeds, *Bot. Gaz.*, **69**: 127-152.
- , 1928: Overcoming delayed germination of *Nelumbo lutea*, *Bot. Gaz.*, **85**: 341-344.
- JONES, W. N., 1925: Polarity phenomena in sea kale roots, *Ann. Bot.*, **39**: 359-372.
- JORGENSEN, I., and J. H. PRIESTLEY, 1914: The distribution of the overhead electrical discharge employed in recent agricultural experiments, *Jour. Agr. Sci.*, **6**: 337-349.
- , and W. STILES, 1917: Atmospheric electricity as an environmental factor, *Jour. Ecol.*, **5**: 203-209.
- KARLING, J. S., 1924: A preliminary account of the influence of light and temperature on growth and reproduction in *Chara fragilis*, *Bull. Torrey Bot. Club*, **51**: 469-488.
- KATER, J. M., 1927: A cytological study of dormancy in the seed of *Phaseolus vulgaris*, *Ann. Bot.*, **41**: 629-643.
- KEINHOLTZ, R., 1924: The effect of high temperatures on the germination and subsequent growth of corn, *Philippine Jour. Sci.*, **25**: 311-347.
- KELLERMAN, K. F., 1926: A review of the discovery of photoperiodism: the influence of the length of daily light periods upon the growth of plants, *Quart. Rev. Biol.*, **1**: 85-94.
- KELLCOTT, W. E., 1904: The daily periodicity of cell division and of elongation in the root of *Allium*, *Bull. Torrey Bot. Club*, **31**: 529-550.
- KEMPTON, J. H., 1924: The rate of growth of green and albino maize seedlings. *Jour. Agr. Res.*, **29**: 311-312.
- KIDD, F., and C. WEST, 1918: Physiological pre-determination: The influence of the physiological condition of the seed upon the course of subsequent growth and upon the yield. II, *Rev. Lit.*, Chap. I, "Parental conditions affecting the potentiality" of the seed, *Ann. App. Biol.*, **5**: 112-142.

- KIDD, F., C. WEST, and G. E. BRIGGS, 1920: What is the significance of the efficiency index of plant growth, *New Phytol.*, **19**: 88-96.
- KIESSELBACH, T. A., 1924: Relation of seed size to yield of small grain crops, *Jour. Amer. Soc. Agron.*, **16**: 670-682.
- KNIGHT, L. I., and WILLIAM CROCKER, 1913: Toxicity of smoke, *Bot. Gaz.*, **55**: 337-371.
- KNOTT, J. E., 1926: Further localization of the response in plant tissues to relative length of day and night, *Amer. Soc. Hort. Sci. Proc.*, **23**: 67-70.
- , 1927: Catalase in relation to growth and to other changes in plant tissue, *Cornell Univ. Agr. Expt. Sta. Mem.* 106.
- KNUDSON, LEWIS, 1925: Hydrogen-ion concentration and plant growth, *Jour. Amer. Soc. Agron.*, **17**: 711-716.
- KURZ, HERMAN, 1923: Hydrogen ion concentration in relation to ecological factors, *Bot. Gaz.*, **76**: 1-30.
- LEHENBAUER, P. A., 1914: The growth of maize seedlings in relation to temperature, *Physiol. Res.*, **1**: 247-288.
- LEITCH, I., 1916: Some experiments on the influence of temperature on the rate of growth in *Pisum sativum*, *Ann. Bot.*, **30**: 25-46.
- LOEB, J., 1915: Rules and mechanism of inhibition and correlation in the regeneration of *Bryophyllum calycinum*, *Bot. Gaz.*, **60**: 249-277.
- , 1916: Further experiments on correlation of growth in *Bryophyllum calycinum*, *Bot. Gaz.*, **62**: 293-302.
- , 1916: On the association and possible identity of root forming and geotropic substances or hormones in *Bryophyllum calycinum*, *Science*, n.s., **44**: 210-211.
- , 1916: "The Organism as a Whole," 379 pp., G. P. Putnam's Son, New York.
- , 1917: A quantitative method of ascertaining the mechanism of growth and of inhibition of growth of dormant buds, *Science*, n.s., **45**: 436-439.
- , 1917: Influence of the leaf upon root formation and geotropic curvature in the stem of *Bryophyllum calycinum* and the possibility of a hormone theory of these processes, *Bot. Gaz.*, **63**: 25-51.
- , 1917: The chemical basis of axial polarity in regeneration, *Science*, n.s., **46**: 547-551.
- , 1918: Chemical basis of correlation. I, Production of equal masses of shoots by equal masses of sister leaves in *Bryophyllum calycinum*, *Bot. Gaz.*, **65**: 150-174.
- , 1924: "Regeneration from a physico-chemical view point," 143 pp., McGraw-Hill Book Company, Inc., New York.
- LONG, E. R., 1915: Growth and colloid hydration in cacti, *Bot. Gaz.*, **59**: 491-497.
- LOOMIS, W. E., 1923: Some relations of hardening to transplanting, *Amer. Soc. Hort. Sci. Proc.*, **20**: 206-215.
- , 1927: Temperature and other factors affecting the rest period of potato tubers, *Plant Physiol.*, **2**: 287-302.
- LUND, E. J., 1929: Continuous bioelectric currents; a mechanism for cell correlation, *Amer. Jour. Bot.*, **16**: 846-847 (abst.).
- , 1929: The electric polarity of the Douglas fir and the internal distribution of its electric correlation currents, *Amer. Jour. Bot.*, **16**: 858 (abst.).
- MACDOUGAL, D. T., 1903: The influence of light and darkness upon growth and development, *Mem. N. Y. Bot. Gard.*, **2**: 1-319.
- , 1916: The mechanism and conditions of growth, *Mem. N. Y. Bot. Gard.*, **6**: 5-26.
- and H. A. SPÖEHR, 1917: Growth and imbibition, *Proc. Amer. Phil. Soc.*, **56**: 289-352.
- , 1917: Growth of wheat (*Triticum*) and corn (*Zea*), *Carnegie Inst. Wash. Year Book*, **16**: 85-87.

- MACDOUGAL, D. T., 1917: Rate and course of growth of succulents, *Carnegie Inst. Wash. Year Book*, **16**: 83-85.
- , 1918: Development of conceptions included in growth, *Carnegie Inst. Wash. Year Book*, **17**: 55-57.
- , 1918: The growth mechanism of protoplasm, *Carnegie Inst. Wash. Year Book*, **17**: 57-58.
- , 1918: The nature and course of growth in higher plants, *Carnegie Inst. Wash. Year Book*, **17**: 58-59.
- , 1918: Temperature and the hydration and growth of colloids and of cell masses, *Carnegie Inst. Wash. Year Book*, **17**: 68-70.
- , 1919: Growth in organisms, *Science*, n.s., **49**: 599-605.
- , 1919: Hydration and growth, *Proc. Amer. Phil. Soc.*, **58**: 346-372.
- , 1920: Hydration and growth, *Carnegie Inst. Wash. Pub.* 297.
- , 1920: The physical factors in the growth of the tomato, *Bull. Torrey Bot. Club*, **47**: 261-269.
- , 1921: Growth of trees, *Science*, n.s., **54**: 338.
- , 1921: Growth in trees, *Carnegie Inst. Wash. Pub.* 307.
- , 1921: The distinctive agencies in the growth of the cell, *Soc. Exper. Biol. Med. Proc.*, **19**: 103-110.
- and F. SHREVE, 1924: Growth in trees and massive organs of plants, *Carnegie Inst. Wash. Pub.* 350.
- MACMILLAN, C., 1891: On the growth-periodicity of the potato tuber, *Amer. Nat.*, **25**: 462-469.
- MACHT, D. I., 1926: Concerning the influence of polarized light on the growth of seedlings, *Jour. Gen. Physiol.*, **10**: 41-52.
- , 1928: Effect of polarized light on plants, *Amer. Jour. Bot.*, **15**: 621.
- MARTIN, J. H., 1927: Comparative studies of winter hardiness in wheat, *Jour. Agr. Res.*, **35**: 493-537.
- MASON, S. C., 1925: Partial thermostasy of the growth center of the date palm, *Jour. Agr. Res.*, **31**: 415-455.
- , 1925: The inhibitive effect of direct sunlight on the growth of the date palm, *Jour. Agr. Res.*, **31**: 455-469.
- , 1925: The minimum temperature for growth of the date palm and the absence of a resting period, *Jour. Agr. Res.*, **31**: 401-415.
- MCCALL, A. G., 1923: The influence of acidity itself on plant growth without regard to other factors, *Jour. Amer. Soc. Agron.*, **15**: 290-297.
- MCCLELLAND, T. B., 1928: Studies of the photoperiodism of some economic plants, *Jour. Agr. Res.*, **37**: 603-628.
- MCROSTIE, G. P., 1924: Longevity of alfalfa and clover seeds, *Sci. Agr.*, **4**: 236-238.
- MILLER, E. C., 1925: Unpub. data, *Kans. Agr. Expt. Sta.*
- MORINAGA, T., 1926: Effect of alternating temperatures upon the germination of seed, *Amer. Jour. Bot.*, **13**: 141-159.
- , 1926: The favorable effect of reduced oxygen supply upon the germination of certain seeds, *Amer. Jour. Bot.*, **13**: 159-166.
- MURNEEK, A. E., 1925: Correlation and cyclic growth in plants, *Bot. Gaz.*, **79**: 329-333.
- NEWCOMBE, F. C., 1923: Optimum temperatures for growth of some grass coleoptiles, *Papers, Mich. Acad. Sci. Arts and Letters*, **3**: 203-210.
- NEWTON, R., 1924: Colloidal properties of winter wheat plants in relation to frost resistance, *Jour. Agr. Sci.*, **14**: 178-191.
- , 1924: The nature and practical measurement of frost resistance in winter wheat, *Univ. Alberta Coll. Agr. Res. Bull.* 1.
- NIGHTINGALE, G. T., 1922: Light in relation to the growth and chemical composition of some horticultural plants, *Amer. Soc. Hort. Sci. Proc.*, **19**: 18-29.

- OAKLEY, R. A., and H. L. WESTOVER, 1921: Effect of length of day on seedlings of alfalfa varieties and the possibility of utilizing this as a practical means of identification, *Jour. Agr. Res.*, **21**: 599-607.
- ORGA, I., 1923: Longevity of seed of *Nelumbo nucifera* (Japanese), *Bot. Mag. Tokyo*, **27**: 87-95; *Bot. Abst.* **14**: 899.
- OSMASTON, B. B., 1918: Rate of growth of bamboos, *Indian Forester*, **44**: 52-57; *Expt. Sta. Rec.* **44**: 518-519.
- PACK, D. A., 1921: After-ripening and germination of *Juniperus communis*, *Bot. Gaz.*, **71**: 32-60.
- , 1921: Chemistry of after ripening, germination and seedling development of Juniper seeds, *Bot. Gaz.*, **72**: 139-151.
- PALLADIN, W., 1923: "Plant Physiology," Eng. trans., P. Blakiston's Son & Co.
- PEARSALL, W. H., 1923: Studies in growth. IV, Correlations in development, *Ann. Bot.*, **37**: 261-275.
- , 1925: Hydrogen-ion concentration and growth, *Sci. Prog.*, **20**: 58-67.
- and A. M. HANBY, 1926: Growth studies. V, Factors affecting the development and form of leaves, *Ann. Bot.*, **40**: 85-103.
- , 1927: Growth studies. VI, On the relative sizes of growing plant organs, *Ann. Bot.*, **41**: 549-557.
- PENROSE, L. S., 1925: A note on the relation of rate of growth to structure in plants, *New Phytol.*, **24**: 294-299.
- PIETERS, A. J., 1925: Difference in internode lengths between, and effect of variation of light duration upon, seedlings of annual and biennial white sweet clover, *Jour. Agr. Res.*, **31**: 585-596.
- POPP, H. W., 1926: A physiological study of the effect of light of various ranges of wave length on the growth of plants, *Amer. Jour. Bot.*, **13**: 706-737.
- , 1926: Effect of light intensity on growth of soybeans and its relation to the auto-catalyst theory of growth, *Bot. Gaz.*, **82**: 306-320.
- PORTERFIELD, W. M., 1928: A study of the grand period of growth in bamboo, *Bull. Torrey Bot. Club*, **55**: 327-406.
- POWERS, W. L., 1927: The effect of hydrogen-ion concentration on the growth of certain plants, *Soil Science*, **24**: 1-4.
- PRANTL, K., 1873: Ueber den Einfluss des Lichts auf das Wachstum der Blätter, *Arbeiten Bot. Inst. Würzburg*, **1**: 371-384.
- PRESCOTT, J. A., 1921: Some observations on the growth of maize in Egypt, *Sultanic Agr. Soc. Bull.* 7 (quoted by Hanna, 1925.)
- PRIESTLEY, J. H., and A. F. EVERSLED, 1922: Growth studies. I, A quantitative study of the growth of roots, *Ann. Bot.*, **36**: 225-237.
- and W. H. PEARSALL, 1922: Growth studies. II, An interpretation of some growth curves, *Ann. Bot.*, **36**: 239-249.
- and ———, 1922: Growth studies. III, A volumeter method of measuring the growth of roots, *Ann. Bot.*, **36**: 485-488.
- , 1922: The toxic action of traces of coal gas upon plants, *Ann. App. Biol.*, **9**: 146-155.
- , 1925: Light and growth. I, The effect of brief light exposure upon etiolated plants, *New Phytol.*, **24**: 271-283.
- , 1926: Light and growth. II, On the anatomy of etiolated plants, *New Phytol.*, **25**: 145-170.
- , 1928: The meristemic tissues of the plant, *Biol. Rev.*, **3**: 1-20.
- , 1929: Cell growth and cell division in the shoot of the flowering plant, *New Phytol.*, **28**: 54-81.
- RABER, O., 1928: "Principles of Plant Physiology," The Macmillan Company, New York.

- REED, ERNEST, 1923: Hypothesis of formative stuffs as applied to *Bryophyllum calycinum*, *Bot. Gaz.*, **75**: 113-142.
- REED, H. S., 1919: Growth and variability in *Helianthus*, *Amer. Jour. Bot.*, **6**: 252-271.
- and F. F. HALMA, 1919: On the existence of a growth inhibiting substance in the Chinese lemon, *Univ. Calif. Pub. Agr. Sci.*, **4**: 99-112.
- and ———, 1919: The evidence for a growth-inhibiting substance in the pear tree, *Plant World*, **22**: 239-247.
- and R. H. HOLLAND, 1919: The growth rate of an annual plant *Helianthus*, *Nat. Acad. Sci. Proc.* **5**: 135-144.
- , 1920: Slow and rapid growth, *Amer. Jour. Bot.*, **7**: 327-333.
- , 1920: The dynamics of a fluctuating growth rate, *Proc. Nat. Acad. Sci.*, **6**: 397-410.
- , 1920: The nature of the growth rate, *Jour. Gen. Physiol.*, **2**: 545-561.
- , 1921: A method for obtaining constants for formulas of organic growth, *Nat. Acad. Sci. Proc.* **7**: 311-316.
- , 1921: Correlation and growth in the branches of young pear trees, *Jour. Agr. Res.*, **21**: 849-875.
- , 1923: A note on the statistics of cyclic growth, *Proc. Nat. Acad. Sci.*, **9**: 65-67.
- and A. R. C. HAAS, 1924: The effect of hydroxyl-ion concentration on the growth of walnut roots, *Amer. Jour. Bot.*, **11**: 78-85.
- , 1927: Growth and differentiation in plants, *Quart. Rev. Biol.*, **2**: 79-101.
- REGEMBAL, L. O., and R. B. HARVEY, 1927: The effect of ethylene on the enzymes of pineapple, *Jour. Amer. Chem. Soc.*, **49**: 1117-1118.
- RIPPEL, A., 1922: Die gesetzmässige Erforschung von Reaktionsgleichgewicht und Reaktionsgeschwindigkeit bei den höheren Pflanzen, *Jour. Landw.*, **70**: 9-44; *Bot. Abst.*, **12**: 472-473 (1923).
- ROBBINS, W. J., 1926: Relation of hydrogen-ion concentration to the growth of plants, *Mo. Sta. Bull.* **244**: 30.
- , S. BRODY, A. G. HOGAN, C. M. JACKSON, and C. W. GREENE, 1928: "Growth," 182 pp., Yale University Press.
- ROBERTSON, T. B., 1907-1908: On the normal rate of growth of an individual and its biochemical significance, *Arch. f. Entwicklungsmech. d. Organismen*, **25**: 580-614.
- , 1923: "The Chemical Basis of Growth and Senescence," 389 pp., J. B. Lippincott Company, Philadelphia.
- ROSA, J. T., 1921: Investigation on the hardening process in vegetable plants, *Univ. Mo. Agr. Expt. Sta. Res. Bull.* **48**.
- ROSE, D. H., 1915: A study of delayed germination in economic seeds, *Bot. Gaz.*, **59**: 425-444.
- ROSE, R. C., 1919: After-ripening and germination of seeds of *Tilia*, *Sambucus*, and *Rubus*, *Bot. Gaz.*, **67**: 281-309.
- ROTUNNO, N. A., 1924: Effect of size of seed on plant production with special reference to radish, *Bot. Gaz.*, **78**: 397-413.
- RUDOLFS, W., 1923: Influence of temperature and initial weight of seeds upon the growth-rate of *Phaseolus vulgaris* seedlings, *Jour. Agr. Res.*, **26**: 537-541.
- SACHS, J., 1874: Ueber den Einfluss der Lufttemperatur und des Tageslichts auf die stündlichen und täglichen Aenderungen des Längenwachstums der Internodien, *Arbeit. Bot. Inst. Würzburg*, **1**: 99-192.
- SALMON, S. C., 1917: Why cereals winterkill, *Jour. Amer. Soc. Agron.*, **9**: 353-380.
- and F. L. FLEMING, 1918: Relation of the density of cell sap to winter hardness in small grains, *Jour. Agr. Res.*, **13**: 497-506.
- SANDE-BAKHUYZEN, H. L. VAN DE, 1926: Growth and growth formulas in plants. *Science*, n.s., **64**: 653-654.

- SANDE-BAKEHUYZEN, H. L. VAN DE, 1928: Studies upon wheat grown under constant conditions. I, II, *Plant Physiol.*, **3**: 1-31.
- SCHAFFNER, J. H., 1923: The influence of relative length of daylight on the reversal of sex in hemp, *Ecology*, **4**: 323-334.
- , 1927: Control of sex reversal in the tassel of Indian corn, *Bot. Gaz.*, **84**: 440-449.
- SCHANZ, F., 1919: Wirkungen des Lichts verschiedener Wellenlänge auf die Pflanzen, *Ber. d. d. bot. Ges.*, **37**: 430-442.
- SCHLEY, E. O., 1913: Chemical and physical changes in geotropic stimulation and response, *Bot. Gaz.*, **56**: 480-490.
- SELLSCHOP, J. P. F., and S. C. SALMON, 1928: The influence of chilling above the freezing point on certain crop plants, *Jour. Agr. Res.*, **37**: 315-339.
- SHIRLEY, H. L., 1928: The influence of light intensity and quality upon the growth of plants, *Amer. Jour. Bot.*, **15**: 621-622.
- STADLER, L. J., 1930: Some genetic effects of X-rays in plants, *Jour. Heredity*, **21**: 3-19.
- STRAUSBAUGH, P. D., 1921: Dormancy and hardiness in the plum, *Bot. Gaz.*, **71**: 337-358.
- SUMMERS, F., 1924: Factors governing bud formation: A chapter of plant physiology, *New Phytol.*, **23**: 20-50, 78-102, 113-131.
- SWINGLE, W. T., 1928: Metaxenia in the date palm, *Jour. Heredity*, **19**: 257-268.
- THATCHER, R. W., 1913: Enzymes of apples and their relation to the ripening process *Jour. Agr. Res.*, **5**: 103-116.
- TINCKER, M. A. H., 1925: The effect of length of day upon the growth and reproduction of some economic plants, *Ann. Bot.*, **39**: 721-754.
- , 1928: The effect of length of day upon the growth and chemical composition of the tissues of certain economic plants, *Ann. Bot.*, **42**: 101-140.
- , 1929: The effect of length of day on plants, *Jour. Roy. Hort. Soc.*, **54**: 354-378.
- , 1930: Some experiments with ultra-violet ray glasses, *Jour. Roy. Hort. Soc.*, **55**: 79-87.
- TJEBBES, K., and J. C. UPHOF, 1921: Der Einfluss des elektrischen Lichtes auf das Pflanzenwachstum, *Landw. Jahrb.*, **56**: 315-328; *Bot. Abst.*, **10**: 206.
- TRUMPF, C., 1924: Ueber den Einfluss intermittierender Belichtung auf das Etiolement der Pflanzen, *Bot. Arc.*, **5**: 381-410 (quoted by Priestley, 1926).
- TSCHIRCH, A., 1921: Besitzt die Pflanze Hormone? *Vierteljahrsschr. Naturforsch. Ges. Zurich*, **66**: 201-211; *Bot. Abst.*, **12**: 465-466.
- VACHA, G. A., and R. B. HARVEY, 1927: The use of ethylene, propylene, and similar compounds in breaking the rest period of tubers, bulbs, cuttings, and seeds, *Plant Physiol.*, **2**: 187-192.
- VOGT, E., 1915: Über den Einfluss des Lichts auf das Wachstum der Koleoptile von *Avena sativa*, *Zeits. f. Bot.*, **7**: 193-270; *Bot. Gaz.*, **60**: 423.
- WALLER, A. D., 1900: The electrical effects of light upon green leaves, *Proc. Roy. Soc.*, **67**: 129-137.
- WALLER, J. C., 1924: On the fluctuations of potential in green leaves under the influence of light, *Jour. Physiol.*, **58**, *Proc. XXXVIII-XXXIX*.
- , 1925: Plant electricity. I, Photoelectric currents associated with the activity of chlorophyll in plants, *Ann. Bot.*, **39**: 515-538.
- WALSTER, H. L., 1920: Formative effect of high and low temperatures upon growth of barley: A chemical correlation, *Bot. Gaz.*, **69**: 97-126.
- WANSER, H. M., 1922: Photoperiodism of wheat: a determining factor in acclimatization, *Science*, n.s., **56**: 313-315.

- WEAVER, J. E., and W. J. HIMMEL, 1929: Relation between the development of root systems and shoot under long- and short-day illumination, *Plant Physiol.*, **4**: 435-459.
- WEIMER, J. L., 1929: Some factors involved in the winter killing of alfalfa, *Jour. Agr. Res.*, **39**: 263-283.
- WEST, C., G. E. BRIGGS, and F. KIDD, 1920: Methods and significant relations in a quantitative analysis of plant growth, *New Phytol.*, **19**: 200-207.
- , 1924: Effects of freezing and low temperatures upon plants, *Science Prog.*, **18**: 386-392.
- WILLIAMS, MAUD, 1923: Observations on the action of X-rays on plant cells, *Ann. Bot.*, **37**: 217-225.
- , 1925: Some observations on the action of radium on certain plant cells, *Ann. Bot.*, **39**: 547-562.
- WOFFENDEN, L. M., and J. H. PRIESTLEY, 1924: The toxic action of coal gas upon plants. II, The effect of coal gas upon cork and lenticel formation, *Ann. App. Biol.*, **11**: 42-54.
- WOLFE, T. K., and M. S. KIPPS, 1926: Comparative value of scarified and of unhulled seed of biennial white sweet clover for hay production, *Jour. Amer. Soc. Agron.*, **18**: 1127-1129.
- ZACHAROWA, T. M., 1926: Über den Einfluss niedriger Temperaturen auf die Pflanzen, *Jahrb. f. wiss. Bot.*, **65**: 61-87; *Expt. Sta. Rec.* **57**: 419.
- ZIMMERMAN, P. W., and A. E. HITCHCOCK, 1929: Root formation and flowering of dahlia cuttings when subjected to different day lengths, *Bot. Gaz.*, **87**: 1-14.

AUTHORS' INDEX

(Boldface type indicates bibliographic reference)

A

- Abbe, 822, **840**
 Abbott, **840**
 Abegg, 587, **597**
 Aberson, 127, **141**
 Ackerman, 823, **840**
 Acqua, 523, **553**
 Acton, 239, **292**
 Adams, G. E., **307**
 Adams, J., 706, **721**, 829, 830, 831, **840**
 Adams, M., **666**
 Adams, W. L., 238, **296**
 Addoms, 123, **141**
 Agulhon, 269, **292**
 Ahmann, 12, 14, **41**
 Aiyer, **144**
 Albers, **293**
 Albert, 700, 701, **721**, **724**
 Aldaba, 1, **41**
 Aldous, 700, **721**
 Allard, 546, **556**, 583, 584, **598**, 829, 830, 832, 833, **842**
 Allen, C. E., 2, **41**
 Allen, L. M., 351, **401**
 Allison, F. E., **305**
 Allison, R. V., 107, **141**, 199, 200, **223**, **224**, 272, 284, **293**
 Alsberg, C. L., 569, 573, **597**
 Alsberg, L., **789**
 Alvarado, **41**
 Alway, 157, 160, **171**
 Ambard, 623, 626, **656**
 Ames, 238, 245, 247, 249, **293**, **304**, 537, **553**
 Anderson, A., 115, **145**
 Anderson, A. P., 317, **394**
 Anderson, D. B., 1, 4, **41**
 Anderson, R. J., 568, 569, **597**
 Anderson, V. L., 521, 524, **553**
 Anderssen, 693, 694, 706, **721**
 André, 254, 279, **293**
 Andrews, 199, 200, **224**, 469, **487**
- Annett, 774, **785**
 Appleman, 624, **656**, 751, 774, 776, 777, 778, 779, **785**, 809, 810, 813, 816, **840**, **841**
 Appleyard, 127, **147**
 Arker, 104, **141**
 Armstead, 678, 679, **726**
 Armstrong, E. F., **656**, 774, **790**, **791**, 807, **841**
 Armstrong, H. E., 635, 636, 637, **656**, **657**, 807, **841**
 Arndt, 281, **293**, 690, 691, 692, **721**
 Army, 111, 130, **141**
 Arrhenius, 214, **224**
 Askenasy, 366, **394**, 686, **721**
 Aso, 275, **293**, **306**, 522, **553**, **785**
 Astruc, **41**
 Atkins, 31, 34, 35, 36, **41**, **42**, 706, **721**, **723**, 774, **785**, **786**
 Atwater, 542, **553**
 Auchter, 692, 695, 696, 710, **721**, **841**
 Ayres, 208, **224**

B

- Babb, 818, **841**
 Babcock, 752, **786**
 Babinet, 373, **394**
 Bach, 767, 768, 775, 779, **786**
 Bacon, **295**, 832, **842**
 Badollet, 615, **665**
 Baeyer, 444, 445, 448, **487**
 Baguley, 245, 280, **293**
 Bailey, C. H., 748, 752, 753, 754, 757, **786**
 Bailey, E. M., 613, **657**, **786**
 Bailey, I. W., 767, **786**
 Baker, J. C., **666**
 Baker, J. L., **657**
 Baker, S. M., **487**
 Baker, W. F., **661**
 Bakke, 153, **171**, 209, 215, **224**, 262, **295**, 379, 380, **394**

- Balch, 615, **664**
 Baldwin, H. I., 162, **171**
 Baldwin, M. E., 626, **666**
 Ball, 442, **490**, 704, 712, **724**
 Ballard, 750, 780, **792**
 Balls, 328, **394**
 Baly, 442, 446, 448, 449, **487**, 520, **553**,
 627, 628, **657**
 Bambacioni, 534, **553**
 Banal, 454, 455, **488**
 Bancroft, 204, **224**
 Bang, 582, **597**
 Barakov, 126, **141**
 Baranetzky, 620, **657**, 806
 Bardell, 122, **141**
 Barendrecht, **657**
 Barker, 442, 446, 448, **487**
 Barnes, 383, **394**, 420, **488**, 730, 731,
 736, **786**
 Barnette, 264, **293**
 Barrenscheen, **293**
 Bartholomew, E. T., **657**, 737, **786**
 Bartholomew, R. P., 254, 255, **297**
 Bartlett, A. W., **786**
 Bartlett, H. H., 8, **41**, 85, 189, **230**
 Barton, 633, **657**
 Barton-Wright, 9, **42**
 Batten, 834, **843**
 Baudisch, 522, **553**
 Bauer, 245, **293**
 Baughman, 569, **597**, **599**
 Bayer, 358, **394**
 Bayliss, 607, 612, 620, **657**
 Beal, 200, **224**
 Beaumont, 741, 757, 763, **786**, **796**
 Beber, **792**
 Beck, A. J., 263, **306**
 Beck, W. A., 57, 72, **91**
 Becker, 763, **786**
 Becking, 777, **786**
 Beckwith, 110, 111, **141**
 Becquerel, 63, **91**
 Bedford, 131, **146**
 Beer, G. R. de, **841**
 Beer, R., **41**, 576, **597**
 Behrendt, **567**
 Belden, 363, **396**
 Bellamy, **841**
 Bellani, 373, **394**
 Belval, 439, **489**
 Belzung, 22, **41**
 Benedict, 682, 683, **721**
 Bennett, J. P., 693, 696, **721**, 737, **786**
 Bennett, M. E., 107, **141**
 Bennett-Clark, 835, **842**
 Benoy, 757, **786**
 Benz, **307**
 Berzeller, 625, **657**
 Bergman, 105, **141**, 758, 763, **786**
 Bernard, 19, 20, **41**, 432, **488**
 Berthelot, D., 446, **488**
 Berthelot, M., 279, **293**
 Bertram, 701, **726**
 Bertrand, 272, 273, 275, **293**, 766, 768,
 769, **786**, **787**
 Bessey, 315, **394**
 Beyersinck, 507, **553**, 629, 650, **657**
 Bezagu, 758, **787**
 Bidzinski, **658**
 Bigelow, 749, **787**
 Birch-Hirschfeld, 690, **722**
 Bizzell, 127, **141**
 Black, **306**
 Blackman, F. F., 332, 363, **394**, 453, 456,
 459, 460, 463, 464, 473, 476, **488**,
 737, **787**
 Blackman, V. H., 168, 169, **171**, 354,
 378, **395**, 803, 805, 834, 835, **841**
 Blagowestschenski, **657**
 Blair, A. W., 272, **293**, 538, **558**
 Blake, 696, **722**
 Blanck, 127, **146**
 Blaydes, 315, **395**
 Blodgett, 361, **395**
 Blood, 640, 641, 642, 645, **657**, **663**
 Bloomfield, 619, **664**
 Bloor, 564, 569, 574, **597**
 Blout, **659**, **788**
 Blum, 68, 72, **95**, **96**
 Bodansky, 617, **664**
 Bode, 675, 689, **722**
 Boehm, 248, **293**, 434, **488**, 676, 683, **722**,
 755, **787**
 Bokorny, 450, **488**
 Bolas, 458, **488**
 Bolin, I., **788**
 Bolin, P., 277, **293**
 Bolley, 697, **722**
 Boltz, 238, 245, 247, 249, **293**
 Boncquet, 522, **553**
 Bonnet, **796**
 Bonnier, 431, **488**, 746, **787**
 Bonns, **396**
 Born, 615, **664**
 Bornemann, 453, 458, **488**

- Borowikow, 826, **841**
 Borowski, 129, **141**
 Borrownicka-Ordzywolska, **293**
 Bose, **488**, 681, 682, 683, **722**
 Bottomley, 455, **488**, 504, 505, **553**, **554**
 Boucherie, 683, **722**
 Bouchut, 639, 640, 644, **657**, **668**
 Bourquelot, 628, **657**
 Boussingault, 430, 431, **489**, 506, 508,
 542, **554**
 Bouyoucos, 357, **395**
 Bowerman, 764, **793**
 Boysen-Jensen, 456, **489**, 713, **722**
 Brannon, J. M., 240, **293**
 Brannon, M. A., **41**
 Brasse, 620, 628, 629, **657**
 Braun, **657**
 Brauns, 569, **597**, **599**
 Breazcale, 133, 135, **141**, **145**, 175, 207,
 208, **224**, 282, 288, 289, **294**, 455,
 489, 713, **725**, 808, **841**
 Bredow, 22, **41**
 Brenchley, 104, **143**, 198, 199, 208, 209,
 224, **225**, 243, 269, 271, 275, 284,
 288, **294**, 535, 536, **554**, 803, **841**
 Bricka, **656**
 Briggs, G. E., 178, 179, **224**, 466, 467,
 470, **489**, 758, **791**, 803, 805, 819,
 841, **845**, **850**
 Briggs, L. J., 152, 153, 154, 155, 157,
 158, 159, **171**, 312, 347, 350, 351,
 352, 353, 354, 370, 371, 373, 374,
 375, 377, 378, 384, 385, 386, 388,
 395, 835, **841**
 Brigham, 501, 504, **554**
 Brill, 641, **657**
 Brilliant, 467, **489**
 Bristol, 508, **554**
 Britton, 133, **145**
 Brody, **848**
 Brooks, C., 366, **395**
 Brooks, S. C., 64, 67, 75, 76, 77, **91**
 Brown, A. J., 62, 63, 64, 86, 87, **91**
 Brown, B. E., 256, 272, **293**, **294**, **305**
 Brown, D. E., **143**
 Brown, H. H., 155, 156, **171**
 Brown, H. T., 323, 333, 334, 335, 336,
 337, 366, **395**, 433, 435, 439, 456,
 458, 473, 474, 477, 478, 479, 480,
 489, 614, 620, 621, 625, 627, 630,
 648, 650, 651, **657**, **658**
 Brown, J. G., 16, **46**, **754**, **792**
 Brown, J. W., **294**
 Brown, M. A., 354, **395**
 Brown, P. E., 275, **294**
 Brown, R. E., 641, **657**
 Brown, W. H., 338, 346, 347, **399**, 459,
 463, **489**, 825, 826, **841**
 Bruce, 260, **294**
 Bruch, 248, **294**
 Bruner, **149**
 Bruschi, 652, **658**
 Bryan, 284, **293**
 Buchanan, **307**
 Buchner, 612
 Buckner, 288, **294**, 773, **790**
 Bugarsky, 76, **91**
 Bullis, 273, **298**
 Bunzel, 769, 772, 773, **787**
 Burd, 286, **294**
 Burge, E. L., 780, **787**
 Burge, W. E., 780, **787**
 Burgerstein, 190, **224**, 329, 345, 357, 377,
 388, **395**
 Burk, 448, **489**, 509, **554**
 Burke, 537, **554**
 Burlakow, 757, 780, **787**
 Burns, 374, **395**
 Burroughs, 749, 751, **787**
 Buscalioni, D., 638, **659**
 Buscalioni, L., 332, **395**
 Butkewitsch, 644, **658**
 Butler, 255, **305**, 702, **722**, 752, **787**
 Butlerow, 445, **489**
- C
- Cable, **46**
 Cailletet, 455, **489**
 Cake, 8, **41**
 Caldwell, J. S., 156, **171**, 643, 644, **658**
 Caldwell, M., 621, 626, **666**
 Calvin, **667**
 Cameron, **149**, 208, **224**
 Campbell, A. B., 835, **841**
 Campbell, E. G., 521, **554**
 Campbell, G. F., 625, **664**
 Cannon, 105, 106, 107, 112, **141**, **142**
 Carey, 702, **722**
 Carlson, 109, **142**
 Carr, 281, **297**, 536, **561**
 Carre, 13, **41**, **42**
 Carrero, 237, 265, 266, 287, **296**, **307**, 503,
 563, 696, **724**
 Carrick, 751, **787**
 Carter, 538, **556**

- Castoro, 7, **42**, **48**, 718, **727**
 Cavers, 24, **42**
 Cerighelli, 458, **489**, 746, **787**
 Chace, 818, **841**
 Chandler, 32, 34, **42**, 548, **554**, 702, 717, 722
 Channon, 580, **597**
 Chibnall, 520, 524, 525, 526, 527, 528, 529, 531, 532, 542, **554**, 577, 580, **597**
 Child, **841**
 Chittenden, 639, 640, 641, 642, 643, **658**
 Chizhov, 287, **294**
 Choate, 713, 718, **722**
 Chodat, 767, 768, 775, 779, **786**
 Chrapowicki, 532, **554**
 Chrzaszcz, 626, **658**
 Church, 818, **841**
 Ciamician, 504, **554**
 Clapp, **396**
 Clark, E. D., **665**, 775, **788**
 Clark, Mary, 614, **662**
 Clark, N. A., **841**
 Clark, O. L., 199, **224**
 Clark, W. S., 110, **142**, 676, **722**
 Clarke, 505, **555**
 Clausen, 748, **788**
 Clayson, 13, **42**, 415, **489**
 Clements, F. E., 107, 112, **142**
 Clements, H. F., 217, **224**
 Clevenger, 37, 38, **42**
 Clinton, 358, **396**
 Clowes, 88, **91**
 Clum, 363, 366, 368, 369, **396**
 Coburn, 115
 Coffman, 311, 312, 345, 348, **400**
 Cohn, 515, 516, **555**
 Cohnheim, 645, **658**
 Cole, 214, **224**
 Coleman, 752, 755, **788**
 Colin, 439, **489**, 614, **658**
 Collings, 111, **142**, **294**
 Collins, E. J., 64, **91**
 Collins, G. H., 272, **294**
 Collins, G. N., 835, **841**
 Collison, 135, 136, **142**
 Combes, 774, **788**
 Compton, 619, **658**
 Conner, 281, 284, **294**
 Connstein, 633, **658**
 Conrad, C. M., 14, **42**
 Conrad, J. P., 98, 136, **142**
 Cook, F. C., 269, 270, **294**, **295**
 Cook, M. T., 132, **142**
 Cooley, 358, 361, **396**, **400**
 Coons, 526, **555**
 Cooper, 174, **224**
 Copeland, 324, 354, **396**, 680, 688, **722**
 Copeman, 803, **841**
 Corson, 262, **295**
 Cottrell, 111, 115, **142**
 Coupin, H., 125, 775, **788**
 Coville, 281, **295**, 504, **555**, 813, 816, **841**
 Cowdry, 25, **42**
 Cowles, 344, **396**
 Crider, 703, **722**
 Crist, 102, 109, 117, **142**, **148**, 782, **788**
 Crocker, 197, 216, **224**, **227**, 257, 259, **295**, 453, **489**, 741, 742, 743, 744, 762, 774, 776, 778, 780, 781, **788**, **789**, 811, 812, 836, **841**, **842**, **845**
 Crone, 194, 195, **224**
 Cross, **42**
 Crowther, 504, **555**
 Crozier, 38, **42**, **91**
 Cruess, **788**, **793**
 Crump, 158, **171**
 Cuisinier, 629, **658**
 Cullinan, 349, **396**
 Cummings, 458, 459, **490**
 Curtis, 382, 383, **396**, 549, **555**, 693, 694, 702, 703, 705, 707, 708, 709, **722**
 Czapek, 125, **142**, 575, **597**, 611, **658**, 709, **723**
 Czerny, 736, **795**
- D
- Dachnowski, 549, **555**
 Daikukara, 502, **555**
 Daish, 433, 435, 439, **490**, 629, **658**
 Damon, E. B., 67, **94**
 Damon, S. C., **144**, 246, **297**
 Dandeno, 129, 131, **142**
 Dangeard, 576, **597**
 Darsie, 747, **788**
 Darwin, 326, 328, 329, 332, 341, 351, 352, 353, 368, **396**, 685, **723**
 Dastur, 467, **490**
 Davidson, J., 186, **224**, 289, **295**, 537, 542, **555**, 708, **723**
 Davidson, W. C., 626, **663**
 Davis, A. R., 37, **45**, 78, 82, **92**, 176, 177, 179, 189, 216, **224**, **226**, 236, 279, 284, **295**, **299**, **658**, **659**
 Davis, E. F., 137, **142**
 Davis, W. A., 408, 433, 435, 439, **490**, **658**

- Davis, W. B., 782, **795**
 Davis, W. E., 743, 762, 776, 777, 781,
 782, **788**, 812, 816, **842**
 Dawson, 275, **304**
 Day, **295**
 Dean, 419, **490**, 628, **659**
 Deats, 833, **842**
 DeBary, 629
 De Beer (*see* Beer).
 De Candolle, 136, **142**
 De Heen, 275, **301**
 Delecano, **597**, 706, 709, **723**, 733, **788**
 Delzenne, 641, **659**
 Delf, 78, 79, 80, 87, **91**
 De Long, 741, **786**
 De Luca, 582, **598**
 Demolon, 259, **295**
 Demoussy, 254, 284, **293**, **300**, 432, 458,
 490, **494**, 738, **792**
 Denny, 60, 61, 62, 87, **91**, 185, **224**, 761,
 788, 813, 814, 818, **842**
 De Saussure (*see* Saussure).
 Detmer, 592, 593, **598**, 713, **723**
 Deuber, 261, 264, **295**, 427, **490**
 De Vries, 66, **91**, **92**, 708, **723**
 Dickson, 252, 253, 254, 255, **295**
 Diehl, **792**
 Dillman, 130, **141**, 584, **598**
 Dinshaw, 415, **493**, **665**
 Dixon, 31, 32, 33, 34, **42**, 81, **92**, 169,
 171, 353, **396**, 440, 442, 446, **490**,
 680, 682, 683, 684, 685, 686, 687, 688,
 689, 690, 691, 703, 705, 706, 712,
 723, **724**, 835, **842**
 Dobson, 613, 614, **665**
 Doby, 614, **659**
 Dodge, 322, **396**
 Dole, 356, **396**
 Doreas, 174, **224**
 Dore, W. H., 271, **298**
 Dore, W. S., **42**
 Dorée, 9, **42**
 Dosdall, 356, **396**
 Doubt, 837, **842**
 Dowding, 254, **295**
 Drabble, E., 28, **42**, **43**, 345, **396**
 Drabble, Hilda, 28, **43**, 345, **396**
 Drain, 749, 756, 769, **788**
 Dubruffaut, 620
 Duchon, 781, **793**
 Duclaux, 464, 465, **490**
 Dufrenoy, 185, **224**, 362, **396**
- Duggar, 196, 213, **224**, **225**, 318, 358, 360,
 396, **659**
 Duley, 98, 115, **142**, **145**, 259, 286, **295**
 Dunlap, 586, **598**
 Dustman, 127, **142**
 Duvel, 752, **788**, 811, **842**
 Dymond, **295**
- E
- Eames, 165, **172**, 670, **724**
 Eaton, F. M., 29, **43**, 363, **396**, **842**
 Eaton, S. V., 259, **295**
 Eckerson, 80, 81, **92**, 108, 109, **143**,
 322, 323, **396**, 523, 524, 535, 536,
 555, 677, 816, 817, **842**
 Edson, 677, 703, **725**
 Effront, 621, 643, **659**
 Ehlers, 363, 366, 367, **396**
 Eisenmenger, 212, 219, **225**
 Elfvig, 685, **724**
 Eliasberg, 254, **299**
 Elliot, 697, **724**
 Elliott, 747, **788**
 Eltinge, 828, **842**
 Elvove, 523, **558**
 Emmerling, A., 532, **555**
 Emmerling, O., **659**
 Epple, 536, **561**
 Erdman, 209, 215, **224**
 Erdmann, **302**
 Ernest, 125, 126, **148**
 Errera, 685, **724**
 Escombe, 323, 333, 334, 335, 336, 337,
 366, **395**, 456, 458, 473, 474, 477,
 478, 479, 480, **489**, 650, 651, **658**
 Espino, 204, **225**, 502, **555**
 Esselen, **43**
 Estabrook, 329, **398**
 Estioko, 137, **146**
 Euler, 579, **598**, **788**
 Everest, 774, **788**
 Evershed, 803, 810, **847**
 Ewart, 107, **143**, 443, 447, 448, 449, 463,
 468, 469, **490**, **491**, 681, **724**, **788**,
 842
 Ewing, 178, **228**, 516, **560**
 Eyster, 20, **43**, 426, **491**
 Ezell, 782, **788**
- F
- Faber, **43**
 Fagan, **555**

- Fales, **659**
 Falk, 614, 616, 618, 634, 635, 636, 637,
 659, 663, 788
 Famintzin, 23, **43**
 Farr, 120, 121, **143**
 Faul, 16, **43**
 Feher, **555**
 Feist, **659**
 Fellenberg, 13, 14, **43**
 Fellows, 752, 755, **788**
 Fenton, 446, **491**
 Ferguson, 374, **402**
 Fermi, 638, **659**
 Fernald, **842**
 Fernbach, 415, 418, **491, 638, 660**
 Fincke, 449, **491**
 Findlay, 57, **92**
 Fink, 1, **43**
 Fischer, A., 705, **724**
 Fischer, E., 512, **555**
 Fischer, H., 458, **491, 509, 543, 555**
 Fischer, M. H., 66, **92**
 Fisher, D. F., 366, **395**
 Fisher, E. A., 644, **660**
 Fisher, R. A., 803, 805, **842**
 Fittbogen, 190, **225**
 Fitting, 29, 30, **43**
 Fleck, **48**
 Fleming, 823, **848**
 Fletcher, 137, **143**
 Fleury, 589, **598**
 Flint, L. H., 835, **841**
 Flint, W. P., 697, **724**
 Flood, 389, **397**
 Fluri, 281, **295**
 Fong, **788**
 Forbes, 284, **295**
 Formaini, 586
 Fosse, 542, **556**
 Foubert, 583, 584, **598**
 Francis, **598**
 Frank, A. B., 358, **397**
 Frank, B., 101, **143, 508, 529, 556**
 Frank, E., **303**
 Frankel, **660**
 Frankfurt, 580, **601**
 Fraymouth, 753, **788**
 Fred, 127, **143, 408, 420, 499**
 Free, 88, **92, 105, 143, 198, 199, 225, 230**
 Freeman, 361, 376, 377, 380, 381, **397,**
 539, 561
 Frei, 355, **397**
 Fremy, 13, 14, **43**
- Freud, 625, **657**
 Frey, 4, **43**
 Friedemann, **598**
 Friedrich, 756, **789**
 Friesner, 806, 807, **842**
 Fujita, **92, 93**
- G
- Gailey, 735, **791**
 Gallagher, 582, **598, 767, 768, 789**
 Galwialo, **491**
 Ganeau de Lamarlière, 380, **397**
 Ganong, 150, **172, 378, 397, 473, 474,**
 491, 743, 789
 Gardiner, 19, **43, 660**
 Gardner, F. E., 701, 703, 707, **724**
 Gardner, V. R., 546, **556**
 Gardner, W. A., 815, **842**
 Garner, 133, **143, 252, 295, 546, 556, 583,**
 584, 598, 829, 830, 832, 833, 842
 Gast, 436, 439, **491**
 Gaudechon, 446, **488**
 Gefan, 67, **91**
 Genevois, 737, **789**
 Georgeson, 111, 116, **143**
 Gerber, 582, 583, 586, **598, 646, 660, 746,**
 789
 Gerdel, 376, **397**
 Gericke, 206, 210, 211, **225, 253, 263, 287,**
 295, 537, 548, 556, 807, 842
 Gerlach, M., 501, **556**
 Gerlach, P., 454, 459, **491**
 Gershberg, 285, **297**
 Gettler, **666**
 Gibson, 110, **143, 446, 449, 491**
 Giddings, 354, **397**
 Gies, **230, 592, 599**
 Giglioli, 64, **92**
 Gilbert, B. E., 238, 276, 279, 280, **296,**
 301, 831, 843
 Gilbert, J. H., 507, **558**
 Gilbert, L. O., 586, **598**
 Gile, 237, 261, 262, 265, 266, 267, 268,
 287, **296, 696, 724**
 Gilson, 9, **43**
 Giltay, 190, **225**
 Ginsburg, 237, **296, 741, 789**
 Girard, 435, **491**
 Glenn, 615, **663**
 Glimm, 622, **660**
 Godlewski, 455, 456, **491, 680, 681, 724,**
 746, 789

Goff, 110, 111, **143**, 697, 703, **724**
 Gore, 732, 748, 749, 787, **789**
 Gortner, 29, 32, **44**, **45**, **789**
 Gorup-Besanez, Von, 638, **660**
 Gosney, 635, 636, 637, **657**
 Goss, 811, **843**
 Gössl, 273, **296**
 Graber, 699, 700, 701, **724**
 Gradenwitz, 458, **491**
 Grafc, 248, **296**, 449, 450, **491**, 579, **598**
 Gray, G. P., 38, **43**
 Gray, J., 329, **397**
 Greaves, 233, 235, **296**, 538, **556**, **561**
 Green, 589, 592, 593, **598**, 621, 627, 628,
 632, 633, 638, 639, 644, 650, **660**, **661**
 Greene, **848**
 Gregory, **225**, 803, 806, 819, 834, **841**, **843**
 Griffin, 617, **661**, **664**
 Griffiths, 501, **556**
 Gris, 261, **296**
 Groom, 248, **296**
 Gross, 515, 516, **555**
 Grover, 527, **554**
 Groves, **843**
 Grüss, 7, **43**, 652, **661**, 756, **789**
 Gruzit, 470, **491**
 Guerrant, 580, 581, **598**
 Guilliermond, 25, 26, **43**
 Gurjar, 544, **556**, 741, 752, 754, 757, **786**,
789
 Gursky, 111, **143**
 Gustafson, 36, 38, **43**, **44**, 758, 759, **789**,
790, 809, **843**

H

Haag, 214, 215, **227**, 264, **300**
 Haas, A. R. C., 35, 37, **44**, 125, 127, **143**,
 177, 186, 188, **225**, **228**, 237, 244, 251,
 252, 264, **296**, **303**, 447, 460, 463,
 473, **496**, 697, 728, 742, 760, 762,
789, **793**, 836, **848**
 Haas, P., 418, **491**, 519, 540, 541, **556**,
 571, 572, 573
 Haber, **44**
 Haberlandt, **44**, **119**, **143**, 190, **225**, 342,
 389, **397**, 465, **492**, 575, **598**, 650,
660, **843**
 Hackenberg, 802, **843**
 Haeln, 625, 626, **661**
 Haerdtl, 415, 417, **496**
 Hafenrichter, 734, 735, 759, **789**
 Hagen, 327, **397**

Haigh, 698, 699, **728**
 Hales, 689
 Haley, 633, 634, 635, **661**
 Halket, **172**
 Hall, A. D., 104, 126, **143**, 199, 208, 209,
225, 267, 268, **296**, 535, **554**
 Hall, E. H., 260, **296**
 Halma, 35, 38, **48**, 810, **848**
 Halstead, 215, **227**
 Hamlin, 636, **659**
 Hammett, 198, **225**, **297**
 Hampton, 777, **786**
 Hanby, **847**
 Hanna, 818, 825, **843**
 Hannig, **31**
 Hanriot, **598**
 Hansteen, 533, **556**, 652, **661**
 Hansteen-Cranner, 15, **44**, 575, 579, **598**,
599
 Harder, 456, **492**
 Hardin, 238, **296**
 Harding, 419, **492**
 Hardy, 162, **172**
 Harlan, 536, 651, **663**
 Harley, **841**
 Harlow, 3, 9, **44**
 Harper, 21, **44**
 Harrington, G. T., 741, 742, 743, 744,
 745, 746, 774, 776, 778, 780, 781,
788, **789**, 814, **843**
 Harrington, J. B., 830, **843**
 Harrington, O. E., 29, **45**
 Harris, E. S., 67, **94**
 Harris, F. S., 98, 102, **144**
 Harris, J. A., 29, 30, 31, 32, 33, **44**, **45**,
 182, **225**
 Harrison, G. T., 278, **296**
 Harrison, W. H., 104, **144**
 Hart, 257, 259, 260, **296**
 Harter, 11, **49**, 219, **226**, 278, **296**, 357,
397
 Hartig, 702, 705, **724**
 Hartwell, 132, **144**, 245, 246, 248, 252,
 256, 263, 279, 280, 282, **297**, **307**
 Harvey, E. M., 545, 546, **556**, 837, **843**
 Harvey, E. N., 468, **492**
 Harvey, R. B., 178, **225**, **306**, 761, 772,
 773, 776, 778, 779, **789**, **795**, **796**,
 814, 818, 824, 829, 830, **843**, **848**, **849**
 Haselhoff, 269, **297**
 Hasselbring, 191, **225**, 733, **787**, **789**, **790**
 Haukinson, 524, **557**
 Häveler, 101, **144**

- Hawkins, L. A., 162, 163, **172**, 374, 378,
399, 733, **790**
 Hawkins, R. S., 135, **144**, 339, **397**
 Haynes, 14, **41**, **45**, **48**
 Hays, 110, 111, **144**
 Headden, 111, **144**, 233, 235, 273, **297**,
 539, **557**
 Heald, 835, **841**
 Hedrick, 131, **144**
 Hedricks, **843**
 Heilbron, 442, 446, 448, 449, **487**, **492**,
 520, **553**
 Hein, 24, **45**
 Heinicke, 776, 778, 782, **790**
 Heise, 459, 463, **489**
 Hellriegel, 110, **144**, 282, **297**, 507, 542,
557, 592, **599**
 Hemmi, **172**, 356, **399**
 Henderson, 351, 458, **488**
 Hendrickson, **173**, 339, 355, **397**
 Hendry, 278, **297**
 Henri, **661**
 Henrici, 463, 466, **492**
 Henslow, 151, **172**
 Hepburn, 647, **661**
 Herlitzka, 426, **491**
 Heron, **657**, **668**
 Herzfeld, 730, **790**
 Hesse, 123, **144**
 Hibbard, P. L., 179, 189, **226**
 Hibbard, R. P., 29, **45**, 211, 212, **225**, 285,
297, 470, **491**, 818, **843**
 Hicks, G., **599**
 Hicks, P. A., 547, 548, 549, **557**
 Hiestand, 579, **602**
 Hilditch, **599**
 Hill, A. W., 19, **43**, 671, **724**
 Hill, D. D., 824, **843**
 Hill, G. R., 739, **790**
 Hill, J. H., **663**
 Hill, T. G., 28, **45**, 418, **491**, 519, 540, 541,
 556, 571, 572, 573
 Himmel, 832, **850**
 Hitchcock, A. E., 832, **850**
 Hitchcock, D. I., 617, **664**
 Hixon, 214, **225**
 Hoagland, 37, **45**, 78, 82, **92**, 176, 177,
 179, 182, 183, 185, 186, 187, 188,
 189, 193, 194, 197, 208, 209, 213, 215,
 216, 217, **225**, **226**, 236, 237, **295**,
297
 Hobart, 249, **297**
 Hoffer, 263, 264, 281, **297**
 Hoffman, C. T., **45**
 Hoffman, W. F., 33, **45**, 182, **225**
 Hogan, **848**
 Hogounenq, 608, **661**
 Hole, **144**
 Holland, 803, **848**
 Hollander, **664**
 Holle, 167, **172**, 675, **724**
 Holmes, 613, **662**
 Holtz, 384, **402**
 Honda, 275, **299**
 Hooker, H. D., 12, 14, **41**, 97, 98, **144**,
 452, 453, **492**, 545, 550, **557**, 803,
 824, **844**
 Hooker, J., 638
 Hopkins, 264, **297**, 732, 749, 751, 752,
 757, **790**
 Horn, 467, **492**, **497**
 Hornberger, 285, **297**
 Horner, **561**
 Horning, 25, **45**, 650, **661**
 Horton, **656**, **661**
 Horvat, 579, **598**
 Hostermann, 830, **844**
 House, 622, **663**
 Hover, 758, **790**
 Howard, A., 103, **144**
 Howard, B. J., 749, **787**
 Howard, G. L. C., **144**
 Howard, W. L., 811, 812, 813, 816, **844**
 Howe, 124, **144**
 Howes, 380, **397**
 Howlett, 546, **557**
 Hoyer, 633, **658**, **661**
 Huber, 347, **397**
 Hubert, 638, **660**
 Hudson, C. S., 615, 617, 618, 619, **661**,
662
 Hudson, D. P., **553**
 Huerre, 629, **662**
 Hughes, **295**
 Hulton, **657**
 Hunter, C., **144**
 Hunter, J. H., 284, **293**
 Hurd, 38, 39, **45**
 Hurd-Karrer, 32, 33, **45**
 Huston, 285, **298**, 699, **725**
 Hutchins, 106, **144**
 Hutchinson, D. M., 765, **790**
 Hutchinson, H. B., 502, 504, **557**

I

Nienkoff, 190, **226**
 Ilin, 29, **45**
 Ijij, **226**, 325, 326, **397**, 467, **492**, **790**
 Imas, **298**
 Inamdar, 803, **844**
 Ingen-Housz, 429, 430, **492**, 739
 Inman, 764, **790**
 Irvine, 613, 614, **665**
 Irving, 20, **47**, 466, **492**, 524, **557**, 760,
790
 Irwin, 78, **92**, 174, 181, **226**
 Ivanow, 584, 589, 590, 594, **599**, **790**
 Iwanoff, L. A., 352, **397**, 581, **599**
 Iwanoff, M., 534, **557**

J

Jackson, C. M., **848**
 Jackson, H., 455, **488**, 581, **598**
 Jacobson, C. A., 613, **662**
 Jacobson, H., 579, **599**
 Jacobson, H. G. M., 215, **226**
 Jacoby, 450, **492**
 Jacques, 67, **94**
 Jacquot, 753, **790**
 James, 457, 463, **492**
 Jamieson, 569, **597**, **599**
 Janse, 681, **724**
 Janssen, 254, 255, **297**
 Javillier, **298**, 645, **662**
 Jean, 102, 117, **144**, **148**
 Jeffreys, 336, 342, **397**
 Jeffs, 119, 120, **144**
 Jegorow, 590, **599**
 Jenkins, 104, **148**
 Jennings, 268, **298**
 Jensen, C. A., **145**
 Jensen, I. J., **844**
 Jess, 458, **492**
 Jivanna, 317, **397**
 Jodidi, 519, 525, **557**, 651, **662**, 718, **724**
 Jodin, 267, **298**
 Joëssel, **796**
 Johnson, E. L., 828, **844**
 Johnson, H. V., 182, **226**
 Johnson, I. J., 111, **141**
 Johnson, M. O., 265, **298**
 Johnson, O. C., 515, 516, **555**
 Johnston, 199, 210, **226**, 271, 277, **298**,
 373, **397**
 Johnstone, 755, 756, **790**

Joly, 685, 686, **723**, **724**
 Jones, C. H., 458, 459, **490**, 677, 703, **725**
 Jones, F. M., **661**
 Jones, H. A., 781, **790**
 Jones, H. W., 253, **298**
 Jones, J. A., 814, 815, 817, **844**
 Jones, J. P., **298**
 Jones, J. S., 273, **298**, 540, **557**
 Jones, L. H., 214, **226**, 260, 262, 264, **298**
 Jones, L. R., 132, **144**
 Jones, R. L., **298**
 Jones, W. J., 285, **298**, 699, **725**
 Jones, W. N., 328, **398**, 628, **662**, 774,
791, **844**
 Jordan, 237, 245, **298**
 Jorgensen, 77, 78, 80, 84, **95**, 199, **230**,
 421, 433, 447, 465, **492**, 834, **844**
 Joslin, **658**
 Jost, 190, **226**, 712, **725**
 Jung, 276, **298**
 Jupe, **295**

K

Kaho, 88, **92**
 Kamerling, **45**
 Karchevski, 757, **790**
 Karling, **844**
 Karlson, 738, **790**
 Kas, 283, **302**
 Kastle, 523, **558**, 614, **662**, 767, 768, 773,
790
 Katayma, 275, **298**
 Kater, **844**
 Kayser, E., **662**
 Kayser, R., 434, **492**
 Kearney, 219, **226**
 Keeble, 774, **790**, **791**
 Keinholtz, **844**
 Keller, 29, **45**
 Kellerman, 197, **227**, **662**, 830, 832, **844**
 Kelley, 272, 275, **298**, **307**, 502, **558**
 Kellicott, 806, **844**
 Kellner, 502, **558**
 Kellogg, **557**
 Kelly, F. C., **302**
 Kelly, J. W., 236, **306**
 Kempton, 819, **844**
 Kendall, **665**
 Kennedy, 718, **726**
 Kerr, 539, **562**
 Keuhl, 454, **492**
 Keyser, 539, **558**

- Khankoje, 384, **398**
 Kidd, 181, 182, 188, **230**, 447, **492**, 736,
 758, 763, **791**, 803, 805, 819, **841**,
844, **845**, **850**
 Kiesselbach, 98, 115, **144**, **145**, 191, 192,
227, 318, 323, 353, 368, 378, 384,
 385, 387, 388, **398**, **400**, 819, 820,
845
 Kimbrough, 751, **791**
 Kimpflin, 449, **492**
 King, C. J., 278, **296**
 King, F. H., 110, 111, **145**
 Kinoshita, 503, **558**
 Kipps, 814, **850**
 Kirkwood, 592, **599**
 Kite, 66, **92**
 Kizel, 628, **662**
 Kjeldahl, 464, **492**
 Klason, 9, **45**
 Klercker, 109, **145**
 Klinger, 730, **790**
 Klotz, 526, **555**
 Kniep, 462, **493**
 Knight, L. I., 836, **841**, **845**
 Knight, R. C., **145**, 328, 339, 341, 354,
 376, **395**, **398**, 550, **558**, **725**, 766, **791**
 Knop, 120, 194, 195, 200, 201, 206,
 210, **227**, 242, 266, **299**, 579, **599**
 Knott, 776, 778, **791**, 833, 834, **845**
 Knowlton, 696, **725**
 Knudson, 129, **145**, 239, 240, 241, **299**,
 549, **558**, 614, **662**, 732, **791**, 836,
845
 Kny, 468, **493**
 Koch, 622, **667**
 Koga, 622, **662**
 Kohl, 190, **227**, 617, **662**
 Koketsu, 162, 163, **172**
 Kokichi, **667**
 Kolkwitz, 752, 757, **791**
 Komleff, 732, **794**
 Kooper, 529
 Kopaczewski, 14, **45**
 Korsakow, 582, **599**
 Korstian, 28, 31, 32, 33, 34, **46**
 Kosmann, 620, **662**
 Kossel, 579, **599**
 Kossowitch, 126, **145**, 508, **558**
 Kostytschew, 254, **299**, 432, 459, **493**, 736,
 738, 741, **791**, **794**
 Kosutany, 529, **558**
 Kotowski, **92**
 Kozlowski, **46**
- Krabbe, 86, **92**, 652, **662**
 Kraemer, 415, 417, **493**
 Kramer, **148**
 Krassovsky, 111, **145**
 Kratzmann, 279, 280, **299**
 Krauch, 620, **663**
 Kraus, E. J., 543, 544, 547, **558**, **560**
 Kraus, G., 434, **493**
 Krause, 626, **658**
 Krauss, 182, **229**
 Kraybill, 543, 544, 545, **558**, 772, **795**
 Kreusler, 456, 473, **493**
 Kreuzhage, 266, 267, **299**
 Kritzler, 575, **601**
 Krüger, F., 358, **397**
 Krüger, W., 501, **558**
 Kühne, 612
 Kuiper, 459, **493**
 Kunkel, 167, **172**
 Kunze, 125, **145**
 Kurz, 836, **845**
 Küster, 85, **92**
 Kuyper, 329, 330, 339, 341, **398**
- L**
- Laidlow, 328, **398**
 Lake, **42**
 Lakon, 532, 533, **558**
 Lalou, **661**
 Lamor, 336, **398**
 Langdon, 735, **791**
 Lanham, 257, **299**
 Lantz, 776, 777, 778, 780, **791**
 Lapique, 177, **227**
 Larson, 252, **299**
 Laskovsky, 592, **599**
 Latshaw, 232, 245, 247, 254, 266, 272,
 279, **299**, 454, 500, **558**
 Lau, 126, **145**
 Laurent, E., 522, **558**
 Laurent, J., 239, **299**
 Lavison, 64, **92**, 165
 Lawes, 507, **558**
 Lawrence, J. V., 29, 30, 31, 32, 34, **44**,
45, 182, **225**
 Lawrence, Z. W., **45**
 Lea, 646, **663**
 Leathes, 572, **599**
 Leavenworth, 524, **560**
 LeClerc, 537, 538, **555**, **558**, 713, **725**
 Leclerc du Sablon, 582, 589, 592, 594,
599, 681, 702, **725**

- Lee, B., 11, **46**
 Lee, H. A., 111, 115, **145**
 Legg, A. T., 834, **841**
 Legg, V. H., 12, **46**
 Lehenbauer, 821, **845**
 Leick, 331, **398**
 Leitbeg, 329, **398**
 Leitch, 821, **845**
 Lemmerman, 459, **488**
 Lemmermann, 268, **299, 303, 493**
 Lemoigne, **300**
 Lepeschkin, 16, **46, 76, 79, 80, 82, 92, 93, 389, 398**
 Lepkovsky, 7, **49, 524, 525, 562**
 Lesage, 345, **398**
 Leukel, 700, 701, **724, 725**
 Levene, 574, 579, **599**
 Levine, 283, **299**
 Lewin, 704, **725**
 Lewis, 578, 806
 Lewitsky, 25, **46**
 Leydhecker, 276, **299**
 Liebig, 125, **145, 444, 451, 452, 493**
 Likiernik, 579, **580, 601**
 Lilienfeldt, 99, 100, **145**
 Lindet, 413, 417, **493**
 Lindow, **303**
 Lindstrom, 241, **299**
 Ling, 415, **493, 652, 663, 665**
 Linossier, 775, **791**
 Lintner, 624, **663**
 Linz, 651, **663**
 Lipman, 236, 243, 251, 270, 279, 284, **295, 299, 305, 507, 509, 538, 558**
 Livingston, **93, 105, 132, 133, 143, 144, 145, 156, 162, 163, 166, 169, 172, 173, 194, 196, 197, 199, 207, 213, 227, 230, 328, 329, 338, 341, 346, 347, 350, 356, 370, 371, 372, 373, 374, 378, 379, 394, 398, 399, 402, 451, 493**
 Lloyd, 88, **93, 326, 328, 329, 339, 341, 399**
 Loeb, J., 218, **227, 515, 558, 809, 810, 845**
 Loeb, W., 446, **493**
 Loew, 246, 249, 251, 252, 253, 256, 275, **299, 775, 777, 778, 779, 791**
 Loftfield, 327, 329, 330, 331, 332, 339, 340, 341, 342, 368, 377, **399**
 Loiseleur, 608, **661**
 Lomanitz, 277, **299, 300**
 Long, E. R., 754, **791, 792, 826, 845**
 Long, F. L., 16, **46, 470, 478, 493**
 Long, F. W., 328, **399**
 Loo, **227**
 Loomis, **845**
 Lovenhart, 767, **790**
 Lowsma, 534, **562**
 Lubimenko, 462, 465, 466, **493, 494**
 Lubrzynska, 585, **601**
 Lukaszewicz, 254, **300**
 Lund, 742, **791, 836, 845**
 Lundegårdh, 453, 454, 456, **494**
 Lunn, **143**
 Luthra, 754, **791**
 Lutman, 31, 34, **46, 253, 300, 360, 399, 755, 756, 757, 791**
 Lyman, 633, 634, 635, **661**
 Lyon, C. J., 246, **300, 764, 765, 791, 792**
 Lyon, M. E., 758, **792**
 Lyon, T. L., 127, 129, **141, 145, 539, 558**
- M
- MacDaniels, 165, **172, 670, 722**
 MacDougal, 16, **46, 86, 88, 93, 172, 415, 455, 494, 496, 599, 673, 674, 675, 677, 682, 684, 687, 689, 690, 691, 706, 713, 725, 754, 792, 799, 800, 822, 826, 845, 846**
 MacGillivray, 245, 246, **300**
 Macht, 627, 628, **662, 828, 846**
 MacLean, H., 574, 579, 582, **600**
 MacLean, Ida, 574, 579, 582, **600**
 MacMillan, 806, **846**
 Maestrini, 614, **663**
 Magistad, 30, **46, 281, 300**
 Magistris, 579, **598**
 Magness, 749, 750, 756, 780, **792**
 Magnus, H., 9, **48**
 Magnus, von M., **48**
 Mahood, **46**
 Maige, 732, 758, **792**
 Mameli, 252, 261, **300, 508, 558**
 Maneval, **304**
 Mangel, **559**
 Mangelot, 576, **600, 792**
 Mangham, 712, **725**
 Mangin, L., 431, **488, 697, 725, 746, 787**
 Mangin, M. L., 3, 15, **46**
 Mann, A., 651, **663**
 Mann, C. E. T., 252, 257, **300**
 Maquenne, 284, **300, 415, 432, 455, 494, 592, 594, 600, 662, 738, 792**
 Marcano, 642
 Mariana, 318, **399**
 Markley, 519, **557**
 Marsh, R. P., 263, **300**

- Marsh, R. S., 258, **300**
 Marshall, 705, **723**
 Marslow, 626, **663**
 Marston, 25, **46**
 Martin, J. C., **148**, 209, 217, **226**
 Martin, J. H., 823, 824, **846**
 Martin, S. H., 35, 36, **46**
 Martin, S. H. C., 639, 640, **663**
 Martin, T. L., **145**
 Martin, W. H., 209, **229**, 285, **304**, 359,
 360, **399**, **401**
 Martinand, 614, **663**
 Masashi, 37, **47**
 Maskell, 269, **294**, 457, **494**, 690, 695,
 708, 710, 711, 712, 713, **725**, **726**
 Mason, S. C., 826, **846**
 Mason, T. G., **46**, 162, **172**, 440, **490**,
 690, 695, 704, 707, 708, 710, 711,
 712, 713, **725**, **726**
 Masoni, 38, **46**
 Massey, 132, **145**
 Masunaga, 182, **229**
 Mathew, 615, **663**
 Matthaei, 363, **394**, 459, 460, 463, 464,
 473, 476, **488**, **494**, 748, **792**
 Maximow, 323, 350, **399**
 Maxwell, 580, 581, **600**, **601**
 Mayer, 753, **790**
 Mazé, M., 592, **600**
 Mazé P., 239, 243, 265, 267, 281, 284,
300, 501, **559**
 McCall, 199, 204, 209, 214, 215, **227**,
 264, 285, **300**, 836, **846**
 McCallum, 254, **301**
 McCampbell, 701, **727**
 McClelland, 832, **846**
 M'Clenahan, 580, 586, **600**
 McCool, 30, 34, **47**, 109, 276, **301**
 McDermott, 640, **668**
 McDonnell, 273, **301**
 McDougal, 121, **145**
 McGee, 432, 443, 460, 473, **497**, **498**,
 733, 734, 763, **795**
 McGeorge, 276, **301**, 501, **559**
 McGinnis, 737, **792**
 McGuire, 614, 616, 618, **659**, **663**, **788**
 McHargue, 198, **227**, 243, 272, 273,
 274, 275, 283, 284, **301**, 775, **792**
 McIlvane, 214, **229**
 McKee, 130, **141**
 McKibben, **301**
 McLane, 835, **841**
 McLean, F. T., 238, 276, 279, 280, 286,
296, **301**, **303**, 476, **494**
 McLean, R. C., 191, 192, **227**, 370, **399**
 McMurtrey, 252, 271, **295**, **301**
 McRostie, **846**
 Meacham, 37, 38, **49**
 Meara, **658**
 Mehta, 6, 8, **47**
 Meier, 215, **227**
 Mellanby, 417, **494**
 Mendel, 640, 641, 642, **658**, **663**
 Mendiola, 191, 192, **227**
 Merkle, **144**
 Merz, 421, 424, **499**
 Metzger, 128, **145**
 Meuer, 182, **227**, 281, **301**
 Meyer, A., 415, 416, 417, 434, 435,
494, 532, **559**, 733, **792**
 Meyer, B. S., 30, 31, **47**, 380, **399**
 Meyers, A., 22, **47**
 Meyers, C. N., 279, **301**
 Michaelis, **93**, **663**
 Michiels, 275, **301**
 Middleton, 765, **792**
 Miede, 614, **663**
 Mikosch, 22, **47**
 Milad, 693, **721**
 Millar, 30, 34, **47**, 118, **145**
 Miller, C. F., 232, **304**
 Miller, E. C., 23, **47**, 107, 111, 115, 116,
145, 159, **172**, 232, 245, 247, 254,
 266, 272, 279, **299**, 311, 312, 315,
 319, 320, 322, 339, 345, 348, 349,
 355, 356, 360, 363, 365, 366, 367, 368,
 369, 377, 378, 384, 386, **399**, **400**,
 436, 439, 440, 454, 474, 475, 476,
 481, **494**, 500, 528, 529, 542, 543,
558, **559**, 588, 589, 590, 591, 592,
 593, **600**, 732, **792**, 803, 826, **846**
 Miller, E. V., 816, **841**
 Miller, H. G., 259, **301**
 Miller, M. F., 98, **145**, 286, **295**
 Miller, N. H. J., 502, 504, **557**
 Miller, R. W., **306**
 Minder, 462, **493**
 Minges, 275, **294**
 Mirasol, 280, **302**
 Mitchell, 540, **557**
 Mitscherlich, 373, **400**
 Miyake, 37, **47**, 280, **302**
 Mobius, 20
 Mockeridge, 505, **559**
 Mogensen, 316, **402**

Moillard, 455, **495**
 Molisch, 128, **146**, 260, 266, 282, **302**, 465,
495, 532, **559**, 676, 677, 681, 682, **726**
 Moll, 455, **495**
 Molliard, **146**, 240, **302**
 Molz, 72, 73, **93**, 167
 Montemartini, 361, **400**
 Montgomery, A. M., 353, **398**
 Montgomery, E. G., 384, 385, **400**
 Moore, B., 448, **495**, 508, 509, 522, **559**,
 767, **792**
 Moore, M. G., 568, **597**
 Moore, Wm., 697, **726**, 782, **792**
 Moravek, **93**
 Morgulis, **792**
 Morinaga, 780, **792**, 815, **846**
 Morison, 267, 268, **296**
 Morkrjetsky, 697, **726**
 Morris, 433, 435, 439, **489**, 614, 620, 621,
 625, 627, 630, 648, 651, **657**
 Morse, F. W., **302**, 749, **792**
 Morse, W. J., 132, **144**, 272, **302**, 677, 703,
725
 Moss, **295**
 Mottier, 22, 23, 25, **47**
 Moulton, C. R., 698, 699, **728**
 Moulton, S. C., **557**
 Mouton, 641, **659**
 Muenschler, 191, 192, 193, **227**, 340, 341,
400, 508, 533, **559**
 Mukerji, 137, **146**
 Müller, 470, **495**
 Müller-Thurgau, 101, **146**, 361, **400**, 533,
 534, **559**, 751, **792**
 Müntz, A., 501, **559**
 Müntz, M., 589, **600**
 Murneck, 8, **47**, 545, 546, **556**, 699, **726**,
 805, **846**
 Mussi, 644, **663**

N

Nagaoka, 274, **302**, 502, **559**
 Nägeli, 414, 415, **495**, 688, **726**
 Nakamura, 284, **302**
 Nanji, 652, **663**
 Nathansohn, 181, 182, **227**
 Naylor, 622, **663**, **666**
 Nazarova, 29, **45**
 Nef, 448, **495**
 Negelein, 442, 462, **499**, 522, **562**
 Neidig, 538, **559**, **663**
 Neller, 129, **146**, 272, **302**

Nelson, D. H., 233, 235, **296**, 538, **556**
 Nelson, J. M., 417, **498**, 615, 617, 619,
 635, **659**, **661**, **664**
 Nelson, N. T., 700, 701, **724**, **726**
 Nemecc, 283, **302**, 781, **793**
 Neumeister, 638, **664**
 Neun, 638, **666**
 Newcomb, 543, **559**
 Newcombe, 99, 100, **146**, 630, **664**, 764,
793, 820, **846**
 Newton, J. D., 126, **146**, 233, 235, **302**,
 357, **400**
 Newton, R., 823, **846**
 Nicholas, 450, **495**
 Nichols, 373, 374, **400**
 Nicloux, 634, **661**, **664**
 Nicolas, 259, **302**, 450, **495**, 732, 758, **792**,
793
 Nightingale, 544, 547, **560**, **846**
 Njegovan, 579, **600**
 Nobbe, 101, 110, **146**, 194, 242, 255, 276,
302
 Noble, 212, **230**
 Noll, 246, 247, **302**
 Nordenson, 579, **598**
 Nordhausen, 689, **726**
 Norris, 13, **42**, **47**
 North, 165, **172**
 Nottin, 413, 417, **493**

O

Oakley, **847**
 Oddo, 261, **302**, **303**
 O'Dwyer, 8, **47**
 Ohga, 28, **47**, 162, **172**, 811, **847**
 Olney, 732, 749, **793**
 Olson, 258, 260, **302**, **306**, 536, **560**
 Olsson, **664**
 Onslow, 768, 769, 775, **793**
 Oppenheimer, **793**
 Ormerod, **656**
 Orr, 236, **302**
 Osborne, T. B., 510, 511, 517, 518, 519,
 524, **560**, 622, 623, 625, **664**
 Osborne, W. A., **664**
 Osmaston, 825, **847**
 Osterhout, **47**, 67, 76, 78, 82, 83, 84, 87,
93, **94**, 174, 176, 218, 219, 220, **224**,
227, **228**, 282, 283, **302**, 447, 448, 460,
 463, 473, **495**, 731, 742, **793**
 O'Sullivan, 418, **495**, 615, 616, **664**
 Ota, **793**

- Otto, 529, **556**
 Overholser, 776, 779, **793**
 Overton, E., 85, **94**
 Overton, J. B., 170, **172**, 673, 674, 675,
 682, 684, 687, 691, **725, 726**
 Owen, 458, **495**
- P
- Paack, 576, **600**, 817, **847**
 Page, 508, **554**
 Paine, H. S., 615, 617, 618, 619, **662, 664,**
665
 Paine, S. G., **394**
 Palladin, V. I., 232, 267, **302**, 426, **495,**
 623, **665**
 Palladin, W., 428, **495**, 582, **600**, 623, **665,**
 731, 732, 733, 736, 738, 751, 754, **793,**
794, 847
 Pande, 803, **844**
 Pantanelli, 182, **228**, 452, 468, 469, **495,**
 502, **660**
 Parija, **787, 794**
 Parker, 127, **146**, 233, 236, 249, **302, 303**
 Parkin, 435, 438, 439, **495**
 Parrozzani, 580, **600**
 Paton, 652, **665**
 Paulino, 502, **562**
 Payen, 620
 Payne, 111, 116, **143**
 Pearsall, 178, **228**, 515, 516, **560**, 803, 809,
 810, 836, **847**
 Peirce, 329, **397**, 673, **726**, 736, 737, 747,
 748, **788, 794**
 Peklo, 651, **662**
 Pelbois, **656**
 Pelouze, 633, **665**
 Pember, **144, 145**, 200, **228**, 263, 280, 282,
 286, **297, 298, 303**
 Penrose, **847**
 Peralata, 137, **146**
 Perciabosco, 503, **560**
 Perrey, 439, **495**
 Perrier, 239, **300**
 Persecke, **146**
 Persoz, 620
 Pertz, 328, **396**
 Peters, 588, 592, **600**
 Peterson, C. B., 245, 247, **303**
 Peterson, W. H., 245, 247, 257, 258, **296,**
303, 408, 420, **499**
 Petrie, 25, **45**, 178, 179, **224**, 650, **661**
 Pettibone, 718, **726**
 Pfeffer, 66, 86, **94**, 190, 194, 195, **228, 240,**
 241, 242, 267, 274, **303**, 441, 452, 473,
496, 736, 741, **794**, 807
 Pfeiffer, F., 127, **146**
 Pfeiffer, T., 238, 277, 282, **303**
 Pfenniger, 7, **48**
 Pfothenhauer, 238, 282, **303**
 Phillips, 685, **723**
 Pickering, 131, 135, 136, **146**
 Pickler, 652, **665**
 Piemeisel, 384, 385, **401**
 Pierre, I., 267, **303**
 Pierre, W. H., 236, **303**, 701, **726**
 Pieters, **847**
 Pigorini, 529, **560**
 Pincussen, 627, **665**
 Piper, 274, **304**
 Pirschle, 594, **600**
 Pitra, **305**
 Pitsch, 501, **560**
 Pitz, 259, **303**
 Plaetzer, 460, **496**
 Platt, 641, 642, **665**
 Plester, 466, **496**
 Poirault, 19, **47**
 Polak, 626, **665**
 Policard, 576, **600**
 Politis, 25, **47**
 Pollacci, 261, **302, 303**, 332, **395**, 455, **496,**
 508, **558**
 Polle, 98, **146**
 Pond, 651, **665**
 Pool, 344, 345, **400**
 Poole, 442, 446, **490**
 Popenoe, **44**
 Popoff, 623, **665**
 Popova, 623, **665**
 Popp, 827, 829, **847**
 Porodko, 99, 100, **146, 147**
 Porterfield, 803, 825, **847**
 Porthheim, 248, **296**
 Potter, 747, **794**
 Powell, 22, **47**
 Powers, 158, **172**, 259, 260, **303**, 836,
847
 Pozerski, 641, 643, **659, 665**
 Pozzi-Escot, 523, **560**
 Prantl, 806, **847**
 Prazmowski, 507, **560**
 Prescott, 825, **847**
 Prianischnikov, 137, **147**, 251, 279, 280,
303, 501, 503, 533, **560**

- Priestley, J. H., 3, 9, 10, 11, 20, 27, 46, 47, 49, 165, 166, 168, 172, 440, 442, 446, 447, 496, 499, 515, 516, 560, 575, 585, 600, 678, 679, 726, 766, 791, 798, 799, 800, 803, 810, 824, 825, 834, 838, 844, 847, 850
- Priestley, Joseph, 429, 430, 496
- Pringsheim, 9, 48
- Prunet, 621, 665
- Pugh, 507, 558
- Pulling, 162, 169, 172, 350, 400
- Puriewitsch, 478, 479, 480, 496, 651, 652, 665
- Q
- Quirk, 35, 36, 48
- R
- Raber, 83, 94, 219, 228, 535, 560, 801, 847
- Rabkin, 792
- Raciborski, 128, 147
- Randolph, 23, 24, 48
- Rankin, E. J., 264, 306
- Rankin, W. H., 697, 726
- Raper, 572, 599
- Ravenna, 504, 554
- Ravin, 241, 303
- Ray, 761, 794
- Rea, 35, 36, 46, 322, 400
- Read, 148
- Redfern, 182, 185, 186, 187, 228
- Reed, E., 848
- Reed, G. B., 768, 770, 772, 776, 779, 794, 795
- Reed, H. S., 34, 35, 38, 48, 128, 132, 134, 147, 177, 186, 188, 225, 228, 237, 244, 246, 249, 251, 252, 253, 255, 256, 264, 296, 303, 357, 361, 400, 650, 665, 803, 805, 810, 818, 836, 848
- Regeimbal, 761, 795, 818, 848
- Rehfous, 318, 400
- Reichert, 413, 417, 418, 496
- Reid, F. R., 133, 145, 233, 272, 305
- Reid, M. E., 549, 550, 560
- Reimer, 258, 259, 303
- Renner, 166, 169, 172, 346, 354, 400, 688, 689, 726, 727
- Rhine, J. B., 594, 600, 714, 715, 716, 727
- Rhine, L. E., 776, 780, 795
- Rhodes, Anna, 99, 100, 146
- Rhodes, E., 10, 48, 165, 172
- Rich, 105
- Richard, 665
- Richards, E. H., 506, 561
- Richards, H. M., 455, 496, 745, 747, 755, 795
- Richards, P. E., 285, 300
- Richardson, A. E. V., 386, 400
- Richardson, W. D., 233, 266, 304
- Ricome, 357, 400
- Ridgway, 123, 147
- Riedel, 458, 488, 496
- Riesenberg, 450, 496
- Rigg, 123, 147
- Rippel, 238, 276, 282, 304, 400, 459, 496, 803, 848
- Rischawi, 795
- Ritter, 3, 9, 48
- Rivett, 576, 600
- Roach, 240, 304
- Roark, 273, 301
- Robbins, W. J., 178, 213, 214, 228, 240, 241, 304, 515, 516, 560, 848
- Robbins, W. R., 304
- Roberts, E. A., 30, 123, 147, 162
- Roberts, H. F., 539, 540, 561
- Roberts, R. H., 7, 49, 545, 549, 561
- Robertson, A., 648, 649, 665
- Robertson, R. A., 613, 665
- Robertson, T. B., 803, 848
- Robinson, M. E., 561, 793, 795
- Robinson, W. O., 232, 272, 304
- Rockwood, 542, 553
- Rogers, 703, 727
- Rohmann, 795
- Rolf, 574, 579, 599
- Roller, 505, 555
- Rollo, 736
- Römer, 287, 307
- Rosa, 822, 824, 848
- Rose, D. H., 772, 773, 795, 848
- Rose, R. C., 772, 788, 795, 816, 817, 837, 843, 848
- Rosenberg, 780, 795, 796
- Rosenblatt, 272, 293
- Roshardt, 684, 685, 727
- Rosso, 503, 560
- Rothgeb, 752, 755, 788
- Rothstein, 663
- Rotmistrov, 111, 147
- Rotunno, 819, 848
- Roux, 415, 494, 663

- Rudolfs, 182, 185, **228**, 277, 278, **304**, 819
848
 Rudolph, 25, **48**
 Ruggles, 697, **726**
 Ruhland, 82, 85, **94**, 182, **228**, **727**
 Ruot, **300**
 Rumbold, 697, **727**
 Rumm, 358, **400**
 Ruprecht, 280, **304**
 Russel, 115, **145**
 Russell, E. J., 116, 127, **147**, 246, 255,
304, 506, **561**
 Russell, J. B., 642, **665**
 Ryan, 38, **43**
 Rybin, 350, **399**
 Ryszelberghe, 79, 80, 86, **95**
- S
- Sabalitschka, 450, **496**
 Sablon (*see* Leclerc du Sablon).
 Sachs, 22, 125, **147**, 154, **172**, 190, 194,
 195, **228**, **229**, 242, 266, **304**, 336,
 430, 434, 472, 473, 474, 476, **496**,
 592, **600**, 685, 692, 713, **727**, 806,
 807, **848**
 Saeger, 505, **561**
 Salisbury, 318, 319, 322, 323, **401**
 Salmon, 701, **727**, 822, 823, 824, **843**,
848, **849**
 Salter, 214, **229**, 238, **304**, 376, **397**
 Samec, 415, 417, **496**
 Sammett, **299**
 Sampson, 351, **401**
 Samuel, 274, **304**
 Sande-Bakhuyzen, 803, **848**, **849**
 Sando, 564, 574, **600**
 Sanford, 697, **727**
 Sani, 128
 Saposchinkoff, 469, **496**
 Sapoznikow, 532, **561**
 Sargant, 648, 649, **665**
 Saunders, 355, 363, 365, 366, 367, 368,
 369, **400**
 Saussure, De, 429, 430, 431, **496**, 506, 587,
 588, 592, **598**, 739, **795**
 Sawa, 275, **299**
 Sawyer, 408, 433, 435, 439, **490**
 Sayre, 316, 324, 325, 326, 327, 330,
 332, 333, 334, 336, 343, 344, **401**,
 427, **497**
 Scarth, 327, **401**
 Schaffner, 831, **849**
 Schander, 358, **401**
 Schanz, 827, **849**
 Scheele, 429
 Schenker, **665**
 Scherer, 697, **727**
 Schertz, 421, 424, 427, 429, **497**, **499**
 Schillbach, **303**
 Schimper, 20, 22, **48**, 194, **229**, 248,
 255, **304**, 416, 434, 435, **497**, 522
 Schlesinger, 622, 623, **665**, **666**
 Schley, **849**
 Schloesing, 190, **229**
 Schmidt, E. W., 9, 25, **48**, 276, **304**
 Schmidt, R. H., 588, **600**, 714, 715, **727**
 Schmitz, 613, **665**
 Schneiderhan, 132, **147**
 Schneider-Orelli, 708, **727**
 Schoenbein, 766, 775, **795**
 Schollenberger, 268, **304**
 Schramm, 508, **561**
 Schreinmocher, 204, **229**, 275
 Schreiner, 128, 132, 134, 135, **147**, 204,
229, 245, **304**, 504, **561**
 Schröder, J., **302**, 705, **727**
 Schröder, H., 63, 64, **95**
 Schroeder, 467, **497**
 Schroger, **48**
 Schryver, L. B., 415, 447, **497**
 Schryver, S. B., 8, 13, 14, **42**, **47**, **48**,
489, **497**, 524, **554**
 Schultz, 503, **561**
 Schulz, E. R., 524, 525, **562**
 Schulz, M., 542, **561**
 Schulze, B., 111, **147**, 283, **304**, 529,
 531, **561**
 Schulze, E., 7, **48**, 534, **561**, 579, 580,
 581, **601**, 718, **727**
 Schürhoff, **48**
 Schuster, 256, 257, **304**
 Schütz, 529, 531, **561**
 Schwarz, 119, 122, 123, **147**
 Schweigart, 626, **661**
 Schwendener, 318, 324, **401**, 681, **727**
 Scofield, 193, **229**
 Scott, 165, **172**, **173**
 Scurti, 586, **601**
 Sears, 281, **294**
 Seelhorst, 98, 101, **147**, **148**
 Seifrizz, 15, **48**, 66, 67, **95**
 Sekine, 522, **553**
 Sellschop, 823, **849**
 Semmens, 627, 628, **657**, **665**
 Sen, 81, **95**

- Senebier, 429, 430, **497**
 Senft, **305**
 Severini, 502, **560**
 Sewell, 132, 135, **148**, 211, **229**
 Shantz, 152, 153, 154, 155, 157, 158,
 159, **171**, 312, 347, 350, 351, 352,
 353, 354, 370, 371, 373, 374, 375,
 377, 378, 384, 385, 386, 388, **395**,
 401
 Sharp, 16, **48**
 Sharrer, 236
 Shattuck, 697, **727**
 Shaw, 538, **561**
 Shedd, 33, **48**, 260, **304**
 Sheloumova, 754, **794**
 Shepperd, 111, **148**
 Sherman, H. C., 620, 621, 622, 623,
 625, 626, 638, **665**, **666**
 Sherman, Hope, 744, 780, 782, **795**
 Shirley, 827, **849**
 Shive, 107, **141**, 156, **173**, 194, 195, 198,
 199, 200, 204, 208, 209, 210, 212,
 213, 214, 216, **224**, **226**, **229**, 262,
 263, 264, 285, **293**, **298**, **300**, **304**,
 305, 360, 373, **401**
 Shohl, 419, **497**
 Shorey, 134, **147**, 579, **601**
 Shreve, E. B., 339, 345, 346, 355, 363,
 374, 379, **399**, **401**
 Shrevc, F., 689, **725**, **846**
 Shull, 63, 64, 87, **95**, 160, 162, 163, 166,
 168, **173**, **305**, 682, **727**, 762, 763,
 782, **795**
 Shulov, 277, **305**
 Shulvo, 503, **561**
 Sideris, 182, **229**
 Sidorin, 265, **305**
 Siegert, 276, **302**
 Siegfried, 444, **497**
 Sigmund, 633, **666**
 Simon, 697, **727**
 Singh, L., 6, **48**
 Singh, S. B., 803, **844**
 Sinnott, 577, 578, **601**
 Sjöberg, 621, 626, 627, **666**, **667**
 Skene, 184, **229**
 Skinner, 132, 134, **145**, **147**, **148**, 204,
 229, 233, 272, **305**, 504, **561**
 Small, J., 35, 36, **46**
 Small, T., 458, **495**
 Smedley, 585, **601**
 Smith, A. M., 367, **401**, 456, **488**, **497**,
 754, **795**
 Smith, E. F., 35, 36, **48**, 685, **727**
 Smith, E. P., 760, 765, **795**
 Smith, G. M., 16, **46**, 674, 675, 684, 687,
 691, **725**
 Smith, H. B., 329, **401**
 Smith, J. B., **144**, 673, **726**
 Smith, J. G., 255, 268, **296**
 Smith, R. S., 129, **145**
 Smith, T. O., **305**, 702, **722**
 Smolenski, 579, **601**, **602**
 Snow, L. M., 122, **148**
 Snow, R., **727**
 Snyder, 538, **559**
 Sommer, A. L., 243, 250, 267, 270, 271,
 305
 Sommer, W., **660**
 Sorauer, **229**
 Sörensen, 637, 638, **667**
 Sorokin, 250, 271, **305**
 Spaeth, 88, **95**
 Spalding, 122, **148**, 150, **173**, **401**
 Spencer, 622, **663**
 Spirgatis, 459, **497**
 Spitzer, G., 536, **561**
 Spitzer, W., **795**
 Spoehr, **46**, 408, 429, 432, 433, 441, 443,
 444, 445, 446, 447, 448, 450, 451,
 453, 460, 462, 473, 477, 482, **497**, **498**,
 561, 733, 734, 763, 764, 765, **795**, 799,
 845
 Sponsler, 4, **48**, **49**, 416, **498**
 Stadler, 828, **849**
 Stahl, A. L., **229**
 Stahl, E., 190, **229**, 332, 379, **401**
 Stanescu, 437, 469, **498**
 Stanewitsch, 582, **600**
 Stange, 28, **49**
 Stanton, 813, **842**
 Stark, O. R., 57, 58, **95**, 718, **727**
 Stark, R. W., 538, **561**, 584, 586, **601**
 Starring, 549, **561**
 Stefan, 336, **401**
 Stegmann, 579, **602**
 Steiger, 580, 581, **601**
 Steinkoenig, 232, **304**
 Stern, A. L., **49**
 Stern, H. J., **553**
 Steward, 75, **95**, 580, **601**, 709, **728**
 Stewart, C. R., 501, **561**
 Stewart, G. R., **148**
 Stewart, G. N., 76, **95**
 Stewart, J., 260, 284, **305**
 Stewart, R., **305**

- Stich, 742, 755, 762, **795**
 Stieler, **148**
 Stiles, 66, 77, 78, 80, 84, 87, **95**, 177, 181, 182, 183, 187, 188, 198, 199, 208, 216, 218, **229**, **230**, 421, 433, 442, 457, 459, 460, 462, 465, **492**, **498**, 834, **844**
 St. John, E., **661**
 St. John, J. L., 258, 260, **302**
 Stoa, 130, **141**
 Stockberger, 774, **796**
 Stocklasa, 125, 126, **148**, 254, 255, 256, 281, **305**, **306**, 446, **498**, 580, **601**, 736, **795**
 Stolhane, 209, **230**
 Stoll, 261, **307**, 432, 442, 444, 445, 463, 466, 468, 473, 476, **499**
 Stone, 622, **667**
 Stout, A. B., 24, **49**
 Stout, G. J., **142**
 Stoward, 615, **667**, **795**
 Strasburger, **601**, 683, 684, 685, 686, **728**
 Strausbaugh, 823, **849**
 Strobel, 236
 Strowd, 521, **561**
 Strugger, 327, **402**
 Stuart, 236, **302**
 Stutzer, 503, **561**
 Sugiura, 634, **659**
 Sullivan, 128, **147**
 Summers, **849**
 Surface, 697, **728**
 Suzuki, U., 528, 531, 533, **562**
 Suzuki, V., 283, 284, **306**
 Swanback, **306**
 Swanson, **306**, **667**, 701, **727**
 Swingle, 808, **849**
 Szűcs, 281, **306**
- T
- Tait, 638, **667**
 Takamine, 620, **667**
 Tammann, 464, 465, **498**
 Tanberg, 620, **666**
 Tangl, 76, **91**
 Tanka, 612, **667**
 Tarr, 212, **230**
 Tartar, 258, 259, **303**
 Tashiro, 742, **796**
 Taylor, A. E., 569, 573, **597**, 633, **667**
 Taylor, G. S., 737, **792**
 Taylor, J. K., 507, 509, **558**
 Taylor, T. C., 417, **498**
 Ten Eyck, 111, **148**
 Tenney, 134, **148**
 Terroine, 586, **601**, **796**
 Thatcher, **49**, 137, **148**, **306**, 411, 420, 423, **498**, 500, 512, 536, 538, **562**, 594, **601**, 609, 612, 622, 632, **667**, **849**
 Thielmann, 352, **397**
 Thoday, 167, **173**, 467, 475, **498**, 742, 760, **796**
 Thom, 384, **402**
 Thomas, A. W., 415, **498**, 625, 626, **666**, **667**
 Thomas, E. C., **561**
 Thomas, E. E., 697, **728**
 Thomas, E. M., 8, **48**, **497**
 Thomas, H. S., 760, **796**
 Thomas, M., **796**
 Thomas, N., 374, **402**
 Thomas, W., 522, 523, 526, 527, **562**
 Thompson, 718, **728**
 Thone, 373, **399**
 Thornton, 243, 271, **293**
 Thut, 689, **728**
 Timiriazeff, 461, 478, **498**
 Tincker, 828, 830, **849**
 Tinker, **91**
 Tisdale, 104, **148**
 Tjebbes, 63, **95**, 830, **849**
 Tollens, **43**, 194, **230**
 Tommasi, 586, **601**
 Tompson, 615, **664**
 Toole, 215, **230**, 713, 714, **728**
 Torrey, 648, 650, **667**
 Tottingham, 7, **49**, 194, 195, 196, 197, 200, 201, 204, 205, 206, 208, 210, 213, 215, **227**, **230**, 252, 259, 260, 263, 264, 277, 278, 279, **296**, **306**, 524, 525, 534, 539, **562**
 Transcau, 378, **402**, 481, **498**
 Traub, 700, **728**
 Traube, M., 766, **796**
 Treboux, 501, **562**
 Treitel, 108, **148**
 Trelease, H. M., 207, 219, **230**
 Trelease, S. F., 198, 199, 207, 208, 219, **230**, 277, 279, **306**, 328, 338, 374, **402**, 502, **562**, 825, 826, **841**
 Tröndle, 82, **95**
 Trost, 281, **297**
 Trowbridge, 698, 699, **728**
 True, R. H., 85, 189, 218, **230**, 237, 249, 250, **306**, 774, **796**

- Trumpf, 825, **849**
 Truog, 30, 37, 38, **46, 49, 233, 245, 249,**
 280, **302, 306**
 Tschirch, 575, **601, 808, 849**
 Tsweet, 426, **498**
 Tucker, 98, **148**
 Tupper-Carey, 3, **49, 166**
 Turner, 102, **148, 548**
 Turpin, 126, **148**
 Tutin, 13, 14, **49**
 Tuttle, 578
 Twiss, 23, **49**
 Tychowski, 626, **665**
- U
- Ullrich, 532, 533, **562**
 Underhill, 640, **663**
 Underwood, L. E., 199, 208, 209, **225**
 Underwood, L. M., 104, **143**
 Unger, 370, **402, 685, 728**
 Uphof, 830, **849**
 Ursprung, 68, 72, **95, 96, 167, 366, 402,**
 461, 468, 469, **498, 499, 681, 688, 728**
 Usher, 442, 446, **447, 499**
- V
- Vacha, 761, **795, 814, 849**
 Vagi, **555**
 Valentine, **45**
 Vallee, 586, **601**
 Van Slyke, 637
 Van Wisselingh, 9, **49**
 Veihmeyer, 98, **142, 173**
 Ver Hulst, 408, 420, **499**
 Verschaffelt, 380, **402**
 Vesque, 685, **728**
 Vieser, 449, **491**
 Ville, G., 427, **499**
 Ville, M. G., 506, 508, **562**
 Vines, 623, 638, 639, 640, 644, 645, **667,**
 685, **723, 728**
 Vinson, 614, 619, **667**
 Vivian, 537, **563**
 Voegtlin, 279, **301**
 Voelcker, 270, **307**
 Vogel, 501, **556**
 Vogt, 826, **849**
 Von Fürth, 591, **601**
 Von Mohl, 323, **402, 430**
 Von Schmidt, **49**
 Vosburgh, 617, 618, **663, 667**
- W
- Wager, 447, **499**
 Wakabayashi, 758, **796**
 Wakeman, 524, **560**
 Wakker, 575, **601**
 Waksman, 134, **148, 667**
 Walbridge, 253, **300**
 Walker, F., 621, **666**
 Walker, J. A., **666**
 Waller, A. D., 835, **849**
 Waller, J. C., 835, **849**
 Walster, **849**
 Walters, 538, **561**
 Walton, 615, **665**
 Wangler, 519, **557**
 Wann, 264, **297, 508, 562, 697, 728**
 Wanser, **849**
 Warburg, 261, **307, 442, 456, 460, 462,**
 499, 522, 562, 765, 796
 Ward, 629, **667**
 Warington, 243, 269, 270, 271, **294, 307**
 Warner, C. H., 447, **499**
 Warner, J. D., 111, **142**
 Wartenberg, 633, **658**
 Wassilieff, 534, **562**
 Wayman, 625, **666**
 Weatherwax, 199, **230, 419, 499**
 Weaver, 97, 98, 102, 107, 109, 110, 111,
 112, 113, 114, 117, 121, **142, 144,**
 148, 149, 316, 361, 362, 402, 832,
 850
 Weber, C., **499**
 Weber, F., 327, **402**
 Webster, J. E., 521, 522, **562, 580, 602**
 Webster, T. A., 448, **495, 559**
 Weevers, 254, **307, 439, 440, 499**
 Weidling, 450, **496**
 Weigand, 343, **402**
 Weimer, 11, **49, 824, 850**
 Weiss, A., 318, 362, **402**
 Weiss, F., **402, 638, 667, 779, 796**
 Weizmann, 255, **307**
 Weldon, 30, **47**
 Wells, 537, **563**
 Wessels, 282, **297**
 West, C., 758, **791, 803, 805, 819, 823,**
 841, 844, 845, 850
 West, E. S., 279, 284, **299**
 Wester, 273, **307**
 Westermaier, 680, **728**
 Westover, **847**
 Wetzell, 151, **173**

- Wheeler, H. J., 252, 279, 282, **297**, **307**
 Wheeler, R. V., 12, **46**
 Wheldale, 774, **796**
 Wherry, 233, **307**
 Whimster, 766, **796**
 Whitaker, 121, **149**
 White, 614, 638, **667**, **668**, 752, **796**
 Whitley, **559**, 767, **792**
 Whitney, **149**
 Whitson, 537, **563**
 Whitten, 64, **96**
 Wierzchowski, 629, **668**
 Wiesner, 427, **499**
 Wiessmann, **299**
 Wiggins, 325, **402**
 Wilcox, **307**
 Wilfarth, 287, **297**, **307**, 507, **557**
 Wilkins, 247, **307**
 Will, **660**
 Willaman, 419, **499**, 741, 757, 763, 782,
 786, **792**, **796**
 Williams, Maud, 828, **850**
 Williams, P. H., 458, **495**
 Willis, 265, **307**, 503, **563**
 Willstätter, 252, 261, **307**, 421, 423,
 425, 432, 442, 444, 445, 463, 466,
 468, 473, 476, **499**, 608, **668**
 Wilson, B. D., 136, **149**, 506, **563**
 Wilson, H. W., 354, **402**
 Wilson, J. B., 271, **295**
 Wilson, J. D., 162, **172**, **173**, 356, **399**
 Wilson, J. K., 129, 136, **145**, **149**, 390, **402**
 Wilson, W. E., **489**
 Wimmer, 287, **307**
 Winkler, 470, **499**
 Winterstein, 534, **561**, 579, **602**
 Wodehouse, 78, **96**, 176, **231**
 Woffenden, 11, **47**, 838, **850**
 Wolfe, H. S., 505, **563**
 Wolfe, T. R., 814, **850**
 Wolff, E., 266, 267, **299**
 Wolff, J., 261, **307**, 415, **491**, 628, **668**
 Wollney, 190, **231**
 Woo, 521, **563**
 Wood, F. M., 4, 6, **49**
 Wood, J. G., 151, **173**
 Woodard, 260, **307**
 Woods, 370, **402**, 773, **796**
 Woodward, 194, **231**
 Worley, 86, 87, **91**
 Wormall, 27, **47**, **49**
 Wortmann, 109, **149**
 Wrangell, M. von, 233, 235, 245, **307**
 Wurdack, **49**
 Wurmser, 462, **499**
 Wurtz, 639, 640, **668**
 Wyatt, 251, **307**

Y

 Yamano, 280, **307**
 Yap, 468, 469, **499**
 Yapp, 322, **402**
 Yocum, 713, **728**
 Yoder, 538, **558**
 Yoshida, 768, **796**
 Youden, 185, **224**
 Young, 628, **668**
 Yuncker, 355, **402**, 468, **499**

Z

 Zacharowa, 824, **850**
 Zalenski, 323, 330, 347, **402**, **403**, 581, **602**
 Zaleski, 532, 535, **563**, 738, 780, **796**
 Zavitz, 129, **149**
 Zdobnický, 446, **498**
 Zerban, **796**
 Zhemchuzhnikov, 341, **403**
 Zimmerman, 832, **850**
 Zirkle, 20, 21, 24, **49**, 416, **499**
 Zucker, 358, **403**

SUBJECT INDEX

A

- Absolute transpiration, 374
Absorbing gradient, 167
Absorbing power, 72
Absorption, active, 176
 of CO₂ by leaf, 443
 depth by roots, 116
 passive, 169, 175
 ratio, definition, 179
 factors affecting, 179-182
 of solutes, 174-221
 of water, 150-170
Accelerator, 611
Accessory cells, 317
Acetaldehyde, 594
Acetamide, utilization, 504
Acetic acid, 404, 566
 excreted by roots, 125
 formula, 566
 relation to invertase, 619
 to lipase, 635
 to protein formation, 249
 to respiration, 735
Acetyl value, 753
Achrodextrin, 419
Acid (*see* various kinds).
Acid value of fat, 572
Acidity, of cell sap, 35-39
Acids, influence on transpiration, 357
Activated formaldehyde, 449, 520
Activator, 611
Active regulation of stomata, 337
Adamkiewicz's reaction, 515
Additive effects, 219
Adenine, in plants, 541
 in soil, 134
Adrenalin, 765
Aeration, influence on decay, 134
 relation to temperature, 106
 response of roots, 107
 of soils, 103-106
 by water plants, 104
 of water cultures, 104, 199
Aerial conditions, relation to transpiration, 350-354
Aerobic respiration, 735-739
Aesculin, 631
After-ripening, 815-818
 changes during, 816
Age, relation to elemental requirements, 284-289
Air temperature, 364
Alanine, formula, 513
 in soil, 134
 in tomato, 523
 utilization, 504
Albino plants, 241
Albumins, 517
Alcohol *vs.* petroleum, 482
Aleurone, 510
Aleurone grains, 510
Aleurone layer, 510
 of corn, 648-651
Alfalfa, absorption of elements, 237
 acidity of sap, 36
 calcium content, 247, 249
 —Mg ratio, 251
 enzymes of, 613
 crepsin of, 645
 H-ion concentration and growth, 836
 iodine content, 236
 leaf structure, 313-314
 temperature, 365
 lithium content, 225
 manganese content, 273
 oil of stem and leaves, 578
 organic compounds, 700
 oxidases of, 769
 phosphorus, absorption, 245
 content, 257-258
 proteins, conjugated, 519
 of leaf, 524
 root hairs, 30, 124
 roots, 109, 111, 115, 138
 seed coat, 64
 solubility of inorganic salts, 238
 stomata of, 317, 321-322
 type, 331

- Alfalfa, strontium, content, 225
 sulphur content, 257-258
 response to, 259-260
 temperature of leaves, 365
 titanium, response to, 283
 transpiration, 312, 352, 370, 375
 water culture of, 214
- Algae, aeration by, 104
 fixation of nitrogen, 508
- Alkalis, influence on transpiration, 357
- Alkaloids, 26, 404, 541
- Alloxan, 504
- Almond, oil formation, 583
 seed coat, 60
- Aluminum, 233, 279
 function in cell, 281
 influence on growth, 280
 on plant life, 280-282
 on soil relationships, 280
- Amandin, 517
- Amaranthus, 312, 350, 352, 746, 774,
 778, 781, 812, 829
- Ambrosia, 313
- Amides, 513
- Amines, 504, 540
- Amino acids, classification, 513
 described, 512
 influence on diastase, 626
 in protein formation, 512, 523
 in protoplasm, 799
 in respiration, 734
 in seedlings, 718
 in seeds, 519
 utilization, 504
- Ammoniacal nitrogen, in air, 506, 509
 utilization, 501-503
- Ammonium salts, in plant nutrition,
 501-503
- Ampholyte, 178
- Amygdalin, 631
- Amylase (*see* Diastase).
- Amylo-cellulose, 414
- Amylodextrin, 419
- Amylopectin, 415
- Amyloses, 415
 (*See also* Starches.)
- Amylum (*see* Starch).
- Anaerobic respiration, 735-739
- Anesthetics, relation to guttation, 389
 permeability, 83-84
 photosynthesis, 432
 respiration, 760-762
- Anions, absorption, 182-184, 187-190
 influence on permeability, 83
- Antagonism, 218-221
 of chlorine, 279
- Anthocyanin, 26, 774
- Antienzyme, 611
- Apple, acidity, 35, 185
 affected by walnut, 132
 catalase, 782
 CO₂ exhaled, 749-750
 crepsin, 645
 fruit-bud formation, 545
 influence on other plants, 131
 movement of solutes, 695
 organic reserves, 700
 oxidases, 769, 772-773
 respiration, 749, 751, 756
 respiratory quotient, 745-746
 seed coats, 63
 stomata, 321
 transpiration, 361
 water content of leaf, 309
- Appleman's diastase method, 624
- Araban, 420
- Arabinose, 7, 408, 420
- Arachidic acid, 566
- Arachin, 517
- Arbutin, 631
- Arginine, action on diastase, 626
 formula, 513
 in seeds, 534-536
 in soil, 134
 utilization, 504
- Arsenic, in nutrition, 283-284
- Artichoke, 180, 183, 630, 645, 832
- Artificial ripening, 817
- Asafoetida, 595
- Ascent of water, 675-689
 under low evaporation, 676
 under high evaporation, 679
- Asparagine, defined, 513
 in leaves, 532
 in respiration, 734
 in seeds, 534-535
 utilization, 734
- Asparagus, cytase, 630
 oxidases, 769
 relation to chlorine, 278
 respiration, 754, 757
 seeds, 3, 812
- Aspartic acid, action on diastase, 626
 formula, 513
 in tomato, 523

Aspartic acid, utilization, 504
 Assimilation number, 466
 Assimilation quotient, 431
 Atmometer, defined, 371
 free water surface, 372
 moist porous surface, 373
 standardization, 374
 Atropine, 541
 Auximones, 504-506
 Avenalin, 517

B

Baeyer hypothesis, 445
 Balanced solutions, 218-221
 Barium, 283
 Bark, translocation in, 711
 Barley, absorption, depth, 117
 of elements, 237
 of ions, 183, 188-189
 acidity, 185-186
 CO₂ fertilization, 458
 production, 127
 composition, 235
 cytase, 626
 distribution of elements, 238
 etiolation, 466
 erepsin, 645
 formation of grain, 536
 influence, of electricity, 834
 on other plants, 129-131
 iron content, 235
 maltase, 629
 mitochondria, 25
 phospholipides, 581
 proteases, 638
 proteins, 517, 538
 raffinose, 411
 relation to light, 830
 respiration, 752, 765
 response to aluminum, 280
 to ammonium salts, 501
 to boron, 243, 270
 to chlorine, 278-279
 to iodine, 284
 to iron, 263
 to lithium, 284
 to manganese, 275-276
 to nitrates, 501
 to potassium, 256
 to silicon, 268-269
 root hairs, 124
 roots, 98, 101-102, 104, 111
 Barley, salt requirement, 286, 288
 seed coats, 62-63
 stomata, 321-322, 331
 transpiration, 192-193, 361-362, 370-371
 water cultures, 199, 208
 water requirement, 385-386
 wilting coefficient, 157
 Bean (*see also* Lupine, *Vicia*).
 absorption by, 239
 acidity, 37-38
 CO₂ fertilization, 458
 composition, 235
 conduction of water, 675
 erepsin, 645
 etiolation, 466
 growth, 821
 nitrogen, content, 500
 in leaves, 531
 nutrition, 470
 oil of seed, 578
 phospholipides, 581
 photosynthesis, 466, 470
 protein, 517, 533
 relation to light, 461, 829-830
 respiration, 757
 response to arsenic, 283
 to boron, 270
 to calcium, 248
 to sulphur, 260
 root hairs, 122
 roots, 80, 81, 101, 129
 salt requirement, 288
 seed coats, 63
 starch grains, 414
 solarisation, 469
 temperature of leaves, 369
 transpiration, 359
 wilting coefficient, 156-157
 Beet, absorption, 180, 183
 CO₂ fertilization, 458
 production, 126
 concentration of sap, 32
 content of boron, 269
 of iodine, 236
 of sulphur, 258
 depletion of soil, 132
 enzymes, 613
 guard cells, 325
 oxidase, 773
 phospholipides, 580
 protease, 638
 protein, 539

Beet, raffinose, 211
 respiration, 757
 response to aluminum, 280
 to ammonium salts, 501
 to chlorine, 277
 to light rays, 827
 to nitrates, 501
 to phosphorus, 246
 to potassium, 255
 to sulphur, 260
 roots, 111
 tyrosinases, 770
 water cultures, 214
 Bellani plates, 373
 Beneficial influence, plant to plant,
 129-130
 Benzidine reaction, 770
 Biuret reaction, 514
 Bleeding, 676
 Bleeding pressure, 676
 Bloom on fruits, 574
 Borax fertilizer, 271-272
 Bordeaux mixture, effect on transpi-
 ration, 358-360
 Boron, amount necessary, 270
 effect on structure, 270-271
 fertilizer, 271-272
 occurrence in plants, 269
 physiological rôle, 269-271
 Breathing *vs.* respiration, 740
 Bromelin, 613, 642-644
 Bubble method, of photosynthesis, 472
 Buckwheat, 37, 127, 129, 132, 196, 237,
 243, 244, 245, 256, 270, 277, 626,
 629, 645, 746, 780, 823, 827, 829, 830,
 831
 Buttermilk, utilization, 504
 Butyric acid, 566

C

Cabbage, 30, 124, 132, 234, 245, 247, 256,
 257, 258, 275, 279, 280, 309, 321, 369,
 500, 521, 524, 578, 645, 769, 806
 Caffeine, 541
 Calcium, antidoting agent, 251
 component of cell wall, 249-250
 of plant parts, 248-251
 of proteins, 249-250
 influence on translocation, 248
 magnesium ratio, 251
 occurrence in plants, 233-234, 247
 physiological rôle, 247-251
 Calcium, relation to acidity in cells, 249
 to middle lamella, 249-250
 Calculated wilting coefficient, 152-153
 Callose, 124
 Camphor, 595
 influence on transpiration, 357
 Cane sugar (*see* Sucrose).
 Capillarity, water ascent, 685
 Capric acid, 566
 Caproic acid, 566
 Caprylic acid, 566
 Carbohydases, 613, 614-631
 cellulase, 629-630
 diastase, 620-628
 glucase, 628-629
 inulase, 628
 invertase, 614-620
 Carbohydrates, absorbed by roots, 239-
 241
 in cell sap, 26
 classification, 405
 polysaccharoses, 411-420
 sugars, 406-411
 definition, 404
 first formed, 439
 in leaf, 433-441
 in plant, 404-420
 relation to chlorophyll, 428
 to fats and oils, 582, 592-594
 in respiration, 732
 stored foods, 605
 translocation, 248, 710-714
 Carbon, amount in plant, 233
 function, 244
 Carbon assimilation, 420
 Carbon bisulfid, 814
 Carbon dioxide, absorption by leaf, 443
 in air and soil, 453-454
 application in agriculture, 458-459
 concentration and photosynthesis, 455-
 456
 diffusion, 334
 excretion by roots, 125-128
 method of studying photosynthesis,
 473
 relation to respiration, 731, 733, 735-
 739, 762-764
 solvent action, 126-128
 supply available, 453-459
 used by plant, 454
 Carbon monoxide, 455
 Carbon-nitrogen ratio, 543-551
 defined, 543-544

- Carbon-nitrogen ratio, influence of light, 833
 relation to fruit buds, 545
 to growth stages, 547
 to length of day, 546
 to organs of plant, 548
 to root and shoot, 548
- Carnauba wax, 568, 573
- Carotin, 428
- Carotinoids, 428-429
- Carrot, 132, 178, 180, 181, 183, 185, 246, 277, 279, 408, 428, 579, 630, 749-750, 757, 832
- Casein, utilization, 504
- Casparian strip, 165
- Castor bean, 243, 270, 359, 510, 517, 534, 576, 579, 644, 778
- Catalase, 243
 acid relations, 778
 in cell sap, 27
 defined, 767
 drying effect, 778
 effect of photoperiodism, 833
 nature of, 777
 preparation and study, 776
 relation to respiration, 779
 to vitality, 781
 temperature relations, 778
 X-rays, effect, 828
- Catalysts, 607
- Cations, absorption, 182-190
 influence on permeability, 82-84
- Celery, 603, 778, 814, 817, 818
- Cell (*see* Plant cell).
- Cell sap, acidity, 35-38
 concentration, 27-34, 68
 composition, 26
 need for water, 308
 origin of, 25-26
 osmotic value, 68
 relation to transpiration, 245
 sources of materials, 27
- Cell wall, composition and properties, 1-15
 membrane, 59
 origin, 1
 of root hair, 123
- Cellobiose, 6
- Cellulase, 613, 629
- Cellulose, as carbohydrate, 412
 kinds, 5-9
 in root hair, 124
- Center of origin, starch grains, 413
- Cerebrosides, 575
- Cerotic acid, 566
- Ceryl alcohol, 568, 573
- Cetyl alcohol, 573, 757
- Chemical analysis for permeability, 74-75
- Chemical combination and water, 309
- Chemical theory of membrane action, 86-87
- Chemicals, influence on transpiration, 356-361
- Chemistry of chlorophyll, 422
 of photosynthesis, 441-451
- Chemotropism, of roots, 98-102, 108-109
- Cherry, 321
 gum, 420, 408
 oxidases, 769
 respiration, 739
- Chlorides, in cell sap, 27
 fertilizers, 277-279
 in protoplasm, 16
- Chlorine, antagonistic ion, 279
 fertilizer, 277-279
 influence on asparagus, 278
 on roots and tubers, 277
 occurrence in plants, 232-233, 235, 276
- Chloroform, influence on maltase, 629
 permeability, 83
 respiration, 760
- Chlorophyll, *a* and *b*, 422-428
 absorption of light, 424
 amount and photosynthesis, 465-467
 chemistry of, 422-423
 fluorescence, 423
 formation, 426-428
 function, 441-443
 optical properties, 423-425
 relation to, calcium, 427
 to iron, 261, 427
 to magnesium, 252, 427
 to manganese, 276, 427
 to phosphorus, 427
 to sulphur, 259, 427
- Chlorophyllase, 423
- Chlorophyllin, 422-423
- Chlorophyllogen, 426, 428
- Chloroplasts, described, 20-21
 of guard cells, 324
 pigments of, 421-429
 reactive surface, 470
- Chlorosis, defined, 261
 due to lack of iron, 261-264
 of magnesium, 252
 of manganese, 276

- Cholesterol, 568, 575
 Choline, 134, 575
 Chondriosomes, 24–25, 650
 Chromoplasts, 21
 Cinnamon, 595
 Citric acid, 583
 relation to invertase, 619
 Citrus plants and fruits, 188, 251, 252, 817
 Classification, of amino acids, 513
 of carbohydrates, 405
 of cell parts, 1
 of cell wall compounds, 5
 of enzymes, 612–613
 of lipides, 565, 569–575
 of proteins, 516
 Climate, relation to protein formation, 537–540
 to transpiration, 350–354
 to water requirement, 385–386
 to wilting coefficient, 154–156
 Clover, absorption of phosphorus, 245
 acidity of sap, 37
 catalase, 780
 composition, 234
 CO₂ production, 126
 depletion of soil, 132
 erepsin, 645
 H-ion concentration and growth, 835
 influence, of electricity, 834
 of light, 834
 on other plants, 131
 manganese content, 273
 oxidases, 769
 phospholipides, 581
 response to aluminum, 280
 to boron, 270
 to sulphur, 259
 roots, 109, 111
 stomata, 321–322
 water cultures of, 214
 Coagulases, 613, 645
 Cobalt chloride method, transpiration, 315, 332, 360, 378–380
 Cocaine, 541
 Cocklebur, absorption of water, 160–161
 catalase, 782
 relation to light, 831
 seed coats, 60, 63, 812
 transpiration, 361–362
 Coefficient, energy absorption, 477
 temperature, 86, 463
 transpiration, 374
 Coefficient, wilting, 152
 Coenzyme, 611
 Coffee tree, 690, 692
 Cohesion theory, ascent of water, 686–689
 Cold resistance, 822–824
 Collodion, film, 332
 membrane, 175
 Colloidal solution, of chlorophyll, 425
 defined, 50–51
 Colloidal theory, of membrane action, 88–89
 Colloids (*see also* Absorption, Cell wall, Membranes, Polysaccharoses, Proteins, Protoplasm).
 relation to stomatal behavior, 328
 to water loss, 346
 Companion cells, 671
 Compensation point, 460
 Composition of plant, 232–238
 distribution of element, 238
 influence of plant, 233–235
 of soil, 236–238
 Compound celluloses, 8
 Compound interest law and growth, 805
 Compound lipides, 574–575
 described, 574
 distribution, 579
 function, 581
 occurrence, 578–582
 relation to oil and protein, 580
 in seeds, 580
 Concentration, of cell sap, 28–33
 critical, 220
 methods of expressing, 51–52
 relation to absorption ratio, 180–182
 to nutrient solutions, 207–208
 to starch formation, 469–470
 Coniine, 541
 Conjugated proteins, 517, 518
 Copper, 284
 Cork formation, 11, 838
 Corn, absorption of elements, 236–237
 of ions, 182
 of organic compounds, 239–241
 acidity, 36–39, 185–186
 aeration of roots, 106–107
 alcohol source, 482
 aluminum content, 279
 amino acids, 519, 718
 calcium content, 247
 carbohydrates in leaves, 438
 CO₂ production, 127, 455

- Corn, cell sap, root hair, 30
 cells of root, 17
 coloring matter, 428
 composition, 233-235
 depth of absorption, 117
 diastase, 626
 distribution of elements, 238
 embryo, 648-652
 endosperm, 648-652
 energy utilized, 482
 enzymes of roots, 129
 erepsin, 645
 formation of protein, 533, 535
 growth, 264, 804, 821, 825
 influence of electricity, 835
 iron supply, 266
 leaf structure, 313-314, 345
 leaf surface, 314, 348
 magnesium content, 252
 maltase, 629
 manganese content, 272
 mitochondria, 25
 nitrogen content, 500, 531
 oil, 568, 570, 573, 578
 oxidase, 769
 pentosans, 420
 pentose, 408
 phospholipides, 580-581
 phosphorus content, 245
 phytosterol, 568
 polypeptides, 519
 potassium content, 254
 photosynthesis, 476
 primordia of leucoplasts, 23-24
 proteases, 638
 proteins, 517, 539
 respiration, 753
 respiratory quotient, 746
 response to ammonium salts, 501-502
 to barium, 283
 to light, 829, 831
 to manganese, 274
 to moisture, 159, 355
 to nitrate, 501-502
 to potassium, 256
 to sulphur, 260
 to zinc, 284
 root hairs, 119, 122, 124
 roots, 98, 101-102, 110-111, 115, 138,
 241, 349
 salt requirement, 285-286, 289
 seed, 648-652
 silicon content, 266-267
- Corn, starch, 418
 starch grain, 414
 stomata, 317-323, 341
 temperature of leaves, 365-369
 transpiration, 191-192, 310-311, 316,
 353, 357, 361-362
 variation of dry matter, 340, 475
 water, content, 308
 cultures, 200, 211-212, 214, 220
 of leaf, 338-340
 lost, 313
 requirement, 385-388
 used, 309
 wilting coefficient, 154, 156
- Corylin, 511, 517
- Cotton, acidity, 36
 aluminum content, 279
 composition, 6
 magnesium in seeds, 253
 movement of water, 690
 oil, 568, 570, 573, 578
 phospholipides, 581
 phytosterol, 568
 raffinose, 411
 relation to light, 831
 response to boron, 243, 270
 to phosphorus, 247
 roots, 111, 241
 translocation of carbohydrates, 710-
 712
- Cotton seed meal, 504
- Cowpeas, acidity, 37
 boron content, 269
 calcium-magnesium ratio, 251
 composition, 234
 nitrogen content, 500
 in leaves, 529
 oil of stem and leaves, 578
 protein, 517
 response to barium, 283
 to strontium, 283
 stomata, 317, 321-322
 temperature of leaves, 365-369
 transpiration, 316, 355
 water content, 309
 water lost, 313
- Cradina, 613, 644
- Creatine, 134, 504
- Creatinine, 504
- Critical water-supplying power of soil,
 163
- Criticism of nutrient solutions, 216-218
- Crone's solution, 195

Crude lipides, 564, 565
 Cucumber, 124, 186, 213, 321, 458, 645, 827
 Cucurbita (*see* Pumpkin, Squash).
 Cucurbitin, 517
 Cultivation, benefits, 103
 Cultural solutions, 194
 Cultures, sand, 194
 water, 194
 Cuticle, 11, 314, 332
 Cuticular transpiration, 332, 344
 Cutin, 9-12
 Cystine, 511
 action on diastase, 626
 formula, 513
 in tomato, 523
 Cytase, 6
 (*See also* Cellulase.)
 Cytoplasm, 18-19
 Cytoplasmic membrane, 65-68
 measuring permeability, 74-79

D

Dahlia, 180
 Date, 7, 630, 808
 Date palm, growth in light and darkness, 826
 Death point, temperature, 370
 Decomposition products, of roots, 133-136
 Deionized air, 765
 Deleterious influence of one plant on another, 130-138
 causes, 132-138
 Derived lipides, 575
 Derived proteins, 519
 Dextrinase, 613
 Dextrins, 419, 433
 Dextrose (*see* Glucose).
 Diastase, activity in tubers, 751
 from different plants, 621
 in after ripening, 816
 in cell sap, 27
 effect of aluminum salts, 281
 of potassium oxalate, 248
 factors influencing, 625-628
 chemicals, 625
 light, 627
 temperature, 625
 in guard cells, 327
 kinds, 620-622
 occurrence, 620-622

Diastase, of plants and animals, 622
 preparation, 622-624
 secretion, 129, 620
 study of activity, 624
 taka, 620
 translocation, 621
 Dichlorethylene, 814
 Differentiating stage of growth, 800
 Diffusion, through membranes, 56-59
 method of measuring permeability, 77
 through small openings, 333-336
 in solutions, 52-53
 through stomata, 336-337
 Digestion, in plants, 603-653
 and animals, 652
 extracellular, 653
 intracellular, 653
 literature on, 656-668
 nature of, 605-606
 questions on, 653-656
 Disaccharoses, 410-411
 Donnan equilibrium, solute intake, 178-179
 Dormancy, causes, 811-813
 defined, 811
 localized, 813
 overcoming, 813-818
 Downward movement of water, 689-691
 Drying oils, 571

E

Economic importance of photosynthesis, 481
 Economy constant, 805
 Ectoplast, 18, 66
 Ectosarc, 66
 Edestin, 511, 516, 517
 Efficiency index of production, 805
 Elaioplasts, 576
 Electrical conductivity, measuring permeability, 76-77
 Electrical phenomena, solute absorption, 175
 Electrical theory, of photosynthesis, 446
 Electricity, influence on growth, 834-836
 on respiration, 765
 Elemental requirement and age, 284-289
 Elements absorbed by plants, 232-289
 distribution in plants, 238-239
 essential *vs.* unessential, 242-244
 forms in which absorbed, 239-242
 inorganic compounds, 239
 organic compounds, 239-242

- Elements, function, 244-284
 influence on photosynthesis, 470
 literature on, 292-307
 number and kind, 232-239
 influence of plant, 233-236
 of soil, 236-238
 questions on, 289-292
 Elodea, 23, 24, 122, 246, 456, 457, 462, 524, 709, 764, 828
 Elongating stage of growth, 800
 Elongation, periodic, 806
 Embryonic stage of growth, 798
 Emulsin, 613, 632
 Endodermal pressure, 676
 Endodermis, function, 165
 passage cells, 165
 permeability, 64, 165
 structure, 164-166
 Endoplasm, 18
 Endosmosis, 59
 Endosperm, 648-652
 respiration, 757
 Energenesis, 730
 Energy, absorbed by leaves, 477
 for absorption of solutes, 180
 relations, in photosynthesis, 471-482
 of plant, 729
 released in respiration, 737
 utilized in photosynthesis, 478-480
 in transpiration, 350-352
 for water ascent, 687
 Enollactim, 637
 Enzymes, in cell sap, 27
 classification, 612-613
 defined, 607
 endocellular, 647
 formation in plant, 647-652
 intracellular, 647
 longevity, 614
 nature of, 607-610
 nomenclature, 611-612
 occurrence, 613-646
 relation to heat, 608
 to photosynthesis, 464
 secreted by roots, 128-129
 Epictesis, 177
 Epidermal cells, 314
 osmotic value, 325
 Epidermis, 314, 317, 323, 325
 Epithelial layer of scutellum, 648-652
 Epithem hydathodes, 389
 Equivalent weight solution, 52
 Erepsin, 613, 645
 Ereptase (*see* Erepsin).
 Erucic acid, 567
 Erythro-dextrin, 419
 Essential elements, 242-244
 Essential oils, 564, 565, 594
 Esterases, 613, 634
 (*See also* Lipases.)
 Ether extract, 564
 Ethyl alcohol, in respiration, 735-736
 Ethyl bromid, 814
 Ethylene, 761, 818
 Ethylene chlorhydrin, 813-814
 Ethylene dichlorid, 813, 814
 Etiolated plants, characteristics of, 825
 defined, 824
 photosynthesis of, 466
 Eucalyptus, 595
 Evaporating power, of air, 352-354
 defined, 352
 effect on transpiration, 350-354
 of solar radiation, 350-351
 Evaporation, measurement of, 371-374
 ratio to transpiration, 374-376
 relation to transpiration, 370-371
 to water ascent, 676-689
 to wilting coefficient, 155-157
 value of, 371
 Evaporimeter, 371
 (*See also* Atmometer.)
 Evident plasmolysis, 69, 70
 Evident stage of growth, 797
 Excelsin, 511, 517
 Excretions of roots, 124-138
 acids, 125
 beneficial, 129
 carbon dioxide, 125
 enzymes, 128
 toxic, 136
 Exomosis, 59
 Extraction of protein, 511, 524
 Exudation pressure, 676
- F
- Factors, limiting, 451
 Fat metabolism in plant, 564-595
 literature on, 597-602
 questions on, 595-597
 Fat solvents, 564
 Fats (*see also* Lipides).
 artificial synthesis, 586-587
 changes during formation, 583
 during germination, 587-594

- Fats**, changes during germination,
 amount of oil, 588
 carbohydrates and fats, 593
 fatty acids of the oil, 589
 of cotyledons, 590
 of hypocotyls and roots, 591
 chemical properties, 570-573
 described, 569
 distribution in cell, 575
 drying oils, 571
 and fatty oils, amount in plant, 578
 hydrolysis, 570
 occurrence with carbohydrates, 578
 in plants, 577
 physical properties, 569
 relation to carbohydrates, 582
 in respiration, 732
 saponification, 571
 stored food, 605
 synthesis, 582-587
 translocation, 714-717
 values for determining characteristics,
 572
- Fatty acids**, 565-568
 from carbohydrates, 520
 percentage in fats and oils, 570
 relation to fat formation, 584
- Fatty oils** (*see* Fats and fatty oils).
- Fatty substances**, 564
- Feeding power of plants**, 236
- Fehling's solution**, preparation, 407
- Fennel**, 595
- Fermentation**, 736
- Ferments**, 612
- Fertilizers**, boron, 271-272
 effect on toxic substances, 134
 manganese, 274-275
 as oxidizers, 135
 sulphur, 259-260
- Feterita** (*see* Sorghum).
- Films**, influence on transpiration, 358-360
- Flax**, cell wall of fiber, 1, 4
 formation of oil, 584-585
 magnesium in seeds, 253
 need of boron, 243
 oils, 568, 570, 573-574
 protease, 638
 relation to light, 829-830
 response to boron, 270
 to temperature, 823
 roots, 101
 water culture, 214
- Fluorescence**, 423
- Foods of plant**, 603-605
- Formaldehyde**, activated, 449, 520
 condensation in plants, 448
 detection in leaves, 449
 formation by plants, 445-448
 photosynthetic quotient, 433
 theory of photosynthesis, 444-451
 utilization, 450
- Formative stage of growth**, 798
- Formhydroxamic acid**, 520
- Formic acid**, 566
 excreted by roots, 125
 in protein formation, 249
 in respiration, 735
- Four-salt solution**, 195, 200, 205
- Freed sorgo** (*see* Sorghum).
- Freeman's method**, transpiration, 380
- Freezing**, effect on plants, 823
- Fructose**, 240
 description, 409
 in leaves, 433-441
- Fruit-bud formation**, 545
- Fruit sugar** (*see* Fructose).
- Fucoxanthin**, 429
- Fundamental stage of growth**, 797
- Fungi**, relation to transpiration, 361-362
 to photosynthesis, 470-471
- Furfurol**, 813

G

- Galactans**, 409, 419
- Galactolipides**, 575
- Galactose**, 240, 409, 420
- Ganong leaf punch**, 474
 respirometer, 743
- Gas bubbles**, in stems, 674
- Gases**, effect, on cork formation, 838
 on growth, 837
- Gentianose**, 411, 613, 631
- Gentiobiose**, 411
- Germination**, amino acids, 718
 catalase activity, 775-781
 changes, in carbohydrates, 713
 in fats and oils, 587-594
 in proteins, 717-719
 enzyme formation, 647-652
 respiration, 741-748
 of seeds, 814-815
 translocation of oil, 714
- Glandular hairs**, 342
- Gliadin**, 516, 517, 518
- Globulin**, 511, 516, 517

Glucase, 613, 628, 632
 Glucose, described, 408
 in leaves, 433-441
 utilization by plants, 239-241
 Glucosidases, 613
 emulsin, 632
 myrosin, 632
 phytase, 632
 rhamnase, 632
 Glucosides, 404
 in cell sap, 26
 mustard oils, 257
 occurrence, 631
 Glutamic acid, 513
 Glutamine, 504, 513
 Glutelins, 517, 518
 Glutenin, 516, 517, 518
 Glycerine (*see* Glycerol).
 Glycerol, 241, 568
 Glycerophosphoric acid, 579, 581
 Glycine, 504, 513
 action on diastase, 626
 Glycinin, 517
 Glycolic acid, 433
 Glycoproteins, 518
 Glyoxalic acid, 433
 Graminin, 419
 Gram molecular solution, 51
 Grape, *erepsin*, 645
 fungi and transpiration, 361
 oil of seed, 573
 oxidases, 769
 respiration, 739
 response to sulphur, 260
 sap of vine, 27
 Grape sugar (*see* Glucose).
 Grey-speck disease, 274
 Growth, after-ripening, 815-818
 compound interest law, 805
 curves, 802-806
 dormant period, 811-818
 effect of cell sap, 34
 elementary stage, 797
 factors affecting, 818-838
 fundamental, 820-838
 electricity, 834-836
 gases, 837
 H-ion concentration, 836
 light, 824-834
 moisture, 838

Growth, factors affecting external,
 nutrients, 838
 temperature, 820-824
 internal, 818-820
 fundamental stage, 797
 inhibiting substances, 810
 literature on, 840-850
 nature, 797-798
 of organs, 801
 periodicity, 807
 periodic elongation, 806
 of plant, 797-838
 promoting substances, 808
 questions on, 838-840
 relation to H-ion concentration, 212-
 216
 rhythm, 807
 stages in plant cell, 798-801
 differentiation, 800
 elongation, 800
 embryonic, 798
 Growth curves, 802-806
 Growth-inhibiting substances, 808, 810
 Growth-promoting substances, 808
 Guaiaicum reaction, 770
 relation to oxidase, 767
 Guanine, 504, 541
 Guard cells, 317, 324
 changes in content, 326-328
 osmotic relations, 325-326
 osmotic value, 325
 physiology of, 324-326
 Guttation, 388-390

H

Habitat, effect on cell sap, 28
 Haemoglobins, 518
 Hairs, kinds, 342
 relation to transpiration, 342-344
 Hardening of plants, 824
 Heat, in respiration, 747
 Hehner value, 572
 Helianthus annuus (*see* Sunflower).
 Heller's test, 514
 Hemicelluloses, definition, 7
 hydrolytic products, 7-8
 occurrence, 7-8, 408, 420
 in starch, 415
 Hemoglobin, 504
 Hemp, 517, 572, 578, 585, 633, 638, 715,
 829, 831
 Hexoses, 408-410

- H-ion concentration, of cell sap, 35-39
 influence on catalase, 779
 on diastase, 626
 on invertase, 619
 on lipase, 636
 on oxidases, 772
 on root hairs, 121
 of oily seeds, 715
 optimum for growth, 213-215
 relations to growth, 213-214, 836
 to iron supply, 264
 to nutrient solutions, 212-216
 to stomatal opening, 327
- Hippuric acid, 504
- Histidine, 504
 in developing seeds, 534-536
 formula, 513
 in tomato, 523
- History of nitrogen nutrition, 506
 of nutrient solutions, 194
 of photosynthesis, 429-430
 of proteases, 638
- Hoagland's solution, 196-197
- Hopkins-Cole's reaction, 515
- Hordein, 517
- Hormones, 243, 808
- Humidity, effect on stomata, 318, 330
 influence on transpiration, 353
- Hyaloplasm, 66
- Hydathodes, 389
- Hydration and growth, 799
- Hydrocelluloses, 6
- Hydrocyanic acid, 640-642
- Hydrogen, amount in plant, 233
 function, 244
- Hydrolases, 613
- Hydrostatic pressure, in cell, 71
 in osmosis, 57
- Hydrostatic system, 675
- Hydrotropism, 97
- Hydroxy-fatty acids, 10-12, 134, 575
- Hygrometric paper, 379
- Hygroscopic coefficient of soil, 153
- Hygroscopic water, 153
- Hypertonic solution, 71
- Hypogaecic acid, 567
- Hypotonic solution, 71
- Hypoxanthine, 504
- I
- Imbibition, defined, 55
 relation to diffusion, 55-56
- Imbibition, relation to entrance of water, 166
 to hardened plants, 823
 to water ascent, 685, 687
 to water loss, 346
- Impermeable membrane, 54
- Incipient drying, 166, 346
 relation to leaf surface, 348
 to root system, 349
 to transpiration, 346-350
- Incipient plasmolysis, 69, 71
- Incipient wilting, 347
 relation to leaf surface, 348
 to root system, 349
 to transpiration, 346-350
- Index, stomatal, 319
 of transpiring power, 153, 345, 380
- Inhibitor, 611
- Injection experiments, 696
- Injury and respiration, 755-757
- Inorganic compounds (*see* Solutes).
- Inorganic nitrogen, 501-503
- Inorganic salts (*see* Solutes).
- Intake, of solutes, 174-221
 factors affecting absorption ratio, 179-182
 concentration of exterior medium, 180-182
 light, 179-180
 literature on, 223-231
 mode of entrance, 174
 active or physiological absorption, 176-179
 passive or physical absorption, 175-176
 questions on, 221-223
 relation to transpiration, 190-193
 unequal absorption of ions, 182-190
 factors influencing, 187-190
 concentration of external solution, 187
 different ions, 188-189
 interchange of ions, 186-187
 mechanism of, 183-184
 reaction of exterior solution, 184-18
- Intake, of water, 150-170
 literature on, 171-173
 questions on, 170-171
- Intercellular spaces of leaf, 315
- Internal factors of growth, 818-820
 of photosynthesis, 453, 465-471
 of respiration, 759
- Intramolecular respiration, 735, 736

- Inulase, 613, 628
 Inulin, 419
 in leaves, 433
 Invertase, 613
 factors influencing, 618
 in industry, 615
 nature of action, 616
 occurrence, 614
 preparation of, 615-616
 from green plants, 616
 from yeast, 615
 secretion by root, 129
 Invertin (*see* Invertase).
 Iodine, content of plants, 236
 method measuring, diastase action, 624
 photosynthesis, 473
 in plant nutrition, 284
 value, 573
 Ions, antagonistic, 219
 unequal absorption of, 182-190
 factors influencing, 187-190
 interchange from plant to exterior, 186-187
 mechanism of, 183-184
 reaction of exterior solution, 184-186
 Irisin, 419
 Iron, absorption from soil, 265
 form and amount necessary, 261-264
 immobility in plant, 265
 in nutrient solutions, 195, 201
 occurrence, in barley, 235
 in oats, 235
 in plants, 260
 in wheat, 235
 physiological rôle, 261
 relation to H-ion concentration, 264
 in respiration, 765
 spraying with, 265
 Isoelectric point, of cell sap, 516
 definition, 178
 of proteins, 515-516
 relation to guard cells, 328
 Isotonic solution, 71
- J
- Jaminian chains, 674
 Johnson grass (*see* Sorghum).
 Juglansin, 517
- K
- Kafir (*see* Sorghums).
 Kafirin, 517
- Kephalin, 574
 Kinase, 612
 Knop's solution, 195, 200
 Kudzu, 701
- L
- Laccases, 768
 Laccol, 769
 Lactam ring, in chlorophyll, 422
 in lipase, 637
 Lactic acid, 404
 influence on respiration, 765
 Lactim, 637
 Lactone ring, 423
 Laminaria, 76, 77, 82-84, 760, 762, 764
 Latent osmotic pressure, 68
 Lateral extent of roots, 115-116
 Lateral movement, of organic compounds, 709
 of solutes, 695-696
 of water, 691-692
 Lauric acid, 566
 Law of limiting factors, 452
 of minimum, 451
 Leaf surface, 314, 348
 methods of measuring, 376
 relation to incipient wilting, 348-349
 Leaf test time, 380
 Leaves, absorption, of energy, 477
 of water, 150-151
 carbohydrates in, 433-441
 daily variations, 435-438
 first formed, 439
 variations in different parts, 438
 general structure, 313, 344
 nitrogen in, 527-532
 compounds of, 531
 diurnal variation, 527
 total, 528
 number of stomata, 318
 temperature of, 362-370
 water content, 338-341
 Lecithins, described, 574
 relation to magnesium, 253
 to peroxidase, 767
 to phosphorus, 246
 Lecithoproteins, 518
 Legumelin, 516, 517
 Legumin, 511, 517
 isoelectric point, 516
 Length of day, relation to carbon-nitrogen ratio, 546

- Lettuce, 236, 247, 279, 280, 459, 500, 645, 757, 782, 814, 827
- Leucine, in developing seeds, 536
in digestion, 640-641
formula, 513
in seedlings, 718
in tomato, 523
utilization, 504
- Leuco compounds, 431, 472
- Leucoplasts, 21, 22
- Leucosin, 516, 517
- Levulose (*see* Fructose).
- Liebig's law of minimum, 451
- Light, chemical changes by, 832
influence on absorption ratio, 179-180
on diastase, 627
on germination, 815
on growth, 824-834
on permeability, 82
on photosynthesis, 459-463
on protein synthesis, 533
on respiration, 765
on reproduction, 830-832
on root hairs, 122
on roots, 110
on stomatal movement, 329
on transpiration, 352
on value of nutrient solutions, 206-207
- Lignin, 8-9
- Lignocellulose, 8-9
- Lignoceric acid, 566
- Limiting factors, 451-453
- Linolenic acid, 567
- Linolic acid, 567
- Linseed meal, 504
- Lintner's method, diastase activity, 624
- Lipaseidine, 634
- Lipases, 613, 633-637
factors influencing action, 634-637
preparation and study, 633-634
relation to sugar formation, 594
- Lipides, changes during germination, 587-588
classification, 565, 569-575
compound lipides, 565, 574
distribution, 579
function, 581
relation to oil and protein, 580
in seeds, 580
derived, 565, 575
simple, 565, 569-574
- Lipides, composition, 565-569
fatty acids, 565-568
glycerol, 568
defined, 564
distribution in cell, 575-577
occurrence in plant, 577-582
synthesis, 582-587
changes during formation, 583
general observations, 585
relation to carbohydrates, 582
- Lipins, 574
(*See also* Compound lipides.)
- Lipoid theory of permeability, 85-86
- Lipoids, 574, 799
(*See also* Compound lipides.)
- Lithium, in alfalfa, 235
in nutrition, 284
in plants, 232
in tobacco, 235
- Living membrane (*see* Cytoplasmic membrane).
- Locus, of starch grain, 413
- Long day plants, 830
- Loss of water from plants, 308-390
literature on, 394-403
questions on, 390-394
- Lupine, absorption of ions, 189
aeration of roots, 104, 107
amino acids, 718
chemotropism of roots, 99-100
hemicellulose in seeds, 7
hydrotropism of roots, 97
phospholipides, 579
protein, 517
rate of growth, 806
response to aluminum, 280
to silenium, 284
structure of root, 164
water culture, 199, 220
- Lupinus (*see* Lupine).
- Lycopersicin, 428
- Lycopin, 428
- Lysine, action on diastase, 626
formula, 513

M

- Magnesium, carrier of phosphorus, 253
constituent of chlorophyll, 252
injury, 253
occurrence in plant, 233-234, 252
in oily seeds, 253
relation to chlorosis, 252

- Malic acid, in cell sap, 27
 photosynthetic quotient, 433
 in respiration, 583
- Malt sugar (*see* Maltose).
- Maltase (*see* Glucase).
- Maltose, 241
 described, 411
 from starch, 418
- Manganese, as fertilizer, 274-275
 need of by plants, 273-274
 occurrence in plants, 233, 272-273
 physiological rôle, 275-276
- Mangold, 247, 255, 408
- Manna, 211
- Mannans, 409, 419
- Mannite, 409
 in leaves, 433
- Mannitol (*see* Mannite).
- Mannosans, 409, 419
- Mannose, 7, 240
 described, 409, 420
- Maysin, 517
- Medullary rays, 670
- Melibiose, 411, 613, 631
- Melicitose, 411
- Membranes, cell wall, 59
 collodion, 175
 cytoplasmic, 59, 65
 diffusion through, 56-59
 kinds, 54-55
 literature on, 91-96
 nature of, 54
 of plant cell, 59
 questions on, 89-91
 of seed coats, 60-64
 theories of action, 85-89
- Mesophyll of leaf, 315
- Meteorological conditions, effect on transpiration, 350-354
- Methods, of aerating, nutrient solutions, 199-200
 soils, 103-105
 of determining, catalase, 776
 oxidase activity, 770
 relation of solute intake, 190-193
 total nitrogen of leaves, 528-531
 unequal ion absorption, 182
 utilization of organic compounds, 239-242
 water supplying power, 160-164
 wilting coefficient, 152-154
 of extraction of proteins, 511, 524, 526
- Methods, of measuring, antagonism, 219
 influence of sprays on transpiration, 358
 leaf surface, 376
 leaf temperature, 363
 oxygen supplying power, 106
 permeability of protoplasm, 74-79
 photosynthesis, 471-475
 photosynthetic ratio, 431-432
 respiration, 741-744
 stomatal aperture, 328
 transpiration, 376-382
 water requirement, 384
 of preparation of diastase, 622
 of invertase, 615
 of lipase, 633-634
 of nutrient solutions, 200-206
 of peroxidase, 775
 of proteases, 639-644
 of renewing nutrient solutions, 198-199
 of studying, diastase, 624
 lipase, 633-634
 proteases, 639-644
- Micellae, of cell wall, 4
 of starch grain, 416
- Middle lamella, defined, 2-3
 relation to calcium nutrition, 249-250
- Millet, 132, 157, 246, 267, 268, 279, 385
- Millon's reaction, 514
- Milo (*see* Sorghum).
- Minerals, translocation in seedlings, 288-289
- Minimum, law of, 451
- Mitochondria (*see* Chondriosomes).
- Moisture, effect on nitrogen content, 538
 on stomata, 330
- Moisture equivalent of soil, 153
- Moisture-holding capacity of soil, 153
- Monosaccharoses, 407-411
 hexoses, 408
 pentoses, 408
- Morphine, 541
- Mullein, hairs, 343
- Mustard, 81, 120, 124, 126, 131, 200, 243, 257, 270, 283, 284, 501, 645, 780, 814, 829
- Mustard oils, 257
- Mutarotation, 617
- Myricyl alcohol, 568, 573, 575
- Myristic acid, 566
- Myrosin, 613, 632
- Myrrh, 595

N

- Naphthol reaction, 770
 Nicotine, 541
 Nitella, 67, 78, 82, 176-180, 181, 189
 Nitrates, occurrence in plants, 521
 in plant nutrition, 501-503
 in rain, 509
 reducing substances, 523
 reduction in plants, 520-524
 Nitrites, in cell sap, 27
 in leaves, 521-523
 in nutrition, 503
 in rain water, 509
 Nitrogen, absorption from air, 506-509
 from soil, 501-506
 inorganic, 501-503
 organic, 503-506
 amount in air, 506-509
 in plant, 233
 in protein, 511
 bases, 540-543
 carbon ratio, 543-551
 in compounds, 531
 effect on growth, 500
 fixation by nonleguminous plant, 507-509
 function, 244
 influence on root development, 102-103
 in leaves, 527-532
 compounds, 531
 diurnal variation, 527
 methods of determining, 527
 total nitrogen, 528
 loss from plants, 542
 metabolism, 500-551
 literature on, 553-563
 questions on, 551-553
 movement in stems, 694
 occurrence in plant, 500
 sources, 500-509
 time of application and protein, 537
 in twigs, 700
 Nitrogenous compounds, in cell sap, 27
 inorganic absorbed, 501-503
 organic absorbed, 242, 503-506
 Nodules, relation to boron, 271
 to sulphur supply, 259
 Nomenclature of enzymes, 611-612
 Non-drying oils, 571
 Nonreducing sugars, defined, 407
 in leaf, 437-438
 Non sugars (*see* Polysaccharoses).

- Normal cellulose, 5-6
 Normal solution, 52
 Nucleic acid, 134, 246, 504
 Nucleoproteins, 19, 246, 253, 518
 Nucleus, 19-20
 Nutrient solutions, 193-218
 best solution, 216
 characteristic and response, 201
 criticism of data, 216-218
 factors determining value, 206-212
 concentration, 207-208
 physiological balance, 209-212
 temperature and light, 206-207
 water *vs.* sand cultures, 209
 historical, 194
 H-ion relations, 212-216
 kinds, 194-197
 technique, 197-206
 aeration, 199-200
 preparation, 200-206
 renewal, 199
 Nutrients, depletion in soil, 132-133

O

- Oats, absorption of elements, 237
 acidity of sap, 36-37
 amino acids, 519
 boron content, 269
 CO₂ production, 126
 catalase, 781
 diastase, 626
 erepsin, 645
 influence of electricity, 834
 on other plants, 129-131, 137
 iodine content, 236
 iron content, 235
 magnesium needs, 252
 maltase, 629
 manganese content, 273
 nitrate content, 521
 nitrates *vs.* ammonium salts, 501
 pentosans, 420
 phospholipides, 580-581
 photosynthesis, 470
 polypeptides, 519
 potassium response, 255-256
 protein, 517-538
 relation to light, 830
 response to aluminium, 280
 to barium, 283
 to chlorine, 278
 to cobalt, 284

- Oats, response to iodine, 284
 to manganese, 274
 to nickel, 284
 to phosphorus, 246
 to strontium, 283
 to sulphur, 260
 to zinc, 284
 roots, 98, 110-111, 113, 138
 salt requirements, 286
 starch grain, 414
 stomata, 321-322
 transpiration, 312, 352, 361-362, 370-371
 water culture, 200, 211, 214
 water requirement, 385-386
 wilting coefficient, 154, 157
 Observed wilting coefficient, 152
 Oil (*see* Lipides).
 Oleanol, 586
 Oleic acid, 567
 Onion, bulb scale, 60, 64
 cell division, 806
 cytase, 630
 depletion of nutrients, 132
 permeability of scape, 78
 respiration, 757
 response to cobalt, 284
 to light, 832
 to nickel, 284
 to potassium, 256
 to sulphur, 257
 to zinc, 284
 Optical properties, chlorophyll, 423-425
 protein, 511
 triglycerides, 570
 Orange, 35, 38, 177, 237, 244, 645
 Organic acids, absorbed by roots, 241-242
 in cell sap, 27
 Organic compounds, absorbed, 239-242, 503-506
 respiration, 731
 of soil, 134
 storage, 698-702
 translocation of, 698-719
 carbohydrates, 710-714
 lateral, 709
 fats and oils, 714-715
 proteins, 717-719
 tissues concerned, 704-709
 utilization of, 702-704
 Organs, growth of, 801
 Origin of materials of cell sap, 27
 of plastids, 22-24
 Origin of vacuole, 25-26
 Oryzenin, 517
 Osazones, 407
 Osmosis, defined, 57-58
 examples, 56-59
 Osmotic concentration, of cell sap, 68
 of external solution, 68
 relation to exterior solution, 69-71
 Osmotic forces, relation to water intake
 167-169
 Osmotic pressure, defined, 27-28, 57-59
 of cell sap, 27-34
 distribution in nutrient solutions,
 201-203
 examples of, 56-59
 latent, 68
 potential, 68
 Osmotic relationships of plant cell, 68-73
 Osmotic value of cell sap, 68
 of guard cells, 325-326
 Oxalic acid, in cell sap, 27
 excreted by roots, 125
 in protein formation, 249
 photosynthetic quotient, 433
 relation to invertase, 619
 in respiration, 735
 in soil, 134
 Oxidases, 243
 action of, 767
 in apples, 749
 classification, 768-770
 laccases or phenolases, 768
 tyrosinases, 769
 defined, 766
 effect of phosphorus, 246
 factors influencing, 772
 healthy *vs.* diseased tissues, 773
 methods of studying, 770-772
 relation to physiological functions,
 773-775
 to sap pigments, 774
 secreted by roots, 128-129
 Oxycelluloses, 6
 Oxydase (*see* Oxidase)
 Oxygen, amount in plant, 233
 evolution in photosynthesis, 430-433
 function, 244, 730, 735-740
 method of studying photosynthesis,
 472
 relation to chlorophyll formation, 428
 to germination, 815
 in respiration, 730, 735-740, 762-763
 response of root, 107-108

Oxygen, in soil, 103-108
 supply and photosynthesis, 468
 supplying power of soil, 106
 in water cultures, 104
 Oxygen respiration, 735
 Oxygenase, 582
 defined, 766, 768
 relation to oxidase, 767-768

P

Palmitic acid, 566
 Papain, 613, 639-642
 Papayacin, 640
 Papayotin, 640
 Papaytin, 640
 Paracaoutchouc, 408
 Paralyzer, 611
 Parenchyma, 670, 671
 Parsnip, 183, 256, 277, 814
 Passage cells, 165
 Passive absorption, of solutes, 175-176
 of water, 169-170
 Passive regulation, of stomata, 337
 Pea, absorption of elements, 237
 of ions, 182, 187
 acidity, 185-186
 boron content, 269
 catalase, 781
 composition, 235
 erepsin, 645
 etiolated plants, 820
 fixation of nitrogen, 509
 formation of protein, 535
 heat of respiration, 747, 765
 influence on other plants, 130, 135
 iodine content, 236
 manganese content, 273
 oil of seed, 578
 oxidase, 769
 phospholipides, 581
 protein, 517
 rate of growth, 806
 relation to light, 830
 respiratory quotient, 746
 response to aluminum, 280
 to arsenic, 283
 to boron, 270
 to calcium, 250
 to chlorine, 276
 to cobalt, 284
 to lithium, 284
 to manganese, 275

Pea, response to nickel, 284
 to nitrates *vs.* ammonium salts, 502
 to organic compounds, 504
 to titanium, 283
 to zinc, 284
 root hairs, 30, 119, 122, 124
 roots, 81, 101, 107, 129, 241
 translocation of fats, 714
 water cultures, 200, 213
 wilting coefficient, 154
 Peach, 131, 321
 dormancy, 812
 gum, 408
 oil reserves, 576
 oxidases, 769
 protein, 517
 respiration, 739
 translocation of solutes, 693, 697
 water movement, 692
 Peanut, oils of, 568, 570, 573, 578
 phospholipides, 581
 protein, 517
 respiration, 753
 response to low temperature, 823
 seed coat, 60, 87
 Pear, 701, 779, 810
 Pectases, 613, 646
 Pectic acid, 14, 15
 Pectic substances, 12-15
 in leaf, 433
 Pectin, 14
 in root hairs, 124
 Pectinase, 613, 631
 Pectose, 13
 Pentosans, described, 420
 in hardening, 824
 in leaf, 433, 436
 in soil, 134
 in twigs, 700
 Pentoses, occurrence, 134, 408, 433
 Pepper, 156, 279, 428, 757
 Pepsin, occurrence, 638
 preparation, 639
 Peptase (*see* Pepsin).
 Peptides, defined, 519
 Peptone, defined, 519
 in digestion, 640
 in seedlings, 718
 utilization, 504
 Periodic elongation, 806
 Periodicity of growth, 807
 Permeability, cell wall membrane, 59-64
 contrasted with absorption, 73

- Permeability, cytoplasmic membrane, 67-68
 defined, 54
 effect of direction, 61
 endodermis, 165
 extreme changes, 84
 factors influencing, 79-85
 methods of measuring, 74-79
 seed coats, 60-64
- Permeable membrane, 54
- Peroxidase, defined, 767
 occurrence, 27, 775
- Pfeffer's solution, 195
- Phaseolin, 517
- Phaseolin, 517
- Phaseolus (*see* Bean).
- Phenolases, 768
- Phenol oxidases, 769
- Phenolphthalin reaction, 770
- Phenyl alanine, 513
- Phleim, 419
- Phloem, 671, 694
 in conduction, 694, 707-709
- Phlorizidin, 631
- Phosphates, absorbed, 245
 in cell, 16, 27
 influence on respiration, 764
- Phospholipides, described, 574
 distribution, 15, 575, 579
 function, 581
 relation to oil and protein, 580
 in seeds, 580
- Phospholipins, 574
 (*See also* Phospholipides.)
- Phosphomolybdic acid, 514
- Phosphoproteins, 518
- Phosphorus, 244-247
 form in which absorbed, 245
 occurrence, 233-234, 244-245
 physiological rôle, 246-247
 relation to silicon, 267-268
- Phosphotides, 574
- Phosphotungstic acid, 514
- Photochemical induction, 460
- Photoperiod, 829
- Photoperiodism, defined, 829
 discussed, 829-834
- Photosyntax, 420
- Photosynthesis, 420-482
 absorption of CO₂, 443
 chemistry of, 441-451
 coefficient of energy absorption, 477
 contrasted with respiration, 739
- Photosynthesis, economic importance, 381
 experimental evidence on, 445-451
 condensation of formaldehyde, 448
 intermediate products, 449
 organic nutrition, 450
 reduction of CO₂, 445
- factors influencing, 451-471
 amount of chlorophyll, 465-467
 CO₂ supply, 453-459
 light, 459-462
 protoplasmic factors, 468-471
 temperature, 463-465
 water supply, 467
- function of chlorophyll, 441
- history of, 429-430
- incident radiation in, 476
- literature on, 487-499
- methods of measuring, 471-477
 absorption of CO₂, 473
 increase in organic matter, 473
 liberation of oxygen, 472
- nature, 420
- products, 430-441
- questions on, 482-487
- rate of, 475
- theories of, 444
- utilization of energy, 478
- Photosynthetic number, 466
- Photosynthetic quotient, 431
- Phyllins, 423
- Physical absorption of solutes, 175-176
- Physical theories of water ascent, 683-689
- Physiological absorption, 176-179
 balance, 209-212
- Physiologically balanced solution, 218
- Phytase, 613, 632
- Phytins, 423, 631
- Phytosterol, 134, 568, 573
- Phytyl alcohol, 422
- Picric acid, 514
- Pigments, 404, 774
 of chloroplasts, 421-429
- Pineapple, absorption of salts, 182
 acidity, 35
 bromelin, 642
 relation to manganese, 276
 ripening, 817
 spraying with iron, 265
- Pisum sativum (*see* Pea).
- Pits, 1, 670

- Plant, elemental composition of, 233
 influence, of one on another, 129-138
 on elemental composition, 233-236
 relation to wilting coefficient, 157-160
 synthetic power, 404
 water requirement of, 383-388
- Plant cell, 1-39
 absorbing power, 72
 literature on, 41-49
 questions on, 39-41
 stages in growth, 798-800
 suction power, 72
 turgor, 71
- Plant foods, 605
- Plasma membrane, 18, 66-67
 electric potential, 67
 permeability, 67
- Plasmodesma, 19
- Plasmolysis, 69-71
- Plasmolytic method, measuring permeability, 75-76
- Plastids, 20-24
- Polarized light, effect on diastase, 627
 on growth, 828
- Polypeptides, 519
- Polysaccharoses, 411-420
 amyloses, 412-419
 celluloses, 5-9, 412
 galactans, 419
 mannosans, 419
 pentosans, 420
 starches, 412-419
- Poppy and oxidase, 774
- Populin, 631
- Porometer, 328
- Porous-cup atmometers, 373
- Porphyrins, 423
- Potassium, as catalyst, 256
 in food manufacture, 255
 general effect on plants, 256-257
 occurrence in plants, 233-234, 254
 physiological rôle, 255-256
vs. sodium, 282-283
- Potato, absorption of tissue, 180
 acidifying power, 185
 action of potassium, 255
 after-ripening, 816
 aluminum content, 279
 boron content, 269
 CO₂ exhaled, 749-750
 produced, 126
 catalase, 777
 cell sap concentration, 32
- Potato, chlorosis and magnesium, 253
 copper content, 284
 cytase, 630
 depletion of soil, 132
 depth of absorption, 117
 erepsin, 645
 fertilized with CO₂, 458
 formation of cork, 11
 growth-inhibiting substances, 810
 growth-promoting substances, 809
 influence on plants, 131
 leucoplasts, 22
 nitrate reducing substance, 523
 nitrates *vs.* ammonium salts, 501-503
 overcoming dormancy of, 813-814
 oxidase, 769, 774
 pentoses of, 408
 peroxidase, 775
 phospholipides, 580
 protein formation, 534
 proteins, 178, 517
 relation to light, 830, 832
 respiration, 732, 751, 754-756, 763
 response to borax, 272
 to chlorine, 277
 to low temperature, 823
 to potassium, 256
 to sulphur, 260
 roots, 101, 111
 salt requirement, 289
 starch grains, 414
 starch of, 418
 stomata, 321-322
 stomatal type, 331
 sulphur content, 257
 temperature of, 747
 tyrosinase, 770
 water lost, 313
- Potential difference, protoplasmic membrane, 67
- Potential osmotic pressure, 68
- Potometer method, measuring transpiration, 377
- Proenzyme, 612
- Prolamins, 517, 518
- Proline, 513
- Prolipase, 612
- Prooxidase, 612
- Propylene chlorhydrin, 813
- Propionic acid, 566
 in respiration, 735
- Proteases, 613, 637-645
 erepsins or ereptases, 645

- Proteases, historical, 638
 kinds, 638-645
 methods of preparation, 639-640, 642-644
 studying, 637, 642-644
 pepsins or peptases, 638
 trypsins or tryptases, 639
- Protein, amino acids of, 512
 amphoteric nature, 178, 515-516
 chemical properties, 511-516
 classification, 516, 520
 combined, 527
 composition, 511
 conjugated, 518
 defined, 509
 derived, 519
 diurnal variations of nitrogen, 527
 methods of determining, 527
 nitrogen compounds of leaf, 531
 total nitrogen in leaves, 528
 extraction from leaves, 524
 effect of previous treatment, 525
 separation from cells, 526
 formation and light, 533-534
 in leaves, 532
 in seeds, 534-536
 factors influencing, 537-540
 isoelectric point, 178, 515
 metabolism in leaf, 524, 533
 occurrence, 509
 of plant, 509-540
 in protoplasm, 799
 physical properties, 511
 qualitative reactions, 513-515
 relation to oil formation, 586
 to solute intake, 178
 in respiration, 733
 rôle of magnesium in formation, 275
 of potassium in formation, 255
 simple, 517
 solubility, 511
 soluble, 527
 stored food, 605
 sulphur content, 258
 synthesis, 520-540
 translocation, 717-719
- Proteoses, defined, 519
 in seedlings, 718
- Protochlorophyll, 426
- Protoplasm, 15-25
 longevity, 16
 need for water, 308
 parts, 17
- Protoplasm, properties, 15
 in respiration, 731
- Protoplasmic factors, photosynthesis, 468-471
- Protoplasmic membrane (*see* Cytoplasmic membrane).
- Pumpkin, acidity of sap, 38
 chemotropism of roots, 99
 conduction of water, 675
 fixation of nitrogen, 509
 growth, 806
 oils, 578
 photosynthesis, 476
 protein formation, 533-534
 root hairs, 119
 roots, 111
 seed coats, 60
 stomata, 321-322
 temperature of leaves, 365-366
 transpiration, 316
 water content, 309
- Purine bases, 505, 541
- Pyridine, 134, 504
- Pyrogallol, 764
- Pyrrole-carbonic acid, 261
- Q
- Quinine, 541
- Quinone, 134
- Quotient, assimilation, 431
 photosynthetic, 431
 respiratory, 582
- R
- Radiation (*see* Solar radiation).
- Radioactivity, of potassium, 256
- Radish, absorption of organic acids, 241-242
 aeration of roots, 107
 catalase, 780, 782
 composition, 234
 fertilized with CO₂, 459
 fixation of nitrogen, 509
 permeability of roots, 81
 relation to light, 830, 832
 response to aluminum, 280
 to arsenic, 283
 to chlorine, 277
 to iodine, 284
 to sulphur, 260
 root hairs, 30, 120, 134

- Radish roots and temperature, 108
 ..transpiration, 359
- Raffinose, 411
- Rape, 131, 132, 234, 237, 245, 246,
 258, 259, 260, 573, 578, 585
- Rapic acid, 567
- Ratio, absorption, 179
 carbon nitrogen, 543-551
 photosynthetic, 431
 respiratory, 582
- Rays, affecting growth, 827
 utilized in chlorophyll formation, 426
 in condensation, 442, 446
 in photosynthesis, 424, 442, 460-462
- Red amber sorgo (*see* Sorghum).
- Redtop, 132, 234, 280, 814
- Reducing sugars, defined, 407
 in leaf, 437-438
- Reductases, 128-129
- Rennets (*see* Rennins).
- Rennins or rennets, 613, 645-646
- Reproduction and light, 830-832
- Resins, 15, 134, 564, 594
- Respiration, aerobic, and anaerobic, 735-
 739
vs. breathing, 740
 contrasted with photosynthesis, 739
 defined, 730
 energy released, 737
 enzymes of, 766-783
 factors affecting, 748-766
 anesthetics, 760
 CO₂ content, 762
 electricity, 765
 injury, 755
 light, 765
 moisture, 752
 oxygen supply, 762
 salts, 764
 temperature, 748
 tissues, 757
 in leaves, 432
 literature on, 785-796
 loss in weight, 732
 methods of measuring, 741-744
 nature of, 730
 organic materials used, 731-735
 in plants, 729-783
 production of heat, 747
 questions on, 783-785
 relation to catalase, 779
 respiratory quotient, 744-747
- Respiratory index, 759
- Respiratory quotient, 582
 defined, 744
 factors influencing, 744-747
 of seeds, 716, 746
- Respirometers, 741-744
- Rhamnose, 404, 408, 613, 632
- Rhythm of growth, 807
- Rice, acidity, 36
 aeration of, 104
 ammonium salts *vs.* nitrates, 501-503
 influenced by other plants, 137
 iron supply, 265
 maltase, 629
 manganese content, 272
 oil of, 578
 proteins, 517
 respiration, 757
 response to aluminum, 280
 to caesium, 284
 to manganese, 274
 salt requirement, 287
 starch grain, 414
 wilting coefficient, 154, 157
- Ricin, 517
- Ricinoleic acid, 567
- Ricinus (*see* Castor bean).
- Ring experiments, 693-695, 702-703,
 711
- Ripening, after ripening, 815-818
 artificial, 817
- Röhmman-Spitzer reaction, 771
- Root hairs, 118-124
 advantage, 119
 cell walls, 123-124
 concentration of cell sap, 28, 30
 conditions affecting formation, 122
 defined, 119
 factors affecting, 121, 122-123
 growth, 119-122
 location, 118
 longevity, 121
- Root pressure, 168, 676
- Root systems, 97-118
 depth of absorption, 116-118
 extent, 110-118
 relation to incipient wilting, 349
- Roots, 97-138
 decomposition products, 133-136
 depth of absorption, 116-118
 excretions of, 124-138
 acids, 125-128
 beneficial or toxic substances, 129-
 138

- Roots, excretions of, enzymes, 128-129
 extent of, 110-118
 factors affecting development, 97-110
 moisture, 97-98, 112-116
 oxygen, 103-108
 solutes, 98-103
 influence of phosphorus, 246
 of sulphur, 259
 length, 110
 literature, 141-149
 number, 110
 questions on, 138-141
 root hairs, 118-124
 structure, 164-166
 weight, 98, 102, 138
 working depth, 113
 Rotatory power, sugars, 406
 Rusts, influence on stomata, 322
 photosynthesis, 470
 transpiration, 361-362
 Rutabagas, 132, 246, 247, 258
 Rye, acidity, 185
 aluminum content, 279
 amino acids, 519
 CO₂ production, 127
 diastase, 626
 erepsin, 645
 maltase, 629
 oil of seed, 578
 polypeptides, 519
 protein, 517
 relation to light, 829-830
 response to aluminum, 280
 to cobalt, 284
 to iron, 263
 to manganese, 274
 to nickel, 284
 to potassium, 256
 to zinc, 284
 roots, 110, 111, 113
 sitosterol, 568
 stomata, 321-322
 transpiration, 312, 352, 361-362
 water culture, 198
 water requirement, 385-386
- S
- Saccharase (*see* Invertase).
 Saccharose (*see* Sucrose).
 Sach's method, photosynthesis, 474
 Sach's solution, 195
 Salts (*see* Solutes).
 Sand cultures, 194, 209
 Sand drown, 252
 Sap flow, 677
 Sap pressure, 676
 Saponification, of fats, 571
 value, 572
 Saponin, 631
 Saturated fatty acids, 566
 Saturation deficit, 166, 689
 Schweitzer's reagent, 6
 Scutellum of corn, 648, 649, 650
 Seed coats, membranes, 60-64
 permeability to solutes, 62-64
 to water, 60-62
 Seeds, after-ripening, 815
 dormancy of, 811-813
 imbibition of water, 160
 longevity, 811
 means for measuring water-supplying
 power of soil, 160-162
 overcoming dormancy, 814-818
 size and growth, 819-820
 Selective absorption, of elements, 236
 Selenium, 283
 Semi-drying oils, 572
 Semipermeable membrane, cell wall,
 62-63
 cytoplasm, 67
 defined, 54
 seed coats, 62-65
 Serine, 513
 Sesamum, root excretions, 137
 Shive's solution, 196
 Short-day plants, 830
 Sieve plates, 671
 Sieve theory of membrane action, 85
 Sieve tubes, 671, 712
 Significance of transpiration, 382-383
 Silicates, in nutrition, 267-269
 occurrence, 27, 267
 Silicin, 631
 Silicon, occurrence, 233, 234, 266
 physiological rôle, 266-267
 Simple lipides, 569-574
 fats and fatty oils, 569-573
 waxes, 573
 Sinapis (*see* Mustard).
 Siningrin, 631, 632
 Sitosterol, 568
 Sodium, in nutrition, 282-283
 Soil, aeration, 103-106
 cones for water-supplying power, 162

- Soil, fertility and water requirement, 386-388
 moisture and water requirement, 388
 texture and root development, 109
 type and wilting coefficient, 154
- Solar radiation, 350
 coefficient of absorption, 477
 determination of energy used, 479
 energy used in photosynthesis, 479
 expressed, 350
 influence on cyclic factors, 350
 on transpiration, 350-352
 total incident, 476
 utilization by leaves, 478
- Solarisation, 469
- Soluble starch, 418, 624
- Solutes, defined, 51
 influence on permeability, 82-85
 on root development, 98-103
 intake by plants, 174-221
 relation to transpiration, 190-193
 translocation, 692-695
- Solution theory of membrane action, 85
- Solutions, colloidal, 50
 culture, 194
 defined, 50
 diffusion, 52-54, 56-59
 expressing concentration, 51-52
 hypertonic, 71
 hypotonic, 71
 isotonic, 71
 literature on, 91-96
 nutrient, 193-218
 questions on, 89-91
 true, 50
- Solvent, 51
- Sørensen method, 637
- Sorghum, acidity, 36
 catalase, 778, 780, 781
 depth of absorption, 116
 influence on plants, 132, 135-136
 leaf surface, 348
 light rays, effect, 827
 nitrogen content, 500
 in leaves, 531
 oxidase, 774
 phospholipides, 581
 photosynthesis, 476
 proteins, 517
 relation to soil moisture, 159
 respiration, 752-753
 response to aluminum, 280
 to phosphorus, 246
- Sorghum, roots, 107, 111, 113, 138, 349
 stomata of, 319-323
 structure of leaf, 345
 temperature and growth, 821
 of leaf, 365-369
 transpiration, 192, 310, 311, 316, 352, 370-371
 water of leaf, 338-340
 water requirement, 385-386
 wilting coefficient, 154, 157-158
- Soybeans, absorption of elements, 237
 acidity, 37
 amino acids, 718
 boron content, 269
 calcium-magnesium ratio, 251
 composition, 234
 light rays affecting, 827
 low temperature, effect, 823
 manganese content, 272, 273
 nitrate, content, 521
 nitrogen content, 500
 in leaves, 529
 oil formation, 584
 oils of, 568, 570, 573, 578
 phospholipides, 580-581
 proteins, 517
 relation to light, 829-831
 response to barium, 283
 to iron, 263
 to phosphorus, 246
 to potassium, 257
 to strontium, 283
 root oxidation, 129
 stomata of, 321-322
 temperature of leaves, 365-369
 transpiration, 316, 355
 water culture, 200, 212
- Spectrum, of carotin, 424
 of chlorophyll, 424
 of xanthophyll, 424
- Spherocrystals, starch grains, 415
- Spinach, 236, 237, 276, 524, 645, 778, 782, 833
- Spraying, iron salts, 265
 manganese salts, 276
- Sprays, relation to transpiration, 358-360
- Squash, aeration of roots, 107
 globulin of, 511
 iron supply, 266
 oil of, 570, 573
 proteins, 517
 relation to light, 829, 830
 root hairs, 122, 124

- Squash, roots, 110
 seed coats, 60
 stomata, 321-322
- Standard rate of water loss, 380
- Starch, composition, 418
 general properties, 417-419
 grain (*see* Starch grain)
 in guard cells, 326-327
 in leaves, 433-441
 occurrence, 412
 paste, 418
 permanent, 416
 relation, to potassium, 255
 of sulphur, 259
 soluble, 418
 temporary, 416
- Starch grain, center of origin, 413
 composition, 415
 kinds, 413
 occurrence, 413
 relation to plastids, 416
 structure, 414
- Starch paste, 418, 624
- Starch plants, 469
- Starches, 412-419
 dextrans, 419
 inulin, 419
 starch or amyllum, 412-419
- Stearic acid, 134, 566
- Sterols, 564, 565, 568
- Stigmasterol, 568
- Stoma, 315, 317
- Stomata, capacity, 332-337, 342
 daily movement, 330-332
 defined, 317
 dimensions, 323
 factors influencing number, 318-319,
 322-323
 movement and transpiration, 341-342
 number, 318-323
 and transpiration, 339-341
 occurrence, 317
 opening and closing, 323-332
 factors influencing, 329-330
 methods of measuring, 328
 regulation of water loss, 337-342
- Stomatal apparatus, 318
- Stomatal index, 319
- Stomatal pore, 318
- Stomatal transpiration, 332, 344
- Stomatal types, 331
- Straight head of rice, 104
- Strawberry, 459
- Strontium, in alfalfa and tobacco, 235
 in nutrition, 283
 in plants, 232
- Strychnine, 541
- Suberin, 9-11
- Subsidiary cells, 317, 327
- Substance quotient, 802
- Substrate, 611
- Succinic acid, 27, 134, 249
- Sucrase (*see* Invertase).
- Sucrose, description, 410
 in leaves, 433-441
 utilization by plants, 239-241
- Suction pressure of cell, 72-73
- Suction tension of cells, 72-73
- Sudan grass (*see* Sorghum).
- Sugar plants, 469
- Sugars, first formed, 439
 in guard cells, 327
 kinds or types, 407-411
 disaccharoses, 410-411
 monosaccharoses, 407-410
 trisaccharoses, 411
 physical and chemical reactions, 406-
 407
 formation of osazones, 407
 reducing action, 407
 specific rotatory power, 406
 in respiration, 732
 translocation, 698, 710-714
- Sulphates, occurrence, 16, 27, 257-258
- Sulphur, amount used by plants, 257
 as fertilizer, 259-260
 form in which utilized, 257
 formative effects, 259
 occurrence in plant, 233, 257-258
 physiological rôle, 258
 in protein, 511
- Sulphur reaction, protein, 515
- Sulphuretted oils, 595
- Sunflower, absorption of energy, 478
 acidity, 36, 38
 aluminum content, 279
 area of stomata, 336
 changes in oil in germination, 588-594
 chemotropism of roots, 100
 composition, 235
 conduction of water, 675
 etiolation and photosynthesis, 466
 formation of oil, 584
 iron supply, 266
 light rays, effect, 827-828
 need of zinc, 244

Sunflower, oils of, 568, 570, 573, 578
 pentoses, 408
 permeability of cells, 81, 86
 photosynthesis, 467, 476
 plastids, 23
 relation to light, 829
 respiration, 733-734
 respiratory index, 759
 respiratory quotient, 746
 response to aluminum, 280
 root hair, 30, 119
 roots, 6
 seed coats, 63
 stomata, 341
 transpiration, 357, 361-362
 water lost, 313
 Sweet potato, 11, 104, 733, 755, 756
 Synthetic power of plant, 404

T

Taka diastase, 620, 629
 Tammann's principle, 464
 Tanks, evaporation, 372
 Tannic acid, influence on transpiration, 357
 precipitation of proteins, 514
 Tannin, 404
 absorption of oxygen, 760
 action on diastase, 625
 on invertase, 619
 in cell wall, 15, 61
 influence on oxidase, 773
 nature of, 631
 occurrence, 632
 relation to oil, 586
 Tartaric acid, 27, 583, 619
 Tartrate, ferric and ferrous, 263
 Tautomerization, 637
 Temperature, action on invertase, 619
 of air, 364
 coefficient, 86, 463
 of permeability, 86-87
 of photosynthesis, 463
 death point, 370, 822-824
 influence on bromelin, 643
 on diastase, 626
 on glucase, 629
 on lipase, 637
 on papain, 641
 on permeability, 79-82
 on photosynthesis, 463-465
 on root hairs, 120

Temperature, influence on stomata, 330
 on transpiration, 352
 on nutrient solutions, 206-207
 of leaves, 362-370
 factors influencing, 363
 methods of measuring, 363-364
 relation to growth, 820-824
 respiration, 748-752
 secretion of enzymes, 652
 response to roots, 108-109
 Terpenes, 594
 Tetrachloride, 813
 Theine, 541
 Theobromine, 541
 Theories of membrane action, 85-89
 Theory, chemical, of photosynthesis, 86-87
 colloidal, 88-89
 photosynthesis, 444-451
 sieve, 85
 solution, 85
 Thermocouple, 362-365
 Thermotropism of roots, 108-109
 Three-salt solution, 196, 203, 204
 Tiglic acid, 567
 Timothy, acidity, 37
 aluminum content, 279
 calcium content, 247
 composition, 234
 depletion of soil, 132
 relation to light, 830
 response to aluminum, 280
 to selenium, 283
 to sulphur, 260
 toxic extracts, 136
 Titanium, 283
 Tobacco, absorption of elements, 237
 calcium content, 247
 composition, 234
 influence upon plants, 131, 133
 lithium content, 235
 relation to light, 830
 response to potassium, 257
 to sulphur, 260
 root hairs, 124
 sand drown and magnesium, 252
 strontium content, 235
 transpiration, 191
 Toluene, action on diastase, 625
 on invertase, 616
 on maltase, 629
 Tomato, absorption of elements, 237
 acidity, 37

- Tomato, affected by walnut, 132**
 amino acids, 523
 boron content, 269
 catalase, 778, 782
 color, 428
 erepsin, 645
 fertilization with CO₂, 458
 growth-inhibiting substances, 810
 growth-promoting substances, 809
 influence, of low temperature, 823
 on other plants, 131
 peroxidase, 775
 phosphorus content, 245
 plastids, 22
 relation to light, 827, 829, 830, 833
 to potassium, 257
 respiration, 757
 response to phosphorus, 246
 to potassium, 256
 ripening, 817
 root hairs, 124
 stomata, 321-322
 sulphur content, 258
 synthesis of protein, 523
 transpiration, 358-361
 water content, 309
 water lost, 313
 wilting coefficient, 154
- Tonoplast, 18, 66**
Tottingham's solutions, 195
Toxic substances, of roots, 134-138
Tracheae, 670
Tracheids, 670
Tradescantia, 80, 120, 123, 549, 675, 810
Translocation, 669-719
 literature on, 721-728
 minerals in seedlings, 288-289
 movement of materials, 672-719
 inorganic compounds, 692-696
 organic compounds, 678-719
 water, 672-692
 need of, 669
 questions on, 719-721
 tissues concerned, 669-672
- Transpiration, coefficient, 374**
 cuticular, 332, 344
 during day and night, 311-312
 defined, 311
 effect of humidity, 353
 of temperature, 352
 of wind, 353-354
- Transpiration, factors influencing rate, 313-362**
 aerial and meteorological conditions, 350-354
 chemicals, 356-361
 concentration of sap, 345
 fungi, 361-362
 hairs, 342-344
 incipient drying, 346-350
 leaf structure, 313-346
 water in soil, 354-356
 methods of measuring, 376-382
 cobalt chloride, 378-380
 Freeman's method, 380-382
 potometer, 377
 weighing, 377-378
 ratio to evaporation, 374-376
 relation to intake of solutes, 190-193
 to leaf temperature, 368
 to number of stomata, 339
 to stomatal opening, 341
 relative, 316, 374
 significance, 382-383
 stomatal, 332, 344
- Transpiring power, 374**
Triangle system in nutrition, 203-206
Trichites, 416
Trichlorethylene, 814
Trichomes, 342
Triglycerides, 575
Trisaccharoses, 411
Triticin, 419
Triticum (see Wheat).
True solution, 50
Trypsin, 613
 occurrence in plants, 639-644
 preparation, 641, 643-644
- Tryptases (see Trypsin).**
Tryptophane, in digestion, 637, 638, 640
 formula, 513
 in seeds, 534
- Tuberin, 516, 517**
Turanose, 411
Turgidity, 71
 of leaves, 365
 relation to transpiration, 355
- Turgor pressure, 71-72**
Turnip, 245, 247, 257, 260, 280, 408, 645, 769
Turpentine, 595
Tyloses, 695
Tyrosinases, 769

Tyrosine, action on diastase, 626
 in digestion, 640, 641
 formula, 513
 in seedlings, 718
 in soil, 134
 utilization, 504

U

Ultra-violet light, in carbohydrate synthesis, 446, 449
 in condensation, 448
 effect on growth, 827
 in protein formation, 534
 Unequal absorption of ions, 182-190
 (*See also* Ions.)
 Unessential *vs.* essential elements, 242-244
 Unsaturated fatty acids, 567
 Upward transfer of inorganic compounds, 692-695
 Urea, 504
 Uric acid, 504

V

Vacuole, origin, 25-26, 800
 (*See also* Cell sap.)
 Valeric acid, 566
 Valine, 513
 Valonia, 38, 67, 78, 176
 Vanillin, 134
 Van Slyke method, 637
 Vertical penetration of roots, 112-115
 Vessels (*see* Tracheae).
 Vicia faba, cell walls of root, 6
 etiolated plants, 825
 growth, 801, 806
 legumin, 511
 need of boron, 243
 of zinc, 244
 nitrate-reducing substance, 524
 osmotic value of sap, 73
 permeability of pith cells, 86
 photosynthesis, 466
 protein formation, 534
 proteins, 517
 response to aluminum, 280
 to boron, 269-271
 Vicilin, 516, 517
 Vignin, 517

Vigor, relation to acidity, 38
 Vital theories of water ascent, 680-683
 Vitamines, 243, 404, 504, 808
 Volatile fatty acids, 566

W

Walnut, absorption of ions, 188
 formation of oil, 584
 need for magnesium, 252
 proteins, 517
 toxic effect, 132, 137
 Water, amount lost from plant, 312-313
 amount needed, 309
 amount in soil and transpiration, 354-356
 cohesive force, 686, 688
 content of leaf, 338
 control of loss, 337-342
 cultures *vs.* sand cultures, 209
 diffusion through cell wall, 59-62
 entrance into root, 164-170
 evaporation from plant, 311-388
 factor influencing loss, 313-362
 of guttation, 388-390
 imbibition, 55
 influence on root development, 97-98
 on root hairs, 122
 on photosynthesis, 467
 on secretion of enzymes, 652
 intake by leaves, 150-151
 by plants, 150-170
 loss from plants, 308-390
 need by plants, 308-311
 percentage in tissue, 309
 in cell sap, 26
 relation to respiration, 752-755
 requirement of plants, 383-388
 standard rate of loss, 380
 test time, 380
 translocation of, 672-692
 ascent of water, 675-689
 in absence of living cells, 683
 physical theories, 683-689
 under high evaporation, 679-691
 under low evaporation, 676-679
 vital theories of, 680-683
 downward movement, 689-690
 lateral movement, 691-692
 pathway of movement, 672
 water-conducting cells, 673

- Water, vapor diffusion, 334
 working margin, 339
- Water cultures, 194
- Water supplying power of soil, critical, 163
 at wilting, 160-164
- Watermelon, 124, 321, 365
- Wave lengths of light, in photosynthesis, 460-462
- Waxes, 564, 565, 573
- Waxy gene, 587
- Weighing method of measuring transpiration, 377
- Weight of roots, 98, 102, 138
- Wheat, acidity, 36, 37, 185
 aluminum content, 279
 amino acids, 519
 boron content, 269
 calcium content, 247
 magnesium ratio, 251
 CO₂ production, 127
 carbon nitrogen ratio, 547
 catalase, 780
 cell sap concentration, 29
 composition, 234-235
 diastase, 626
 erepsin, 645
 fixation of nitrogen, 509
 formation of grain, 535-536
 influence of electricity, 834
 of other plants, 133, 135, 137
 on other plants, 129-130, 137
 iron content, 235
 maltase, 629
 manganese, content, 273
 mitochondria, 25
 movement of organic materials, 698
 nitrate content, 521
 nitrates *vs.* ammonium salts, 501-502
 oil of seed, 578
 pentosans, 420
 permeability of seed coat, 63
 phospholipides, 580-581
 polypeptides, 519
 potassium content, 254
 proteases, 638
 protein, 517, 518, 537-540
 relation to light, 829, 830
 respiration, 739, 748, 752, 757, 765
 respiratory quotient, 746
 response to aluminum, 280
 to arsenic, 283
- Wheat, response to barium, 283
 to borax, 271
 to chlorine, 277-279
 to iron, 262-263
 to phosphorus, 246
 to potassium, 256
 to strontium, 283
 to sulphur, 260
 root hairs, 122
 roots, 98, 101-102, 110, 111, 113, 128, 138
 salt requirement, 285, 287
 sitosterol, 568
 starch, 418
 stomata, 318, 321-322
 translocation of carbohydrates, 713
 transpiration, 312, 352, 361-362, 370-371
 utilization of organic compounds, 504
 water cultures, 196, 206-212, 215-216, 219
 water lost, 313
 water requirement, 385-386
 wilting coefficient, 154, 157-158
 yellow berry, 539
- Wilted plants, temperature of, 368
 transpiration of, 355
- Wilting, incipient, 347
 permanent, 152
 relation to leaf surface, 348
 to root system, 349
 to transpiration, 346-350, 355
- Wilting coefficient, calculated, 152
 defined, 152
 factors influencing, 154-160
 climatic conditions, 154-157
 kind of plant, 157-160
 type of soil, 154
 methods of determining, 152-154
 observed, 152
- Wind, influence on transpiration, 353-354
- Winter injury, 701
- Working depth of roots, 113, 116-118

X

- Xanthine, 134, 504, 541
- Xanthium (*see* Cocklebur).
- Xanthophyll, 428
- Xanthoproteic reaction, 514

X-rays and growth, 828

Xylan, 420

Xylem, 670

 conduction, 692-695, 704, 705

Xylose, 7, 408, 420

Y

Yellow berry, 539

Z

Zalenski's law, 323

Zea mays (*see* Corn).

Zein, 517

Zinc, 243-244, 284

Zymase, 611

Zymogen, 612

 of lipase, 636

