UNIVERSAL
LIBRARY
OU_170945
UNIVERSAL
LIBRARY

OUTLINES OF EVOLUTIONARY BIOLOGY

By the same Author

THE BIOLOGICAL FOUNDATIONS OF SOCIETY

ANIMAL LIFE AND HUMAN PROGRESS

Edited by

ARTHUR DENDY
D.Sc., F.R.S.

OUTLINES OF EVOLUTIONARY BIOLOGY

BY

ARTHUR DENDY, D.Sc., F.R.S.,

Professor of Zoology in the University of London (King's College);
Honorary Member of the New Zealand Institute, formerly
Professor of Biology in the Canterbury College
(University of New Zealand), and Professor of
Zoology in the South African College,
Cape Town

With Glossary of Technical Terms

Fourth Edition

LONDON

CONSTABLE & COMPANY LTD

First Published . . 1912
Second Edition . . . 1912
Reprinted 1914
" 1916
" 1918
" 1920
" 1921
Third Edition . . 1923
Reprinted . . . 1924
Fourth Edition . . . 1929

PRINTED IN GREAT BRITAIN BY THE WHITEFRIARS PRESS LTD.,
LONDON AND TONBRIDGE.

PREFACE

Biology, the fundamental science of living things in all their manifold relations, is a study which, at the present time, is but little encouraged by educational authorities in this country. It has no place in the ordinary school curriculum and even in our Universities it has been thrust into the background, partly because University authorities devote so much of their attention nowadays to subjects which are considered more likely to bring in a direct pecuniary reward to the student, and partly because of the immense elaboration of the various branches of biological science, such as Zoology, Botany, Physiology, Comparative Anatomy and Embryology, that has taken place in recent years, and the claims of these to more or less separate recognition.

The student, if he studies Biology at all for its own sake, which is seldom the case, usually confines himself almost entirely to one or other of these branches, which he finds treated more or less as an independent science, with an extensive literature of its own, and he runs a grave risk of losing sight of the general principles which underlie all and from which all derive their chief educational value.

The medical student, it is true, usually takes a year's course in what is called Biology, but his curriculum is, perhaps unavoidably, dominated by the type-system and by what is thought likely to be of direct service to him in his future anatomical and physiological studies, so that in the brief time which the medical authorities allow him to devote to the scientific foundation of his professional work he has but little opportunity for a philosophical treatment of the subject.

When we at length come to realize the meaning of Man's position as, for the time being, the highest term of a great evolutionary series which stretches far back into the dawn of

the earth's history, and to appreciate the importance of the fact that he derives his existence from the same ultimate sources and is subject to the same natural laws as all the other living things with which he shares the earth, we shall perhaps see the necessity for making Biology, in the widest sense of the term, one of the foundation stones of our educational system.

In the meantime those who wish to familiarize themselves with the rapidly accumulating results of biological investigation and the bearing of these results upon human problems ought not to be debarred from so doing by want of the necessary knowledge of fundamental facts and principles, and it is largely with a view to the requirements of such students that the present work is offered to the public.

That even the elementary study of biological theory should, wherever possible, be preceded by a systematic course in Zoology and Botany, based upon the type-system and including laboratory work, is, no doubt, indisputable. Unfortunately, under existing conditions, regular laboratory work is, for most people, impossible. We are apt to forget, however, that in reality we all of us spend our lives in a biological laboratory, where we are surrounded by living organisms which we can hardly avoid studying. In this way we learn much of the nature of living things and are to some extent prepared for the study of biological principles.

The problems of life, however, cannot be satisfactorily solved if we confine our attention to the higher and more familiar forms of plants and animals. Man, in particular, is far too complex a type to begin with in a philosophical treatment of the subject. The logical method of study is, no doubt, to follow as closely as possible the course which we believe to have been taken in the actual evolution of living things, beginning with the simple and ending with the complex. This method, of course, is attended with certain practical difficulties, mainly due to the microscopic size of the more primitive organisms, but these difficulties are not insurmountable and need not be considered in relation to the present work.

As I wish this book to be of use to those who have had no special biological training, as well as to students who have taken the ordinary first year's course, I have, in the earlier chapters, dealt in a very elementary manner with the structure and functions of both plants and animals. I have described Amœba

and Hæmatococcus in considerable detail and used these familiar organisms as pegs on which to hang some elementary ideas with regard to the nature of living things and the differences between animals and plants. Otherwise I have as far as possible avoided the type-system as being altogether unsuitable for a work of this kind, though of course I have been obliged to refer to numerous different organisms in illustration of special points.

It was only by rigidly excluding from the earlier part of the book everything that was not considered essential to the understanding of general principles that it has been possible to find space for even a brief presentation of the evidence upon which the theory of organic evolution rests, and for a discussion of the principal factors which appear to have co-operated in determining the course of that evolution.

Although the entire work is intended to be of an elementary character, it has been impossible, in connection with the theory of heredity, to avoid, on the one hand, a considerable amount of cytological detail, and, on the other, some discussion of theoretical speculations of a highly controversial nature. In dealing with these vexed questions, which underlie the whole problem of organic evolution, I have endeavoured to present the views of opposing schools of thought as fairly as possible, but I must confess that I have ventured to lay considerable stress upon ideas which, though widely accepted elsewhere, have not as yet met with much appreciation in this country, though that they will do so in the future can hardly be doubted.

By way of introduction to the discussion of the factors of organic evolution a chapter has been devoted to the views of Buffon, Erasmus Darwin and Lamarck, and another to those of Charles Darwin, Robert Chambers and Alfred Russel Wallace, and I have endeavoured to present the opinions of these classical authors as far as possible by means of quotations from their own writings.

In a work such as the present the employment of numerous technical terms is, of course, unavoidable, but it is hoped that the meaning of these is sufficiently explained in the text, and the use of the index should obviate any difficulties in this respect, especially if the book is read systematically from the first chapter onwards.

It is a pleasure to record my thanks to many colleagues who have ungrudgingly helped me in various ways. Amongst these

I should like especially to mention Professor Poulton, Professor Herbert Jackson, Dr. Stapf, Dr. Daydon Jackson, Dr. Sibly and Professor G. E. Nicholls; while to Mr. R. W. H. Row, of the Zoological Department at King's College, I am much indebted for the trouble which he has taken in reading through the proof-sheets and for many valuable suggestions.

I owe a sincere acknowledgment to my publishers, Messrs. Constable & Co., for their generosity in the matter of illustrations. Most of these are either entirely new or, in some cases, specially re-drawn from original memoirs. I have made extensive use of photomicrography for microscopic subjects, and in the preparation of the photographs at King's College have received much assistance from Dr. Rosenheim, Mr. Row, and my assistant Mr. Charles Biddolph.

For the loan of the blocks from which the remainder of the illustrations have been printed, or for permission to copy, I am indebted to the generosity of the following :—

Messrs. George Allen and Son,
"The American Journal of Science,"
Mr. Edward Arnold,
Messrs. George Bell and Sons,
Messrs. A. and C. Black,
The Cambridge University Press,
The Clarendon Press,
Messrs. Constable & Co.,
Messrs. Duckworth & Co.,
Herr W. Engelmann,
Herr Gustav Fischer,
"The Journal of Experimental Zoology,"
Messrs. Kegan Paul, Trench, Trubner & Co
The Council of the Linnean Society of London.
Messrs. Longmans, Green & Co.,
Mr. John Murray,
"The Quarterly Journal of Microscopical Science
The Council of the Ray Society,
Messrs. Smith, Elder & Co.,
The Trustees of the British Museum,
Messrs. T. Fisher Unwin,
Messrs. F. Warne & Co.,
Verlag des Bibliographischen Instituts, Leipzig und Wien.

I must also express my gratitude to the numerous authors whose work I have made use of, and whose names are mentioned in the appropriate places.

I am indebted to the Council of the Royal Society of Arts for permission to make use of the Aldred Lecture which I delivered before the Society in 1909, and which is to a large extent reprinted from their Journal in Chapter XIV.

ARTHUR DENDY.

KING'S COLLEGE, LONDON,
December, 1911.

PREFACE TO SECOND EDITION

So short a time has elapsed since the publication of the first edition of this book that it has not been found necessary to make many alterations in reprinting it. Advantage has been taken, however, of the opportunity afforded to make a few corrections and to add a few notes. At the request of my publishers I have also added a Glossary of Technical Terms, and I have to thank Professor Bernard Bosanquet, LL.D., for his kindness in revising the proof-sheets of this, with special reference to the Greek and Latin derivations. I am also indebted to the Rev. A. C. Headlam, D.D., Principal of King's College, for valuable advice in this connection.

ARTHUR DENDY.

KING'S COLLEGE, LONDON.
October, 1912.

PREFACE TO THIRD EDITION

— ✦ —

TEN years have elapsed since the publication of the second edition of this book, and the time has now come when it seems desirable to make a thorough revision of the text, and to incorporate a certain amount of new matter based upon recent advances in Biological Science.

Amongst these advances, none have a greater claim upon our attention than the remarkable results obtained by Professor T. H. Morgan and his colleagues in America with regard to the location of the "Mendelian factors" or "genes" in the chromosomes of the germ cells, and I have included a very brief account of these results in Chapter XIII., together with three illustrations, for which I am indebted to the publishers, Messrs. Henry Holt & Co.

The chapters dealing with heredity have been rearranged and amplified, and the problems of the origin of living things, the individuality of the organism and the age of the earth, have received more attention.

As in the case of the first edition, I have made use of addresses which I have delivered on various occasions, especially of my Presidential Address to Section D of the British Association for the Advancement of Science at the Australian meeting in 1914. This is reprinted, with certain modifications, in Chapter XXVIII., as a summary of the whole argument with regard to the *modus operandi* of organic evolution, and in the hope of showing that biologists are not so utterly incapable of forming a mental picture of the course of events as might be supposed by readers of some recent pronouncements. It is important that the general public should realize that the endless discussions amongst biologists as to the details of the process by no means invalidate the doctrine of organic evolution in its essential aspects, and that the foundations of that doctrine have been in no way undermined by recent investigations. On the contrary, they have been strengthened and extended.

The very generous and almost unanimous appreciation with which the book has been received by numerous reviewers and correspondents has naturally been a source of much gratification, but I have long been aware of its many deficiencies. These were duly emphasized by an anonymous critic, evidently deeply imbued with mechanistic ideas, who was good enough to inform us, amongst other things, that "the present-day biologist is certainly incompetent to discuss the philosophy of so vast a subject as that of the nature of life, which is admittedly an infinitely intricate nexus of complex chemical events." As to the first of these statements, I am inclined to agree with my critic, but it may be doubted whether the present-day chemist is in any better position. The bio-chemist, however, is now entering into his kingdom, and may confidently be expected to throw much light upon the problem of the evolution and reactions of living matter. That, however, is not quite the same thing as the problem of the nature of life, which is one that chemists and biologists alike would probably do well to leave in the hands of the philosophers. It is certainly beyond the scope of the present volume, in which it is only very briefly referred to.

I am, as before, indebted to several of my scientific colleagues for valuable information and suggestions, and especially to my publishers for the very generous manner in which they have allowed me absolute freedom to make such alterations in the text and illustrations as seemed desirable.

ARTHUR DENDY.

KING'S COLLEGE, LONDON,

CONTENTS

PART I.—THE STRUCTURE AND FUNCTIONS OF ORGANISMS—THE CELL THEORY

CHAPTER I

PAGE

Introductory: The nature of life—The living organism viewed as a machine—The essential functions of the living body—The source of energy in living things 1

CHAPTER II

Amœba as a typical organism—The properties of protoplasm . . 12

CHAPTER III.

Hæmatococcus—The differences between animals and plants . . 27

CHAPTER IV

The cell theory—Unicellular organisms—Differentiation and division of labour—Co-operation—The transition from the unicellular to the multicellular condition—The early development of multicellular animals and plants 36

CHAPTER V

The cell theory as illustrated by the histological structure of the higher animals and plants—Limitations of the cell theory—The cell as the physiological unit 51

CHAPTER VI

The multiplication of cells—Mitotic and amitotic nuclear division . 69

PART II. THE EVOLUTION OF SEX

CHAPTER VII

Limitation of the powers of cell-division—Rejuvenescence by conjugation of gametes—The origin of sex in the Protista . . . 81

CHAPTER VIII

PAGE

Sexual phenomena in multicellular plants—The distinction between somatic cells and germ cells—Alternation of sexual and asexual generations—Suppression of the gametophyte in flowering plants. 95

CHAPTER IX

Sexual phenomena in multicellular animals—Structure and life history of Hydra and Obelia—Alternation of generations—The cœlomate type of structure—Secondary sexual characters—The evolution of sex 113

CHAPTER X

Origin of the germ cells in multicellular animals—Maturation of the germ cells—Reduction of the chromosomes—Sex determination in insects—Different forms of gametes—Mutual attraction of the gametes—Fertilization and parthenogenesis . 129

PART III.—VARIATION AND HEREDITY

CHAPTER XI

Variation—Meristic and substantive variations—Fluctuations and mutations—Somatogenic and blastogenic variations—Origin of blastogenic variations 148

CHAPTER XII

Heredity—General observations—Preformation and epigenesis—The common-sense view of heredity—Weismann's theory of the continuity of the germ plasm—The nucleus as the bearer of inheritable characters 161

CHAPTER XIII

The Mendelian experiments in hybridization—The doctrine of unit characters and the purity of the gametes—The localization of Mendelian factors in the chromosomes—The possible nature of these factors—Galton's law of inheritance . . . 171

CHAPTER XIV

The inheritance of acquired characters and the mnemic theory of heredity 196

PART IV.—THE THEORY AND EVIDENCE OF ORGANIC EVOLUTION: ADAPTATION

CHAPTER XV

Organic evolution *versus* special creation—The origin of living things—Mechanism and vitalism—The problem of individuality 218

CHAPTER XVI

PAGE
The continuity of life—The conception of species—The principles of taxonomy—The taxonomic evidence of organic evolution . . 232

CHAPTER XVII

Connecting links - Homology and analogy - Convergent evolution—Change of function—Vestigial structures -Reversion . 243

CHAPTER XVIII

Ontogeny—The recapitulation hypothesis—Interpretation of the ontogenetic record—Palingenetic and cænogenetic characters . . 274

CHAPTER XIX

The stratified rocks—Geological periods—The age of the habitable earth—The geological record—The succession of the great vertebrate groups 293

CHAPTER XX

Fossil pedigrees—Ancestry of birds, horses, elephants and whales . 316

CHAPTER XXI

Geographical distribution—Areas of distribution—Barriers to migration—Means of dispersal - Changes in the physical conditions of the earth's surface—The evidence afforded by the study of geographical distribution with regard to the theory of organic evolution . 330

CHAPTER XXII

Adaptation to environment in animals—Deep sea animals—The colouration of animals - Protective and aggressive resemblances—Warning colours—Mimicry—Epigamic ornamentation 345

CHAPTER XXIII

Adaptation to the environment in plants—Alpine plants, desert plants and lianes—The modification of flowers in relation to insect-fertilization 361

PART V.—FACTORS OF ORGANIC EVOLUTION

CHAPTER XXIV

Views of Buffon, Erasmus Darwin and Lamarck 376

CHAPTER XXV

Robert Chambers and the "Vestiges of Creation"—Natural selection—The views of Charles Darwin and Alfred Russel Wallace . . 394

CHAPTER XXVI

PAGE

Illustrations of the action of natural selection in the struggle for existence Degeneration—Artificial selection—Mutation and adaptation 406

CHAPTER XXVII

Isolation—Physiological selection Non-adaptive characters—Excessive growth Synchronism in evolution of organs—Indifferent characters 419

CHAPTER XXVIII

The mechanism of organic evolution: summary and recapitulation—The ancestry of man 430

INDEX 455

GLOSSARY OF TECHNICAL TERMS xvii

GLOSSARY OF TECHNICAL TERMS

ABIOGENESIS (Gr. *a*, without; *βίος*, life; *γένεσις*, birth), spontaneous generation, the origin of living from not living matter.

ACHROMATIC FIGURE (Gr. *a*, without; *χρῶμα*, colour), that part of the nuclear figure which remains colourless after treatment with certain staining reagents.

ADRENAL (Lat. *ad*, near to; *renes*, kidneys), a glandular body attached to the kidney.

ALBUMIN (Lat. *albumen*, white of egg), a proteid substance which occurs in the white of eggs.

ALLANTOIS (Gr. *ἀλλᾶς*, sausage), a membranous bag which grows out from the alimentary canal in the embryos of higher vertebrates, and serves as an organ of respiration or nutrition, or both.

ALLELOMORPH (Gr. *ἀλλήλων*, one another; *μορφή*, kind, sort, form), one of a pair of alternative characters in Mendelian inheritance.

AMBULATORY (Lat. *ambulator*, walker), used in walking.

AMITOTIC (Gr. *a*, without; *μίτος*, thread), a term applied to nuclear division without mitosis (*q.v.*).

AMNION (Gr. *ἀμνίον*), a membranous bag which encloses the embryo in higher vertebrates.

AMŒBOID, a term applied to movements like those of Amœba.

AMPHIMIXIS (Gr. *ἀμφί*, on both sides; *μίξις*, mingling), the mingling of maternal and paternal characters in the fertilisation of the egg.

ANABOLISM (Gr. *ἀναβολή*, throwing up), the constructive chemical processes which go on in the living body, whereby food material is converted into protoplasm.

ANALOGY (Gr. *ἀναλογία*), superficial resemblance due to similarity of function.

ANATOMY (Gr. *ἀνά*, *τομή* cutting up), the study of the structure of organisms (more especially as revealed by dissection).

ANDRŒCIUM (Gr. *ἀνήρ*, man; *οἰκίον*, dwelling), the collective stamens or "male" organs of a flower.

ANEMOPHILOUS (Gr. *ἄνεμος*, wind; *φίλος*, beloved), a term applied to flowers which are pollinated by wind.

ANISOGAMY (Gr. *ἄνισος*, unequal; *γάμος*, marriage), the union of differentiated (male and female) gametes or sexual cells.

ANTHERIDIUM (Gr. *ἀνθηρός*, pertaining to a flower), an organ or receptacle in which male sexual cells or gametes are produced, in ferns and algæ

ANTHERS (Gr. *ἀνθηρός*, pertaining to a flower), the receptacles which contain the pollen grains in flowering plants.

ANTIBODY (Gr. *ἀντί*, opposed to), a substance formed in the blood as a protection against the action of foreign proteids.

ANTICRYPTIC (Gr. *ἀντί*, opposed to; *κρυπτός*, hidden), a term applied to colouration adapted for concealment when used as a means of aggression by ambuscading.

ANTITOXIN (Gr. *ἀντί*, opposed to; *τοξικόν*, poison), a substance formed in the blood as a protection against poisons.

APATETIC (Gr. *ἀπατητικός*, fallacious), a term applied to misleading colouration, whether for offence or defence.

APOGAMY (Gr. *ἀπό*, away from; *γάμος*, marriage), the suppression of the sexual process in the reproduction of certain plants.

APOSEMATIC (Gr. *ἀπό*, away from; *σῆμα*, signal), a term applied to warning colours, which serve to frighten away enemies.

ARCHEGONIUM (Gr. *ἀρχή*, beginning; *γόνος*, fruit, offspring), the female organ or receptacle in which the ovum is lodged in certain plants, and in which the young plant begins its development.

ARCHITYPE (Gr. *ἀρχι-*, primordial, chief; *τύπος*, type), an original form from which others may be derived.

ARTHROPODS (Gr. *ἄρθρον*, joint; *πούς*, foot or limb), animals with jointed limbs, belonging to the group Arthropoda, *e.g.*, lobsters and insects.

ARTIODACTYL (Gr. *ἄρτιος*, equal; *δάκτυλος*, finger), having an even number of fingers or toes.

ASEXUAL REPRODUCTION, reproduction without any sexual process.

ASTER (Gr. *ἀστήρ*, star), a star-like figure appearing in the cell during mitosis.

ATAVISM (Lat. *atavus*, ancestor), a sudden return on the part of an organism to an ancestral condition.

AUTOMATISM (Gr. *αὐτόματος*, acting of one's own will), spontaneous action, not in response to recognisable stimuli.

BINOMIAL (Lat. *binominis*, having two names), a term applied to the Linnean system of nomenclature, in which each species is known by a generic and a specific name.

BIOGENESIS (Gr. *βίος*, life; *γένεσις*, birth), the origin of living things from pre-existing living things.

BIOGENETIC LAW (Gr. *βίος*, life; *γένεσις*, origin), Haeckel's term for the recapitulation hypothesis.

BIOLOGY (Gr. *βίος*, life; *λόγος*, discourse), the science of living things.

BIOPHORS (Gr. *βίος*, life; *φορεύς*, carrier), the smallest living units of which protoplasm is composed (according to Weismann's theory).

BLASTOCŒL (Gr. *βλαστός*, embryo; *κοῖλον*, a hollow), the cavity of a blastula embryo.

BLASTODERM (Gr. *βλαστός*, embryo; *δέρμα*, skin), a layer of cells which in heavily yolked eggs spreads over the surface and gives rise to the embryo.

BLASTOGENIC (Gr. *βλαστός*, germ; *rt.* *γεν-*, origin), a term applied to characters which originate in the germ cells.

BLASTOMERES (Gr. *βλαστός*, embryo; *μέρος*, part), the undifferentiated cells into which a developing egg first divides.

BLASTOPORE (Gr. *βλαστός*, embryo; *πόρος*, passage), the mouth of a gastrula embryo.

BLASTOSPHERE (Gr. *βλαστός*, embryo; *σφαῖρα*, sphere), a hollow, spherical embryo composed of a single layer of cells.

BLASTOSTYLES (Gr. *βλαστός*, embryo; *στῦλος*, pillar), the rod-shaped individuals which in certain hydroid colonies (*e.g.*, Obelia) bear the developing medusæ.

BLASTULA, another name for blastosphere (*q.v.*).

BRACHIOPODS (Gr. *βραχίων*, arm; *πούς*, foot), invertebrate animals which bear a superficial resemblance to bivalve Mollusca, but belong to a totally different group, known as Brachiopoda; sometimes called lamp shells.

CÆNOGENETIC (Gr. *καινός*, recent; *γένεσις*, origin), a term applied to characters of comparatively recent origin.

CAINOZOIC (Gr. *καινός*, recent; *ζωή*, life), a term applied to the most recent of the main divisions of the earth's history,

during which the more modern forms of living things appeared.

CALYX (Gr. *κάλυξ*, calyx), the outermost of the whorls of modified leaves of which a typical flower is composed.

CAMBIUM (late Lat., exchange), a layer of cells which lies between the wood and the bast and which, by cell division, causes increase in the thickness of both.

CAMBRIAN, the first epoch of the palæozoic era, the characteristic rocks of which are largely developed in North Wales (Cambria).

CARBOHYDRATES, a group of chemical compounds which contain the elements carbon, hydrogen and oxygen, the two latter in the proportion H_2O; *e.g.*, starch, sugar.

CARBON DIOXIDE (= carbonic acid gas), a gaseous compound of carbon and oxygen, having the formula CO_2.

CARBONIFEROUS (Lat. *carbo*, coal; *ferre*, to bear), one of the palæozoic epochs, during which coal was deposited.

CARPALS (Gr. *καρπός*, wrist), the bones of the wrist.

CARPELS (Gr. *καρπός*, fruit), the modified leaves which form the so-called ovary of a flower, from which the fruit arises.

CASEIN (Lat. *caseus*, cheese), a proteid substance found in cheese.

CASTRATION (Lat. *castrare*, to castrate), the removal of the male gonads or testes.

CELL (Lat. *cella*, apartment, cell), a nucleated protoplasmic unit (see p. 36 *et seq.* for origin of the term).

CELLULOSE, the substance of which vegetable cell walls are usually composed; a carbohydrate.

CENTROSOME (Gr. *κέντρον*, centre; *σῶμα*, body), a minute protoplasmic body concerned in the mechanism of nuclear division.

CENTROSPHERE (Gr. *κέντρον*, centre; *σφαῖρα*, sphere), a minute differentiated mass of protoplasm immediately surrounding the centrosome (*q.v.*).

CERCARIA (Gr. *κέρκος*, tail), the tailed larva of a parasitic fluke.

CHELA (Gr. *χηλή*, claw), a claw-shaped siliceous spicule found in certain sponges.

CHEMOTAXIS (Gr. *τάξις*, arrangement), a movement or arrangement in response to a chemical stimulus.

CHLOROPHYLL (Gr. *χλωρός*, green; *φύλλον*, leaf), the characteristic green colouring matter of plants.

CHLOROPLASTIDS (Gr. χλωρός, green; πλάστης, modeller). proteid bodies (contained within cells) in which chlorophyll is deposited.

CHORDATE (Gr. χορδή, cord), provided with a notochord (*q.v.*).

CHROMATIN (Gr. χρῶμα, colour), a constituent of the nucleus which becomes stained by certain dyes and which is believed to be the bearer of inheritable tendencies.

CHROMATOPHORES (Gr. χρῶμα, colour; φορεύς, carrier), proteid bodies (contained within cells) in which colouring matter is deposited.

CHROMOMERES (Gr. χρῶμα, colour; μέρος, part), the constituent parts of chromosomes (*q.v.*); termed by Weismann "ids."

CHROMOSOMES (Gr. χρῶμα, colour; σῶμα, body), definite aggregations of chromatin which appear during mitotic nuclear division; termed by Weismann "idants."

CILIA (Lat. *cilium*, eyelash), hair-like protoplasmic projections from the surface of a cell, which have the power of rapid, co-ordinated vibration.

CLAVICLE (Lat. *clavicula*, small key), one of the bones of the shoulder girdle, the collar-bone in man.

CLEAVAGE, the division of the developing egg into undifferentiated cells or blastomeres.

COCCYX (Gr. κόκκυξ, cuckoo), the lower end of the vertebral column in man.

CŒLENTERATE (Gr. κοῖλον, cavity; ἔντερον, gut), the term applied to those animals (Cœlenterata) in which there is only one cavity in the body, the enteron or digestive cavity.

CŒLOM (Gr. κοῖλον, cavity), the body cavity, which lies between the gut and the body wall in cœlomate animals.

CŒLOMATE, possessing a body cavity or cœlom (*q.v.*).

COLLOIDS (Gr. κόλλα, glue), gummy substances which will not diffuse through organic membranes.

CONGENITAL (Lat. *congenitalis*, present at birth), a term applied to characters present at birth (but not necessarily blastogenic).

CONJUGANT (Lat. *conjugare*, to join together), one of two "conjugating" individuals (in Paramœcium, &c.).

CONJUGATION (Lat. *conjugare*, to join together), the union of two sexual cells or gametes to form a zygote, which is capable of developing into a new individual (the term is sometimes limited to cases of isogamy, but is used in this work in a more general sense).

CONVERGENCE, the acquisition, by different organisms, of similar form or structure as the result of a similar mode of life, and not as the result of inheritance from common ancestors.

CORACOID (Gr. κόραξ, raven ; εἶδος, form ; anything hooked like a raven's beak), one of the bones of the typical shoulder girdle.

COROLLA (Lat., little wreath), one of the whorls of modified leaves of which a flower is composed, usually formed of gaily coloured petals.

CORPORA LUTEA (Lat., yellow bodies), glandular structures which make their appearance on the surface of the ovary (in mammals) at the spots whence ova have been discharged.

CORPUSCLE (Lat. *corpusculum*, little body), a term applied to certain cells, such as blood corpuscles.

CORRELATION, the dependence of one character upon another.

CORTICAL (Lat. *cortex*, bark, rind), belonging to a protective outer layer.

COSMOPOLITAN (Gr. κόσμος, world ; πολίτης, citizen), of world-wide distribution.

COSMOZOA (Gr. κόσμος, universe ; ζῷον, living thing), minute germs which are supposed to float about in space between the planets (purely imaginary).

COTYLEDONS (Gr. κοτυληδόνες, suckers), the seed-leaves of flowering plants.

CRETACEOUS (Lat. *creta*, chalk), a term applied to the geological period in which the chalk rocks were deposited.

CRYPTIC (Gr. κρυπτός, hidden), a term applied to colouration when adapted for concealment.

CRYSTALLOIDS (Gr. κρύσταλλος, crystal ; εἶδος, form), a group of chemical substances which usually form crystals, and which are capable of diffusing through organic membranes.

CYCLOPEAN (Gr. κύκλωψ, cyclops), having a single eye in the middle of the head.

CYCLOSTOME (Gr. κύκλος, circle ; στόμα, mouth), a term applied to the lampreys on account of their suctorial circular mouths.

CYST (Gr. κύστη, bladder, bag), a protective envelope formed around an organism during a period of rest.

CYTOLOGY (Gr. κύτος, a hollow vessel [cell] ; λόγος, discourse), the special study of cells.

Cytolysis (Gr. *κύτος*, cell; *λύσις*, breaking up), the disintegration of cells.

Cytoplasm (Gr. *κύτος*, cell; *πλάσμα*, *lit.* that which is moulded, used in the sense of the formative material), the protoplasm of the cell body, outside the nucleus.

Cytostome (Gr. *κύτος*, cell; *στόμα*, mouth), the mouth of a unicellular organism.

Cytotaxis (Gr. *κύτος*, cell; *τάξις*, arrangement), a movement or arrangement of cells in response to stimulation by other cells.

Cytotropism (Gr. *κύτος*, cell; *τροπή*, turning), *see* cytotaxis.

Degeneration, simplification of structure by reduction of parts.

Dendron (Gr. *δένδρον*, tree), a branching outgrowth of a nerve cell.

Dentition (Lat. *dens*, tooth), tooth arrangement.

Denudation (Lat. *denudare*, to lay bare), the wearing away of rocks by atmospheric and other agencies.

Dermatogen (Gr. *δέρμα*, skin; *rt.* *γεν-*, origin), the embryonic layer which, in higher plants, gives rise to the epidermis.

Determinants, hypothetical bodies of ultramicroscopical size, which are supposed to exist in the chromatin substance of the nucleus and to be responsible for the transmission of inheritable characters.

Deutoplasm (Gr. *δεύτερος*, secondary; *πλάσμα*, formative material), the food material or yolk stored in an egg.

Devonian, the name given to the geological period in which the old red sandstone was deposited.

Diatoms (Gr. *δίς*, double; *ἄτομος*, *lit.* indivisible, used in the sense of "atom"), a group of unicellular plants provided with double siliceous envelopes.

Dichogamy (Gr. *δίχα*, in two; *γάμος*, marriage), maturation of the stamens and pistil of a flower at different times, preventing self-fertilisation.

Dihybridism (Lat. *duo*, two; *hybrida*, hybrid), a Mendelian term for a cross between organisms which differ as regards two pairs of alternative characters.

Dimorphic (Gr. *δίς*, double; *μορφή*, form), having two forms.

Diœcious (Gr. *δίς*, double; *οἶκος*, dwelling place), having the male and female organs in separate individuals.

Diploid (Gr. *διπλόος*, two-fold), having a double set of chromosomes.

ECHINOIDS (Gr. *ἐχῖνος*, hedgehog; *εἶδος*, form), sea-urchins.

ECTODERM (Gr. *ἐκτός*, outside; *δέρμα*, skin), the outer layer of cells in a multicellular animal.

ECTOPLASM (Gr. *ἐκτός*, outside; *πλάσμα*, formative material), the outer part of the protoplasm in cells.

EDENTATES (Lat. *edentare*, to knock out the teeth), a group of mammals without teeth in the front part of the jaw.

EMBRYO (Gr. *ἔμβρυον*), a young organism in an early stage of its development.

EMBRYOLOGY (Gr. *ἔμβρυον*, embryo; *λόγος*, discourse), the study of the development of organisms.

EMBRYO-SAC, a chamber in the ovule or immature seed, in which the embryo plant begins its development.

ENDODERM (Gr. *ἔνδον*, within; *δέρμα*, skin), the inner layer of cells in a multicellular animal.

ENDOPLASM (Gr. *ἔνδον*, within; *πλάσμα*, formative material), the inner part of the protoplasm in cells.

ENDOSARC (Gr. *ἔνδον*, within; *σάρξ*, flesh), the inner part of the protoplasm in Amœba, &c.

ENDOSPERM (Gr. *ἔνδον*, within; *σπέρμα*, seed), nutrient substance stored within a seed, around the embryo.

ENGRAM (Gr. *ἐν*, in, upon; *γράμμα*, something written or drawn), a term used in the mnemic theory of heredity for an impression made upon a germ cell and capable of giving rise to a corresponding character in the developing organism.

ENTELECHY (Gr. *ἐντελέχεια*, perfection or total reaction), a kind of guiding principle, by which it is attempted to explain life.

ENTERON (Gr. *ἔντερον*, intestines), the digestive cavity in embryos and simple animals.

ENTOMOPHILOUS (Gr. *ἔντομος*, cut up, = insect; *φίλος*, beloved), a term applied to flowers which are pollinated by insects.

ENUCLEATE, deprived of nucleus.

ENZYME (Gr. *ἐν*, in; *ζύμη*, leaven, ferment), a substance that influences some chemical action in the body.

EOCENE (Gr. *ἠώς*, dawn; *καινός*, recent), the first subdivision of the cainozoic period in the earth's history.

EPIBLAST (Gr. *ἐπί*, upon; *βλαστός*, germ), the outer layer of cells in the animal embryo.

EPICORACOID (Gr. *ἐπί*, upon; *κόραξ* [coracoid]), one of the bones of the shoulder girdle in reptiles, &c.

EPIDERMIS (Gr. ἐπιδερμίς: ἐπί, upon; δέρμα, skin), the outer layer of the skin.

EPIGAMIC (Gr. ἐπί, upon; γάμος, marriage), a term applied to ornamentation which serves as a sexual attraction.

EPIGENESIS (Gr. ἐπί, upon; γένεσις, origin), the theory of development by the differentiation of previously undifferentiated protoplasm; opposed to "preformation."

EPISEMATIC (Gr. ἐπί, upon; σῆμα, signal), a term applied to colouration which aids in recognition.

EPITHELIUM (Gr. ἐπί, upon; θήλη, teat), a layer of cells covering a surface.

EUCALYPTS (Gr. εὖ, well; καλυπτός, covered; so-called from the flower bud, covered by the calyx), trees of the genus Eucalyptus, found in Australia.

EXCRETION (Lat. *excretus*, separated out), the function by which waste products are got rid of.

FEMUR (Lat., thigh), the thigh bone.

FIBULA (Lat., pin), one of the bones of the leg.

FISSION (Lat. *fissio*, a cleaving), the division of a cell into (usually) two daughter cells.

FLAGELLUM (Lat., whip), a whip-like protoplasmic projection from the body of a cell, capable of active movement.

FLUKES, a group of parasitic worms (Trematoda).

FŒTAL MEMBRANES, sac-like membranes which serve for the protection, respiration, &c., of the embryo in reptiles, birds and mammals.

FŒTUS (Lat., young animal), a term usually applied to the partially developed young of mammals, while still within the womb.

FUNICULUS (Lat., little cord), the stalk by which the ovule or seed is attached to the wall of the so-called ovary in flowering plants.

GAMETES (Gr. γαμέτης, spouse), sexual cells (germ cells) which unite in pairs to form zygotes, which develop into new organisms.

GAMETOGENESIS (Gr. γαμέτης, spouse; γένεσις, origin), the process by which gametes originate in the parent organism.

GAMETOPHYTE (Gr. γαμέτης, spouse; φυτόν, plant), the sexual or gamete-producing generation, which alternates with the asexual sporophyte in many plants.

GAMOBIUM (Gr. *γάμος*, marriage; *βίος*, life), the sexual generation, which alternates with an asexual generation (agamobium) in many organisms.

GANGLION (Gr. *γάγγλιον*, swelling), an aggregation of nerve cells.

GANOIDS (Gr. *γάνος*, sheen; *εἶδος*, form), an ancient group of fishes, usually with polished scales.

GASTRÆA (Gr. *γαστήρ*, paunch, belly), a hypothetical ancestral animal resembling the gastrula embryo.

GASTRAL CAVITY (Gr. *γαστήρ*, belly), digestive cavity.

GASTRULA (Gr. *γαστήρ*, belly), a stage in the development of multicellular animals in which the embryo consists of a two-layered sac, with a digestive cavity and a single opening.

GASTRULATION (Gr. *γαστήρ*, belly), the process by which the gastrula is formed.

GENE (Gr. *γένεσις*, origin), a name sometimes given to the factors in the germ cells that are responsible for the appearance of special characters in the offspring.

GENUS (Gr. *γένος*, race), a group of closely related species.

GERM CELLS, single cells which are capable of developing into new individuals (usually after conjugating in pairs).

GERMINAL DISK, a speck of active protoplasm in a heavily-yolked egg, from which the embryo develops.

GERM LAYER, one of the fundamental layers of cells which appear at an early stage of development in multicellular animals.

GERM PLASM, that part of the protoplasm of the germ cell (probably the chromatin substance of the nucleus), which is supposed to be the bearer of inheritable tendencies.

GLAND (Lat. *glans*, nut), an organ which secretes or excretes some special substance.

GLIADIN (Gr. *γλοιά*, glue), a proteid substance occurring in flour.

GLUCOSE (Gr. *γλυκύς*, sweet), a carbohydrate, also known as grape sugar.

GLUTININ (Lat. *gluten*, glue), a proteid substance occurring in flour.

GONAD (Gr. *γόνος*, reproduction), the organ (ovary or testis) in which the germ cells appear.

GONODUCT (Gr. *γόνος*, reproduction; Lat. *ductus*, conduit), a duct or tube through which germ cells pass to the exterior of the body.

GONOPHORE (Gr. *γόνος*, reproduction; *φορεύς*, bearer), an individual which bears gonads or reproductive organs (in Hydroids).

GONOTHECA (Gr. *γόνος*, reproduction; *θήκη*, box), a hollow skeletal structure containing gonophores (in Hydroids).

GRAAFIAN FOLLICLE, a capsule imbedded in the mammalian ovary and containing an unfertilized ovum.

GYNŒCIUM (Gr. *γυνή*, woman; *οἰκίον*, dwelling place), the "female" organs of a flower, consisting of ovary, style and stigma, formed from modified leaves known as carpels.

HÆMATID (Gr. *αἷμα*, blood), a red blood corpuscle.

HÆMATOCHROME (Gr. *αἷμα*, blood; *χρῶμα*, colour), a red modification of chlorophyll, found in Hæmatococcus.

HÆMOGLOBIN (Gr. *αἷμα*, blood, *globulin*, a proteid), the red colouring matter of blood.

HAPLOID (Gr. *ἁπλόος*, one-fold), having a single set of chromosomes.

HERMAPHRODITE (Gr. *Ἑρμῆς*, *Ἀφροδίτη*, a god and goddess), bearing both male and female reproductive organs.

HETEROGENY (Gr. *ἕτερος*, different; *rt. γεν-*, birth), an alternation of normal sexual with parthenogenetic individuals in the life cycle.

HETEROSPOROUS (Gr. *ἕτερος*, different; *σπόρος*, seed), producing two kinds of spores.

HETEROSTYLED (Gr. *ἕτερος*, different; *στῦλος*, pillar), a term applied to certain plants (Primula) which produce two kinds of flowers, differing in the length of the style.

HETEROZYGOTE (Gr. *ἕτερος*, different; *ζυγωτός*, joined together), a Mendelian term applied to an organism produced by the union of two gametes which differ as regards some particular alternative factor.

HEXADACTYLISM (Gr. *ἕξ*, six; *δάκτυλος*, finger), a condition in which six fingers or toes are present instead of the normal five.

HISTOLOGY (Gr. *ἱστός*, web; *λόγος*, discourse), the science which deals with animal and vegetable tissues or cell-aggregates.

HOLOPHYTIC (Gr. *ὅλον*, altogether; *φυτόν*, plant), a term applied to the typical vegetable method of nutrition, by aid of chlorophyll.

HOLOZOIC (Gr. *ὅλον*, altogether; *ζῷον*, animal), a term applied to the typical animal method of nutrition, by means of already elaborated, solid food material.

HOMOLOGY (Gr. *ὁμολογία*, agreement), essential structural identity due to community of descent.

HOMOPLASY (Gr. *ὅμος*, the same; *πλάσσω*, I mould), secondary resemblance due to similarity of habit.

HOMOSPOROUS (Gr. ὅμος, the same; σπόρος, seed), producing spores of one kind only.

HOMOZYGOTE (Gr. ὅμος, the same; ζυγωτός, yoked), a Mendelian term applied to an organism produced by the union of two gametes which resemble one another as regards some particular alternative factor.

HORMONE (Gr. ὅρμων, that which sets in motion), an internal secretion which circulates in the body and acts as a stimulus.

HUMERUS (Lat. *humerus*), the bone of the upper arm.

HYBRIDIZATION (Lat. *hybrida*, hybrid), the crossing of two distinct varieties or species by the union of the male gametes of the one with the female gametes of the other.

HYDRA (Gr. ὕδρα, a water serpent), the common fresh-water polype.

HYDRANTH (Gr. ὕδρα, water serpent; ἄνθος, flower), a flower-like nutritive individual of a hydroid colony.

HYDROCAULUS (Gr. ὕδρα, water serpent; καυλός, stalk), the stem of a hydroid colony.

HYDROID (Gr. ὕδρα, water serpent; εἶδος, form), Hydra-like.

HYDROTHECA (Gr. ὕδρα, water serpent; θήκη, box), a cup-like skeletal structure containing a hydranth.

HYDROZOON (Gr. ὕδρα, water serpent; ζῷον, animal), an aquatic animal of the group to which Hydra belongs.

HYPERPHALANGY (Gr. ὑπέρ, above; φάλαγξ, phalanx), a condition in which the number of phalanges in the digits is increased, as in some whales.

HYPERTONIC (Gr. ὑπέρ, above; τόνος, tone), a term applied to solutions in which the osmotic pressure has been raised by addition of salts, &c.

HYPOBLAST (Gr. ὑπό, below; βλαστός, germ), the innermost layer of cells in the embryo of a multicellular animal.

HYPOSTOME (Gr. ὑπό, below; στόμα, mouth), the part below the mouth in a hydroid animal.

ID (Gr. ἴδιος, personal, peculiar), a complete ancestral germ-plasm, a chromomere (Weismann).

IDANT (Gr. ἴδιος, personal, peculiar), an aggregation of ids, a chromosome (Weismann).

IDIOPLASM (Gr. ἴδιος, personal, peculiar; πλάσμα, formative material), the hereditary substance of any particular cell.

INFLORESCENCE (Lat. *florescere*, to begin to flower), the arrangement of flowers on the parent plant.

INTEGRATION (Lat. *integer*, entire), the process by which individuals of a lower order become united to form an individual of a higher order.

INTERCELLULAR (Lat. *inter*, between; *cellula*, a small chamber [cell]), lying between cells.

INTERCLAVICLE, one of the bones of the shoulder girdle in reptiles and monotremes.

INTERSTITIAL, occupying interstices or gaps.

INTUSSUSCEPTION (Lat. *intus*, within; *suscipere*, to take up), the addition of new particles throughout the entire mass (of protoplasm), resulting in growth.

INVAGINATION (Lat. *in*, in; *vagina*, sheath), the pushing of one part of a hollow body into the other, so that part of the original outer surface becomes internal.

INVERTEBRATE (Lat. *in-*, not; *vertebra*), without a backbone.

ISOGAMY (Gr. ἴσος, equal; γάμος, marriage), the conjugation of similar, mutually undifferentiated gametes.

JURASSIC, one of the subdivisions of the mesozoic era, the characteristic rocks of which are greatly developed in the Jura mountains.

KARYOGAMY (Gr. κάρυον, nut, used for nucleus; γάμος, marriage), the fusion of nuclei in conjugation.

KARYOKINESIS (Gr. κάρυον, nut, nucleus; κίνησις, movement), another term for mitosis (*q.v.*).

KARYOPLASM (Gr. κάρυον, nut, nucleus; πλάσμα, formative material), the protoplasm of the nucleus.

KARYOSOME (Gr. κάρυον, nut, nucleus; σῶμα, body), a special aggregation of chromatin in the resting nucleus.

KATABOLISM (Gr. καταβολή, a throwing down), a term applied to all the destructive chemical processes which go on in the living body, resulting in the formation of waste products.

LABYRINTHODONTS (Gr. λαβύρινθος, labyrinth; ὀδούς, tooth), a group of extinct amphibians, so-called from the pattern of the teeth.

LARVA (Lat. *larva*, ghost, mask), an immature but more or less active stage in the development of certain animals, differing widely in appearance from the adult.

LEGUMIN (Lat. *legumen*, pulse), a proteid substance found in peas and beans.

LEUCOCYTE (Gr. λευκός, white; κύτος, cell), a white blood corpuscle.

LININ (Gr. λίνον, thread), an achromatic substance which forms a network of threads in the nucleus.

LYSIN (Gr. λύσις, breaking up), a chemical substance which brings about the disintegration of cells.

MALIC ACID (Lat. *malum*, apple), an organic acid found in sour apples and other fruit.

MAMMAL (Lat. *mamma*, breast), a vertebrate animal which suckles its young.

MANUBRIUM (Lat., handle), the projection on which the mouth is placed in a jelly fish.

MEDUSÆ (Lat. *Medusa*, the Gorgon), jelly fish, the sexual individuals of certain hydroids.

MEGAGAMETES (Gr. μέγας, large; γαμέτης, spouse), the large (female) gametes, where the latter are differentiated into two sizes.

MEGALECITHAL (Gr. μέγας, large; λέκιθος, yolk, *lit.* porridge), a term applied to eggs which contain much yolk.

MEGANUCLEUS (Gr. μέγας, large; Lat. *nucleus*, kernel), the larger (somatic) nucleus in Paramœcium, &c.

MEGASPORANGIUM (Gr. μέγας, large; σπόρος, seed; ἀγγεῖον, vessel), a large sporangium, in cases where the latter are differentiated into two sizes.

MEGASPORE (Gr. μέγας, large; σπόρος, seed), a large spore, in cases where large and small are produced.

MEIOSIS (Gr. μείωσις, reduction), the reduction of the chromosomes which takes place in the maturation of germ cells.

MERISTEM (Gr. μεριστής, a divider), an undifferentiated tissue in which cell-division is going on actively (in plants).

MERISTIC (Gr. μεριστής, a divider), numerical (variation).

MEROGONY (Gr. μέρος, part; γόνος, reproduction), the development of enucleated eggs, after fertilization.

MESENTERY (Gr. μέσος, middle; ἔντερον, intestines), the membrane which supports the intestines in the body cavity.

MESOBLAST (Gr. μέσος, middle; βλαστός, germ), the middle one of the three layers of cells of which the body of a cœlomate embryo is made up.

MESODERM (Gr. μέσος, middle; δέρμα, skin), that part of the body which is derived from the embryonic mesoblast.

MESOGLŒA (Gr. μέσος, middle; γλοιά, glue), the gelatinous supporting layer between ectoderm and endoderm in cœlenterates.

MESOPHYLL (Gr. μέσος, middle; φύλλον, leaf), the middle layer of a leaf.

MESOZOIC (Gr. μέσος, middle; ζωή, life), one of the primary divisions of the earth's history.

METABOLISM (Gr. *μεταβολή*, change), the sum total of the chemical processes which go on in the living body.

METACARPALS (Gr. *μετά*, next after; *καρπός*, wrist), the bones in the palm of the hand.

METAGENESIS (Gr. *μετα-*, expressing change; *γένεσις*, birth), the alternation of sexual and asexual generations.

METAMERIC (Gr. *μετά*, next after; *μέρος*, portion), a term applied to a type of segmentation in which the similar parts (metameres) of which the body is composed follow after one another in longitudinal series.

METAMORPHIC (Gr. *μετα-*, expressing change; *μορφή*, form), a term applied to rocks which have undergone extensive changes since they were laid down.

METAMORPHOSIS (Gr. *μεταμόρφωσις*, transformation), a more or less abrupt change from one stage of development to another

METAPODIALS (Gr. *μετά*, next after; *πούς*, foot), a collective term for metacarpals and metatarsals.

METATARSALS (Gr. *μετά*, next after; *ταρσός*, foot [ankle]), the bones of the instep.

MICROGAMETES (Gr. *μικρός*, small; *γαμέτης*, spouse), the small (male) gametes, where the latter are differentiated into two sizes.

MICROLECITHAL (Gr. *μικρός*, small; *λέκιθος*, yolk), a term applied to eggs with little yolk.

MICRONUCLEUS (Gr. *μικρός*, small; Lat. *nucleus*, kernel), the smaller (germ) nucleus in Paramœcium, &c.

MICROPYLE (Gr. *μικρός*, small; *πύλη*, gate), a small opening in the integuments of an ovule, through which the pollen tube usually enters.

MICROSPORANGIUM (Gr. *μικρός*, small; *sporangium*), a small sporangium, in cases where the latter are differentiated into two sizes.

MICROSPORE (Gr. *μικρός*, small; *σπόρος*, seed), a small spore, in cases where large and small are produced.

MICROZOOID (Gr. *μικρός*, small; *ζῷον*, a living thing; *εἶδος*, form), a small individual, in unicellular organisms in which two sizes occur.

MIOCENE (Gr. *μείων*, less; *καινός*, recent), one of the subdivisions of the cainozoic era of the earth's history.

MITOSIS (Gr. *μίτος*, thread), the changes undergone by the nucleus in typical cases of nuclear division, in which various thread-like structures appear.

MNEMIC (Gr. *μνήμη*, memory), a term applied to a theory which attributes the phenomena of heredity to a kind of memory.

MONADS (Gr. *μονάς*, unit), minute unicellular organisms of the group Flagellata.

MONŒCIOUS (Gr. *μόνος*, single; *οἰκίον*, dwelling place), having the male and female sexual organs in one and the same individual; hermaphrodite.

MONOHYBRIDISM (Gr. *μόνος*, single; Lat. *hybrida*, hybrid), a Mendelian term for a cross between organisms which differ as regards one pair of alternative characters.

MONOPODIAL (Gr. *μόνος*, single; *πούς*, foot), a type of branching in which the main axis is continued after each branch is given off.

MONOSOME (Gr. *μόνος*, single; *σῶμα*, body), the unpaired chromosome which appears in the nuclei of certain cells.

MONOTREME (Gr. *μόνος*, single; *τρῆμα*, aperture), a member of the primitive mammalian group Monotremata.

MORPHOGENESIS (Gr. *μορφή*, form; *γένεσις*, origin), the development of form and structure.

MORPHOLOGY (Gr. *μορφή*, form; *λόγος*, discourse), the study of form and structure.

MULTICELLULAR (Lat. *multi*, many; *cellula*, cell), composed of many cells.

MUTATION (Lat. *mutatio*, change), a suddenly appearing sport or variety, which breeds true.

NECTARY (Gr. *νέκταρ*, the drink of the gods), an organ in which honey is produced in a flower.

NEURON (Gr. *νεῦρον*, string, nerve), a nerve cell with its attached fibre, a unit of the nervous system.

NOTOCHORD (Gr. *νῶτον*, back; *χορδή*, string), a cord of cells around which the backbone is formed in vertebrate animals.

NUCELLUS (Lat., *nucleus*, kernel), an inner part of the ovule or immature seed, really a megasporangium.

NUCLEAR MEMBRANE, the membrane which encloses the nucleus.

NUCLEINIC ACID, one of the chemical constituents of the nucleus.

NUCLEOLUS (Lat. dim. of *nucleus*, kernel), a special aggregation of chromatin or other substance in the resting nucleus.

NUCLEOPLASM (Lat. *nucleus*, kernel; Gr. *πλάσμα*, formative material), the protoplasm of the nucleus.

NUCLEUS (Lat., kernel), a specialised protoplasmic body found in the interior of every typical cell.

ONTOGENY (Gr. ὄν, ὄντος, a being; *rt.* γεν-, birth), the life-history (development) of an individual organism.

OOCYTE (Gr. ᾠόν, egg; κύτος, cell), an immature ovum; a cell from which an ovum originates.

OOGENESIS (Gr. ᾠόν, egg; γένεσις, origin), the process by which ova are formed in the animal body.

OOGONIA (Gr. ᾠόν, egg, γόνος, fruit), the female organs, containing the oospheres, in Fucus, &c.

OOGONIA (Gr. ᾠόν, egg; γονεύς, ancestor), the cells from which the oocytes arise in oogenesis.

OOSPHERE (Gr. ᾠόν, egg; σφαῖρα, sphere), a name frequently applied to the plant ovum.

OPHIUROID (Gr. ὄφις, snake; οὐρά, tail), a brittle-star or sand-star.

OPPOSABLE (Lat. *opponere*, to place opposite), a term applied to the thumb or great toe when capable of being placed with its tip opposite to those of the other digits.

ORDOVICIAN, one of the palæozoic epochs of the earth's history.

ORGAN (Lat. *organum*, implement), a specialised part of a living body concerned in some particular function.

ORGANELLÆ (Lat. dim. *organum*, implement), a term sometimes applied to the organs of unicellular organisms.

ORGANISM (Lat. *organum*, implement), that which has organs, viz., a living body.

ORTHOGENESIS (Gr. ὀρθός, straight; γένεσις, descent), evolution along an apparently predetermined line.

OSMOSIS (Gr. ὠσμός, pressure), the diffusion of dissolved substances through semi-permeable membranes (upon which they exert a pressure).

OVARY (Lat. *ovum*, egg), in animals the female gonad, the organ in which eggs are produced; in higher plants the part of the flower in which the immature seeds (ovules) are produced.

OVIDUCT (Lat. *ovum*, egg; *ductus*, conduit), the tube or duct through which the eggs pass to the exterior of the body.

OVOTESTIS (Lat. *ovum*, egg; *testis*, testicle), a gonad which produces both male and female gametes.

OVULE (Lat. dim. *ovum*, egg), the immature seed of a flowering plant.

OVUM (Lat., egg), a female germ cell or gamete.

PÆDOGENESIS (Gr. παῖς, child; γένεσις, birth), the parthenogenetic production of offspring by immature females.

PALÆONTOLOGY (Gr. παλαιός, ancient; ὄν, ὄντος, being; λόγος, discourse), the science of fossil organisms.

PALÆOZOIC (Gr. παλαιός, ancient; ζωή, life), the name given to one of the principal periods of the earth's history, in which ancient forms of life existed.

PALINGENETIC (Gr. πάλιν, backwards [should be παλαιός, ancient]; γένεσις, origin), of ancient origin.

PANGENESIS (Gr. πᾶν, all, every; γένεσις, origin), the name given by Charles Darwin to his theory of heredity, in accordance with which every cell of the body contributes something towards the formation of the germ cells.

PARAPHYSES (Gr. παραφύσις, that which grows alongside), hair-like structures which grow amongst the reproductive organs (in Fucus, &c.).

PARASITE (Gr. πάρασιτος, one who lives at another's table), an organism which nourishes itself at the expense of another living organism without making any return.

PARENCHYMA (Gr. παρέγχυμα, filling material), a kind of ground tissue in which various organs are imbedded.

PARIETAL (Lat. *paries*, wall), one of the bones of the skull, hence a region of the head.

PARTHENOGENESIS (Gr. παρθένος, maiden; γένεσις, birth), the production of offspring from unfertilised eggs.

PELAGIC (Gr. πέλαγος, sea), living in the open sea.

PENTACRINOID (Gr. πέντε, five; κρίνον, lily; εἶδος, form), resembling a Pentacrinus (sea-lily), a term applied to the stalked larva of the feather-star.

PENTADACTYL (Gr. πέντε, five; δάκτυλος, finger), having five fingers or toes.

PERIBLEM (Gr. περί, around; βλῆμα, cover), one of the principal cell-layers in the embryos of higher plants, covering the plerome.

PERISARC (Gr. περί, around; σάρξ, flesh), a horny protective layer which surrounds the body in certain hydroids (*e.g.*, Obelia).

PERISSODACTYL (Gr. περισσός, odd; δάκτυλος, finger), having an odd number of fingers or toes.

PERISTALSIS (Gr. περιστέλλω, I constrict), the movement of the alimentary canal by means of which food is passed along.

PERITONEUM (Gr. περιτόναιος, stretched over), the thin membrane which lines the body cavity and covers the viscera.

PERMIAN, the latest of the palæozoic epochs, the characteristic rocks of which are extensively developed in the province of Perm, in Russia.

PETALS (Gr. πέταλον, leaf), the modified leaves which form the corolla of a flower.

PHAGOCYTES (Gr. φαγεῖν, to devour; κύτος, cell), amœboid cells which devour other cells (*e.g.*, bacteria) in the bodies of multicellular animals.

PHAGOCYTOSIS, the action of phagocytes.

PHALANGES (Gr. φάλαγξ, phalanx), the bones of the fingers and toes.

PHLOEM (Gr. φλοιός, bast), the outer part of the vascular bundles, forming the bast (in higher plants).

PHOTOSYNTHESIS (Gr. φῶς, light; σύνθεσις, composition), the process by which carbohydrates are built up from simpler constituents under the influence of sunlight, in green plants.

PHYLLODE (Gr. φύλλον, leaf; εἶδος, form), a leaf stalk modified so as to resemble a leaf.

PHYLUM (Gr. φύλον, troop, tribe), one of the principal divisions of the animal kingdom.

PHYLOGENY (Gr. φῦλον, tribe, race; γένεσις, origin), the ancestral history of a race.

PINEAL GLAND or BODY (Lat. *pinea*, fir-cone), a body attached to the upper surface of the human brain, representing an additional pair of eyes present in ancestral vertebrates.

PISTIL (Lat. *pistillum*, pestle), a collective term for the "female" organs of a flower, = gynœcium.

PITUITARY BODY (Lat. *pituita*, slime, mucus), a glandular body attached to the under surface of the brain.

PLACENTA (Lat., a flat cake), the organ by which, in mammals, the fœtus is attached to the womb and through which it is nourished.

PLANKTON (Gr. πλαγκτόν, wandering), the floating population of seas and lakes.

PLASMA (Gr. πλάσμα, formative material), the liquid portion of the blood.

PLASMODIA (Gr. πλάσμα, formative material), multinucleate masses of protoplasm, formed by the union of many amœboid cells (in Mycetozoa).

PLASMOGAMY (Gr. πλάσμα, formative material; γάμος, marriage), the fusion of the cytoplasm of two cells.

PLASTICITY (Gr. πλαστός, moulded), the power of responding to changes in the environment.

Plastids (Gr. *πλαστής*, modeller), proteid bodies which occur in the cytoplasm of certain cells and have the power of forming special substances.

Plastogamy, *see* Plasmogamy.

Pleistocene (Gr. *πλεῖστος*, most; *καινός*, recent), the latest of the cainozoic epochs.

Plerome (Gr. *πλήρωμα*, that which fills up), the central cylinder of undifferentiated cells in the embryo of the higher plants.

Pliocene (Gr. *πλείων*, more; *καινός*, recent), one of the subdivisions of the cainozoic era of the earth's history.

Pluteus (Lat., pent-house), the free-swimming larva of sea-urchins and brittle-stars.

Polar body, an imperfect cell separated from one pole of the ovum during maturation.

Pollen (Lat., flour, dust), a fine dust consisting of the microspores or pollen grains of flowering plants.

Pollination, the application of pollen to the stigma of a flower (often loosely spoken of as fertilisation).

Pollinia, solid aggregations of pollen grains found in the flowers of orchids.

Polydactylism (Gr. *πολυδάκτυλος*, many-toed), a condition in which more than the normal number of fingers or toes are present.

Polymorphic (Gr. *πολύμορφος*, multiform), occurring in many forms.

Polype (Gr. *πολύπους*, many footed), a name applied to Hydra and various other Cœlenterate animals in allusion to the numerous tentacles.

Postaxial (Lat. *post*, behind; *axis*), lying behind the axis of a limb.

Preaxial (Lat. *præ*, in front; *axis*), lying in front of the axis of a limb.

Precipitin (Lat. *præcipitare*, to throw down), a substance formed in the blood of one animal by addition of the serum of another, and causing the formation of a precipitate when the serum containing it is added to the serum of the second or of some closely related animal.

Pre-formation, an old theory in accordance with which every egg contains a complete miniature of the organism into which it will develop.

Prehension (Lat. *prehendere*, to seize), catching hold.

PRIMORDIA (Lat. *primordium*, origin), hypothetical particles of the germ plasm which are supposed to be responsible for the development of special inheritable characters.

PRIMORDIAL UTRICLE (Lat. *primordium*, origin; *utriculus*, little bag), the protoplasmic lining of a typical vegetable cell, next to the cell wall.

PROBOSCIS (Gr. *προβοσκίς*, trunk, snout), a term somewhat loosely applied to any prehensile, suctorial or other organ which projects from the neighbourhood of the mouth.

PROCRYPTIC (Gr. *πρό*, on behalf of; *κρυπτός*, hidden), a term applied to protective resemblance whereby concealment is effected.

PRONUCLEUS (Lat. *pro*, in place of; *nucleus*, kernel), the reduced nucleus of a mature gamete before it unites with its mate to form the zygote nucleus.

PROTANDROUS (Gr. *πρῶτον*, first; *ἀνήρ*, man, male), a term applied to hermaphrodite organisms in which the male organs mature before the female.

PROTEIDS, PROTEINS (Gr. *Πρωτεύς*, the changeable one), a group of complex chemical compounds which form the chief constituents of protoplasm.

PROTHALLUS (Lat. *pro*, in place of; *thallus*, a green stalk), the sexual individual (gametophyte) in ferns, &c.

PROTOGYNOUS (Gr. *πρῶτον*, first; *γυνή*, woman, female), a term applied to hermaphrodite organisms in which the female organs mature before the male.

PROTOPLASM (Gr. *πρῶτος*, first; *πλάσμα*, formative material), the essential constituent of all living bodies; "the physical basis of life."

PROTOZOON (Gr. *πρῶτος*, first; *ζῷον*, animal), a unicellular animal.

PSEUDOPODIUM (Gr. *ψευδής*, false; *πούς*, foot), a temporary, irregular protoplasmic projection from a naked cell, generally used as an organ of locomotion (*e.g.*, in Amœba).

PYRENOID (Gr. *πυρήν*, fruit stone; *εἶδος*, form), a starch-forming proteid body, found in certain cells.

RADIUS (Lat., spoke), one of the bones of the forearm.

RECAPITULATION HYPOTHESIS, the theory in accordance with which an individual organism repeats its ancestral history in its own development.

RECEPTOR (Lat., receiver), an organ which receives stimuli, a sense organ.

Regression, filial (Lat. *regressus*, a going back), a return on the part of the offspring of exceptional parents towards the average condition of the species.

Respiration (Lat. *respiratio*, breathing), essentially the interchange of the two gases, oxygen and carbon dioxide, the former being taken in by the organism (or tissue) and the latter given out.

Reversion (Lat. *reversio*, a turning back), the sudden reappearance of some long-lost ancestral character.

Rodents (Lat. *rodere*, to gnaw), animals of the order Rodentia (*e.g.*, rabbits, mice).

Rostellum (Lat. dim. *rostrum*, beak, snout), one of the three stigmas of an orchid modified to form a kind of cement gland.

Rotifers (Lat. *rota*, wheel; *ferre*, to carry), wheel animalcules, a group of minute aquatic worms with cilia arranged like wheels.

Saprophytic (Gr. σαπρός, putrid; φυτός, growing), living on dead organic matter.

Sarcode (Gr. σάρξ, flesh; εἶδος, form), an old term for protoplasm.

Scapula (Lat., shoulder blade), the shoulder blade.

Secretion (Lat. *secretus*, separate), a useful substance separated or secreted by some special organ (gland); *or* the process involved therein.

Sedimentary (Lat. *sedere*, to settle down), a term applied to rocks deposited as sediment under water.

Segmentation (Lat. *segmentum*, a cutting), division into parts, as in a dividing ovum or in the segmented body of a worm.

Segregation (Lat. *segregare*, to set apart), separating out.

Sematic (Gr. σῆμα, signal), a term applied to colours used as signals.

Sepals (Lat. *sepes*, fence, enclosure), the modified leaves which form the outermost whorl (calyx) of a typical flower.

Serum (Lat., whey), the watery liquid that separates out from clotted blood.

Silurian (Lat. *Silures*, an ancient British tribe), one of the palæozoic epochs, the characteristic rocks of which are largely developed in Wales, &c. (Siluria).

Soma (Gr. σῶμα, body), the body of an organism, contrasted with the germ cells.

Somatic, pertaining to the soma or body.

Somatogenic (Gr. σῶμα, body; *rt.* γεν-, origin), originating in the soma or body.

SOMATOPLEURE (Gr. *σῶμα*, body; *πλευρά*, side), the body wall, enclosing the body cavity.

SOMITE (Gr. *σῶμα*, body), one of the divisions of which a metamerically segmented body is made up. = metamere.

SPECIES (Lat., sort, kind), a group of individuals which closely resemble one another owing to descent from common ancestors and at the same time differ from all other species (*see* p. 234).

SPECIFIC CHARACTERS, characters by which one species is distinguished from others.

SPERMARY (Gr. *σπέρμα*, seed, sperm), a general term for a gonad in which male gametes are produced (testis).

SPERMATID (Gr. *σπέρμα*, sperm), a cell which develops directly into a spermatozoon.

SPERMATIST (Gr. *σπέρμα*, sperm), an old term applied to one who believed that the animal embryo was produced entirely by the male.

SPERMATOCYTE (Gr. *σπέρμα*, sperm; *κύτος*, cell), a cell from which spermatids, and hence spermatozoa, originate.

SPERMATOGENESIS (Gr. *σπέρμα*, sperm; *γένεσις*, origin), the process by which male gametes (spermatozoa) originate.

SPERMATOGONIA (Gr. *σπέρμα*, sperm; *γονεύς*, ancestor), the cells from which the spermatocytes originate in spermatogenesis.

SPERMATOZOID, a term sometimes applied to a plant spermatozoon.

SPERMATOZOON (Gr. *σπέρμα*, sperm; *ζῷον*, a living being), the term applied to a male gamete or germ cell when differentiated as a free-swimming, active organism.

SPICULES (Lat. *spiculum*, a little sharp point), minute mineral bodies, usually of definite shape, secreted by special cells and forming the skeleton of many invertebrate animals (*e.g.*, certain sponges).

SPIREME (Gr. *σπείρημα*, coil), the coiled thread of chromatin substance which occurs at a certain stage in mitosis.

SPLANCHNOPLEURE (Gr. *σπλάγχνα*, viscera; *πλευρά*, side), the gut wall, as opposed to the body wall.

SPONTANEOUS GENERATION, the (supposed) origin of living things from not-living matter.

SPORANGIUM (Gr. *σπορά*, seed; *ἀγγεῖον*, vessel), a capsule in which spores are produced.

SPORE (Gr. *σπορά*, seed), a single cell which is capable of giving rise without any sexual process to a new individual (*e.g.*, in ferns); absolutely different from a true seed.

Sporophyll (Gr. *σπορά*, seed; *φύλλον*, leaf), a spore-bearing leaf.

Sporophyte (Gr. *σπορά*, seed; *φυτόν*, plant), the asexual, spore-producing generation in certain plants (*e.g.*, ferns and flowering plants).

Sport, a suddenly appearing variation; a mutation.

Stamens (Lat. *stamen*, thread), the modified leaves which form the "male" organs of a flower.

Staminodes (Lat. *stamen*, thread; Gr. *εἶδος*, form), imperfect stamens.

Statoblast (Gr. *στατός*, standing; *βλαστός*, bud), a dormant bud, protected by a special envelope; found in certain fresh-water invertebrates.

Stigma (Gr. *στίγμα*, spot), the moist spot on the end of the style of a flower, on which pollen is deposited.

Stoma (Gr. *στόμα*, mouth), a minute opening in the epidermis of a leaf, leading into air spaces in the mesophyll.

Stratified (Lat. *stratum*, pavement), arranged in layers.

Style (Gr. *στῦλος*, pillar), part of the "female" organs of a flower, bearing the stigma.

Suprascapula (Lat. *supra*, above; *scapula*, shoulder blade), a bone or cartilage which lies above the scapula in the shoulder girdle.

Suspensor (Lat. *suspendere*, to hang up), a row of cells by which the embryo is attached to the embryo sac in flowering plants.

Synaposematic (Gr. *σύν*, together; *ἀπό*, away from; *σῆμα*, signal), sharing a common warning colour.

Synapsis (Gr. *σύναψις*, conjunction), the pairing of chromosomes prior to nuclear reduction.

Syncytium (Gr. *σύν*, together: *κύτος*, cell), a layer of protoplasm not divided into separate cells but with many nuclei.

Syndesis (Gr. *συνδησαί*, to bind together), another term for synapsis (*q.v.*).

Syngamy (Gr. *σύν*, together; *γάμος*, marriage), the sexual union of gametes (conjugation).

Tarsals (Gr. *ταρσός*, foot [ankle]), the bones of the ankle.

Taxonomy (Gr. *τάξις*, arrangement; *νόμος*, law), the science of classification.

Testis (Lat., testicle), an organ in which male gametes are produced; a male gonad.

Thylacine (Gr. *θύλακος*, pouch; *κύων*, dog), a carnivorous marsupial (pouched mammal) found in Tasmania.

THYMUS, a glandular body derived from the epithelium of certain of the gill slits.

THYROID (Gr. *θυρέος*, shield), a glandular body derived from the floor of the pharynx.

TIBIA (Lat., shin-bone), one of the bones of the leg.

TORPEDO (Lat., numbness, electric ray), a kind of ray, with powerful electric organs.

TRIASSIC (Gr. *τριάς*, three), the earliest epoch of the mesozoic era, so-called from the three-fold subdivision seen in Germany.

TRICHOCYSTS (Gr. *θρίξ*, hair; *κύστις*, pouch), minute sacs containing hair-like processes (in Paramœcium, &c.).

TRILOBITE (Gr. *τρεις*, three; *λοβός*, lobe), an extinct crustacean of the palæozoic era.

TURBELLARIAN (Lat. *turbellæ*, stir), a kind of flat worm whose ciliated surface stirs up the water.

ULNA (Lat., arm), one of the bones of the forearm.

UNGULATE (Lat. *ungula*, hoof), a hoof-bearing animal of the order Ungulata.

UNGULIGRADE (Lat. *ungula*, hoof; *gradus*, step), walking on the hoof.

UNICELLULAR (Lat. *unus*, one; *cellula*, cell), consisting of a single cell.

UNISEXUAL (Lat. *unus*, one; *sexus*, sex), either male or female, not hermaphrodite.

UREA (Gr. *οὖρον*, urine), a nitrogenous compound formed as a waste product in animal bodies.

UTERUS (Lat., womb), an enlarged portion of the oviduct, in which an embryo or fœtus undergoes development; the womb in mammals.

VACUOLE (Lat. *vacuus*, empty), a space in the protoplasm of a cell, filled with gas or liquid.

VAS DEFERENS (Lat., a vessel which carries down), a duct through which spermatozoa pass to the outside of the body.

VASCULAR BUNDLE (Lat. *vasculum*, a small vessel), a bundle of vessels, &c., through which sap is distributed in higher plants.

VERTEBRA (Lat., joint, vertebra), one of the segments of the backbone.

VERTEBRATE, having a backbone.

VESTIGIAL (Lat. *vestigium*, trace, vestige), reduced almost to the point of disappearance.

VITALISM (Lat. *vita*, life), the doctrine which attributes the phenomena of life to a special vital force.

VITELLINE MEMBRANE (Lat. *vitellus*, yolk), a delicate membrane which encloses an ovum.

XYLEM (Gr. *ξύλον*, wood), the woody part of a vascular bundle.

ZOŒA (Gr. *ζῷον*, animal), a larval stage of crabs and other Crustacea.

ZONA RADIATA (Lat., radiate zone), a membrane which encloses the ovum in mammals, probably the equivalent of the vitelline membrane in lower animals.

ZOOID (Gr. *ζῷον*, animal ; *εἶδος*, form), an individual member of a colony (*e.g.*, in Obelia).

ZOOPHYTE (Gr. *ζῷον*, animal ; *φυτόν*, plant), an old term applied to certain plant-like invertebrates (*e.g.*, Obelia).

ZOOSPORE (Gr. *ζωός*, alive ; *σπορά*, seed), an actively swimming spore.

ZYGOSIS (Gr. *ζύγωσις*, joining together), another term for conjugation or the sexual union of gametes.

ZYGOSPORE (Gr. *ζυγόω*, I join together ; *σπορά*, seed), a zygote formed by the conjugation of two similar gametes (*e.g.*, in Spirogyra).

ZYGOTE (Gr. *ζυγωτός*, joined together), a cell produced by the conjugation of two gametes and capable of developing into a new individual.

OUTLINES OF EVOLUTIONARY BIOLOGY

PART I.—THE STRUCTURE AND FUNCTIONS OF ORGANISMS—THE CELL THEORY

CHAPTER I

Introductory: The nature of life. The living organism viewed as a machine—The essential functions of the living body—The source of energy in living things.

THERE are many ways in which the extremely heterogeneous materials of which the earth is composed may be classified. Physicists often speak of them as solid, liquid or gaseous respectively, but we know that one and the same substance may exist in any of these conditions, changing from one to the other in accordance with changing conditions of temperature and pressure. Chemists, on the other hand, tell us that all substances are made up of certain definite chemical elements, occurring free or in a state of combination with one another, and that the almost infinite variety of gases, liquids and solids with which we are familiar has arisen mainly from this power of combination in very diverse but perfectly definite ways. The tendency of modern research, however, is to show that even the so-called chemical elements are not really so elementary in their nature as has been supposed, and it is quite conceivable that they may all have a common origin.

Our present purpose is to investigate a condition of matter which in some respects transcends the classifications of the chemist and the physicist, a condition in which it exhibits those peculiar phenomena which we regard as manifestations of Life, and the study of which constitutes the science of Biology. It is not

that living matter differs fundamentally from not-living matter in chemical or physical characters. On the contrary we recognize in it exactly the same chemical elements—or rather some of them—as we find in other constituents of the earth, and these elements appear to obey precisely the same chemical and physical "laws" in both cases, but in the living body they are associated and combined with one another in such a manner as to give rise to substances much more complex than any found outside the animal and vegetable kingdoms, and possessed of peculiar properties which raise them to an altogether higher plane of existence. The complex substances in question constitute protoplasm, which is the one essential constituent of every living thing, upon the peculiar properties of which the life of the organism depends.

We may begin our investigations into the nature of this life by examining the well-worn but none the less valuable analogy of the flame of a candle. Chemists and physicists have taught us that flame consists of incandescent matter, raised to a high temperature by the process of combustion, or chemical union with the oxygen of the atmosphere, and that the flame can exist only so long as the combustion goes on and a sufficiently high temperature is thereby maintained to render the burning matter luminous, or in other words to produce those vibrations of the invisible and intangible ether which we recognize as light. The flame, then, is the outward and visible sign of certain chemical and physical processes, of the action and reaction between the material which is being burnt and the atmosphere which surrounds it.

Similarly biologists have learnt to recognize life as the expression of the constant interaction which goes on between the living organism and its environment, or, in the words of Herbert Spencer, "the continuous adjustment of internal relations to external relations." So far as we have yet been able to analyze it, this interaction also consists of chemical and physical processes, amongst which combustion plays a large part; but the whole business is vastly more complex than the processes involved in the production of a flame, and so far many of its details have defied analysis.

We may vary our analogy by looking upon the body of a living organism, whether plant or animal, as an extremely elaborate engine or machine, whose existence depends upon a perfect

adaptation to its environment, and whose action consists in continual self-adjustment to changes in that environment. What we call the life of the organism consists of the sum total of all the activities which it thus exhibits. The question at once arises: How, then, does a living organism differ from a mere man-made machine? and this question is one which it is by no means easy to answer. An organism, however, is not merely a piece of apparatus which has the power of maintaining itself for a longer or shorter period in a state of equilibrium with its environment and thereby preserving itself from destruction, for it also has the power of reproducing its kind by a process of self-multiplication. In the case of an artificial machine, where there is little or no automatic adjustment, the forces of the environment very soon get the upper hand; the metal work becomes corroded by oxidation, or worn away by friction, and presently the whole affair comes to a standstill. Oxidation and friction, and innumerable other chemical and physical agencies also tend to destroy the machinery of the living body, but for a longer or shorter period they are held in check by automatic processes of repair and renewal, and when the inevitable end does come it is normally not until the organism has produced at least enough offspring to take its place in the struggle for existence.

Samuel Butler, the well-known author of "Erewhon," makes one of his characters discuss the somewhat fantastic suggestion that some day the construction of machines might be so perfected that they also would be able to reproduce their kind, and the little steam-engines would be seen playing about the door of the engine shed. It certainly does not seem possible that machines will ever multiply in this way, but could they do so, and should they at the same time be able to feed and grow, it is difficult to see why they should not be as much entitled to be called living organisms as any of the plants and animals which inhabit the earth to-day. They would, however, still be very different from plants and animals both in structure and composition.

One of the most remarkable and characteristic features of the living things which inhabit this earth is that they are all composed fundamentally of materials which are totally different in their nature from any which we should be likely to choose in the construction of a machine. In making an engine we select those substances which seem best calculated to resist the destructive

action of the environment; hard and rigid metals which will bear heavy strains, and as far as possible such as will be proof against the chemical action of the atmosphere; and we do our best by means of oil and paint to protect even these from injurious influences.

A living body may also have its hard protective structures, as the shell of the oyster and the scales of the fish, or its rigid levers, as the bones in our own limbs, but the really essential part of the organism is built up of just those materials which are most liable to destruction by chemical and physical agencies—of that almost liquid and extremely unstable substance which we have already referred to as protoplasm, and of its various derivatives. The experience of every day teaches us how rapidly the bodies of animals and plants decay when they are left exposed to the atmosphere after life has become extinct; and this decay is simply the destruction caused by the disintegrating forces of the environment. A disabled steamboat may lie rusting on the shore for many years without undergoing much change, but the dead body of a stranded jelly-fish thrown up beside it will become disorganized and disappear in the course of a few hours, and yet the jelly-fish when alive was undoubtedly the more complex and perfect piece of apparatus.

The body of an organism, moreover, undergoes destruction not only after death; it is always undergoing destruction, and its very life depends upon its destruction, just as the flame of a candle depends upon the destruction of the candle. But as it is destroyed it is constantly built up again; new protoplasm is formed and new tissues take the place of those which are worn out. The life of the organism is, in fact, the outcome of the constant struggle between destructive and constructive forces, and the keener the struggle the more vigorous will be the life—just as the flame will be brighter or hotter in proportion to the activity of the combustion to which it owes its existence.

Life, like the flame, is a manifestation of energy, and the living body is, like the steam-engine, a machine for transforming one kind of energy into another. Moreover, the ultimate source of the energy is the same in both cases. That of the steam-engine is derived from the combustion or oxidation of coal, which contains stores of energy derived millions of years ago from the light and heat of the sun by the green plants which flourished in the vast forests of the Carboniferous epoch. The green plants

of to-day still derive supplies of energy from the same source and lock up in their leaves and stems what they do not themselves expend, while the animals in turn derive their energy from the green plants upon which they directly or indirectly feed. Hence both plants and animals are ultimately dependent upon the sun for their existence.

Even the most superficial examination is sufficient to demonstrate the fact that the body of any of the more familiar animals or plants is, as we have already indicated, an extremely complicated thing. Whatever may be the degree of complexity, however, and however much one organism may differ from another in details of structure, whether it be a microscopic alga or an oak tree, an Amœba or a man, there are always certain things which have to be done, certain actions or functions which have to be performed, in order that its life may be maintained.

In the first place, the organism must safeguard itself as far as possible from the destructive influences of its environment. It must not only be able to protect itself from such physical agents as heat and cold, mechanical impact and friction, but it may have to select a situation where life is possible, or to escape from other organisms by which it is liable to be attacked. All this involves the expenditure of energy in some form or another; it may be in the manufacture or secretion of protective envelopes or shells, such as we find even in some of the simplest Protozoa, or it may be in actively moving away from the source of danger. Thus it appears that the very first thing necessary for the maintenance of life is the expenditure of energy. This energy, though ultimately derived from the sun, is, as we have already seen, derived immediately from the combustion of fuel, very much as in the case of a steam-engine, but with the important difference that in the living organism the fuel is, at any rate to a large extent, the actual substance of which the body is composed. In this respect the comparison with a candle is especially apt, for it is the combustion of the actual substance of which the candle is composed that liberates the energy manifested in the light and heat of the flame.

Now combustion is, of course, simply another name for what chemists term oxidation, or combination with the element oxygen, a process which is often accompanied by the liberation of a considerable amount of energy in the form of heat and light, though this is by no means always the case. In the

higher animals sufficient heat is evolved to maintain the temperature of the body at a level considerably above that of the surrounding atmosphere, and such animals are accordingly termed "warm-blooded"; in plants, on the other hand, and in the "cold-blooded" lower animals, the amount of heat evolved is not as a rule sufficient to raise the body temperature to any great extent, if at all. Heat, however, is only one form in which energy may be manifested, and in living organisms it may, as a matter of fact, be much more conspicuously manifested in the form of motion, especially in animals, while in not a few cases even a low temperature combustion may liberate energy in the form of light, as in the glow-worm and numerous other luminous animals and plants.

When a piece of charcoal is burnt in the air it enters into combination with the elementary oxygen gas of the atmosphere, and another invisible gas which we term carbon dioxide, or carbonic acid, is produced, in accordance with the equation—

$$\underset{\text{(Carbon)}}{C} + \underset{\text{(Oxygen)}}{O_2} = \underset{\text{(Carbon Dioxide).}}{CO_2}$$

In this process energy is set free in the form both of heat and light. We must now inquire a little more carefully whence this energy really comes, for although this is a question primarily for the chemist and physicist it is also clearly one which the biologist cannot afford to leave unanswered.

In accordance with the principles of the conservation of energy and the indestructibility of matter we believe that the quantities of energy and matter which exist in the universe are fixed and constant. Neither energy nor matter can be created and neither can be destroyed, though each may express itself in a great variety of ways and change more or less readily from one mode of expression to another. Thus, as we have already seen, the energy of the sun's rays may be utilized in building up the bodies of green plants, and locked up, as it were, in the substances of which these are composed.

We also know that different chemical elements have a very strong "affinity" for one another, their atoms tending to unite and form complex molecules when they are brought within the sphere of each other's attraction. Once united they can only be separated again by the expenditure of energy, and when they unite a corresponding amount of energy is

liberated. We may say, for example, that in the elements carbon and oxygen, so long as they remain separate, a certain amount of energy remains latent. We call this potential energy. When the carbon and oxygen atoms are allowed to come together and unite, this potential energy of chemical affinity is liberated as kinetic or active energy, and manifested in the form of light and heat.

It is from the potential energy of chemical affinity that the energy of a living organism is immediately derived. Protoplasm, the fundamental constituent of both plants and animals, contains chemical compounds of extremely complex structure, composed of many elements and containing a large amount of potential energy locked up in them. Chief amongst these are the proteids (proteins), which are extremely unstable bodies, readily breaking up on oxidation into simpler and more stable combinations and thus liberating energy. It is the presence of these unstable proteids which confers upon protoplasm its peculiar fitness to form what has been so aptly termed by Huxley "The physical basis of life." They play the part of the gunpowder in a cartridge, ready to produce a manifestation of energy as soon as the proper stimulus is applied.

It is, then, the breaking up of proteids, or of some other complex substances, usually by recombination of their constituents with oxygen, which furnishes the constant supply of energy which an organism requires. This process, however, can only go on so long as the supply of combustible matter on the one hand and of oxygen on the other is adequately maintained, and this brings us to the consideration of two of the most important functions which every living organism must perform, nutrition and respiration.

Under the head of nutrition we must include all those processes which are concerned in building up the body, in making good the waste of substance necessitated by the expenditure of energy and thus providing new stores of fuel for the use of the organism. The first step in nutrition is the taking into the body of suitable food material. In the case of the typical animal this material must contain in some form or other all the necessary supply of potential energy, locked up in more or less complex and unstable chemical compounds such as it can obtain only from the bodies of other organisms. The green plant, on the other hand, by virtue of the chlorophyll

which it contains, has the power of absorbing energy directly from the sun's rays and using this to build up complex substances from very simple constituents. The feeding of the organism, whether plant or animal, is comparable to the stoking of the engine, but with this difference, that the food material, unlike the fuel in the engine furnace, has usually to undergo complex chemical processes, which may actually result in the formation of new protoplasm, before it is available as a source of energy.

Supplies of energy are, of course, useless unless they can be liberated when required. The fuel must be burnt, and for this purpose, as we have already said, a supply of oxygen gas is necessary, and the function which is concerned in providing this supply we call respiration. The term respiration, however, is one in the employment of which we shall have to exercise a certain amount of care. It is naturally associated in our minds with the mechanical act of breathing which we ourselves perform. We can see a man breathing, but we cannot see an oak tree breathing; nevertheless the oak tree performs the function of respiration just as efficiently as the man. We have to learn to dissociate the essential part of this function, which is common to all living things, from the subsidiary complications which have been introduced in the case of the higher animals during the course of their evolution from lower forms.

Respiration, in the scientific acceptance of the term, is simply the exchange by the organism of the carbon dioxide gas which has been formed in the body in the process of combustion for the oxygen gas which is required for that combustion. It is therefore a double function—oxygen being taken in and carbon dioxide got rid of by one and the same process. This process is, in its essential features, an extremely simple one, depending upon the well-known physical principle of diffusion, in accordance with which two gases of different densities tend to change places, until equilibrium is established, whenever they are placed in the necessary relations with one another, as when they are separated only by some membrane through which both can pass.

Carbon dioxide, however, is not the only waste product resulting from the breaking up of the complex proteids, for these also contain hydrogen, nitrogen, sulphur and phosphorus, and other products of decomposition are accordingly formed

which contain amongst them all of these elements. These must also be eliminated from the body, and this process of elimination of waste products constitutes the function of excretion. This function may be performed in a variety of ways and by a variety of organs. In so far as the carbon dioxide is concerned it is, as we have already seen, an essential part of the function of respiration. Urea, on the other hand, a nitrogenous substance which is perhaps the most characteristic waste product in the higher animals, is eliminated by special excretory organs, such as the kidneys. In the case of the higher plants the waste products are for the most part stored up in the leaves and got rid of when these are shed.




FIG. 1.—Diagram of Metabolism.

We have thus seen that the energy exchanges of a living organism, and therefore also its life, depend upon a series of complex chemical processes which take place within the body. All these processes collectively are spoken of as metabolism, and we may distinguish between two sets of metabolic changes: those which are constructive and lead to the building up of new living protoplasm out of food material, and those which are destructive and lead to the decomposition of the body substance, the liberation of energy and the formation of waste products. The former are termed anabolic and the latter katabolic.

We may roughly illustrate these elementary conceptions of the chemical processes which take place in the living body by the accompanying diagram, in which a mass of living protoplasm is represented as balanced in a very unstable position on the apex of a triangle. It is constantly undergoing destruction,

accompanied by the liberation of energy and resulting in the formation of waste products, substances which, in falling down one side of the triangle to a lower level, to a greater or less extent lose their potential energy. On the other side of the triangle, however, complex food material, containing fresh supplies of potential energy, is supposed to be taken in, or, in the case of green plants, actually built up from simple constituents by the energy of the sun's rays, and used in repairing the waste of the protoplasmic body.

The chemical processes which constitute the metabolism of the living body are in reality far more complex and varied than might be supposed from the necessarily imperfect account given in the foregoing pages. All sorts of regulative actions and reactions of a chemical nature take place which have been more or less fully investigated by physiologists, but about which much still remains to be learnt. The chief agents in these processes are those remarkable substances known as enzymes or ferments, which probably play an important part in every living body, but the discussion of these is beyond the scope of the present work.

If the constructive processes proceed more vigorously and rapidly than the destructive, if the food supply is abundant and the expenditure of energy comparatively low, the body may grow, though, as we shall see presently, only within certain limits. If the reverse is the case and the expenditure exceeds the income, the body may dwindle away and finally die. If it is to remain in a condition of healthy equilibrium, a just balance must be maintained between the two sides of the account.

The growth of a living organism differs from that of an inanimate body in one very important respect. It takes place by the absorption of food material which is different from its own substance, but which it converts into its own substance, or assimilates, by chemical processes. The growth of an inanimate body is effected by mere addition of material which is not assimilated, though it may be, as in the case of a snowball or a crystal, already of the same nature.

Perhaps the most characteristic property of living things is, as we have already suggested, the power of reproduction. This is the last resort of the organism in the struggle for existence. The individual, which owes its very life to the perishable nature of its body, always succumbs to the destructive influences of the environment sooner or later, but before yielding to the inevitable

it will, under normal conditions, have produced offspring which will carry on the struggle for another generation.

The phenomenon of reproduction is intimately associated with that of growth, and may be traced back to the division of a simple ancestral mass of protoplasm into two parts whenever its volume increased to such an extent that the surface was no longer sufficient for the necessary intercourse between the organism and its environment. With this division of the protoplasmic body the proper proportion is restored, and hence reproduction by multiplication of protoplasmic units may be looked upon as primarily the direct consequence of superabundant nutrition.

We have now learnt to look upon an animal or a plant as a complex and extremely delicate piece of mechanism, constantly employed in collecting energy directly or indirectly from the sun's rays and in using that energy to maintain an incessant struggle against the destructive forces of its environment. This incessant getting and spending, winning and losing, constitutes what we call the life of the organism, so far as that life is capable of being expressed in chemical and physical terms. In considering what is the meaning of all this we must remember that, primarily at any rate, every living thing exists for its own benefit, and that living, like virtue, is its own reward. The organism also, however, exists for the benefit of future generations, to which it may hand on the lamp of life before its own flame is finally extinguished. There is a race life as well as an individual life, and we cannot realise too clearly that in the economy of nature the former is of infinitely greater importance than the latter.

CHAPTER II

Amœba as a typical organism—The properties of protoplasm

In illustration of the general principles dealt with in the foregoing chapter we may now consider a definite concrete example of a living organism. Probably none is better suited for this purpose than the familiar Amœba, which may be regarded as a kind of pocket edition of a typical animal.

Amœbæ may be found creeping about on the mud at the bottom of ponds and ditches. Although of microscopic size and, usually at any rate, invisible to the naked eye, they are by no means the smallest or simplest of living things, but exhibit within the narrow limits of their jelly-like bodies a considerable amount of structural differentiation.

In general appearance (Fig. 2) an Amœba resembles nothing so much as an irregular speck of translucent jelly, but if we watch it for a few minutes under the microscope we soon find that it is something more than this. If in an active and healthy condition it never maintains the same shape for long together, but manifests an ever-changing irregularity as it slowly creeps about from place to place, throwing out irregular projections of its body first in one direction and then in another and withdrawing old projections as new ones are put forth.

The viscid substance of which the entire body is composed is protoplasm, but this protoplasm is not homogeneous throughout; on the contrary, it exhibits a characteristic differentiation into parts or organs, which can be more or less readily distinguished from one another and each of which has its own duties or functions to perform.

Inasmuch as it consists of but one protoplasmic unit, however, we may speak of the body of an Amœba as a single cell.[1] As in all other typical cells, the most fundamental differentiation

[1] The origin and meaning of this term will be discussed more fully in a later chapter.

which it shows is into cell-body and nucleus. The cell-body forms by far the greater part of the organism, and the




FIG. 2 —Amœba.

A, *B*. The same individual in two phases of active movement, showing change of form.
C. Another specimen, of a different species. Note the numerous short projections at the hinder end due to contraction, while at *ect.* the commencement of a new pseudopodium is indicated by a thickening of the ectoplasm.
D. A specimen with two nuclei.
E. Diagram of reproduction by simple fission.
c.v. Contractile vacuole; *ect.* ectoplasm or ectosarc; *end.* endoplasm or endosarc; *f.p.* food particles; *f.v.* food vacuole; *nu.* nucleus; *psd.* pseudopodium. (The arrows show the general direction in which the animal is moving.)

protoplasm of which it is composed is often distinguished as cytoplasm.

The nucleus (Fig. 2, *nu.*), composed of a somewhat different variety of protoplasm sometimes known as karyoplasm or nucleoplasm, is a very definite body of more or less rounded form, sometimes shaped like a bun, and easily distinguishable from the cytoplasm even in the living animal by its more highly refractive character. Its position is by no means constant, for it floats about from place to place in the interior of the almost liquid cell-body.

The cytoplasm is very imperfectly differentiated into inner and outer portions. The former, in which the nucleus is lodged, is often called the endosarc or endoplasm (Fig. 2, *end.*), the latter the ectosarc or ectoplasm (Fig. 2, *ect.*). The ectoplasm must be regarded as a feebly developed protective layer ; it is the part which comes into direct relation with the surrounding water and through which all intercourse between the Amœba and its environment must take place. Though soft and jelly-like, it is a good deal firmer and denser than the endoplasm, and it is also more transparent, for the endoplasm contains imbedded in it numerous more or less opaque particles of various kinds which give it a coarsely granular character. Most of these particles are minute, but others are generally present of comparatively large size and enclosed in drops of clear liquid. These latter are food particles (Fig. 2, *f.p.*) undergoing digestion, and they can frequently be identified as the bodies of other organisms which the Amœba has taken in, microscopic plants or animals smaller than itself. The drops of liquid in which they occur are termed food vacuoles (Fig. 2, *f.v.*).

Another spherical drop of liquid (Fig. 2, *c.v.*) may be observed somewhere near the surface of the cell-body. This is perfectly clear and contains no solid particles ; moreover it undergoes a rhythmical dilatation and contraction, gradually increasing to a maximum size and then suddenly disappearing owing to the discharge of its contents into the surrounding water. If the spot where this "contractile vacuole" disappears be carefully watched another drop of liquid is seen gradually to accumulate there, and the process is repeated.

We are told that in the early days of chemistry, before the highly specialized apparatus which is now used was thought of, the originator of the atomic theory performed his experiments with the ordinary domestic crockery. So also an Amœba is able to perform, with the extremely simple apparatus at its disposal,

all those actions or functions which are really essential for the maintenance of life.

In the higher animals the primary differentiation of the body is into an outer protective and an inner digestive layer, each of very complex structure. The Amœba accomplishes the same end in its own primitive manner by the differentiation into ectoplasm and endoplasm. In most of the higher animals, again, we find very well developed organs of locomotion in the form of limbs. The Amœba has no permanent organs of locomotion at all but merely temporary projections of the body, the so-called pseudopodia (Fig. 2, *psd.*), which are put forth when required. In both cases, however, movement is effected in essentially the same way, by contraction and expansion of the living protoplasm. In the higher animals this power of contraction is localized in the muscles, which are highly specialized for the purpose and have no other duties to perform, while in the Amœba any part of the body, or at any rate of the ectoplasm, may contract or expand as occasion requires.

In the process of formation of a new pseudopodium we see first a thickening and protrusion of the clear ectoplasm (Fig. 2, *C.*, *ect.*), accompanied by a streaming in of the endoplasm, and the latter seems to bulge out the ectoplasm as it flows forwards. The pseudopodium is withdrawn again by a reversal of the process, the endoplasm streaming out from it into the central mass of cytoplasm and the ectoplasm contracting after the retreating endoplasm. Thus at the posterior end of an actively creeping Amœba one frequently sees numerous blunt projections which are the last remnants of retracted pseudopodia (Fig. 2, *C.*). The shape of the pseudopodia when fully extended differs very much in different kinds of Amœbæ. In some species they are comparatively short, thick and blunt, as in our illustration, while in others they are very long and slender, radiating outwards from the body of the animal in all directions. They are used by their possessor not only as organs of locomotion but also as tactile organs and, as we shall see directly, for the capture of prey.

The protrusion and retraction of pseudopodia imply, of course, the expenditure of energy, and this energy must be derived from the combustion of the body of the Amœba. In this way the protoplasm is gradually used up, and, unless the animal is to die of starvation, it must be replaced, which brings us to the consideration of the manner in which an Amœba performs the

important function of nutrition. As it crawls slowly about the pseudopodia come into contact with all sorts of solid particles in the surrounding water. Some of these will be inorganic, grains of sand and so forth, others will be the dead or living bodies of other organisms, sometimes much smaller than the Amœba itself. The Amœba has the remarkable power of distinguishing amongst these different kinds of particles those which are good for food from those which are not. How it does so we do not know; we can only say that the presence of a particle which is good for food stimulates the living protoplasm in a way quite different from that in which it is stimulated by the presence of a mere grain of sand. In the latter case the Amœba will simply pass to one side and avoid the object; in the former it will put forth pseudopodia which will close around and envelop it. The food particle is thus passed through the ectoplasm into the interior of the body. There is no definite mouth, but food is taken in wherever it happens to come into contact with the surface of the body, and the aperture closes up after it. Thus a temporary mouth is formed as occasion demands. Similarly there is no permanent digestive cavity or stomach, but merely a temporary food vacuole into which a digestive fluid is doubtless secreted by the surrounding protoplasm.

Digestion, as in higher animals, is essentially a process of solution, whereby those parts of the food which are digestible are dissolved and rendered capable of diffusing from the digestive cavity into the surrounding body. The higher animals make use chiefly of three classes of food material, proteids, carbohydrates (*e.g.*, starches and sugars) and fats. It is said that Amœba can only digest proteids, which of course it must obtain from the protoplasmic bodies of other organisms. When digestion is complete a certain amount of insoluble residues from the food will remain over; these constitute the fæces and have to be got rid of. There is, however, no permanent vent or anus, and the fæces are cast out through the ectoplasm at the hinder end of the body as the animal crawls along.

Owing to the minute size of the whole organism there is no need for a complex circulatory system, such as is found in the higher animals, for the distribution of the digested food; it merely soaks into the surrounding protoplasmic body from the food vacuoles, and, by anabolic changes which are not fully understood, is assimilated, that is, converted into new, living protoplasm.

It is not easy, if it be possible at all, actually to observe the process of respiration in so small an animal as an Amœba, but we know perfectly well from the analogy of higher organisms what must take place. Oxygen is required for the combustion of the protoplasm from which the energy of the organism is derived, and this oxygen occurs in a state of solution in all ordinary water which is exposed to the air. At the same time carbon dioxide, or carbonic acid gas, must be produced as one of the products of the combustion, by oxidation of the carbon in the protoplasm. This waste product (CO_2) will first of all be dissolved in the water which forms the greater part of the bulk of the living organism, while at the same time the water by which the animal is surrounded may be regarded as a very dilute solution of oxygen. The outermost layer of the ectoplasm may be looked upon as a thin membrane separating the two solutions.

We know from experiment that whenever two gases, or solutions of gases, of different density, are separated from each other by a thin organic membrane, they will pass through that membrane in opposite directions until a state of equilibrium is established between the two. This well-known process of diffusion is, as we have already seen, the essential feature of respiration in all plants and animals, although probably the purely physical phenomenon is controlled to some extent by the living protoplasm.

In the case of the Amœba then, the carbon dioxide diffuses out through the ectoplasm into the surrounding water while the oxygen from the surrounding water diffuses in, and the necessary exchange of gases is brought about. No specialized organs of respiration, such as we meet with in the higher animals, are required. The whole surface is a respiratory surface, and all parts of the interior are within reach by the simple process of diffusion, aided doubtless by the circulation of the semi-liquid protoplasm which is constantly going on inside the body.

Other waste products must be formed by the combustion of the protoplasm in addition to carbon dioxide. What these are we do not exactly know in the case of the Amœba, but it is evident that they must contain nitrogen, which is one of the essential constituents of all proteids. These waste products must be got rid of by some process of excretion, and it is usually supposed that they are passed in a state of solution to the contractile vacuole and thence periodically expelled to the exterior, so that

the contractile vacuole is probably to be regarded as the special excretory organ of the animal.

In all but the lowest animals there is a more or less specialized nervous system, whose function it is to place the different parts of the body in communication with one another and, through the mediation of the sense organs, with the external world or environment. The action of this system depends primarily upon one of the fundamental properties of living protoplasm, the power of responding to stimuli by some definite change in its own condition. The stimulus is, in the first instance, supplied by some factor of the environment, such as light, heat, electricity or mechanical impact. It may appear to originate in the central nervous system itself, but this is probably secondary. It has the effect of liberating stored energy in those parts of the organism which are sensitive to that particular stimulus, in somewhat the same way that the stimulus of heat may have the effect of liberating the stored energy in a charge of gunpowder. The living molecule has, indeed, actually been described as explosive. In both cases potential energy is converted into kinetic energy, and the effect which is produced may be out of all proportion to the amount of energy represented by the liberating stimulus itself.

In the higher animals, then, the stimulus received from the external environment, whatever its nature may be, acts primarily upon some special sense organ or receptor, whence it is transmitted along highly specialized tracts of tissue, the nerves, to some part of the central nervous system, where it usually gives rise to what we call a sensation. The central nervous system, again, not only has the power of receiving stimuli through afferent or sensory nerves, but also of sending stimuli through efferent nerves to the various organs of the body, whereby their functions are controlled and regulated. The contraction of muscles and the secretion of glands are all controlled in this manner, and the entire working of the body is co-ordinated largely by the action of the nervous system.

In the Amœba, however, we see no trace of a special nervous system, nor of sense organs, but nevertheless the organism is certainly capable of receiving and responding to stimuli; in other words it is irritable. Thus the protoplasmic body responds by contraction to the stimuli of mechanical impact, heat, light, electricity and chemical reagents, and, as we have already seen,

the presence of particles which are good for food causes the protrusion of pseudopodia in a definite and purposive manner. Probably the whole of at least the ectoplasm is to some extent sensitive to stimuli of certain kinds, and it is also probable that stimuli may be conducted from one part of the body to another without the existence of special nervous tracts.

One of the most difficult problems in connection with the physiology of Amœba—and indeed of any living organism—is that of automatism. Does an Amœba do anything really automatically or spontaneously, or are all its actions the result, direct or indirect, of the application of external stimuli to the explosive molecules of living matter? Is the organism merely a machine run by the environment, or is it something more? Here, of course, at the very beginning of our investigations, we are face to face with the old and much-discussed question of the existence of an animating or vital principle which exercises some sort of control over the physical and chemical processes upon which the life of the organism depends. This is a question which perhaps falls within the province of the philosopher rather than that of the biologist. The theory of vitalism, by postulating the existence of some such special vital force in all living things, undoubtedly enables us to avoid many difficulties, but it is doubtful if it really explains anything. As a matter of fact the more we study living organisms by actual observation and experiment, the more fully are we able to interpret their behaviour in terms of chemistry and physics, but this is a very different thing from saying that chemistry and physics will ultimately yield a complete explanation of vital phenomena.

It is quite possible, for example, that the movements of the Amœba may all ultimately be interpreted in such terms, for Bütschli has shown that they can be closely imitated by minute drops of oil-foam, containing potash, surrounded by water. The substance of which these droplets are composed is of course totally different chemically from protoplasm and is in no sense alive, but it seems highly probable, if not certain, that since purely physical processes (amongst which surface tension plays a very important part) are capable of producing strikingly amœboid movements in the oil-foam, they may also be largely, if not solely, responsible for the similar phenomena of movement in the living protoplasm of the Amœba itself, which seems closely to resemble an oil-foam in its physical properties.

Like other organisms, the Amœba sometimes undergoes a period of rest, during which its various activities are more or less completely suspended. Under these circumstances the pseudopodia are withdrawn, the body is rounded off and a protective envelope or cyst is secreted by the protoplasm. This, however, is only a temporary state, perhaps necessitated by unfavourable conditions of the environment, and sooner or later the organism emerges from its retirement and resumes its activity.

If in the course of its wanderings the Amœba meets with an abundant supply of food and takes in more than is actually required to make good the waste of protoplasm; if, in other words, anabolism preponderates over katabolism, the organism may increase in size by growth, by the addition of new particles of protoplasm in excess of those which are used up. These new particles are deposited, not on the surface, but throughout the whole mass of protoplasm, between those which are already formed. Thus growth takes place, not by accretion, as in a crystal or a snowball, but by intussusception, and we have here a characteristic though by no means absolute distinction between the growth of not-living and that of living matter.

As in all organisms, however, there is a limit to the size which the body may attain, and this limit varies with different species of Amœba. It depends primarily, no doubt, upon the necessary relation between surface and volume. As we have seen, all interchange between the organism and its environment has to be maintained through the surface, and a given area of surface cannot supply the wants of more than a certain volume of protoplasm. As the animal grows the volume must necessarily increase in a much higher ratio than the surface, and the proportion between the two is rapidly altered. This is probably not the whole explanation of the limitation of growth in an Amœba, the problem being doubtless complicated by other factors, but we may take it as quite certain that increase beyond a certain size, if possible, would inevitably result in death. Such a calamity is avoided by the simple expedient of dividing into two parts whenever the limit of safety is reached. The nucleus divides first and the two halves move away from one another, then the protoplasm constricts into a bridge between the two nuclei, the bridge narrows and finally ruptures, and instead of one Amœba there are now two, each exactly resembling the parent (Fig. 2, *E*.).

This simple fission of a single protoplasmic unit, or cell, forms, as we shall see later on, the essential feature of ordinary reproduction throughout the animal and vegetable kingdoms. It will be observed that in this process generation succeeds generation without the intervention of anything which we can speak of as death. There is indeed no room for death in the history of these simple organisms, unless it be death by accident, for every time fission takes place the entire body is used up, and nothing is left over to die. Nor is there any distinction to be drawn between parent and offspring, for the two new individuals are in all respects similar to one another, and neither can be said to precede the other in point of time. Obviously, fission results not only in reproduction but also in multiplication, or increase in the number of individuals, though accidents of one kind or another usually keep the numbers at approximately the same level. It sometimes happens that fission takes place within the protective envelope or cyst, secreted by the parent Amœba, giving rise to a number of so-called spores which will undergo a longer or shorter period of rest while waiting for a favourable opportunity to resume their active life.

We have now become sufficiently well acquainted with the nature of protoplasm to profit by a more detailed examination of its physical and chemical properties. We have seen that, as it occurs in the body of an Amœba, it is a viscid, more or less liquid, colourless substance, almost transparent, but exhibiting, under moderately high powers of the microscope, a granular appearance due to the presence of numerous minute and more or less opaque particles. Even apart from these coarser granules, however, the protoplasm itself never exhibits a perfectly uniform structure. It is by no means homogeneous but shows a more or less distinct differentiation into different portions, as, for example, into nucleoplasm and cytoplasm, ectoplasm and endoplasm, and so forth. In other words it is an organised substance. Moreover, it has a characteristic minute structure or texture which can to some extent be recognized under high powers of the microscope and concerning the interpretation of which different observers are as yet by no means all agreed. According to Professor Bütschli it is a kind of microscopic foam, consisting of exceedingly minute drops of a more liquid substance separated by very thin layers of denser material, and thus resembling physically such a foam as can be prepared from a mixture of oil, salts of various kinds, and

water. If this really be a correct account of the minute structure of living protoplasm it helps us, as we have already seen, to explain its characteristic movements in terms of well known physical phenomena.

Other competent observers, however, maintain that the appearance of foam-structure is a delusion and that what Bütschli interprets as thin sheets separating the droplets from one another are in reality very delicate fibres arranged in a network. These fibrillæ are supposed to be contractile and thus to be responsible for the movements of the protoplasm as a whole. But whence comes the contraction of the fibrillæ?

Various considerations, again, and especially the phenomena of heredity, oblige us to postulate for protoplasm an even more minute fundamental structure than the microscope is capable of revealing to us. It is, in all probability, made up of ultra-microscopic material units, each composed of a group of molecules, which units must themselves be regarded as living bodies capable of nourishing themselves, growing and multiplying by division.

It is difficult to form a satisfactory idea of the chemical composition of protoplasm because it is impossible to analyze it in the living condition; indeed, so long as it lives, it is constantly undergoing chemical change, and the moment it dies it ceases to be protoplasm. It is certain, however, that it is not a definite chemical compound, but a mixture of several distinct substances: proteids, mineral salts and water. Moreover, different samples of protoplasm, taken from different organisms or from different parts of the same organism, may differ widely from one another in chemical composition. Thus the difference between nucleoplasm and cytoplasm is largely a chemical one, depending to some extent upon the relatively large amount of phosphorus present in the former.

By far the most characteristic and important of the chemical constituents of protoplasm are the proteids (proteins). These form a remarkable class of substances which do not occur in nature except in the bodies of plants and animals. They are definite chemical compounds containing the elements carbon, hydrogen, oxygen, nitrogen, sulphur and frequently phosphorus, and they have an extremely complex and unstable constitution, readily splitting up on oxidation into simpler and more stable compounds and thereby liberating kinetic energy. Many

different kinds of proteids are known to us and have received special names; such are the albumin which occurs in the white of an egg, the casein which is met with in cheese, the legumin which is characteristic of peas and beans, the gliadin and glutinin of flour, and so forth,

These proteids are, for the most part at any rate, colloid substances, that is to say they are more or less jelly-like and incapable of diffusing through organic membranes. This may be accounted for if we assume that the highly complex molecules of which they are composed are too large to pass through the very minute pores which occur in such membranes and which readily allow of the passage of the molecules of simpler, crystalloid substances. The colloid nature of the proteid constituents of protoplasm plays a very important part in determining its properties and behaviour. Crystalloid mineral salts and other diffusible substances in a state of solution can pass through a cell-wall or membrane by osmosis, and thus the living protoplasm receives fresh supplies of nutriment, but the colloid proteids are as a rule formed inside the cell and cannot usually pass out again until they have undergone some chemical change whereby they are rendered diffusible.

The mineral salts which we find in the protoplasm, usually in a state of solution, are of very various kinds, compounds of sodium, potassium, calcium and other elements with various inorganic and organic acids, such as sulphuric, hydrochloric, malic and citric acids.

Finally, water must always be present in living protoplasm and usually forms a very large percentage of the whole mass.

Whatever view we may take with regard to the question of vitalism, there can be no doubt that the most distinctive property of living protoplasm is its power of controlling chemical and physical processes so as to make them yield results different from those which would be obtained if we were dealing with not-living matter. The various processes upon which depend the functions of movement, nutrition, respiration and excretion all appear to be controlled in this manner, but the general principle is perhaps most beautifully illustrated in the case of many of the lower animals and plants, in which the protoplasm secretes a protective or supporting skeleton of some mineral substance, such as silica, or carbonate of lime. Silica, for example, in the inorganic world, occurs abundantly in a state of solution in water, from which it

may be deposited in different forms, in shapeless masses as in the case of flints, or in symmetrical crystals as in some specimens




FIG. 3.—Different forms of Radiolarian Skeletons. In the central figure the protoplasmic pseudopodia are seen coming out from the openings in the shell. (From Haeckel's "Kunstformen der Natur.")

of quartz, whilst the beautiful opal, chemically speaking, is merely a hydrated form of silica.

Many simple unicellular organisms, such as the Radiolaria (Fig. 3) amongst animals, and the diatoms amongst plants, have




FIG. 4.—Different forms of Foraminiferan Skeletons. (From Haeckel's "Kunstformen der Natur.")

the power of taking up dissolved silica from the water in which they live and using it for building skeletons. These skeletons,

however, which are really composed of opal, do not consist either of shapeless masses or of geometrical crystals, but assume beautifully symmetrical forms which vary with each particular kind of organism and which are wholly different from any forms occurring in the inorganic world. The same is true of those somewhat more highly organized members of the animal kingdom, the siliceous sponges, whose skeletons consist of spicules of opal (Fig. 90), often of most beautiful and characteristic shape, and all formed by the activity of the living protoplasm of special cells.

Whilst many unicellular organisms and many sponges thus manufacture for themselves skeletons of a siliceous character, others, living perhaps in the same water, secrete skeletons which are composed of carbonate of lime. Such, for example, are the Foraminifera, the dead calcareous shells of which (Fig. 4) accumulate to-day at the bottom of the deep sea in many places in the form of ooze, while in the Cretaceous period of the earth's history they played an important part in building up the chalk cliffs on the south coast of England. Each of these microscopic shells, which are often of extreme beauty and frequently ornamented with elaborate patterns, is formed as a protective envelope by a simple protoplasmic organism closely resembling an Amœba.

It is evident, then, that we must attribute to living protoplasm a very remarkable power of selection or choice, for it is able, as it were, to pick out certain materials from its environment for its own purposes and to reject others. We have already seen this in the case of the selection of food materials by the Amœba; we see it again in the selection of the materials for skeleton formation in other simple organisms. The fact that one organism will select silica while another selects carbonate of lime from the same sample of sea water and for the same purpose, must correspond to some deep-seated difference in the protoplasm of which they are composed, and illustrates very well the diverse potentialities of this remarkable substance.

CHAPTER III

Hæmatococcus—The differences between animals and plants.

In striking contrast to Amœba, which, though primitive, is nevertheless a very typical example of an animal organism, stands Hæmatococcus or Sphærella, which, by botanists at any rate, is regarded as a very simply organized member of the vegetable kingdom. Like Amœba, this organism is of microscopic size, consisting of only a single cell or protoplasmic unit.

Hæmatococcus pluvialis (also known as *Sphærella lacustris*) occurs in temporary pools of stagnant rain-water or, in the resting condition, in dried-up mud or dust. Though individually invisible, or barely visible, to the naked eye, it may occur in such dense associations as to give the water a bright red (or sometimes green) colour and form a red crust on the sides of the vessel in which it is cultivated. A closely related, if not identical, species (*Hæmatococcus nivalis*) is the cause of the red patches which are sometimes observed on the snow-fields in Arctic regions. Cultivation is easy, and the same stock may be kept going for many years and multiplied indefinitely. Some thirty years ago I had a sample given to me in Australia, descendants of which are now flourishing in full vigour in England. It can be dried up when not required and when wanted again in the active condition needs only to be supplied with fresh rain-water and placed in the sun.

In the resting condition each individual consists of a spherical protoplasmic body (Fig. 5, A) of a bright red or green colour, or sometimes partly green and partly red, with a more or less centrally placed nucleus (*nu.*). It differs from an Amœba in the presence of a very distinct, firm cell-wall (*c.w.*) on the outside, as well as in its definite shape and characteristic colour. The cell-wall is composed of cellulose, one of a group of chemical compounds known as carbohydrates. These compounds are all characterized by the fact that they contain only three elements, carbon, hydrogen and oxygen, the hydrogen and oxygen occurring

in the same proportions as in water (H_2O). Thus the chemical formula for cellulose is $(C_6H_{10}O_5)_n$, while that for glucose or grape sugar, another carbohydrate, is $C_6H_{12}O_6$. The presence of very definite cell-walls, composed of cellulose and formed as a secretion by the living protoplasm, is very characteristic of vegetable as contrasted with animal organisms.

The protoplasm which lies inside the cell-wall is, as we have already said, either red, green or parti-coloured. The green




FIG. 5. —Structure and Life-history of *Haematococcus pluvialis*.

A. Resting stage with thick cell-wall
B. Division into four motile zoospores within the old cell wall.
C. Free-swimming zoospore
D. Division of the resting cell into 32 microzooids or gametes.
E. Free swimming gamete
F—G. Conjugation of two gametes
H. Zygote with four flagella, formed by conjugation.
J. Zygote with flagella withdrawn
K. Resting cell formed from the zygote by secretion of a thick cell-wall
c.w. cell-wall, *fl* flagellum; *nu* nucleus, *py* pyrenoid, *vac* vacuole.
(Figs. *D—K* adapted from Peebles.)

colour is due to the presence of that extremely characteristic vegetable pigment known as chlorophyll, a remarkable product of the activity of the living protoplasm with which we are all familiar in the case of ordinary green plants. The red pigment, known as hæmatochrome, is but a slight chemical modification of the green chlorophyll, and the one may readily be converted into the other. If some nitrogenous substance, such as a small quantity of manure water, be placed in a vessel containing red Hæmatococcus, the latter will in a short time assume a bright green colour, whence we may conclude that the red colouration is probably an effect of nitrogen starvation.

When a dried-up sample of Hæmatococcus is supplied with fresh rain-water and placed in the sunlight it undergoes a remarkable change. The protoplasmic body within the cell-wall undergoes division, first into two and then into four parts (Fig. 5, B). This is effected by a process of simple fission exactly comparable to that which we have already described in the case of Amœba. The four parts or daughter cells (sometimes called zoospores) are for a short time kept together within the old cell-wall, but presently this ruptures and they escape into the surrounding water.

It will now be seen that these so-called zoospores differ greatly in structure from the resting Hæmatococcus. Instead of being spherical they are more or less oval or pear-shaped in outline (Fig. 5, C). Each has secreted a new cellulose wall of its own (*c.w.*), but this is separated from the main protoplasmic body by a considerable space, or vacuole, filled with water (*vac.*), across which stretch delicate threads of colourless protoplasm, which keep the protoplasmic body in position. The main mass of protoplasm is coloured red or green, as before, and contains the nucleus (*nu.*). At one end it is drawn out into a kind of beak, from which two very long and slender threads of colourless protoplasm (*fl.*) pass outwards, through minute apertures in the cellulose wall, into the surrounding water. Owing to their whip-like form and characteristic lashing movements, these are termed flagella.

It is by the very rapid movements of the flagella that the locomotion of the active Hæmatococcus is effected. They are carried in front, and the body of the organism is pulled through the water by their action much as a boat is pulled by a pair of sculls, at a rate which, though very slow when judged by our own standards, appears very rapid when considered in relation to the minute size of the organism. The movements of the flagella are somewhat complex and of an undulatory kind. They appear to be entirely automatic, but it seems probable that they must be performed in response to stimuli which we are unable to recognize. The flagella are much more definite and highly specialized structures than the pseudopodia of an Amœba. Like the latter, however, they owe their value as organs of locomotion to that inherent power of contraction which is one of the most characteristic features of living protoplasm. It is probable that each really consists of several very slender filaments, lying

side by side, and that the complex undulatory movements are due to alternating contractions and relaxations of these.

The presence of a firm cell-wall makes the protrusion of pseudopodia in the case of Hæmatococcus quite impossible, and at the same time prevents the organism from taking in any solid food, for there is no aperture through which such food could pass. It must therefore depend entirely for its food supply upon substances which are able to pass through the cell-wall in a state of solution. These substances are all very simple chemical compounds, consisting of certain mineral salts and carbon dioxide gas, which, amongst them, contain all the elements necessary for the formation of protoplasm. They are, however, very stable bodies, with little or no affinity for oxygen gas and little potential energy. They cannot, therefore, by themselves supply the energy which the organism requires for its vital activities. Energy has to be supplied from the environment and the simple food materials thereby partially deoxidised and combined together in more complex and less stable molecules containing stores of potential energy which can be liberated by oxidation as required.

The energy which Hæmatococcus uses for the building up of its complex molecules is, as we have already observed for green plants in general, the radiant energy of the sun, in the form of light. This direct absorption of solar energy can only take place in organisms which possess chlorophyll or some functionally equivalent pigment, such as hæmatochrome. The energy is temporarily stored up in molecules of sugar or starch, and the building up of these carbohydrates under the influence of light is known as photosynthesis.

The first step in this complex process involves a chemical decomposition, carbon dioxide, obtained in solution from the surrounding water, being decomposed with evolution of free oxygen gas.

We have already seen that in the combustion of charcoal the reverse of this takes place, carbon and oxygen combining to form carbon dioxide and the act of combination being accompanied by the liberation of energy. It is obvious that if energy is liberated in the one process a corresponding amount must be absorbed in the other.

When a glass jar of water containing Hæmatococcus, or any green aquatic plant, is placed in bright sunlight the decomposition

of carbon dioxide in the plant takes place so rapidly that minute bubbles of oxygen may often be seen rising to the surface of the water. If, for example, we cut off a leafy branch of the common Canadian water weed, known as *Elodea canadensis*, and fix it under water in such a jar, it is possible to arrange the experiment so that a regular stream of small oxygen bubbles will be given off from the cut end, and it is further possible to adjust the experiment so delicately that the interposition of a dark screen between the jar and the sunlight will cause the immediate cessation of the stream of bubbles, which will start again the instant the screen is removed. This simple and beautiful experiment clearly demonstrates the dependence of the process of decomposition of carbon dioxide upon the presence of sunlight.

The oxygen liberated in this way is not (with the exception of a relatively small quantity used in respiration) required by the organism, and is accordingly at once discharged into the surrounding medium. The carbon, on the other hand, is needed for the manufacture of new protoplasm. It is never actually set free as carbon, but its molecules are probably recombined—under the influence of the sunlight—with the molecules of water to form the carbohydrate known as glucose or grape sugar. This process may be represented by the equation—

$6\ CO_2$	$+$	$6\ H_2O$	$=$	$6\ O_2$	$+$	$C_6H_{12}O_6$
(Carbon Dioxide)		(Water)		(Oxygen)		(Glucose).

It is probable that a simpler compound, possibly formaldehyde (CH_2O), is formed as an intermediate product, while, on the other hand, the glucose appears to be rapidly converted into starch, which is the first visible product of the process of photosynthesis in the plant cell.

Starch, like glucose and cellulose, is a carbohydrate, and, though differing in many of its chemical and physical properties, has the same general formula as the latter $(C_6H_{10}O_5)_n$. This means simply that the elements carbon, hydrogen and oxygen are present in the same proportions as in cellulose, but they must be linked together differently in the molecule.

The first step in the actual construction of the proteid molecule is then the combination of carbon with the elements hydrogen and oxygen in the proportion H_2O. In the higher plants starch first appears in the chlorophyll-containing cells of the leaves in

the form of starch grains, which may afterwards be converted into sugar again and then, in solution, transferred to other parts of the plant, where it is redeposited and stored up, once more in the form of starch grains, for future use, as in the potato and in starch-containing seeds such as peas and beans.

Both starch and chlorophyll are, at any rate usually, formed in the cell in connection with specialized portions of the protoplasm known as plastids. These are regarded as living bodies which are specially concerned in the formation of chlorophyll, starch and other substances. When they contain chlorophyll they are termed chloroplastids, and in the higher plants they take the form of numerous minute "chlorophyll corpuscles" of definite shape, which occur in abundance in the cells of all green parts, and in connection with which the starch grains are formed (*vide* Fig. 26). In Hæmatococcus practically the whole central mass of cytoplasm is coloured by the chlorophyll (or hæmatochrome) and may perhaps be regarded as a single large chloroplastid. The starch, however, is collected around small, specialized, proteid bodies imbedded in the general mass of cytoplasm. These are known as pyrenoids (Fig. 5, C, *py.*).

We have thus seen how the green plant obtains the carbon, hydrogen and oxygen which it requires for the manufacture of protoplasm. Other elements, however, have to be combined with the molecules of carbohydrate before proteids can be formed. These are nitrogen, sulphur and, sometimes at any rate, phosphorus, all of which are obtained by green plants by the decomposition of mineral salts—nitrates, phosphates and sulphates—which exist in solution in the water or damp soil in which the plant grows. In the higher plants these substances are taken up by the root-hairs and transmitted to the leaves by a system of vessels and tracheids analogous to the circulatory system of animals. In such a plant as Hæmatococcus they simply diffuse into the protoplasmic body from the surrounding water by the process of osmosis. Exactly what happens when they meet with the carbohydrates we do not know, but further chemical combinations must take place, possibly still more or less dependent upon sunlight, which finally result in the formation of new proteid molecules which are added to the already existing protoplasm.

Respiration in Hæmatococcus probably takes place exactly as in Amœba, but it is more easily studied in the case of the higher plants. In daylight the process is greatly obscured by

the absorption of carbon dioxide and the evolution of oxygen gas which accompany photosynthesis. In darkness, however, the gaseous interchange which forms the essential feature of respiration can readily be detected, carbon dioxide, produced by oxidation of the protoplasm, being given off and oxygen taken in.

No special organ of excretion has been observed in Hæmatococcus, though a contractile vacuole occurs in closely allied forms, and waste products must simply diffuse into the surrounding water through the permeable cell-wall.

We have already seen that Hæmatococcus multiplies itself by simple fission within the old cell-wall. This process usually results immediately in the production of four new individuals. Under favourable circumstances it may be repeated very rapidly, without the organism going through any true resting stage, so that in a short space of time the number of active zoospores may be very largely increased. The individuals thus produced are usually all of the same form, and ultimately of the same size, as the parent. Occasionally, however, a somewhat different process of multiplication takes place. Instead of dividing into four relatively large zoospores a resting individual may divide into thirty-two or sixty-four much smaller "microzooids" (Fig. 5, D), which differ from the ordinary active form in the absence of the characteristic cell-wall with its underlying vacuole.

The microzooids (Fig. 5, E) swim actively about by means of their flagella. Sooner or later, however, they come together in pairs (Fig. 5, F, G), and the members of each pair fuse completely with one another to form a single individual (Fig. 5, H) with four flagella, which presently loses its flagella, secretes around itself a thick cell-wall, and enters upon the resting state (Fig. 5, J, K). From this resting individual new generations will be produced by the ordinary method of division into zoospores.

We have here an excellent illustration of what is usually termed sexual reproduction, the essential feature of which is the union or conjugation of two sexual cells or gametes (in this case the microzooids) to form a single cell, the zygote, which is the starting point of a fresh series of cell generations. This important process will be discussed more fully in a subsequent chapter.

We have spoken of Amœba as an animal, and, as we have seen, many people regard Hæmatococcus as a plant. We must next endeavour to find out what it is that really differentiates a plant from an animal. Of course amongst the more highly organized

members of the animal and vegetable kingdoms we can point to many obvious distinctions. The higher plants are fixed and stationary, while the animals move about from place to place by means of special organs of locomotion. The animals have complex digestive, respiratory, excretory, nervous and sensory organs, which are wanting in the plants. Lastly, the animals have no chlorophyll and cannot therefore, like the green plants, obtain their supplies of energy directly from the sun's rays by photosynthesis, but must depend upon the potential energy contained in the complex molecules of their food, which they obtain ready made from the bodies of other organisms.

Amongst the lower organisms, however, we find that most of these distinctions disappear. Thus many of the lower plants move about actively while many of the lower animals, such as the sponges, hydroids and corals, are fixed and stationary in the adult condition, though still showing their animal nature in other respects, such as their method of nutrition. This mixture of what were once regarded as distinctively animal and vegetable characters in such forms as the corals and hydroids gave rise to the name "zoophytes," or animal-plants, by which these organisms were known to the older naturalists.

When we descend to forms still lower in the scale of organization, consisting each of a single cell, we find that every distinction may disappear except that of the presence or absence of chlorophyll and the mode of nutrition immediately dependent thereon:—plant-like or holophytic as in Hæmatococcus, animal-like or holozoic as in Amœba.[1]

It cannot be maintained, however, that even these characters form an absolute distinction between plants and animals, for, in the first place, many undoubted plants, such as the Fungi, have lost their chlorophyll by degeneration, and, in the second place, while botanists claim Hæmatococcus and the forms closely related to it as plants, zoologists claim them as animals, chiefly because they are so closely related in structure to other unicellular flagellates which contain no chlorophyll that we cannot refuse to include them in the same group.

[1] The nutrition of any typical green plant is holophytic, that of any typical animal holozoic. The latter term implies the taking in of solid food derived from the bodies of other organisms, and is thus distinguished from the saprophytic type of nutrition met with in many of the lower animals and plants (*e.g.* Fungi), which consists in the absorption of liquid food derived from the decaying bodies of other organisms.

The explanation of the difficulty really lies in the fact that both plants and animals originally sprang from common unicellular ancestors which were neither the one thing nor the other. The first appearance of chlorophyll initiated the great cleavage between the animal and vegetable kingdoms. Thenceforward the two great groups developed each along lines of its own. By virtue of their chlorophyll the green plants became the great proteid manufacturers of the world, and the animals became dependent upon them for their food supply. Animals are largely dependent upon green plants in another respect also, for the latter, as we have seen, split up the carbon dioxide, formed as a waste product in the respiration of both groups, and thus set free fresh supplies of the necessary oxygen.

Closely correlated with the differences in their method of nutrition are other great differences in the mode of life of the higher plants and animals. Plants have no need to move from place to place in search of food, which they obtain from the air and the soil, and the supplies of which are constantly renewed by wind and rain. Highly organized animals, on the other hand, would soon exhaust their supplies if they remained always in the same place, and it is doubtless the necessity for actively seeking out and even contending one with another for fresh supplies that has brought about the wonderful elaboration and perfection of their organization, while the fact that in so many cases they devour one another, instead of remaining directly dependent upon vegetable organisms, must have greatly intensified the struggle for existence and correspondingly increased the rate of progress in their evolution.

CHAPTER IV

The cell theory—Unicellular organisms—Differentiation and division of labour—Co-operation—The transition from the unicellular to the multicellular condition—The early development of multicellular animals and plants.

We have seen that, although Hæmatococcus and Amœba differ widely from one another in various respects, they nevertheless exhibit a fundamental agreement in structure, for each consists essentially of a single nucleated mass of protoplasm, each is a single cell.

The history of the term cell is a curious one, and affords a good illustration of the manner in which our scientific conceptions




Fig. 6.—Thin Section of a Bottle Cork, showing cellular Structure, × 170. (From a photograph.)

gradually become modified and improved as our knowledge increases. Nothing was known of cells before the invention of the microscope, but in the latter half of the seventeenth century this invention opened up an entirely new field of research, and enabled the earlier microscopists to lay the foundations of the modern science of biology. To Robert Hooke has been assigned the credit of first observing the cellular structure of vegetable tissues, and his observations, published in 1665, were soon afterwards

confirmed by Nehemiah Grew, who published his great work on the Anatomy of Plants in 1672.

It is now a matter of common knowledge that many vegetable tissues, such as cork and pith, when seen in section under the microscope, exhibit a honeycomb-like appearance, being composed




Fig. 7.—Part of a cross section of a Maize Root, showing cellular Structure, × 84. (From a photograph.)

Cort., cortex; pi., pith; V., vessels.

of rectangular or polygonal, or it may be spherical chambers separated from one other by firm walls. This structure is very well shown in Fig. 6, which represents part of a thin section of an ordinary bottle cork, and in Fig. 7, which represents part of a transverse section of a root of maize. It was the resemblance to a honeycomb that led to the application of the term cell to these chambers. The earlier observers naturally attached most

importance to the cell-walls, which indeed are alone visible in dead tissues such as dry cork and pith.

It was not until 1846 that von Mohl first gave the name protoplasm to the slimy contents of the cells in living tissues. It then gradually became evident that this protoplasm was the really vital constituent of the cell, and that it was identical in nature with the substance of which minute naked organisms such as the Amœba are composed, and which was already known by the name sarcode, given to it by Dujardin in 1835.

The cell theory, first propounded in a very imperfect form by Schleiden and Schwann, about the year 1838, rapidly developed, during the course of the nineteenth century, into one of the most fertile generalizations of natural science. At the present day the term cell is extended to protoplasmic units which may have no cell-walls at all, and to which therefore it is etymologically quite inapplicable, and for a long time a cell has been defined simply as a single nucleated mass of protoplasm.

In accordance with the cell theory such nucleated masses of protoplasm are the organic units of which the bodies of all living things are built up. The simpler organisms, such as Amœba and Hæmatococcus, consist each of a single unit only, and are therefore said to be unicellular, while the more complex forms, both of animals and plants, consist each of many such units united together in a multicellular body. Moreover, we now know that cells never originate *de novo* but multiply by division, so that each one is the immediate descendant of a pre-existing cell, a very important fact which was emphasized by Virchow in his often quoted phrase "Omnis cellula e cellula."

The zoologist includes under the name Protozoa all those unicellular organisms which he claims as members of the animal kingdom, whilst the unicellular plants are relegated to the domain of the botanist under the name Protophyta, but, as we have already seen, it is impossible to draw a rational line of demarcation between these two groups and they are often included together under Haeckel's term Protista.

The outstanding feature in all these simple forms of life is that the single cell is a complete and self-supporting organism. It has to perform all the necessary vital functions for itself, by means of such simple organs, temporary or permanent, as can be produced by differentiation within the microscopic limits of its

protoplasmic body.[1] It is surprising what a high degree of organization, as indicated by complexity of structure, may be attained in such a case.

Differentiation and division of labour are the results of progressive evolution, and at the same time the means by which further progress is effected. Even in Amœba and Hæmatococcus we see clearly enough the operation of these two great principles. Many unicellular organisms, however, exhibit a far higher degree of organization. The Protozoon, Paramœcium (Fig. 8), so common in infusions of decaying vegetable matter, swims actively about by means of innumerable short vibratile cilia which project all over the surface of the body. It has a definite mouth, through which




FIG. 8.—*Paramœcium aurelia*, × 300. (From Marshall and Hurst's "Practical Zoology.")

AV, anterior contractile vacuole (dilated); EC, ectoplasm with trichocysts; EN, endoplasm; EP, micronucleus; FV, food vacuole; M, mouth; MY, contractile fibrillæ; N, meganucleus; OG, groove leading to mouth: PV, posterior contractile vacuole (contracted); TR, discharged trichocyst threads; X, cilia.

solid food particles are taken in, and a less definite anal spot at which fæcal matter is ejected. It has special weapons of offence or defence (trichocysts) which can shoot out from the surface of the body long threads when the animal is irritated. It has two contractile vacuoles, each with a system of radiating canals discharging into it, and it has two nuclei, large and small (meganucleus and micronucleus), which appear to fulfil different functions and each of which doubtless has a complex structure of its own. How complex the structure of the nucleus may be we shall be better able to judge when we come to speak of the phenomena of nuclear division in a subsequent chapter.

[1] The organs into which a single cell may be differentiated are sometimes spoken of as organellæ, but if we define an organ as any part of an organism which is specialized for the fulfilment of some particular function, it is quite unnecessary to distinguish the organs of a single cell by a special term.

Paramœcium and many other Protozoa, again, have specialized contractile threads of protoplasm lying just beneath the surface of the body, comparable to the muscle fibres of higher animals, which enable them to perform movements of a different kind from those effected by flagella or cilia. By means of such contractile fibres, localized mainly in a long stalk, the bell-animalcule, Vorticella (Fig. 9, 10), can instantaneously draw in its ciliated disc and pull itself out of harm's way on the approach of danger. Other examples of these highly organized ciliate Protozoa (Infusoria) are shown in Fig. 9. These forms should be compared with the Radiolaria and Foraminifera represented in Figs. 3 and 4.

Another very important factor in the progress of organic evolution is supplied by the principle of co-operation between different organic units. This is illustrated to some extent in the process known as colony-formation met with in certain Protozoa and Protophyta. Carchesium, Epistylis and Zoothamnium (Fig. 9, 11–15), for example, are colony-forming Infusoria closely related to Vorticella. Vorticella itself multiplies rapidly by simple longitudinal fission. The bell-shaped protoplasmic body at the end of the stalk divides into two parts, one of which swims away, attaches itself to some foreign object, and develops a new stalk. If, instead of separating, the two daughter cells remained together and went on dividing, and if this division also extended each time to the upper part of the stalk, the organism would presently arrive at a branching, tree-like condition. This is what has happened in Carchesium, Epistylis and Zoothamnium, and also in various other Protozoa.

This arborescent type of colony-formation, moreover, is by no means the only one met with amongst the Protista. It is characteristic of stalked forms. Other forms, which are not stalked, may give rise to free-swimming or floating, solid or hollow aggregates of plate-like or it may be spherical shape. The development of such colonies is perhaps nowhere better seen than in the small group of unicellular organisms to which Hæmatococcus belongs, the members of which are known, on account of their plant-like character and their possession of flagella, as Phytoflagellata.

Hæmatococcus, or the closely related Chlamydomonas, may be taken as the starting point of the series. These two are always solitary, the individuals separating completely from one another





Fig. 9.—Various forms of Ciliate Protozoa (Infusoria), highly magnified (From Haeckel's "Kunstformen der Natur.")

1, *Codonella*; 2, 3, *Dictyocysta* (shell only); 4, *Tintinnopsis* (shell only); **5, *Cyttarocyclis*** (shell only); 6, *Petalotricha* (shell only); 7, 8, ***Stentor*; 9, *Freia*; 10, *Vorticella*;** 11, 12, *Carchesium*; **13, *Epistylis*;** 14, 15, *Zoothamnium*.

fter each cell-division. In Pandorina (Fig. 10), however, which s another common fresh-water organism, the individuals pro-uced by fission remain together and form a solid ball, composed f from sixteen to sixty-four cells, enclosed in a gelatinous nvelope. These little colonies swim about actively by means of neir flagella, which project from the surface in pairs, one pair elonging to each individual. Multiplication is usually effected y the division of each individual cell into sixteen, so that as nany daughter colonies are formed as there were cells in the arent colony, and these daughter colonies finally separate from one another. Eudorina (Fig. 40) forms slightly larger colonies of a similar kind, but with the component individuals somewhat widely separated from one another by the gelatinous matrix. Finally, in Volvox (Fig. 11), one of the most familiar and beautiful of the microscopic fresh-water organisms, we find the individual cells, each one still closely resembling a Hæmatococcus, arranged side by side in the gelatinous wall of a hollow sphere, with their flagella projecting from the surface, while aughter colonies are frequently seen swimming about freely in he interior of the sphere.



'IG. 10.—*Pandorina morum*, × 400. (From Vines' "Botany.")
, free-swimming colony; B, conjugation of two gametes.

In all these colonies the gelatinous matrix or ground substance s formed as a secretion by the cells which it serves to hold ogether. It is noteworthy that the connection between the ndividual cells is much more intimate in Volvox than it is in the ower types, for they are all united together by extensions of heir protoplasmic bodies which give a reticulate appearance to he wall of the sphere. Volvox, moreover, attains a relatively arge size, and there may be as many as 22,000 cells in a single olony, though about half that number appears to be more sual.

We meet with another example of the formation of hollow pherical colonies in the case of the beautiful Radiolarian

Sphærozoum (Fig. 12), which floats about in the surface waters of the open ocean and has in each of its component cells a supporting skeleton of branched siliceous spicules.

The co-operation of a larger or smaller number of cells to form a colony at once opens up new possibilities with regard to





FIG. 11.—*Volvox aureus.* (From Weismann's "Evolution Theory," after Klein and Schenck.)

A, mature colony containing daughter colonies (*t*) and ova (*o*); *B*, group of 32 developing spermatozoa seen end on; *C*, the same seen sideways; *D*, mature spermatozoa, × 824.

differentiation and division of labour. If a sufficiently good understanding, so to speak, can be established between the different members (or zooids) of the colony it will no longer be necessary for each one to do everything for itself. At the expense of becoming mutually dependent upon one another they will be able to specialize in different directions, some identifying themselves with one necessary duty or function and some with

other. As a result of this specialization the various functions ay be much more efficiently and economically performed, but a less important result will be that the different individuals will longer be able to lead independent lives—if separated from e another they will perish because unable to perform for emselves individually all the functions which are necessary for eir existence.

In colonies of Protista we meet with little if any of this ferentiation and division of labour; from the physiological int of view the cell units remain almost if not quite indendent of one another, and that is why they are still classed amongst the unicellular organisms. There can be no doubt, however, that it was this habit of colony-formation that led to the origin of true multicellular animals and plants—Metazoa and Metaphyta—from unicellular ancestors. The component cells of a colony gradually became integrated to form an individual of a higher order, and this process was accompanied by that differentiation and division of labour which in course of time led to the astonishing complexity of structure which characterizes e higher members of both the animal and vegetable kingdoms.



IG. 12.—A colony of Sphærozoum, cut in half. (After Haeckel, in "Challenger" Report.)

contrast to this complexity of the organism as a whole we all find that the individual cells of one of the higher animals plants are usually much simpler in structure than the more ghly organized Protista. After what we have said about ferentiation and division of labour the reason for this should sufficiently obvious.

Perhaps no more convincing demonstration of the applicability the cell theory to the higher plants and animals could be ven than that which is afforded by the study of development, ·, however highly organized a plant or an animal may be in the ult condition, it always commences its individual existence as single cell—the fertilized ovum or zygote—and attains the

adult state by means of a longer or shorter series of cell-divisions. The earlier cell-divisions constitute what is termed the segmentation of the ovum, and result in the formation of a number of daughter cells, which exhibit little or no differentiation amongst themselves and are known as blastomeres. Sooner or later, however, differentiation sets in and leads to the formation of more or less highly specialized tissues or cell aggregates.

In the primitive, fish-like Amphioxus,[1] for example, the ovum (Fig. 13, I) is a spherical, nucleated cell about $\frac{1}{250}$th inch in diameter. After fertilization by a male gamete or spermatozoon it divides first into two equal and similar embryonic cells or blastomeres (Fig. 13, II) by a vertical cleavage. Another vertical cleavage, at right angles to the first, divides each blastomere into two smaller ones (Fig. 13, III). This is followed by a horizontal cleavage, which results in the formation of eight cells, in two tiers of four each, the four upper ones being slightly smaller than the four lower (Fig. 13, IV). The blastomeres go on dividing and presently arrange themselves in the form of a hollow sphere, whose wall is composed of a single layer of cells (Fig. 13, VII). The embryo has now reached the blastula (or blastosphere) stage of its development, a stage which is passed through by all multicellular animals whose life-history follows a typical course unmodified by secondary features.

If we allow for the fact that the cells all remain together instead of separating from one another after each division, it is obvious that the segmentation of the fertilized ovum into blastomeres is identical with the process of multiplication by fission in such a protozoon as Amœba. The fact that each blastomere is equivalent to a single protozoon and multiplies in a similar manner has been experimentally demonstrated in an extremely interesting way by Herbst, whose observations were made upon the development of the common sea urchin (Echinus). He found that, if the eggs are allowed to develop in sea water from which every trace of calcium has been removed, the blastomeres actually do separate after each division and give rise to 808 individual cells, which swim about separately like so many flagellate Protozoa instead of remaining united together and co-operating with one another to form the normal blastula. The blastula stage itself, of course, corresponds very closely in general features with such a protozoon colony as we meet with in the case




FIG. 13.—Early Development of Amphioxus. (Adapted from Ziegler's Models, after Hatschek.)

I, the fertilized egg; *II*, two blastomeres formed by the first cleavage; *III*, stage with four blastomeres; *IV*, stage with eight blastomeres; *V*, stage with sixteen blastomeres; *VI*, stage with thirty-two blastomeres, cut in half vertically; *VII*, blastula or blastosphere stage, cut in half; *VIII*, early stage of gastrulation, cut in half

of Volvox or Sphærozoum (compare Figs. 11 and 12), a point to which we shall have occasion to return in a later chapter.

In the blastula of Amphioxus the cells are still all very much alike, except that those at one pole of the sphere are somewhat larger than the others. Differentiation, however, now sets in in a very marked manner, and the cells thereby become divided into two distinct groups. That portion of the wall of the hollow blastula which is formed by the larger cells becomes pushed inwards or invaginated (Fig. 13, VIII), much as a tennis ball may be pushed in by the pressure of the thumb, until it comes into contact with the inner surface of the remainder of the wall. In this way the original cavity (blastocœl) is obliterated and the embryo takes on the form of a double cup (Fig. 13, IX, X). The cavity of this cup is an entirely new formation. It is the primitive digestive cavity of the animal and is known as the enteron or gastral cavity. Its mouth gradually contracts to a narrow aperture, the blastopore. The outer layer of cells forming the wall of the cup is termed the epiblast and the inner the hypoblast, and the two are continuous with one another all round the blastopore. The stage now reached is spoken of as the gastrula stage.

In nearly all Metazoa the blastula stage of development is followed by one exhibiting the essential features of the gastrula, or at any rate some indication thereof. The primary differentiation of the component cells of the body into an outer epiblast (which becomes the ectoderm of the adult) and an inner hypoblast (which becomes the endoderm of the adult), the one serving for protection and for the maintenance of all the necessary relations with the external environment, and the other surrounding a gastral cavity and concerned with the digestion of the solid food which the animal captures, is closely correlated with the characteristic animal or holozoic method of nutrition.

In later stages of development, in all animals higher than the

---

IX, young gastrula in longitudinal section; *X*, older gastrula in longitudinal section; *XI*, *XII*, *XIII*, transverse sections of older embryos, showing the formation of the cœlomic pouches, notochord and neural tube; *XIV*, longitudinal section of embryo of about the same age as *XII*; *XV*, side view of embryo of same age as *XIV* with the epiblast stripped off from one side to show the mesoblastic somites formed from the cœlomic pouches.

bp. blastopore; *blc*. blastocœl or segmentation cavity; *c.p*. cœlomic pouch; *ent*. enteron; *ep*. epiblast; *hyp*. hypoblast; *m.s*. mesoblastic somites; *not*. notochord; *n.p*. neuropore or anterior opening of neural tube; *n.pl*. neural plate; *n.t*. neural tube (central nervous system, formed by folding of neural plate); *o.c.p*. openings of cœlomic pouches into enteron.

Cœlenterata (a group which includes such forms as jelly-fish, anemones and corals), a third layer of cells makes its appeara between the first two and forms the mesoblast (giving rise to mesoderm of the adult). In Amphioxus this mesoblast arises a series of hollow, pouch-like outgrowths of the hypoblast (Fig. XI, XII, *c.p.*), and the cavities which these pouches contain g rise to the body cavity or cœlom, while their walls give rise mesodermal tissues.

In accordance with what is commonly known as the ger layer theory, these three layers of cells, epiblast, mesoblast, a hypoblast, can be recognized in the embryos of all the higl animals, and from them all the various parts of the adult bc are derived. The epiblast gives rise to the outer skin epidermis, the nervous system and the essential parts of sense-organs; the hypoblast gives rise to the lining epithelium the alimentary canal and its various outgrowths, including digestive glands, while from the mesoblast arise the varic connective and skeletal tissues, the blood-vessels and the essent organs of reproduction. The cells of which each tissue is co posed acquire a characteristic structure of their own, and this way the histological differentiation of the body is gradua completed.

With the early stages in the development of Amphiox described above, we may compare the corresponding processes the life-history of a flowering plant. Here the ovum, instead being at once liberated from the parent, undergoes all t earlier stages of its development within the so-called ovu which, with the contained embryo, will ultimately be set free the ripe seed (compare Chapter VIII.).

As a definite example we may take the common weed known shepherd's purse, *Capsella bursa-pastoris* (Fig. 14). The ovu lies in a chamber in the ovule termed the embryo-sac. It is first a single nucleated mass of protoplasm without any cell-wa After fertilization it divides into two cells separated by a wa and the process is repeated by a series of divisions parallel to t first one until we have a row of cells. The cell at one end this row, known as the basal cell (Fig. 14, A, B, *b.c.*), is larg than the others and is attached to the wall of the embryo-s At the opposite end is a rounded cell, called the embryonic c from which the body of the young plant will be chiefly form The remainder of the row, including the basal cell, is known

the suspensor, and serves for the attachment and nutrition of the embryo, which at first develops entirely at the expense of the parent, having no means of feeding itself. All the cell-divisions




FIG. 14.—Four stages in the early Development of a Flowering Plant, *Capsella bursa-pastoris*, × 200. (From Scott's "Structural Botany," after Hanstein.)

b.c., basal cell of suspensor; *ct.*, cotyledons growing out; *d*, dermatogen; *e*, embryonic group of cells; *g.p.*, growing point of stem; *h*, uppermost cell of suspensor; *pe*, periblem, *pr*, *pl*, cells of plerome; s_1, s_2, cells derived from *h*.

so far have taken place in planes parallel to one another, thus giving rise to a single row of cells, but the embryonic cell now divides into four parts by the formation of two cell-walls at right angles to each other and to the preceding divisions (Fig. 14, A, *e*), and each of these again divides into two by the formation

of a wall parallel to the earlier divisions (Fig. 14, B, *e*). embryo now consists of eight cells or "octants." The next sions are parallel to its surface and cut off a superficial cov of cells, known as the dermatogen (Fig. 14, C, *d*), from w the whole of the epidermis of the adult shoot will be der The mass of rapidly dividing cells within this soon bec differentiated into two parts, the plerome (Fig. 14, D, *pr*, *pl*), in the axis of the embryo, and the periblem (Fig. 14, D, *pe*), between the plerome and the dermatogen. The plerome give rise to the vascular system of the plant and the tissues ciated therewith, while the periblem will give rise to the co tissues of the stem and root and the mesophyll or middle lay the leaves. The periblem of the root, and the root-cap, are r formed from the uppermost cell of the suspensor (Fig. 14, By further cell-multiplication and differentiation in the primary layers—dermatogen, periblem and plerome—all various tissues of the adult plant are produced.

Thus we see that in the higher plants and animals alik development of the individual from the fertilized egg consis the first place of a process of cell-division, and in the second of differentiation amongst the cells thus produced, accomp by grouping of the differentiated cells to form the more o sharply defined tissues of the adult.

CHAPTER V

The cell theory as illustrated by the histological structure of the higher animals and plants—Limitations of the cell theory—The cell as the physiological unit.

In all the higher animals and plants the constituent cells of the adult body are grouped in more or less well defined tissues, which originate from the fertilized ovum in the manner indicated in the last chapter, and the cells of each tissue co-operate with one another in the fulfilment of some common function. The study of the microscopic structure of tissues is termed histology.

As examples of animal tissues we may take blood, epithelium, fat; cartilage, muscular tissue and nervous tissue, as met with in typical vertebrates.

Blood is exceptional in that it is a liquid tissue, a condition which is of course necessary in order that it may circulate through the blood-vessels and perform its functions as the distributor throughout the body of food material and oxygen, and the carrier of carbon dioxide and other waste products from all the various parts of the body to the special organs of respiration and excretion. Floating in the liquid portion, or plasma, are found two kinds of cells, the white and red blood-corpuscles.

The white corpuscles, or leucocytes (Fig. 15, a.), closely resemble Amœbæ. They are colourless, nucleated cells, exhibiting amœboid movements, and they have the remarkable power of creeping through the thin walls of the blood-capillaries into the surrounding tissues. Like the Amœba they feed, in part at any rate, by taking in and digesting the bodies of other minute organisms which may gain access to the body. They exhibit a much greater degree of independence than most of the cells of the body and can even live outside the body for a time if kept in suitable culture media and at the proper temperature. Their most important function appears to be to defend the body from the attacks of bacteria and other harmful micro-organisms.

If these gain entrance into the tissues at any weak spot they are set upon by the leucocytes and literally devoured. This process is known as phagocytosis, and in this capacity the leucocytes are often spoken of as phagocytes. It is obvious that the health of the body must depend largely upon the activity of the phagocytes and their efficiency in dealing with disease-producing "germs."

The white blood-corpuscles, then, differ in no essential particular as regards their structure and mode of life from so many Protozoa. It is true they cannot live permanently outside the




FIG. 15.—Blood Corpuscles of the Frog, × 326. (From a photograph.)

a., white corpuscle or leucocyte; b., red corpuscles or hæmatids. The nuclei appear light-coloured in the photograph owing to their having been stained blue in the preparation.

body, but that is also the case with many parasitic Protozoa which live in the blood of other animals. That they are not independent organisms, but form an integral part of the body in which they occur, is, however, obvious from the fact that they have a common origin with all the other tissues from the developing ovum. In the adult they are formed from cells in the spleen and certain other parts.

The red corpuscles, or hæmatids, are very different things. They float passively in the blood-stream and serve as the carriers of oxygen gas from the respiratory organs to the various tissues. Unlike the leucocytes they have definite and constant outlines, though, owing to the flexible nature of the thin cell-membrane by which they are enclosed, they may undergo temporary distortion.

Individually of a pale yellow colour, and so small as to be quite invisible to the naked eye, they occur in such vast numbers as to give the blood its characteristic scarlet or purple colour. It is estimated that in a cubic millimetre of human blood there are about five millions of these red corpuscles.

In the frog the hæmatids are flattened oval cells about 0·02 mm. in longer diameter, with a centrally placed nucleus (Fig. 15, b.). In man they are a good deal smaller, and circular in outline, like biscuits, and, as in all the Mammalia, the nucleus



FIG. 16.—Epithelium from the Mesentery of a Frog, × 280. (From a photograph.)

The underlying tissues are seen indistinctly through the transparent epithelial cells, whose outlines only are visible.

has entirely disappeared. They owe their red colour, and their power to act as carriers of oxygen, to the presence in them of a peculiar pigment known as hæmoglobin, with which the oxygen appears to enter into a state of loose chemical combination from which it is easily liberated again when required by the tissues. They may indeed be regarded as mere bags of hæmoglobin, formed from highly specialized cells which have lost all power of independent existence. They cannot multiply by division, but, as the old ones are worn out, they are replaced by the formation of new ones from less specialized cells in the red marrow of the bones.

The term epithelium is applied to any layer of cells covering a free surface. An epithelium is therefore primarily a protective layer, but it frequently becomes modified for other purposes. It may, for example, become glandular, certain of its cells taking on the function of secretion, or it may become sensory, with cells specially adapted for the reception of stimuli. It may consist of a single layer of cells or of several layers one above the other.

A good example of the single-layered type is found in the peritoneal epithelium which covers the surface of the mesentery or membrane supporting the intestines in the cœlom or body cavity. Fig. 16 represents a portion of such an epithelium in which the cell-outlines have been rendered very distinct by staining with silver nitrate; the nuclei, however, are not shown by this method. Each cell has the form of a thin, flat, polygonal plate, and they all fit accurately together at their edges. With this Figure should be compared Fig. 28, A, which represents a single-layered epithelium prepared in such a way as to show both nuclei and cell-outlines.




Fig. 17.—Five isolated Epithelial Cells from the inner Surface of the human Cheek, × 420. (From a photograph.) The nuclei are stained darkly.

If we gently scrape the inside of the cheek with some clean, blunt instrument, and examine the milky-looking product under the microscope, we shall find that it contains a number of flattened, scale-like bodies (Fig. 17), either entirely separated from one another or still more or less connected together by their edges, and probably to some extent overlapping. These also are epithelial cells, which have formed part of the special epithelium known as the epidermis, which is derived from the epiblast or external cell-layer of the embryo and covers the outer surface of the body. If we examine our preparation more carefully we shall find that the cells have an irregularly rounded contour and that they measure about 0·08 mm. in diameter. There is a more or less centrally placed nucleus (which appears dark in the figure owing to the manner in which it has been stained) and the

cytoplasm is granular. They are, however, dead, or at any rate moribund cells. Owing to the constant friction to which the




FIG. 18.—Vertical Section of Stratified Epithelium from the Mouth of a fœtal Cat, × 280. (From a photograph.)

der., dermis; epd., epidermis; s.m., Stratum Malpighii, or layer of actively dividing cells

surface of the body is exposed such cells are always being rubbed off, and it is these which, by accumulating in places where the friction is less severe, form the so-called scurf of the hair.




FIG. 19.—Section of Adipose Tissue from which the Fat has been dissolved out, leaving the thin-walled Cells empty and shrivelled, × 175. (From a photograph.)

As they are worn away their places are taken by other cells which arise from a deeply situated layer, at the lower limit of the

epidermis, in which cell-division goes on actively throughout life. In this way a many-layered or stratified epithelium is formed, as shown in Fig. 18, which represents a small portion of a thin vertical section through the epidermis (epd.) in the mouth of a fœtal cat. At the lower limit of the epithelium, resting immediately upon the connective tissue of the dermis (der.), is seen the layer of actively dividing cells (s.m.). The cells cut off from this layer are gradually pushed outwards, becoming flattened and scale-like as they approach the surface.

Fat, or adipose tissue, consists of an aggregation of more or




FIG. 20.—Section of Cartilage, showing the Cartilage Cells (c.c.) imbedded in the transparent intercellular Matrix or Ground Substance (m.), × 390. (From a photograph.)

less globular cells, swollen out by the accumulation within them of drops of oil. If the oil is dissolved out by suitable reagents the empty cells are left with their cell-walls or membranes in a somewhat shrivelled condition, as shown in Fig. 19, and the tissue now bears a curious resemblance, when seen in section, to vegetable parenchyma, such as is seen in sections of pith (compare Fig. 7).

Cartilage, or gristle, is one of the skeletal tissues, serving for the support of the body and the protection of special organs. In some of the lower vertebrates, such as the dog-fish, it forms practically the whole of the internal skeleton, but in higher forms

it is to a greater or less extent supplemented or even replaced by bone. It consists mainly of a tough, translucent matrix, or intercellular substance, which is formed as a secretion by the cartilage cells and in which the latter are imbedded at wide intervals (Fig. 20). In this respect it differs greatly from the epidermis, in which the cells lie close together and little or no intercellular substance is developed. The cartilage grows by repeated division of the cells which it contains and the secretion of additional intercellular matrix between them. The frequent arrangement of the nucleated cells in pairs, as shown in the illustration, is an indication of recent cell-division. Bone is a more complex tissue than cartilage and is further strengthened and hardened by the deposition of calcareous salts, chiefly phosphate of lime, in the matrix.




FIG. 21.—Unstriped Muscle Fibres from the Wall of the Rabbit's Intestine, × 300.

nu., nuclei.

Muscular tissue is specialized in a totally different direction from any of the foregoing. Its function is to contract, and by so doing to bring about the various movements of which the higher animals are capable. There are two very distinct kinds of muscular tissue, the one comparatively simple and the other much more complex in structure. The former, which is known as unstriped muscle (Fig. 21), consists of greatly elongated cells, the muscle-fibres, associated in sheets or bundles. Each has a centrally placed nucleus and its cellular nature is at once obvious. The wall of the alimentary canal, outside its lining epithelium, is composed chiefly of muscle-fibres of this kind. Their rhythmical and co-ordinated contraction causes the characteristic peristaltic movement whereby the onward passage of the food is secured. These and similar movements effected in other organs by the action of unstriped muscular tissue take place quite independently of the will—whence the term " involuntary " is often applied to this type of muscle.

Striped or striated muscular tissue is usually under the control of the will, and is hence often spoken of as " voluntary," but it is found in the higher animals wherever very sharp, precise movements are required, as for example in the walls of the heart, the

contraction of which serves to pump the blood through the blood-vessels. It is more especially associated, however, with the movements of the limbs, the bones of which form a system of levers operated by the muscles which are attached to them. It differs greatly in minute structure from unstriped muscle, though consisting essentially of greatly elongated, nucleated fibres endowed with remarkable powers of contraction. These fibres, and the fibrillæ into which they are subdivided, are characterized by a transverse striation of alternate light and dark bands. Their structure is very complex and in the fully developed muscle it is difficult if not impossible to recognize the limits




FIG. 22.—Striped Muscle-Fibres (m.) from the Tail of a larval Axolotl, showing their nuclei (n.), × 560. (From a photograph.)

between the constituent cells. Fig. 22 represents a number of striated muscle-fibres from the tail of a larval axolotl, in which each fibre is seen to be provided with several distinct nuclei.

The nervous system, as we have already pointed out, serves to place the different parts of the body in communication with one another and exercises a controlling and co-ordinating influence over the whole, while through the mediation of the special organs of sense it keeps the organism in close touch with its environment. The tissue of which it is composed (Fig. 23) consists of nerve-cells and nerve-fibres, but the fibres are merely outgrowths of the cells. A cell and fibre together form a neuron —a single unit of the nervous system. The nerve-cells, or rather their bodies, occur chiefly in the brain and spinal cord, which constitute the central nervous system, but also in small

local aggregations, or ganglia, in various parts of the body. The nerve-fibres extend outwards from the central nervous system in long, slender bundles, the nerves, which are distributed to the various organs.

The body of a nerve-cell contains the nucleus and is usually much branched into slender processes or dendrons (Fig. 24), which are quite distinct from the nerve-fibre and are supposed to afford the means of transmitting impulses between one nerve-cell and another, with the dendrons of which they interlace.



FIG. 23.—Nervous Tissue, as seen in a thin Section of the Brain (Medulla oblongata) of the Monk Fish. Two large nucleated Nerve Cells are shown imbedded in a Mass of smaller Cells and Fibres, × 168. (From a photograph.)

Like other highly specialized tissue-cells of the animal body the neurons have lost the power of multiplication by division. Moreover there appears to be no provision, in some adult vertebrates, for their renewal when worn out or injured. A certain number are formed in the course of the development of the embryo and these have to serve the animal for the whole of its life.

All the different kinds of cells met with in the body, a few of which have been thus briefly described, are derived from the apparently simple unicellular ovum by repeated subdivision and gradual differentiation. The functions which in an Amœba are all performed by a single protoplasmic unit are in one of the

higher animals distributed amongst thousands of millions of such units, arranged, so to speak, in regiments and armies, each group with its own duties to perform and all co-operating for the common good under the supervision and control of the central nervous system. The marvellous perfection of the whole machinery is the result of that differentiation and division of labour which was first rendered possible by the union and co-operation of the individuals of a protozoon family to form a multicellular body.




FIG. 24.—Diagram of a Neuron, (From Hertwig.)

Nervenfortsatz, a nerve-fibre coming off from the body of the cell.

Turning now to the higher plants, we shall find that, in accordance with their much lower degree of functional activity, their organization is far less elaborate than in the higher animals. In correlation with their stationary habit all those organs and tissues which are specially concerned with locomotion are absent, and in further correlation with this character there are no nervous system and no special organs of sense. Of the functions concerned with the life of the individual —that is, other than reproductive functions — that of nutrition is alone highly developed. The entire plant is little more than a piece of apparatus for extracting carbon, water and mineral salts from the air and soil, and converting these, with the aid of the sun's rays, into organic substances. Although the higher plants often attain a much larger size than any animals, this does not indicate a higher degree of organization, for it is brought about simply by the repetition of similar parts—such as roots, branches and leaves—and the accumulation of dead cell-walls in the form of wood and bark. As we have already seen, a green plant, instead of spending the energy which it derives from the sun on its own

activities, stores most of it up in the complex chemical compounds which it manufactures.

Nevertheless, though the degree of histological differentiation is not nearly so high as it is in the higher animals, we find in the higher plants also a considerable variety of cells and tissues, derived, as we have already pointed out, from the dermatogen, periblem and plerome of the embryo.

We may illustrate this point by a study of some of the cells and tissues which occur in the well-known spiderwort of our gardens, *Tradescantia virginica*. If we examine the flowers of this plant we shall find that the stamens are covered with long




FIG. 25.—Structure of a Hair from a Stamen of *Tradescantia virginica*.

A. End of a hair as seen under a low power of the microscope. The hair is made up of a single row of cells.

B. A single cell more highly magnified.

c.w. cell-wall; *nu.* nucleus; *p.u.* primordial utricle; *vac.* vacuole filled with coloured or colourless cell-sap.

slender hairs. It will be convenient to make these hairs the starting point of our inquiry. If we study them first under a low magnifying power we shall see that each hair (Fig. 25, A) is made up of a single row of cells, arranged like the beads in a necklace; most of the cells are elongated, but towards the apex of the hair they become short and spherical.

If we now concentrate our attention on one of the larger cells and study it carefully under a moderately high power of the microscope, we shall find that it exhibits the appearance shown in Fig. 25, B. It measures about 0·27 mm. in length by 0·08 mm. in breadth and consists of a thin-walled bag filled with living protoplasm. The wall (*c.w.*) is transparent and colourless and is composed, as in Hæmatococcus, of cellulose.

The granular, colourless protoplasm does not fill the interior of the cell in a uniform manner, but is arranged partly as a thin lining to the cell-wall, known as the primordial utricle (*p.u.*), and partly in irregular strings which branch and anastomose and stretch across the cavity of the cell in various directions. These strings of protoplasm tend to converge towards an irregular mass in which the nucleus is situated. The nucleus itself (*nu.*) is a nearly spherical body of denser protoplasm, about 0·024 mm. in diameter. The extensive space which lies inside the primordial utricle and between the strands of protoplasm is filled with a more fluid liquid known as the cell-sap. It is to this cell-sap that the flowers of Tradescantia owe their colour; if the flowers are blue the cell-sap will be found to be blue and if they are white it is because the cell-sap is colourless.

The most striking feature of the cell which we are examining still remains to be noticed. The protoplasm is in constant movement. This is at once evident from the characteristic streaming of the small granules which it contains. Both in the primordial utricle and in the network of threads a constant circulation is kept up, though not in a very definite manner, as the threads themselves are constantly undergoing slow changes in their arrangement. The arrows in Fig. 25, B indicate approximately the course taken by the streaming protoplasm at the time when the drawing was made.

The streaming of the protoplasm appears at first sight to be an essentially vital phenomenon, but it is probably merely the mechanical result of chemical and physical processes going on in the cell, such as the diffusion of various substances in solution from one cell to another, which must take place in the process of nutrition. If the cell is killed by the addition of alcohol the physical and chemical conditions are at once altered and the movement ceases; the protoplasm is coagulated and, if we are dealing with a cell containing coloured cell-sap, the nucleus absorbs the colouring matter with great avidity and becomes deeply stained, while the cytoplasm stains only very slightly or not at all. We are thus able to make the cell stain itself differentially, without the aid of any extraneous colouring matter, the cell-sap acting as what is termed a nuclear stain.

It will be necessary to restrict our further observations on Tradescantia to the structure of the leaf (Fig. 26). The leaves

of this plant are long and narrow, somewhat resembling those of grasses. There is a pronounced midrib and the so-called veins




FIG. 26.—Histology of the Leaf of *Tradescantia virginica*.

A. Part of a transverse section of the leaf.
B. Piece of the epidermis stripped from the lower surface of the leaf.
C. Chlorophyll cells from the mesophyll, as seen in a longitudinal section of the leaf.
D. Portions of four vessels from a vascular bundle, with spiral and annular markings, as seen in a longitudinal section of the bundle.

(All more or less highly magnified.)

a.c. air-cavity; *c.c.* chlorophyll cell; *cp.* chloroplastids; *ep.c.* epidermic cell; *epd.* epidermis; *g.c.* guard-cell; *mes.* mesophyll; *nu.* nucleus; *par.* colourless parenchyma; *sh.* sheath of vascular bundle, composed of thin-walled cells containing starch grains; *sk.* thick-walled skeletal tissue; *st.* stoma; *v.b.* vascular bundle; *ves.* vessels.

run parallel with one another from base to apex, as in all typical Monocotyledons.

If we cut a thin transverse section of a living leaf and examine it under the microscope in a drop of water (Fig. 26, A) we

shall see at once that it is made up of three principal tissue-systems, the epidermis, the mesophyll and the vascular bundles. The epidermis (*epd.*) covers the upper and lower surfaces in the form of two single layers of cells, the mesophyll (*mes.*) occupies the space between these two layers, and the vascular bundles (*v.b.*)—corresponding to the veins of the leaf—are imbedded in the mesophyll at fairly regular intervals (only one is shewn in the figure). We must examine each of these tissue-systems separately, and in order to gain a correct idea of the form and arrangement of the cells of which they are composed it will be necessary to study them from various points of view.

The epidermis may be stripped off bodily from the surface of the leaf and then exhibits under the microscope the appearance shown in Fig. 26, B. It is composed of elongated cells, placed side by side in a single layer. The amount of protoplasm which these cells contain is very small, but the nucleus (*nu.*) is frequently conspicuous. Their external walls are specially thickened in relation to their protective function, a feature which can only be seen in sections (Fig. 26, A). At frequent intervals little slit-like openings occur in the epidermis. These are the stomata (*st.*) which lead into air-spaces in the mesophyll. Each stoma is bounded by a pair of specially modified epidermic cells known as the guard-cells (*g.c.*)—the only epidermic cells containing chlorophyll—which have the power of opening and closing the stoma like a pair of lips and thus regulating the amount of aqueous vapour which passes through the stomata in the process of transpiration. On the outer side of each guard-cell lies another epidermic cell of much smaller size than the ordinary kind, and these, together with the guard-cells, form a kind of roof (or floor) to the air-cavity (Fig. 26, A, *a.c.*).

The mesophyll contains the chlorophyll-bearing cells, by which the assimilation of carbon dioxide is effected and which are at once recognized by their green colour. They appear more or less round or oval in transverse sections (Fig. 26, A, *c.c.*), but are really considerably elongated, parallel to the length of the leaf, as shown in Fig. 26, C. They come in contact with one another by numerous short protuberances, between which lie the spaces in which the air, containing carbon dioxide and aqueous vapour, circulates. Each contains a nucleus (*nu.*) and numerous small, biscuit-shaped green bodies, the chloroplastids or chlorophyll corpuscles (*cp.*), imbedded in the cytoplasm.

In certain places the green mesophyll cells are interrupted by groups of cells containing no chlorophyll. At intervals beneath the upper epidermis we see masses of large, thin-walled, colourless cells forming a parenchyma or ground-tissue (*par.*), while beneath the vascular bundles we find bands of very thick-walled cells (*sk.*) which play an important part in the mechanical support and strengthening of the leaf.

The vascular bundles are surrounded each by a sheath of thin-walled cells (*sh.*) containing numerous small starch grains. Within this lie the bast or phloem and the wood or xylem, composed of the elongated tubular elements through which the sap circulates. The raw sap consists of water with mineral salts in solution, and ascends through the xylem, while elaborated sap, containing the proteids which have been manufactured in the leaf by the anabolic processes, descends through the phloem.[1] For our present purposes we may confine our attention to certain of the xylem elements, known as the spiral and annular vessels. These consist really of dead cell-walls, forming long narrow tubes each composed originally of a row of cylindrical cells placed end to end. In the course of their development the transverse dividing walls between these cells are absorbed, the protoplasm disappears, and nothing remains but a long hollow tube whose walls are strengthened by spiral or annular thickenings. Portions of these vessels are represented separately in Fig. 26, D; in A they are seen only in transverse section (*ves.*).

Such are the principal kinds of tissue met with in a typical flowering plant, and such is the way in which it carries out the principles of co-operation, differentiation and division of labour amongst its constituent cells.

To most people it will probably appear that the fundamental truth and general applicability of the cell theory are sufficiently firmly established by considerations such as those with which we have been dealing. It has, however, certain undoubted limitations, and upon these limitations some biologists are inclined to lay a good deal of stress.

Thus, from the point of view of the cell theory, we regard the cell as the organic unit; there are, however, units of a lower order, of which the cell itself is composed. The chloroplastids of one of the higher plants, for example, exhibit a good deal of individuality, being capable of independent growth and multi-

[1] Recent research has thrown grave doubt on this view. The circulation of the sap is probably a far more complex process than was formerly supposed.

plication, while, as we shall see later on, it is necessary for theoretic reasons to postulate the existence of some such bodies as Profess Weismann's biophors as the primary units of which living protoplas is built up.

Then, again, although it may be questioned whether such u nucleated unicellular organisms as Haeckel's Monera really exis there can be no doubt that the most simply organized living thin visible to us, the Bacteria, which probably stand a long way belo the point where the animal and vegetable kingdoms part company and which are the most abundant of all living organisms, do not sho that sharp differentiation into cell body and nucleus which is s



FIG. 27.—*Bacillus saccobranchi.* Bacteria from the Blood of a Fish (*Sacc branchus*) stained so as to show the distribution of the chromati (nuclear) material, which is represented in black, and which may b arranged in small scattered granules throughout the cell, or in an irregul network, or in an irregular, more or less twisted rod, × 2000. (Aft Dobell in the "Quarterly Journal of Microscopical Science.")

characteristic of typical cells, the nuclear constituents being mor or less scattered throughout the cytoplasm (Fig. 27).

A difficulty of another kind is met with in the fact that in a good many cases the division of the nucleus is not followed—a any rate not immediately—by corresponding division of th cytoplasm. Some Amœbæ constantly have two nuclei, and we some times get relatively large masses of protoplasm containing man nuclei formed by repeated division. These are termed syncytia We meet, in fact, with all degrees of separation of the cytoplasm into distinct cells, and a great many of the cells even of highl developed plants and animals may remain connected togethe throughout life by thin strands of protoplasm. We have alread noticed an example of this continuity of the protoplasm in th

case of Volvox; another is shown in Fig. 28, B, which represents a syncytial epithelium.

On the other hand, in some of the lower organisms—the Myxomycetes, slime-fungi or Mycetozoa, as they are variously called—numerous originally separate Amœba-like individuals may fuse together to form plasmodia, which may continue to feed and grow and undergo nuclear division until they form great sheets of living protoplasm containing perhaps hundreds or thousands of nuclei (Fig. 29). These and similar facts, however, interesting and instructive as they undoubtedly are, cannot be regarded as constituting a serious invalidation of the cell theory.




FIG. 28.

A. A single-layered epithelium with very distinct cell-outlines, from the brain of a reptile (*Sphenodon punctatus*), × 750.

B. A syncytial epithelium, without cell-outlines, from another part of the brain of the same animal × 750.

nu. nuclei.

There is no more fundamental or more stimulating conception in the domain of biological science than that of the continuity of life as formulated by this theory. We have to imagine the whole organic world as consisting of a continuous stream of living protoplasm, which commenced to flow many millions of years ago and has continued without interruption ever since. At every cell-division the stream branches and physical continuity is more or less completely interrupted, but this in no way invalidates the conclusion that if all living things did not actually have a common origin in a single primordial protoplasmic unit (far less complex than a nucleated cell), they at least originated from a number of such units which themselves arose under unknown conditions from inorganic matter.

The modern science of cytology, which is contrasted with histology as the study of individual cells rather than that of tissues or cell combinations, and which is yielding such important

results both for pure biology and for medical science, owes its origin and development entirely to the elaboration of the cell



FIG. 29.—Part of the Plasmodium of a Mycetozoon (*Badhamia utricularis*) × 50. (From a photograph.)

The small dark spots are the very numerous nuclei.

theory under the influence of improved methods of microscopical investigation.

There is another point of view with regard to the living cell which we may briefly refer to in this place. It is not only the morphological or structural unit of the body but also the physiological or functional unit. All the essential vital processes take place within the bodies of cells, and all the different materials required for and produced by these processes pass in and out of them. Each cell may be looked upon as a microscopic laboratory in which the complex chemical reactions comprised under the term metabolism take place, and although, in the higher organisms, the cells have become mutually dependent upon one another, yet each retains a certain degree of physiological as well as of morphological individuality.

CHAPTER VI

The multiplication of cells—Mitotic and amitotic nuclear division

We have already seen that the possibilities of structural differentiation within the limits of the individual cell are by no means exhausted by the distinction between cytoplasm and nucleus, but it is only when we come to study in detail the process of cell division that we begin to gain any adequate conception of the fundamental complexity of the organic unit. We have hitherto spoken of this process, as it occurs for example in Amœba, as though it were a simple matter, initiated by constriction of the nucleus into two parts and concluded by a corresponding division of the cytoplasm. The researches of the last fifty years, however, rendered possible by the improvements in microscopical apparatus and micro-chemical technique, have taught us that in the vast majority of cases the process of cell-division is one of extreme complexity, accompanied by remarkable phenomena which reveal a previously unsuspected degree of structural differentiation within the nucleus itself. To these phenomena Schleicher in 1878 gave the name karyokinesis, for which Flemming, in 1882, proposed to substitute mitosis. Both these terms are still in common use.

In a typical cell (Fig. 30) the cytoplasm (*cyt.*) is a semi-liquid substance usually enclosed in a thin cell-membrane (animal cells) or a thicker cell-wall (plant cells). It exhibits a microscopic structure which is variously interpreted as reticular (fibrillar), alveolar (foam-like), or simply granular, the probability being that the real truth is expressed by a combination of these different views. It may or may not contain plastids of various kinds (*e.g.* chloroplastids in green plants).

The nucleus (*nu.*), consisting of the so-called nucleoplasm or karyoplasm, is usually a spherical, more or less centrally situated body enclosed in a definite nuclear membrane (*n.m.*). Within this membrane the karyoplasm is differentiated into various constituents. In the first place there is a network or reticulum of

delicate protoplasmic threads, known as the linin network, th meshes of which are filled with a clear, probably liquid ground substance known as nuclear sap. These two together seem t differ but little from the cytoplasm which lies outside th nucleus.

The most characteristic constituent of the nucleus is anothe substance, to which, on account of the readiness with which i becomes coloured by certain dyes, the name chromatin[1] has bee given. This substance usually occurs in the form of smal granules (*ch.g.*) scattered over the linin network, so that whe very close together they appear to form a chromatin network




FIG. 30.—Diagram of a typical Cell.

ch g., chromatin granules; *c.m.*, cell-membrane; *c.s.*, centrosomes lying in centrosphere *cyt.*, cytoplasm; *n.m.*, nuclear membrane; *nu.*, nucleus; *nucl*, nucleolus.

while not infrequently a specially large aggregation of chromatin substance forms a nucleolus or karyosome (*nucl.*).

Owing to the presence of this chromatin the nucleus as a whole under low powers of the microscope, appears to be deeply coloured by such stains as various preparations of logwood and carmine and the basic aniline dyes. We have already had occasion to observe this staining property in the case of the hair-cells of Tradescantia, where, it will be remembered, the nucleus becomes deeply stained by the coloured cell-sap as soon as the cells are killed by the action of alcohol. Other stains, again, affect the cytoplasm rather than the nucleus, and these various staining reactions enable us to differentiate fairly sharply between the different constituents of which the cell is composed, though it is a matter of some doubt exactly how far the structure of the

[1] Greek χρῶμα, a colour.

living protoplasm really corresponds to the appearances exhibited in our preparations.

The differences in their staining reactions of course indicate corresponding differences in chemical composition between the chromatin and the cytoplasm, and analysis has shown that the chromatin is characterized by the presence of relatively large quantities of phosphorus. This is contained in the complex nucleinic acid, with which various albuminous bodies may be combined to form the chromatin substance.

When a typical animal cell is about to divide another structure makes it appearance, usually just outside but occasionally inside the nucleus. This is the centrosome (Fig. 30, *c.s.*), a very minute body which has peculiar staining properties and which is surrounded by a differentiated area ot protoplasm known as the centrosphere or attraction sphere (Fig. 31, A, *csph*). It has been questioned whether a centrosome and attraction sphere are always present or whether they make their appearance only when the nucleus is about to undergo mitosis. This process certainly seems to be initiated by the centrosome, which may divide into two parts long before the nucleus itself commences to do so, so that two centrosomes often appear alongside the so-called resting nucleus (Figs. 30; 31, A). Presently the two centrosomes move away from one another, both still keeping close to the nucleus, and each is now seen to be surrounded by its own attraction sphere (Fig. 31, B). Around each attraction sphere delicate threads or fibrillæ of the cytoplasm become radially arranged to form a star or aster, and the rays of the asters which lie between the two centrospheres combine to form a spindle (Fig. 31, C, *ksp*).

In the meantime remarkable changes have commenced in the nucleus itself. The chromatin granules, together with the linin by which they are apparently held together, have arranged themselves in the form of a long coiled thread, the spireme (Fig. 31, B), and presently the nuclear membrane begins to disappear (Fig. 31, C, *km*), being apparently dissolved in the general protoplasm. In this way the distinction between cytoplasm and nucleoplasm is obliterated.

The spireme thread breaks up into a number of short lengths known as chromosomes (Fig. 31, C, *chrs*), the actual number being, with certain exceptions, a constant character for each species of plant or animal. The centrosomes at about this

time take up their positions at points corresponding to two opposite poles of the original nucleus, with the spindle of fine




FIG. 31.—Diagram of the principal Stages in the mitotic Division of the Nucleus in a typical Animal Cell. (From Weismann's "Evolution Theory," adapted from E. B. Wilson.)

aeq, equatorial plate; *chr*, chromatin; *chrs*, chromosomes; *cs*, centrosome; *csph*, centrosphere, containing one or two centrosomes; *kk*, nucleolus; *km*, nuclear membrane; *kn*, nucleus; *ksp*, *sp*, nuclear spindle; *p*, aster; *tk*, daughter nucleus; *tz*, daughter cell; *zk*, cytoplasm, forming the cell body.

protoplasmic fibres stretched between them (Fig. 31, D), and the chromosomes "go on the spindle," arranging themselves in a so-called equatorial plate across its widest part (Fig. 31, D, *aeq*).

The shape of the chromosomes varies much in different cases; they may be more or less spherical, but they are frequently short, rod-like bodies, often shaped like a V (Fig. 32, A). Each one is composed, like the spireme thread from which they are derived, of an aggregation of chromatin granules, held together by a linin basis. The chromatin granules are sometimes arranged like the beads on a necklace (Fig. 32, B), and are also known as chromomeres. The number of the chromosomes also varies greatly, from as low as two in a variety of the horse-worm (Ascaris) to as many as one hundred and sixty-eight in the shrimp Artemia. In cases where the chromosomes are very small each one may perhaps be equivalent to only a single chromomere.

Either before or after taking up its position in the equatorial




FIG. 32.—Sperm-mother-cells of a Salamander, during Mitosis. In *A* the chromosomes are shown; in *B* the spireme thread is split lengthwise, and also shows very clearly the chromomeres of which it is made up. (From Weismann's "Evolution Theory," after Hermann and Drüner.)

c, dividing centrosome; *chr*, chromosomes; *Jd*, chromomeres; *zk*, cytoplasm.

plate, each chromosome splits longitudinally into two parts (Fig. 31, D), in fact the splitting can sometimes be observed in the spireme thread even before it breaks up transversely into chromosomes (Fig. 32, B). The result of this splitting is that the number of chromosomes is doubled; but the daughter chromosomes very soon separate into two equal groups, one of which moves towards each centrosome (Fig. 31, E). Each group contains one of the two halves of each parent chromosome.

Having migrated to opposite poles of the spindle the two groups of daughter chromosomes there form the foundations of two new nuclei (Fig. 31, F). The chromosomes break up into granules again; a new nuclear membrane is formed, whereby a portion of the general cytoplasm is separated off to form the linin network and ground-substance of the nucleus; the asters and nuclear

spindle more or less completely disappear—though the centrosome may certainly persist in some cases if not in all—and the newly constituted nucleus (Fig. 31, G, *tk*) enters upon a longer or shorter period of inactivity accompanied by growth.

In the meantime the cytoplasm which constitutes the cell-body has also divided into two parts in a plane which passes through the middle of the nuclear spindle and at right angles to its length. In animal cells this division is usually effected by a constriction which starts from the outside (Fig. 31, F, G) and in plant cells by the deposition of a cell-plate (Fig. 34, E, *c.p.*) in the equator of the nuclear spindle. This cell-plate forms the foundation of the double cell-wall which will separate the two daughter cells; it must not, of course, be confounded with the equatorial plate formed temporarily by the chromosomes.

Various attempts have been made to explain the dynamics of this remarkable process of mitosis or karyokinesis, the essential features of which are always much the same though the details vary considerably in different cases. The centrosomes, with their centrospheres, asters and spindle, sometimes spoken of collectively as the achromatic figure, are usually regarded as a special mechanism for bringing about the equitable partition of the chromatin substance between the two daughter nuclei. This substance is evidently so important that no rough and ready division will suffice. It is probable, as we shall see later on, that the chromomeres of which each chromosome is composed have different properties, and that it is necessary, in ordinary cell-division, not only that the chromosome as a whole shall be divided into two parts but that each daughter nucleus shall have its share of each individual chromomere. In other words a qualitative as well as a quantitative division of the chromatin material has to be effected, and this is secured by the longitudinal splitting of the chromosomes. A transverse division would only result in the separation of the chromomeres into two groups, but the longitudinal division involves each one.

According to some observers the fibres of the nuclear spindle are actively contractile and actually pull the two halves of each split chromosome asunder. Others maintain that the centrosomes attract the chromosomes in somewhat the same way as the poles of a horse-shoe magnet attract iron filings sprinkled between them.

Of late years the electro-magnetic explanation has been coming

more prominently to the front. Thus Gallardo has suggested that the chromatin substance is charged with negative and the cytoplasmic colloids with positive electricity, while the centrosomes are capable of acquiring a positive potential higher than that of the general cytoplasm. Increase of this potential causes the centrosome to divide and the radiations which form the asters and spindle indicate lines of force in the cytoplasm. The two daughter centrosomes, inasmuch as they bear like charges of electricity, repel one another. In a similar way the chromosomes divide under the influence of their high negative charges and the two halves of each repel one another and are at the same time attracted by the positive centrosomes. The two new groups of negatively charged chromosomes then attract the positive cytoplasm in opposite directions and thus the division of the cell body follows upon that of the nucleus.

Whatever may be the physical explanation of these complex phenomena, we must think of them as lying at the root of all normal processes of growth and multiplication in the higher plants and animals. With comparatively rare exceptions, some of which will be mentioned later on, every one of the innumerable series of cell-divisions initiated by the fertilized ovum, and continued throughout life in the growth and repair of tissues, is accompanied by complicated processes similar to those above described. The process of cell-multiplication, however, is frequently confined in adult organisms to certain regions. Thus, as we have already seen, in the higher animals the growth of the epidermis depends upon cell-divisions which go on only in its deepest layer, the stratum Malpighii (Fig. 18, s.m.). Most of the cells in the body sooner or later lose the power of division, but they are then usually short-lived, as in the case of those cells which form the outer layers of the epidermis and which rapidly become converted into more or less horny scales to be cast off on reaching the surface.

The majority of the tissues are thus renewed throughout life by the mitotic activity of some unspecialized cell-group, a high degree of specialization in the tissue cells of the higher organisms being always, as we have already seen in the case of red blood corpuscles and nerve cells, accompanied by the loss of the power of multiplication.

The limitation of cell-multiplication to definite circumscribed regions of the body is perhaps best seen in the case of the higher

plants, where the various meristematic or actively dividing tissues remain in an undifferentiated embryonic condition and give rise to those additions to the permanent tissues whereby growth is effected. Such actively dividing meristem is found at the growing points of stems and roots, where it serves to bring about growth in length, and in the cambium, which serves, by the addition of new elements to the wood and the bast, to bring about growth in thickness.

The microscopic appearance of such a meristematic tissue,




FIG. 33.—Part of a longitudinal Section of the actively growing Root of a Hyacinth (*Galtonia candicans*) showing the Nuclei of the Cells in various stages of mitotic Division, A × 280; B × 640. (From photographs.)

when suitably stained and prepared for examination, is shown in Fig. 33, taken from photographs of part of a longitudinal section of the growing point of the root of a hyacinth (*Galtonia candicans*). The cell-walls are as yet thin and inconspicuous and filled with dense protoplasm, while the conspicuous nuclei exhibit all stages of mitosis, the whole forming a striking contrast to the dead tissues, such as cork and wood, of which the bulk of many plants is made up, and which consists merely of cell-walls without any protoplasmic contents (*cf.* Figs. 6 and 7).

Mitosis in the cells of the higher plants is usually, though by

no means always, characterized by the absence of recognizable centrosomes. The actual appearance of some of the principal stages in the process is shown more highly magnified in Fig. 34,




FIG. 34.—Six selected Stages in the mitotic Division of the Nucleus in the growing Root of *Galtonia candicans*, × 1120. (From photographs.)

A. Resting nucleus with large nucleolus (*Nuls.*).
B. Spireme stage, with coiled chromatin thread.
C. The spireme thread has broken up into chromosomes which are forming the equatorial plate.
D. The chromosomes have split longitudinally and the two groups of daughter chromosomes thus formed are passing to opposite poles of the spindle.
E. Formation of the cell-plate (*c.p.*) across the equator of the nuclear spindle.
F. Completion of the cell-division, and disappearance of the individual chromosomes in the daughter nuclei.

which represents a series of six selected stages arranged in proper sequence, reproduced from photo-micrographs.

Fig. 34, A represents the so-called resting stage of the nucleus, in which it will be noticed that there is, in addition to the minute, scattered chromatin granules, a large spherical chromatin nucleolus or karyosome (*Nuls.*). B shows the spireme

stage, with the chromatin granules collected together in a long spirally coiled thread and the nucleolus still very conspicuous. C shows the group of chromosomes formed by transverse breaking




FIG. 35.—Mitosis in the segmenting Egg of the Horse-Worm (*Ascaris megalocephala*), × 770. (From photographs.)

A. Lateral view of the egg during the first cleavage; showing the nuclear spindle (*sp.*), the equatorial plate (*aeq.*), one of the two centrosomes (*c.s.*), the other being out of focus, and the asters (*as.*) formed by fine threads of protoplasm radiating from around the centrosomes. Polar bodies (*p.b.*) are also shown.

B. The same stage viewed from one pole, showing the four V-shaped chromosomes (*chr.*) in the equatorial plate.

C. The first division is completed and the nuclei have again passed into the spireme stage. A polar body (*p.b.*) is still visible.

D. Each of the first two blastomeres has again reached the stage represented in A and B.

up of the spireme thread. The karyosome has now disappeared, having apparently been used up in the formation of the chromosomes. D shows the two groups of daughter chromosomes formed by longitudinal splitting of the parent chromosomes and retreating towards the two ends of the spindle, which is only

faintly visible. E shows the commencement of the cell-plate (*c.p.*) across the middle of the spindle, and F the two young daughter cells each with a new nucleus in which the chromosomes have again broken up into granules.

It is only by the examination of large numbers of examples that all the minute details of the process can be elucidated, but the main features as represented in the above figures can very easily be made out.

For comparison with the process of mitosis as seen in typical plants such as Galtonia, we may take the first division of the fertilized egg in the horse-worm, Ascaris, a classical subject from the study of which much of our knowledge of nuclear division in animal cells has been derived. In this case there are only four chromosomes, but they are large and conspicuous, and characteristically V-shaped when forming the equatorial plate on the spindle.

Fig. 35 is again taken from actual photographs. In this figure, A represents a side view of the entire egg-cell during the division of the nucleus, with spindle (*sp.*), asters (*as.*), centrosomes (one only of which, *cs.*, appears in the photograph, the other being out of focus), and equatorial plate (*aeq.*). B shows a similar stage viewed from one pole, so that the spindle itself does not appear, but the four chromosomes forming the equatorial plate are distinctly visible. C shows the two daughter cells or blastomeres resulting from the first division of the egg, each with the nucleus preparing for further division, and D represents a later stage in which the nucleus of each daughter cell is again actually in process of division and shows the separate chromosomes very distinctly.

It must not be supposed that the phenomena of mitosis are by any means confined to the higher animals and plants; they are observable throughout the animal and vegetable kingdoms, in unicellular as well as multicellular forms. The process has long been known to take place, for example, in at any rate some Amœbæ, and it usually occurs wherever there is a clearly differentiated nucleus. The Bacteria and their allies, in which the chromatin granules are scattered throughout the cell body and there is no proper differentiation into cytoplasm and nucleus, apparently form exceptions to the general rule.

There are, however, even amongst the higher animals, some cases of cell-division which do not exhibit mitotic phenomena, but in

which the nucleus appears simply to constrict into two or more parts (Fig. 36). This is known as direct or amitotic nuclear division. It is frequently met with in degenerating cells and pathological tissues, but it is doubtful if it ever occurs (in the higher organisms at any rate) in cells which are destined to undergo long-continued multiplication. We may therefore regard it as a more or less abnormal process with which we have no need to concern ourselves any further. The phenomena of mitosis, on the other hand, are thoroughly normal and practically universal, and, as we shall see later on, they are of the deepest significance from the point of view of the theories of heredity and variation.



FIG. 36.—Amitotic nuclear Division as seen in Cells from the Cavity of the Paraphysis in Sphenodon, × 1000.

nu. nuclei.

PART II.—THE EVOLUTION OF SEX

CHAPTER VII

Limitation of the powers of cell-division—Rejuvenescence by conjugation of gametes—The origin of sex in the Protista.

By the process of cell-division an unbroken continuity has been established in the chain of living things from the earliest appearance of unicellular organisms to the present day. Every cell is the descendant of pre-existing cells and, in accordance with the theory of evolution, all cells which exist to-day, distributed amongst the bodies of countless millions of different organisms, could, if our knowledge were sufficiently complete, be traced back to a single ancestral cell.

It by no means follows from these considerations, however, that there is, under natural conditions, no limit to the ordinary process of cell-division. On the contrary it is well known that in any cell family, whether belonging to a unicellular or a multicellular organism, the power of multiplication tends to become exhausted, and, if that particular cell family is to continue its existence, has to be in some way renewed.

Take, for example, an ordinary ciliate or flagellate Protozoon, which multiplies by simple fission. If a single individual be isolated and placed in water containing suitable food material, and kept under suitable conditions of temperature, light and so forth, it will multiply very rapidly, until possibly hundreds of generations of separate cells have been produced and the total number increased perhaps to millions. But under ordinary circumstances a time may arrive when the individuals begin to show signs of exhaustion, accompanied by physical degeneration, and to slack off in their rate of multiplication. They may be stimulated to renewed activity for a time by special feeding or by constantly varying the culture medium,[1] but in a

[1] Mr. L. L. Woodruff has kept a culture of Paramœcium under observation for five years (to May, 1912), taking precautions to prevent the possibility of conjugation, but constantly varying the culture medium. During this time more than

state of nature the chief if not the only means by which the family can be kept from ultimate extinction is conjugation, the




FIG. 37.—Life History of Copromonas. (From Bourne's "Comparative Anatomy," after Dobell.)

cv., contractile vacuole; *cph.*, cell pharynx; *cst.*, cell mouth; *fv.*, food vacuole *N.*, nucleus; *R.*, reservoir; *tr.*, flagellum. (For further explanation see text.)

exhausted individuals approaching one another and finally uniting in pairs. In this way they appear to become rejuvenated and

average of about one division every fifteen hours—and at the end of the period the organisms were still in a perfectly normal condition.

their failing powers of multiplication by cell-division are completely restored.

For the purpose of studying this process of conjugation in its primitive simplicity we can hardly do better than take the minute flagellate form Copromonas, which is found in water frequented by frogs, from the excrement of which it derives its nutriment. The adult organism (Fig. 37, A) consists of a very minute ovoid mass of protoplasm with a single flagellum (*tr.*) springing from the narrow end. Alongside the base of the flagellum is a definite cell mouth (cytostome, *cst.*) through which solid particles of food are taken into the interior of the body. Close to this there is a contractile vacuole (*cv.*), accompanied by a "reservoir" (*R*) into which it discharges. The nucleus (*N*) is situated nearer to the broadly rounded hinder end of the body, which may also contain a number of food-vacuoles (*fv.*).

If the food supply be abundant the individual Copromonas will grow and presently divide into two by simple longitudinal fission, which commences at the narrow anterior end (Fig. 37, B—D). The division of the nucleus is said to be amitotic. The two daughter cells separate, feed, grow and repeat the process, and in this way a whole swarm of monads is produced. In the course of a few days, however, they appear to become exhausted and conjugation sets in, the individuals uniting in pairs (Fig. 37, 2—5). The result of each such union is a single larger individual, which may either undergo a period of rest within the protection of a special envelope or cyst (Fig. 37, 7), or at once assume the ordinary form and begin to multiply with renewed activity (Fig. 37, *V*). For the continued existence of the species it is probably necessary that the encysted monads should at some time or another be swallowed by frogs and passed out again in the fæces, in order that they may be brought in touch with the necessary food supply.

We have here, as in the case of Hæmatococcus described in Chapter III., a perfectly typical example of conjugation[1] occurring at longer or shorter intervals in the life cycle of the organism. The whole process consists in the union of two separate cells, known in this connection as gametes, to form a single cell known as the zygote, and it is of the utmost importance to observe that not only is there a union between the cytoplasm of the two gametes but the nuclei also unite to form a single zygote nucleus. Indeed,

[1] Also known as syngamy or zygosis.

as we shall see later on, it is the union of the nuclei which is the really important part of the business, for in some cases (*e.g.*, Paramœcium) the union of the two cell bodies is a merely temporary affair, a necessary preliminary to an exchange and subsequent union of nuclei.

In such simple cases as that of Copromonas we see all the essential features of the sexual process which occurs so constantly throughout the animal and vegetable kingdoms. It is evident that in itself conjugation is not a process of reproduction, for its immediate result is to halve the total number of cells instead of doubling it. It has in fact exactly the opposite effect to that of cell-division. It is a process which appears to be necessary for the rejuvenescence, at longer or shorter intervals, of exhausted cells, whereby they are endowed with renewed powers of multiplication by ordinary cell-division. At the same time it forms the starting point of all those remarkable structural modifications of the organism, whether unicellular or multicellular, which accompany the evolution of sex.

In Copromonas and in Hæmatococcus, although there is a true sexual process, there is apparently no sexual differentiation at all; there is no distinction between male and female gametes; the two conjugating cells are exactly alike, and the conjugation is therefore said to be isogamous. In Copromonas, moreover, the gametes or sexual cells are indistinguishable from the ordinary individuals, every individual being at least a potential gamete. Starting from such a case as this we find, even amongst the unicellular plants and animals, every stage in the evolution of highly specialized male and female gametes, differing widely from the ordinary individuals and from each other. Conjugation will then take place between two dissimilar gametes, and is said to be anisogamous.

The first hint, so to speak, of sexual differentiation is to be observed in the behaviour of the conjugating gametes; it is a physiological rather than a structural or morphological phenomenon, and consists in the fact that one gamete is active while the other remains comparatively passive. We shall find that this distinction lies at the root of all sexual differentiation throughout the animal and vegetable kingdoms. The more active gamete is spoken of as male and the more passive as female. The passivity of the female is intimately associated with and probably to a large extent dependent upon the fact that it contains more

cytoplasm and is therefore more heavily weighted than the male gamete. This cytoplasm, moreover, is in many cases densely charged with food material, which constitutes the capital with which the zygote, formed by the union of the two gametes, has to begin its new life cycle.

It is quite clear that the primary distinction between the sexes is a simple case of division of labour accompanied by a corresponding structural differentiation. Two ends have to be secured by the gametes. They must come together in order that they may conjugate, and therefore one or both must be capable of active locomotion. They must also contain between them sufficient material, either in the form of actual protoplasm or of some substance that can easily be worked up into protoplasm, to give the new individual which results from their union a fair start in life.

A cell body heavily weighted with food material is, however, clearly incompatible with great activity, so one of the two gametes remains unencumbered and becomes specialized as the active partner, charged with the duty of seeking out its mate and bringing about their union, while the other, more or less burdened with the necessary supplies, passively awaits the event. The conjugation of such differentiated gametes leads to a more satisfactory result than can be attained in cases of isogamy like that of Copromonas, for the new individual will have a better chance in life owing to the greater amount of capital with which it commences. Such sexual differentiation of the gametes finds its most complete expression in the formation of female ova and male spermatozoa, which are especially characteristic of the higher animals (compare Fig. 69), though they also occur in many plants and even in some unicellular forms. The process of conjugation in such a case is often spoken of as the fertilization of the ovum by the spermatozoon.

These considerations enable us to understand at once the great difference in size which usually distinguishes the male from the female gamete, whence the general terms microgametes and megagametes so often applied to them. The microgamete is as small as possible in order that its activity may not be impaired; the megagamete is swollen out with nutrient material.

We may illustrate these general principles by a brief description of a few more cases of conjugation amongst unicellular organisms.

Bodo, or Heteromita (Fig. 38), is a very minute flagellate monad




FIG. 38.—Life History of Bodo, or the Springing Monad, very highly magnified. (From Dallinger and Drysdale.)

A. Ordinary individual.
B., C. Multiplication by longitudinal fission (the nucleus divides and the cell body and both flagella split lengthwise).
D—F. Multiplication by transverse fission (the nucleus and cell body divide, the trailing flagellum splits lengthwise and a new anterior flagellum is budded out at one end).
G. Two gametes about to conjugate.
H. Conjugation.
J. Zygote formed by conjugation, with flagella still attached.
K. Fully formed zygote.
L. Escape of spores by rupture of the zygote wall.
M. Development of the spores.
a.f., anterior flagellum; *a'.f'.*, new anterior flagellum sprouting out; *nu.*, nucleus;

which occurs in long-standing infusions of cod's head. It differs from Copromonas chiefly in the possession of two flagella and in the absence of a cell mouth, all its food being taken in in a state of solution by diffusion through the thin cell membrane. The two flagella both spring from the beak-like anterior extremity. One (A, *a.f.*) extends forwards and by its movements enables the organism to swim actively about, the other (A, *t.f.*) hangs down and is trailed behind during active locomotion. The monad anchors itself by the trailing flagellum and then, by coiling and uncoiling the latter, executes characteristic springing movements. Ordinary multiplication, not preceded by any sexual process, is effected by simple fission, which may be either longitudinal (B, C) or transverse (D—F).

There are no structurally differentiated gametes or sexual cells, but conjugation (G—J) is effected between two apparently similar individuals which are indistinguishable from the ordinary form. It is noteworthy, however, that one of the two gametes at the time of union is anchored, while the other swims actively up to it, and thus we get a slight indication of physiological differentiation into active and passive, or male and female. The male gamete also arises by a somewhat peculiar method of fission. Conjugation of the two gametes produces a zygote which has somewhat the shape of a triangular sac (K). The flagella disappear and in the interior of the sac cell-division goes on with great rapidity, giving rise to an immense number of very minute spores, which ultimately escape from the corners of the sac in the form of very fine dust (L, *sp.*). Each spore no doubt is a minute nucleated cell, but it is so small that the nucleus cannot at first be made out. It grows by absorbing liquid food from the infusion in which it lives, and as it grows the nucleus becomes apparent, flagella are put forth, and the adult form is gradually attained (M). We have here a striking illustration of the fact that the most obvious result of conjugation is an increase of the power of cell-division.

As a case of complete morphological as well as physiological differentiation between male and female gametes in a unicellular organism we may take that of *Coccidium schubergi*, which occurs as a parasite in the intestine of a centipede (*Lithobius forficatus*). The life history of this remarkable protozoon is very complicated and it is not necessary for our purposes to describe it in detail. The adult organisms occur in the form of spherical nucleated cells, each actually inside one of the epithelial cells

which line the intestine of the host and upon which the parasites feed (Fig. 39, A.). The latter increase in number very rapidly by a kind of multiple fission, and successive generations of parasites attack fresh epithelial cells of the host until the epithelium is more or less completely destroyed. After many generations have been produced asexually in this manner a sexual process sets in. Megagametes and microgametes are produced; the former by growth of an ordinary individual into a large spherical ovum, or egg-cell (Fig. 39, B., ♀ *gam.*), the latter by growth and division of an ordinary individual into a number




FIG. 39.—*Coccidium schubergi*, highly magnified. (After Schaudinn.)

A. A full grown Coccidium lying within an epithelial cell of the host.
B Male and female gametes about to conjugate.
coc, the Coccidium; *c.r.*, the cone of reception put out by the female gamete; *nu.*, nucleus of female gamete; *nu.coc.*, nucleus of adult Coccidium; *nu.ep.*, nucleus of epithelial cell of host; ♂ *gam.*, male gamete or spermatozoon; ♀ *gam.*, female gamete or ovum.

of very much smaller spermatozoa or sperm cells (Fig. 39, B., ♂ *gam.*).

The ovum is densely filled with food granules and has no power of locomotion. The spermatozoon closely resembles a flagellate monad, being provided with a pair of flagella by means of which it swims actively about; the body, however, is long and slender and consists almost entirely of nuclear (chromatin) material. It seeks out the ovum, which exercises a peculiar attraction upon it, and the two conjugate, the spermatozoon boring its way into the ovum and their nuclei fusing to form the zygote nucleus. The only trace of activity, apart from nuclear phenomena, which the ovum exhibits is the protrusion of a small "cone of reception" (Fig. 39, B. *c.r.*) from the surface of the cell towards the approaching spermatozoon, which seems to indicate that the

attraction is mutual. The process of conjugation is followed as usual by cell-division on the part of the zygote, which in this case results in the formation of a small number of comparatively large spores, enclosed in tough protective envelopes. From these spores new individuals are produced which, under favourable circumstances, commence the life cycle afresh. It is extremely interesting to observe that we have here, in a unicellular Protozoon, as complete a sexual differentiation of the gametes as we meet with in any of even the most highly organized plants and animals.

We must now briefly notice the sexual phenomena exhibited by those interesting Protista which we have already had occasion to refer to in Chapter IV. under the name Phytoflagellata. It will be remembered that in Hæmatococcus (Fig. 5) the process of simple fission sometimes results in the production of a relatively large number (32—64) of small individuals instead of the usual four comparatively large ones. These small individuals are specialized gametes, differing from the large ones not only as regards size but also in the absence of the characteristic cell-wall of the latter. There is, however, no differentiation into male and female. Conjugation is of the isogamous type and produces a zygote which grows into an ordinary resting cell which will presently begin to multiply actively by ordinary fission.

We have also seen that this organism forms the starting point of a series of forms, represented by the genera Hæmatococcus, Pandorina, Eudorina and Volvox, which illustrate progressive stages in the process of colony formation. The same series also shows us very clearly the differentiation between male and female gametes—the origin of sex in the vegetable kingdom. It will be remembered that Pandorina forms colonies of sixteen or thirty-two cells enclosed in a common envelope (Fig. 10, A). Asexual reproduction is effected by each cell of the colony dividing into 2, 4, 8, and finally 16 or 32, which form a daughter colony within the parent, to be liberated presently by softening of the parental envelope. Occasionally, however, the individual cells of a colony divide each into eight gametes. These are small cells, each with a pair of flagella, which escape and swim about separately. They exhibit no clear distinction into male and female, but some are comparatively large, some small, and some intermediate in size. They conjugate in pairs (Fig. 10, B), and the two members of a conjugating pair are often, though apparently not always, of

different sizes. It is probable that we have here a kind of foreshadowing of that sharp differentiation into large (female)




FIG. 40.—Sexual Differentiation in Eudorina, highly magnified. (From Gœbel.)
I. A female colony, containing female gametes or ova and surrounded by male gametes or spermatozoa, some of which have already penetrated its gelatinous matrix.
II. Mother cell of a male colony.
III.—VI. Division of the mother cell into the spermatozoa of which the male colony is composed.
M_1, the fully developed male colony.

megagametes and small (male) microgametes of which we have already spoken.

In Eudorina, which forms colonies somewhat similar to those of Pandorina, this differentiation is already fully expressed (Fig. 40). The megagametes or ova[1] differ scarcely at all from ordinary

[1] Often termed by botanists oospheres.

individuals. They are shown imbedded in the gelatinous matrix of the large colony on the left of the figure. The microgametes or spermatozoa,[1] on the other hand, are much smaller, club-shaped bodies, having a characteristic yellowish colour and with a pair of flagella at the narrow, pointed end (Fig. 40, M_3). They are produced in bundles of sixty-four by repeated division of a mother cell (Fig. 40, II—VI). Thus the male and female gametes, spermatozoa and ova, do not occur together in the same colony, but the colonies, when they consist of gametes and not of ordinary individuals, contain only one or the other kind. Hence the sexual differentiation is in this case extended from the gametes themselves to the colonies which bear them, and we may recognize colonies of three kinds: (1) Asexual, which produce no gametes and reproduce by ordinary fission of all or any of the component cells, (2) male sexual, which produce microgametes or spermatozoa, and (3) female sexual, which produce megagametes or ova. The bundles or colonies of microgametes (Fig. 40, M_1, M_2) swim about actively by means of their flagella, apparently in search of the larger and much less active female colonies (Fig. 40, I). Having found such a colony the now separated microgametes (Fig. 40, M_3) bore their way in, ultimately conjugating with the megagametes to form zygotes.

In any one colony of Pandorina or Eudorina the constituent cells are all of one kind, all ordinary asexual cells or all male gametes or all female gametes. In Volvox (Fig. 11) we meet with a further advance. Even in asexual colonies which do not produce gametes at all we find the cells differentiated in so far that some only are capable of giving rise (asexually) to daughter colonies, while in the female colonies only some of the cells form female gametes or ova (Fig. 11, A, *o*). The male gametes (Fig. 11, B—D) are very similar to those of Eudorina. They unite with the female gametes to form zygotes, which, after a period of rest, develop into new Volvox colonies.

In order to emphasize the fact that the process of conjugation is essentially a nuclear phenomenon we may now turn to the case of Paramœcium. The general appearance and structure of this protozoon have been described in Chapter IV. (Fig. 8). It multiplies by simple transverse fission, and under favourable conditions continues to do so until exhaustion sets in, when its

[1] Often termed by botanists spermatozoids.

failing powers are restored by conjugation. The conjugation in this case, however, is not quite like that which takes place in the other unicellular organisms which we have been studying, and the term conjugant may be applied, in preference to the term gamete, to the individuals concerned.

It may easily be observed that the union of the two conjugants (Fig. 41) is a merely temporary affair. They remain attached together by their mouth-bearing surfaces for some hours




FIG. 41.—Diagram of the Process of Conjugation in Paramœcium.

gam., gametic nuclei; *M.*, mouth; *meg.*, meganucleus; *mic.*, micronucleus; *mig.* migratory nucleus; *p.b.*, products of the division of the micronucleus which disappear (polar bodies); *st.*, stationary nucleus; *zyg.*, zygote nucleus. (For further explanation see text.)

and then separate again and continue their independent lives. Before separating, however, they evidently undergo some kind of rejuvenescence whereby their vigour and power of multiplication are completely restored. This is accounted for by the fact that during the time of their union certain complex nuclear processes take place, the net result of which is an exchange of chromatin material between the two conjugants.

It will be remembered that Paramœcium differs from most Protozoa in the possession of two nuclei, large and small, or meganucleus and micronucleus (Fig. 41, A, *meg.* and *mic.*). The

latter is alone concerned in the process of conjugation, the meganucleus in the meantime breaking up and being absorbed into the cytoplasm, to be replaced in the manner described later on We may confine our attention, therefore, to the behaviour of the micronucleus. In each conjugant this divides mitotically into two daughter nuclei (Fig. 41, B, *mic.'* and *p.b.*) each of which again divides, so that there are now four micronuclei (Fig. 41, C). Of these four three (*p.b.*) go to the bad, being apparently absorbed into the cytoplasm, while the remaining one (*mic.''*) divides once more, so that each conjugant has now again two micronuclei (Fig. 41, D). These two, though similar in appearance,[1] differ strikingly in their behaviour, one of them remaining quiescent while the other passes over into the body of the other conjugant. They are therefore known respectively as the stationary (*st.*) and the migratory (*mig.*) micronuclei. In this way the migratory micronuclei of the two conjugants change places with one another, as indicated by the arrows, and the sole object of the temporary union of the two conjugants appears to be to enable this interchange to take place. When it has been effected a true conjugation occurs between the two micronuclei in each cell (Fig. 41, E, *gam.*), derived one from each conjugant. This is the real sexual process. The migratory and stationary nuclei are gametic nuclei and the result of their union is a zygote nucleus (Fig. 41, F, *zyg.*). Moreover, we have here again an evident distinction into male and female gametic nuclei, characterized in the usual way by the activity of the one and the passivity of the other. The two conjugants themselves, however, cannot be distinguished as male and female, for each produces both male and female gametic nuclei and may therefore be regarded as hermaphrodite.

After the interchange of gametic nuclei has taken place the two conjugants separate as ex-conjugants (Fig. 41, F). The zygote nucleus in each divides repeatedly by mitosis and from the daughter nuclei thus produced both micronuclei and meganuclei are formed. Meanwhile the ex-conjugants themselves begin to divide once more by fission and the new micronuclei and meganuclei are distributed amongst the new individuals (Fig. 41, G).

The essential feature of this very complicated process is clearly

[1] Except that the migratory micronucleus is somewhat smaller than the stationary one.

the same as in the simpler cases which we have examined, and consists in the union of two nuclei belonging to different cells to form a single zygote nucleus which has renewed powers of multiplication by division. As already observed, the micronucleus alone takes part in the process, the meganucleus being merely concerned in the life of the individual and its multiplication by ordinary fission.

CHAPTER VIII

Sexual phenomena in multicellular plants—The distinction between somatic cells and germ cells—Alternation of sexual and asexual generations—Suppression of the gametophyte in flowering plants.

WHEN we consider the habit of colony formation which is so common amongst the Protophyta, and which we have discussed in the cases of Pandorina, Eudorina and Volvox, we see at once that it is impossible to draw any strictly logical distinction between such primitive forms and the true multicellular plants or Metaphyta. The common fresh water alga, Spirogyra, for example, might be regarded either as a colony of single cells or as a very simple multicellular plant in which the constituent cells exhibit little or no differentiation amongst themselves. In any case it forms a very convenient starting point for the consideration of the sexual phenomena met with in Metaphyta, being in this respect actually in a much more primitive condition than either Eudorina or Volvox.




FIG. 42.—Part of a filament of Spirogyra, showing one complete cell and parts of two others; highly magnified.

c.w., cell-wall; *cr.*, chromatophore; *nu.*, nucleus; *p.u.*, primordial utricle; *pyr.*, pyrenoid; *str.*, strands of protoplasm; *vac.*, vacuole.

The fully developed Spirogyra plants consist of long green filaments of hair-like dimensions, which float in loose slimy masses in clear fresh water. Each filament consists of a single row of cylindrical cells placed end to end, each cell being enclosed in a thin, transparent wall of cellulose (Fig. 42, *c.w.*), whereby its protoplasmic contents are completely separated from those of adjacent cells. The cytoplasm forms a thin primordial utricle (*p.u.*), lining the cell-wall and enclosing a large vacuole (*vac.*) filled with colourless, watery cell-sap, in which a more or less central mass of cytoplasm, containing the

nucleus (*nu.*), is suspended by slender radiating protoplasmic threads (*str.*). So far, both in structure and arrangement of its component cells, the plant closely resembles a single hair of Tradescantia (compare Fig. 25). It differs, however, in the presence in each cell of one or more conspicuous chloroplastids or chromatophores (*cr.*), coloured bright green by chlorophyll and wound spirally round and round inside the cell-wall like pieces of ribbon. It is from these characteristic structures that the name Spirogyra is derived.




FIG. 43. — Conjugation in Spirogyra, showing in one Filament solitary Cells (s.c.) which have failed to mate, and in the other Zygotes (zyg.), × 82. (From a photograph.)

The filaments increase in length by transverse fission of the component cells. Every cell, however, or to speak more accurately its protoplasmic contents, must also be looked upon as a potential gamete. Conjugation in some species takes place between the cells of two filaments which are lying side by side, parallel with one another (Figs. 43, 44). In others it takes place between adjacent cells of the same filament, but we may confine our attention to the former case. The first indication of the process is seen in the formation of a small, hollow protuberance on the wall of one of a pair of cells which happen to be more or less opposite to each other (Fig. 44, *a.*) This is shortly followed by the formation of a similar protuberance on the wall of the other cell (*b.*). The two protuberances meet (*c.*) and fuse together, and the cell-walls at the point of union are dissolved away (*d.*). Thus a hollow canal is formed placing the cavities of the two conjugating cells in free communication with one another. In the meantime changes are going on in the protoplasmic contents of the conjugating cells, essentially similar in the two members of each pair but with one cell still taking the lead and the other lagging somewhat

behind. The chloroplastid breaks up; the primordial utricle retreats from the cell-wall towards the middle, and the entire protoplasmic contents round themselves off into a compact nucleated mass—the gamete (*gam.*). The time has now arrived for the all-important event; the gamete from one cell-chamber creeps through the canal into the other chamber and conjugates with the gamete which there awaits it (Fig. 44, *e.*). The result is a zygote or zygospore (Figs. 43, 44, *zyg.*) which surrounds itself with a thick protective envelope within the cell-wall of the parent and after a period of rest germinates, giving rise by repeated transverse division to a new filament.

In this case it will be observed that the two conjugating gametes are morphologically alike, and we may therefore describe the process of conjugation as isogamous. As in the case of Bodo, however, there is a physiological distinction between the two as regards their activity; the gamete which takes the lead throughout the whole process and finally crawls through the canal of communication is obviously to be regarded as male, and its partner as female. Moreover, one entire filament may produce nothing but male gametes and may therefore be regarded as a male plant (Fig. 44, ♂), while the other may produce only female gametes and therefore be regarded as a female plant (Fig. 44, ♀). In the closely related form, Zygogonium, there is no distinction of any kind between the two sexes, both gametes exhibit the same degree of activity and they meet each other half-way, in the connecting canal between their respective chambers, to form the zygote.




FIG. 44.—Diagram of two conjugating filaments of Spirogyra.

a.—*e*, pairs of cells in successive stages of conjugation; ♂ *gam.*, male gametes; ♀ *gam.*, female gametes; *S.C.*, solitary cell; *zyg.*, zygote.

In Spirogyra, as we have just seen, every cell of the adult plant is a potential gamete or germ cell; in the case of Volvox, it will

be remembered, this is not so, certain cells only being concerned in the sexual process. We have here a kind of fore-shadowing of that distinction into somatic or body cells and sexual or germ cells which is so characteristic of the higher organisms, both plants and animals. We see a somewhat similar fore-shadowing



FIG. 45.—*Fucus vesiculosus*, about half nat. size. (From Vines' "Botany.")
b, air bladders; *f*, fertile branch.

even in the unicellular Paramœcium, except that the distinction is here confined to the nuclei, the meganucleus being concerned with the life of the individual and the asexual process of ordinary cell-division, while the micronucleus is alone concerned in the sexual phenomena. We can, in this case, distinguish between somatic nucleus and germ nucleus, though not between somatic and germ cells.

The loss of the power to act as germ cells or gametes which the vast majority of the constituent cells in a typical multicellular organism usually suffer is undoubtedly one of the penalties which they have to pay for their high degree of specialization. The germ cells themselves, on the other hand, always remain in a more primitive, less specialized condition, and may, in fact, be regarded as so many unicellular Protista enclosed within the multicellular body. They resemble the free-living Protozoa and Protophyta also in that they exhibit a certain degree of independence and are in the majority of cases actually set free from the parent body as unicellular individuals;




FIG. 46.—*Fucus vesiculosus*; Section through a female Conceptacle, × 50. (From Vines' "Botany," after Thuret.)

short-lived, it is true, unless they happen to meet one another and conjugate, but nevertheless enjoying that liberty which is only possible to independent organisms.

All this is very beautifully illustrated in the case or the common brown seaweed or bladder-wrack, *Fucus vesiculosus* (Fig. 45). The entire plant consists of flattened branches, copiously subdivided and attached by a "hold-fast" usually to some rock between tide-marks. Here and there the branches are swollen out to form air-bladders (*b*), which serve as organs of flotation. The histological structure of the plant is comparatively simple and need not detain us; we are concerned only with its reproductive processes.

Fucus vesiculosus is diœcious or unisexual, there being distinct

male and female plants. In both cases certain branches (*f*), usually described as fertile, are characterized by the presence of numerous minute spherical pits, opening on to the surface by narrow mouths. These pits or conceptacles, one of which is represented in vertical section in Fig. 46, contain the sexual organs, male antheridia or female oogonia, as the case may be, intermingled with hair-like structures known as paraphyses. The antheridia (Fig. 47, *a*) are attached to the branching paraphyses in the male




FIG. 47.—*Fucus vesiculosus.*

a, branching paraphysis from male conceptacle, bearing antheridia; *b*, an oogonium surrounded by unbranched paraphyses and with its contents divided into eight ova; *c*, a discharged ovum surrounded by spermatozoa, one of which will fertilize it; *d*, a developing embryo; all × 160. (From Vines' "Botany," after Thuret.)

conceptacles in the form of small sacs in which the male gametes (spermatozoa) are produced. These are minute, nucleated, pear-shaped cells, each with two flagella; they are produced in large numbers in each antheridium and set free by rupture of the wall of the latter to make their way out of the opening of the conceptacle by their own activity.

The oogonia are oval sacs, a good deal larger than the antheridia, and occur amongst the hair-like paraphyses in the female conceptacles (Fig. 46). In each oogonium (Fig. 47, *b*) eight female gametes (egg cells, ova or oospheres) are formed by cell-division. These are spherical, nucleated cells, very much larger than the

spermatozoa, owing to the great amount of cytoplasm which they contain. They are liberated by rupture of the oogonium and discharged through the opening of the conceptacle on to the surface of the plant. There they are found by the spermatozoa, which swarm around them in large numbers, endeavouring to conjugate (Fig. 47, *c*). Finally a single spermatozoon succeeds in boring its way into each large egg cell, and fertilization is effected by the union of the male and female nuclei. The zygote, well supplied with food material by the egg cell, begins to undergo cell-division immediately, forming a multicellular embryo (Fig. 47, *d*) which attaches itself by root-like processes and grows into a plant resembling the parents.

Here we have a perfectly typical case of differentiation of the gametes or germ cells into large passive female ova and small active male spermatozoa, and conjugation is anisogamous, the ovum being "fertilized" by the spermatozoon.

In the ferns, mosses and other more highly organized plants a new complication is introduced by the fact that two distinct forms of the plant alternate with one another in the life cycle. In one only of these forms, known accordingly as the gametophyte, does a sexual process occur; the other, known as the sporophyte, reproduces by means of unicellular spores, which are produced asexually and develop into new individuals without any process of conjugation. The gametes or germ cells, borne on the gametophyte, on the other hand, conjugate, and the zygote develops, not into another gametophyte but into a sporophyte, while, conversely, the spores produced by the sporophyte develop into gametophytes.

This alternation of sexual and asexual generations is a phenomenon of very wide-spread occurrence in the vegetable kingdom, and, as we shall see in our next chapter, something of the same kind occurs also in certain multicellular animals.

Take, for example, any ordinary fern. The conspicuous plant (Fig. 48) is the sporophyte. It is very highly organized and shows the typical differentiation into root, stem and leaf met with in all the higher groups of the vegetable kingdom. Some or all of the leaves sooner or later produce on their lower surfaces sporangia (Fig. 48, A, C), little sac-shaped structures in which the spores arise by division of mother cells into fours. These spores are liberated, by rupture of the sporangia, in the form of fine brown dust, which may be carried to considerable distances by the wind.




FIG. 48.—The Sporophyte Generation of a Fern, *Aspidium filix mas.* (From Strasburger.)

A, section through a sorus or group of sporangia, covered by the indusium (× 20, after Kny); B, lower surface of a pinna, showing the indusia covering the sori; C, lower surface of a pinna with the sori exposed

If one of them alights on a suitable spot, in a moist and shady situation, it may germinate (Fig. 49). Its thick outer wall ruptures and a delicate tube is put forth, containing the protoplasm and nucleus. Cell-division takes place and results presently in the formation of the gametophyte.




FIG. 49.—Diagram of a young Prothallus (*pth.*) formed by Germination of a Fern Spore.

rh., rhizoid or root hair; *sp.c.*, spore coat.

The gametophyte of the fern (Fig. 50) is known as a prothallus. It is an independent, self-supporting plant, but much less highly organized than the sporophyte, consisting usually of a green, heart-shaped plate of cells, not more than perhaps a quarter of an inch in diameter, and attached to the substratum by delicate hair-like rhizoids. It develops no vascular system but nevertheless obtains its food in the same way as the sporophyte, absorbing water containing dissolved mineral salts from the soil by means of its rhizoids, and splitting up carbon dioxide, obtained from the air, by aid of its chlorophyll. Such prothalli are frequently to be found attached to the surfaces of flower-pots and walls in damp greenhouses and other places where ferns are grown.




FIG. 50.—The Gametophyte Generation or Prothallus of a Fern, *Aspidium filix mas*, × 8 (From Strasburger.)

A, lower surface of a sexually mature prothallus, showing antheridia (*an*), archegonia (*ar*), and rhizoids (*rh*)
B, an older prothallus with the young sporophyte generation or fern plant (*b*, *w*) attached to it.

The sexual organs, male antheridia (Fig. 50, *an*) and female archegonia (Fig. 50, *ar*), are, like the rhizoids, found on the lower surface of the prothallus, both usually occurring on one and the same plant, which is therefore monœcious or hermaphrodite. The antheridia (Fig. 51, *a*) are essentially similar

to those of Fucus, being hollow sacs in which the male gametes are developed. The latter (Fig. 51, *s*.) are active spermatozoa, each having a spirally coiled body, consisting chiefly of chromatin material, and bearing a bunch of cilia at one end, by the vibration of which the gamete swims actively about in any dew or other moisture which may be deposited on the prothallus.




FIG. 51.—Antheridium of a Fern, discharging Spermatozoa (Antherozoids) from its opening, highly magnified. (From Vines' "Botany.")

a, antheridium; *s*, spermatozoon.

The archegonia (Fig. 52) differ considerably from the oogonia of Fucus, having a characteristic structure which is more or less accurately repeated in the corresponding organs of many of the higher plants. Each consists of a hollow swollen venter, sunk in the tissue of the prothallus, and a long neck which projects from the surface, and the wall of which is composed of four rows of cells. The venter contains a single relatively large ovum or oosphere (Figs. 52, A, *o*, and 52, B), above which an axial row of canal cells (*K'*, *K''*)




FIG. 52.—Archegonia of a Fern, *Polypodium vulgare*, × 240. (From Strasburger.)

A, young, showing ovum (*o*) and canal cells (*K'*, *K''*), and with the end of the neck closed. *B*, mature, with the end of the neck open.

extends into the neck. When the ovum is ready for fertilization the canal cells degenerate into mucilage and the cells at the end

of the neck separate so as to form an opening (Fig. 52, B). The spermatozoa appear to be attracted to the opening by an acid secretion discharged therefrom. One of them makes its way down the neck to the ovum and fertilizes it by the usual process of conjugation.

The zygote begins to develop, by cell-division, within the venter of the archegonium, and forms a young sporophyte, which for some time remains attached to the prothallus as shown in Fig. 50, B, drawing nutriment therefrom by means of a special temporary organ known as the foot. Presently, root, stem and leaf are developed and the sporophyte becomes self-supporting.

One very remarkable fact in connection with the sexual process in the fern remains to be noticed. The gametes, as we have seen, are normally produced in special sexual organs and are themselves perhaps as highly differentiated in relation to the function of conjugation as gametes ever are. It has been found, however, that if the normal sexual union between ova and spermatozoa be prevented a conjugation may take place between nuclei from adjacent vegetative cells of the prothallus, resulting in the formation of an embryo sporophyte by so-called apogamy. In these cases it is obvious that the sexual process is not really suppressed, but simply transferred to ordinary prothallial cells, which, though they do not conjugate under normal circumstances, have retained the power of so doing when occasion arises. It seems probable, however, that in some cases true apogamy, or suppression of the sexual process, occurs, the embryo sporophyte arising from the prothallus without any conjugation of gametes.

The gametophyte or prothallus of an ordinary fern is, as we have already seen, produced by the development of a unicellular spore (Fig. 49), and in most cases is monœcious or hermaphrodite, bearing both male and female sexual organs and male and female gametes. In the less commonly known and not very fern-like "heterosporous" forms (Isoëtes, Salvinia and Marsilea), however, the gametophyte is dicœcious or unisexual, there being distinct male and female prothalli, and this sexual differentiation affects not only the prothalli themselves but the spores from which these are developed. Hence in these forms we find small microspores which produce male prothalli, and large megaspores which produce female prothalli. The spores themselves are set free from the parent sporophyte, but the prothalli are very much

reduced in size and never become free from the spore-coat; they nevertheless develop antheridia and archegonia respectively, in which spermatozoa and ova are produced, and from the conjugation of these arise zygotes or fertilized ova which develop into new sporophytes.

We have briefly noticed these heterosporous ferns because as regards the sexual phenomena which they exhibit, they constitute a very interesting connecting link between the ordinary (homosporous) ferns, which produce only one kind of spore, and the highest members of the vegetable series, the flowering plants.

In the flowering plants an alternation of sexual and asexual generations can still be traced, but here the gametophyte is so much reduced in size and has become so degenerate in structure that it is quite inconspicuous, and can only be detected by microscopical examination and recognized as constituting a distinct generation in the light of our knowledge of lower forms.

The flowering plant itself is the sporophyte, and it is heterosporous, producing microspores and megaspores. The pollen grains are the microspores, while the megaspores are represented by the embryo sacs enclosed within the ovules or unripe seeds. The microspores, like the spores of ferns, are set free from the parent sporophyte, the megaspores, however, are never set free as such, and in neither case does the gametophyte become free from the spore-coat.

The terms pollen grain and embryo sac were applied to the structures in question long before their true nature as microspores and megaspores was recognized, and they have become so firmly established that it is hardly possible to avoid using them.

If we examine any typical, fully developed flower, such as is represented diagrammatically in Fig. 53, we shall find that it consists of four whorls or circlets of specially modified leaves. Beginning at the outside we find first the calyx (*Ke*), composed of a number of sepals, which usually, but by no means always, retain the green colour characteristic of leaves and serve mainly for the protection of the inner parts of the flower while in the bud; then the corolla (*K*), composed of petals, which may be brightly coloured and serve to attract insects; then the androecium composed of stamens (*a*, *f*); and lastly, in the centre of the flower, the gynœcium or pistil (*n*, *g*, *F*), composed of carpels. The stamens and carpels are often spoken of as the essential

parts of the flower. They are really to be regarded as spore-bearing leaves or sporophylls.

Each stamen consists usually of a long stalk or filament (*f*), bearing an anther (*a*) at its extremity. The anther is a bilobed structure, and each lobe contains two chambers, or pollen sacs, in which the pollen grains (*p*) are formed by the division of mother cells into fours, just as the spores of an ordinary fern are developed within the sporangia. The pollen sacs are, in fact, nothing but sporangia—and microsporangia, because they contain microspores.




FIG. 53.—Diagram of a typical Flower in vertical Section. (From Vines' "Botany.")

a, anther; *em*, embryo sac; *E*, ovum; *f*, filament of stamen; *F*, wall of ovary; *g*, style; *i*, integument of ovule; *K*, corolla; *Ke*, calyx; *n*, stigma; *p*, pollen grains; *ps*, pollen tube; *S*, ovule.

The pistil is formed of a varying number of carpels, which, either singly or united, give rise to a closed chamber below, the so-called ovary[1] (*F*), surmounted by a longer or shorter style (*g*), ending above in a rounded viscid surface, the stigma (*n*). In the interior of the ovary, attached to the carpels, are developed the ovules (*S*), which are nothing but sporangia (megasporangia) enclosed each in a double envelope (*i*). In each ovule a single embryo sac or megaspore (*em*) is produced. Only one ovule is represented in the diagram, but there are usually a large number in each ovary.

Having thus briefly described the parts of the sporophyte with which we are immediately concerned, we must turn our attention for a few moments to the gametophyte. The male gametophyte, which never consists of more than a very small number of cells, is developed from the pollen grain or microspore. This latter is at first a perfectly typical unicellular spore, with a single nucleus surrounded by cytoplasm, and the whole enclosed in a thick protective cell-wall often ornamented with microscopic sculpture of various patterns. The commencement

[1] This is a very unfortunate name because the structure in question is an entirely different kind of organ from the ovary of animals.

of germination of this spore in typical cases (Fig. 54) is marked by the division of the nucleus into two. Around one of these two cytoplasm collects to form a naked "antheridial cell" (*m*); the other, with the remainder of the cytoplasm, constitutes the "vegetative cell" (*k*), which may or may not divide again. The antheridial cell divides into two "generative cells." The vegetative cell, or cells, represents the last vestige of the body of the male prothallus; the generative cells are male gametes. The germination of the pollen grain and development of the male prothallus are completed by the putting forth of the pollen tube (Fig. 53, *ps*, Fig. 54), which takes place if the pollen grain is fortunate enough to alight upon the stigma of a flower of the right kind. The pollen tube finds its way through the loose tissue of the style to the ovary and comes into intimate relations with one of the ovules contained therein.




FIG. 54.—Germination of the Pollen Grain of *Lilium martagon*, × 375. (From Strasburger, after Guignard.)

k, nucleus of the vegetative cell of the pollen tube; *m*, antheridial cell; *g*, male gametes formed by division of the antheridial cell.

The female gametophyte is represented by a few cells formed by division of the megaspore (embryo sac), or rather of its nucleus, and to some extent of its cytoplasm, within the ovule. The process is a somewhat complicated one, but, without going into details, we may note that at the time when the ovule is ready for "fertilization" the embryo sac in a typical flowering plant (Angiosperm) contains seven cells, one of which is a female gamete (ovum or oosphere), while the others may be taken to represent the female prothallus, including a vestige of an archegonium. The arrangement of these cells is shown in Fig. 55 (*at*, *e*, *k*, *s*).

The embryo sac or megaspore (*E*) is surrounded by a cellular layer known as the nucellus (Fig. 55, *K*), which represents the wall of the sporangium, and this in turn by two other coats (*ai* and *ii*), the outer and inner integuments of the ovule, which grow up around the nucellus. The entire ovule is attached to the wall of the ovary by a stalk or funiculus (*f*), upon which it is

frequently bent sharply round as shown in Fig. 55. Opposite to the spot where the funiculus is attached to the ovule an aperture is left in the integuments known as the micropyle (*m*). It is through this micropyle that the tip of the pollen tube usually forces its way in search of the female gamete (*e*), which lies at the end of the embryo sac close to it. The wall of the pollen tube and that of the embryo sac are absorbed where they come in contact with one another, and thus a passage is opened for the male gamete, which passes down the pollen tube into the embryo sac and there conjugates with the ovum. The zygote thus formed develops within the embryo sac into an embryo sporophyte[1]; the integuments of the ovule become hardened to form the seed coat; reserve food material, such as starch or oil, is stored up either in the embryo itself or in the endosperm[2] around it, and the ovule and its contents separate from the parent sporophyte as the ripe seed (Fig. 56, A).




FIG. 55.—Diagram of the unfertilized Ovule of a Flowering Plant (Angiosperm) in longitudinal Section. (From Vines' "Botany.")

ai, outer integument, *at*, antipodal cells; *e*, ovum; *E*, embryo sac; *f*, funiculus; *ii*, inner integument; *k*, central or definitive nucleus of embryo sac; *K*, nucellus; *m*, micropyle; *s*, synergidæ.

When the seed ripens the development of the contained embryo is suspended for an indefinite period, to be resumed again if and when the seed finds a suitable situation in which to germinate. The embryo may then continue its development into the adult sporophyte (Fig. 56, B).

It is interesting to notice that no less than three distinct generations take part in the formation of the seed. The seed coat belongs to the parent sporophyte, while the contents of the

[1] *Vide* pp. 48—50 (Fig. 14).

[2] The second generative nucleus from the pollen tube conjugates with the nucleus in the middle of the embryo sac (Fig. 55 *k*), and the "endosperm" arises by repeated division of the nucleus resulting from this conjugation. The whole process is somewhat complex and it is not essential to our present purpose to describe it in detail.

embryo sac at first represent the female gametophyte, which disappears as the zygote develops into the embryo of another sporophyte. In this way a very intimate relation is established between each sporophyte generation and the one which precedes it, and the gametophyte is crushed out of existence, as an independent generation, between the two.

Accompanying this almost total suppression of the gametophyte we find a delegation of certain responsibilities connected with the sexual function to the asexual sporophyte, and the development by the latter of what may be termed vicarious sexual characters. These characters find their expression in that most remarkable feature of all the flowering plants, the flower itself. Thus the use of the terms male and female may be extended in the first instance to the stamens and pistil, though these are really merely the spore-bearing leaves of the asexual generation. Similarly the transference of the pollen grains from stamens to stigma is often spoken of as the fertilization of the flower, though it is obviously not the true process of fertilization but only a necessary preliminary to the conjugation of the gametes, and is therefore more accurately spoken of as pollination.




FIG. 56.—Garden Pea (*Pisum sativum*).

A, ripe seed split in half; *B*, seed germinating. *cot.*, cotyledons or seed leaves; *pl.*, plumule or shoot of embryo; *rad.*, radicle or root of embryo; *test.*, testa or seed coat.

It will have been observed from the foregoing description that not only is the male gametophyte of the flowering plant reduced almost to the point of disappearance, but the male gamete itself has apparently suffered great degeneration. It is no longer an active spermatozoon, swimming about by means of flagella or cilia, as in Eudorina or in the ferns, but a shapeless nucleated mass of protoplasm which has at the most a sort of amœboid power of locomotion. By far the greater part of the travelling which it has to accomplish in order to reach the ovum is

effected while it is still enclosed within the pollen grain and at the expense of some external agency, for it is not until the pollen grain has alighted upon the stigma and the pollen tube is put forth that the "generative cell" begins to exercise its own feeble powers of locomotion.

The transference of the pollen to the stigma is effected usually in one of two ways, either by the action of the wind or by the agency of insects. Flowers which are pollinated in the first of these two ways are said to be anemophilous, and they are usually small and inconspicuous, as in the grasses and plantains, and many forest trees. It is a very extravagant method of pollination, involving the production of enormous quantities of pollen, most of which is wasted, for only a very minute percentage of the pollen grains will ever chance to alight upon stigmas. We realize this when we see the enormous quantities of yellow pollen dust which are blown off the pine trees in spring time. The entomophilous or insect-pollinated flowers, on the other hand, have hit upon a much more economical way of doing the business. The development of nectar or honey as a bait for their insect visitors, and of gaily coloured petals or sepals and sweet scents as a means of attracting them, and in many cases of elaborate mechanical contrivances to secure that the insect shall not obtain its reward without doing the work of pollination, all co-operate in bringing about the desired end, and the study of these various adaptations forms one of the most interesting chapters in biological science. We shall refer to it again when we come to deal with adaptation and natural selection.

In many cases a complete sexual differentiation is manifested by the entire flowers themselves, some having stamens without carpels and others carpels without stamens, and being spoken of as "male" or "female" flowers accordingly. We see this, for example, in the case of the vegetable marrow, where both kinds of flower are borne on the same plant, while in other cases, such as the weeping willow and the Japanese Aucuba, the whole plant may be either "male" or "female," producing flowers of the one kind only. Thus the terminology which strictly speaking is applicable only to the sexual gametophyte, has, as a matter of convenience, been extended to the asexual sporophyte in order to describe the secondary sexual characters which have been transferred to it in consequence of the suppression of the former.

The telescoping of successive generations one within the other

—the embryo sporophyte into the ovule of the preceding sporophyte generation, with the gametophyte crushed in between—is the most characteristic feature of the life cycle of the higher plants.

From the homosporous ferns upwards throughout the vegetable series it is obvious that the gametophyte is not nearly so well adapted in its organization to the conditions under which the higher plants have to live as is the sporophyte. There has apparently been a kind of rivalry between the two alternating generations, in which the gametophyte has had much the worst of it. The sexual function itself, however, is far too important to be altogether abandoned, and so the successful sporophyte has finally taken over many of the responsibilities connected therewith, while the poverty-stricken gametophyte has ultimately become entirely parasitic upon its rival.

CHAPTER IX

Sexual phenomena in multicellular animals—Structure and life history of Hydra and Obelia—Alternation of generations—The cœlomate type of structure—Secondary sexual characters—The evolution of sex.

In multicellular animals or Metazoa, as in multicellular plants, a sharp distinction can usually be drawn between the somatic cells which build up the various tissues and are concerned with the life of the individual, and the germ cells or gametes which are concerned with the propagation of the race and which alone (in most cases) have the power of separating from the parent soma or body and giving rise to new individuals.

In nearly all the Metazoa the gametes are sexually differentiated into relatively large, passive ova and much more minute, active spermatozoa which swim about by means of flagella. The actual gametes arise by subdivision of undifferentiated primordial germ cells. In the sponges, whose organization has not advanced very much beyond that of complex colonies of Protozoa, the primordial germ cells are merely wandering amœboid cells, resembling the white blood corpuscles of vertebrates. Some of these round themselves off and give rise to more or less spherical ova, others divide into spermatozoa, and probably the entire sponge itself is in most cases either male or female, producing one kind of gamete only. In the sponge the germ cells are not localized in very definite organs but scattered singly or in groups throughout the gelatinous ground-substance of which the body is largely composed.

In the great majority of Metazoa, on the other hand, the germ cells are segregated in well-defined organs termed gonads. As a rule each gonad produces only ova, when it is known as an ovary; or spermatozoa, when it is known as a spermary or testis; only occasionally does it produce both, as in the case of the ovotestis of the snail. The gonads may accordingly be spoken of as female, male, or hermaphrodite as the case may be, and the same terms are also applied to the animals themselves, a male or a

female animal possessing either male or female gonads, while a hermaphrodite animal may either possess a combined ovo-testis or both ovaries and testes separately.

In illustration of these points we may briefly describe the structure and life history of the common fresh water polype,




FIG. 57. —The fresh water Polype (Hydra) cut in half longitudinally and greatly enlarged. (From Marshall and Hurst's "Practical Zoology.")

A, mouth; B, hypostome; C, digestive cavity; D, ectoderm, E, mesoglœa; F, endoderm, G, tentacle; H, testis; I, ovum in ovary; K, bud; L, foot.

Hydra (Fig. 57), so frequently found attached to aquatic plants in ponds and ditches. Hydra is a member of the great group Cœlenterata, which includes the sea-firs, jelly-fish, sea-anemones and corals, and which are distinguished by the fact that they retain throughout life the fundamental features of the gastrula (compare Fig. 13, IX, X). The body of a typical Cœlenterate animal consists essentially of a simple sac (Fig. 57) whose wall

is composed of two layers of cells. The cavity of the sac (C) is the digestive or gastral cavity (enteron), and it has only a single opening to the exterior, the mouth (A), usually surrounded by a ring of tentacles (G). The wall of the sac is solid and there is no body cavity or cœlom surrounding the digestive tube as in higher animals (Cœlomata). The outer cell layer (D) of the body wall is the ectoderm (epiblast of the embryo), the inner (F) is the




FIG. 58.—A small portion of a thin longitudinal Section through the Body Wall of *Hydra viridis*, × 800. (From Marshall and Hurst's "Practical Zoology.")

A, a large ectoderm cell; B, its nucleus; C, its muscle process; D, an undischarged thread cell; E, its trigger process; F, a thread cell with discharged thread; G, interstitial cells; H, mesogloea; I, endoderm cell; K, vacuole; L, nucleus of endoderm cell; M, green algal cells living in the endoderm cells; N, flagellum of endoderm cell.

endoderm (hypoblast of the embryo) and between the two is a gelatinous, non-cellular supporting lamella, the mesogloea (E).

Hydra itself is a very small form, but easily recognizable by the naked eye. The body is long and slender or short and thick, according to its state of contraction, and the same is true of the tentacles, which may be visible as mere knobs around the mouth at the unattached end of the animal, or as long slender threads extended through the water like fishing lines and serving for the capture of the minute organisms upon which the Hydra feeds. The mouth is situated on the top of a conical projection,

the hypostome (Fig. 57, B), which lies within the circle of tentacles.

The endoderm, which immediately lines the gastral cavity, is made up of a single layer of relatively large cells (Fig. 58, I) whose function is digestive. The ectoderm is made up of several kinds of cells, some larger than others. The larger ones (A) are much broader at their outer than at their inner ends and the interstices thus left between the latter are filled up by small interstitial cells (G). The endoderm cells and the larger ectoderm cells both send out prolongations of their bodies into the gelatinous mesoglœa (H) which lies between them, and these processes, having the form of elongated fibres (C), are the seat of that power of contraction which Hydra possesses in such a high degree—they are in fact muscular.

Hydra has two very distinct methods of reproduction, asexual and sexual respectively. The former consists in a process of budding, little outgrowths of the body being formed, which elongate, acquire mouth and tentacles, and for a time remain attached to the parent (Fig. 57, K). In this way temporary colonies of polypes may be produced, but sooner or later the buds separate and begin to lead independent lives.

Sexual reproduction is effected by means of ova and spermatozoa, which are essentially similar to those of higher animals. They are produced in gonads—ovaries and testes—and as both kinds of gonad usually occur in the same individual the animal is hermaphrodite. The testes (Fig. 57, H) take the form of little swellings situated at a short distance beneath the ring of tentacles and formed each by an accumulation of interstitial ectoderm cells. These are the primordial germ cells, by the division of which the spermatozoa are formed. The spermatozoon is perfectly typical, resembling a flagellate protozoon, with an ovoid head consisting almost entirely of chromatin and a long cytoplasmic tail or flagellum by means of which it swims actively about when shed into the surrounding water by rupture of the testis.

There is usually only a single ovary, appearing as a larger projection from the body wall nearer to the attached end of the animal; it consists at first, like the testes, of a heap of primordial germ cells formed by the multiplication of interstitial cells. In each ovary, however, only a single cell develops into a mature ovum (Fig. 57, I), its sister cells, which may all be

regarded as potential ova, being sacrificed for the benefit of the one; in fact they are simply devoured by the voracious egg




FIG. 59.—Development of Hydra. (From Bourne's "Comparative Anatomy," partly after Brauer.)

A, the mature ovum, full of yolk granules and still attached to the body wall of the parent; B, section of blastula or blastosphere produced by segmentation of the ovum; C, the embryo becoming solid by migration into the blastocœl of cells cut off from the wall of the blastula to form the hypoblast; D, solid embryo composed of epiblast and hypoblast and enclosed in a protective shell; E, embryo flattening itself out within the shell; F, embryo emerging from the shell and with the gastral cavity appearing in the endoderm (hypoblast); G, empty shell after the escape of the embryo

blc, blastocœl; *ec*, ectoderm (epiblast); *en*, endoderm (hypoblast); *i*, solid mass of hypoblast cells; *mg*, mesoglœa; *sh*, shell; *she*, outer layer of shell; *shi*, inner layer of shell.

cell, which puts forth pseudopodia and feeds upon them like a hungry Amœba. In this way the ovum attains a relatively large size and its cytoplasm becomes loaded with yolk corpuscles

which will serve later on for the nutrition of the developing embryo.

Some of the surrounding cells of the ectoderm at first form a covering or envelope for the growing ovum, but this is presently ruptured and the mature egg is exposed on the surface of the body of the parent Hydra. There it is found by a spermatozoon, which is attracted towards it and by its own activity bores its way into the ovum. This act of fertilization is concluded in the usual manner by the fusion of the nucleus of the spermatozoon (male pronucleus) with that of the ovum (female pronucleus) to form the zygote nucleus.




FIG. 60.—*Obelia geniculata*.
A, part of hydroid colony; B, free-swimming medusa; both × 18. (From photographs.)
bst., blastostyle; *gon.*, gonad; *gth.*, gonotheca; *hyc.*, hydrocaulus; *hyd.*, hydranth; *hyth.*, hydrotheca; *mn.*, manubrium; *p.s.*, perisarc; *r.c.*, radial canal; *ten.*, tentacles.

The fertilized ovum or zygote (Fig. 59, A) undergoes segmentation while still remaining attached to the parent Hydra. In this way a single-layered, hollow blastula (B) is formed, which becomes converted into a two-layered embryo by migration of cells into the interior to form the at first solid hypoblast or endoderm (C, D, *i*). The epiblast or ectoderm cells (D, *ec*) now secrete a thick horny protective envelope (*sh*, *shi*) around the embryo, which falls off from the parent and undergoes a period of rest at the bottom of the pond. After a time the interrupted development is resumed, the horny envelope is ruptured, and the embryo escapes (F). The gastral cavity appears in the midst of the endoderm cells, the mouth is formed by perforation at one end, and the tentacles bud out. With the formation of the mouth the gastrula stage is reached, but it will be noted that

this condition is arrived at by a somewhat different route from that which leads to the corresponding stage in Amphioxus (compared Fig. 13, I—X).

Closely related to Hydra are a large number of marine Cœlenterates, which, from their obviously animal nature combined with their plant-like mode of growth, were known to the older naturalists as zoophytes. One of the most familiar examples of these is Obelia (Fig. 60), which is frequently found attached to rocks or seaweeds near low water mark.

Obelia differs from Hydra in several interesting particulars. In the first place the asexual process of multiplication by means of budding takes place in a very regular manner, and the buds, instead of separating from the parent, remain connected together to form permanent colonies (Fig. 60, A) in which the constituent individuals or persons (sometimes called zooids) are arranged in a perfectly definite way. The colony is comparable to an arborescent colony of Protozoa such as Zoothamnium or Epistylis (compare Fig. 9, 11—15), but the individuals of which it is composed are units of a higher order than single cells.

In the second place the colony develops a common skeleton, secreted by the ectoderm, which takes the form of a slender tube of horny perisarc (*ps.*) enclosing all the branches and expanding at the end of each into a little cup or hydrotheca (*hyth.*), occupied by a single zooid. Lastly the colony is polymorphic, the zooids exhibiting a certain amount of differentiation and division of labour amongst themselves.

A network of root-like branches at the base of the colony creeps over the substratum and serves for attachment. From this network, which is not shown in the illustration, arises a little forest of vertical stems, each of which has a characteristic zig-zag outline (Fig. 60, A). From each angle of the stem a short branch is given off which terminates in a single hydra-like zooid known as a hydranth (*hyd.*), enclosed in one of the horny cups or hydrothecæ, from the mouth of which its tentacles are extended into the water.

The structure of the hydranth is similar in all essential respects to that of Hydra. In the middle of the ring of tentacles is the mouth, situated on a projecting hypostome and leading into the digestive cavity, and the different hydranths of the colony are all placed in communication with one another by the tubular hydrocaulus, or common stalk (*hyc.*), enclosed in the horny

perisarc. These hydranths are the nutritive individuals of the colony, whose function it is to capture and digest the prey.

Very often we find, in the angle between a hydranth-bearing branch and the main stem, a short branch bearing an individual or zooid of a different kind, enclosed in a horny cup of totally different shape. These individuals are somewhat club-shaped; they have no mouth and no tentacles, and they are termed blastostyles (Fig. 60, A, *bst.*). The horny cup in which each is enclosed is urn-shaped, with constricted mouth, and is distinguished by the name gonotheca (*gth.*). The function of the blastostyle is exclusively reproductive and it is entirely dependent for its nutrition upon digested food received from the hydranths through the hydrocaulus. It reproduces by budding, and the buds are often found attached to it in large numbers, within the sheltering gonotheca, as shown in the figure.

The colony itself increases in size by the formation of new buds in regular succession, alternately on the right and left sides, beneath what is, for the time being, the topmost hydranth of each main stem, each new bud giving rise to a hydranth-bearing branch which overtops its immediate predecessor. The buds formed on the blastostyle, on the other hand, do not develop into hydranths at all, but into another kind of individual known as a medusa, or medusoid person, which presently detaches itself from the parent and escapes through the mouth of the gonotheca as a free-swimming individual.

The medusa of Obelia (Fig. 60, B), though larger than the hydranths, is still very small, not more than about $\frac{1}{10}$th of an inch in diameter. At first sight it looks very different from a hydroid individual (hydranth), but it can easily be shown to have the same fundamental plan of structure. It consists of a circular disk surrounded by a fringe of tentacles (*ten.*). From the middle of one surface projects a handle-shaped structure, the manubrium (*mn.*), corresponding to the hypostome of the hydranth and bearing the mouth at its extremity. This mouth leads into a central digestive cavity from which four radial canals (*r.c.*) run outwards through the gelatinous ground-substance to a circular marginal canal. The medusa swims actively about by muscular contractions of the disk, and in doing so it assumes a bell-like shape with the manubrium projecting from the convex surface, like the handle of the bell.

Most medusæ—the larger of which are familiar to us as

"jelly-fish"—are more definitely bell-shaped, but the manubrium lies in the hollow of the bell, like its clapper; in comparison with these the Obelia medusa may be said to turn itself inside out in the act of swimming. In accordance with their active life the medusæ have a fairly well developed nervous system and a number of sense organs around the margin of the bell. The point with which we are immediately concerned, however, is their mode of reproduction.

Unlike the hydranths and blastostyles of which the Obelia colony is composed the medusæ are sexual individuals, bearing sexual organs or gonads from which the gametes are set free. The gonads (Fig. 60, B, *gon.*) are masses of germ cells lying one beneath each radial canal, on the same side of the disk as the manubrium. The sexes are distinct, the medusæ being either male or female, and the gonads accordingly producing either spermatozoa or ova, which, when mature, are discharged into the water by rupture of the gonad.

The ova are fertilized by the spermatozoa and undergo segmentation much as in the case of Hydra, developing ultimately into a hydroid individual (hydranth), which by budding gives rise to a new Obelia colony.

It is obvious that we have here a case of alternation of sexual and asexual generations (metagenesis), comparable to that which occurs in the fern, except that the sexual generation arises from a multicellular bud and not from a unicellular spore. The sexual medusoid individual is produced by budding from the asexual hydroid, and itself gives rise, through the conjugation of gametes and the development of the zygote thus produced, to the asexual hydroid again. The process is somewhat complicated by the fact that the hydroid also produces other asexual individuals by budding, but this really amounts to little more than does the formation of numerous branches by the budding of one of the higher plants, for in the latter case also each bud may be regarded as, potentially at any rate, a perfect individual.

We may draw an even closer comparison between the alternation of hydroid and medusoid generations in the Cœlenterata and that of sporophyte and gametophyte in the higher plants, for in the former, as in the latter, we see in many instances a more or less strongly developed tendency towards the suppression of the sexual generation (sometimes called the gamobium in animals).

In Tubularia, for example, the medusoid individual never

separates from the parent colony, but remains attached to it as a bud, though still showing clear evidence, in its bell-like shape and in the presence of the manubrium and of radial and circular canals, of its medusoid nature. It is in fact merely a degenerate




FIG. 61.—A single Hydranth of Tubularia, with medusoid Individuals (Gonophores) budded out between the two Circles of Tentacles; highly magnified. (After Allman.)

act., actinula larva enclosed in gonophore; *act.'*, actinula larva escaping; *ent.*, enteron or digestive cavity; *gon.*, gonophore; *m.*, mouth; *per.*, perisarc; *ten.*, tentacles.

medusa or gonophore (Fig. 61, *gon.*). It still retains its sexual function, producing either ova or spermatozoa, and in this case the fertilized ova actually develop into young hydroids or "actinula larvæ" (Fig. 61, *act.*, *act.'*) before escaping from the parent gonophore. We have here a telescoping of the successive generations quite comparable to what we find in a flowering

plant, and again it is the sexual generation which has undergone reduction.

In other cases the medusoid bud or gonophore more or less completely loses its medusa-like structure and becomes a mere sac containing the gonad, and it has been suggested that in Hydra we may have the last stage in this progressive reduction of the sexual generation, the medusoid having altogether disappeared, after having transferred its sexual functions to the hydroid.

It seems almost incredible that the germ cells themselves which are originally produced by one generation should in this manner be transferred to what is really the preceding generation, but as a matter of fact we see all stages in this process in different genera of Hydrozoa. Even in Obelia and certain other medusæ the germ cells do not originate in the gonads beneath the radial canals but in the ectoderm of the manubrium, reaching their final position by a process of migration. In Eudendrium, where the medusoid is reduced to a mere vestige, the germ cells no longer originate in the sexual individual at all, but in the main stem of the hydroid colony, whence they migrate into the medusoid bud. If we imagine them ceasing to migrate from their place of origin in the hydroid, while the medusoid is no longer formed, we reach the condition of Hydra, with a complete transference of the sexual function to what should be the asexual generation.

In the cœlenterates, however, it is not always the asexual (hydroid) generation which predominates, for in some cases this is suppressed more or less completely and the medusa or jelly-fish reproduces its own kind directly without the intervention of a hydroid phase.

In cœlenterate animals such as Hydra and Obelia, as we have already seen, the body consists of a single hollow tube whose wall is made up of only two cell layers, the ectoderm on the surface and the endoderm lining the digestive cavity, with a supporting layer of gelatinous consistency—the mesoglœa—between the two. In the case of the larger jelly-fish this mesoglœa attains a great thickness; it is, however, never a true cell layer like the ectoderm and endoderm, but rather of the nature of intercellular substance secreted by the cells on either side of it.

In Hydra and Obelia the germ cells arise from the ectoderm,

and the gonads (Fig. 62, A, *gon.*) are accordingly situated close to the surface of the body and no special ducts are required for the conveyance of ova or spermatozoa to the exterior.

In the great group Cœlomata, which includes practically all animals higher in the scale of organization than the cœlenterates, we find a different state of affairs. The mesoglœa has been replaced by a true cellular mesoderm (Fig. 62, B, *mes.*), formed of cells derived from ectoderm or endoderm, or from both, and in the thickness of this layer a cavity is developed, the cœlom or




FIG. 62.—Comparison of Cœlenterate and Invertebrate Cœlomate Types of Structure.

A. Diagram of a transverse section of a cœlenterate animal.
B. Diagram of a transverse section of an invertebrate cœlomate animal.
cœl. cœlom or body cavity; *cœl. ep.* cœlomic epithelium lining body cavity; *d.v.* dorsal blood-vessel; *ect.* ectoderm; *end.* endoderm; *ent.* enteron or digestive cavity; *g.a.* genital aperture; *g.d.* genital duct (gonoduct); *gon.* gonad; *mes.* mesoderm; *mesgl.* mesoglœa; *n.c.* double nerve cord; *som.* somatopleure or body wall; *spl.* splanchnopleure or gut wall; *v.v.* ventral blood-vessel.

body cavity (*cœl.*), which more or less completely surrounds the digestive tube or alimentary canal (compare the development of Amphioxus, Fig. 13, XI—XIII). The outer layer of the mesoderm unites with the ectoderm to form the body wall or somatopleure (*som.*), while the inner layer unites with the endoderm to form the gut wall or splanchnopleure (*spl.*), and the body thus acquires the form of a double tube. The body cavity is lined by a layer of epithelial cells (*cœl. ep.*), and it is in this layer that the germ cells multiply and accumulate. The gonads (Fig. 62, B, *gon.*) therefore project into the body cavity and into this cavity the mature germ cells are primarily discharged. In the great majority of cases

special genital ducts or gonoducts (*g.d.*) are developed which pierce the body wall and serve for the passage of the germ cells to the exterior. The sexes are usually distinct in the higher forms (Vertebrata), but many of the invertebrate cœlomates (*e.g.*, the earthworm) are hermaphrodite, the same individual bearing both male and female gonads (testes and ovaries) with the corresponding gonoducts (vasa deferentia and oviducts).

Fertilization of the ova by the spermatozoa, or in other words conjugation of the gametes, may take place either within the body of the parent, as in most terrestrial forms, or externally, as in a very large proportion of aquatic animals. In the former case special organs are developed for the transference of the spermatozoa from one individual to another, and such transference usually occurs even in hermaphrodite forms, which, as a rule, are incapable of self-fertilization. Further modifications may arise in connection with the nutrition of the embryo, which may remain within the body of the parent—in an enlarged portion of the oviduct known as the uterus—until it has reached an advanced stage of development. This takes place more particularly in the females of the higher vertebrates.

In connection with the sexual differentiation, more especially in the higher animals, numerous secondary sexual characters may arise which are not directly connected with the organs of reproduction. Such are the various ornamental outgrowths of hair, feathers and so forth, which distinguish the males of many vertebrates and are supposed to appeal to the æsthetic sense and thus to contribute towards the mutual attraction between male and female, and the special weapons, such as antlers and spurs, which male animals frequently develop and which are used in combat for the possession of the females.

Although not directly connected with the gonads these secondary sexual characters seem to depend for their development in some curious way upon the presence of these organs. Thus it is well known that if the testes be removed by castration the secondary sexual characters will not, in most cases at any rate, develop properly. We see an excellent illustration of this in the case of the antlers of the stag, which are confined to the male and do not develop at all if the animal be castrated in early youth, while if the operation be performed after the antlers are fully developed these are prematurely cast off and replaced by imperfect ones.

How this intimate correlation between gonads and secondary sexual characters is brought about is still uncertain, but there is strong reason to suppose that it is due to the secretion by the gonad of some specific substance (hormone), perhaps of the nature of a ferment, which circulates throughout the body—chiefly no doubt in the blood—and controls the development of the characters in question. That internal secretions may act in this way upon organs remote from their own place of origin is well known and is strikingly exemplified in the case of the corpora lutea of the mammalian ovary. These structures appear on the surface of the ovary in the places whence ova have been discharged, and are apparently of a glandular nature. As the fertilized ova pass down the oviduct they begin to develop, and on reaching the uterus fix themselves to the wall of the latter, in which they become imbedded. The spot where fixation takes place is far distant from the ovary, but it has been demonstrated that if the corpora lutea on the surface of the latter be destroyed the embryos will not become fixed at all. There is a close correlation, then, between the presence of the corpus luteum and the fixation of the embryo, and this is explained by supposing that the corpus luteum secretes some substance which, circulating in the blood, reaches the uterus and stimulates its epithelial lining to respond to contact with the embryo. Moreover, the reaction, whatever its cause, appears to be mutual, for if the discharged ovum does not get fertilized the corpus luteum does not attain its full development and soon disappears.

We have now very briefly traced the evolution of sexual characters from their starting point in the male and female gametes of the Protista to their culmination in the higher plants and animals. We have seen how sexual differentiation, which primarily concerns the gametes themselves, is gradually extended to the colonies or to the multicellular individuals from which the gametes arise, or even to a preceding, originally non-sexual generation. The various structural modifications thus brought about are all directed towards one end, the conjugation of the gametes. The mutual attraction which undoubtedly exists between the gametes themselves is not sufficient, at any rate in the case of the more highly developed and complex organisms, where the distances between their places of origin are relatively very great, to secure their union.

In the flowering plants their own efforts are supplemented by

all the elaborate devices for securing pollination, and by far the most active part in the process is played by external agencies, especially by those insects which have become the vicarious fertilizers of the flowers.

In the higher animals, on the other hand, the necessity for bringing the gametes into close proximity with one another has led to the development of all those secondary sexual characters, both bodily and mental, which play so conspicuous a part in the drama of life. Throughout the whole course of this remarkable process of evolution, except in the case of certain obviously degenerate forms, we observe that same fundamental distinction between the sexes which we first noticed in the gametes of unicellular organisms, and which in the higher animals is extended with the sexual differentiation itself from the gametes to the complex multicellular body which bears them. The female is the more passive partner and is especially concerned with the nutrition and rearing of the offspring, and her bodily organization is especially adapted to her maternal functions. These functions constitute an inevitable handicap in the struggle for existence, and the females and young of the higher animals are in most cases largely dependent upon the less burdened and consequently more active and vigorous males for their protection.

The explanation of this progressive sexual differentiation is undoubtedly to be found in the advantages to be derived from division of labour and the accompanying possibilities of specialization. The origin of conjugation itself, upon which all sexual phenomena are based, is another, and more fundamental, question. At first, as we have seen, the conjugating gametes were apparently exactly alike one another and exhibited no visible sexual differentiation at all. The habit of conjugation probably arose from the necessity of making good some disturbance of equilibrium in the protoplasm of the cell. It has been supposed that, as the result of repeated fission, some condition of inequality was gradually set up amongst the daughter cells, whereby some of them came to have too much of one constituent and too little of another, while others were in the opposite condition. In this way the successive unicellular generations gradually became more and more enfeebled—as we saw in the case of Paramœcium—and, owing perhaps to some sort of polarization, those which had become modified in opposite directions came to exercise an attraction upon one another which resulted in conjugation and restoration

of the proper equilibrium. It may be that from the very first the inequalities of fission resulted in the accumulation of more active protoplasm in some cells and a greater amount of reserve material in others, and that this was the starting point of the differentiation into male and female.

Although fusion of the nuclei (karyogamy) of the two gametes appears now to be the most important feature of conjugation, we must suppose that it was preceded by plastogamy[1] or fusion of the cytoplasm, which obviously constitutes the natural preliminary to karyogamy. In some of the lower Protozoa such plastogamy has been sometimes observed unaccompanied by karyogamy, and it is possible that in some cases plastogamy alone is sufficient to bring about rejuvenescence and renewed activity in cell-division.

[1] Sometimes called plasmogamy.

CHAPTER X

Origin of the germ cells in multicellular animals—Maturation of the germ cells—Reduction of the chromosomes—Sex determination in insects—Different forms of gametes — Mutual attraction of the gametes—Fertilization and parthenogenesis.

In many multicellular animals the distinction between somatic cells and germ cells becomes manifest at a very early stage in the development of the individual. An extreme instance of this is seen in the parasitic round-worm of the horse, *Ascaris megalocephala*. Here the distinction in question precedes all other histological differentiation. The two cells or blastomeres into which the fertilized ovum first divides (Fig. 35, C, D) are originally similar to one another, but as they prepare for the next mitotic division of the nucleus a remarkable difference is, according to the observations of Professor Boveri, established between them. Both at first (in the case of the variety known as *univalens*) exhibit two elongated chromosomes (the variety *bivalens*, which is represented in Fig. 35, having four), but in one the thickened ends of the two chromosomes are thrown off into the surrounding cytoplasm, where they degenerate, while the more slender middle portions break up into a number of short pieces. Thus two differentiated cells are produced, one with two large chromosomes and the other with numerous small ones. The latter gives rise by its subsequent divisions to somatic cells only. The former is a primordial germ cell; for some five or six times it will divide like its parent cell into a somatic cell and a primordial germ cell, but after these early divisions the primordial germ cells will give rise to their own kind only, until the time comes for the production of the actual gametes. The somatic cells, on the other hand, will gradually become differentiated into all the various tissue cells of the adult.

Perhaps the most significant part of this remarkable process as observed in Ascaris is the elimination of chromatin material from the nuclei of the somatic cells when these are first

enesis according to whether ova or spermatozoa are produced nereby, is accompanied by nuclear phenomena of very great nterest, whereby the maturation of the germ cells is effected. Before describing this process we must lay stress upon certain reliminary considerations.

As we have already seen, each kind of animal or plant is naracterized by the appearance of a definite number of chromo-omes in the nuclei of its cells at the time when these are under-oing division by mitosis. Although differing greatly in different pecies the number is usually the same for all the cells of which ne body in each case is com-osed. It is usually an even umber, and (with certain ex-eptions) it remains the same successive generations of dividuals.




FIG. 64.—Ovum of the Horse Worm (*Ascaris megalocephala*) during the Process of Fertilization, showing the male and female Pronuclei (pro), × 770. (From a photograph.)

It will also be remembered nat the zygote or fertilized g from which the individual velops is formed by the con-gation of two gametes, ovum nd spermatozoon, and that in is process the nuclei of the metes, sometimes called the ale and female pronuclei, nite, or at any rate co-operate a single nucleus. Fig. 64 is ken from an actual photograph of an egg of Ascaris in process fertilization; the spermatozoon has already entered the um and the male and female pronuclei (*pro.*) are seen lying le by side in the cytoplasm. Each pronucleus brings with it own set of chromosomes, and hence the zygote nucleus has uble the number of chromosomes possessed by either of the metes. Thus it appears at first sight that every conjugation sexual union of gametes (zygosis) must be accompanied a doubling of the number of chromosomes, and we might erefore expect to find each successive generation with twice as any chromosomes in its nuclei as the preceding one. That is is not actually so depends (in the case of animals) upon the ct that the nuclei of the gametes contain only half the number chromosomes characteristic of the somatic cells; if the

genesis according to whether ova or spermatozoa are produced thereby, is accompanied by nuclear phenomena of very great interest, whereby the maturation of the germ cells is effected. Before describing this process we must lay stress upon certain preliminary considerations.

As we have already seen, each kind of animal or plant is characterized by the appearance of a definite number of chromosomes in the nuclei of its cells at the time when these are undergoing division by mitosis. Although differing greatly in different species the number is usually the same for all the cells of which the body in each case is composed. It is usually an even number, and (with certain exceptions) it remains the same in successive generations of individuals.



FIG. 64.—Ovum of the Horse Worm (*Ascaris megalocephala*) during the Process of Fertilization, showing the male and female Pronuclei (pro), × 770. (From a photograph.)

It will also be remembered that the zygote or fertilized egg from which the individual develops is formed by the conjugation of two gametes, ovum and spermatozoon, and that in this process the nuclei of the gametes, sometimes called the male and female pronuclei, unite, or at any rate co-operate as a single nucleus. Fig. 64 is taken from an actual photograph of an egg of Ascaris in process of fertilization; the spermatozoon has already entered the ovum and the male and female pronuclei (*pro.*) are seen lying side by side in the cytoplasm. Each pronucleus brings with it its own set of chromosomes, and hence the zygote nucleus has double the number of chromosomes possessed by either of the gametes. Thus it appears at first sight that every conjugation or sexual union of gametes (zygosis) must be accompanied by a doubling of the number of chromosomes, and we might therefore expect to find each successive generation with twice as many chromosomes in its nuclei as the preceding one. That this is not actually so depends (in the case of animals) upon the fact that the nuclei of the gametes contain only half the number of chromosomes characteristic of the somatic cells; if the

somatic cells have eight the mature ovum or spermatozoon will have only four, and so on. This reduction of the number of chromosomes (meiosis) is the essential part of the process of maturation which the animal germ cells undergo, and it is




FIG. 65.—Diagram of Gametogenesis.

effected by a modification of the mitotic nuclear division, in which the chromosomes are separated into two groups, half the total number of entire chromosomes going into one daughter cell and half into the other.

In a typical case of spermatogenesis the first stage is the

multiplication of cells (the so-called spermatogonia) derived from the germinal epithelium, in the testis, by ordinary cell-division. Let us suppose the number of chromosomes found in the nuclei of the somatic cells to be eight; it will, of course, remain the same so long as the character of the mitosis undergoes no change, each chromosome splitting into two at every nuclear division. Presently, however, we find the chromosomes arranged in pairs instead of all appearing separately in the mitotic figure, and the cells, which have increased considerably in size by the absorption of nutriment, may now be termed primary spermatocytes. This pairing of the chromosomes (synapsis) marks the onset of the "reducing division"; a nuclear spindle is formed, the paired chromosomes arrange themselves upon it, and the two members of each pair separate and travel towards opposite poles. Thus two new nuclei are formed each with only four chromosomes. The reduction is now complete and the new generation of cells, with reduced nuclei, may be termed secondary spermatocytes. One more mitotic division takes place, this time involving the splitting of each chromosome, so that there is no further reduction in their number, and giving rise to the minute spermatids, each of which develops a long, vibratile, cytoplasmic tail and forms a spermatozoon. Hence we see that each primary spermatocyte gives rise to four spermatozoa, with reduced nuclei containing half the number of chromosomes found in the somatic cells. The essential features of the whole process are represented diagrammatically in Fig. 65.

The process of oogenesis takes place in essentially the same manner; the so-called oogonia,[1] derived from the germinal epithelium of the ovary, multiply and give rise to oocytes. Synapsis and reduction in the number of the chromosomes take place as they do in spermatogenesis, but, owing doubtless to the fact that it takes a comparatively large amount of cytoplasm to form the body of an egg, we find that only one perfect ovum arises from each primary oocyte, the other three forming the "polar bodies." Owing to their minute size as compared with the ovum itself, two of the polar bodies (Fig. 35, A, *p.b.*) appear to be cast out of the latter as it undergoes maturation, while the third is formed by division of the first; it will be clear, however, from a careful study of Figs. 65 and 68 that the

[1] This term is very unfortunately chosen and must not, of course, be confounded with the same term as applied to the female organs of such plants as Fucus.




FIG. 66.—Some Stages in the Spermatogenesis of a Grasshopper (*Stenobothrus viridulus*). (After Meek.)

1. A spermatogonium in mitosis, with seventeen chromosomes (eight pairs and one accessory). Polar view.
2. Resting or growth stage following the mitosis of the spermatogonium. The ordinary chromosomes have become resolved into a network, but the accessory chromosome retains its individuality.
3. Primary spermatocyte formed by growth of 2, preparing for mitosis.
4. Mitosis of the primary spermatocyte, showing the pairing (synapsis) of the sixteen ordinary chromosomes on the nuclear spindle and the accessory chromosome unpaired. Side view.
5. Later stage in the mitosis of the primary spermatocyte, showing separation of the paired chromosomes. Side view.
6. Still later stage in the division of the primary spermatocyte into two secondary spermatocytes; the chromosomes massing at the two poles of the spindle (one mass only will contain the accessory chromosome). Side view.
7. A secondary spermatocyte in mitosis, showing the reduced number of ordinary chromosomes (8) and the accessory chromosome. (The sister-cell would of course contain no accessory chromosome). Polar view.
8. Later stage in the mitosis of the secondary spermatocyte; each chromosome (including the accessory one, which lags behind the others) has split into two parts and the two groups are separating. Side view.
9. A spermatid, formed by division of a secondary spermatocyte with an accessory chromosome. It will form a single spermatozoon.

× The accessory chromosome.

process is merely one of repeated cell-division as in the case of spermatogenesis. The three polar bodies consist almost entirely of chromatin and each of course contains the same reduced number of chromosomes as the ovum itself; they undergo no further development, however, and finally disappear. The truth of the view, now generally held, that the polar bodies are merely ova which have not sufficient cytoplasm to allow of their development, is demonstrated by the fact that in one of the turbellarian flat-worms, according to Francotte, the exceptionally large first polar body may occasionally be fertilized and actually develop as far as the gastrula stage.

The details of the process of gametogenesis vary very much in different cases, but the above outline may be regarded as generally applicable.

In a large number of insects it has been found that the male animal possesses an odd number of chromosomes in the somatic nuclei, due to the presence of a single "accessory" chromosome or "monosome," while the female possesses an even number (one more than the male owing to the presence of two "accessory" chromosomes). This leads to a curious complication in the process of spermatogenesis. The accessory chromosome (Fig. 66, X) can often be distinguished by its appearance from the others, and at the time of synapsis (Fig. 66, 4) it has no mate. Hence in the reducing division the chromosomes are separated into two unequal groups, one of which contains the accessory chromosome while the other does not (Fig. 66, 5). Two kinds of spermatozoa are accordingly produced in equal numbers, one kind with an odd number of chromosomes and the other with an even number.

The matured ova, on the other hand, all have the same number of chromosomes, because the accessory chromosome has a synaptic mate. Fertilization of an ovum by a spermatozoon containing an accessory chromosome results in the production of a female animal with an even number of chromosomes in its somatic cells; fertilization by a spermatozoon which has no accessory chromosome results in the production of a male animal with an odd number of chromosomes in its somatic cells, as shown in Fig. 67.

Thus it appears that the chromosomes, at any rate in some cases, have a very important influence on the determination of sex, and that the latter is not, as has often been supposed, merely the result of nutritional and other environmental influences upon

the developing organism, but a character of far more deeply seated origin, which may affect every cell in the body.

It must not be forgotten that the chromosomes, as such, are only recognizable during the process of mitosis; in the resting condition of the nucleus they appear to be broken up into larger or smaller granules of chromatin scattered through the linin reticulum. The observations on accessory chromosomes above mentioned, and others to be referred to presently, point to the




FIG. 67.—Diagram illustrating the Correlation between the Number of Chromosomes and the Sex in certain Insects. (The numbers of chromosomes given in this diagram are arbitrarily chosen and are obviously different from those which occur in Stenobothrus, as shown in Fig. 66.)

conclusion, however, that, in spite of this, the different chromosomes preserve some sort of individuality from one cell-generation to another. In other words, we have reason to believe that the chromosomes which make their appearance at the onset of each mitosis are, taken each as a whole, the same as those which became disintegrated at the close of the preceding mitosis, though it seems not impossible that the constituent parts of the old chromosomes (chromatin granules, chromomeres or ids), after absorbing nutriment and increasing in size during the resting period, may come together in new combinations to form the new chromosomes each time division of the nucleus takes place.[1]

[1] *Vide* Farmer, Croonian Lecture, Proc. Royal Soc., Ser. B, Vol. 79, 1907.

It is also highly probable, indeed almost certain, that the chromosomes which are derived from the male parent remain throughout life distinct from those which are contributed by the female parent. According to this view every ordinary somatic cell has two sets of chromosomes, paternal and maternal respectively, and this again is strongly supported by the observations on the germ cells of insects above referred to, where all the chromosomes appear to be duplicated, with the exception of the accessory chromosome in the male animal.

There is reason for believing, therefore, that in ordinary cases every paternal chromosome in an unreduced nucleus has an equivalent or "homologous" mate derived from the female parent, and that the phenomenon of synapsis[1] represents a pairing of these homologous paternal and maternal mates. The reducing division which follows on synapsis consists in the separation of the mates once more, one of each pair going to each daughter cell, so that the matured germ cells are left with a single instead of a double set of chromosomes.

If we assume that, as seems highly probable, the chromosomes of each paternal or maternal set are not all identical but differentiated amongst themselves—a differentiation which in some cases is actually visible, as shown in Fig. 66—and that one of each kind is necessary to make up the full complement of the nucleus of the gamete, the importance of the pairing of homologous chromosomes which takes place in synapsis becomes at once evident, for one of each pair goes to each daughter nucleus, which will therefore be certain to receive a chromosome of each kind instead of a chance assemblage. The chromosome of each kind which it receives, however, may be either the paternal or the maternal representative of that kind, and as these, though essentially homologous, may differ from one another to some extent in accordance with individual peculiarities of the parents from which they were derived, it will be seen that the matured gametes may differ widely amongst themselves in their nuclear constitution. This, as we shall see presently, is a very important matter from the point of view of the theories of heredity and variation.

This somewhat complex subject will be rendered more readily

[1] The pairing of the chromosomes, for which we have used the term "synapsis," is spoken of by some writers as "syndesis," and by others as "conjugation." The use of the latter term seems likely to lead to confusion.

intelligible by a careful study of Fig. 68, which represents in a very diagrammatic manner the formation of the polar bodies and the distribution of the maternal and paternal chromosomes in the maturation of a typical animal ovum.

Periodic reduction of the number of chromosomes is clearly a necessary consequence of the sexual process, for a doubling of




FIG. 68.—Diagram of the Maturation of a typical Animal Ovum, showing the Behaviour of the Maternal and Paternal Chromosomes and the Formation of Polar Bodies. (The somatic number of chromosomes is supposed to be four; the maternal chromosomes are shaded and the paternal not, and the differences between the two of each set are indicated by their shapes.)

A, ordinary somatic mitosis in an oogonium, each chromosome split; B, daughter oogonium; C, synapsis in primary oocyte; D, reducing division, formation of first polar body; E, commencement of formation of second (or third) polar body by ordinary mitosis and of division of the first; F, mature ovum with three polar bodies.
chr., chromosomes; *c.s.*, centrosome; *n.m.*, nuclear membrane; *p.b.* 1—3, polar bodies.

the number at every zygosis or conjugation of gametes could not go on indefinitely without some such compensation. In animals, as we have seen, the reduction takes place during the maturation of the sexual cells, but it is by no means necessarily associated with this process, for in the ferns, where alternating sexual and asexual generations are represented by independent and well-developed organisms, the reduction takes place in the process of spore-formation by the sporophyte. Hence the gametophyte (pro-thallus) to which the spore gives rise has in all its somatic cells

the reduced (haploid) number of chromosomes, while the sporophyte (fern plant proper), owing to the fact that it develops from a fertilized ovum and receives a set of chromosomes from each parent, has the full number, or, perhaps we should say more correctly, the double (diploid) number. The same is true of all the higher plants.

Even amongst the Protozoa the phenomenon of nuclear reduction has been observed, and it probably occurs wherever the sexual process takes place. Thus, in the case of Copromonas, the life history of which we have already dealt with, the nucleus of each of the similar gametes, previous to uniting with its mate to form the zygote nucleus, gives off two "polar bodies" which undergo degeneration in the cytoplasm (Fig. 37, 3, 4). In the conjugating Paramœcium, again, those products of division of the micronucleus (Fig. 41, B, C) which undergo no further development may be regarded as polar bodies.




FIG. 69.—Diagram of typical Spermatozoon and Ovum, the former much more highly magnified than the latter.

ax., axial filament; *c.g*, chromatin granules; *cs.*, centrosome; *cyt.*, cytoplasm; *m.p.*, middle piece; *n.m*, nuclear membrane; *nu*, nucleus; *nuls.*, nucleolus; *v.m.*, vitelline membrane; *y.g.*, yolk granules.

As we have already seen the mature gametes throughout both the animal and vegetable kingdoms usually exhibit a very strongly marked sexual dimorphism, which attains its fullest expression in the differentiation into active spermatozoon and passive ovum (Fig. 69).

A typical spermatozoon, as we have also pointed out, closely resembles a flagellate protozoon. It consists of a "head" and a "tail," connected together by a "middle piece" (*m.p.*). The head contains the nucleus (*nu.*), which almost entirely fills it, being covered with only a very thin envelope of cytoplasm. The middle piece contains a centrosome (*cs.*). The tail, or flagellum, is

the active locomotor organ, by the movements of which the spermatozoon swims about; it contains an axial filament (*ax.*) and may or may not be provided with a lateral undulating membrane.




FIG. 70.—Diagram of the Structure of a Bird's Egg.

a c., air chamber; *alb.*, albumin; *ch.*, chalazæ, twisted cords of dense albumin which serve to keep the "yolk" in position; *g.d.*, germinal disk; *nu.*, nucleus; *sh.*, shell; *sh.m.*, shell membrane; *v.m.*, vitelline membrane; *yk.*, "yolk."

A typical ovum is a relatively large, spherical cell with a conspicuous nucleus (*nu.*) surrounded by a large quantity of cytoplasm (*cyt.*), and the whole enclosed in a delicate vitelline membrane (*v.m.*). The actual size of the ovum depends almost entirely on the amount of food material (deutoplasm or yolk), which is stored up in the cytoplasm in the form of granules (*y.g.*). In Amphioxus (Fig. 13, I) the amount of food material is very small, and the egg is only about $\frac{1}{250}$th inch in diameter.

An extreme contrast to the egg of Amphioxus is seen in that of a bird (Fig. 70), where the amount of yolk is enormously large and the active protoplasm is confined to a minute "germinal disk" (*g.d.*), containing the nucleus (*nu.*), which lies within the vitelline membrane (*v.m.*) on the top of the "yolk" (*yk.*), while the ovum proper is entirely enclosed in accessory structures—the "white" or albumin (*alb.*) and the shell (*sh.*), with its lining membrane (*sh.m.*).




FIG. 71.—Ovum of a Rabbit, ×200. (From Marshall's "Vertebrate Embryology," after Bischoff.)

MO, spermatozoa which have penetrated the zona radiata; N, nucleus; NU, nucleolus; Z, zona radiata.

The mammalian ovum, on the other hand, is, like that of Amphioxus, very minute, in the rabbit (Fig. 71) again only about $\frac{1}{250}$th inch in diameter. It is enclosed in an envelope known as the zona radiata (Z), the equivalent of the vitelline membrane, and it

contains very little deutoplasm. This is correlated with the fact that it develops within the body of the parent at the expense of food material derived from the blood of the latter. There is reason to believe, however, as we shall see later on, that the small size of the mammalian egg is a secondary feature.

The plant egg-cell may also be loaded up with food material, so as to attain a large size, as in the green alga, Chara, where the contrast between the minute flagellate spermatozoon and the relatively gigantic ovum, filled in this case with starch grains, is very striking. In the higher plants, however, where, as in the case of the Mammalia, the developing embryo is not dependent for its nutrition upon food supplies stored in the egg-cell, the latter remains quite small, as, for example, in the fern (Fig. 52) and the flowering plant (Fig. 55, *e*).

According to some authorities one of the most important differences between ovum and spermatozoon in animals lies in the fact that the centrosome of the former disappears finally during the process of maturation, the centrosome of the zygote being contributed by the spermatozoon alone. In view of the fact, however, that a definite centrosome is not usually recognizable at all in the higher plants we cannot attribute very great importance to its supposed absence in the animal ovum, and we shall also see presently that centrosomes appear in developing eggs which have not been fertilized by spermatozoa.

We have already had occasion to refer to the existence of some attractive force whereby the male and female gametes are brought together in conjugation. Many observers maintain that this is simply a case of positive chemotaxis, or response to the chemical stimulation of the protoplasm of one gamete by a specific secretion of the other in such a way as to bring about a mutual approach (or an approach of the male to the female gamete).

It is a well-known fact that certain spermatozoa are attracted by specific chemical substances. Thus the free-swimming spermatozoa of ferns and mosses are attracted by weak solutions of malic acid and cane sugar respectively. Those of Coccidium are attracted by nuclear matter discharged from the ovum in the process of maturation.

There can be no doubt that, whether the attracting substance be secreted by the germ cells themselves or by some other part of the organism, chemotaxis sometimes plays a very important

part in bringing the gametes together. So also, of course, do many other factors in various plants and animals, but we must distinguish between factors which act directly upon the gametes, such as chemotaxis, and those which act indirectly through the soma or body of the organism, as for example through the visual and olfactory senses of the higher animals.

It is possible, however, that chemotaxis itself is but a secondary factor which serves to bring the gametes within the range of one another's direct influence. Thus in Coccidium (Fig. 39) the chemotactic action seems to be exhausted after a certain number of spermatozoa have been attracted to the neighbourhood of the ovum and a fresh attraction appears to be exerted by the ovum itself or by its nucleus.

The term cytotropism, or cytotaxis, has been applied to the attraction which, according to some observers, is sometimes set up between two adjacent cells, and something of this kind perhaps comes into play in the mutual attraction of gametes. It can perhaps act only at very short distances, and hence the necessity for some preliminary means of attraction such as chemotaxis. That chemotaxis alone is not a sufficient explanation of the phenomenon in question is suggested by the case of Spirogyra. The conjugation of the gametes in this plant has already been described in Chapter VIII. It will be remembered that the process may take place between the cells of two filaments lying close together, parallel with one another (Figs. 43 and 44), and is then inaugurated by those of the male filament. Each of these cells which happens to lie opposite to a cell of the female filament puts forth a hollow protuberance of its wall, which is presently met by a similar protuberance from the wall of the female cell, the two projections uniting to form a canal through which the protoplasmic body of the male gamete creeps inside the cell-wall of the female gamete to conjugate with the latter. It sometimes happens, however, that, owing to inequalities in the sizes of the cells, there may be a cell in one filament which lies between two cells of the opposite filament and for which there is no mate, all the adjacent cells being coupled. In such cases the solitary cell (Figs. 43 and 44, *S.C.*), if it exhibits any of those remarkable activities which are shown by the conjugating cells on either side of it, merely makes preliminary advances which are prematurely checked, as though there were a competition for partners in which it was unsuccessful. Here it is obvious that

in the case of two cells lying opposite to one another, though not in contact, and though each is enclosed in a firm cell-wall, some stimulus is transmitted from one to the other which calls forth a definite response manifested in the formation of the connecting canals and the conversion of the protoplasmic contents of the cells into gametes. The insufficiency of the principle of chemotaxis to account for these phenomena appears to be indicated by the fact that cells which have no mates do not form either complete connecting canals or gametes, though apparently exposed equally with their neighbours to the influence of any chemical substances dissolved in the surrounding water. A possible explanation appears to be that the solitary cell cannot attract, or at any rate retain, the attention of a mate to stimulate it to complete the process of conjugation.

The primary attraction of the gametes, as we have already observed, probably depends upon some difference of polarity between the two. That it is mutual is demonstrated by such cases as that of Zygogonium (see p. 97) and by the fact that even when the ovum is too heavily laden with food material to take any active part in the process of conjugation it yet in many cases puts out a definite "cone of attraction" towards the advancing spermatozoon, as seen in Coccidium (Fig. 39). What the real nature of this primary attraction between the gametes is we do not know; it may ultimately be explicable in terms of some force already known to us, or it may be one of those cases where it will be convenient to cloak our ignorance by the assumption of some special vital reaction of which we know nothing.

Although as a general rule an egg does not develop unless fertilized by a spermatozoon, this is by no means always the case, and many instances are known of parthenogenesis or the development of unfertilized eggs. This may either be a normal occurrence in the life cycle or it may be artificially induced.

Natural parthenogenesis occurs chiefly in insects, especially amongst the aphides or plant lice. In these animals males and perfect females appear only in the autumn. Fertilized eggs are then laid which hibernate through the winter and hatch in the spring, producing imperfect viviparous females. In these imperfect females eggs are formed which develop parthenogenetically within the body of the parent and give rise to fresh generations of viviparous forms. This reproduction by means of unfertilized eggs

is repeated again and again throughout the summer months and thus the aphides multiply with great rapidity. In the autumn, however, males and perfect females are again produced. The viviparous imperfect females, as well as the males, are generally winged, the perfect females are wingless. We have here another kind of alternation of generations, in which forms which reproduce parthenogenetically alternate with others which exhibit the normal sexual process; to this type of alternation the term heterogeny is sometimes applied. A very large number of parthenogenetic generations may intervene between two sexual ones.

Another well-known case of parthenogenesis is that of the hive-bee, where the eggs laid by the queen may either be fertilized or not, in the former case giving rise to females (workers or queens) and in the latter to males (drones). Other instances occur amongst those parasitic flat-worms known as flukes (Trematoda) and in some Crustacea (Cladocera, the so-called water fleas).

The most remarkable cases of natural parthenogenesis, however, are those to which the special term pædogenesis has been applied, in which the imperfect females do not even wait to attain maturity before producing their offspring, but actually do so in the larval condition, as in Chironomus and some other two-winged flies (Diptera).

In general we may say that parthenogenesis occurs in cases where it is desirable to take advantage of a brief season of favourable conditions to multiply the race as rapidly as possible. It is necessary to make hay while the sun shines. When adverse conditions set in, such as the advent of winter in the case of the aphides, or inability to find a suitable host in the case of parasitic flukes, the vast majority of the race will perish, but a sufficient number will be able to protect themselves in some way (like the encysted cercariæ of the fluke), or a sufficient number of fertilized and protected eggs will be produced (as in the aphides) to tide over the evil time and form the starting points for fresh generations at the first favourable opportunity.

It seems possible, also, that in some cases parthenogenesis may be continued indefinitely without fertilization ever occurring, for in certain species of minute rotifers and crustaceans no males have as yet been observed.

Recent researches have shown that parthenogenesis can be artificially induced in cases where it does not occur naturally at

all, and Professor Loeb[1] goes so far as to maintain that the problem of fertilization is really one of physical chemistry. He holds that the development of the egg is to be regarded as a chemical process which depends mainly on oxidation, and finds that the unfertilized eggs of various animals (sea-urchins and worms) will undergo development (at any rate up to a certain point) after exposure to the action of certain chemical reagents. The unfertilized eggs of a sea-urchin, for example, developed into larvæ after being placed for two hours in sea water, the osmotic pressure of which had been raised about 60 % by the addition of some kind of salt or sugar, but this "hypertonic" solution must contain a sufficient quantity of free oxygen. In another case the unfertilized eggs of the worm Chætopterus were stimulated to develop into larvæ by the mere addition of potash and acids, without the osmotic pressure of the sea water being raised.

Exactly what takes place under these circumstances we do not know, and any speculation on this point is perhaps somewhat premature, but it is quite clear from the experiments of Loeb and other workers in the same field that we can no longer regard fertilization as an indispensable condition of development even in the case of eggs which do not naturally exhibit the phenomenon of parthenogenesis. These experiments may also throw some light upon the process of normal fertilization, especially as regards the nature of the actual stimulus which causes the fertilized egg to begin segmenting.

R. S. Lillie has since shown that in the case of the starfish, "a short exposure of the eggs to temperatures between 32° and 38° C. will cause the development of almost every egg to a free-swimming larval stage," the responsiveness of the eggs depending upon the state of maturation and being very slight after both polar bodies have been extruded.[2]

The casting out of polar bodies during the maturation of the ovum led many of the earlier observers of this phenomenon to believe that the matured ovum is incapable of development because it has an imperfect nucleus, the importance of the nucleus as taking the lead in cell-division having been established at a comparatively early date. The imperfect nucleus of the matured ovum was termed the female pronucleus, and it was

[1] "Die chemische Entwicklungserregung des tierischen Eies (künstliche Parthenogenese)." Berlin, 1909.

[2] See "Problems of Fertilization," by F. R. Lillie (The Chicago University Press, 1919, p. 143).

supposed to be converted into a perfect segmentation nucleus by union with the male pronucleus brought into the egg by the spermatozoon (Fig. 64), and the power of cell-division was supposed to result from this completion of the nucleus. The observations upon which this belief was based were perfectly correct, but the conclusions drawn from them have not been sustained by recent investigations, for in cases of artificial parthenogenesis development may take place in spite of the fact that reduction of the nucleus of the ovum has occurred in maturation and has not been made good by union with the nucleus of a spermatozoon.

In cases of parthenogenesis it is clear that the developing organism is provided only with maternal chromosomes, but we are now also acquainted with cases which form the exact converse to this, only paternal chromosomes being present. Such cases may arise when an ovum is artificially enucleated, so that all the maternal chromosomes are removed, and then fertilized by a spermatozoon. It has actually been found possible in this way to induce the development of enucleated eggs, and the phenomenon, our knowledge of which we owe mainly to Delage, is known as merogony. Although it is obvious that, as a result either of artificial parthenogenesis or of merogony, the developing organism may start life with only half the normal number of chromosomes, it is possible that, as maintained by Delage, this number may be subsequently doubled in some way.

It cannot therefore be the union of male and female pronuclei that furnishes the stimulus to development; this union, or amphimixis as Weismann terms it, has another significance, and, as we shall see later on, is intimately connected with the transmission of inherited characters from parents to offspring.

Boveri, followed by other observers, has put forward the view that the unfertilized egg cannot develop because the centrosome, which is to be regarded as the dynamical centre of the cell, has been eliminated during the process of maturation. It is the spermatozoon that, in the act of fertilization, brings with it the centrosome upon the activity of which the cell-divisions of the fertilized egg depend. This is probably perfectly true in cases of normal fertilization and development in animals, but the view that the centrosome of the spermatozoon supplies the essential stimulus to development seems to be hopelessly negatived by the phenomena of parthenogenesis, in which new centrosomes undoubtedly arise in unfertilized eggs.

It seems therefore as if we were for the present thrown back upon Loeb's hypothesis of a chemical stimulus, which he maintains for normal fertilization as well as for artificial parthenogenesis. In the former case the necessary chemical substances are supposed to be brought in by the spermatozoon.

What it is that stimulates the unfertilized ovum to develop in normally occurring parthenogenesis is another question. It is said, however, that in most cases the second polar body either never leaves the egg or actually re-enters it and that its nucleus takes the place of the sperm nucleus in uniting with the female pronucleus to form the segmentation nucleus ; but the discussion of this very difficult problem is altogether beyond the scope of the present work.

PART III.—VARIATION AND HEREDITY

CHAPTER XI

Variation—Meristic and substantive variations—Fluctuations and mutations—Somatogenic and blastogenic variations—Origin of blastogenic variations.

The term variation is used in more than one sense; it may be defined in the first instance as the process whereby closely related organisms come to differ amongst themselves. It is a matter of everyday experience that neither animals nor plants exhibit absolutely fixed and constant characters, which are handed on without alteration from parent to offspring. This is very well seen in the case of human families, in which there is rarely any difficulty in distinguishing the different members by more or less pronounced and characteristic individual traits. One may be fair and another dark, one short and another tall, one with brown eyes and another with blue, one clever and another stupid, and so on. In this way they vary amongst themselves and deviate from the common parents of the family often to a very considerable extent.

We cannot, however, avoid extending the use of the term variation from the process itself to the results of that process, and speaking of organisms as exhibiting variations, but this usage is not likely to cause any confusion.

Variations are of many kinds and may be classified in different ways according to the point of view from which we regard them.

Meristic variations, which are variations in the number of the repeated parts of an organism, are sometimes contrasted[1] with substantive variations, which depend upon the structure (including shape, size and colour) of the organism or its parts.

Small fluctuating or continuous variations, which fluctuate

[1] Bateson, "Materials for the Study of Variation." (Macmillan & Co., London 1894.)

about a typical condition, are contrasted with sudden, discontinuous variations, or mutations.

Somatogenic variations, which affect the body of the organism and are acquired in the life-time of the individual, are contrasted with blastogenic or germinal variations, which arise as a consequence of some modification in the germ cells.

These three methods of classification obviously overlap one another. Thus a meristic variation may be continuous or discontinuous, somatogenic or blastogenic, and so on, but it will be convenient to deal with each group separately.

Meristic or Numerical Variations. In a very great number of organisms certain parts are repeated with a greater or less degree of regularity and constancy, and it is upon this repetition that the symmetry of the organism very largely depends. An ordinary star-fish, for example, is radially symmetrical, with five similar arms or rays radiating from a common centre; meristic variation, however, may give rise to four-rayed or six-rayed individuals. The common jelly-fish, *Aurelia aurita*, again, usually has four principal radii, but specimens are occasionally found with two, three, or six.

All vertebrate animals, on the other hand, and many invertebrates, are bilaterally symmetrical, and at the same time metamerically segmented, *i.e.* with repetition of similar parts in linear series one behind the other. The vertebral column, for example, is made up of a larger or smaller number of morphologically equivalent units, the vertebræ, to which the ribs are attached in linear series on each side, and the limbs are arranged in two pairs, in each of which the same fundamental structure can be traced. Many instances occur in different animals of variation in the number of vertebræ, and in man the occasional occurrence of thirteen ribs instead of the normal twelve on each side is well known. Cases of polydactylism, or the development of extra digits on hand or foot, also come under the head of meristic variation.

In the vegetable kingdom, where the repetition of similar parts, such as the leaflets of leaves, is even more conspicuous than amongst animals, meristic variation is again a common phenomenon. A clover leaf, for example, normally consists of three leaflets, but the occasional discovery of a specimen with four has been a source of satisfaction to superstitious folk from time immemorial. We meet with similar variations in the number

of petals in flowers and the number of flowers in inflorescences. An example of this will be given later on in the case of the grape hyacinth.

Substantive Variations. Examples of this type of variation are seen in the shape, size and colour of the human body and of its various parts. The total height of the individual, the shape of such features as the nose, ears and fingers, the colour of eyes and hair, are all subject to very great variation. The same is true of the shape and size of leaves and the colour of many flowers. Numerous physiological variations, which doubtless depend upon unrecognized and perhaps unrecognizable differences in structure, may also be classed under this head, as for example the variations in the egg-laying powers of fowls and the milk-giving powers of cows, and in the percentage of sugar present in the roots of the sugar beet.

Fluctuating Variations. The variations which come under this heading are also sometimes spoken of as normal or continuous. They may be either meristic or substantive. They are characterized by the fact that they pass into one another by small or even insensible gradations, which fluctuate on either side of a typical condition, so that the extent to which a given organism (or part of an organism) varies can be graphically represented in the form of a curve. Fluctuating meristic variations lend themselves most readily to this graphic method of treatment, for all we have to do is to count the numerically varying parts in a sufficiently large number of cases and plot our curve accordingly.

The manner in which this is done is represented in the accompanying diagram (Fig. 72), which expresses graphically the results obtained by counting the number of flowers in 202 inflorescences of the common grape hyacinth (*Muscari* sp.). The number of flowers in an inflorescence ranged from 20 to 42, forming 23 classes, and the number of inflorescences in each class ranged from 1 to 29 (frequencies).

The base line of the diagram is divided into a number of equal parts (abscissæ) corresponding to the classes. At one side an ordinate is erected on the base line and divided into a number of equal parts corresponding to the frequencies (from 1 to 29) of the inflorescences belonging to each class. Lines are then ruled parallel to the base line and to the ordinate respectively, so as to divide the paper into a number of equal squares (or the

proceeding may be simplified by working with already squared paper). The record is completed by shading in an appropriate square for each inflorescence, the position of the square being determined by the number of flowers which the inflorescence contains and by the number of similar inflorescences which have preceded




FIG. 72.—Frequency Polygon, representing Fluctuating Variation in Inflorescences of the Grape Hyacinth.

it in the enumeration. Thus an inflorescence with twenty-five flowers must be represented by a square added to the column above the number 25 on the base line, and so on. If now we join the middle points of the tops of all the columns by straight lines, we get a zig-zag line which represents the curve of variation as determined by our actual observations. It is obviously a very imperfect result, but its imperfection is undoubtedly due

in the main to the fact that the number of observations upon which it is based has not been sufficiently large to give a fair average.

The larger the number of individual cases examined and recorded the more closely will our zig-zag line approximate to a regular curve. Even as it is, with all its imperfections, it shows certain very characteristic features. It rises steeply in the middle and falls away from the highest point, or mode, at first suddenly and then more gradually, on either side. This is a graphic representation of the facts, (1) that the most frequently occurring number of flowers in the inflorescence (28) lies not very far from midway between the two extremes, and (2) that the




FIG. 73.—Fluctuating Variation in Human Stature. (From Lock.)

more the number of flowers deviates from this on either side the smaller is the corresponding number of inflorescences; or, to put it more generally, the number of individuals exhibiting any given degree of deviation from the typical condition of the species is inversely proportional to the amount of that deviation.

Fig. 73 is a diagram constructed on the same principles as the above, but based upon totally different material and a very much larger number of observations. It is taken from Mr. R. H. Lock's work on "Variation, Heredity and Evolution," and shows the variation in stature observed amongst 4,426 British members of the University of Cambridge. The dots in this diagram correspond to the middle points of the tops of the vertical columns in the preceding one. The statures are reckoned in the nearest

whole numbers of inches. It is clear that a zig-zag line formed by joining the dots in the diagram would approximate fairly closely to the curve actually drawn.

The normal curve of variation agrees very closely with what mathematicians term the curve of frequency of error, which is the graphic representation of the mode of occurrence of chance deviations from a mean or average and may be derived from the theory of probability. Such a curve may be experimentally produced by drawing a vertical line on a target and firing a large number of shots at it. There will be a more or less strongly marked tendency for the shots to hit the line, but various causes may prevent them from actually doing so. Most of them will probably strike to the right or left of the line and fairly near it, but a few will probably be very wide of the mark on either side. If the distances of the striking places from the vertical line be measured and tabulated the result may be expressed in the form of a curve which, if the number of shots be large enough, will closely resemble the curves described above. The fact that the normal curve of fluctuating variation for any kind of organism is practically identical with the mathematical curve of frequency of error suggests very forcibly that the variation in question is due to chance or accident causing each individual in the course of its development to depart more or less from the typical condition of the species to which it belongs. These deviations must depend upon numerous factors. They are to some extent, no doubt, due to the direct influence of the environment, such as the effect of nutrition upon the size of the organism, but they may also depend largely upon the varying characters of the germ cells from which the organism develops, and especially upon the permutations and combinations which happen to take place in the maturation of the germ cells and in their sexual union.

In short, the general tendency is doubtless for each individual to conform to the type of the species to which it belongs, but many accidental circumstances combine to prevent the realization of this tendency and deviations from the type take place in accordance with the laws of chance. It should be noted, however, that the curve of variation is by no means always symmetrical.

Mutations. The term mutation, or discontinuous variation, is applied to the process whereby new and more or less conspicuous characters appear suddenly and spontaneously, without any

obvious reason. In extreme cases the organisms exhibiting such mutation are often spoken of as sports or monstrosities; the latter term, however, is also frequently applied in the case of purely artificial modifications, which must not be included under this heading. Such artificial modifications are not, at any rate as a rule, inherited by future generations, while true mutations usually, if not invariably, are.

Mutations differ from fluctuating variations not only in that they usually deviate more widely from the type of the species, but also in the much greater rarity of their occurrence and in the fact that they do not fluctuate about the old mean or average condition but about a new one of their own; nevertheless it may be questioned whether we can logically draw a hard and fast distinction between the two.

Mutations may be either meristic or substantive. Human beings with six fingers or toes, in place of the normal five, are not infrequently met with, and this meristic mutation (hexadactylism) is well known to be transmitted by heredity.

The classical instance of the Ancon or otter sheep, on the other hand, affords one of the best known examples of substantive mutation. To quote the words of Huxley,[1] "It appears that one Seth Wright, the proprietor of a farm on the banks of the Charles River, in Massachusetts, possessed a flock of fifteen ewes and a ram of the ordinary kind. In the year 1791, one of the ewes presented her owner with a male lamb, differing, for no assignable reason, from its parents by a proportionally long body and short bandy legs, whence it was unable to emulate its relatives in those sportive leaps over the neighbours' fences, in which they were in the habit of indulging, much to the good farmer's vexation." The inheritance of this peculiarity was so strong that this single individual actually became the starting point of a new breed.

Mutations, more or less pronounced in character, are also not infrequently met with in the vegetable kingdom. Foxgloves, for example, are sometimes found in which some or all of the petals are converted into stamens, and it has been proved by experiment that this peculiarity is handed down from parent to offspring.

Professor Hugo de Vries has, as is well known, made a special study of mutation amongst plants. In the year 1886 this disguished botanist found a large number of specimens of the evening

[1] "Darwiniana," p. 35.

primrose, *Œnothera lamarckiana*, growing in a field near Amsterdam, whither they had made their way from a neighbouring garden. The plants were in a state of intense variability and their seeds gave rise to several quite distinct new forms, which, if they had occurred in a state of nature, would have been considered as separate species. Professor De Vries attributes great importance to mutations as the starting points of new species, which he believes to arise in this sudden manner rather than by fluctuating variation.[1] We shall discuss this point in a subsequent chapter.

The difference between fluctuating variation and mutation is sometimes illustrated by means of the model known as Galton's polygon (Fig. 74). A thick slab of wood is cut into the form of a polygon, with unequal sides and capable of resting in a position of more or less stable equilibrium upon any of its edges, the




FIG. 74.—Model of a Polygon in two Positions, illustrating the Difference between Fluctuating Variation and Mutation.

degree of stability depending upon the position of the centre of gravity above the edge upon which it rests.

The polygon may be supposed to represent an organism, or rather a number of successive generations of an organism, whose stability (or adherence to type) tends to be more or less disturbed by the unknown factors which cause variation. If the model be pushed it may be made to rock backwards and forwards on either side of a mean or average position, and if the oscillation does not exceed certain limits it will return to rest in that position. This oscillation may be compared to fluctuating variation. If the disturbing force be sufficiently great, however, the model will topple over into a new position of stability and come to rest on another edge. This may be compared to the process of mutation or discon-

[1] "The Mutation Theory." Trans. by Farmer and Darbishire. London, 1910

tinuous variation, whereby an organism acquires a new type of structure.

Somatogenic Variations. Characters are said to be somatogenic or "acquired" when they arise in the life-time of the individual exhibiting them and owe their origin to the direct influence of the environment upon the soma or body. They are, usually at any rate, not transmitted by heredity to succeeding generations, except perhaps to a very limited and inappreciable extent.[1] Under this heading are included the effects of use and disuse of organs, and numerous cases in which modifications of the body are artificially produced, as well as those in which they are due to natural causes.

Amongst the effects of use and disuse we may mention, on the one hand, the enlargement or the atrophy of special organs consequent upon the extent to which they are employed, and, on the other, the effects of education. The muscles of an athlete may be greatly increased in size by constant use, and similarly if one of the two kidneys be removed the other, having more work thrown upon it, becomes enormously enlarged; but we should not expect these modifications to be handed on to the next generation. Children have been taught to speak ever since man first became differentiated from his speechless ancestors, but every child has to learn the art anew and if brought up amongst foreigners will come to speak a language different from that of its parents.

The docked tails of fox terriers and the slender waists of certain women are artificially produced somatic modifications which are well known not to be inherited. They are merely disfigurements, effected by easily recognizable mechanical agencies.

Much more remarkable and difficult to understand are those cases in which the addition of specific chemical reagents to the water in which aquatic larvæ are developing produces such definite and extensive modifications of structure as to give rise to veritable monstrosities. The "Lithium larvæ" of sea-urchins and frogs have long been known and more recently Stockard has described[2] the "Magnesium larva" of the fish *Fundulus heteroclitus* (Fig. 75). He found that, when the eggs of this fish are subjected to the influence of magnesium chloride dissolved in sea water, a large percentage of the larvæ acquire a "cyclopean" character, with a single median eye in place of the ordinary pair.

[1] This question will be discussed in Chapter XIV.

[2] "Journal of Experimental Zoology," February, 1909.

Such larvæ may hatch and swim about in a perfectly normal manner, but it is not known whether they can be reared to the adult condition. These observations seem to indicate that the cyclopean monsters which sometimes occur in man and other mammals may also be somatogenic variations due to some unknown environmental influence.

Blastogenic or Germinal Variations. In this category are included those variations which are believed to owe their origin to some modification in the germ cells from which the organism exhibiting them has developed.

It is important to observe that the term congenital, sometimes used in this connection, is not synonymous with blastogenic, for it is obvious that animals which, like the mammalia, remain within the womb of the mother during the early stages of development, may come to develop purely somatogenic characters before birth, due to environmental influences acting *in utero* (*e.g.* poisoning of the fœtus due to parental alcoholism).

It is very doubtful, as we shall see later on, whether we can really draw any absolute distinction between blastogenic and somatogenic characters, and it seems by no means impossible that somatogenic modifications may sooner or later make an impression upon the germ cells and thus ultimately become blastogenic.

Blastogenic modifications are from their very nature as attributes of the germ cells handed on by heredity from generation to generation. All true mutations must be regarded as blastogenic and many so-called fluctuating variations may also perhaps belong to the same category.

The modifications of the germ cells by virtue of which the offspring come to differ to a greater or less extent from their parents are often attributable in large measure to permutations and combinations of different characters which take place in the sexual process (amphimixis) and the preceding nuclear reduction, and Professor Gates has shown that, in the case of Œnothera, mutation may be correlated with abnormal distribution of the chromosomes in the reducing division. It has long been suspected, however, that the germ cells themselves, apparently independently of the body in which they are enclosed, may be influenced by the environment to which an animal or plant is exposed, and the observations of Tower[1]

[1] "An Investigation of Evolution in Chrysomelid Beetles of the Genus Leptinotarsa," by William Laurence Tower. (Publications of the Carnegie Institution, Washington, 1906.)




FIG. 75.—Free-swimming Larvæ of *Fundulus heteroclitus*. (From Stockard.)

A. Normal larva, with anteriorly placed mouth (M).
B. Incompletely cyclopean larva, with the two eyes joined and occupying the position usually taken by the mouth.
C. Completely cyclopean larva, with single antero-median eye. Dorsal aspect.
D. Lateral aspect of same, showing the ventral mouth (M).
E. Ventral aspect of same; *ys*, yolk sac.

upon beetles of the genus *Leptinotarsa* may be referred to in this connection.

This observer considers that all permanent variations in these beetles, so far as can be discovered, arise in the germ cells and are in no wise the results of inherited somatic modifications. He attributes their appearance to the direct action of the environment upon the germ plasm and supports his views by a series of very interesting experiments. He subjected the parents to environmental stimuli of various kinds during the growth and maturation of their germ cells, and then, after the ova had been fertilized, allowed the development of the young to take place under normal conditions. The parents, having already reached their final state, were not themselves visibly affected by the stimuli, but a large percentage of the offspring showed surprising modifications which were strictly inherited. These modifications appear to be in no way adaptive. They seem to bear no relation to the nature of the stimulus which calls them forth and to be of no value to the organism in the struggle for existence.

We may cite one example of Tower's experiments. Four males and four females of *Leptinotarsa decemlineata* (the potato beetle) were exposed during the earlier part of the laying period (the eggs being matured and laid in successive batches) to extremely hot, dry conditions accompanied by low atmospheric pressure. The eggs were removed as soon as laid and reared under natural conditions. From 506 larvæ thus reared 96 adult beetles were obtained, of which 82 were of a form known as *pallida*, 2 of a form known as *immaculothorax*, and the remainder unmodified During the later part of the laying period the same parents were kept under normal conditions and yielded 319 eggs from which 61 normal beetles were obtained and none of the other forms, and these normal beetles continued to breed true for three generations, after which they were killed.

The two specimens of the *immaculothorax* form obtained in the earlier part of the experiment unfortunately died from disease, as also did all but two of the *pallida*. The remaining two, however, both being male, were crossed with normal females, yielding hybrid offspring with the *decemlineata* characters dominant, and these hybrids, breeding *inter se*, gave offspring which separated out in a characteristic Mendelian fashion[1] into *pallida*, *decemlineata* and hybrids again. There can be no

[1] See Chapter XIII

question therefore that the *pallida* characters, first due to modification of the germ cells by the action of changed environment, were strictly heritable.

It should be observed that the forms *pallida* and *immaculothorax* also occur occasionally, but rarely, in a state of nature as sports or mutations, a fact which suggests that sports or mutations in general may owe their existence to the apparently direct action of the environment upon the germ cells. It is, of course, possible, or even probable, that the change in the environment merely acts as a kind of liberating stimulus, which enables characters already latent in the germ cells to express themselves in the developing organism, which, under normal conditions, they are unable to do.

We shall have to return to the question of the origin of blastogenic variations in future chapters.

CHAPTER XII

Heredity—General observations—Pre-formation and epigenesis—The common-sense view of heredity—Weismann's theory of the continuity of the germ plasm—The nucleus as the bearer of inheritable characters.

When we study the life histories of the unicellular Protista we find ourselves face to face with the problem of heredity in its simplest form. The Amœba divides into two parts by simple fission, the division of the cell body being preceded by that of the nucleus. The two daughter cells exactly resemble one another, and, except in point of size, also resemble the parent, while the latter ceases to exist as an individual in the very act of reproduction. Here we may suppose that we are dealing with a division which is qualitative as well as quantitative, that every organ possessed by the parent cell is divided into two similar parts and the total inheritance thus fairly apportioned between the offspring, which will therefore be exactly similar to one another and will need only to feed and grow in order to become exactly similar to the parent.

The young Amœbæ may be supposed to resemble the parent because they arise by duplication of the parent and of its organs;[1] moreover, there is a perfect continuity of the living substance, or protoplasm, of which the body is composed from one generation to the next, and the whole of the body of the parent is used up in providing the bodies of the offspring. Thus, although the individuality of the parent comes to an end, the Amœba never dies, for there is never anything left over to die, and, barring accident, it goes on multiplying for ever. We have here a typical illustration of the so-called immortality of the Protista.

The case is very different amongst the higher plants and animals. Here, as we have already seen, each individual starts

[1] We cannot, however, say this of all Protista, for in many cases the division takes place asymmetrically and entirely new organs have to be formed by one or both of the daughter cells, as, for example, in the transverse fission of Bodo (Fig. 38, D—F) In such cases it looks as if the nucleus might be the real seat of the inherited tendencies, and as if it were able, by its influence, to mould the daughter cell into the form of the parent.

its life as a single cell—the fertilized ovum or zygote—which is strictly comparable to a unicellular protistan. Like the Amœba it divides (under favourable circumstances) repeatedly, but the products of division, instead of separating from one another and going each its own way as an independent unicellular organism, all remain together and co-operate with one another to form a multicellular body of greater or less complexity. The cells of which this body is composed become differentiated and specialized in various directions. In so doing the vast majority of them lose their faculty for independent existence, and when their powers of division have become exhausted the tissues into which they are combined become worn out and ultimately die. Thus the body or soma, as a whole, must suffer death sooner or later. The only cells which are, even potentially, exempt from this fate are the germ cells. These, instead of becoming highly specialized constituents of the soma, remain in the condition of more or less independent Protista, and have the power of separating sooner or later from the parent body. Like most of the Protista they have also the habit of conjugating in pairs and thereby renewing their powers of cell-division, and thus arise the zygotes or fertilized eggs from which the new individuals take their origin.

The eggs from which the individuals of different kinds of plants and animals arise are for the most part extraordinarily similar to one another. The ovum of a rabbit, as we have already seen, is a minute nucleated mass of protoplasm about $\frac{1}{250}$th inch in diameter, that of a human being is a similar but somewhat larger cell, and if the ova of a hundred different kinds of mammals were mixed together it would be an extremely difficult, if not impossible task to sort them all out, even after the most minute microscopical examination. Even where conspicuous differences exist, as between the eggs of a mammal and those of a bird, these are due almost entirely to the development of accessory features, such as protective envelopes and food-yolk, which have little to do with the nucleated mass of protoplasm which constitutes the really vital part of the egg. Yet each kind of fertilized egg, if it develop, will give rise to an organism resembling the parent from which it was itself derived. Moreover, the resemblance will not be merely a general one, it will be specific, and probably even more than specific, for it may include minute individual characters peculiar to one or other of the

parents. Everyone is familiar with cases of this kind. It may be some abnormality of fingers or toes, or a lock of white hair in some special situation in a dark-haired man, or even some trifling nervous habit, that is thus indelibly impressed upon the organism and handed on from one generation to another.

Two sharply contrasted views as to what takes place in the development of the egg were maintained by the older embryologists, and, in a modified form, survive to the present day. The so-called "evolutionists," or "pre-formationists," maintained that the egg (or sperm) contains in itself a complete miniature of the organism into which it develops, and that the process of development consists simply in an unfolding ("evolution") and growth of this miniature. This idea, especially associated with the name of an eighteenth century naturalist, Charles Bonnet, when carried to its logical conclusion, involves the further supposition that every egg contains in miniature the bodies of all future generations, like nests of boxes one within the other.

In opposition to this view the upholders of the theory of "epigenesis" maintained that there is no pre-formation of organs in the egg but that the different parts of the adult organism become gradually differentiated from the simple undifferentiated ovum during the course of development. This view, which is said to have originated with Aristotle and was strongly supported by the great pioneer embryologist C. F. Wolff about the middle of the eighteenth century, almost entirely superseded the crude ideas of the pre-formationists, but at the present day the latter are being revived to some extent, but in a more refined form, as a result of modern experiments in embryology. It cannot be disputed that in some cases certain parts of the adult organism can be traced back to corresponding portions of the egg, which cannot therefore be entirely undifferentiated, and it is probable that in the end the truth will be found, as in so many other cases, to lie in a compromise between the two extreme views.

The great problem which has to be solved by any theory of heredity is—How is it that the apparently simple germ cells of a multicellular organism are able to develop into a complex body consisting, perhaps, of hundreds of different kinds of cells, each specialized in its own way for some particular function, and the whole similar in almost every particular to the parent form? It may help us in the consideration of this question if we begin with a simple analogy, with which everyone is more or less familiar, the

baking of bread.[1] We all know that the successive batches of loaves turned out from the same bakery resemble one another very closely, and are likely to differ from those turned out by another baker. We also know that the resemblance between the loaves is dependent on two sets of factors, *viz.*, the peculiarities of the dough and the conditions to which it is subjected in the process of baking. If any of these factors are changed the result will vary in a corresponding manner. If the dough be mixed with milk instead of water, or if sugar be added instead of salt, you will get a different kind of loaf. A loaf baked in a tin differs from a cottage loaf, and the result may be profoundly modified by changes in the temperature of the oven, or by variations in the length of time during which the baking is allowed to continue. If, however, you start with precisely the same kind of dough and subject it to precisely the same conditions, the resulting loaves must turn out the same, for like causes must always produce like effects.

It is very similar in the complex processes of heredity. The dough is represented by the germ plasm, or protoplasm of the germ cells, and the loaves by the individual organisms which are developed therefrom. If the germ plasm from which the young organism develops is exactly like the germ plasm from which the parent developed, and if it is exposed to exactly the same conditions during the course of development, the offspring must resemble the parent. This is what may be called the common-sense view of heredity, and there is no mystery whatever about the matter.

It is easy to demonstrate by experiment that the conditions, or environment, to which the developing organism is subjected, play a profoundly important part in determining the result. One of the most remarkable instances of this is the case of the " magnesium larva " of the fish *Fundulus*, described in the preceding chapter (see Fig. 75), in which the addition of a small quantity of magnesium chloride to the water in which the eggs are developing causes the young fish to produce a single eye in the middle of the head instead of one on each side. Every farmer's wife knows that a hen's egg will only develop into a chick when incubated within certain very narrow limits of temperature (about 104° F.), and one has only to consider what takes place in the highest group of animals, the mammalia, in order to appreciate the supreme importance of securing

[1] I was unaware, or had forgotten, when I wrote this, that Professor J. Arthur Thomson had made use of a very similar analogy in his excellent work on Heredity (London, John Murray), but he compares the germ plasm to the leaven, not to the dough. Perhaps it is a better comparison.

and maintaining exactly the right environment for the developing young. The womb of the mother is literally an oven within which the germ plasm is baked at a uniform temperature, and also fed on exactly the right kind of food ; any variation of the conditions, as, for example, by alcoholic poisoning, is likely to lead to disastrous results.

It is difficult to distinguish sharply between the two sets of factors which, between them, determine the character of the developing organism, *viz.*, those which exist already in the germ plasm and those which are usually referred to as environmental. It is commonly recognized that there is an internal as well as an external environment, that the organism is influenced by factors operating within its own body as well as by factors operating from without, and it is tolerably certain that many factors, although they actually exist in some form in the germ plasm itself, do not produce their effects until the organism is more or less advanced in development. Hence it is very difficult to define exactly what is meant by the term " heredity." We may perhaps say that it is the sum total of the processes whereby the young organism comes to resemble the parent, but we must remember that the environment must be inherited as well as the material substance of which the body is composed. The latter, indeed, can hardly be said to be inherited to any greater extent than the former, for the fertilized egg may contain but an infinitesimal fraction of the substance which goes to make up the adult body, the remainder being taken in from the external world during the process of growth.

There is one very important respect in which our analogy between the production of new loaves of bread and the development of new organisms breaks down. For every batch of bread a new lot of dough has to be mixed. The germ plasm, on the other hand, may be said to mix itself. It constantly increases in quantity by the absorption of nutriment which it converts into protoplasm, and there is always enough left over to produce the next batch of organisms. This, at least, is the view maintained by the late Professor August Weismann in his celebrated theory of the " Continuity of the Germ Plasm." [1]

It was Weismann who conceived of the germ cells as equivalent to so many unicellular Protista, capable of multiplying indefinitely by simple fission. In this process the protoplasm of each cell is

[1] For full accounts of this theory see the English translations of Weismann's two chief works on the subject, "The Germ Plasm" (Contemporary Science Series, 1893) and "The Evolution Theory" (Edward Arnold, 1904).

directly handed on to its daughter cells, as in the case of a dividing amœba, and thus the continuity of the germ plasm is a literal fact. He laid great stress upon the distinction between germ cells and somatic or body cells. The former remain comparatively undifferentiated themselves, but have the power, under suitable conditions, of giving rise by division to both germ cells and body cells. The latter sooner or later become differentiated into the various tissue cells of which the body is composed—epithelial cells, muscle cells, nerve cells, and so forth—and, becoming highly specialized, each in its own particular way, usually lose the power of acting as germ cells and either cease to divide at all or give rise only to daughter cells of their own kind. We know now, however, that in certain more or less exceptional cases even highly differentiated tissue cells may become "de-differentiated," and give rise to germ cells. This must mean that they have retained a certain amount of the original germ plasm with all its potentialities of development. In other cases, as we have seen in a previous chapter, the distinction between germ cells and somatic cells becomes finally and apparently irrevocably established at a very early stage in individual development. This is clearly shown, as Weismann points out, by the well-known fact that in the case of the higher animals if the gonads—ovaries or testes—be excised even at a very early stage of development, complete sterility always ensues, for no new germ cells are ever formed under these circumstances.

A variable number of cell generations may intervene between one lot of germ cells and the next, but the germ plasm itself is directly continuous through all these generations and, of course, is carried on in the same way, by cell division, from generation to generation of complete organisms. The early segregation of germ cells from somatic cells, observed in so many cases, is no doubt a strong point in favour of Weismann's views, but the theory of the continuity of the germ plasm does not depend upon this phenomenon.

Certain phenomena, such as the regeneration of lost parts in many animals and the propagation of plants by buds and cuttings, necessitate the supposition that some at any rate of the somatic cells must retain a more complete sample of the ancestral germ plasm than is necessary for their own development. For the hereditary substance of any particular cell Weismann adopts Nägeli's term "idioplasm," and in order to account for the phenomena just referred to he is obliged to postulate the existence, in the somatic cells in question, of "accessory idioplasm," which is only called

into activity under exceptional conditions, as, for example, when it becomes necessary for a crab to regenerate a lost limb or for an earth worm to renew a portion of its body which has been bitten off by a bird or chopped off by a spade.

If the germ plasm, as Weismann supposes, remains unaffected (except, perhaps, through nutrition) by the various influences to which the body is exposed, being, indeed, to a large extent protected by the body from the action of the environment, we actually have each individual starting from much the same kind of material as its parent, and one of the conditions of heredity is established. In accordance with this view the offspring can hardly be said to inherit its characters from the parent at all, but both derive them from a common source, the continuous stream of germ plasm.

Weismann's theory of heredity, however, goes much further than this. He identifies the germ plasm with the chromatin substance in the nuclei of the germ cells, and in this respect makes a great advance upon his predecessors, to some of whom, especially the late Sir Francis Galton, the general idea of continuity was also familiar. To this chromatin he attributes great complexity of structure and, above all, he postulates the existence therein of certain ultra-microscopical units to which he gives the name "determinants." Each of these is supposed to be responsible in some way or other for the development of some particular part of the adult organism. We have thus introduced the idea of internal factors in the germ plasm itself, which exercise each a specific influence upon the developing individual.

The determinants of Weismann's theory are by no means simple bodies, for each is supposed to be made up of a number of "biophors." The biophors are the lowest vital units but each in its turn is made up of molecules in the chemical sense of the term. On the other hand the determinants are supposed to be grouped in units of a higher order termed "ids," each of which is a complete ancestral germ plasm, theoretically sufficient in itself to determine all the different features of an entire organism. The ids may in some instances correspond to the chromosomes, but these appear generally to be composite bodies ("idants") made up each of a large number of ids (chromomeres). The determinants, and of course the biophors also, are far below the limits of visibility even with the aid of the most powerful microscope; the ids, however, frequently appear during the process of mitosis and may give the spireme

thread or the chromosomes into which it divides a characteristic beaded appearance (Fig. 32, B). Biophors, determinants, ids and idants must all be looked upon as living entities, growing by the absorption of nutriment and multiplying by division.

Although, in the light of recent investigations, we are unable to retain Weismann's views as to the structure of the germ plasm in their entirety, they undoubtedly contain a large element of truth, and are strongly supported by the remarkable phenomena that accompany cell division.

The entire process of mitosis serves to emphasize the importance of the chromatin substance of the nucleus. It is evidently of the utmost consequence that this substance should be accurately apportioned between the daughter cells. We accordingly find the elaborate mechanism of centrosomes and nuclear spindle, and a splitting of each individual chromosome, which takes place longitudinally when the chromosomes themselves happen to be elongated in form. If, as Weismann maintains, and as can actually be demonstrated in many cases, each elongated chromosome is made up of a row of chromomeres or ids, which may be supposed to differ to some extent from one another as to the determinants which they contain, it is obvious that longitudinal splitting of the chromosome is the only way in which a qualitative as opposed to a mere quantitative division of the hereditary substance can be brought about. This mode of division, then, otherwise difficult to explain, is fully intelligible in accordance with Weismann's theory.

It is not necessary to suppose, moreover, that such division always results in identical daughter chromosomes. We might assume either that all the individual ids divide into similar halves, containing similar determinants, in which case the two daughter chromosomes would be exactly alike, or that some or all of the ids divide each into two dissimilar halves containing different determinants, when the daughter chromosomes would be unlike each other. In the former case the division would be said to be integral and in the latter differential. It is by differential division that Weismann believes the histological differentiation of the soma to be brought about. It must be admitted, however, that there is no direct evidence for the occurrence of differential division of the kind postulated by Weismann, and that the belief in such a process is inconsistent with modern views as to the arrangements of " factors " in the chromosomes.

When we consider the phenomena of maturation and fertilization

we find them strongly corroborative of Weismann's views. We have already pointed out, in Chapter X., that each particular species of plant or animal is, as a general rule, characterized by the appearance of a definite and constant number of chromosomes in all the cells of the body during the process of mitosis. At some period in the life-cycle, however, in typical plants during the process of spore-formation and in animals during the maturation of the ova and spermatozoa, this number is reduced to half by separation of the entire chromosomes into two groups, one of which passes to each of two daughter cells. Thus the mature germ cells have only half the number of chromosomes characteristic of the species (or, in the case of typical plants, of the sporophyte generation). The full number is made up again by the union of male and female gametes to form the zygote or fertilized egg.

To the combination of the maternal and paternal chromosomes in the nucleus of the zygote Weismann has given the name amphimixis, and he sees in this mingling of ancestral germ plasms the cause of that mixture of paternal and maternal characters which we commonly find in animals and plants. If, for the sake of simplicity, we imagine that each chromosome consists (as appears to be sometimes the case) of only a single id or chromomere, and that eight of these are present in the nucleus of the mature germ cell, we may represent the effect of repeated amphimixis upon the constitution of the nucleus by means of the diagram (Fig. 76), which shows how the ids must become more and more diversified in each successive generation. In this diagram A represents an unreduced nucleus composed of sixteen ids, eight paternal and eight maternal, all the paternal and all the maternal ids respectively being supposed to be alike. After reduction and union with another mature germ cell containing also only one kind each of paternal and maternal ids, but both differing in some respect from those of its mate, the nucleus of the next generation might contain four kinds of ids, two paternal and two maternal, as shown in B, while in the next generation there might be eight kinds, as shown in C, and in the next sixteen, as in D.

We must, then, in accordance with the views of Weismann, look upon the germ plasm of any one of the higher organisms as being made up of a larger or smaller number of ids, each one representing the inheritance received from some more or less remote ancestor on the paternal or maternal side, though of course

it is quite possible that there may be a number of ids of the same kind. When, during the process of maturation, half the total number of chromosomes (each made up of one or more ids) are eliminated from the germ cell, it appears to be largely a matter of chance which shall go and which shall remain, and the nature of the new combination of ids resulting from the process of




FIG. 76.—Diagram illustrating the Composition of the Germ Plasm (Chromatin Substance of the Nucleus) out of Ancestral Ids, and the Effect thereon of repeated Amphimixis. (From Weismann's "Evolution Theory.")

A—*D* the unreduced nucleus, containing sixteen chromosomes (each consisting of a single id), of four successive generations. In *A* the germ plasm consists of only two kinds of ids; in *B* of four; in *C* of eight, and in *D* of sixteen. *mJ*, *pJ*, maternal and paternal ids

amphimixis must also be a matter of chance, depending upon what luck the germ cells happen to have in their mating.

As has been well said, a new shuffling of the cards must take place in each generation. The characters of the organism developed from any zygote will depend upon the hand dealt out to it in the processes of reduction and amphimixis, and as it can rarely, if ever, happen that any two hands will be exactly alike, so it will rarely, if ever, happen that any two organisms, however closely related, will exactly resemble one another in all their

characters. Indeed, the only cases in which even an approximation to exact resemblance is known, at any rate amongst the higher animals, are those of "identical" twins, and the explanation of these is that they have arisen by an integral division of a single fertilized ovum, followed by separation of the first two daughter cells or blastomeres thus produced.

We therefore find in the processes of reduction and amphimixis, in the permutation and combination of ancestral characters, an abundant source of variation. This, however, is not supposed to explain fully the origin of variations, and Weismann accordingly invokes the aid of another hypothesis, his theory of "Germinal Selection." In accordance with this theory the determinants of which the ids are composed are supposed to be differently situated with regard to their facilities for obtaining the nutriment necessary for their growth and multiplication. There is a kind of struggle for existence going on amongst them. Those which are more successful in obtaining supplies, having once got a start, will tend to supplant those which are less successful. Some will become weaker and some stronger, and thus, as the result of differences in nutrition, variation is set up amongst the determinants themselves If these vary it follows that their determinates, or the parts which they control in the developing organism, will vary also.[1]

In this way Weismann seeks to avoid the necessity of believing in the transmission from parent to offspring of modifications which result from the direct action of the environment upon the body itself, without, however, altogether denying that external influences, and especially nutrition, may act upon the germ plasm through the body and thus cause modifications in the offspring. The problem of the inheritance or non-inheritance of "acquired" characters is, however, so important that it will be better to reserve the consideration of Weismann's views on the subject for a general discussion of the matter in a later chapter.

We have seen that Weismann's theory of the continuity of the

[1] There would seem, however, to be a serious objection to the theory of germinal selection in the fact that the nucleus of any given germ cell contains many ids, and that similar determinants must as a rule recur in each id. We can hardly suppose that the corresponding determinants in each id are always subject to precisely the same advantages or disadvantages of position. It seems much more likely that variations in this respect in different ids would tend to neutralize one another, the kind of determinant which is unfavourably situated in one id being favourably situated in another, so that each kind would, on an average, have the same chance of nutrition.

germ plasm involves the acceptance of the chromatin of the nucleus as the actual material basis of hereditary transmission. There can be no doubt that the phenomena of ordinary mitosis in the case of the body cells, and those of maturation and fertilization in the case of the germ cells, strongly support this view, while the simple fact that the spermatozoon, consisting almost entirely of chromatin substance and with a minimum of cytoplasm, contributes equally with the ovum to the characters of the offspring in normal cases, seems almost conclusive as to the predominating importance of the chromatin in this respect. Some observers, however, still maintain that the cytoplasm plays a very important part in heredity.

It is probable that much light will be thrown upon this question by the development of that extremely important branch of biological science known as experimental embryology, which is as yet in its infancy. We have already pointed out that in certain cases eggs containing no nucleus may be fertilized by spermatozoa, and may then develop up to a certain point, and that this process is termed merogony. Many years ago Boveri claimed to have fertilized enucleate fragments of the eggs of one genus of sea-urchins (Sphærechinus) with the sperm of another genus (Echinus), and obtained larvæ with only paternal characters. He concluded from this experiment that the nuclear substance is alone responsible for the transmission of inherited characters. Unfortunately it seems that his results are open to a different interpretation, and they have been severely criticized. They certainly cannot be regarded as by any means conclusive.

More recently Godlewski has succeeded in fertilizing eggs of the common sea-urchin (Echinus) with sperm of the feather star (Antedon), belonging not only to a distinct genus but to a widely different order of echinoderms. The larvæ of these two types are easily distinguished even in early stages of development. The larvæ produced by fertilization of normal eggs of Echinus with sperm of Antedon are said to be of the maternal type. This result is in itself very remarkable, but Godlewski was also able to fertilize enucleate egg fragments of the sea-urchin with sperm of the feather star. Eight larvæ produced in this way reached the blastula stage, but only four developed as far as the gastrula. These four, however, were again of the maternal type, and could only be distinguished by their size from those of the pure Echinus culture. From these experiments Godlewski concludes that

cytoplasm as well as chromatin must be concerned in the transmission of hereditary characters, for no maternal chromatin was present in the eggs from which the larvæ developed. Whether these results, which are in direct opposition to those of Boveri, will be confirmed or refuted by further observations remains to be seen. Walker, in his interesting work on heredity,[1] has accepted Godlewski's conclusions and made use of them in support of the theory that the chromosomes are the bearers of individual characters only, while racial characters may be transmitted by "the whole protoplasm of the cell."

The "Mendelian" experiments in hybridization, to be discussed in the next chapter, leave us in no possible doubt as to the immense importance of the chromosomes, nor as to the existence in these remarkable bodies of definite "determinants," "factors" or "genes," which are responsible for the transmission of a vast number of heritable peculiarities.

[1] "Hereditary Characters and their Modes of Transmission," by C E Walker (London, Edward Arno'd, 1910)

*

CHAPTER XIII

The Mendelian experiments in hybridization—The doctrine of unit characters and the purity of the gametes The localization of Mendelian factors in the chromosomes—The possible nature of these factors—Galton's law of inheritance.

WHATEVER view we may adopt as to the mechanism of heredity there can be no doubt as to the existence of a material foundation for the transmission of characters from parent to offspring. We know that the protoplasm which forms the material basis of all living things is continuous, by means of the germ cells or gametes, in an unbroken stream from one generation to another. At each conjugation of gametes, however, two such streams are mingled, and the offspring receives part of its initial stock of protoplasm from one parent and part from the other, each part bringing with it all the potentialities which may have been derived from a long line of ancestors. Bearing these facts in mind, we must now direct our attention to some results which have been obtained by the "Mendelian" method of attacking the problem of heredity.

In the early part of the nineteenth century much attention was paid by horticulturists to experiments on the hybridization of plants. It was found that, within certain limits, it was possible to fertilize the flower of one variety of plant with the pollen of another variety, and in this manner to alter the character of the offspring. Many crosses or hybrids between different varieties were thus obtained, differing in various ways from the parent plants. It was also found that by repeatedly fertilizing the flowers of one variety with the pollen of another the descendants of the first could be entirely changed into the second. This clearly proved that all the distinctive characters of the male parent were in some way represented in the pollen grains, and could be transmitted by these to future generations, but it also proved something more, it proved that it was possible to eliminate the special characters of the female parent, or at least to prevent them from manifesting themselves in the offspring.

As a rule it is only possible to bring such experiments to a

successful issue when working with closely related species or varieties. The flower of one kind of orchid, for example, may perhaps be fertilized by the pollen of a different orchid, but the pollen of such a plant as a lily would probably not have the slightest effect upon it.

The first observer to throw a clear light upon the meaning of the remarkable results obtained by hybridization was Gregor Johann Mendel, a native of Austrian Silesia, born in 1822, whose work has recently attracted so much attention. As Abbot of Brünn, he was the happy possessor of a garden, and presumably also of that peace and quiet which are so essential to intellectual work. He was not content with merely casual experiments; he had time to think about what he was doing and he attacked the problem in the true scientific spirit. Unfortunately for science, however, his seclusion was a little too complete. He was content to publish his results in 1865 and 1869 in the proceedings of a local natural history society, where they remained buried for more than thirty years. Thus, by the irony of fate, our own illustrious countryman, Charles Darwin, although a contemporary of Mendel, probably never heard of those remarkable discoveries which bid fair to solve some of the problems in which he himself was so deeply interested, nor did they influence the views of Weismann.

In order to gain an insight into the nature of Mendel's work we cannot do better than turn to his original memoir, entitled "Experiments in Plant Hybridization," of which an excellent translation has been published by Professor Bateson,[1] one of the leading exponents of what is now termed Mendelism. Even fifty years ago, experiments in hybridization were, as we have already seen, no new thing. Mendel had many predecessors in this line of research, but it was reserved for him to introduce exact statistical methods into the work, and it is to these methods that he owed his success. It was already known that hybridization, or the crossing of distinct species and varieties, might result in the production of several distinct types of offspring from the same hybrids. Mendel was not content with this knowledge: he proceeded by numerous and often repeated experiments, extending over several years, to classify the offspring produced by hybridization, to follow out their descendants from generation to generation, and above all to find out the exact numerical proportions in which the different types appeared in

[1] *Vide* Bateson, "Mendel's Principles of Heredity" (Cambridge, 1909).

successive generations. It was the discovery of these proportions that furnished the clue to the mystery.

Mendel found the material which he required for his experiments chiefly in the numerous garden varieties of the common edible pea. How these varieties first originated we do not know. Possibly they arose as sudden and apparently spontaneous variations, or mutations. No less than twenty-two such varieties were available for experiment.

The next thing was to select certain differentiating characters upon which to concentrate attention, and this is a very important point. Of course, all the varieties agreed with one another in most of their characters; in other words, they were all edible peas exhibiting the specific characters of the plant known to botanists as *Pisum sativum*, but they differed in numerous minor features. Of these differentiating characters Mendel selected seven for the purposes of his experiments, amongst which we need mention only two: (1) the form of the ripe seed, which may be either round and smooth or, alternatively, angular and wrinkled; and (2) the difference in colour of the seed-contents or cotyledons, which may be either yellow or, alternatively, green, and which usually determine the colour of the seed as a whole.

The two alternative characters of each pair were artificially united by cross-fertilization, the flowers of a round-seeded pea being fertilized by the pollen of a wrinkled-seeded pea, those of a green-seeded pea by the pollen of a yellow-seeded pea, and so on.

In this way a number of hybrid plants, represented in the first instance by seeds, were obtained.[1] These hybrids constituted what modern writers term the F^1 or "first filial" generation, and the curious fact was observed that every hybrid closely resembled one of the two parents, instead of being, as is sometimes the case in other hybrids, intermediate in character between them. Further experiments with the offspring of the hybrids, however, showed that, although only one of the two alternative characters manifested itself in the hybrid, the other was there also in a latent or dormant condition, and appeared again in

[1] It must be remembered that the pea-seed consists chiefly of the young plant in a dormant condition, and that its characters are therefore, with the exception of those appertaining to the seed-coat, which are not considered in this chapter, those of the sporophyte generation which follows the conjugation of the gametes. The fact that the complete life-cycle of the plant really includes two generations, a well developed sporophyte and a vestigial gametophyte, does not affect the Mendelian conclusions.

subsequent generations. The character which appears in the hybrid is said to be *dominant*, while that which is suppressed is said to be *recessive*. In the case of these peas, then, one character is always dominant over the other in the hybrid, and, moreover, it is always the same character, and it does not matter whether it is derived from the male or from the female parent. Thus the round form of seed is dominant over the wrinkled, the yellow colour of the seed-contents over the green, and so on.

Having obtained the hybrids, the next step was to follow the history of the offspring throughout successive generations. For this purpose the flowers of the plants raised from the hybrid seeds were allowed to fertilize themselves with their own pollen, no further crossing being permitted. The seeds thus obtained (constituting the F^2 or "second filial" generation) were now again apparently of two kinds, resembling the two original parent forms from which the hybrid was produced. Moreover, these two kinds occurred in definite proportions, three of the dominant to one of the recessive—three round seeds to one wrinkled, three yellow to one green, and so on. Of course, these proportions are only averages, and, in order to eliminate errors of chance, large numbers of observations must be made—the greater the number the more reliable the result. To take an actual example from Mendel's work, 7,324 seeds were obtained in the second trial year from the hybrids between round and wrinkled. Of this number 5,474 were found to be round, and 1,850 wrinkled—showing the ratio of 2·96 to 1. Again, out of 8,023 seeds produced by the hybrids between green and yellow, 6,022 were yellow and 2,001 green, the ratio being 3·01 to 1. These experiments have often been repeated during recent years, especially by Mr. A. D. Darbishire,[1] and it is found that the average ratio of three to one is always maintained.

The significance of this proportion is not at first sight obvious. It is necessary to continue the experiment for at least another generation in order to gain further insight into the matter. We have as the result of the self-fertilization of our hybrids apparently only two kinds of seeds or plants, which we may call D, showing the dominant character, and R, showing the recessive character, in the proportion of 3 D to 1 R. If these

[1] Some beautiful illustrations of Mendelian results in both plants and animals are given in the late Mr. Darbishire's work "Breeding and the Mendelian Discovery" (Cassell & Co., Ld, 1911).

plants are again cultivated and allowed to fertilize themselves we find that every one of the R's breeds true, and no matter how many generations we raise they will always remain of the recessive type. These are now called "extracted recessives." When, however, we cultivate the plants showing the dominant character in the same way we soon find that, though similar to one another externally, they are not in reality all alike, for one-third of them will yield nothing but D's, while the remaining two-thirds will yield D's and R's in the same proportion of 3 to 1 as the original hybrid. Moreover, the D's obtained from the one-third will continue to breed true from generation to generation, and do what we will we can never get an R out of them again. They are called "extracted dominants."

It is obvious then, from these experiments, that the apparent D's are not all true D's, but that two-thirds of them contain the recessive character in a latent or dormant condition, and are, therefore, still hybrid in composition. If we indicate those which we can thus prove by breeding to contain the recessive character by the letters D (R), we can sum the whole story up in the following simple diagram:—




FIG. 77.—Monohybridism.

Thus we see that from generation to generation of the offspring of the hybrid there goes on a constant sorting out into three categories, the two original parental types and the hybrid form being always produced in definite proportions. If we assume that each kind produces on an average an equal number of offspring, we shall see from the diagram that in the course of a few generations of undisturbed reproduction by far the greater number of the plants will have finally reverted, in equal proportions, to one or other of the original types,[1] but a certain number

[1] This statement, of course, applies only to cases in which the different types are unable to cross with one another.

will always remain in the hybrid condition and will continue to split up as before in the characteristic Mendelian proportions.

We see, then, from Mendel's experiments, that in the case of peas, where one of the two alternative characters is dominant over the other, the offspring of the first hybrid appear in the proportion of three apparent dominants to one recessive, but that further analysis shows that the real proportion is

1 D : 2 D (R) : 1 R.[1]

This proportion has since been observed not only in peas but in a large number of other cases, including animals as well as plants. It is evidently a phenomenon of very common occurrence, though we cannot as yet say that it occurs universally whenever two forms with alternative characters are crossed. Moreover, as we have already noticed, the phenomenon of dominance is not always shown, and the hybrid may exhibit a character intermediate between those of the two parents or different from either. The occurrence of Mendelian proportions, however, is sufficiently frequent to demand explanation and this explanation we must now seek.

Suppose we take a large number of black and an equal number of white counters, all alike in shape, size and weight, and after shaking them up thoroughly in a bag, draw them out two at a time, and one on top of the other, without looking. Each pair that we draw out may consist of white over white, black over white, white over black, or black over black. If we draw out a sufficiently large number of pairs entirely at random in this way and then count them, we shall find that they occur in the proportion :—1 W W : 1 B W : 1 W B : 1 B B, or, since B W and W B may be looked upon as the same, 1 W W : 2 W B : 1 B B, or one all white, two white and black, and one all black ; this being, of course, only what is to be expected in accordance with the mathematical law of probability. This is also the same as the simple Mendelian proportion, and at once suggests that the latter may, perhaps, be explained in a similar way as the result of random union of characters in accordance with the laws of chance.

We know that each individual plant or animal produced by sexual reproduction is formed by the union of two germ cells or gametes. Now these gametes are formed in very large numbers

[1] This is sometimes written more fully 1 D D : 2 D (R) : 1 R R. The reason for so doing will be obvious from what follows.

in the parent organisms, and if we suppose that each one contains (potentially) only one of the two alternative characters with which we are experimenting, and if we further suppose that the two kinds are produced in equal numbers and that they unite at random, then, in accordance with the law of chance, we should expect to get in the offspring the proportion of one with the one character, two with both characters and one with the other character, exactly as Mendel found in his experiments.[1] There seems to be no other possible explanation of the Mendelian phenomena.

The conclusions to be drawn from these results are of fundamental importance. In the first place, we learn that small individual characters may be separately represented in the germ cells and separately transmitted from parent to offspring. These are sometimes called " unit characters," and we shall see later on that there are the strongest reasons for believing that the " factors " which are responsible for their appearance are actually present as material entities in the chromosomes of the nucleus.

In the second place, we may conclude from these experiments that, as regards the unit characters with which we are dealing, we have a complete segregation amongst the germ cells or gametes, each of which carries the factor for only one of each pair of alternatives (technically termed allelomorphs), and in this respect it makes no difference whether the germ cell be male or female. Thus we arrive at what is sometimes termed the doctrine of the " purity of the gametes "—purity, that is to say, with regard to each character of any such pair of alternatives, and without reference to the other innumerable characters which must also be represented in the germ cells.

We may now examine an example of a class of practical problems which may be solved by the application of such simple Mendelian principles.

Fowl-fanciers are well acquainted with a particular breed of fowl known as the blue Andalusian. It has long been known that this kind of fowl cannot be made to breed true. Some of the offspring will be black and others white with black splashes,

[1] A little consideration will show that if the alternative characters are represented in equal numbers of both male and female gametes, the facts that a male must always unite with a female, and that the actual number of sperm cells produced is usually very much larger than the number of ova, will not affect the result.

the remainder being like the parents. It has been shown, moreover, that the three kinds of chicken occur, on an average, in definite proportions, a quarter being black, a half blue, and a quarter white splashed with black. Here we have the familiar Mendelian proportion 1 : 2 : 1, suggesting that the blue Andalusian is really a hybrid, and that the so-called " wasters " are the parent forms. It is easy to prove that this is the case, for if the two kinds of waster are mated we invariably get the blue Andalusian again. The old idea of the so-called practical breeder would have been to go on destroying the wasters and carefully selecting the blues in order to maintain the " purity of the breed." We now know, however, that there is no such thing as a pure blue Andalusian breed ; the blue is really a hybrid, and you can get more blues by mating the wasters than by breeding from the blues themselves. This case is also interesting as affording an example of a hybrid which differs in character from either of the parent forms.

If only a single pair of alternative characters or allelomorphs is dealt with in the experiment the case is termed one of monohybridism, and such cases yield the proportion 1 : 2 : 1 (or apparently 1 : 3 in cases of dominance) amongst the offspring of the hybrid, *i.e.* in the F^2 generation. It will frequently happen, however, that the two varieties which are united in the formation of the hybrid will differ from one another as regards more than one pair of alternative characters. We may illustrate this by a case of dihybridism, in which two pairs of such characters are involved. The case selected is one which shows us how, under certain circumstances, we can obtain a form exhibiting an entirely new combination of characters, which in spite of its hybrid nature will continue to breed true.

Suppose a gardener had only two kinds of peas, one with round green seeds and the other with wrinkled yellow seeds, and that he wished to obtain peas with wrinkled green seeds. Mendel has shown us how he may get what he desires, both surely and speedily, from the material already in his possession.

The necessary procedure will be evident from the following scheme :—

Let R = round, W = wrinkled, Y = yellow, and G = green. We know from previous experiments that R is dominant to W, and Y to G.

R G crossed with W Y gives the hybrid, R (G) (W) Y, which, owing to the dominance of R and Y, will appear in the form of round yellow seeds (the brackets around the G and W indicating the recessive nature of green and wrinkled). That is not what our gardener wants, and if he knew no better he would naturally be




FIG. 78.—An Example of Dihybridism in Peas.

A, wrinkled yellow peas; B, round green peas; C, hybrid peas (F^1 generation, round and yellow in appearance) produced by crossing A and B; D, plant of the F^1 generation, with seeds of the F^2 generation, produced by self-fertilization and of the four different kinds, round yellow, round green, wrinkled yellow, and wrinkled green, lying in the pods. (Photographed from a preparation by Mr. Darbishire, who has reproduced the same subject in colours in his work on "Breeding and the Mendelian Discovery").

much disappointed with the result. If, however, the hybrids be allowed to fertilize themselves and reproduce, then their offspring will appear in the apparent proportions :—

9 R Y : 3 R G : 3 W Y : 1 W G,

no account being taken of the non-apparent recessive characters. The meaning of the proportion 9 : 3 : 3 : 1 exhibited in this

case will be readily understood from the accompanying table (Fig. 79) :—

Germ cells → / ↓	R Y	R G	W Y	W G
R Y	R Y R Y	R (G) R Y	(W) Y R Y	(W) (G) R Y
R G	R Y R (G)	R G R G	(W) Y R (G)	(W) G R G
W Y	R Y (W) Y	R (G) (W) Y	W Y W Y	W (G) W Y
W G	R Y (W) (G)	R G (W) G	W Y W (G)	W G W G

FIG. 79.—Dihybridism.

The constitution of the hybrid (in so far as the characters in question are concerned) is R (G) (W) Y. Each of its germ cells, however, contains one factor, and one only, from each pair of alternatives. Each may, therefore, contain R Y, R G, W Y or W G. These different kinds of germ cells will occur on the average in equal numbers, and on self-fertilization of the hybrid flowers they will unite in pairs at random. The possible ways in which such union may take place are shown in the table, and if allowance be made for the phenomenon of dominance, in accordance with which G disappears from view whenever it meets Y, and W whenever it meets R (as indicated by the brackets in the table), we get the apparent proportion of 9 round yellow seeds, 3 round green seeds, 3 wrinkled yellow seeds, and 1 wrinkled green seed. The number of wrinkled green seeds will be small at first, but they will breed true, containing as they do only the extracted recessive characters, for if a dominant character were present it would necessarily show itself.

Thus we see that one way of producing new forms of plants and animals is by the artificial combination of characters which already exist in different varieties. These elementary or unit characters can be brought together by the process of hybridization, and new organisms produced in somewhat the same

way as that in which the chemist is able to produce new compounds by analysis and synthesis from other substances.

Probably no man has made more successful use of the process of hybridization in the production of new and valuable forms of plant-life than Luther Burbank, at his celebrated Californian nurseries. Mr. Burbank himself is unfortunately not a writer, and for a scientific account of his work we are indebted to Professor Hugo de Vries, who in his book on "Plant Breeding"[1] describes what he himself saw and heard during his visits to Mr. Burbank's farms. Some idea of the commercial value of Mr. Burbank's work may be formed from the fact that special companies have been formed for the propagation and sale of some of these wonderful hybrids. White blackberries, stoneless prunes, "plumcots" and thornless cacti are only some amongst the many novelties which he has produced by crossing different varieties by hybridization and thus combining two or more desirable qualities in one plant.

Take, for instance, the case of the stoneless prune. It had somehow or other come to the knowledge of Mr. Burbank that about 200 years ago there existed in France a plum known as the "Prune sans noyau." He succeeded in obtaining specimens of this fruit, but it proved to be of little or no commercial value owing to its poor quality. Its one valuable feature was its stonelessness, and Burbank set to work to transfer this character, by hybridization, to a variety of good quality. He succeeded, and there appears to be no reason why the stoneless character should not be similarly implanted upon all the different varieties of plums now in cultivation.

Similarly, the "plumcots" are hybrids between plums and apricots, which Professor de Vries speaks of as "most delicious and beautiful fruits."

It must be admitted that Burbank's work is practical rather than scientific. He apparently pays no attention to the principles of Mendel in his operations, but just goes on hybridizing until he gets what he wants. In this process enormous numbers of plants which do not fulfil his requirements have to be destroyed for every one that is worth preserving.

He is not necessarily concerned with the production of pure breeds; of forms, that is to say, which will breed true from seed,

[1] Hugo de Vries, "Plant Breeding" (London, Kegan Paul, Trench, Trübner & Co., Ld., 1907)

or, in other words, of forms which will hand on their desirable qualities to future generations by heredity. This does not matter in the case of fruit trees and other plants which can be propagated by buds independently of sexual reproduction. As a general rule, a fruit tree cannot be relied upon to come true from seed, the characters which it has received from different ancestors not being permanently combined, but separating out and undergoing fresh combinations in the sexual process, probably in accordance with Mendelian principles. The seedlings may therefore be "degenerate," as horticulturists say, and will no longer exhibit those valuable qualities which depend upon the confluence in one individual of particular lines of ancestry.

The majority of Burbank's productions could not survive in a state of nature at all; they are essentially artificial and have to be artificially propagated by means of buds or cuttings. In this respect they are quite different from the pure races which it is possible to produce by hybridization carried out in accordance with Mendelian principles, in which new and permanent combinations of unit characters, capable of being transmitted by heredity, are effected.

Professor Bateson, Professor Biffen, Mr. Hurst and others have lately done much to demonstrate the possibilities of progress in this direction, and the value which the application of the Mendelian principles of heredity must have from the economic point of view. We know now that such cereals as wheat and barley obey the Mendelian laws of hybridization as regards various important characters. So also do horses as regards the colour of their coats, and human beings as regards the colour of their eyes, and in some other respects, especially as regards the inheritance of certain diseases. In short, it appears certain that Mendelian principles have a very general application, and the economic value of the knowledge of such principles must be enormous. Professor Biffen has shown, for example, that susceptibility and insusceptibility to that destructive disease in wheat known as "rust," behave as Mendelian characters, and that it is possible by a very simple process of hybridization to confer immunity from this disease upon naturally susceptible varieties.

From the theoretical point of view the great value of the Mendelian experiments lies in the possibilities which they present, at any rate in certain cases, of analyzing the constitution of the hereditary substance (germ plasm), and thereby gaining some

insight into the mechanism of heredity. We may regard the existence of " unit characters " as being conclusively demonstrated by these experiments, and the fact that we are able to interchange these characters and to add and subtract particular characters to and from the organism seems to indicate very clearly that the germ plasm must contain material primordia or " factors," as they are often called, which are responsible for the development of these characters.

In so far as they demonstrate the existence of such factors—which evidently correspond very closely with Weismann's hypothetical determinants—the Mendelian experiments may be taken as affording confirmation of Weismann's theory of the constitution of the germ plasm. Their results also harmonize very well with those of recent cytological investigations. We have seen that there is strong evidence for regarding the chromatin substance of the nucleus as the material basis of heredity. We have further seen that this chromatin is very complex in structure and that the chromosomes, or units of the highest order of which it is composed, can in many cases be optically resolved into chromomeres or units of the next lower order. According to Weismann's theory these chromomeres or ids are in their turn made up of the determinants. Moreover the associations and redistributions of chromosomes which take place in the process of " reduction " and in the conjugation of the germ cells seem to afford ample opportunity for those permutations and combinations of factors the occurrence of which is demonstrated by the Mendelian experiments. As Professor Farmer observes, " The facts of meiosis[1] are seen to fall completely into line with conclusions drawn from experiments on breeding as far as the numerical distribution of characters is concerned." [2]

The doctrine of the " purity of the gametes " teaches us that any given mature germ cell contains only one member of any given pair of alternative factors or primordia (allelomorphs). This may be accounted for by the pairing of the chromosomes and the subsequent halving of their number which take place at some period or other prior to the formation of the gametes. There is good reason to believe that each member of such a pair of chromosomes is homologous with or morphologically equivalent

[1] *I.e.* the phenomena accompanying the reduction in the number of chromosomes which takes place periodically in all typical organisms (*vide* Chapter X.).

[2] Croonian Lecture. Proceedings of the Royal Society, B, Vol. 79, 1907.

to the other, the difference between them resulting from the fact that one is paternal and the other maternal in origin.[1] Reduction (or halving of the total number of chromosomes) is accomplished by the distribution of the two members of each pair to different daughter cells. Hence if the paternal and maternal chromosomes contain different alternative factors (or determinants), derived from different parents, so also will the gametes when these are formed.

Suppose we represent the two members of any pair of factors by the letters *a* and *b*, then any one gamete may contain either *a* or *b*, but not both. When the gametes unite in conjugation the zygote will again have both maternal and paternal chromosomes and there will be three possibilities as to its constitution in regard to the characters in question. If a gamete containing *a* happens to unite with another containing *a* the zygote will contain the pair *a a*, and will be termed in Mendelian phraseology a "homozygote."[2] If a gamete containing *b* happens to unite with another containing *b* the zygote will contain the pair *b b* and will again be a homozygote. If, on the other hand, a gamete containing *a* unites with another containing *b* the zygote will contain the pair *a b*, and such a zygote is termed a heterozygote" or hybrid (compare Fig. 80).

In accordance with what is termed the "presence or absence hypothesis" one of the two "factors" in an allelomorphic pair may be merely negative in character; *i.e.* it may have no real existence as a material primordium or determinant. In the words of Professor Bateson, "All observations point to a conclusion of great importance, namely that a dominant character is the condition due to the *presence* of a definite factor, while the corresponding recessive owes its condition to the *absence* of the same factor. This generalization, which so far as we yet see, is applicable throughout the whole range of Mendelian phenomena, renders invaluable assistance in the interpretation of the phenomena of Heredity. The green pea, for instance, owes its recessive greenness to the *absence* of the factor which, if present, would turn the colouring matter yellow, and so forth."[3]

It is obvious that if, in our general formula, we take *a* to represent the dominant factor and *b* the recessive, we might

[1] Compare Chapter X.

[2] This term has been extended to the fully developed organism which arises from the zygote.

[3] Bateson, "Mendel's Principles of Heredity" (Cambridge, 1909), pp. 53—54.

substitute *not a* for *b* without altering the result, and the differences between the paternal and maternal chromosomes of any given pair may depend merely upon the absence from one or the other of one or more factors which are present in its mate. There is strong reason for believing, however, that the presence or absence hypothesis is by no means applicable to all cases.

Mendelian phenomena are often greatly complicated and rendered very difficult of interpretation by the fact that the activity of a given factor, or its power to influence the development of the zygote, may be dependent upon the presence of another factor belonging to a different "allelomorphic pair." In other words, a given character may depend not merely upon the presence of a single factor in the zygote but upon the co-operation of two or more factors, and if these factors happen to be separated in the process of reduction and do not happen to come together again in the union of the gametes to form the zygote, then the character in question[1] will not appear in the organism developed from the zygote. In this way it may happen that a character which was present in the ancestors of a particular organism may disappear for many generations and then suddenly re-appear as the result of some cross or hybridization in which the necessary factors happen to be brought together again in the zygote. In this way are explained those cases of "reversion" to ancestral types which Darwin found to occur so frequently as the result of cross-breeding.

One of the most thoroughly investigated cases of this kind[2] is that of certain white sweet peas belonging to the variety known to horticulturists as "Emily Henderson." Plants of this variety are not really all alike but differ from one another in the shape of their pollen grains, and when the two kinds, distinguishable only in this way, are crossed, the offspring are frequently found to possess purple flowers resembling those of the wild Sicilian pea from which our cultivated varieties have been derived. It is not necessary to go into the somewhat complicated analysis of this case in any detail, but it has been demonstrated by the researches of Professor Bateson and Professor Punnett that the re-appearance of the lost colour in the hybrid is due to the re-union in the zygote of certain factors which had become separated at some period or other in the ancestral history of the white-flowered parents.

[1] Professor Bateson terms such characters "compound characters."
[2] Bateson, *op. cit.*, pp. 89 *et seq.*

The existence of interactions of this kind between the different factors or determinants in the germ plasm, giving rise often to very complex results as regards the characters of the offspring, is a sufficient explanation of the fact that many cases of hybridism are at present incapable of interpretation in terms of the Mendelian theory, and such cases cannot be legitimately used as arguments against the validity of that theory. It is obviously impossible to explain the results of any particular cross until we have some knowledge, not only of the extremely complex constitution of the parental germ plasm on both sides, but also of the way in which the factors which meet in the zygote may be expected to influence one another.

Another important phenomenon that demands at any rate a brief consideration in this connection is that of "linkage" of characters. It is often observed when several or many characters, belonging to different pairs of alternatives, are kept under observation at the same time, that they tend to remain together in definite groups throughout whole series of experiments. This phenomenon seems to be best explained by the supposition that all the factors for each such group of linked characters are contained in the same chromosome, and as the chromosomes usually retain their individuality from one generation to another, throughout all the cell divisions that may take place, the linkage is not normally broken. In cases of ordinary dihybridism, such as that considered in an earlier part of this chapter, we must assume that the factors for the two different pairs of alternative characters concerned must be lodged in different pairs of chromosomes, otherwise the re-assortment of characters which takes place in the F^2 generation would be impossible.

The phenomenon of linkage, in the able hands of Professor T. H. Morgan and his colleagues in America, has in recent years thrown a flood of light upon what is sometimes termed the factorial hypothesis, and necessitated considerable modification of Weismann's views as to the constitution of the germ plasm. These indefatigable observers have found a most suitable subject for their investigations in a dipterous insect known as *Drosophila*, a small, fruit-feeding fly which is easily reared in captivity, and has the great merit of undergoing frequent mutations, whereby a very large number of peculiar modifications are produced. Most, at any rate, of these modifications must be regarded as abnormalities, such as the reduction of the wings to a vestigial condition, changes in the colour of the eyes,




FIG. 80.—Monohybridism in *Drosophila*. Result of crossing a vestigial-winged fly with a normal long-winged fly. Long is dominant to vestigial. The chromosomes bearing the factors for vestigial are represented by cross-barred oblongs, those bearing the factors for long by plain oblongs. The four possible combinations of these chromosomes, resulting from the conjugation of the F^1 gametes, are shown in the lower half of the diagram. (From "The Mechanism of Mendelian Heredity," by Morgan, Sturtevant, Muller and Bridges)

and so forth, but though they seem to be utterly valueless from the point of view of the welfare of their possessor, they are none the less




FIG. 81.—Diagram of the chromosome group as it occurs in the body cells of *Drosophila ampelophila*, male and female. X and Y are the sex chromosomes, the hook on Y is a convention. (From "The Mechanism of Mendelian Heredity," by Morgan, Sturtevant, Muller and Bridges.)

important for experimental purposes, for they are all separately heritable unit characters, behaving in strict Mendelian fashion (Fig. 80).




FIG. 82.—Diagram of single crossing over of maternal and paternal chromosomes during synapsis. Two composite chromosomes result (D), in which the factors form new linkage groups as shown in C. (From "The Mechanism of Mendelian Heredity," by Morgan, Sturtevant, Muller and Bridges.)

Breeding experiments have shown that these characters form four linkage groups, while cytological observations have shown that there are also four chromosomes in each of the mature germ cells and four pairs in each of the body cells (Fig. 81). Moreover, these

chromosomes differ among themselves in shape and size, and there is a rough correspondence between the size of each chromosome and the number of separately heritable mutations in what appears to be the corresponding linkage group. These correlations can hardly be mere coincidences, and must be taken as affording strong evidence of the existence of material factors [1] in the chromosomes.

But Morgan and his colleagues have gone further than this in locating the Mendelian factors, and have shown by indirect but very convincing evidence that they must be arranged in each chromosome in linear series. They have, in fact, been able to make maps of the chromosomes of *Drosophila* showing the relative position of each separate factor. This has been rendered possible by the occurrence of another phenomenon known as "crossing over," which consists in a disturbance of the normal linkage of characters in such a manner that certain characters are transferred from one group to another. This is supposed to result from the adhesion of the paired chromosomes at the time of synapsis. When the maternal and paternal chromosomes of such a pair try to break away from one another they get mixed up, and two composite chromosomes are formed, each partly maternal and partly paternal in origin, and therefore each with some maternal and some paternal factors (Fig. 82). New linkage groups are thus established, differing from those of the original chromosomes. It is obviously more likely that crossing over will take place between two factors that are widely separated in an elongated chromosome than between two that lie nearer together, and thus the relative frequency of crossing over of characters, as observed in breeding experiments, affords a clue to the position of the corresponding factors in the chromosomes. For further information on this subject the reader should refer to the admirable little book on "The Mechanism of Mendelian Heredity," [2] by Professor Morgan and his colleagues, and to Morgan's more recent work on "The Physical Basis of Heredity." [3]

Although the work of Morgan and his colleagues, built upon the foundations laid by Mendel, may be regarded as having finally settled—in the affirmative—the question of the existence of material factors or genes in the germ cells, and of their location in the chromosomes, yet these factors have never actually been seen, and their chemical and physical nature remains entirely obscure. It is

[1] In his work on "The Physical Basis of Heredity," Morgan has adopted the term "gene" in preference to "factor."

[2] London, Constable & Co., 1915.

[3] Philadelphia and London, J. B. Lippincott Co., 1919.

legitimate, however, to speculate as to what they really are and how they produce their effects, and in this connection some of the most important results of recent physiological investigations are extremely suggestive.

It has been shown by Starling and others that the growth of the animal body, and the functions of the various organs of which it is composed, are largely controlled and regulated by infinitesimal quantities of chemical substances secreted by the so-called ductless or endocrine glands. As examples of these glands may be mentioned the pituitary body at the base of the brain, the thyroid, the thymus and the adrenals, the secretions of which, circulating in the blood, may produce a profound effect even upon distant parts of the body. The substances secreted by these glands are technically known as hormones, but very little, if anything, is known about their chemical composition. Similarly, the development of the lens of the eye from the embryonic epidermis appears to be determined by the chemical stimulus of some hormone secreted by the optic vesicle growing out from the brain immediately beneath it. This is clearly indicated by the fact that if the optic vesicle be excised and transplanted to some other situation beneath the embryonic epidermis the latter will give rise to a lens in the new locality.

From these facts we may conclude that development in general is largely controlled and directed by chemical stimuli, and it seems not unreasonable to infer that the Mendelian factors are the sources of stimuli of this kind; that if, for example, a fly develops with vestigial instead of normal wings it is because some definite chemical substance contained in or produced by a particular factor in the germ cell exerts its specific influence upon the developing organism, just as the presence of magnesium chloride causes the young *Fundulus* larva to develop with an eye in the middle of the head instead of one on each side (*cf.* Fig. 75).

As to the nature of the factors or genes themselves, we can only guess that they may be aggregations of proteid molecules. They must be living entities, capable of assimilating nutriment, growing and multiplying, and they must be distributed throughout the developing organism by the mechanism of mitosis.

In accordance with the views here expressed it would seem that the Mendelian factors are really modifying factors, and of course the modifications are inherited just in so far as the factors are handed on in the germ plasm from one generation to the next.

Whether or not development could take place without the aid of any Mendelian factors at all we do not know, but it is quite conceivable that it might do so. How they arise in the germ plasm we do not know. It is probably a problem of molecular chemistry, and one which offers a most promising field for future investigation. Their existence, however, is of vital importance to the organism, as we see when we reflect that the presence of a particular factor in the fertilized ovum may make all the difference between a feeble-minded idiot and a normal human being; and it is purely a matter of chance, depending upon what takes place in the maturation of the germ cells, and what luck these have in their mating, which factors out of all the possible alternatives a particular individual may receive from its parents. The responsibilities of parentage are indeed great, and the sooner they are realized the better will it be for the prospects of the human race.

Attention has frequently been called to the alleged discrepancy between the results of the Mendelian experiments and those obtained by the late Sir Francis Galton and others by statistical methods based upon the quantitative estimation of characters in a number of successive generations. As a result of his investigations Galton was able to formulate the following "Law" of inheritance:—"The two parents contribute between them on the average one-half, or (0·5) of the total heritage of the offspring; the four grand-parents, one-quarter, or $(0{\cdot}5)^2$; the eight great-grandparents, one-eighth, or $(0{\cdot}5)^3$, and so on. Thus the sum of the ancestral contributions is expressed by the series $\{(0{\cdot}5) + (0{\cdot}5)^2 + (0{\cdot}5)^3$, &c.$\}$, which, being equal to 1, accounts for the whole heritage."[1]

This series has been modified by Professor Karl Pearson for certain reasons into which we cannot enter in this place, but it may be taken as a substantially correct expression of the results obtained by biometrical inquiry. If we remember that Galton's Law merely expresses the *average* results which may be anticipated from the interbreeding of a large population, in which hybridization probably plays a very small part, it does not appear in any way antagonistic to the Mendelian theory. It is of course not applicable to individual cases of hybridization, where we are concerned, not with general averages, but with the permutations and combinations of alternative character units.

[1] Proceedings of the Royal Society of London, Vol. LXI., 1897, p. 402.

Intimately bound up with Galton's Law of Inheritance is another important generalization known as the Law of Filial Regression, which we owe to the same distinguished philosopher. The law of ancestral inheritance teaches us that *on an average* the individual derives half its characteristics from its immediate parents and the remaining half from its more remote ancestry. If the immediate parents, or one of them, happen to depart from the average condition of the race in respect of any character there will be a tendency on the part of the offspring to inherit the deviation in question; but not to the same extent, for the influence of the more remote ancestry will tend to counteract that of the parents and cause a partial return—or regression—towards mediocrity. As a result of his statistical investigations Galton estimated that the offspring of parents exhibiting a marked deviation from the average would *tend* to inherit that deviation to the extent of only one-third of its magnitude in the parents (the mean of the two parental deviations being taken as the standard of comparison). In the words of Professor Karl Pearson, "It is the heavy weight of this mediocre ancestry which causes the son of an exceptional father to regress towards the general population mean; it is the balance of this sturdy commonplaceness which enables the son of a degenerate father to escape the whole burden of the parental ill. Among mankind we trust largely for our exceptional men to extreme variations occurring among the commonplace, but . . . if we could remove the drag of the mediocre element in ancestry, were it only for a few generations, we should sensibly eliminate regression or create a stock of exceptional men." [1]

[1] Grammar of Science, 1900, pp. 456—457.

CHAPTER XIV

The inheritance of acquired characters and the mnemic theory of heredity.

THE problem of the inheritance or non-inheritance of what are commonly called "acquired characters" has attracted so much attention in recent years and is of such vital importance for the general theory of evolution that we shall have to devote the greater part of the present chapter to its consideration. We may define the term "acquired character," or perhaps better, "acquired modification," as meaning some alteration that arises in the individual body as the direct or indirect result of the action of the environment (internal or external) during its own life-time. A good example is the production of callosities on the hands by the use of golf clubs or hockey sticks, or the enlargement of one of the two kidneys in consequence of the removal of the other.

The problem of the transmission or non-transmission of such modifications from parent to child is essentially a modern one. Lamarck, in 1815, explicitly stated his belief that acquired characters are inherited; indeed this belief, as we shall see later on, formed one of the foundation stones of his theory of evolution. Charles Darwin also adopted the same view, but at the same time fully realized the difficulty of accounting for such transmission, a difficulty which he endeavoured to overcome by his celebrated theory of "Pangenesis." One of the first and foremost of those who maintained the opposite view was August Weismann, whose theory of the "Continuity of the Germ Plasm" we have already dealt with, while reserving the consideration of its all-important bearing upon the controversy now under discussion for the present chapter. A brief review of the diametrically opposed positions of these two great authorities will serve as a fitting introduction to the problem.

Darwin's theory of pangenesis was put forward in 1868.[1] He supposed that all the constituent cells of which the body is

[1] For a complete exposition of the theory see Darwin's "Animals and Plants under Domestication" (Ed. 2, Vol. II., Chapter XXVII.).

composed not only multiply by ordinary cell-division, so as to build up the various tissues, but also, throughout life, give off extremely minute "gemmules" which wander through the body and are collected in vast numbers in the germ cells. The gemmules, although so small as to be invisible even with the highest powers of the microscope, are supposed to be capable of absorbing nutriment and multiplying by division, and each one is supposed, in some mysterious and unexplained manner, to represent the particular cell of the body from which it was derived, and to be capable, at the proper time and in the proper place, of impressing the character of its parent cell upon a corresponding cell of the new organism which develops from the germ cell.

In Darwin's own words:—

"The development of each being, including all the forms of metamorphosis and metagenesis, depends on the presence of gemmules thrown off at each period of life, and on their development, at a corresponding period, in union with preceding cells. Such cells may be said to be fertilized by the gemmules which come next in due order of development. Thus the act of ordinary impregnation and the development of each part in each being are closely analogous processes. The child, strictly speaking, does not grow into the man, but includes germs which slowly and successively become developed and form the man. In the child, as well as in the adult, each part generates the same part. Inheritance must be looked upon as merely a form of growth, like the self-division of a lowly organized unicellular organism. Reversion depends on the transmission from the forefather to his descendants of dormant gemmules, which occasionally become developed under certain known or unknown conditions. Each animal and plant may be compared with a bed of soil full of seeds, some of which soon germinate, some lie dormant for a period, whilst others perish."[1]

Suppose some part of the body in a particular multicellular individual were to become modified by use or disuse, or by the direct action of the environment. Then the gemmules given off from the modified cells would also be affected in a corresponding manner and would carry information of the change to the germ cells. It would be as if some constituency with many representatives changed its political opinions and instead of sending conservative members to the House of Commons took to sending liberals. When the proper time came the new representatives

[1] *Loc. cit.*, pp. 398–9.

would vote according to their instructions; but we must also suppose that the old ones could never be turned out and that there would be a struggle between the two. At first the old ones would be the more numerous and would outvote the new ones; presently, however, the new ones, being constantly reinforced, would come to outnumber the old ones and perhaps be able to give effect to the altered views of their constituency. As Darwin says, "It is generally necessary that an organism should be exposed during several generations to changed conditions or habits, in order that any modification thus acquired should appear in the offspring." It would probably be more in accord with the facts if, instead of "several generations" we said "a large number of generations." In this sense, we may well believe that acquired characters can be inherited, without expecting to be able to demonstrate such inheritance by cutting off the tails of a few generations of mice.

The theory of pangenesis apparently explains a great deal, but it involves so many unprovable assumptions as to the nature and behaviour of the "gemmules" that it cannot be accepted as more than what Darwin himself termed it, a provisional hypothesis or speculation.

It is interesting to observe that Darwin finds the *cause* of variation in the direct influence of the environment, including under that term the effects of use and disuse upon the organism. In this respect he agrees with the views of Lamarck and differs widely from those of Weismann and many other modern biologists, who deny, either totally or in part, the possibility of the inheritance of acquired or somatogenic characters. It will have been noticed that the theory of pangenesis is of an essentially pre-formationist character, for it assumes the existence, within the fertilized egg, of an immense number of material particles (gemmules) which in some way or other represent the different inheritable characters of the body.

In accordance with Weismann's theory, which is also pre-formationist in character, the germ cells of multicellular plants and animals may be regarded as so many unicellular organisms, which multiply by fission and periodically, if they chance to meet with mates, conjugate with one another. Their cytoplasm as well as their chromatin is directly continuous from generation to generation just as it is in a dividing Amœba, and theoretically there is

no reason why the constant succession of germ cells should ever be interrupted by death. The soma, or body, however, stands in a very different position. It may be regarded as a kind of appendage thrown off from the chain of germ cells after each conjugation, and resulting from the fact that most of the cells arising from the segmentation of the fertilized egg not only remain together in intimate association with one another but become specialized in various directions and co-operate with one another to form a complex multicellular individual. Having exhausted its powers of growth and renewal this individual body sooner or later dies; but the germ cells periodically renew their powers of cell-division by conjugation and, under favourable conditions, go on for ever.

According to Weismann, inherited characters are transmitted not from soma to soma but from germ cell to germ cell, by virtue of the continuity of the germ plasm. The soma has little if any influence upon the germ cells which it contains beyond that which is involved in supplying them with protection and nourishment. There is no other means of communication between the soma and the germ cells, and hence somatogenic characters, which are acquired in the life-time of the individual body as the direct result of the action of the environment (including use and disuse of organs), cannot be transmitted to the germ cells and therefore cannot be inherited. The only characters which can be inherited are blastogenic characters, which arise by modification of the germ plasm in the germ cells themselves.

This denial of the transmission of so-called acquired characters constitutes the most important difference between the theories of heredity propounded by Weismann and Darwin. Both these theories postulate the existence of ultra-microscopical material particles, determinants or gemmules, but Weismann's theory allows of no transference of such particles from soma to germ cell, only from germ cell to germ cell and from germ cell to soma. There is supposed to be no mechanism for the transmission of somatogenic characters to the next generation. According to the older view the germ cells give rise to the soma and the soma to the germ cells alternately. According to the newer one the germ cells give rise to the soma and at the same time to the next generation of germ cells, while the soma gives rise to nothing but itself and ultimately perishes.

The contrast between the two views is clearly expressed in the

accompanying diagram (Fig. 83), in which, for the sake of simplicity, the complication introduced by the process of conjugation of the germ cells has been ignored.

The inheritance of somatogenic characters being denied, Weismann is obliged to seek the origin of variations from some source other than the action of the environment and use and




FIG. 83.—Diagram to illustrate the contrast between Darwin's Theory of Pangenesis and Weismann's Theory of the Continuity of the Germ Plasm.

The figures represent an imaginary organism with four processes given off from the soma or body, which is supposed to contain only a single germ cell (dotted). Three generations are represented, and for the sake of simplicity the complication introduced by the periodical conjugation of male and female germ cells is omitted. Figs. A, B, C show how an acquired character—the elongation of one of the processes as a result of its use for some special purpose—may be supposed to affect the germ cells through the migration of gemmules (indicated by the small arrows), and thus be transmitted by heredity in accordance with the theory of Pangenesis. Figs. A′, B′, C′ show how such an acquired character is, in accordance with Weismann's theory, unable to make any impression upon the germ cells and is therefore not transmitted by heredity. In the first case the germ cells of each generation are supposed to arise from the soma; in the second case they are supposed to arise more or less directly from the preceding generation of germ cells, which also gives rise to the soma in which they are enclosed, as indicated by the large arrows.

disuse, and he finds it, as we have already seen in Chapter XII., chiefly in the chance permutations and combinations of ancestral "determinants" that take place in the maturation and fertilization of the germ cells.

The long-drawn-out logomachies that still obscure the problem before us have always been largely, if not chiefly, concerned with the definition of terms.

It is, of course, obvious that inasmuch as any organism differs to a greater or less extent from its ancestors, the differences being as a general rule greater in proportion to the remoteness

of the particular ancestor with which it is compared, the differentiating characters must have been acquired, in the ordinary sense of the word, during the interval which separates the two generations in question. For example, there can be no reasonable doubt that birds are descended from ancestors which were reptilian in character and had no feathers. Feathers have unquestionably been acquired somehow or other during the progress of the bird's evolution. This, however, is not the sort of acquisition the inheritance of which is in dispute. Weismann and his followers would deny altogether that feathers originated as somatogenic characters; they would say that certain apparently fortuitous modifications in the constitution of the germ cells themselves were responsible for the first appearance of feathers—probably in an extremely rudimentary form—and that this new character proving to be of value in the struggle for existence was preserved and fostered by natural selection until after a long process of evolution the elaborate plumage of existing birds was perfected.

It is no less obvious that the term "congenital," so much used in medical literature, is apt to be extremely misleading. A congenital character is merely one with which an individual is born, but in the mammals, for example, birth only takes place after a longer or shorter period of gestation in the womb of the mother, during which there has been abundant opportunity for the acquisition of characters that were in no way represented in the germ cells. It is to be feared that much discussion on the inheritance of such diseases as alcoholism and syphilis has been rendered perfectly futile by failure to recognize the distinction between what is really germinal (or blastogenic) and what is merely congenital.

It is one of Weismann's chief merits that he endeavours, though perhaps not altogether successfully, to give precision to the terminology employed in discussions on heredity. He does so in these words:—

"By *acquired* characters I mean those which are not preformed in the germ, but which arise only through special influences affecting the body or individual parts of it. They are due to the reaction of these parts to any external influences apart from the necessary conditions for development. I have called them '*somatogenic*' characters, because they are produced by the reaction of the body or soma, and I contrast them with the '*blastogenic*' characters of an individual, or those which originate solely in

the primary constituents of the germ ('Keimesanlagen'). It is an inevitable consequence of the theory of the germ-plasm, and of its present elaboration and extension so as to include the doctrine of determinants, that somatogenic variations are not transmissible, and that consequently every permanent variation proceeds from the germ in which it must be represented by a modification of the primary constituents."[1]

The expression "apart from the necessary conditions for development" clearly indicates a difficulty with which Weismann was faced in endeavouring to draw an absolutely clear-cut line of demarcation between somatogenic and blastogenic. It is obviously impossible to make any sharp distinction between the influences of the environment upon the developing organism, which in fact constitute the necessary conditions of development, and those environmental stimuli to which the adult body is exposed, just as it is impossible to draw a sharp distinction between the period of development and that of adult life. From the commencement of the segmentation of the fertilized egg until the time of its final death and dissolution the organism is exposed to environmental stimuli, and, as we have already insisted, its resemblance to the parent form depends upon how far those stimuli are normal (*i.e.*, the same as those to which its ancestors were exposed) just as much as upon the actual constitution of the germ plasm. Moreover, some of the influences or stimuli which affect its development arise, as we have also insisted, from sources actually present in the germ cells, for the determinants, genes, or factors can be nothing but sources of stimulation. Any character that shows itself in the organism must be the combined result of the action of external and internal factors. We cannot divide the characters of the organism into two categories, and say that the one lot is blastogenic and the other somatogenic, except in a more or less arbitrary manner. We may, however, perhaps say that a blastogenic character is one that cannot develop without the co-operation of some specific factor in the germ cell while in the production of a somatogenic character no such germinal factor takes part.

We may at once agree with Weismann that blastogenic characters alone are transmitted from parent to offspring, but the real question is—Can a somatogenic character be converted into, or give rise to, a blastogenic one? In other words—Can a

[1] "The Germ-Plasm: A Theory of Heredity," by August Weismann (Contemporary Science Series, 1893), p. 392.

ıodification of the body or soma, arising in the life-time of the ıdividual and itself in no way represented in the germ plasm of the arent, affect the germ cells in such a way that the offspring deve-›ped from them will exhibit a corresponding modification of its ›ma ?

It is useless either to deny or to assert the possibility of the inheri-ance of such modications on any purely *à priori* grounds. The fact, it be a fact, that no satisfactory mechanism for the transference f such modifications from parent to offspring has yet been demon-trated does not justify us in denying the possibility of such trans-erence. Our decision must depend upon an unbiassed examination f the evidence which can be brought forward on each side.

For convenience of treatment we may arrange this evidence nder four heads :—(1) that derived from the study of the normal tructure and functions of the body, and the effects of changed nvironment ; (2) from the study of artificial (including accidental) ıutilations ; (3) from transplantation experiments ; and (4) from hysiological experiments.

(1) There are many perfectly normal features of the body, espe-ially in animals, that are extremely difficult to account for except ›y the theory of the inheritance of acquired characters. We have lready referred to the fact that the thickness of the human skin an be increased by continual pressure or friction, as, for example, ›y the action of golf clubs or other implements. Buffon, in the ighteenth century, called attention to the thickness of the skin on he sole of the human foot,[1] which he evidently regarded as an cquired character perpetuated by inheritance. This case has more ecently been investigated by Richard Semon, one of the staunchest upporters of the doctrine of the inheritance of acquired characters, whose little book, "*Das Problem der Vererbung erworbener Eigen-chaften*," published in 1912, contains an interesting discussion of he whole subject.

Semon shows that the skin of the foot-sole begins to thicken as arly as the fifth month of fœtal life, and therefore many months ›efore it comes in contact with the ground, so that the thickening annot be produced in the fœtus as a merely somatogenic character, ›y pressure and friction, though it was probably acquired in this nanner in the first instance. If this view be correct this would ›ppear to be an example of precocious inheritance, the character ppearing in later generations at an earlier date in the life-history

[1] See quotation on p. 379.

than when it first arose, a very well-known phenomenon. The opponents of these views would no doubt attribute the precociously thickened foot-sole to the all-pervading influence of natural selection. They would say that the thickness of the skin is subject to variation, that these variations (presumably mutations) are heritable, and that the thickened soles have enabled their possessors to survive in the struggle for existence, while those with thinner soles have succumbed. This view seems to be finally negatived by the fact that the thickened sole would in any case be produced as a somatogenic character as soon as ever the infant began to walk, so that the fact of its being already present before birth can hardly be supposed to confer any important advantage upon its possessor such as might give opportunity for the action of natural selection.

It is a well known fact that the "habit" and even the structure of a plant are largely determined by the conditions under which its growth takes place.[1] A plant growing in a hot-house may acquire a very different habit from another of the same species growing in the open air. Many alpine or sub-alpine plants have become adapted to their peculiar environment by various highly characteristic modifications, amongst which a reduction in the size of the leaves is one of the most conspicuous, and such plants may be induced to change their mode of growth by simply removing them to sufficiently warm and sheltered situations, in which their habit may come to approach that of their lowland relatives. In such cases it is difficult to say how far the habit of the plant, whether alpine or lowland, is really "inherited," or how far it may be produced afresh in each generation as a direct response to environmental stimuli.

It appears, however, from the observations of Bordage,[2] that peach trees in the climate of Réunion gradually acquire an almost evergreen habit, and that this character is hereditarily transmitted, being exhibited by seedlings of the modified trees when grown in situations where the peach is usually deciduous. Dr. Bordage considers, and it appears to us that he has good reason for so doing, that his observations and experiments definitely prove, in the case of plants, the hereditary transmission of characters acquired under the influence of a change of climate.

To take another example, it has been shown that in rats and

[1] The reader should consult the quotations from Lamarck bearing upon this point given in Chapter XXIV., especially the case of *Ranunculus aquatilis*.

[2] Edmond Bordage, "A propos de l'hérédité des caractères acquis" (Bulletin Scientifique de la France et de la Belgique. Tome XLIV. Paris, 1910).

mice certain modifications in bodily structure are produced as the result of raising or lowering the temperature to which the young animal is exposed during its growth, and such modifications appear to be inherited. Sumner[1] found, as the result of a large number of careful measurements, that mice reared in a warm room (about 21° C.) differed considerably from those reared in a cold room (about 5° C.) as regards the mean length of the tail, foot and ear, which were longer in the former than in the latter. The same differences occurred to a recognizable extent in the offspring of the warm room and cold room parents, although these offspring were all reared together in a common room under identical temperature conditions.

Observations such as these lead us to hope that the question of the inheritance or non-inheritance of somatogenic characters which have undoubtedly arisen in response to the direct action of the environment may, before long, be answered conclusively. They doubtless require confirmation and extension, but they afford very strong evidence in favour of the inheritance of such characters.

Professor Eigenmann[2] has arrived at very similar conclusions as a result of his careful study of animals which live in dark caves. A very characteristic feature of such animals is the bleaching which they undergo, due to the loss of pigment. Professor Eigenmann regards this character as due in the first place to the direct influence of the environment (*i.e.* the absence of light) upon the individual. He tells us "The bleached condition of animals living in the dark, an individual environmental adaptation, is transmissible, and finally becomes hereditarily fixed." In Amblyopsis, one of the blind cave fishes, the fixation of this character has become so complete that even when the young are reared in the light they develop without pigment—the originally somatogenic character has apparently become blastogenic. In the well known European Proteus—a tailed amphibian which lives in subterranean waters—on the other hand, it appears that the bleached condition has not yet become so firmly established, for this animal becomes darker when exposed to the light. Professor Eigenmann points out that "natural selection cannot have affected the coloration of the cave forms, for it can be of no consequence whether a cave species is white or black."

[1] Francis B. Sumner, "An Experimental Study of Somatic Modifications and their Reappearance in the Offspring" (Archiv für Entwicklungsmechanik der Organismen, Bd. 30, 1910).

[2] "Cave Vertebrates of America. A Study in Degenerative Evolution" (Washington: Carnegie Institution, 1909).

We do not know how many generations it may take to effect the fixation of a character acquired slowly under the influence of a constantly repeated or continuous environmental stimulus, but the fact that human beings have not yet learned to speak without being taught shows that the number may, in some cases at any rate, be very large. Speech, however, is a comparatively recent acquisition in the human race and many of the higher animals perform actions without being taught which their ancestors may very well have originally learnt to perform by observation or experience. It would be extremely difficult to explain the nest-building habits of birds, and other so-called "instincts," except as having been originally acquired in this way in the life-time of the individual.

(2) As regards the alleged inheritance of mutilations, we may quote two typical cases from amongst a number collected by Professor Brewer and given in Professor Cope's "Primary Factors of Organic Evolution." [1]

"A female (and very prolific) cat, when about half-grown, met with an accident. 'Her fine, long tail was trodden on and had a compound fracture, two vertebræ being so displaced that they ever after formed a short offset between the near and far end of the tail, leaving the two out of line. At first I noticed that out of every litter of kittens some had a tail with a querl in it.' With successive litters the deformity increased, until 'not a kitten of the old cat had a straight tail, and it grew worse in her progeny until now we have not a cat with a normal tail on the premises' (in a cat-population of six or eight, exclusive of young kittens). 'The tails are now in part mere stumps, some have a semicircular sweep sideways, and some have the original querl. Perhaps the deformity was somewhat aggravated by in-and-in breeding and by artificial selection practised by my Chinaman, who, with the perversity of his race, preferred the crooked tails, and thus preserved them in preference to the normal kittens. There are no other abnormally-tailed cats in the neighbourhood.'"

"A person, when a boy of ten years, cut the terminal phalange of the little finger of his left hand with a sickle. The joint was not injured, nor was the function of the finger seriously impaired. There was, however, an obvious deformity. The finger was ill-shaped and crooked, and the nail abnormal. He married and had two children, the first a son, with normal fingers, the second a daughter, who had the little finger of the corresponding (the left) hand deformed from birth in the same

[1] The Open Court Publishing Co., Chicago, 1896.

manner. The function of the finger was not seriously injured, but the deformity was precisely the same in shape, even to the malformation of the finger-nail. She died at thirty, without children, consequently no observation on a succeeding generation could be noted. None of his other kindred had malformed fingers, nor had any ancestor of the child for at least three generations, and there was no knowledge of any such in the more remote ancestry."

Against such remarkable but quite exceptional cases as these, which certainly seem to be well authenticated, must be set the numerous instances in which artificial mutilations, even though repeated for many generations, are known to have produced no heritable effect. Weismann makes the following observations on this point :—

"Experiments on mice also showed that the cutting off of the tail, even when performed on both parents, does not bring about the slightest diminution in the length of tail in the descendants. I have myself instituted experiments of this kind, and carried them out through twenty-two successive generations, without any positive result. Corroborative results of these experiments on mice have been communicated by Ritzema Bos and, independently, by Rosenthal, and a corresponding series of experiments on rats, which these two investigators carried out, yielded the same negative results.

"When we remember that all the cases which have been brought forward in support of an inheritance of mutilations refer to a *single* injury to one parent, while, in the experiments, the same mutilation was inflicted on both parents through numerous generations, we must regard these experiments as a proof that all earlier statements were based either on a fallacy or on fortuitous coincidence. This conclusion is confirmed by all that we know otherwise of the effects of oft-repeated mutilations, as for instance the well-known mutilations and distortions which many peoples have practised for long, sometimes inconceivably long, ages on their children, especially circumcision, the breaking of the incisors, the boring of holes in lip, ear, or nose, and so forth. No child of any of these races has ever been brought into the world with one of these marks ; they have to be re-impressed on every generation." [1]

These remarks are no less applicable to the docking of the tails of sheep and dogs, and, in short, it cannot be seriously questioned that in the vast majority of cases the results of artificial or accidental mutilations are not transmitted from parent to offspring, a circum-

[1] Weismann, "The Evolution Theory" (London, 1904), Vol. II., pp. 65-6

stance for which the human race, especially in time of war, may be devoutly thankful. The fact that no one has yet succeeded in producing experimentally a heritable mutilation, however, does not prove that such a phenomenon may not occur exceptionally and as the result of peculiar conditions of which we know nothing. Weismann's arguments can hardly be regarded as conclusive in the face of such strong evidence as that collected by Professor Brewer. Moreover, there appears to be considerable difference of opinion as to whether or not the effects of circumcision are ever inherited. Darwin, in discussing this point,[1] admits that it is possible that all the recorded cases of apparent inheritance of such effects may be accidental coincidences, but the fact that there are such recorded cases prevents us from accepting the sweeping generalization which Weismann makes in the last sentence of the paragraph above quoted.

(3) Another line of inquiry is opened up by the possibility of transplanting parts of one individual into the body of another, with which they may become completely incorporated. It was hoped that in this way conclusive evidence might be obtained as to the alleged influence of the body upon the germ cells. One of the earliest experiments of this kind was that of the late Sir Francis Galton on the transfusion of blood in rabbits. White and black rabbits were employed, and it was found that the transfused blood had no effect upon the colour of the offspring. This result was supposed by Galton to be fatal to Darwin's theory of pangenesis. At any rate, there could be none of his supposed "gemmules" in the blood, but Darwin replied that he never supposed that there were. Obviously, if the theory is to be applicable to plants and to the lower animals, the gemmules must reach the germ cells in some other manner.

More instructive results are to be expected from the transplantation of the germ cells themselves, or of the gonads in which these are contained. Heape, in 1891, succeeded in removing segmenting eggs of an Angora rabbit from the parent and placing them in the uterus of an ordinary doe. The foster-mother had no apparent influence upon them and they developed into Angora rabbits.

Guthrie, in 1908, claimed to have obtained positive results from the transplantation of the ovaries of black hens into white ones, and *vice versâ*. He found that a black hen, into which a "white" ovary had been transplanted, produced, after mating with a white

[1] "Animals and Plants under Domestication" (2nd Ed., 1882), Vol. I., p. 467.

cock, about equal numbers of white and black spotted chicks, and concluded that the black-spotting was due to the influence of the black foster-mother upon the transplanted "white" eggs in her body. Davenport, however, repeated these experiments, and made it tolerably certain that Guthrie's conclusions are erroneous, and that what really happens in such cases is that the ovary of the so-called foster-parent regenerates from fragments left behind after the operation, while the introduced ovary fails to grow. Owing to the difficulty of removing the entire ovary without fatal effects, fowls are very unfavourable subjects for such experiments.

Castle and Phillips, however, have succeeded, in the case of guinea-pigs, in really replacing the ovary of a foster-mother by that of an individual of a different variety, though only a small percentage of their operations proved successful. In these cases they were able to detect no influence of the foster-mother upon the eggs, which developed exactly as if they had remained in the original parent, so that the result was again a purely negative one.

Kammerer, on the other hand, claims to have obtained positive results in the case of salamanders; peculiar colour markings, which had been experimentally produced by submitting the foster-mother to a changed environment, being reproduced in the offspring developed from an ingrafted ovary. Curiously enough, he found that the natural colouration of a foster-mother that had not been experimentally modified had no influence upon the offspring produced from ingrafted ova—transmission was only demonstrated in the case of artificially-produced modifications of the maternal colour markings.[1]

In view of such highly contradictory results, we must suspend our judgment as to the evidential value of these experiments.

(4) The first physiological experiments which we shall describe are those of Professor Agar[2] upon the little freshwater shrimp *Simocephalus*. This investigator found that by feeding this tiny crustacean upon a special culture of unicellular plants he could bring about a well-marked modification of its bodily structure. Practically the entire animal is normally enclosed in a bivalved shell, like that of a mussel, whose edges come almost close together in the middle line below. When the developing animal is fed upon the special food-culture, however, the valves become bent back, so that the shell remains very widely open and cannot be closed. This

[1] *Vide* "*Die Abstammungslehre*" (Jena: Gustav Fischer, 1911, p. 130)
[2] "Philosophical Transactions of the Royal Society," series B, 1913.

is clearly a somatogenic modification due to the influence of the special kind of food. If, now, the modified individuals are replaced under normal conditions, where they are deprived of the special food to which they owe their modification, they produce eggs which, on development, give rise to young individuals resembling the modified parents in the reflexion of the valves of the shell. This certainly looks like a case of the inheritance of an acquired character, and in a certain sense it is so, but the effect soon wears off and disappears completely after a couple of generations. It appears that what has happened is merely this. The special diet has caused the production in the body of the original parent of some product of metabolism which is the effective cause of the modification in question, and a small quantity of this substance has found its way in the ordinary course of nutrition to the growing eggs contained in that body and has thus been carried over to the next generation, on which it produces the same effect. We know from the study of hormones, and from other sources,[1] that almost infinitesimal quantities of specific chemical substances are able to produce very conspicuous and very definite effects upon the animal body, so there is nothing very surprising in this case, but no permanent modification of the germ plasm is effected, and, hence, there is no true inheritance. It is a case of what is sometimes termed " parallel induction," in which the body and the germ cells are exposed at the same time to the same stimulus, but in the case of the germ cells, of course, the effect is delayed until the development of a new individual takes place. The term " somatic induction," on the other hand, is applied to cases, if such there be, in which the body is affected first, and then, in turn, influences the germ cells in such a way that the effect will be transmitted to the next generation.

Another way of approaching our problem has been opened up by the brilliant researches of physiologists upon the composition and properties of the blood serum in the higher animals. It has been shown not only that the serum of different animals exhibits specific reactions, whereby the degree of consanguinity of different species can be chemically tested, but that the blood of each species is highly intolerant of the introduction into it of proteid substances derived from other species, and immediately proceeds, by the formation of so-called " antibodies," to destroy them. It appears that a special antibody is formed for each kind of foreign proteid that may happen to be introduced. Such substances as spermatozoa, blood corpuscles.

[1] Compare the action of magnesium chloride on the larva of *Fundulus* (p. 156).

nervous tissue, and fragments of the lens of the eye, are destroyed in this way, and, as the blood of the animal under experiment can never have had any experience of these bodies under normal conditions, it is extremely difficult to understand how it can have acquired the power of producing the appropriate antibody necessary for dealing with each new emergency as it arises.

Each antibody, or antitoxin, moreover, may be produced in large excess of the amount actually required to deal with the immediate situation, and a highly " sensitized " serum may thus be obtained. It was with such a serum that Messrs. Guyer and Smith carried out the experiments which we are about to describe.[1] It was prepared by grinding up rabbits' lenses with normal salt solution and injecting the mixture into the veins of fowls. The serum of the fowls' blood became " lens-sensitized," capable, that is to say, of dissolving the proteid substance of which the lens of the rabbit's eye is composed.

Messrs. Guyer and Smith injected this serum into the veins of a pregnant rabbit and found that the young animals, when born, exhibited a tendency to develop defective eyes—especially as regards the lens, which tended to be more or less opaque or liquefied. So far, of course, there is no question of any inheritance of acquired characters. The injury to the eyes is purely somatogenic, resulting from the action of the lens-dissolving antibody, or lysin, conveyed directly from the blood of the parent to that of the fœtus and ultimately reaching the eye. It was found, however, that when the young rabbits with defective eyes in their turn produced offspring the defect was inherited, and, instead of gradually dying out in succeeding generations, went on increasing until in some cases the whole eye almost disappeared. It has been followed through at least six generations of rabbits, and, what is still more important as showing that we are probably dealing with a true case of inheritance, it has been shown to be transmissible through the male parent, thus precluding the possibility that it may be due to the action of the maternal blood upon the fœtus *in utero.*

This case brings us back again to the question of parallel induction. We can hardly suppose that it is the presence of the defective lenses in the rabbits of the first modified generation that causes the corresponding change that must take place in the germ cells. It is much more likely that the two modifications occur simultaneously as the result of the same disturbing cause, *viz.*, the presence of the

[1] *Vide* "Journal of Experimental Zoology," Vol. 26, 1918, and Vol. 34, 1920, and Vol. 38, No. 4, January, 1924, where their results are abundantly continued and extended.

lens-dissolving substance in the blood. There is a great difference, however, between this case and that of *Simocephalus*, for in the latter the somatogenic modification of the shell had passed away completely in the third generation. Here the effect seems to be permanent.

Admitting, however, that this is not a case of somatic induction, there seems no reason for denying that it is a case of inheritance of an acquired character. All that is required to bring about such inheritance is that the factors contained in the germ plasm should be permanently modified in such a way that they or their products may influence the body of the developing organism in the same manner as that in which the parent body was influenced by the original stimulus. We do not as yet know how such a specific modification of the factors in question can be brought about, but the fact, if it be established, is perhaps no more difficult to explain than the undoubted fact that the blood is able to produce a specific antitoxin for each foreign proteid that may be introduced into it. It is a question of biochemistry, and we must leave it to the specialists in that department of science.

The germinal factors being, *ex hypothesi*, living, self-propagating units, there seems no reason why a chemical change in their molecular constitution, once established, should not be perpetuated. In this respect they may be compared to bacteria, whose power of affecting other organisms can, as is well known, be artificially modified by suitable methods of culture, the modifications, once produced, being handed on from generation to generation of these minute organisms. Just as these modified bacteria exert a modified influence upon the body of their host, so, we may be allowed to suppose, do the modified factors in the germ plasm exert a modified and a modifying influence upon the developing organism.

If these physiological experiments prove nothing else, they at least indicate very clearly that it is possible to tamper with the delicate mechanism of heredity in such a way as to bring about heritable modifications of the body. We are tempted to suppose that it is only when a modification arising in the body is associated with the formation of some specific chemical substance that can reach and act upon the factors in the germ plasm that it will have any chance of being transmitted by heredity. We are not obliged to suppose that the heritability of the modification must be established immediately, if at all. Changed conditions of the environment, acting upon many generations, as in the case of alpine plants,

may result, not only in an altered mode of growth, but also in metabolic changes, which probably, indeed, come first. Some altered product of metabolism may at length reach the germ cells and bring about modification of the factors, but it may take a long time to effect such a result. It may be that inheritance of acquired characters is always attributable to parallel rather than to somatic induction, and that if Professor Agar's *Simocephalus* had been exposed for a sufficient number of generations to the influence of the special diet, the modification produced thereby would have become permanently heritable, though this is not his own view.

We have already referred to the fact that the control of the growth and functions of the living body is largely attributed by modern physiologists to the action of chemical substances, termed hormones, which circulate in the body fluids and may exert their influence in regions far distant from the places in which they themselves were secreted.[1] Mr. J. T. Cunningham appears to have been the first to apply these ideas to the explanation of the phenomena of heredity, and has recently given a full exposition of his views in a book from which we may quote the following brief passage :—

"The hormone theory supposes that the somatic modifications due to external stimuli—in the case of the flat-fish the disappearance of pigment from the lower side, torsion of the orbital region of the skull, and the extension of the dorsal fin—modify the hormones given off by these parts, increasing some and decreasing others, and that these changes in the hormones affect the determinants, whatever they are, in the gametocytes within the body." [2]

It will be seen that the views expressed above have much in common with Mr. Cunningham's theory, though we should be more inclined to attribute both the changes in the body and those in the germ cells to the action of some "hormone" resulting from altered metabolism.

On the whole, then, the available evidence seems to indicate that suddenly and exceptionally acquired characters, such as mutilations, are occasionally but only rarely inherited to such an extent as to be recognizable, while, on the other hand, the continued action of some external stimulus, extending perhaps over many generations, in the long run affects the germ cells as well as the somatic cells and thus the modifications in question become truly blastogenic.

[1] *Vide* pp. 126, 193.
[2] *Vide* "Hormones and Heredity" (London: Constable & Co., Ltd., 1921), p. 218.

We must look upon the germ cells as highly conservative bodies, possessed of great inertia, which can only be induced very slowly in normal circumstances, or by some sudden revolution, as to the nature of which we can only speculate, in abnormal circumstances, to alter their constitution. This conservatism is no doubt of great value as a check upon the perpetuation of accidental and unfavourable modifications. The adaptation of the individual to its particular environment is to a large extent provided for by somatogenic modifications which arise in its own life-time. What suits one individual, however, may not suit its successors, which may have to live under more or less widely different conditions, and for progressive evolution what is needed is an average adaptation of the race to an average environment. Hence the germ plasm in its evolution lags behind the soma and is only very slowly impressed with those characters which experience has shown to be of permanent value to the race. It is a kind of second chamber which acts as a useful check upon too radical tendencies.

We must now turn our attention to what is known as the "Mnemic"[1] theory of heredity, which, taking for granted the influence of the body upon the germ cells, is not primarily concerned with the actual mechanism whereby that influence may be exerted. This theory is associated more especially with the names of Hering, Samuel Butler,[2] and Semon.[3] Its central idea may be expressed by saying that modifications of the soma act as stimuli, which make more or less permanent impressions or "engrams" upon the germ cells in much the same way that stimuli of various kinds received through the sense organs make impressions upon certain cells in the brain. In the case of the brain cells the original impressions may become dormant and be revived later on as memories, which are a kind of mental reproduction of the phenomena to which the impressions were originally due. In the case of the germ cells it is supposed that the engrams also become dormant, but are aroused to activity again in the course of the development of these cells into new organisms, exerting their influence in such a manner as to bring about a

[1] From the Greek μνημη, memory.

[2] See Butler's "Life and Habit" (2nd Edition, London, 1878) and "Unconscious Memory" (New Edition, London, 1910), the latter of which contains a translation of Hering's lecture "On Memory as a Universal Function of Organized Matter."

[3] Semon, "Die Mneme als erhaltendes Prinzip im Wechsel des organischen Geschehens," 3rd Ed., Leipzig, 1911.

kind of reflection, in the body of the offspring, of the parental characters.

The faculty of receiving and responding to stimuli of various kinds is one of the most characteristic features of living protoplasm. In the higher animals this function is more or less concentrated in definite sense cells, each of which is adapted for the reception of stimuli of one particular kind. The visual sense cells are adapted for the reception of stimuli from the light-vibrations of the ether, the auditory sense cells are stimulated by vibrations of the air or water in which the animal lives, the olfactory sense cells are stimulated by the chemical action of material particles, and the tactile cells by the mechanical stimuli of contact and pressure. In such an organism as the unicellular Amœba, on the other hand, all parts of the superficial protoplasm are probably sensitive to stimuli and no special organs of sense are developed. We may well suppose, therefore, that the undifferentiated germ cells of the multicellular animals and plants are sensitive to stimuli received from the somatic cells, though it may be impossible in the present state of our knowledge to determine with certainty the nature of these.

It is well known that, apart altogether from the highly specialized brain cells, living protoplasm frequently has the power not only of receiving and responding immediately to stimuli of various kinds, but also of storing up impressions or engrams for future use. This is demonstrated quite clearly by the phenomena known as " after-effects " in various plants and animals. One of the best known examples of such after-effects is seen in the daily periodicity of plant growth. The light of the sun acts as a restraining or inhibiting stimulus upon the rate of growth of ordinary plants. In consequence of this the plant grows most rapidly in the early hours of the morning after a prolonged exposure to darkness, and most slowly in the afternoon, after long exposure to daylight. It has been shown that this daily periodicity, or variation in rate of growth in correspondence with the periodic variation in environment, is continued when the plant is kept in perpetual darkness, and the direct stimulation of changing environment thereby rendered impossible. In other words, the plant, though entirely devoid of any nervous system in the ordinary sense of the term, establishes a habit, which must depend upon something analogous to memory on its part.

The mnemic theory of heredity is based, as we have seen, upon a comparison of the phenomena of inheritance with those of memory.

The latter are reasonably explained by supposing that impressions received by certain cells of the brain may be stored up as "engrams" in these cells for use on future occasions, when, under appropriate stimulation, they give rise to mental conditions corresponding to those produced by the original stimuli. The stimulus which evokes a memory is commonly the repetition of some stimulus which was originally associated with the thing remembered. Thus the sight of a person whom we have not seen for a long time, or even of his portrait, will evoke a whole train of memories connected with that person.

The degree of accuracy with which we remember any occurrence depends partly upon the nature of the occurrence itself and partly upon the frequency with which it has been brought under our notice. The first time we take a walk we may have to pay attention to every turning and every signpost in order to find our way at all, but if we take the same walk many times we at length become so familiar with it that we may be thinking of other things the whole time and not consciously notice a single landmark from start to finish. As Samuel Butler has most forcibly pointed out, the more perfect memory becomes the less is it accompanied by consciousness of the things remembered, as when a skilled musician, playing a composition for perhaps the hundredth time, is quite unconscious of the individual actions which he performs by memory in striking the notes, while a beginner, who has only played the same piece once or twice before, may be acutely conscious of every note which he strikes. The development of an individual organism from the egg is, according to the mnemic theory, merely an unconscious repetition, by memory, of acts which have been performed many thousands of times by its ancestors, and, as in the performance of a piece of music, each successive act constitutes the stimulus which calls forth the next.

The fertilized ovum may be looked upon as being charged with the latent memories of past generations. The unconscious memory of what it did last time it was a fertilized ovum prompts it to divide into two cells, this re-arrangement of its constituents supplies another stimulus which prompts it to a further division, and so on through all the stages of ontogenetic development. In the words of Professor Francis Darwin, "the rhythm of ontogeny is actually and literally a habit."[1]

[1] Presidential Address to the British Association, Dublin, 1908

Progressive evolution takes place owing to the fact that each successive generation may add a little bit to the record on its own account, this addition being the result of some new experience due to some difference in its environment as compared with the environment of its predecessors.

The mnemic theory, thus briefly outlined, is undoubtedly of considerable interest, especially from the historical point of view, but it may be questioned whether any great advantage is to be gained by comparing the phenomena of heredity with those of memory, which are themselves no less difficult to explain. The theory really takes us no further than the " common-sense " view which we enunciated in Chapter XII., in accordance with which the offspring resembles its parents just in so far as it develops from the same kind of germ plasm and is subjected to the same series of internal and external influences (or stimuli) during its development. In the elucidation of the nature and mode of action of these stimuli much remains to be done, but the veil of mystery which formerly enveloped the problem has already to a large extent been torn away.

PART IV.—THE THEORY AND EVIDENCE OF ORGANIC EVOLUTION: ADAPTATION

CHAPTER XV

Organic evolution *versus* special creation—The origin of living things—Mechanism and vitalism—The problem of individuality.

At the present day we see the surface of the earth teeming with hosts of living things, incalculable in number and of endless diversity in form and structure. Every situation where life is possible is occupied by plants or animals of some kind or other, all specially adapted in bodily organization to the conditions under which they have to maintain their existence. From the bleak and inhospitable summits of high mountain ranges to ocean depths which can be measured in miles; from the perpetually frozen circumpolar regions to the torrid zone on either side of the equator, living things abound. Seas, rivers, lakes, dry land and air have all alike been taken possession of by representatives of the animal and vegetable kingdoms. A single drop of water may contain thousands of organisms, and every chalk-cliff, coal-seam or peat-bog testifies to the countless myriads which have lived in past times and whose remains have contributed in no small measure to the formation of the earth's crust.

In the animal kingdom alone it is probable that at least a million different kinds or species are living on the earth at the present day. Some half million or so have already been discovered, named and more or less imperfectly described, while every exploring expedition brings back many which have never before been seen.

Nevertheless there must have been a time when no living things whatever existed on the earth. According to the nebular hypothesis our planet is still gradually cooling from a molten state, preceded probably by an incandescent gaseous condition, which must have rendered the existence of any protoplasmic organism a physical impossibility. Protoplasm becomes

coagulated and thereby destroyed as living substance at comparatively low temperatures, and cannot have been present on the earth until the surface of the latter had not only solidified but also cooled down to something approaching its present degree of heat.

Living things must therefore have first put in an appearance at some definite period well advanced in the earth's history. According to the biblical account given in the Book of Genesis their advent was due to a series of special acts of creation performed by the Creator at the appropriate time, and this account forms the basis of the doctrine of Special Creation which still survives amongst uneducated people. Upholders of this doctrine maintain that each kind of plant or animal was not only created as a separate kind and in a state of full perfection, but was specially designed to suit the conditions under which it was placed, and in this way the marvellous adaptation of plants and animals to their environment is supposed to be accounted for. The fish was created to swim in the sea, the horse to run on dry land, the monkey to climb in the tree and the bird to fly in the air, and each was constructed in accordance with its foreseen requirements. Moreover, each species is supposed to be immutable, propagating its own kind by reproduction but never changing into a different kind.[1]

Such a view of the origin of living things could only have arisen in a state of almost complete ignorance of the phenomena which have to be accounted for, and at the present day it has been entirely superseded, as a scientific theory, by the doctrine of Organic Evolution. This doctrine teaches us that species or kinds are not immutable but are subject to changes whereby one may give rise to another, and that all existing species are the more or less modified descendants of pre-existing ones. Modern biologists, moreover, maintain that the further back we trace the ancestral history of living things the less diversity of structure do they show, until finally, if we could trace them back to their origin, we should find all the different lines of descent converging towards a common starting point far back in geological time. We shall see presently that the adaptation to environment which forms such a characteristic feature of all living organisms can be explained just as well in accordance with the theory of organic

[1] Compare the quotation from Linnæus on p. 233 (1st footnote) and that from Buffon on p. 380.

evolution, or transmutation of species, as in accordance with that of special creation.

The fundamental difference between these two opposing and irreconcilable doctrines can be expressed by means of the accompanying simple diagrams (Fig. 84):—




FIG. 84.

The letters A—E are supposed to represent five closely related existing species in each case. According to the doctrine of special creation each of these species has persisted without alteration from the time when it was first created, so that the ancestral species may be represented by the letters A′ B′ C′ D′ and E′, and the lines of descent of existing species run parallel with one another. The idea of evolution, on the other hand, is expressed by showing these lines of descent diverging from a remote ancestral species, *x*, which may have been quite different in character from any of the existing species.

Any existing species at the present day is made up of a larger or smaller number of individuals, which are not all exactly alike but represent so many more or less distinct varieties, and we

know from observation that these varying individuals can be traced back to a common parentage. This is represented in the upper parts of both diagrams, where a 1—8, b 1—7, c 1—4, d 1—5 and e 1—5, on each side, are supposed to represent small groups of varieties of the species A B C D and E respectively, each group being descended from some common ancestor (or pair of ancestors) which itself belonged to the species.

The study of this diagram is alone sufficient to afford strong presumptive evidence in favour of the view of the evolutionist as against that of the upholder of special creation, for the evolutionist in his imagination extends backwards into the past the processes which he sees taking place constantly at the present day, and endeavours to account for the origin of species in accordance with what he knows to be true of the origin of varieties. In other words, the diagram expressing the idea of organic evolution is consistent throughout, whereas that which represents the idea of special creation is made up of two incongruous portions, and is therefore less likely to be correct. The great weakness of the doctrine of special creation, however, lies in its failure to explain countless facts of comparative anatomy, embryology, geographical distribution and palæontology, all of which are readily explicable in terms of evolution. We shall deal with some of these facts in subsequent chapters.

It is obvious, then, that in order to be logically consistent the evolutionist need not postulate more than a single starting point for the evolution of the whole organic world, though he is not obliged to limit himself in this way should evidence be forthcoming that there has been more than one starting point. This brings us to the consideration of the extremely difficult and at present incompletely solved problem of the origin of the first living organisms.

It has been suggested by some that organic life is eternal and that minute germs of living matter—so-called Cosmozoa—occur floating in interplanetary space. The view that such germs may have reached the earth on meteorites has been seriously propounded, and is even associated with the name of the late Lord Kelvin. When we remember that meteorites, if they reach this earth in a solid state at all, usually do so in a more or less incandescent condition, it seems quite incredible that they should ever have formed the vehicles for the transmission of protoplasmic organisms. Even the suggestion of Arrhenius,[1] that Cosmozoa may be propelled from planet to

[1] "Worlds in the Making" (Harper & Brothers, New York and London, 1908).

planet by the *vis a tergo* of the sun's rays, is scarcely more acceptable. At any rate, nobody has ever seen a Cosmozoon, and, even if we believed in their existence, it would not help us to solve the problem of the origin of living things, but would merely transfer the scene of the event to some unknown and quite inaccessible locality.

We shall do better to inquire whether our experience of what takes place on the earth at the present day throws any light upon the problem. Many people in the past have held, and some few still maintain, that living things may, even now, arise, more or less suddenly, from not-living matter. This is known as the doctrine of "Spontaneous Generation" or *abiogenesis*. One of the earliest expressions of this idea is met with in classical mythology, in the story of the birth of Aphrodite from the sea-foam; and Vergil, in the Georgics, accepts the principle involved therein apparently in perfectly good faith.

Vergil's account of the manner in which a swarm of bees may be produced from the decomposing body of a dead ox affords a very striking illustration of that want of scientific training in observation and reasoning which has led to so many erroneous beliefs. He tells us, with much elaboration of detail, that if the body of an ox is well beaten and enclosed in a suitable chamber a swarm of bees will arise from it within a certain number of days. We now know perfectly well what may really happen under these circumstances. In the first place the supposed bees are not bees at all, but drone-flies, which superficially resemble bees, though easily recognizable as belonging to a totally different order of insects by the fact that they possess only two wings instead of four, and consequently any husbandman who followed Vergil's instructions must have been grievously disappointed in his expectations of honey. In the second place the drone-flies are not spontaneously generated from the body of the ox, or from anything else, but are hatched out, first in the form of maggots, from eggs which were laid by pre-existing flies. These maggots, having fed abundantly on the decaying carcase, presently undergo their metamorphosis and emerge as flies.

Many similar instances of alleged spontaneous generation, all resting upon gross ignorance of the real facts of the case, might be collected from the writings of ancient and mediæval authors. The cruder stories, which could be easily disproved by simple observation, were soon cast aside as fables under the influence of modern scientific methods. The invention of the microscope,


however, and the consequent revelation of a new world of hitherto invisible organisms, led to a revival of the doctrine of abiogenesis. It was noticed that organic infusions, even after boiling, presently became densely filled with various kinds of micro-organisms, especially Bacteria, and as the boiling was supposed to have killed any organisms that might have been in them at first it was argued that living things arose in them *de novo*, by spontaneous generation. This was, however, merely a revival of Vergil's story of the swarm of bees in a more refined form. Had Vergil's ox been protected from flies none of the alleged bees would have been produced, and the careful experiments of such observers as Tyndall and Pasteur have conclusively demonstrated that if the organic infusions are adequately protected from the countless microscopical germs which float in the air they will remain free from living organisms, and consequently from putrefaction, for an indefinite period, provided always that they are themselves first properly sterilized. This sterilization, however, cannot always be effected by a single boiling, for the germs of some organisms are extremely resistant to heat and special precautions have to be taken accordingly.

Every story of alleged spontaneous generation has, so far, failed to stand the test of scientific criticism and experiment, and accordingly biologists are now almost unanimous in maintaining the contrary doctrine of *biogenesis*, which teaches that, at the present day, protoplasm can only be formed by, or in connection with, already existing protoplasm, and new organisms can arise only by some process of reproduction from parent organisms.

This is sufficiently obvious of the higher plants and animals. Nobody would expect an elephant, for example, to be produced except by the breeding of elephants; but where did the first elephant come from? The answer, of course, is, that there never was a first elephant; elephants arose by gradual transformation of some pre-existing type, which, in turn, arose from some other. Life knows no beginnings, but perpetual change; and if we could trace the chain of living things back far enough we should probably find it merging quite insensibly into the inanimate world. Evolution takes place in not-living as well as in living matter, and we may be allowed to suppose that the former passed gradually over into the latter at some remote period of the earth's history. This, it is true, implies belief in a kind of spontaneous generation, but it is a rational belief which necessitates only a further extension of the idea of evolu-

tion, and by no means a belief in the sudden transformation of not-living matter into more or less highly organized plants or animals.

It was the presence of the chemical element carbon on the earth's surface that made possible the evolution of living matter. The atoms of this element are tetravalent, that is to say, they have each four linkages whereby four other atoms (or groups of atoms) may be attached to form a complex molecule. In other words, the atoms in question enter into certain definite energy relations with one another. The carbon atoms also have the power of uniting with one another in chains (usually of six), and each member of such a chain may, according to its position, be united with two or three other atoms or atomic groups of various kinds. To take a definite example, the constitution of one of the carbohydrates, a simple sugar having the empirical formula $C_6H_{12}O_6$, may be represented thus :—



Far more complex carbohydrate molecules than this are known to chemists, and the proteid molecule, which contains—in addition to carbon, hydrogen and oxygen—atoms of nitrogen, sulphur, and, sometimes, phosphorus, and even other elements, is enormously complicated in its structure. Chemists have come very near to artificially building up or synthesizing proteid molecules, but they have not yet succeeded in producing anything that exhibits the phenomena of life. The synthesis of living matter apparently now takes place only in the bodies of living organisms, though the gap between the not-living and the living was, in all probability, bridged at some remote period of the earth's history in a manner unknown to us.

We may suppose that, in the course of its progressive evolution from simple to complex, matter gradually acquired those properties which are distinctive of living organisms. We have seen already that life, so far as it can be analyzed, consists in the constant play of energy between the organism and its environment. The colloidal proteid molecule—or multi-molecule, for it consists of many complex molecules held together by feeble attraction—is well adapted to be the seat of such energy exchanges, for it undergoes decom-

positions and recombinations on the slightest provocation, liberating or absorbing energy in the process.[1]

If these views are correct, it seems almost absurd to speak of the first living organisms, for life had no definite beginning, but we may be allowed to indulge in speculations as to the form first assumed by living matter after the transition from the not-living condition had been accomplished. In the first place we may safely assume that it was comparatively simple in structure, for it is generally agreed that the evolution of the higher forms of life has been accompanied by a gradually increasing complexity of organization. It is also certain that it cannot have been animal, for animals,




FIG. 85.—Different Forms of Disease-producing Bacteria, × about 1500. (From Strasburger, after Fischer.)

a, pus cocci; *b*, erysipelas cocci; *c*, gonorrhœa cocci; *d*, bacilli of splenic fever; *e*, bacilli of tetanus; *f*, bacilli of diphtheria; *g*, tubercle bacilli; *h*, typhoid bacilli; *i*, colon bacilli; *k*, cholera bacilli.

as we have seen in a previous chapter, are dependent for their food supply upon other living things, being themselves unable to build up the proteid molecule from inorganic constituents. Green plants are the great proteid manufacturers at the present day, but only by virtue of the fact that they contain chlorophyll, which enables them to utilize the energy of the sun in the initial process of photosynthesis. Now chlorophyll itself is a very complex substance, and we cannot suppose that the first living things already possessed it. If, then, they had no other organisms to feed upon, and if they possessed no chlorophyll, how did they obtain the energy necessary to enable them to maintain life at all?

[1] For an excellent discussion of the problems here all too briefly dealt with the reader is referred to the late Professor Benjamin Moore's little book on "The Origin and Nature of Life" (Williams and Norgate, Home University Library).

The simplest and at the same time the smallest organisms visible to us at the present day are the Bacteria (Fig. 85), many of which are so minute as to be hardly recognizable even under the highest powers of the microscope. These Bacteria are neither plants nor animals, but occupy a position lower than either. They have not even attained to the dignity of perfect cells, for they exhibit no proper differentiation into cell body and nucleus, the chromatin substance, which in a typical cell is aggregated in the nucleus, being scattered in minute granules throughout the cytoplasm (*vide* Fig. 27). They contain no chlorophyll and the colourless protoplasm is enclosed in a very thin and delicate cell wall. In form they vary greatly, being sometimes spherical, sometimes rod-shaped and sometimes corkscrew-shaped, and frequently they occur united together in chains. Some of them swim about by means of cilia or flagella, others are motionless, and they reproduce by simple fission and also by the formation of spores, which have extraordinary powers of resistance and thus serve to secure the wide dispersal of these organisms by air and water.

A great number of different kinds of these Bacteria are already known to us, and doubtless a vast number still remain to be discovered. They occur practically everywhere ; earth, air and water are full of them, and they exercise a most profound influence—sometimes injurious and sometimes beneficial—upon the lives of other living things. Some of them are the active agents in the putrefaction and fermentation which are rapidly set up in dead organisms, and others are responsible for many of the most grievous ills which living flesh is heir to. Thus most of them live either as saprophytes (upon dead organic matter) or as parasites (upon living organisms) and obtain their supply of energy from already formed proteids and other complex chemical compounds.




FIG. 86. — *Nitrosomonas europæa*, × 600. (From Percival's "Agricultural Bacteriology.")

Some, however, are said to live free in the soil and to be able to derive their food supply, and with it their energy, from purely inorganic substances. These are called nitrifying Bacteria. One form, Nitrosomonas (Fig. 86), oxidizes ammonia to nitrous acid, and another, Nitrobacter, oxidizes nitrous to nitric acid, and their energy is derived from these chemical processes. In this way

they perform an important function in preparing the food material in the soil for the use of green plants, but their chief interest for us lies in the fact that they are able to build up their own proteid molecules directly from inorganic constituents without the aid of chlorophyll. They show us that such a thing is at any rate possible, and that therefore the first living things may have been able to maintain their existence without either possessing chlorophyll or having other organisms to feed upon.

It seems likely that of all the organisms known to us these Bacteria come nearest to the first living things, and yet they probably stand very far from them and represent a much later stage in the process of evolution. Minute and apparently simple as the Bacteria are, it seems more than probable that the first living things were very much smaller and simpler, so that even if we had them under the highest powers of our microscopes we should be unable to recognize them. Weismann has suggested that they may have been single biophors, *i.e.* vital units of the first order, such as he believes to constitute the ultimate living particles of protoplasm, and he has actually proposed the name "Biophoridæ" for these hypothetical free-living primordial organisms.

Even though we regard Weismann's Biophoridæ as purely imaginary, yet we have strong evidence of the actual existence of living things so small as to be beyond the limits of visibility even with the aid of the most modern optical apparatus. These ultra-microscopic organisms reveal themselves only by the effects which they produce upon the bodies of certain animals in which they live as parasites. They are so minute that they cannot be removed, like ordinary Bacteria, by the process of filtration, and are hence sometimes called filter-passers. It is said that if even so small a quantity as 0·005 of a cubic millimetre of lymph from an animal suffering from foot and mouth disease be inoculated into a healthy calf, the latter will in due course contract the same disease, although the lymph, so far as microscopical examination enables us to judge, is entirely free from organisms. Many other diseases are believed to be due to such ultra-microscopic parasites. That they are really caused by living organisms, and not merely by lifeless toxins or poisons, is indicated sufficiently clearly by the fact that a period of incubation always follows infection, during which the poisonous matter increases in amount until there is enough to produce its deadly effects, when the characteristic symptoms of the particular disease manifest themselves.

These considerations throw a new light upon the question of spontaneous generation, for if living matter is first formed in such ultra-microscopic particles and can only be recognized as living matter after it has reached a comparatively high stage of evolution, it is obvious that we are not entitled to say that it is never formed from not-living matter at the present day. We cannot see it being formed, and we probably never shall see it being formed, but it is possible that it is still being "spontaneously generated" all the same. We are not logically obliged, as we said before, to content ourselves with a single starting point for organic evolution, and it would be quite impossible to prove that all the different kinds of Bacteria, the simplest organisms visible to us, have descended from a single ancestor. They may equally well have been derived from a number of ancestral protoplasmic units which originated independently from inorganic, not-living matter. If such an event can have taken place once it may have taken place many times, and may still be taking place around us, though the imperfect means of observation at our disposal will not allow us to demonstrate the fact. We may safely affirm, however, that no living organism which we are at present capable of recognizing as such has arisen, or ever will arise, by spontaneous generation, but that all visible organisms have been derived from pre-existing organisms by some process of reproduction; that, in the course of long ages, they have undergone slow changes, whereby they have become more and more diversified and usually more complex in structure, and that in this way the evolution of the animal and vegetable kingdoms has been brought about.

The suggestions as to the origin of living things put forward in the foregoing pages have an important bearing upon the endless controversy between the so-called mechanists and vitalists. In so far as the actions and reactions upon which the phenomena of life depend are explicable in terms of chemistry and physics, we are clearly justified in looking upon the living organism as a machine, and the mechanist would have us believe that it is nothing more. The vitalist, on the other hand, maintains that there is some controlling and regulating influence at work in the living body that is lacking in inanimate matter and which is responsible for phenomena that are essentially vital and incapable of explanation in terms of chemistry and physics.

The antagonism between these two opposing schools of thought

is, perhaps, after all, more apparent than real. The mechanist can hardly deny that there is some real difference between the living and the not-living, and the vitalist must admit that, so far as chemical and physical analysis can take us—and that is a very long way—the living organism is demonstrably a piece of elaborate mechanism. We have already touched upon this point in our chapter on Amœba. It is when he uses such terms as " vital force " and " entelechy " as though they offered some real explanation of vital phenomena that the vitalist lays himself open to attack. The mechanist is no less vulnerable when he tries to make his chemical and physical interpretations cover all the manifestations of life. When we consider the phenomena of consciousness and intelligence as exhibited by the higher animals, chemical and physical explanations altogether fail us, though we may admit that these phenomena depend upon the physical structure of the brain and the chemical processes that take place therein. Consciousness and intelligence have, like other attributes of living matter, arisen slowly and gradually in the course of evolution, and it is just as impossible to say at what stage they first put in an appearance as it is to say at what stage inanimate matter first became alive. We may, perhaps, believe that, as living matter became more and more complex in its structure, it entered progressively into new energy relations with its environment, which became more and more unlike those exhibited by inanimate matter, until at length they passed in some respects altogether beyond the reach of chemical and physical explanations.

It is evident that, from the earliest stages of its evolution, the living substance which we call protoplasm has exhibited a strongly marked and highly characteristic tendency to form itself into individual organisms, each possessing a more or less definite and constant form and size. When, however, we attempt to define exactly what we mean by an individual organism, we find ourselves in a perfect maze of difficulties and contradictions. It is, in short, impossible to frame a definition of the term individual which shall be applicable throughout the whole organic world.

We have spoken in earlier chapters of the process of integration, whereby individuals of a lower order co-operate and combine to form individuals of a higher order, and this process has played a leading part in organic evolution. Amongst the Protozoa and Protophyta, such as Amœba and Hæmatococcus, the individual is typically a single cell, which may be regarded as an individual of

the first order. By remaining together instead of separating after each cell division the daughter cells may form colonies, and from such colonies, by differentiation and division of labour amongst the constituent cell units, individuals of the second order, such as Hydra, have arisen. Most of the animals above the Cœlenterata in the scale of evolution are metamerically segmented, that is to say, they consist primarily of a number of segments or metameres arranged in linear series, and there is good reason to believe that they have originated from linear colonies of individuals of the second order, and are therefore themselves to be regarded as individuals of the third order. The process of integration and re-differentiation amongst the constituent units has, however, in most cases been so complete as largely to obliterate the traces of their origin. The human head, for example, can be shown to consist fundamentally of about a dozen segments, each of which was in all probability originally an individual belonging to a linear colony.

From the morphological or structural point of view, then, it appears that there is no fixed criterion of individuality, for not only do we find different orders of individuality but we find also innumerable intermediate stages between these orders.

If we approach our problem from the physiological standpoint we find ourselves not much better off. We might define the individual as a single organism which is able by itself to perform all the functions necessary for the maintenance of its existence. An Amœba, though only a single cell, would be clearly an individual, because it lives a completely independent life ; so would an earthworm, though its body is made up of a large number of segments, of which each in turn is composed of innumerable cells, for neither the cells nor the segments can live independently, their individuality having been completely merged in that of the worm as a whole.

But how can we apply the physiological test to animals which form complex social organizations like those of the honey bee ? Here the individuals, for it is hardly possible to deny that they are individuals, are mutually dependent to a very large extent. The workers alone collect the food and do the work of the hive upon which the existence of the whole community depends, and without their aid the queen and drones could not exist. We are approaching the same condition in highly civilized human societies, but each member of such a society would be eager to assert his own individuality. Cases of dual and multiple personality, however, show us that even from the psychological standpoint the definition of

human individuality is not quite as easy as it seems. It is certain, however, that, whatever else an individual may be, it is something which works as a whole for its own self-preservation and self-expression, and is more or less antagonistic towards other individuals with which it comes into relation in the struggle for existence.

Individuality, then, though a very real phenomenon, is a very elusive one, and well illustrates the futility of attempting to draw up clear-cut definitions when dealing with living organisms. The great fact which it is important to recognize, from the biological point of view at any rate, is that evolution consists to a very large extent, if not mainly, in the progressive merging of individualities of a lower in others of a higher order, and there is a good deal to be said for the view that the highest order of individuality yet attained is represented by complex social organizations like those of certain insects, and, less perfectly, by civilized human societies.

CHAPTER XVI

The continuity of life—The conception of species—The principles of taxonomy—The taxonomic evidence of organic evolution.

In accordance with the theory of evolution we may picture to ourselves the entire animal and vegetable population of the earth, both past and present, as forming one vast, tree-like organism, all parts of which, if we knew enough about their history, could be traced into actual, although of course not simultaneous, protoplasmic connection with all other parts. This tree commenced its growth far back in geological time, and its branches became ever more and more ramified in succeeding ages, and more and more diversified in character as they diverged from one another. Only the youngest twigs of the tree, however, are still actually alive, being represented by the animal and vegetable population of the earth for the time being. All the older parts have died away, most of them without leaving any traces of their former existence, and thus has arisen the actual discontinuity which is found to occur between the surviving groups of organisms at any given period.

The tendency to structural variation which all organisms exhibit, whatever may be its cause, is responsible for the progressive diversity which is gradually set up between the different branches of the organic tree. The combined action of the forces of heredity and variation bring about "descent with modification." How it is that such modification always leads, in the long run, to a more or less perfect and often very specialized adaptation of both plants and animals to the conditions under which they live will be discussed after we have considered some of the evidence that justifies us in believing that organic evolution has actually taken place.

In any scheme of zoological or botanical classification the lowest unit must, of course, be the individual. The untrained observer, acquainted only with the more familiar plants and animals, sees no difficulty in arranging these in apparently

sharply circumscribed groups. A child collecting flowers by the wayside will tell you without much trouble how many kinds he has found, and these kinds—speaking generally—correspond to the different species recognized by the botanist.

Even amongst the higher and better known plants and animals, however, the so-called species are not always sharply distinguishable from one another, for we not infrequently meet with intermediate forms, or connecting links, between what are usually recognized as distinct species. Linnæus himself, who pronounced most explicitly in favour of the doctrine of special creation,[1] was forced by his profound knowledge of the animal and vegetable kingdoms to recognize this fact in the case of certain groups of plants[2]; and when we come to study some of the lower members of the animal kingdom, as, for example, the sponges, the difficulty of distinguishing species sharply from one another frequently becomes so great that the definition of any particular one is little more than a matter of individual opinion. The more we study the animal and vegetable kingdoms, in short, the more clearly is the fact impressed upon us that if we could have before us all past and present individuals we should find it impossible, except in an arbitrary manner, to arrange them in species at all, for each kind would be found to be connected with others by a series of small gradations.

According to Darwin, the differences which separate existing species from one another have, at any rate in most cases, arisen by the gradual accumulation of small successive variations. If this be the case the fact that we are able logically to distinguish such species from one another at all can only be due to that disappearance of the older portions of the organic tree whereby discontinuity has arisen between the surviving branches. In any case it is quite certain that such destruction of former connecting links has played a very large part in the separation of those groups of individuals to which the term species is usually applied. This process is clearly illustrated in the accompanying diagram (Fig. 87), in which each enclosing line is supposed

[1] "*Species* tot sunt, quot diversas formas ab initio produxit Infinitum Ens; quæ deinde formæ secundum generationis inditas leges produxere plures, at sibi semper similes, ut Species nunc nobis non sint plures, quam quæ fuere ab initio."
Linnæus. Gen. Plant. (1737).

[2] "Species Rosarum difficillime limitibus circumscribuntur et forte natura vix eos posuit." Linnæus. Spec. Plant., Ed. 2, p. 705 (1762). I am indebted to my friend and colleague at the Linnean Society, Dr. B. Daydon Jackson, for showing me these quotations.

to represent the limits of an existing species. Within each one the individuals differ but slightly from one another, not more, perhaps, than might be expected amongst the offspring of the same parents. The three species represented have, however, become more or less widely separated from one another by the dying away of the branches from which they arose, and which are represented in the diagram by dotted lines.

Darwin has told us that he looked "at the term species as one arbitrarily given, for the sake of convenience, to a set of individuals closely resembling each other, and that it does not essentially differ from the term variety, which is given to less distinct and more fluctuating forms. The term variety, again, in comparison with mere individual differences, is also applied arbitrarily, for convenience' sake." [1]




FIG. 87.—Diagram to illustrate the Separation of Species by the Dying out of connecting Links.

This, of course, is no definition of the term species and was not intended as such. A definition in accordance with the above views might, however, be given as follows:—"A species is a group of individuals, closely resembling one another owing to their descent from common ancestors, which has become more or less sharply separated from all other co-existing species by the disappearance of intermediate forms." Such a definition would be in accord with the practice of many systematic naturalists, who are in the habit of uniting species previously considered as distinct whenever intermediate forms are found, the former species being reduced to the rank of varieties of one and the same species.

It is obvious that the element of time must be taken into consideration in forming such a conception of species. At any

[1] "Origin of Species," Ed. 6, p. 42. The reader should compare the very similar views of Lamarck on the species question, given in Chapter XXIV

given time the species living on the earth would form naturally limited groups, which we should be able to define more or less sharply if we had sufficient knowledge of the then existing fauna and flora to enable us to trace their boundaries. If, however, we were to include extinct forms in our survey, it is obvious that the number of existing species which we should recognize would be inversely proportional to the extent of our palæontological information, for the gaps between the survivors would gradually be filled up by the discovery of intermediate fossil forms.

Naturalists have long recognized the fact that there is another way in which more or less sharply defined groups of individuals may arise, and that is by the occasional and sudden appearance of "sports," or "mutations" as they are now generally called,[1] which "breed true," handing on their special peculiarities from generation to generation. Darwin was of opinion that such sports differ only in degree from the ordinary variations to the accumulation of which he attributed the chief importance in the evolution of species. At the present day, as we have already had occasion to point out, some observers, and especially Professor Hugo de Vries,[2] consider them to be totally different in kind from fluctuating or small successive variations, and regard them as affording the sole means by which new species originate.

According to the mutation theory any species may, from time to time, throw off such sports, either singly or in groups, and they are from the first distinguishable by well defined, though it may be minute, characters from the parent form. These mutations are regarded by de Vries as constituting "elementary species," which are already fully characterized and will not change again unless by giving rise to fresh mutations. De Vries maintains that many of the species of flowering plants as defined by Linnæus are really "aggregate species," each made up of a larger or smaller number of such elementary species. The common weed known as *Draba verna*, for example, regarded by Linnæus as constituting a single species, occurs under about 200 more or less distinct forms. All of these so-called elementary species are believed to come true from seed and to have arisen as sudden mutations.

[1] Compare Chapter XI.

[2] *Vide* "The Mutation Theory," by Hugo de Vries. English translation by Farmer and Darbishire (Kegan Paul, Trench, Trübner & Co. Ld., London, 1910).

According to this view a newly arisen species, at its first origin, is already sharply distinguished from the parent species and the extinction of intermediate forms is not required to separate the two.

The elementary species, however, though apparently constant in their characters, are often so similar to one another, and they are moreover so numerous, that for practical purposes of classification it would be undesirable to regard them as distinct species in the ordinary sense of the word. It is far more convenient to maintain the older view that they are merely varieties or subspecies, and their occurrence in no way invalidates our conception of the slow, tree-like evolution of the organic world. If de Vries be right as regards the importance he attributes to them as the sole means by which species have originated, which is extremely doubtful, it merely means that evolution has taken place in a rather more jerky fashion than we previously supposed. It will be necessary to return to this question when we come to discuss the factors of organic evolution.[1]

It is not sufficient for the purposes of classification to arrange the individual plants or animals with which we are acquainted in their respective species. These species in turn must be arranged in groups of higher order, which are termed genera. Each genus stands to the species included within it in much the same relation that the species themselves stand in with regard to individuals, and related genera, though often sharply definable, are only so by virtue of the disappearance of connecting links. The characters by which genera can be distinguished from one another are of a less specialized and more fundamental nature than those which distinguish species. Individual opinion, however, differs greatly as to the exact limits which should be assigned to each, and it is a common thing for an old established genus to be subdivided into several as the result of the discovery of new species and the more exhaustive study of old ones.[2] It is all a matter of convenience, and one may justifiably make a separate genus for any group of closely related species which can be distinguished by some common character from all other co-existing groups of species. Many naturalists, however, consider that the mutual relationships of species are more accurately expressed by making use of subgenera as intermediate groups between genera and species.

[1] *Vide* Chapters XXVI.—XXVIII.

[2] A striking illustration of this is afforded by the recent history of the old genera Peripatus and Amphioxus, each of which is now subdivided into several.

Genera in turn are grouped in families, separated from one another by still more general characters, and with sub-families as intermediate groups where necessary. Families are grouped in suborders and orders, orders in subclasses and classes, classes in phyla (or subkingdoms), and phyla in kingdoms. Of kingdoms only two are recognized, animals and plants, and even these cannot be sharply separated from one another, because amongst the lowest forms of life the distinction between animals and plants, as we have already seen, has not yet arisen.

The arrangement of individual organisms in species, and the grouping of these to form genera, families, orders, classes, phyla and kingdoms, constitutes the work of the systematist and is usually spoken of as classification, while the study of the principles in accordance with which classification should be carried out forms a special branch of biological science sometimes known as taxonomy.

The first and greatest of the modern systematists was Karl von Linné, now usually known as Linnæus, a Swedish naturalist who was born in 1707 and died in 1778. In his great work, the 'Systema Naturæ," which is now recognized as the starting point of modern systematic zoology and botany, he described all the species of plants and animals then known, and endeavoured to arrange them in a "natural system" in accordance with their mutual resemblances and differences. As an aid to the accomplishment of this formidable task he made use of the binomial system of nomenclature, in accordance with which each kind of plant or animal is referred to by the name of the genus as well as by that of the species to which it belongs. The necessity for the constant repetition of longer or shorter descriptions as a means of identification every time there is occasion to refer to a particular species is thus avoided, while at the same time the use of the generic name makes it possible to employ the same specific name in a number of different genera without risk of confusion, a very important point in consideration of the enormous number of species which have to be distinguished from one another.

The binomial system of nomenclature has proved so well adapted to its purpose that it has survived practically unchanged to the present day, although the number of known species has increased enormously in the interval and the Linnæan system of classification has undergone profound modification at the hands

of later investigators. Very many of the more familiar plants and animals are, however, still known by the names which Linnæus gave to them.

It still frequently happens that newly discovered species have to be named and new genera defined, and various attempts have been made to formulate a code of rules for the guidance of those engaged in this work. This is necessary in order to secure, so far as possible, uniformity of method, and to avoid confusion such as would arise from giving the same name to different genera or different species within a genus, or different names to the same genus or species. The chief points so far agreed upon are that generic and specific names (as well as those of larger groups) should be given in either Latin or Greek and that strict attention should be paid to the law of priority, the name first given taking precedence over any which may be proposed subsequently, as is often the case owing to ignorance of the work of previous writers.

The greatest latitude has, however, been allowed in the past with regard to the coining of generic and specific names. Even the resources of the Latin and Greek languages have proved hardly sufficient to meet all requirements, and many generic names have been given which, though euphonious enough, have no meaning whatever. It is said that one eminent naturalist (Dr. Gray) used to make up such names by drawing letters out of a hat, and it is certain that Dr. Leach derived the generic names of a whole series of parasitic crustacea (Cirolana, Conilera, Nerocila, &c.) from anagrams on his wife's name, Caroline. The most satisfactory names, on the other hand, are those which convey some definite information as to the characters of the genus or species concerned or as to the place where it is found.

If we have to classify a number of inorganic bodies we may set about our work in a variety of ways. We may arrange them according to colour, or size, or weight, or shape, or texture, or chemical composition, or according to the places they come from, the precise method adopted depending upon what it is that we wish to express by means of our classification.

It is exactly the same with plants and animals, the way in which we classify them will depend upon our point of view. A fisherman classifies fishes largely according to their food-value, and various other animals according to whether or not they are good for bait, and such classification serves its purpose quite satisfactorily

The aim which the zoologist or botanist sets before himself in classification is the expression of the "natural affinities" of the plants or animals investigated. The existence of such natural affinities was clearly recognized long before the explanation of them was known, and even by upholders of the doctrine of special creation. Thus it was well known to Linnæus that individuals fall naturally into species, that species may be grouped in genera, genera in families, and so on in ever widening circles. It also soon came to be recognized that natural affinities could be best determined by taking into account as many characters as possible instead of relying merely on one or two. A system of classification based on a small number of characters only is always more or less artificial, and though it may serve its purpose for a time it will have to be amended by future workers who are able to bring a more complete knowledge to bear upon the problem. Thus it comes about that our views on the classification of the animal and vegetable kingdoms are always undergoing change, old systems are constantly being discarded as too artificial and more natural ones proposed in their stead.




FIG. 88.—Diagram to show the Tree-like Form assumed by a natural Classification.

As our knowledge progresses it becomes more and more evident that a natural classification assumes a tree-like form. The division of the whole organic world (with the exception of the

lower Protista) into plants and animals is represented by the first branching of the tree, the division of each of these great kingdoms into phyla by the next branching, and the subdivision of phyla into classes, orders, families, genera, species and individuals by the further ramifications, as shown in the accompanying diagram (Fig. 88), which represents a mere fragment of the whole tree selected to show the systematic position of a single species of animal, the common brown bear, *Ursus arctos*.

This great truth affords one of the most striking pieces of evidence in favour of the theory of organic evolution, for the tree-like form assumed by a natural classification bears an unmistakable resemblance to the tree-like development of the whole organic world which evolutionists believe to have taken place. The two results represent, indeed, but slightly different aspects of the same truth; the resemblance between them is no mere coincidence, but the fact that we are able to classify organisms in a tree-like manner indicates very clearly that these organisms have been produced by tree-like evolution.

The systematist is now able to replace the vague groping after "natural affinities" by a much clearer conception of the aims of taxonomy. What he has to strive after is the elucidation of the actual pedigrees of existing organisms, the unravelling of what is termed their phylogeny or ancestral history. This means neither more nor less than the ultimate reconstruction of the whole vast tree of life. Piece by piece this is gradually being done, and it is the great German biologist, Ernst Haeckel, who has led the way in this particular department of biological investigation. Some of the main branches of the tree have already been reconstructed in a satisfactory manner, but it is a work of immense difficulty and practically unlimited extent, and at every step opinions differ as to the value of conflicting evidence and the interpretation of obscure facts. The greater part of the tree is dead and gone beyond recall, and such fragmentary information concerning extinct forms as may be supplied by the discovery of fossils can only be supplemented by indirect evidence derived from the study of existing organisms.

We must now inquire a little more fully into the relation between the tree-like form assumed by a natural system of classification, or the taxonomic tree, as we may term it, and the phylogenetic tree, which represents the actual pedigrees of organisms. In the former (Fig. 88) the main trunk of the tree,

as we have seen, represents the entire organic world; in the latter it represents the remote Protistan ancestors from which both plants and animals have sprung. The first great branching represents in the one case the systematist's main division of organisms into vegetable and animal kingdoms, and in the other the gradual differentiation of the ancestral Protista (which at one time constituted the entire organic world) into the primitive unicellular plants or Protophyta on the one hand and the primitive unicellular animals or Protozoa on the other; and so on with subsequent ramifications.




FIG. 89.—Diagram illustrating the Relation between Classification and Phylogeny.

The parallelism between the two is sufficiently striking to justify us in believing that it would be complete if only our knowledge of classification and phylogeny were so; we should then doubtless see at once that the taxonomic tree and the phylogenetic tree are, after all, one and the same thing, for we should arrange all organisms strictly in accordance with the course of their evolution.

One point remains to be noticed in connection with the phylogenetic tree. The branching has been lateral rather than dichotomous, each successive branch, in addition to giving off secondary branches, being itself continued on indefinitely. The descendants of any given ancestral group did not all undergo modification to the same extent, but some adhered more or less closely to the ancestral condition and have continued to do so to the present day. Even the primitive

ancestral Protista are still represented by descendants which probably differ but little from their remote progenitors and which have not yet reached the level of either plants or animals, and there are still living unicellular forms in abundance which, though they may perhaps be distinguished as plants or animals, have never been able to learn the secret of forming multicellular bodies. So it is with most of the great ancestral groups; they are represented still by descendants which have undergone comparatively little change in structure since remote geological periods. The algæ are still algæ, the cœlenterates are still cœlenterates and the fishes are still fishes, though each of these great groups has in past time given rise to descendants which have gradually become modified into higher types.

Many subordinate groups, such as the trilobites and ammonites and the winged reptiles of the secondary period, have of course become extinct during past geological ages, but the fact remains that even at the present day there still exist on the earth organic types which represent, in a more or less recognizable form, all the principal stages of organic evolution, and thus it is that, even if we had only living plants and animals to consider, our classification of the organic world would still assume a tree-like character, with the simplest organisms at the bottom and the most complex at the top of the tree. It would be difficult indeed to explain this fact in accordance with the theory of special creation and immutability of species.

The lateral branching of the organic tree and the relation which the natural classification of existing animals bears to the phylogenetic or ancestral series are diagrammatically represented in Fig. 89. On the right hand side are shown some of the principal stages in the evolution of vertebrates from ancestral Protista, and at the top of the tree are shown the existing groups by which these stages are actually represented at the present day. Only a few stages are represented and the great majority of the lateral branches of the tree are supposed to have been lopped off.

CHAPTER XVII

)nnecting links — Homology and analogy — Convergent evolution — Change of function — Vestigial structures — Reversion.

In presenting the evidence of organic evolution it is convenient) separate that derived from the study of comparative anatomy om that afforded by taxonomy, but the separation is not logical one, for classification is necessarily based upon com-arative anatomy, and much of the evidence might be equally well ealt with under either heading.

The mere fact that we are able to arrange existing organisms ı progressive series, of which the extremes are connected by ıtermediate forms, in itself suggests that one form has been erived from another. This gradation is equally obvious whether e study entire organisms or confine our attention to their com-onent parts or organs. It is illustrated very clearly by the ccompanying diagram of the modifications exhibited by the liceous spicules of certain sponges (Fig. 90). These micro-opic constituents of the sponge, each of which originates as a ecretion, exhibit an astonishing diversity and beauty of form. The xtreme types are as different from one another as we can well nagine, but in the particular group of sponges from which our lustration is taken (the Tetraxonida) all may be derived from the me four-rayed architype (number 1 in the centre of the gure) and numerous intermediate forms mark out the lines ong which evolution has taken place. An analogous diagram, ith a triaxonid architype, could easily be constructed for those markable deep-sea sponges known as the Triaxonida or exactinellida, and another for the calcareous sponges.

Amongst the higher animals also innumerable illustrations of ıe same general principle of gradation in structure, even in co-xisting types, are met with, and are to be explained in the ay indicated in the last chapter, as expressions of phylogenetic lationship. Take, for example, those now widely contrasted oups of vertebrate animals the Reptilia and the Mammalia. The

reptiles as a group are distinguished from the mammals in many ways. Amongst other things they usually have a scaly epidermic covering, but they never have hair; they lay large,





FIG. 90.—Series of tetraxon Sponge Spicules, showing how all may be derived from the same fundamental type, highly magnified. (From Dendy. Article "Sponges" in Encyclopædia Britannica, Ed. XI.)

heavily-yolked eggs and do not suckle their young; they have a cloaca into which the urinary and genital ducts, as well as the alimentary canal, discharge; they have a very complex shoulder girdle (Fig. 91), consisting of a considerable number of more or less separate bones or cartilages,

:luding suprascapula, scapula, coracoid, epicoracoid, clavicle d interclavicle.

The mammals, on the other hand, are characterized by the ssession of an epidermic covering of hairs; they generally ve very minute eggs almost destitute of yolk, and they always ckle their young; they usually have no cloaca but separate enings for the alimentary canal and urino-genital ducts, and e shoulder girdle (Fig. 92) is very greatly reduced, being often presented by only a single bone, the scapula, with a possible remnant or vestige of the coracoid completely fused with it, though a slender clavicle is sometimes present as well.



g. 91.—Shoulder Girdle and Sternum of a Lizard (*Varanus*) seen from below.

Clavicle; *Cor.* Coracoid; *Ep. C.* Epicoracoid; *Gl.* Glenoid cavity; *Int.* Interclavicle; *R.* Ribs; *Sc.* Scapula; *St.* Sternum.

There exists in Australia and some of the adjacent islands, however, a small but very interesting group of animals known as the Monotremata, represented by the duck-billed Platypus (Ornithorhynchus, Fig. 93) and the spiny anteater (Echidna, Fig. 94). The fact that these animals possess hair and suckle their young justifies us in ssifying them amongst the Mammalia, but at the same time ey exhibit certain characters in respect of which they differ m all typical mammals and agree with the reptiles. Thus they large, heavily-yolked eggs, the alimentary canal and urinonital ducts discharge into a common cloaca, and the shoulder dle (Fig. 95) is made up of a considerable number of separate nes almost exactly as in reptiles, most remarkable amongst ich is the interclavicle, which is found in no other mammals. Here then we have animals still existing which undoubtedly cupy an intermediate position between the reptiles and the pical mammals, and the three groups exhibit a progressive series structural peculiarities. Such definite connecting links as the

Monotremata, however, are more usually met with amongst the extinct animals of past geological periods. They indicate the paths along which the more highly organized groups have progressed during their evolution from more lowly organized ancestral groups, which latter may or may not still be represented by surviving forms at the present day.

It would be difficult to explain the occurrence of such graduated series of organs and organisms by the theory of special creation, and it would be no less difficult to explain in this way those remarkable facts of comparative anatomy which are grouped




FIG. 92.—Shoulder Girdle and part of Sternum of a Rabbit, seen from below.

Cl. Clavicle; *Cor.* Coracoid process of Scapula; *Gl.* Glenoid cavity, *R.* Ribs; *Sc.* Scapula; *St.* Sternum.

together under the terms homology and analogy (or homoplasy), to which we shall next refer.

We have already had occasion to point out that all living organisms are more or less perfectly adapted to the conditions under which they exist, and are accordingly provided with organs suitable for their various requirements. Thus all typical vertebrates have organs of locomotion formed from two pairs of limbs, but these differ very greatly in form and structure in accordance with their adaptation to very diverse conditions of life. In terrestrial vertebrates—amphibians, reptiles and mammals—both pairs of limbs usually take the form of ambulatory legs, adapted for moving the body on dry land. In birds the hind limbs are generally used for the same purpose and similarly constructed, but

› fore limbs are modified to form wings for flying in the air; ł the same is true of the fore limbs of bats and of the extinct



G. 93.—The Duck-billed Platypus (*Ornithorhynchus anatinus*). (From British Museum Guide.)

ing reptiles known as Pterosauria (pterodactyls). The Cetacea hales and porpoises), the Sirenia (dugongs and manatees) and e seals, amongst mammals; and the turtles and extinct




G. 94.—The Echidna or Spiny Anteater (*Echidna aculeata*). (From British Museum Guide.)

hthyosauria and Plesiosauria amongst reptiles, on the other and, have limbs which take the form of paddles and are pecially adapted for swimming in water.

We find, then, three chief types of locomotor organs amongst

.s support to the five metacarpal bones in the palm of the or the five corresponding metatarsal bones in the foot. Each :arpal or metatarsal bone in turn forms the support of a of phalanges which constitute the skeleton of the fingers or The thumb and great toe have each two phalanges and of the other digits has three.

ıen the human arm is stretched out at right angles to the axis of the body, with the thumb towards the head, it is in rimitive position of the pentadactyl limb. The thumb and ıdius then lie on what is called the preaxial or anterior border,



6.—Skeleton of the fore Limb (A) and hind Limb (B) of Man, showing the pentadactyl Structure. (From photographs.)

ıls; fe. femur; fi. fibula: hum. humerus; m.c. metacarpals; mt. metatarsals; phalanges; r. radius; t. tarsals; ti. tibia; ul. ulna; I—V, digits.

ttle finger and the ulna on the postaxial or posterior border ə limb. For convenience of comparison with other types igits are numbered from in front backwards, the thumb No. I and the little finger No. V. Similarly in the hind which in man has become permanently twisted out of its tive position, it is easy to show that the great toe is really :eaxial digit (No. I) and the little toe the postaxial (No. V) g. 96 both limbs are represented in the primitive position. rting from the primitive pentadactyl type let us next inquire closely how different groups of air-breathing vertebrates have l the problems of locomotion on land, in air and in water. considering the modifications of the limbs adapted for

locomotion on dry land we may conveniently confine our attention to the hoofed mammals or Ungulata. In the elephant the limbs remain, as in man, in a primitive condition, with five well developed digits in each. The entire limb is stout and massive and the foot[1] remains very short and affords a broad support for




FIG. 97. Skeletons of Man and Horse, photographed from a group in the Natural History Museum. (From Lankester's "Extinct Animals.")


E, Elbow bone (olecranon process of ulna); H, Heel bone in ankle (the hock of the horse); K, Knee joint (the stifle of the horse); P, Hip bone; Sh, Shoulder bone (scapula); T, Vertebræ of tail (coccyx in man); W, Wrist or carpus (the so-called knee in the horse's fore leg).

the heavy body. This type of limb is somewhat clumsy and not adapted for very rapid locomotion.

In the more typical ungulates we always find a reduction in the number of digits, accompanying an uplifting of the hinder part of the foot from the ground, until finally the animal comes to

[1] The term foot in the case of quadrupeds is commonly used to include both manus and pes.

ι and rest on the extreme tips of one or two toes only. The mption of this "unguligrade" condition is accompanied by gation of the limb and especially of the remaining ıpodial bones (metacarpals and metatarsals), so that the wrist ankle in the horse, for example, are uplifted high above the ınd and form the so-called knee and hock respectively (Fig. 97).



of a Tapir, × $\frac{1}{6}$. (From photographs.)

ıals; m.c. metacarpals; m.t. metatarsals; ph. phalanges; t, tarsals; II—V, digits.

also accompanied by a reduction of the ulna in the fore limb of the fibula in the hind limb to mere vestiges. Thus the 'e limb becomes long and slender and adapted for rapid notion by running on hard open ground.

ıe disappearance of digits from the manus and pes in the ımalia follows a very simple law. The first to disappear is ys the preaxial digit (No. I), which is the shortest of the s (having only two phalanges while the remainder have

three each) and consequently the first to leave the ground as the hinder part of the foot is uplifted. The next to go is the postaxial digit (No. V) from the opposite side, the next No. II and the next No. IV.

In some ungulates the long axis of the foot passes through the middle digit (No. III) and in others between the third and fourth digits. The true ungulates are accordingly divided into two series, odd-toed or perissodactyl and even-toed or artiodactyl.

To the former belong the tapir (Fig. 98), with four digits in the fore foot and three in the hind; the rhinoceros, with four or three digits in the fore foot and three in the hind, and the horse (Fig. 99), with only the middle (third) digit remaining in both manus and pes, but with vestiges of Nos. II and IV in the functionless "splint-bones" which lie alongside the greatly elongated metapodial (= metatarsal or metacarpal) of No. III.




FIG. 99.—Fore and hind Feet of a Horse, showing reduction to a single functional Digit (No. III) with Vestiges of two others (II and IV) in the form of splint bones, × $\frac{1}{8}$. (From Lull, after Marsh.)

In the artiodactyl series (Fig. 100) we find the hippopotamus, with four well-developed toes on each foot; the pig, with four toes on each foot but the two outer ones greatly reduced; the deer, with the two outer digits still further reduced; the sheep and oxen, with the second and fifth digits reduced to small nodules of bone, and the camels and llamas, in which all traces of digits other than the third and fourth have completely disappeared. The gradual reduction of the number of digits in the artiodactyl series is accompanied by fusion of the two remaining metapodials to form a single "cannon bone" (well shown in Fig. 100, deer and camel), whereby the now greatly elongated and uplifted foot acquires much greater strength and rigidity.

It is very easy to see that all the different varieties of perissodactyl and artiodactyl limbs are modifications of one and the same primitive pentadactyl type. We must next

.er the way in which this type has been adapted to form
s of flight in different vertebrate groups.
» wing of the extinct pterodactyls (Fig. 101) was formed




FIG. 100.—Limbs of artiodactyl or even-toed Ungulates. (From Romanes' "Darwin and after Darwin.")

n expansion of the skin of the body stretched between the
and hind limbs, and the phalanges of the little finger were
mously elongated so as to aid in the support of its anterior

margin. The surface of the flying membrane was probably covered with scales. In the bats (Fig. 101) four of the digits[1]




Fig. 101.—Wings of Pterodactyl, Bat and Bird. (From Romanes' "Darwin and after Darwin.")

of the hand, Nos. II—V, are elongated and take part in the support of the flying membrane, the surface of which is either naked or covered with fine hair. In the birds (Fig. 101) the

[1] Including the metacarpals.

flying membrane is formed chiefly of feathers, and the distal part of the wing is supported mainly by the second digit; the first and third digits are greatly reduced, and the other digits are absent. In all these different types of wing the skeleton is again clearly of the pentadactyl type, modified by enlargement, diminution or total suppression of certain of its constituent bones.

In the paddles of the modified aquatic mammals, such as the sirenians, seals (Fig. 102) and whales (Fig. 103), the whole limb




FIG. 102.—Skeleton of right fore Foot (A) and right hind Foot (B) of a Seal (*Otaria hookeri*), × ⅛. (From photographs.)

c. carpals; m.c. metacarpals; m.t. metatarsals; ph. phalanges; t. tarsals; I—V, digits.

is very much shortened and flattened and the digits are enclosed in a common integument so as to offer a greater resistance to the water, but the skeleton still reveals the essential pentadactyl features, and the same is true of those aquatic reptiles, the turtles, plesiosaurians (Fig. 143) and ichthyosaurians (Fig. 144). In the whales, however, a curious increase in the number of phalanges (hyperphalangy) may often be observed, and in the ichthyosaurians supplementary small bones are developed in such positions that the entire skeleton of the paddle assumes the form of a mosaic pavement.




FIG. 103.—Outline and Skeleton of the Greenland Right Whale, *Balæna mysticetus*. (From British Museum Guide.)
b, blowholes or nostrils; *f*, vestige of femur; *p*, vestige of pelvis or hip bone.

We can only explain the occurrence of the same type of skeleton—and that a very complex type—in all these different kinds of organs of locomotion on the assumption that it has been inherited from common ancestors. We cannot believe that one and the same type of skeleton was necessarily the most suitable for all these different cases, including ambulatory legs, wings and paddles, and was therefore specially and independently created for each. We must conclude rather that each organism receives a certain kind of material by inheritance from its ancestors and has to adapt it to its own requirements as best it may; has, in short, to cut its coat according to its cloth, and, whatever the




FIG. 104.—A swimming Crab (*Portunus depurator*), showing jointed ambulatory appendages and also swimming appendages (s.l.). (From a photograph.)

shape of the coat may ultimately develop into, the cloth will retain, more or less evidently, traces of the original pattern.

This conclusion is greatly strengthened when we turn to other groups of animals and see how they have solved the same problems with the aid of different materials. The vertebrates are not the only animals which have organs of locomotion in the form of jointed appendages. Many members of the great group Arthropoda—crustaceans, spiders, and insects—have ambulatory limbs which externally bear considerable resemblance to those of vertebrates. If we examine these limbs, however, we find that they are constructed upon a wholly different plan. In the first place the skeleton is external instead of internal, and is composed

of the hard cuticle secreted by the epidermis, there being no true bone. The muscles therefore lie inside the skeleton instead of outside. The number and arrangement of the limb-segments, again, are totally different, and there is, of course, no pentadactyl structure (compare Fig. 104).

Thus, with different material at their disposal, the arthropods have solved the problem of constructing an ambulatory appendage in a very efficient manner, but quite differently from the vertebrates. Many of them have also solved the problem of locomotion in water by modification of certain of the limbs to form paddles, as in the case of the swimming crab (Fig. 104). Many insects, on the other hand, have acquired the power of flight by means of wings, which, though bearing some external resemblance to those of vertebrates, are totally different in structure and origin not only from the latter but also from the other appendages of the arthropods themselves.

We are now in a position to define the meaning of the terms homology and analogy as used by biologists. Homologous organs are such as have the same essential structure, which they owe to inheritance from common ancestors, though they may be very differently modified in adaptation to different functions. The pentadactyl limbs of air-breathing vertebrates, however much they may differ amongst themselves, are all homologous organs in so far as their essential pentadactyl structure is concerned.

Analogous or homoplastic organs, on the other hand, bear only a superficial resemblance to one another, which they owe not to common ancestry but to adaptation of fundamentally different structures along similar lines for similar functions. The ambulatory appendages of arthropods and vertebrates are analogous but not homologous organs, so also are the wings of birds and insects.

The evolutionary process by which analogous but not homologous structures have come to resemble one another is sometimes spoken of as convergence, and the result may be looked upon as an illustration of the general principle that similar causes tend to produce similar effects. The necessity for the adaptation of different organs and organisms to the same environment and the same mode of life results in a superficial resemblance between the organs and organisms thus adapted.

One of the most familiar examples of convergent evolution

is afforded by the whales, dolphins and porpoises (Figs. 103 and 163) with their extraordinary external resemblance to fishes. The fore limbs, as we have already seen, are modified to form paddles, but they retain the pentadactyl structure and are thus totally different from the fins of fishes, which have never reached the pentadactyl stage. The hind limbs have completely disappeared, but vestiges of the limb bones and their supporting girdle, which in some cases are found buried deeply beneath the skin in the pelvic region (Fig. 103, *f*, *p*), still bear witness to their former presence. The powerful tail fin has obviously no real relationship to the tail fin of a fish, for it lies horizontally instead of vertically. There are, of course, no gills, as in fishes, but the animal comes to the surface to breathe air by means of lungs.




FIG. 105.—The seven cervical Vertebræ of a Whale, fused together in one Mass. (From Reynolds' "Vertebrate Skeleton.")

Not only is the whale not a fish, but it belongs to the group of vertebrates most remote from fishes. It is a warm-blooded mammal, suckling its young and exhibiting other characteristically mammalian features. It has seven cervical vertebræ, a number which is curiously constant throughout the mammalian series, but owing to the extreme shortness of the neck these vertebræ are all crushed together to form practically a single bone (Fig. 105). In the giraffe we also find seven cervical vertebræ, but they are all greatly elongated in accordance with the enormous length of the neck (Fig. 106). On the hypothesis of special creation we should certainly have expected the whale to have fewer vertebræ in its neck than the giraffe, and we can only suppose that the number seven has been inherited from some common mammalian ancestor. The resemblance of the whale to the fish, in short, is simply due to the fact that both have acquired the external form best adapted for an active aquatic life.

The wings of pterodactyls, bats and birds are equally good

examples of convergent evolution within much narrower limits. They can only be regarded as homologous to the extent of all being




FIG. 106.—Skeleton of the Giraffe, showing the seven separate and greatly elongated cervical Vertebræ. (From Brehm's "Thierleben.")

pentadactyl. They do not owe their special characters as wings to descent from a common ancestral winged form, but have been

evolved independently from more primitive pentadactyl types of limb.

We find analogous cases in other vertebrate groups. Several of the lizards, such as the so-called slow worm or blind worm (Fig. 107) and the "glass snakes" (Ophisaurus), have, by loss of their limbs, come so closely to resemble snakes as to be




FIG. 107.—The Slow Worm, *Anguis fragilis*.

indistinguishable by most people. The Coeciliidæ (Fig. 108) amongst amphibians, the Amphisbænidæ amongst lizards and the Typhlopidæ amongst snakes have all adapted themselves to a burrowing underground life, like the earthworms. Their limbs have completely disappeared, the body has become cylindrical and worm-like and they have lost the use of their eyes, but though they




FIG. 108.—A worm-like, limbless Amphibian, *Uræotyphlus africanus*. (From British Museum Guide.)

have all come to resemble one another closely as the result of convergent evolution they are not in reality at all nearly related. The loss of limbs, the assumption of the worm-like form, &c., have taken place quite independently in each group.

The mammalian fauna of Australia consists mainly of members of the single order Marsupialia or pouched mammals, but different representatives of this order have come, by convergence, to resemble closely members of widely different orders of

mammals found in other parts of the world. The so-called marsupial wolf of Tasmania (Thylacinus) closely resembles a typical carnivore in its habits and general structure. Its teeth are adapted for a predaceous life, and the entire skull (Fig. 109, B), with its dentition, bears an extraordinary general resemblance to that of a dog (Fig. 109, A), being distinguishable only by details of structure which would hardly be noticed except by an




FIG. 109.—A. Skull of Dog, side view; B. Skull of Thylacine, side view. (From photographs.)

anatomist. These details, however, are quite sufficient to show that there is in reality no close relationship between the two. Thus the dog (Fig. 110, A, A_1) has in each upper jaw three incisor teeth (i.^{1}—i.^{3}), one canine (c.), four premolars (p.m.^{1}—p.m.^{4}) and two molars (m.^{1}—m.^{2}); and the dentition of the lower jaw is the same except for the presence of a third molar (m.$_3$), which is, however, in a vestigial condition. The thylacine, on the other hand (Fig. 110, B, B_1), has four incisors (i.^{1}—i.^{4}) in the upper and



FIG. 110.—A, A_1, Skull and Mandible of Dog; B, B_1, Skull and Mandible of Thylacine, to show the arrangement of the teeth, &c. (From photographs.)

i.¹—i.⁴, incisors of upper jaw; $i._1$—$i._3$, incisors of lower jaw; c., canine; p.m.¹—p.m.⁴, premolars of upper jaw; $p.m._1$—$p.m._4$, premolars of lower jaw; m.¹—m.⁴, molar of upper jaw; $m._1$—$m._4$, molars of lower jaw.

three ($i._1$—$i._3$) in the lower jaw; and one canine (c.), three premolars ($p.m._{1-3}$) and four molars ($m._{1-4}$) in each jaw. The thylacine skull is further distinguished from that of the dog by the presence of large vacuities in the hinder part of the bony palate and by the strongly marked inflection of the angles of the mandibles. These two characters, both of which are shown in the illustrations, as well as the arrangement of the cheek teeth and other minor features which it is unnecessary to specify, are fundamental peculiarities of the great group Marsupialia and at once indicate the true affinities of Thylacinus.

The case of the Australian marsupial mole, Notoryctes, is equally striking. The powerfully built digging limbs, the soft, close fur, the absence of external ears and the loss of sight, as well as the general shape of the body, all in adaptation to its burrowing habits, cause it to assume a wonderfully mole-like aspect, while in reality it comes nowhere near the true moles as regards genetic relationship.

Perhaps the most remarkable of all known cases of convergent evolution, however, is met with in the Ungulata. We have already seen that amongst the typical ungulate mammals of the present day we can distinguish two series, odd-toed or perissodactyl, and even-toed or artiodactyl. In the odd-toed series the reduction of the digits culminates in the horse, with a single perfect digit in each foot and vestiges of two others in the form of splint-bones. This extreme modification of the unguligrade type is so peculiar that it is difficult to believe that precisely the same line of evolution has been followed independently by two different groups of animals. Yet such appears to be actually the case. There is an extinct group of ungulates known as the Litopterna, whose remains have been described by Ameghino from Tertiary beds of Patagonia. The small size of the brain-cavity, the characters of the dentition, cervical vertebræ, carpus and tarsus, indicate that they were more primitive forms than the true Perissodactyla, and, as Dr. Smith Woodward observes, they reached their maximum of specialization at an earlier period than the latter. We find amongst them forms (Theosodon, Fig. 111, A, B) with three well-developed toes as in the rhinoceros, forms (Proterotherium, Fig. 111, C) with one well-developed toe and two small ones as in some of the extinct ancestors of the horse, and forms (Thoatherium, Fig. 111, D, E) with a single toe as in existing horses; and in all cases the axis




FIG. 111.—Feet of Ungulates belonging to the extinct group Litopterna, from Lower Tertiary deposits of Patagonia. (From Smith Woodward's "Vertebrate Palæontology," after Ameghino.)

A, B, *Theosodon lydekkeri;* right fore and hind feet, × ½
C, *Proterotherium intermixtum;* right fore foot, × ½.
D, E, *Thoatherium crepidatum;* left fore and hind feet, × ½.

of the foot passes down the middle of the third digit. If we compare the foot of Thoatherium (Fig. 111, D, E) with that of a horse (Fig. 99) it is hard indeed to imagine that the animals possessing such closely similar and highly specialized limbs are not nearly related to one another. Expert palæontologists, however, tell us that they are not, and we must believe that the resemblance is due entirely to adaptation to a similar mode of life in the two cases. We shall have something to say as to how this adaptation was brought about in the case of the horse when we come to discuss the ancestral history of that animal in Chapter XX.

It will readily be understood from the examples which we have been considering that the phenomena of convergence provide many pitfalls for the unwary biologist, and have led to many other mistakes in classification besides the popular error of placing the whales amongst the fishes. We have already noticed how the limbs of arthropods have come to bear a superficial resemblance to those of vertebrates, though so absolutely different in their essential structure that no anatomist would dream of regarding them as homologous organs. Many aquatic arthropods, belonging to the class Crustacea, like the lobsters, cray-fishes and crabs, breathe by means of gills which bear a superficial resemblance to those of fishes, but are again by no means homologous structures. Certain other resemblances between arthropods and vertebrates, also due probably to convergence, have, however, led more than one observer to conclude that vertebrates are descended from arthropod ancestors, a conclusion which is by no means justified by the facts.

We have seen, in dealing with the modifications of the pentadactyl limb, how an organ which was originally used for one purpose may come to be used for another and re-adapted accordingly. This change of function, in accordance with new requirements, has been one of the chief factors in organic evolution. In most fishes there is a hollow outgrowth from the front part of the alimentary canal, which becomes filled with gas and forms the air-bladder. This was probably originally an accessory organ of respiration, as it still is in those remarkable survivals, the Australian Mud-fish (*Neoceratodus*, Fig. 112), the South American Lepidosiren and the African Protopterus. These, together with a number of extinct forms, constitute the group Dipnoi, so-called because they breathe both by means of the air-bladder and by means of gills. The air-bladder was

the forerunner of the lungs, which form the sole organs of respiration in the higher vertebrates, having completely replaced the gills, and it was the development, first of the air-bladder and then of the true lungs which rendered possible that great step in the evolutionary history of the vertebrates, the migration from water to land.

In the great majority of existing fishes, however, the air-bladder, when present, has taken on quite a different function as a hydrostatic organ, which assists the fish in maintaining its position at varying levels in the water. In some fishes it has become further modified as a sound-producing organ, and in others it has acquired a remarkable connection with the organs of hearing, the significance of which is doubtful.

The hand of man is a most beautiful example of change of function—from locomotion to prehension—but it has under-





FIG. 112.—The Australian Mud-Fish, *Neoceratodus forsteri*, greatly reduced. (From British Museum Guide.)

gone surprisingly little structural modification in the process. The proboscis of the elephant is also a very efficient organ of prehension, but it is formed by enormous elongation of the nose, which is primarily an organ for conveying air to and from the olfactory organs and lungs. Still more remarkable is the conversion of muscle fibres in the torpedo and the electric eel (Gymnotus) into powerful electric batteries, capable of giving severe shocks and therefore valuable as weapons of offence and defence. In these cases the change of function is accompanied by very profound modifications in structure.

Wherever we turn we find that novel requirements are met, not by the sudden creation of new organs, but by the gradual modification of old ones. As we have already said, the organism has to do its best with the material which it has inherited from its ancestors; and yet the power of living protoplasm to meet every new requirement by a suitable modification of bodily structure

appears to be almost unlimited. We must remember, however, that such modifications, in a state of nature at any rate, only take place very slowly and gradually.

Traces or vestiges of organs which have ceased to be of any use to their possessors persist with astonishing pertinacity in many organisms. Evidently their complete removal must be an extremely slow process. We have already noticed the persistence of vestiges of the pelvic girdle and leg bones in the whale (Fig. 103), of the reduced metapodials or splint bones in



specimen.)

the feet of the horse (Fig. 99), and of the vestigial third molar in the lower jaw of the dog. Unless we are to believe that such structures have been put where they are on purpose to mislead us we cannot possibly explain their occurrence on the theory of special creation. They are, at any rate in many cases, perfectly useless to their possessors, and the only rational way of accounting for their presence is by supposing them to be inherited from remote ancestors in which they were functional.

We may now briefly notice a few other instances of such

vestigial structures. A characteristic feature of oceanic islands is the presence on them of birds which have more or less lost the power of flight. Such were the dodo of Mauritius, the solitaire of Rodriguez, and the gigantic moas of New Zealand. All these forms are now extinct, but we still find in New Zealand several flightless birds surviving. One of the most interesting is the kiwi or Apteryx (Fig. 113), a moderate-sized bird of nocturnal habits, now rapidly becoming exterminated. The whole body is covered with coarse, hair-like plumage and externally shows no trace of wings. There is, however, a minute remnant of a wing present on each side, completely concealed in the plumage and entirely functionless as an organ of flight. Yet it still possesses the pentadactyl skeleton, though in a greatly reduced condition (Fig. 114). It is said that when the kiwi goes to sleep it still endeavours to tuck its long beak under its wing after the manner of other birds. In the extinct moas, to which the kiwis are perhaps related, even the last vestiges of the wings seem to have disappeared, for amongst the enormous quantities of the remains of these gigantic birds which occur in New Zealand no wing bones have ever been found.




FIG. 114.—Skeleton of a Kiwi, showing the vestigial Wing Bones, behind which a piece of Black Paper has been placed, × ¼. (From a photograph.)

There is very strong reason to believe that the remote ancestors of existing vertebrates possessed an additional pair of eyes on the top of the head, behind the still existing lateral eyes. Traces of this second pair—the pineal or parietal eyes—are yet to be found in lampreys and lizards, and especially in that

remarkable New Zealand reptile the tuatara (*Sphenodon punctatus*). This animal (Fig. 115), may be regarded as one of the oldest surviv-




FIG. 115.—The New Zealand Tuatara, × ⅛. (Drawn by Miss V. E. Dendy from a model and photographs.)

ing types of terrestrial vertebrate, the order to which it belongs (the Rhynchocephalia) dating back to the Triassic period of the earth's history.

In the adult tuatara these is still a fairly well developed pineal



FIG. 116.—Section through the Pineal Eye of the Tuatara, × 60. (From photograph.)

le., lens; n., nerve; ret., retina.

eye (Fig. 116), with retina, lens and nerve, but it is only about $\frac{1}{50}$th inch in diameter and lies deeply buried beneath the

skin in the parietal foramen in the middle of the roof of the skull. It may to some extent still be functional, though probably of far less importance than in the extinct amphibia and reptiles of the Palæozoic and Mesozoic periods, in which the presence of a comparatively large parietal foramen indicates that the eye was better developed. In the case of the tuatara it has been demonstrated by anatomical and embryological investigation that the remaining pineal eye is the left-hand member of the original pair. In the lampreys it appears to be the right-hand member.

Turning now to the frog, we sometimes find in this animal a minute light-coloured spot on top of the head (Fig. 117), between the paired eyes. This marks the position of a little sac-shaped vesicle which lies beneath the skin and is known as Stieda's organ, consisting merely of a number of undifferentiated cells surrounding a central cavity and attached to the end of a kind of stalk (Fig. 118). The vesicle represents the functionless vestige of a pineal eye and the stalk probably represents its disappearing nerve.




FIG. 117.—Head of Frog (*Rana temporaria*), showing Stieda's Organ between the lateral Eyes. (From Studnička, after Stieda.)

In the birds and mammals all trace of eye-like structure has disappeared from this region, but a vestige of one or both of the pineal eyes is probably to be recognized in the so-called pineal gland lying on the roof of the brain, which attained such celebrity in the seventeenth century owing to its identification by the philosopher Descartes as the seat of the soul.

In studying the mammalian dentition we again meet with plenty of illustrations of vestigial structures. The whale-bone whales (Balænidæ) have no teeth in the adult at all, but in the fœtus vestiges of teeth can be found imbedded in the gums. The young Australian duck-billed Platypus (Ornithorhynchus) has vestigial teeth which are entirely replaced by horny pads in the adult. The third molar in the lower jaw of the dog (Fig. 110, A_1, $m._3$) is, as we have already seen, evidently in a vestigial

condition and can be of very little if any use to its possessor, and there is reason to fear that in man himself the teeth are disappearing a good deal more rapidly than we could wish, though in this case the disappearance seems to be chiefly due to disease.

A better example of a vestigial structure in man is the coccyx at the hinder end of the vertebral column (Fig. 97), which represents the last remnant of the ancestral tail, and is occasionally accompanied by vestiges of the muscles by which an ordinary tail is moved. The hair on the chest, again, is a vestige of the




FIG. 118.—Section through the vestigial Pineal Eye of the Frog (Tadpole) × 168. (From a photograph.)

epd., epidermis; p.e., pineal eye; r.s., roof of skull; v.n., vestigial stalk and nerve.

hairy coat which once clothed the entire human body, as it still does that of the apes.

Examples of vestigial organs might be multiplied to an indefinite extent, but enough has perhaps been said to show that such structures are of very common occurrence and to indicate their value as evidences of organic evolution. They occur, of course, not only in the adult condition but also, as in the case of the embryonic gill-slits of air-breathing vertebrates, at earlier stages of development, but such cases will be more conveniently dealt with in the next chapter.

Closely akin to the occurrence of vestigial structures is another phenomenon known as atavism or reversion, by which we mean

the sudden and sporadic reappearance of some ancestral structure which had either been completely lost or very greatly reduced. The elder Pliny has placed it on record that Cæsar the Dictator had a horse whose fore feet were like those of a man. This statement evidently refers to a more or less complete return to the ancestral pentadactyl condition. Marsh has given a figure of the fore foot of a horse in which the second digit is fairly well developed, with three perfect phalanges, though not so large as the third, while the first is represented by a splint bone, and a very similar case is exhibited in the Natural History Museum at South Kensington.

In man the occasional excessive development of the canine teeth is regarded as due to reversion to an ancestral condition similar to that of the anthropoid apes, in which the canine teeth are very large and used as weapons The occasional occurrence in man of vestigial tail muscles, and even of a short tail, may also be regarded as due to reversion. Whether or not all such cases are capable of being explained on Mendelian principles, as suggested in Chapter XIII, it is impossible to say, but this does not affect their importance as evidence of the truth of the theory of organic evolution.

Although, in the present chapter, we have so far drawn our illustrations entirely from the animal kingdom, it must not be supposed that the same general principles cannot be equally well demonstrated in the case of plants. Indeed the whole chapter might be re-written entirely from the botanical point of view. Change of function is very well shown, for example, in the "pitchers" of Nepenthes and Sarracenia, formed from modified leaves and serving as traps for catching insects. Convergent evolution is illustrated by the strong superficial resemblance which exists amongst the various Alpine cushion plants belonging to widely different orders, all of which have assumed the form best suited for withstanding the peculiar hardships of their environment. The leaves of the parasitic dodder, reduced to tiny scales (Fig. 186), and the staminodes or functionless stamens of many flowers, again, might well serve as examples of vestigial structures. Considerations of space, however, forbid us to pursue this fertile line of inquiry any further.

CHAPTER XVIII

Ontogeny—The recapitulation hypothesis—Interpretation of the ontogenetic record—Palingenetic and cænogenetic characters.

In dealing with the cell theory, in Chapter IV, we have already laid stress upon the fact that every multicellular animal or plant commences its individual life as a unicellular egg or ovum, and gradually passes by slow stages of cell-division and differentiation into the adult condition. There are, of course, apparent exceptions to this rule in the case of animals and plants which reproduce by budding or by some analogous process, where the bud arises from a group of cells belonging to the parent, but even in these cases reproduction by means of germ cells is resorted to at more or less frequent intervals and the budding must be regarded merely as an additional method of multiplication interpolated in the life-cycle.

The individual organism, then, does not come into existence fully formed in all its perfection, but passes through a longer or shorter process of development to the adult condition. In fact it undergoes a process of individual evolution which constitutes its individual life-history or ontogeny, and the length and complexity of this process are proportional to the complexity of organization of the adult. Thus the complete life-cycle of many of the lower multicellular animals and plants is passed through in the course of a few months, while a man requires twenty years or more to attain his full development.

Although, for the sake of convenience, the ontogeny of any given organism may be divided up into a number of stages, yet these stages cannot in reality be sharply distinguished from one another. Even the division or segmentation of the ovum (Figs. 13 and 121), whereby the organism passes from the unicellular to the multicellular condition, does not take place suddenly but by means of the slow and complicated process of mitosis or karyokinesis (Fig. 31); and in cases where there is an apparently abrupt change, or metamorphosis, from one condition

to another, as, for example, at a later stage, from the chrysalis to the butterfly, the development really progresses quite slowly and gradually internally, although the external appearance may for a long time remain unaltered and give the impression that it is completely at a standstill.

The fact that the young organism cannot commence its life at the stage reached by its parents, but has to make a fresh start from the beginning and go through a whole series of stages




FIG. 119.—A. Chick Embryo of about 5½ days, × 5. B. Rabbit Embryo of about 13 days, × 5. In both cases the fœtal membranes and yolk-sac have been removed. (From photographs.)

before reaching the adult condition, is very significant from the point of view of the evolutionist. Still more significant is the fact that different organisms all commence at the same stage—as unicellular eggs—and come to diverge further and further from one another in structure as their development progresses.

If we examine a number of series of embryos belonging to different vertebrate types, no matter how widely the adult animals may differ from one another, we shall find that as we trace their life-histories backwards they gradually converge until, while still at a relatively advanced stage of development, the different embryos come to resemble one another so closely that

in many cases it is doubtful if even an experienced embryologist could distinguish between them. This great generalization appears to have been first reached by the embryologist von Baer, who in 1827 discovered the mammalian ovum. It may be illustrated by the chick and rabbit embryos represented in Fig. 119.

Von Baer's generalization contained the germ of what is now known as the Recapitulation Hypothesis, or, as Haeckel has termed it, the Biogenetic Law, which states that every organism in its individual life-history recapitulates the various stages through which its ancestors have passed in the course of their evolution. In other words, ontogeny, or the life-history of the individual, is a repetition of phylogeny, or the ancestral history of the race to which the individual belongs.

We have already referred, in Chapter IV (Fig. 13), to some of the earlier stages in the development of that primitive fish-like animal Amphioxus (Fig. 120). Let us next inquire how these stages may be interpreted in accordance with the recapitulation hypothesis. The unicellular ovum (Fig. 13, I) obviously represents the remote protozoon ancestors which were common to the whole animal kingdom, and which are also represented at the present day by independent unicellular organisms such as the Amœba. The segmentation of the ovum into primitive embryonic cells or blastomeres (Fig. 13, II—VI) represents the transition from the condition of the simple protozoon to that of the protozoon colony, in which the individual cells, instead of separating, as in the dividing Amœba, remain together, but still without undergoing any marked differentiation and division of labour. The arrangement of the blastomeres in the form of a hollow sphere, the blastula or blastosphere (Fig. 13, VII), with a single layer of cells surrounding a central cavity, represents the formation of such a protozoon colony as we see in the existing Volvox (Fig. 11) or Sphærozoum (Fig. 12). The process of gastrulation, whereby the single-layered blastula is converted into a two-layered gastrula (Fig. 13, VIII—X), with primitive digestive cavity (enteron) and primitive mouth (blastopore), represents the transition from the protozoon colony to the cœlenterate stage of evolution, the latter being still represented at the present day by such forms as Hydra (Fig. 57), Obelia (Fig. 60), the jelly-fish, the corals and all their numerous relations, which retain in their organization all the essential features of the gastrula,

though generally complicated by the development of tentacles, skeleton, &c. The development of cœlomic pouches (Fig. 13, XI—XIII, *c.p.*) as outgrowths of the primitive digestive cavity, and the conversion of these into mesoblastic somites (Fig. 13, XV, *m.s.*), arranged serially or metamerically down each side of the body, mark the transition from the unsegmented and cœlenterate condition to the metamerically segmented[1] and cœlomate condition. The cavities of the cœlomic pouches form the cœlom or body cavity, which is at first transversely subdivided into compartments, as it still is in the adult earthworm, while their walls form the third germ-layer or mesoblast, lying between the epiblast which covers the surface of the body and



FIG. 120.—The Lancelet (*Amphioxus lanceolatus*), × 2. (From a photograph.)

the hypoblast which lines the digestive cavity. Along the mid-dorsal line of the body a strip of epiblast sinks down (Fig. 13, XI, *n.pl.*) and becomes folded into the form of a tube (Fig. 13, XII—XIV, *n.t.*), the rudiment of the central nervous system (brain and spinal cord), and beneath this tube a long strip of hypoblast becomes nipped off from the roof of the gut, forming the notochord (Fig. 13, XI—XIV, *not.*) or axial skeletal rod—the foundation around which in higher types the vertebral column is built up. A little later the front part of the gut becomes pierced by gill-slits for purposes of respiration and the primitive chordate condition is thus fully attained.

Amphioxus (Fig. 120) does not progress much beyond this stage in its development. It never acquires any limbs but swims about by lateral undulations of the body caused by the contraction

[1] Metameric segmentation has, of course, nothing to do with the segmentation of the ovum, but is the term applied to the transverse division of the body in many animals into a series of joints or segments arranged longitudinally, each of which typically repeats the essential features of all the others.

of the lateral sheets of muscle derived from the mesoblast. No skull and no vertebral column are formed, the notochord remaining throughout life as almost the sole representative of the internal skeleton. The brain does not become distinctly differentiated from the spinal cord and no paired organs of sense are developed, nor does that division of the body into head and trunk, which is so characteristic of typical vertebrates, take place. Amphioxus is a chordate animal but it is not a true vertebrate. It probably, however, represents fairly closely a stage of evolution through which the ancestors of the vertebrates have passed, though it becomes somewhat modified by secondary features in the later stages of its development.

It is easy enough to interpret the earlier development of Amphioxus in terms of the recapitulation hypothesis and to recognize in the ontogeny certain stages of the phylogenetic history. The ontogenetic record, however, is by no means always so readily decipherable. It is generally more or less obscured by secondary features superposed upon it, much as an ancient picture may be concealed by another painted over it. These secondary features are characters which are developed in relation to the requirements of the embryo itself at its various stages, for it is not only the adult organism which becomes modified in structure in the course of evolution but all the stages of its life-history are likewise subject to adaptation.

In the first place nourishment has to be provided for the developing embryo, and this necessity is present from the very first division of the fertilized ovum. The blastomeres into which it divides cannot go about and seek their own food supplies like so many Amœbæ, they have sacrificed the power of leading independent lives for the sake of remaining together and building up a more or less complex multicellular body; but none the less they require feeding. Hence we find that all eggs contain a larger or smaller quantity of nutrient material stored up in the cytoplasm. This usually takes the form of definite granules or particles of food-yolk (deutoplasm), the amount of which varies immensely in different cases. If there is very little the egg is said to be microlecithal as in Amphioxus; if there is much it is said to be megalecithal, as in the frog and still more so in the bird, and the size of the egg, as we have already had occasion to point out in Chapter X. depends almost entirely upon the amount of food-yolk which it contains.

The possession of food-yolk is, of course, of immense importance to the embryo, for the stage which it is able to reach in its development before it has to begin to provide for itself will depend upon the amount of nutrient material which it has at its disposal. The presence of this food-yolk, however, must also act as a mechanical hindrance to the development, just as the supply of provisions which he carries with him must impede the progress of a traveller, though enabling him ultimately to accomplish a longer journey.

In Amphioxus the egg contains hardly any food-yolk and the process of segmentation and the formation of the blastula and gastrula take place in an almost perfectly typical manner There is here practically no hindrance to development and no obliteration of the ontogenetic record. There is, however, just sufficient nutrient material to cause some of the cells—those which will invaginate to form the hypoblast of the gastrula—to be slightly larger than the remainder, which are destined to form the epiblast (Fig. 13, VII, VIII).

Let us compare with this the corresponding stages in the development of the frog (Fig. 121). Here the egg is, as we have already indicated, much larger, owing to the greater quantity of food-yolk which it contains. This is chiefly collected in the lower half of the ovum, while the upper half is deeply pigmented and thus readily distinguished. Segmentation begins as in Amphioxus by the formation of two vertical clefts, or cell-divisions, one after the other and at right angles to one another, whereby the four-celled stage is reached (Fig. 121, I—III). Each cleft begins at the pigmented pole and throughout the whole of the segmentation the yolk-laden half of the egg lags behind the pigmented half because of the mechanical hindrance which the food-yolk opposes to the process of cell-division. The first horizontal cleft (Fig. 121, IV) divides each of the four blastomeres into two daughter cells of very unequal size, an upper pigmented cell with little food-yolk and a much larger, lower, yolk-laden cell with little pigment. After this, segmentation continues to progress more rapidly in the upper than in the lower half of the egg (Fig. 121, V), until we reach the blastula stage (Fig. 121, VI), where we find the large yolk-laden cells forming the lower half of the wall of the hollow sphere and projecting into and partly obliterating its cavity, while the small pigmented cells form the upper half.

The process of gastrulation is profoundly modified by the presence of the food-yolk, and instead of a simple invagination of the lower half of the blastula wall to form the hypoblast, we find the small (epiblast) cells, now arranged in several layers, spreading themselves over the yolk-containing cells until they completely enclose the latter except for a small circular area




FIG. 121.—Early Stages in the Development of the Frog (partly from Ziegler's models and partly adapted from Marshall.)

I, the fertilized ovum; *II—V*, segmentation of the ovum; *VI*, blastula; *VII*, modified blastula, with wall composed of more than one layer of cells; *VIII*, commencement of gastrulation; *IX*, the modified gastrula stage (*VI—IX* in vertical section).

blc., blastocœl or segmentation cavity; *bp.*, blastopore; *ent.*, enteron; *ep.*, epiblast; *hyp.*, hypoblast; *u.l.bp.*, upper lip of blastopore; *yk.c.*, yolk-containing cells.

which corresponds to the blastopore or aperture of invagination in Amphioxus blocked up by yolk cells (Fig. 121, VIII, IX). Indeed, practically the whole of the primitive digestive cavity in the frog's gastrula may be regarded as being filled with yolk cells, from which hypoblast and mesoblast will be derived, and it only gradually opens out later on in development as the yolk is used up. Hence the cœlenterate stage of the ancestral history

(Fig. 121, IX) is very much disguised in the ontogeny, simply owing to the presence of a large quantity of nutrient material in the egg.

In the development of the bird's egg (and also in that of reptiles, which is closely similar) it is still more difficult to recognize the process of gastrulation. The quantity of yolk (Fig. 70) is so enormous that it entirely prevents cell-division from taking place in the greater part of the egg, and segmentation is consequently confined to a small yolk-free area at one pole of the spherical mass, where it gives rise to a layer of cells known as the blastoderm. This blastoderm gradually spreads over the yolk and from it the embryo is formed by a kind of pinching-off process, the yolk remaining enclosed in a bag—the yolk-sac—attached to the lower surface of the embryo, until it is all absorbed by means of a special set of blood-vessels developed in the yolk-sac, and used up in the nourishment of the growing embryo. The embryo itself meanwhile becomes provided with special organs for its protection and respiration, the so-called fœtal membranes. Of these the amnion, formed by outgrowth of the embryonic body-wall, forms a sac filled with fluid, which surrounds the embryo at a distance and leaves it free room for growth, while the allantois, formed by outgrowth of the embryonic gut-wall, forms a highly vascular organ which comes into relation with the extremely porous shell and thus provides for the necessary gaseous interchange.

The yolk-sac, the amnion and the allantois are all organs which have been developed in accordance with the special requirements of the embryo, and which must therefore be left out of account in reconstructing the direct ontogenetic record.

In the dogfish also (Fig. 122) we find an excellent illustration of the formation of a special yolk-sac to contain the enormous supply of food material for the developing embryo, but in this case neither amnion nor allantois is developed.

The typical Mammalia have adopted a very different method of nourishing their young. The developing embryos are retained within the body of the parent and obtain their food supply from the blood of the latter by means of a special organ known as the placenta, which is developed partly from the allantois of the embryo or "fœtus," and by which the latter is attached to the wall of the uterus. This method seems to have proved much more satisfactory than the provisioning of the egg

with food-yolk, and we accordingly find that the mammalian ovum (Fig. 71) has become reduced in size again until it is no larger than that of Amphioxus, *i.e.* about $\frac{1}{250}$th inch in diameter. The early stages of segmentation have also gone back to the primitive type, but, strange to say, a yolk-sac is still formed although there is no yolk for it to contain—affording an admirable example of a vestigial embryonic organ. Here one record has been superposed upon another in the ontogeny and we have a recapitulation of an embryonic stage of the reptilian ancestors of the mammals. After birth, of course, the young



FIG. 122.—Embryo of a Dogfish, with Yolk-Sac (Y.S.) attached. × 2. (From a photograph.)

mammal is nourished by the secretion of milk, and is thereby enabled to reach a very advanced stage of development before it has to begin to find its own food. The chick, owing to the very large amount of food-yolk with which the egg is supplied, is also able to reach a highly developed condition before it hatches and begins to look after itself.

With animals whose eggs contain insufficient food-yolk, and which are not provided with any other special means of nourishing the developing young, the case is very different. They are obliged to hatch and begin life on their own account while still a long way from the adult condition—when only a small part of their ontogenetic journey has been accomplished. Amphioxus, for example, hatches as a free-swimming ciliated embryo shortly after the gastrula stage has been passed through, and completes its development at the expense of food supplies which it obtains for itself.

Embryos which, having hatched at a comparatively early stage of their development, lead independent, self-supporting lives, are commonly spoken of as larvæ, and amongst such larvæ we again find abundant instances of special larval organs developed in relation to their special requirements.

The tadpole of the frog (Fig. 123, 4—11) affords an excellent example of a free-living larva. It has certain special organs, such as its horny jaws and the adhesive glands on the under surface of




FIG. 123.—Stages in the Life History of the Frog. (From Brehm's "Thierleben.")

1, freshly laid eggs; 2, eggs slightly magnified, adhering together by their gelatinous envelopes to form "spawn"; 3, young tadpole still enclosed in the jelly; 4, newly hatched tadpoles fixed by adhesive glands to a blade of grass; 5, 6, tadpoles with external gills; 7, 8, tadpoles with the gills concealed by the operculum; 9, 10, tadpoles with conspicuous hind legs but with the front legs still concealed beneath the operculum; 11, tadpole during metamorphosis, with front legs protruded; 12, young frog with tail not completely absorbed.

(For microscopic details of the early stages see Fig. 121.)

the head, which are developed in relation to its larval life, but there can be no question about the phylogenetic significance of the tadpole stage as a whole. In every essential feature of its organization the tadpole, before its legs develop, is a fish. It swims like a fish by means of its well developed tail, it breathes like a fish by means of its gills and gill-slits, and its internal structure is that of a fish. There can be no doubt that it represents a fish-like stage in the evolution of the frog.

In the tadpole, owing to its free-living, aquatic mode of life,

the characteristic piscine organs are fully functional, but even in the embryos of higher air-breathing vertebrates—reptiles, birds and mammals—while enclosed within the egg-shell or within the womb of the parent, we can still recognize clear traces of a similar fish-like stage in their evolution, for vestiges of gill-slits are present in all (Fig. 124, g.s.) and the arrangement of the principal veins and arteries is unmistakably fish-like.




FIG. 124.—Chick Embryo of about 3 Days, with the Fœtal Membranes and Yolk-Sac removed. (Photographed from one of Ziegler's models.)

au., auditory organ; e., eye; g.s., gill slits; h., heart; m.s., mesoblastic somites; n., nasal organ.

Difficulties in the interpretation of the ontogenetic record arise not only from the addition of new features in the form of embryonic or larval organs but also from the abbreviation of the different stages through which the organism passes. The development of any of the higher organisms must be looked upon as a kind of compromise, due to the necessity of attaining as perfect a condition as possible in as short a time as possible, for the sooner the adult condition is reached the sooner will the organism be able to reproduce its kind, and hence any abbreviation of the earlier stages of development will be advantageous to the species and will be favoured by natural selection. For this reason the fish-like stage in the development of reptiles, birds and mammals is passed through very rapidly and the fish-like structure is no longer fully developed. Although vestigial gill-slits are present the gills themselves are not, and other piscine characters are only represented by transient features.

Turning now to some of the lower groups of the animal kingdom, we may briefly notice a beautiful illustration of the law of recapitulation afforded by the life-history of the common feather-star, Antedon (Fig. 125). This animal, found abundantly in comparatively shallow water off the British coast, belongs to the great phylum Echinodermata, which also includes the star-fish,

sea-urchins and sea-cucumbers. The subdivision to which it belongs—the Crinoidea—is characteristically a deep-water group. It is also a group of great antiquity, the remains of crinoids—such as the well-known "Encrinites" of the Carboniferous period—being abundant in certain Palæozoic formations.

Both the Palæozoic crinoids and the surviving deep-sea members of the group, such as Pentacrinus (Fig. 127), are stalked forms, the "calyx," with its radiating arms, being attached to



FIG. 125.




FIG. 126.

FIG. 125.—The Feather Star (*Antedon bifida*), nat. size.
FIG. 126.—Pentacrinoid Stage in the development of Antedon, × 14.
cir. cirri; *st.* stalk.

the end of a long, jointed, calcareous stem, the lower extremity of which is permanently fixed to the sea-bottom. Antedon, and the other shallow-water crinoids of the present day, on the other hand (Fig. 125), have no stalks but in place thereof a number of slender "cirri" whereby they temporarily attach themselves to seaweed or other objects.

Now in the course of its development from the egg the feather-star passes first through a free-swimming larval stage and then through a fixed stalked stage (Fig. 126), known, from its resemblance to the deep-sea genus Pentacrinus, as the pentacrinoid

stage. Later on the young animal develops cirri and falls off the end of the stalk, assuming once more an active mode of life. Here we recognize very clearly in the pentacrinoid stage of the ontogeny a repetition of the stalked condition through which the ancestors of the feather-star must have passed.




FIG. 127.—A Deep-Sea Crinoid, *Pentacrinus* (*Isocrinus*) *decorus*, about nat. size.

We also find amongst invertebrate animals abundant examples of special larval organs. The body of a caterpillar, for instance, is built up very largely of such structures, and it has to undergo an almost complete reconstruction within the protective envelope of the chrysalis before it reaches the adult condition and emerges as a perfect insect. It is therefore extremely difficult to interpret the caterpillar stage in terms of the ancestral history.

The ophiuroids or brittle stars (Fig. 128), so commonly met with between tide-marks, have remarkable, free-swimming "Pluteus" larvæ (Fig. 129), totally different in appearance from the adult. These larvæ occur in immense numbers in the surface waters of the ocean. They are provided with long slender arms supported by calcareous rods, which probably serve, in part at any rate, to protect the very delicate body from the attacks of other small animals. Before attaining the adult condition the larva undergoes a complex

metamorphosis, during which the long arms are completely lost and the form of the body entirely changed. The echinoids or sea-urchins pass through a very similar larval stage.

The free-swimming "Zoæa" larva of the crab (Fig. 130) is also provided with conspicuous defensive spines which are lost in the




FIG. 128



FIG. 129.

FIG. 128.—A Brittle Star (*Ophiura ciliaris*), × ⅔.
FIG. 129.—The Pluteus Larva of a Brittle Star, × 62.

adult condition (Fig. 104) and which have doubtless been developed in relation to the special conditions of the larval life.

In many cases the development of larval organs causes the young animal to differ so widely from the adult that the relationship of the two for a long time remained unsuspected, and hence the special names which many larvæ have received. In other cases, however, it is the adult animal which has become so profoundly modified in relation to special conditions of life as to

obscure its genetic affinities, which may still be clearly indicated by embryonic or larval stages.

The common Ascidian, for example (Fig. 131), is a sac-shaped organism, permanently attached to rock or seaweed in the adult condition, which by the uninitiated would hardly be taken for an animal at all. Before their life-history was known the Ascidians were placed by zoologists amongst the "Molluscoida," a group of invertebrates supposed to resemble the mollusca or shell-fish. It was only the discovery that the typical Ascidians pass through an active tadpole stage in their development (Fig. 132), with a muscular tail, a notochord and a central nervous system all formed as in vertebrates, that demonstrated their true position as degenerate members of the great phylum Chordata (= Vertebrata in the widest sense of the term), the tadpole stage being, of course, a recapitulation of the ancestral, fish-like, chordate condition.




FIG. 130.—The Zoæa Larva of a Crab (Portunus), × 30. (From a photograph.)

It will be readily understood from the foregoing illustrations that in endeavouring to reconstruct the ancestral history of an organism from the stages which it passes through in its individual development, we have to distinguish very carefully between two sets of characters. In the first place there are characters which are due to inheritance from the adult condition of very remote ancestors and which really indicate stages in what we may call the direct line of evolution. These are termed palingenetic or ancient characters. Such, for example, are the essential features of the gastrula stage, which occurs so generally and which indicates a remote cœlenterate ancestor (the Gastræa of Professor Haeckel) for at any rate the great majority of multicellular animals.

Such also are the essential characters of the tadpole stage of the frog and of the ascidians, and the vestigial gill-slits of higher vertebrates, which indicate descent from some gill-breathing, fish-like form.

In the second place there are characters which have been acquired secondarily by the embryo or larva in relation to its




FIG. 131.—A Simple Ascidian (*Ciona intestinalis*), × ½.

a.p., processes for attachment; *in.ap.*, inhalant aperture; *ex.ap.*, exhalant aperture.




FIG. 132. — Tadpole Larva of a Compound Ascidian (*Diplosoma crystallinum*), × 35. (From a photograph.)

p., papillæ for attachment; t., tail.

special embryonic or larval requirements. These are termed cænogenetic or modern characters, and it is these which tend more or less to obscure the ontogenetic record. Such are the presence of food-yolk, the fœtal membranes of air-breathing vertebrates and the various special larval organs to which we have above referred. It is difficult, however, to draw a hard and fast line between palingenetic and cænogenetic characters, and we must always remember that embryonic stages, as well as the

adult, undergo modification during evolution, and that some cœnogenetic characters are very much more ancient than others.

The relation which exists between the phylogenetic and ontogenetic stages in the evolution of an organism are very diagrammatically expressed in Fig. 133, which is drawn with special reference to the familiar case of the frog. The vertical line is supposed to represent the ancestral history, some of the principal stages of which are indicated. The horizontal line at the top represents the individual life-history, with the stages indicated which represent those selected in the ancestral history. The ovum represents the protozoon ancestor; the blastula the hollow, spherical protozoon colony; the gastrula the cœlenterate; the metamerically segmented embryo the segmented worm, and the tadpole the fish-like stage. The oblique lines represent the lines of evolution of the different ontogenetic stages themselves, in the course of which cœnogenetic characters, such as the acquisition of food-yolk by the ovum and of horny jaws by the tadpole, have arisen. The remaining horizontal lines represent the ontogeny at the different ancestral stages, and their increase in length from below upwards is obviously due to the successive addition of new stages to the ontogenetic record, while the shortness of the horizontal lines as compared with the corresponding portions of the vertical line may be taken to indicate, though very imperfectly, the abbreviation of the ontogeny.




FIG. 133. — Diagram illustrating the Relation between Ontogeny and Phylogeny.

In the vegetable kingdom we find illustrations of the law of recapitulation and of the complication of the ontogenetic record by the development of cœnogenetic characters, quite as striking as any which we find amongst animals. Take, for example, the

life-history of some of the Australian acacias, or wattles. These are leguminous plants and many of them have the pinnately subdivided leaves so characteristic of the order. Others, however, have the pinnate leaves in the adult entirely replaced by narrow "phyllodes," which closely resemble simple undivided leaves like those of some of the eucalypts, but are really only flattened leaf-stalks or petioles. The development of such phyllodes is no doubt to be regarded as an adaptation to the heat and drought of the Australian climate, which delicately subdivided leaves of the ordinary leguminous type are ill-suited to withstand, and the resemblance of the phyllodes to true foliage leaves of the undivided type—and especially to those of the eucalypts—affords a very good illustration of the phenomenon of convergence. If, now, we examine the seedlings of a phyllode-bearing acacia (Fig. 134) we shall find that immediately after the cotyledons or seed-leaves they bear typical pinnate leaves, and then leaves of intermediate form, thus clearly recapitulating the ancestral condition from which the phyllode-bearing forms were derived. A very similar state of things occurs in the common European gorse or furze, another leguminous plant, in which the leaves of the adult have become modified to form spines, while those of the seedling still retain the ancestral ternate condition, somewhat resembling those of the clover.




FIG. 134. — Seedling of a phyllode-bearing Acacia (*Acacia pycnantha*). (From Strasburger.) (The cotyledons have already been shed.)

The cotyledons or true seed-leaves of flowering plants, on the other hand, afford excellent examples of cænogenetic characters developed in relation to the special requirements of the embryo.

They are very commonly modified to form receptacles for a store of food material for the young plant in the form of starch, as in the peas and beans (compare Fig. 56), and may never even leave the seed-coat or emerge above the ground. In such cases they develop no chlorophyll and differ absolutely from ordinary foliage leaves, without, of course, indicating any ancestral stage through which the latter have passed. Even when they emerge above the ground, as in the beech (Fig. 135), and become green, their form is usually widely different from that of the foliage leaves and appears to have been developed largely in adaptation to the necessity for close package within the narrow compass of the seed-coat, the shape of the cotyledons being governed, as Lord Avebury has pointed out, by that of the seed within which, in a dormant condition, they pass most of their lives.




FIG. 135. — Seedling of Beech, showing the Cotyledons. (From Lubbock.)

In short, the embryological investigation of both animal and vegetable organisms leaves no doubt as to the general truth of the recapitulation hypothesis, and must convince any unbiassed observer that, however much modified it may be by abbreviation and by the superposition of secondary features, the life-history of the individual is essentially a condensed epitome of the ancestral history of the race. The law of recapitulation, indeed, may be regarded simply as a logical extension of the law of heredity, for every organism tends to inherit the characters not only of its immediate progenitors but of all its ancestors, and these characters appear in the individual life-history in the same order as that in which they first appeared in the ancestral history—in other words, ontogeny is a repetition of phylogeny and can only be explained in terms of organic evolution. We shall have occasion to consider this question a little more fully in our final chapter.

*

CHAPTER XIX

The stratified rocks—Geological periods—The age of the habitable earth—The geological record—The succession of the great vertebrate groups.

THE materials of which the solid crust of the earth is made up are, as it is perhaps hardly necessary to point out, extremely varied, but whatever may be their physical or chemical characters they are all spoken of by geologists as rocks. In accordance with their mode of formation these rocks may be divided into two chief categories, first, those which, like granite and basalt, have been formed directly by cooling of molten matter, of which the earth was perhaps at one time entirely composed, and, second, those which, like sandstone, shale, limestone and coal, have been formed by accumulation of detritus derived from pre-existing rocks or from the remains of dead organisms. The first are commonly termed igneous and the second sedimentary, the latter deriving their name from the fact that they have been deposited under water. Owing to the manner in which they have been laid down, usually in the form of gravel, sand, mud or ooze, which have subsequently become hardened and consolidated by the pressure of more recent deposits, the sedimentary rocks form a series of layers or strata of varying thickness superposed one upon another. The stratification must at first have been horizontal, but, owing to the irregular shrinkage of the earth's crust and to the action of volcanic upheavals, it has usually been more or less disturbed, so that the planes of bedding have been tilted at various angles and frequently exhibit a high degree of curvature or even contortion. Moreover, rocks which were originally laid down on the bed of the sea have in many cases come to form part of the dry land and even to be uplifted far above sea-level in the form of mountain ranges.

The formation of sedimentary rocks must have been going on ever since the earth became cool enough to admit of the condensation of aqueous vapour into water, and it is still going on in the same way at the present day. Every river is continually

carrying down to the sea immense quantities of sand and mud, which will ultimately be deposited in the form of new strata; every cliff by the sea-shore is slowly or rapidly weathering away under the influence of atmospheric agencies—rain, frost, tides and wind; and far out, beyond the reach of the detritus derived from the land, the sea-bottom is being covered by the slow accumulation of ooze or mud derived almost entirely from the remains of marine organisms, while the activities of corals and other reef-building animals in their turn make no small contribution to the grand total.

The sedimentary rocks naturally contain the remains of vast numbers of organisms which flourished on the earth at more or less remote periods of its history, and the study of these fossils may justly be expected to yield results of the greatest importance from the point of view of the theory of organic evolution. We have here, in fact, the only really direct evidence of the course which the evolution of the animal and vegetable kingdoms has actually taken, and this evidence constitutes what is commonly known as the geological record.

The relative ages of the different sedimentary rocks and of the different geological formations which they build up are of course determined primarily by their position with regard to one another, each layer or bed being necessarily of more recent date than the one below it.[1] The series of strata met with in any particular locality may, however, be very different from that which occurs in other localities, for while mud may be accumulating in one place, sandstone may be forming in another and limestone in a third, and over other areas, which lie above sea-level, rock formation will be replaced by destruction or denudation. Nevertheless, geologists have found it possible to compare the series of stratified rocks found in different parts of the world one with another, and, by the aid of the fossils which they contain, to identify a number of more or less well defined epochs in the geological history of the earth.

At the bottom of the stratified series lies an immense thickness of rocks which seem to have been originally sedimentary, but many of which have undergone profound changes due to pressure and heat since they were laid down. These rocks indicate a very long period of the earth's history, the

[1] Except in a few cases where contortion has been so extensive as to reverse the relative positions.

Geological Time-Scale, as indicated by the Stratified Rocks.

Eras.	Epochs, with relative duration indicated by thickness of stratified rocks.	Some representative British Formations.	Range in Time of Animal Groups. Invertebrates.	Fishes.	Amphibians.	Reptiles.	Birds.	Mammals.	Man.
Cainozoic or Tertiary.	Recent and Pleistocene 4000 feet.	Alluvium, Peat, Boulder Clay, &c.	:	:	:	:	:	:	:
	Pliocene 13000 feet.	Norwich and Red Crag, Coralline Crag, &c.	:	:	:	:	:	:	?
	Miocene 14000 feet.		:	:	:	:	:	:	
	Oligocene 12000 feet.	Hamstead, Bembridge, Osborne and Headon Beds.	:	:	:	:	:	:	
	Eocene 20000 feet.	Barton and Bagshot Beds, London Clay, Thanet Sands, &c.	:	:	:	:	:	:	
Mesozoic or Secondary.	Cretaceous 44000 feet.	Chalk, Greensand, Gault, Wealden, &c.	:	:	:	:	:	:	
	Jurassic 8000 feet.	Oolites, Lias.	:		:	:	:	:	
	Triassic 17000 feet.	White Lias (Rhætic), Elgin Sandstone, &c.	:	:	:	:		:	
Palæozoic or Primary.	Permian 12000 feet.	Magnesian Limestone, Red Marls, &c.	:	:	:	:			
	Carboniferous 29000 feet.	Coal Measures, Millstone Grit, Mountain Limestone, &c.	:	:	:				
	Devonian 22000 feet.	Old Red Sandstone.	:	:					
	Silurian 15000 feet.	Ludlow and Wenlock Shales and Limestones, &c.	:	:					
	Ordovician 17000 feet.	Slates, Flags, Sandstones, &c., of Bala, Caradoc, Llandeilo, Skiddaw, &c.	:						
	Cambrian 26000 feet.	Lingula Flags, Harlech Series, &c.	:						
	Pre-Cambrian (extent unknown). ↓	Archæan Schists, Gneiss and other Crystalline Rocks; Torridonian Sandstone.	?						

pre-Cambrian epoch, during which organic evolution must have been taking place, though only somewhat doubtful indications of organic remains have been met with. Probably the pre-Cambrian rocks originally contained abundant fossils, which have been destroyed by the treatment to which they have been subjected. All the subsequent periods of the earth's history, however, are represented by rocks containing organic remains in greater or less abundance. These deposits indicate a division of the earth's history since pre-Cambrian times into three main eras—primary or palæozoic, secondary or mesozoic and tertiary or cainozoic. Each of these three is subdivided into a series of epochs, as shown in the accompanying table, in which are also mentioned some of the principal rock formations by which the different epochs are represented in the British Islands.

The thickness of the strata deposited during each period differs greatly in different parts of the world, and in North America the various formations appear to be much better developed than in North Western Europe. It is of the utmost importance that our estimates of this thickness should be as accurate as possible, for they constitute important data from which to calculate the age of the habitable earth and the duration of the different geological periods.

Professor Sollas, in his presidential address to the Geological Society of London in 1909, gives the total maximum thickness of the sedimentary rocks from the bottom of the Cambrian to the top of the most recent formations as being no less than 253,000 feet. I have accepted this estimate in drawing up the geological time-scale on page 284, in which the supposed thickness of the deposits belonging to each of the main subdivisions of the three great eras is indicated both numerically and by the relative depth of the space allotted to each.

Professor Sollas estimates that the rate of accumulation of these deposits has averaged about one foot per century, which would give only 25,300,000 years as the total lapse of time since the commencement of the Cambrian epoch. But he also points out that there is good reason for believing that the pre-Cambrian epoch must have been as long as all the succeeding epochs put together, and the total lapse of time since the formation of the stratified rocks (including the pre-Cambrian) commenced might accordingly be estimated at 50,600,000 years.

We must also, of course, make abundant allowance for the fact

that denudation has been going on at all times since the deposition of the stratified rocks commenced, and that the total thickness of these rocks has been enormously reduced thereby, the same material having been used over and over again in rock formation.

Where opinions differ so much, and where there is so much uncertainty as to the value of the data themselves, it is obvious that any estimate of geological time derived from the thickness of the sedimentary rocks can have only a doubtful value, and that it is highly desirable that such an estimate should be checked by making use of other sources of information.

Several other methods of estimating the age of the earth have been employed. One of the most interesting is that which is especially associated with the name of Professor Joly, and which depends upon the amount of sodium present in solution in sea-water. If we knew the total amount of sodium present in the ocean, and if we also knew the rate at which it has been accumulating since the ocean was first formed, it would be a simple matter to calculate the age of the ocean and therefore that of the stratified rocks, whose existence must have commenced with that of the ocean itself. The greater part at any rate of the salt contained in the sea must have been derived from the disintegration of the land and carried down by rivers. Estimates have been made, based upon careful analysis, of the amount of sodium contained in the sea and in the water of various rivers, as well as of the amount of water which flows into the sea annually, and Professor Sollas has come to the conclusion that "on a review of all the facts, the most probable estimate of the age of the ocean would appear to lie between 80 and 150 millions of years," which is considerably in excess of the estimate which he arrives at from the consideration of the thickness of the sedimentary rocks, but, as will be seen from what follows, is still probably much too low.

The discovery in recent years of the radio-active elements has afforded a new method of attacking the problem. It is now known that the element uranium, occurring in various minerals, undergoes a spontaneous disintegration of its atoms, changing very slowly into ionium, then into radium, and finally into lead and helium. The rate at which these changes take place is fairly accurately known, so that it is possible, by determining the percentage of lead or helium in a mineral containing uranium, to estimate the lapse of time since that mineral was first deposited in any particular geological formation.

Professor Soddy [1] estimates that 1 per cent. of lead in terms of the quantity of uranium represents a period of 80 million years, while every cubic centimetre of helium per gram of uranium indicates nine million years. As helium is a gas, and some of it will have escaped from the mineral, the result which it gives must be regarded as a minimum. That given by the lead ratio, on the other hand, may be too high, as lead may have been an original constituent of the mineral. Estimated in this way the age of the oldest Archæan rocks (pre-Cambrian) would seem to be between seven hundred million and sixteen hundred million years.

We must now turn to the consideration of the geological record itself, and in the first place we may ask, what is to be legitimately expected from such a record? Have we any right to expect anything like a complete representation, by fossil remains, of the past history of the organic world? Obviously the answer to this question must be a decided negative. The imperfection of the geological record is due to many causes. It must have been imperfect when first laid down, for the great majority of organisms usually disintegrate and pass away without leaving any recognizable remains behind them at all. In most cases it is only hard skeletal structures that have any chance of being preserved. Bodies composed entirely of soft tissues, such as jelly-fish and many worms, are rarely represented by fossils. Even hard structures, such as animal skeletons, will only be fossilized if they happen by some fortunate chance to find their way to some place where rock formation of a suitable kind is going on. The remains of land animals may be carried by rivers to some sea or lake and buried in a suitable accumulation of mud or sand, but it is more likely that they will not. Marine animals, provided they have hard skeletons, have, of course, many more opportunities of attaining a lasting monument, and we often find great thicknesses of rock, such as chalk and limestone, composed almost entirely of their remains.

Even when the record has been successfully established, however, it is liable to destruction by various agencies. The rocks containing it may be uplifted above sea-level and planed right away by sub-aërial denudation, or they may be sunk so

[1] "Science and Life" (London, John Murray, 1920).

far beneath later accumulations as to be profoundly altered by the action of heat and pressure, by which means any fossils which they contain may be completely destroyed. Then, again, we must remember that only a relatively small proportion of the earth's crust is accessible for investigation. Deep-lying rocks may be brought to the surface by upheaval, and denudation of overlying strata, or they may be reached by deep mining, but we know practically nothing of the strata which now lie beneath the bed of the sea, and even the dry land has only been tentatively scratched by inquisitive man in a few places.

Even were the geological record far less perfect than it actually is, therefore, its imperfection could not legitimately be




FIG. 136.—Three Species of Trilobites. (From British Museum Guide.)
A., *Agnostus princeps*; B., *Olenus cataractes*; C., *Staurocephalus murchisoni*.

used as an argument against the theory of organic evolution. From the nature of the case it must be imperfect and the surprising thing about it is that it should have yielded so much evidence as it has done. The earlier portions of the record, however, have apparently been completely destroyed. The fact that already in the Cambrian epoch highly organized invertebrate animals, such as trilobites (Fig. 136) and brachiopods, were in existence, shows us that evolution must then have been going on for an immensely long period. This period, as we have already indicated, is represented by the pre-Cambrian rocks, in which the organic remains have been so far destroyed as to be rarely recognizable.

The investigation of what remains of the geological record

has, however, yielded some very remarkable and conclusive results. In the first place we have learnt that life on the earth has probably been continuous without a break from its first appearance in pre-Cambrian times to the present day, and in the second place we have learnt that the great groups of animals and




FIG. 137.—Restoration of *Cephalaspis murchisoni*, from the Lower Old Red Sandstone, × ½. (From British Museum Guide, after Smith Woodward.)

plants have appeared on the earth in exactly the order which we should expect on the assumption that each has arisen from some preceding and more lowly organized ancestral group.




FIG. 138.—*Pterichthys milleri*, from the Lower Old Red Sandstone; restored by R. H. Traquair. A. Dorsal; B. Ventral; C. Lateral views, × ½. (From Smith Woodward's "Vertebrate Palæontology.")

In discussing this point we may confine our attention to the Vertebrata, the evolution of which seems to have taken place entirely during post-Cambrian times. The most lowly organized group of true vertebrates existing at the present day is that of the Cyclostomata, which includes the lampreys and hag-fishes.

These are distinguished from true fishes by the absence of jaws, the mouth being suctorial, and by other primitive features. The skull and vertebral column remain cartilaginous throughout life and there are no paired limbs. Neither is any dermal armour of any kind developed. The only structures which they possess which seem at all likely to be preserved as fossils are the horny teeth. Certain bodies known as conodonts, which occur as fossils in strata ranging from the Lower Silurian to the Carboniferous, may perhaps represent such teeth. If so they are perhaps the earliest vertebrate remains as yet known.[1]




FIG. 139.—*Pterygotus osiliensis*, an Upper Silurian Eurypterid, dorsal view, reduced. (From Wood's "Palæontology," after Schmidt.)

The remarkable group of fishes known as Ostracodermi, however, makes its appearance in the Upper Silurian and continues on to the Upper Devonian. These animals agree with the cyclostomes in the absence of true jaws and (in most known forms) of paired fins, and in the extremely primitive character of the vertebral column. They had also, like the cyclostomes, median fins, but they differed from the latter conspicuously in the presence of a strongly developed dermal armour, to the existence of which their fossil remains owe their preservation. As representative genera of this group we may mention Cyathaspis (Upper Silurian), Pteraspis (Lower Devonian), Cephalaspis (Upper Silurian and Lower Devonian, Fig. 137) and Pterichthys (Lower Devonian, Fig. 138).

[1] Palæospondylus, from the Lower Old Red Sandstone of Scotland, is probably also a cyclostome.

The origin of the Ostracodermi is unknown, but their relationship to the cyclostomes has led to their inclusion with the latter in one class, the Agnatha (jawless vertebrates), which stands at the very bottom of the vertebrate series and was probably derived from some primitive chordate ancestor, not unlike Amphioxus, which had no hard structures to be handed down to us in a fossil condition. It is true that the ostracoderms bear a curious resemblance to certain extinct contemporaneous arthropods, the Eurypteridæ (Fig. 139), but this resemblance is probably merely superficial and due to convergence owing to similar conditions of life; it cannot be accepted as evidence of the origin of vertebrates from arthropodan ancestors, which, on other grounds, is extremely improbable.

The most primitive group of true jaw-bearing fishes is that of the




FIG. 140.—Restoration of *Acanthodes wardi*, from the Coal Measures of Staffordshire, × ⅓. (From British Museum Guide.)

Elasmobranchii, including the existing sharks, dog-fishes, skates and rays. These have well-developed paired fins and a dermal armour of scales or denticles, but their primitive character is shown by the fact that the internal skeleton remains cartilaginous throughout life. Fragmentary indications of elasmobranchs occur already in the Upper Silurian, but the first satisfactory specimens so far have been met with in rocks of Lower Devonian age (Old Red Sandstone). A carboniferous form, Acanthodes, is represented in Fig. 140.

The remarkable Dipnoi, feebly represented by the mud-fishes or lung-fishes of the present day—the Australian Neoceratodus (Fig. 112), the African Protopterus and the South American Lepidosiren — seem to have arisen during the Devonian period and to have attained their maximum of development and specialization during that epoch. This group is of especial interest, as we have already had occasion to notice,

as indicating how the transition from an aquatic to a terrestrial mode of life was first rendered possible to vertebrate animals by the development of lungs as organs of respiration. The dipnoids, however, have remained aquatic in habit, and retain their gills for aquatic respiration as well as being able to breathe air directly by means of their lungs.

The ordinary bony fishes (Teleostei), to which the vast




FIG. 141.—*Branchiosaurus amblystomus;* restoration of Skeleton (A) and ventral Armour (B) by H. Credner, nat. size. Lower Permian. (From Smith Woodward's "Vertebrate Palæontology.")

majority of existing species belong, do not attain any prominence as a group before the secondary era, but they had fore-runners in some of the early ganoids which date back to lower Devonian times. The teleosts are the most specialized of all fishes and it is not from such a group that we should expect the next great advance in organization to take its origin.

There are the strongest anatomical and embryological grounds for believing that the Amphibia, a group which at the present

day includes the frogs, toads, newts and salamanders, are the descendants of fish-like ancestors which became adapted to an air-breathing mode of life by the development of lungs. The dipnoid fishes, which, as we have already seen, attained their maximum of development in the Devonian epoch, show us clearly enough how such a transition probably took place, and it was doubtless either from some dipnoid form, or from some other primitive type of fish which had also succeeded in converting its swim-bladder into lungs, that the Amphibia arose. The fact that amphibian remains first occur in Lower Carboniferous rocks is in complete harmony with this hypothesis as to the origin of the group.

The earliest known amphibians are the Stegocephalia, so-called on account of the strongly developed bony armour which covered the head and formed the roof of the skull, as it did already in many of the earlier fishes. These Stegocephalia included both small, salamander-like forms such as Branchiosaurus (Fig. 141) and large crocodile-like creatures—the labyrinthodonts. Some of them survived into the Triassic epoch, after which they appear to have become entirely extinct, and although a fair number of Amphibia still exist at the present day, the group must be regarded as having attained its maximum of development in late Palæozoic and early Mesozoic times. The existing frogs and toads are very highly specialized forms, more or less adapted to a terrestrial life in the adult condition but for the most part resorting to water to deposit their eggs, which hatch out in the form of aquatic fish-like larvæ or tadpoles, breathing by means of gills (Fig. 123). The newts, on the other hand, though developing lungs, retain the fish-like form and the aquatic habit throughout life.

In one respect the imperfection of the geological record as regards the origin of the Amphibia from fishes is especially to be regretted. One of the chief distinctions between the two groups lies in the fact that whereas the Amphibia always have pentadactyl limbs (except when these have been lost by degeneration), the fishes have only fins, which are not pentadactyl. The conversion of the fin into a pentadactyl limb was no doubt an adaptation to the terrestrial mode of life, but neither comparative anatomy nor embryology nor yet the evidence of the geological record have so far enabled us to discover how the transformation of the one type of limb into the other actually took

place. We can only hope that light may yet be thrown upon this difficult problem by the discovery of the fossil remains of intermediate forms.

The reptiles and the amphibians are closely related to one another, but existing reptiles are readily distinguished from existing amphibians in a variety of ways. For example, they produce much larger eggs, within which the young are nourished up to a very advanced stage of development by means of the yolk, while the embryo is provided with the special protective and respiratory fœtal membranes known as amnion and allantois, which are not found in amphibians. A reptile, again, never develops gills at any stage of its existence, while an amphibian




FIG. 142. Skeleton of *Parciasaurus baini*, × $\frac{1}{30}$. (From Smith Woodward, after Seeley.)


not only has gills in the larval but sometimes also in the adult state.

Fossil remains naturally afford no clue as to when the development of the fœtal membranes and the suppression of the larval gills took place, and we are thrown back entirely upon skeletal peculiarities as a means of distinguishing between extinct members of the two groups. From one point of view this is unsatisfactory, but the very difficulty which we experience in drawing a hard and fast line between the fossil reptiles and amphibians only serves to emphasize the fact that the one group has been derived from the other.

One of the chief osteological peculiarities which distinguish existing reptiles from amphibians is, as Dr. Smith Woodward observes, "the degeneration of the parasphenoid bone and its functional replacement in the basi-cranial axis by the pterygoids

the Reptilia succeeds that of the Amphibia in exactly the way ımanded by the theory of organic evolution.

The reptiles as a group attained their maximum of develop- ent in Mesozoic times, and of the nine great orders into ıich the class has been subdivided only four persist at the esent day, and one of these four is represented by only a single ecies. This species, *Sphenodon* (=*Hatteria*) *punctatus* (Fig. 115), w confined to certain small islands off the coast of New aland, is the sole surviving representative of the order



G. 145.—Skeleton of *Iguanodon bernissartensis*, as reconstructed by Dollo, × $\frac{1}{80}$. (From British Museum Guide.)

hynchocephalia, in some respects a primitive group, which, as we ıve already seen, flourished already in the Triassic period. The her existing orders of reptiles are the Chelonia (turtles and tor- ises), the Squamata (lizards and snakes) and the Crocodilia (croco- les and alligators).

Many of the extinct Secondary reptiles were far more highly ecialized and remarkable than any existing forms. Different embers of the class were adapted to the most diverse modes of e, the group having taken full possession of sea, land and air. ıe earliest and at the same time the least specialized of the tinct orders were the Anomodontia or Theromorpha,[1] which Dr. ıith Woodward tells us were "directly intermediate in skeletal

[1] Subdivided by recent writers into several orders, of which the Cotylosauria, luding Pareiasaurus, are the most primitive.

of the Reptilia succeeds that of the Amphibia in exactly the way demanded by the theory of organic evolution.

The reptiles as a group attained their maximum of development in Mesozoic times, and of the nine great orders into which the class has been subdivided only four persist at the present day, and one of these four is represented by only a single species. This species, *Sphenodon* (=*Hatteria*) *punctatus* (Fig. 115), now confined to certain small islands off the coast of New Zealand, is the sole surviving representative of the order



FIG 145.- Skeleton of *Iguanodon bernissartensis*, as reconstructed by Dollo, × $\frac{1}{80}$. (From British Museum Guide.)

Rhynchocephalia, in some respects a primitive group, which, as we have already seen, flourished already in the Triassic period. The other existing orders of reptiles are the Chelonia (turtles and tortoises), the Squamata (lizards and snakes) and the Crocodilia (crocodiles and alligators).

Many of the extinct Secondary reptiles were far more highly specialized and remarkable than any existing forms. Different members of the class were adapted to the most diverse modes of life, the group having taken full possession of sea, land and air. The earliest and at the same time the least specialized of the extinct orders were the Anomodontia or Theromorpha,[1] which Dr. Smith Woodward tells us were " directly intermediate in skeletal

[1] Subdivided by recent writers into several orders, of which the Cotylosauria, including Pareiasaurus, are the most primitive.

characters between the highest Labyrinthodonts (*Mastodonsaurus* and its allies) and the lowest Mammals (Monotremata)." These animals, whose remains have been found only in Permian and Triassic deposits, were terrestrial creatures with limbs modified for walking on dry land, so that they often bore a close general resemblance to mammals. One of the best known is the celebrated Pareiasaurus (Fig. 142), described by the late Professor Seeley from the Karoo formation of Cape Colony. This animal attained a length of some ten or eleven feet.

The Sauropterygia or Plesiosauria (Fig. 143) were long-necked lizard-like forms, sometimes of large dimensions, which had become re-adapted to a marine life, and whose limbs, while retaining the typical pentadactyl structure, gradually became modified to form paddles. The group seems to have persisted throughout the whole of the Secondary period and shows a gradual evolution from the Trias onwards.

The Ichthyopterygia or Ichthyosauria (Fig. 144), which also range throughout the whole of the Secondary period, were more completely adapted to life in the ocean and acquired a remarkably fish-like form, like the whales, dolphins and porpoises amongst existing mammals.

The Dinosauria or Ornithoscelida formed an enormous group of land reptiles which seems to have arisen in the Triassic period and reached its climax in Jurassic and Cretaceous times. Some of them were carnivorous, others herbivorous; some walked on all fours and others on their hind legs, and they often attained gigantic dimensions. The well-known Iguanodon (Fig. 145), from the Wealden deposits of Europe, was a huge herbivore, which seems to have supported its massive body, chiefly at any rate, on its hind limbs, which were much more strongly developed than the front pair. The American Brontosaurus (Fig. 146) and Diplodocus walked on all fours, and the latter attained a length of 80 feet but a large proportion of this was taken up by the enormously long neck and tail. In both these forms the head was of astonishingly small dimensions in proportion to the rest of the body. Other Dinosaurs, such as Stegosaurus (Fig. 147) and Triceratops (Fig. 148), developed an extraordinary dermal armature of bony plates or spines.

Perhaps the most remarkable of all the extinct reptiles of the Secondary period, however, were the Ornithosauria (Pterosauria or pterodactyls), which at that time occupied the place now




FIG. 146




FIG. 147.




FIG. 148.

[For descriptions, see p. 310.

filled by the birds and bats. These animals were very perfectly adapted for flight, the wing being formed, as already described in Chapter XVII, by an extension of the skin supported by the arms, legs and tail, and especially by the enormously elongated fifth digit (Fig. 101). Some of these flying reptiles attained a very large size, the total expanse of the wings in Pteranodon (Fig. 149) being about eighteen feet.

The origin of birds from reptilian ancestors has been quite conclusively demonstrated on anatomical and embryological grounds, and Professor Huxley included both birds and reptiles in one large group, the Sauropsida. The structure of their wings shows, however, that birds cannot have arisen from pterodactyls but must have sprung from some less specialized form, mainly through the development of a dermal exoskeleton




FIG. 149.—Skeleton and Outline of *Pteranodon occidentalis*, from the Upper Cretaceous of Kansas, U.S.A.; × $\frac{1}{54}$. (From British Museum Guide.)

in the form of feathers, which constitutes the chief distinguishing feature of the group. It is, therefore, quite in accordance with expectation that the earliest known bird, Archæopteryx (Fig. 153), should have been found in the lithographic slates of Solenhofen in Bavaria, which are of Upper Jurassic age, and should exhibit characters intermediate between those of existing birds and reptiles. We shall have occasion to refer to this remarkable connecting link more in detail in our next chapter.

The Mammalia, so far as existing evidence indicates, appeared

---

FIG. 146.—Skeleton of *Brontosaurus excelsus*, from the Upper Jurassic of Wyoming, U.S.A.; × $\frac{1}{150}$. (From British Museum Guide, after O. C. Marsh.)

FIG. 147.—Skeleton of *Stegosaurus ungulatus*, from Jurassic of Wyoming; × $\frac{1}{60}$ (From Smith Woodward's "Vertebrate Palæontology," after O. C. Marsh.)

FIG. 148.—Skeleton of *Triceratops prorsus*, from Cretaceous of Wyoming; × $\frac{1}{30}$. (From British Museum Guide, after O. C. Marsh.)

at an earlier date than the birds, but the earliest known mammals were far less highly specialized forms than birds, and although what appear to be mammalian remains have been found as low down as the Trias, the group did not attain much importance before the Tertiary epoch, when it replaced the reptiles as the dominant group of vertebrates. Opinions have been a good deal divided as to whether the mammals arose directly from amphibian ancestors or from some primitive group of reptiles. On the whole the evidence seems to be decidedly in favour of the latter view, which fits in very well with the first appearance of the mammals just when the reptiles were beginning to become dominant, and with the fact that, as we have already seen, some of the earlier reptiles were extraordinarily mammalian in aspect.

The earliest mammals were small forms of doubtful affinities. Dr. Smith Woodward remarks in this connection :—" It is as yet impossible to determine at what particular stage in the evolution of the vertebrate skeleton the lung-breathers first acquired the characteristic mammalian circulatory system, the milk-producing glands, and a dermal covering of hair," these being the principal features, apart from the skeleton, which distinguish mammals from reptiles at the present day. The difficulty is increased by the fact that some of the anomodont reptiles had acquired a dentition very similar to that of primitive mammals, while the earliest known mammals are represented by little more than a few fossil jaws and teeth.

The Mammalia, both living and extinct, may be divided into three main subclasses. (1) *Prototheria*, with the single surviving order Monotremata, represented by the Australian spiny ant-eater (Echidna, Fig. 94) and duck-billed Platypus (Ornithorhynchus, Fig. 93), which, as we have already seen, are intermediate both in anatomical structure and in their method of reproduction between the reptiles and the more typical mammals. (2) *Metatheria*, with the sole order Marsupialia, represented to-day by the Australian kangaroos, wombats, phalangers, thylacines and numerous other pouched mammals, and by the American opossums (Didelphyidæ) and Cænolestes. These are in some respects primitive forms, in which the young are born at a very early stage of their development (there being at the most only a very feebly developed placenta) and usually carried about, attached to the teat of the mother, in a marsupium or pouch. They are readily

distinguished by osteological features, especially the structure of the jaws and teeth (Fig. 110), from the higher mammals. (3) *Eutheria*, the dominant mammals of the present day, with a large number of orders — edentates, whales, sirenians, ungulates, rodents, carnivores, insectivores, bats and primates; with well developed placenta and retaining the young in the womb until a very advanced stage of development. There can be no doubt that the Eutheria are on the whole more highly organized forms than the Metatheria and the latter than the Prototheria. This is especially indicated by the gradual acquisition and perfection of the characteristically mammalian method of nourishing the young by means of the placenta and mammary glands.

The order of appearance in time of the principal subdivisions of the class Mammalia, as indicated by the geological record, entirely supports the evolutionary hypothesis. The earliest known fossils which may possibly be referable to the class are of Triassic age. Tritylodon is represented by an imperfect skull from the Karoo formation of South Africa. This has generally been regarded as mammalian, but Dr. Smith Woodward, notwithstanding the fact that it has tuberculated grinding teeth with deeply cleft roots, considers that it probably belonged to an anomodont or theromorph reptile. Microlestes is represented by double-rooted, multituberculate teeth obtained from European Rhætic formations, and may also possibly be reptilian.

In deposits of Lower and Upper Jurassic age we find more convincing evidence of the existence of true mammals. The celebrated Stonesfield slate of Oxfordshire (Lower Jurassic) has yielded a fragment of a jaw, containing three small multituberculate grinding teeth, to which the name Stereognathus has been given, and one of the Middle Purbeck beds of Swanage (Upper Jurassic) has contributed the well known jaws of Plagiaulax (Fig. 150). Remains of closely related forms, supposed to have belonged to the same family (Plagiaulacidæ), have been discovered in Upper Jurassic and Upper Cretaceous formations of North America, and the family appears to have survived, both in Europe and North America, into early Tertiary times.



FIG. 150.—Mandible of *Plagiaulax minor*, × 4. (From Smith Woodward's "Vertebrate Palæontology," after Falconer.)

The Plagiaulacidæ and related forms have been grouped together in the extinct order Multituberculata, which Dr. Smith Woodward places provisionally amongst the Prototheria, side by side with the surviving order Monotremata, no remains of which are known to occur before Tertiary times. It is possible, however, that the Multituberculata may be metatherian rather than prototherian.

The remains of undoubted Metatheria (Marsupialia) first occur, so far as we yet know, in the same beds as the earliest Multituberculata (leaving out of account the enigmatical Tritylodon and Microlestes). Mandibles of Phascolotherium (Fig. 151) and Amphitherium have been found in the Stonesfield slate, while Triconodon and Spalaco-




FIG. 151.—Mandible of *Phascolotherium bucklandi*; × 3. (From Smith Woodward's "Vertebrate Palæontology," after Goodrich.)

therium are similarly represented in the mammal bed at Durdlestone Bay near Swanage.

Throughout the whole of the Secondary period the mammals remained of insignificant size, and in a more or less primitive condition, such as is represented at the present day by the surviving monotremes and marsupials. The typical placental mammals (Eutheria) are not known to us from formations of earlier date than the Eocene. Then, all at once, they seem to have branched out in every direction and taken possession of land, sea and air just as the reptiles had done before them; whales replacing the Ichthyosauria and Plesiosauria, various groups of land mammals replacing the Theromorpha and Dinosauria, and bats sharing with the birds the kingdom of the air which had formerly belonged to the pterodactyls.

As in the case of their amphibian and reptilian predecessors,

many of the mammalian groups in Tertiary times have run to great size; most of the larger forms, such as the primitive ungulate, Tinoceras (Fig. 152), of the American Eocene, and the giant ground sloth, Megatherium, of the American Pleistocene, are already extinct, but it must not be forgotten that the existing whales are amongst the largest animals that have ever lived, and in bulk at any rate will bear comparison with the largest of the great extinct reptiles.

The last term in the evolutionary series of the Mammalia is man,




FIG. 152.—Skeleton of *Tinoceras ingens*, from the Middle Eocene of Wyoming, $\times \frac{1}{30}$. (From British Museum Guide, after O. C. Marsh.)

whose advent, so far as we at present know from the direct evidence of fossil remains of human skeletons, dates back only to about the commencement of the Pleistocene epoch.[1]

There is one more point that is well worth emphasizing about the evolution of the Vertebrata, as indicated not only by the geological record but also by the facts of comparative anatomy. Each successive great group appears to have arisen, not from the most highly specialized members of some preceding great group, but from comparatively undifferentiated forms. Thus the

[1] *Vide* Chapter XXVIII.

Amphibia arose, not from bony fishes, but from primitive dipnoids or ganoids; the reptiles arose, not from frogs or toads, but from primitive stegocephalian amphibia; the birds arose, not from pterodactyls, but from comparatively unspecialized reptiles; the mammals also arose from the more primitive reptilian forms, and man himself, whose advent undoubtedly marks the commencement of a fresh line of evolution, belongs to the order Primates, which in respect of bodily organization, as seen, for example, in the typical pentadactyl limbs, is far more primitive than many other mammalian groups.

Each great group seems to have begun in a small way, then developed rapidly, branching out in many directions and becoming the dominant group for the time being, only to dwindle away again and give place to some new and vigorous off-shoot. The dominance of any particular group has often been accompanied by the attainment of enormous size by some of its individual members,[1] and it is not impossible that this may have had something to do with its subsequent decline or complete extinction.

So far as the animal kingdom is concerned, we may perhaps say without exaggeration that the succession in time of the different groups, as indicated by the geological record, amounts to positive demonstration of the truth of the theory of organic evolution. In the case of plants the record is perhaps not quite so clear, but here also there can be no reasonable doubt that the great groups succeeded one another in a manner consistent with the theory, commencing with the algæ and ending with the flowering plants of the present day.

[1] A possible explanation of this fact is suggested in Chapter XXVII

CHAPTER XX

Fossil pedigrees—Ancestry of birds, horses, elephants and whales.

In our last chapter we gave a brief outline of the general course of evolution amongst vertebrate animals as indicated by the geological record. We may now study in somewhat greater detail certain branches of the great phylogenetic tree which are represented by fossil remains in such a way as to make them particularly instructive from the point of view of the evolution theory.

One of the most highly specialized groups of vertebrates that have ever existed is that of the birds. We have already pointed out that, on anatomical grounds, birds are classed together with reptiles as Sauropsida. They agree with reptiles in their method of reproduction by means of large, heavily yolked eggs, and in the presence, in the embryo, of the characteristic fœtal membranes, amnion and allantois, as well as in certain morphological characters of the adult. They differ from reptiles, however, in many striking features. Thus they possess feathers, which almost (but not quite) completely replace the reptilian scales as a protective exo-skeleton. The anterior limbs are modified to form wings constructed, as we have already seen in Chapter XVII, on an entirely different plan from those of flying reptiles. The digits of the hand are very greatly reduced; as a rule [1] only one of them, and that in a vestigial condition, projects freely from the anterior border of the wing, forming the so-called "ala spuria" (Fig. 101). The true tail is greatly abbreviated and the caudal vertebræ reduced in number and to a large extent fused together to form the "ploughshare bone" which supports the tail feathers. Lastly, all existing birds have completely lost their teeth, which are functionally replaced by the horny beak.

The remains of the earliest known bird, Archæopteryx (Fig. 153), have been found in the celebrated lithographic stone of Solenhofen in Bavaria, of Upper Jurassic age, which, owing to its extremely fine grain, is peculiarly well suited for the preservation of even

[1] The young hoatzin, however, a South American bird (*Opisthocomus cristatus*), still has claws on the first and second digits, which it uses for climbing.

such delicate structures as feathers. This animal was about the size of a rook and the presence of well developed feathers and wings of the avian type is alone sufficient to show that we are dealing with a true bird. It still exhibits, however, a number of features which are usually met with in reptiles but have disappeared in modern birds. The digits of the anterior limb are not nearly so much reduced as in the latter, for three claw-bearing



FIG. 155.—Fossil Remains of *Archæopteryx siemensi*, showing the three fingers in each wing, the long tail, feathers, &c. (From Lankester's "Extinct Animals.")

fingers project from the anterior margin of the wing; the tail is elongated like that of a lizard and supported by about twenty separate vertebræ each carrying a pair of feathers; and numerous teeth are present in the beak.

It is obvious that Archæopteryx represents a stage in the derivation of birds from reptilian ancestors, and this is exactly what we should expect of the earliest birds in accordance with the theory of evolution. Unfortunately, with the exception of a few other toothed birds of Cretaceous date, Archæopteryx is

almost the only link in the pedigree of birds which has so far been discovered, and it teaches us nothing as to the origin of those characteristic avian structures, the feathers, which it possesses already in a fully developed condition.

It will be observed that Archæopteryx occupies a position between reptiles and typical birds exactly comparable with that of the Monotremata between reptiles and typical mammals (see Chapter XVII), the only difference being that the Monotremata still survive side by side with mammals of the most highly advanced type, while Archæopteryx has long since become extinct.

One of the most complete fossil pedigrees as yet known to us




FIG. 154.—Skeleton of Phenacodus, a five-toed Eocene Ungulate. (From Lankester's "Extinct Animals.")

is that of the Equidæ or horse family. As we have already seen in Chapter XVII, the study of comparative anatomy indicates very clearly that the highly specialized single-toed limbs of the horse (Fig. 99) must have arisen from some primitive pentadacty type by gradual suppression of all the digits except the middl one. Amongst the fossil remains of horse-like animals whicl abound in various tertiary formations of Europe and America w find a very complete series of stages in the evolution of the modern horse, which entirely confirms this conclusion. Our knowledge of this extremely interesting phylogenetic series is due largely to the late Professor O. C. Marsh and has been admirably summarised by Mr. R. S. Lull in the American Journal of Science.[1]

[1] Series IV, Vol. XXIII, 1907.




FIG. 155.—Outlines of Horses of different Geological Periods, showing their Relative Sizes. (From Lull.)

a, Protorohippus (Eocene); *b*, Orohippus (Eocene); *c*, Mesohippus (Oligocene); *d*, Merychippus (Miocene); *e*, Pliohippus (Pliocene); *f*, Equus (Recent).

It is generally admitted that the Equidæ originated from the Condylarthra, a group of primitive, five-toed, ungulate mammals which was well established in early Eocene times, and the best-known representative of which is Phenacodus (Fig. 154). The evolution of the horses appears to have taken place chiefly in America, though occasionally representatives of the group seem to have migrated to or from Europe, doubtless by a former land connection in the neighbourhood of Behring Strait. In comparatively recent times, however, the family became confined to the old world and was only re-introduced to America by human agency.

The course of their evolution has evidently been determined by the development of extensive, dry, grass-covered, open plains on the American continent. In adaptation to life on such areas structural modification has proceeded chiefly in two directions. The limbs have become greatly elongated and the foot uplifted from the ground, and thus adapted for rapid flight from pursuing enemies, while the middle digit has become more and more important and the others, together with the ulna and the fibula, have gradually disappeared or become reduced to mere vestiges. At the same time the grazing mechanism has been gradually perfected. The neck and head have become elongated so that the animal is able to reach the ground without bending its legs, and the cheek teeth have acquired complex grinding surfaces and have greatly increased in length to compensate for the increased rate of wear. As in so many other groups, the evolution of these special characters has been accompanied by gradual increase in size (Fig. 155). Thus Eohippus, of lower Eocene times, appears to have been not more than 11 inches high at the shoulder, while existing horses measure about 64 inches, and the numerous intermediate genera for the most part show a regular progress in this respect.

All these changes have taken place very gradually, and a beautiful series of intermediate forms indicating the different stages from Eohippus to the modern horse (Equus) have been discovered. The sequence of these stages in geological time exactly fits in with the theory that each one has been derived from the one next below it by more perfect adaptation to the conditions of life. Numerous genera have been described, but it is not necessary to mention more than a few.

The first indisputably horse-like animal appears to have been

Hyracotherium, remains of which have been found in the London Clay (Lower Eocene). Another Lower Eocene genus was Eohippus, which seems to have arisen in Western Europe, possibly from a hyracotherian ancestry, and migrated, by way of Northern Asia, to America, where its remains occur in rocks of the same age. In this animal (Fig. 156) the fore foot had four well developed digits, while the thumb had already completely disappeared; in the hind foot the great toe had also disappeared and the fifth digit was represented only by a splint bone. In both fore and hind feet the third or middle digit was already conspicuously larger than any of the others.




FIG. 156. — *a*, Fore Foot and *b*, Hind Foot of *Eohippus pernix*, × ½. (Modified from Lull, after Marsh.)

Eohippus was succeeded by Protorohippus (Fig. 155, *a*), which was some 3 inches higher and had lost the vestigial thumb. Then came Orohippus (Fig. 155, *b*), again a little larger and with closely similar feet (Fig. 157), but with a considerable advance in the evolution of the grinding teeth. The last of the Eocene horses was Epihippus, still with four toes in front and three behind, but with the lateral toes further reduced in size and another distinct advance in tooth structure.

In Oligocene times there occurred in North America Mesohippus and Miohippus, and in Europe Anchitherium. Mesohippus (Fig. 155, *c*) was 18 inches or more in height, with three digits and a vestige of the fifth in the fore foot and three digits only in the hind foot (Fig. 158). Miohippus attained a height of 24 inches and closely resembled Mesohippus in the structure of its feet. Anchitherium is supposed to be a European derivative of Miohippus.

In the Miocene period the horses appear to have attained their maximum of development as a group, and a number of extinct American genera are distinguishable. Merychippus (Fig. 155, *d*), Protohippus and Neohipparion were still three-toed horses, though the lateral digits were now greatly reduced (Fig. 159). Pliohippus

(Fig. 155, *e*), which continued on into Pliocene times and attained a height of 48 inches, had the second and fourth digits of each foot represented by mere splint bones as in modern horses, and had therefore already attained to the single-toed condition (Fig. 160).

In Pliocene times, however, we still find a three-toed horse—Hipparion—surviving in Europe, but the modern one-toed genus Equus (Fig. 155, *f*) also makes its appearance both in the old and new worlds, becoming extinct in the new world in Post-Pleistocene times until re-introduced from Europe by the agency of man.

The time occupied in the evolution of the genus Equus from its remote ancestor Eohippus is estimated by Professor Sollas at five or six millions of years. This period is sufficient to allow of a very slow and gradual change from one condition to the other. Allowing five years for each generation, Sollas arrives at the conclusion that somewhere about a million generations intervene between the two extremes. The total increase in height during this time has been 53 inches, and if this increase were spread fairly uniformly over the whole period it would only mean about 0·00005 inch for each successive generation—an amount which would be quite imperceptible to human observers.




FIG. 157.—*a*, Fore Foot and *b*, Hind Foot of *Orohippus agilis*, × ½. (From Lull, after Marsh.)

In reconstructing such a pedigree as that of the horse from palæontological evidence it is of course necessary to bear in mind that the great majority of extinct forms which come to light will almost certainly not be actually in the direct line of descent. Collateral branches will have been given off from the phylogenetic tree in various directions, and it is much more likely that any particular form discovered will belong to one of these branches than that it will belong to the main stem. This fact,

however, by no means vitiates the general argument, for it is usually possible to pick out pretty accurately those which come into or near to the direct line, and even the collaterals afford valuable evidence as to the general course of evolution. We may safely say that the palæontological evidence amounts to a clear demonstration of the evolution of the horse from a five-toed ancestor along the lines indicated above.




FIG. 158.—*a*, Fore Foot and *b*, Hind Foot of *Mesohippus celer*, × ½. (From Lull, after Marsh.)

The ancestry of the elephants is less well known than that of the horses, but recent discoveries in the Egyptian Tertiary formations, which we owe especially to the investigations of Dr. Andrews, have done much to elucidate the history of this remarkable group of mammals, and there can now be no doubt as to the main line of evolution which has led up to the existing Proboscidea. In some respects the elephants have remained in a somewhat primitive condition, as is indicated very clearly by the fact that all the digits remain well developed in both fore and hind feet. It is in the structure of the head that they exhibit a high degree of specialization, marked particularly by the elongation of the snout to form a long prehensile trunk, by the enormous development of the occipital region of the skull, by the enlargement of the incisor teeth to form great tusks, by the shortening of the jaws and by the increase in size and complexity and the reduction in number of the cheek teeth. These changes have been accompanied by a huge increase in the size of the entire body, so that most of the elephants are amongst the largest of known land mammals, whether fossil or recent.

Like the horses, the elephants probably originated from that primitive ungulate group, the Condylarthra. The earliest known form exhibiting proboscidean characters is Mœritherium, a tapir-like animal whose remains have been found in the Middle and Upper Eocene deposits of the Egyptian Fayûm. This was a comparatively small creature, about as large as a Newfoundland dog. It probably differed but little from other primitive ungulates, but the skull (Fig. 161, 1) already shows marked proboscidean tendencies. The position of the nasal bones, away back from the tip of the snout, indicates that there was in all likelihood a short proboscis. The occipital region of the skull is beginning to grow up and air cells are beginning to develop in the bones. The second pair of incisor teeth in each jaw are enlarged to form small tusks and the hinder cheek teeth are beginning to show an increase in complexity of structure. The total number of teeth however (36) is only eight short of the full typical mammalian dentition.




FIG. 159.—*a*, Fore Foot and *b*, Hind Foot of *Neohipparion whitneyi*, × ¼. (From Lull.)

The next stage is represented by Palæomastodon (Fig. 161, 2) from the Upper Eocene of the same region, some species of which were little larger than Mœritherium while others attained almost elephantine proportions. In this genus we notice a strong accentuation of the proboscidean characters. The occiput is higher, the nasal opening in the skull further back, the upper tusks better developed, the cheek teeth more complex; while the canines and all the incisors except the tusks in both jaws have disappeared. It will be observed that as yet there is no shortening of the jaws, but, on the contrary, the lower jaw has become

considerably elongated, apparently serving as a support for the lengthening proboscis.

In *Tetrabelodon angustidens*, from European Miocene formations, this elongation of the mandible is much more marked, so that the lower jaw is much longer than the upper one and the short lower tusk comes to project almost as far forward as the long upper one (Fig. 161, 3). From this time onwards, however, the chin shortens, thereby allowing greater flexibility to the proboscis, so that in the lower Pliocene we find *Tetrabelodon longirostris* (Fig. 161, 4) with the lower jaw only a little longer than the upper, leading the way to the mastodons and true elephants (Elephas), which also appeared in Pliocene times and in which the tusks have entirely disappeared from the greatly abbreviated mandibles while the cheek teeth have become enormously enlarged and complicated (Fig. 161, 5).




FIG. 160.—*a*, Fore Foot and *b*, Hind Foot of *Pliohippus pernix*, × ⅛. (From Lull.)

We have here a wonderfully perfect series of connecting links between the most primitive known ungulate mammals and the elephants. Only forms which appear to lie in or near the direct line of descent have been mentioned in the above brief account. Other modifications of the proboscidean type arose as lateral offshoots from this main stem. One of the most remarkable of these is Dinotherium, with its great, downwardly directed lower tusks (Fig. 162), which appeared in Europe in the Pliocene period.

In the case of the Cetacea, a group which includes the whales, porpoises and dolphins, we have as yet only a much more fragmentary pedigree, but still quite sufficient to justify, on the palæontological side, the conclusion, already arrived at on anatomical grounds, that these extremely aberrant forms are the descendants of typical terrestrial mammals which have become re-adapted to an aquatic life and in accordance therewith have re-acquired a superficial resemblance to their much more remote




Fig. 161.—Some Stages in the Evolution of the Skull in the Proboscidea (From British Museum Guide.)

fish-like ancestors.[1] The fore limbs have become converted into paddles while the hind limbs have entirely disappeared externally




FIG. 162.—Skull of *Dinotherium giganteum*, Lower Pliocene, × (From Smith Woodward's "Vertebrate Palæontology," after Kaup.)

(Fig. 163). The tail has become flattened out into a horizontal fin and there is frequently a well developed dorsal fin. The skull




FIG. 163.—The Dolphin, *Delphinus delphis*, × $\frac{1}{18}$. (From British Museum Guide.)

has undergone very curious changes. The brain case is rounded and strongly arched (Fig. 164) and the nasal apertures or blow-holes lie far back, at or near the highest point of the head

[1] Compare Chapter XVII.

(Fig. 103, *b*), while the jaws have become greatly elongated The teeth have in some cases completely disappeared, as in the whale-




FIG. 164.—Skull of the Dolphin, × $\frac{1}{5}$. (From British Museum Guide.)

bone whales (except for fœtal vestiges), while in others they are present in large numbers but have lost the typical mammalian




FIG. 165.—Dorsal and lateral views of the Skull of a primitive Whale, *Prozeuglodon atrox*, × $\frac{1}{13}$. (From British Museum Guide.)

differentiation into incisors, canines, premolars and molars, being represented by a continuous and uniform series, all of which are conical in shape and single-rooted. Such teeth occur in both

jaws of the porpoises and dolphins (Fig. 164) and in the lower jaw only of the sperm whale.

In the extinct shark-toothed Dolphins (Squalodontidæ), whose remains have been found in Miocene formations of Europe and America, the teeth are still differentiated into incisors, canines, premolars and molars, and the molars have double roots and compressed crowns with serrated edges.

Further back, in Eocene times, there existed, widely distributed over the northern hemisphere, a group of still more primitive whale-like animals known as Zeuglodontidæ. In these the seven vertebræ of the neck, which in existing whales are more or less fused together into a solid mass (Fig. 105), are all separate, and the typical dental formula is identical with that of primitive carnivorous land mammals, viz. i $\frac{3}{3}$, c. $\frac{1}{1}$, p.m. $\frac{4}{4}$, m. $\frac{3—2}{3}$.

The genus Prozeuglodon, from the Egyptian Eocene, approaches so closely in the characters of the skull and teeth (Fig. 165) to the primitive carnivores (Creodontia) of about the same period as to leave no reasonable doubt about the derivation of the Cetacea from that group, although it is quite possible that none of the extinct forms so far discovered are actually in the direct line of descent of any of the modern whales.

CHAPTER XXI

Geographical distribution[1]—Areas of distribution—Barriers to migration—Means of dispersal—Changes in the physical conditions of the earth's surface—The evidence afforded by the study of geographical distribution with regard to the theory of organic evolution.

It is hardly necessary to remind the reader that each species of plant or animal, in a state of nature, is more or less sharply restricted to a certain portion of the earth's surface, the entire region over which it may be found, whether sea or land, being termed its area of distribution. Such areas of specific distribution are nearly always continuous, without any considerable gaps or intervals from which the species is entirely absent. This does not, of course, mean that the species necessarily occurs in all parts of its area of distribution at once, but that it is free to range over the whole of it and may accordingly be found in any suitable part of it at any time. It is necessary to introduce some such qualifying word as "suitable" in this connection, because each species is not only restricted in its range to a more or less well-defined geographical area, but can only live continuously in certain portions of that area, to the special conditions of which it is structurally and physiologically adapted and which constitute its habitat. Thus, for example, a fresh-water snail may perhaps range over an entire continent, but it would be useless to look for it except in fresh water. Individuals of a species may pass with more or less freedom, according to the nature of the case, from one habitat to another within the area of distribution, but it is only on rare and exceptional occasions that they are able to transgress the boundaries of the area itself.

True discontinuity in areas of specific distribution, as distinguished from mere discontinuity of habitats, is extremely rare. We have a good example of it, however, in the case of the marsh

[1] The reader is referred to Dr. Wallace's classical volumes on "Island Life" and the "Geographical Distribution of Animals," and to Professor Heilprin's work on the "Distribution of Animals" in the International Scientific Series (Vol. LVIII, 1887), for further information on this subject.

tit (*Parus palustris*), which has two areas of distribution separated from one another by an interval of four thousand miles—in Europe and Asia Minor on the one hand and in Northern China on the other.

The size of the area over which a species may range varies immensely, in some cases comprising an entire continent, or even more, and in others only a few square miles. Thus the leopard ranges over the whole of Africa and most of Southern Asia, while the Tuatara (Fig. 115) is confined to certain small islands off the coast of New Zealand, and certain species of humming birds are said to occur only on the volcanic peak of Chimborazo in the equatorial Andes.

An area of generic distribution is the sum of the areas of distribution of all the species which are comprised within the genus, and thus genera have usually a much wider geographical range than species. Families, again, have a wider range than genera and orders than families, and so on with groups of still higher value. In short, the more comprehensive the group the larger will be its area of distribution, until we find that the sub-kingdoms or phyla are cosmopolitan, ranging more or less over the entire world, wherever a suitable habitat is to be found.

The reason why species are rarely, if ever, cosmopolitan in their distribution is that they are confined within their own limited areas by the existence of physical conditions which constitute what are called barriers to migration. Such barriers either form absolutely insuperable obstacles to the passage of the species in question or they may be surmounted only at rare intervals and by some happy chance.

The nature of the barriers varies, of course, with the species concerned, and what is a barrier to one may be a high road to another. In the case of marine animals the principal barriers are continents and temperature conditions, while the deep sea itself acts as a barrier to the distribution of shore-dwelling or littoral forms. For terrestrial animals the chief barriers are seas, rivers, mountain ranges, deserts and climate generally; for fresh-water animals land and sea. In the case of plants the barriers to migration are very much the same.

It may be laid down as a general law that every organism, whether animal or vegetable, at some period or other of its existence is specially adapted so as to secure dispersal either by its own exertions or by the action of some external agency. By

some means or another it is able, not only to spread itself over its own area of distribution, but also, if occasion offers, to extend that area by surmounting its barriers.

The lower terrestrial plants, such as fungi, mosses and ferns, are dispersed by means of spores, which, protected by special envelopes, may be widely distributed by the wind. In the higher plants the spores, as agents of dispersal, are replaced by seeds, which, usually still within the fruit, may be carried on the wind, floated on rivers or ocean currents, carried about entangled in the hair or feathers of animals, or actually eaten and passed out uninjured in the fæces. A great many seeds and fruits are specially modified in structure to secure their distribution in one or other of these ways, and the study of such adaptations constitutes one of the most interesting chapters in botanical science. We need only refer here to such fruits as the blackberry, whose succulence tempts the birds to eat them and carry the seeds, safely enclosed in their hard protective envelopes, to long distances; the various kinds of burs with their hooks for entanglement in fur and feathers; the winged fruits of the maple, elm and ash, and the thistledown of the thistles, adapted for floating on the wind.

The dispersal of plants is in all cases passive and dependent on external agencies, though sometimes aided by some purely mechanical device in the plant itself; in the case of animals it may take place either passively or actively, by the exertions of the animals themselves.

Beginning with the marine fauna, we find that the larger forms—whales, porpoises, dolphins and fishes—owe their dispersal mainly to their own active powers of locomotion, while the smaller animals, especially the invertebrates, are largely dependent in this respect upon oceanic currents.

Even animals which, like the sponges and corals, are firmly fixed to the sea-bottom in the adult condition, have free-swimming larval forms (Fig. 166) whose own limited powers of locomotion may, under favourable circumstances, be enormously supplemented by the action of currents. Such larval forms, from the point of view of dispersal, play the part of the spores and seeds of plants, and they occur not only in cases where the adult is strictly sedentary in habit but also where its powers of locomotion are limited, as in many worms, snails, crabs (Fig. 130) star-fishes, brittle stars (Fig. 129) and sea-urchins. The

dispersal even of large and active fish, like the mackerel, is largely assisted by the action of currents upon the floating eggs, and this factor must be of still greater importance in the case of the comparatively sluggish bottom dwellers, such as the turbot and sole.

The more superficial waters of the open ocean are densely populated with pelagic animals and plants and with pelagic eggs and larvæ in various stages of development, all drifting more or less helplessly wherever the ocean currents may carry them, for their own powers of locomotion are usually quite insufficient to enable them to pursue an independent course. This floating population is technically spoken of as "plankton" and its investigation, which is of great importance for the solution of practical fishery problems, has lately attracted a great deal of attention.




FIG. 166.—Free-swimming Larva of a Sponge, *Grantia compressa*; highly magnified.

(The larva swims by means of the rapid undulations of the numerous flagella with which it is provided.)

We must therefore regard all the great ocean currents, such as the Gulf Stream, as highways thronged with life of many kinds, including representatives of all the more important groups of marine animals, any one of which may be on its way to found a new colony and establish its own particular species in some region far distant from its original home. Some of the wanderers are only immature forms, belonging partly to shore-dwelling species, others are adult. Almost all exhibit some special adaptation to their pelagic mode of life. The fish eggs may be floated by oil-globules, and the larvæ of the crabs, brittle stars and sea-urchins are provided with defensive spines (Figs. 129, 130); but the most general and characteristic feature of all the pelagic host is transparency, whereby they are rendered inconspicuous and less likely to become the victims of the numerous enemies which feed upon the plankton. Adult jelly-fish, worms, molluscs and crustaceans, and innumerable larval forms, all exhibit this same peculiarity.

The effect of ocean currents upon the distribution of marine

animals is shown in a very interesting manner in the case of the Mediterranean and the Red Sea. In each of these there is a surface current constantly flowing in from the open ocean and bringing in vast numbers of individuals, both larval and adult, which never find their way out again. Hence these almost enclosed seas form a kind of trap for marine animals and we accordingly find them to be inhabited by an exceptionally rich and varied fauna.

The range of marine species, though sometimes very wide, is usually more or less strictly limited, so that the shores of every continent have their own characteristic fauna and flora. This is no doubt partly accounted for by differences in climatic conditions, food supply and so forth, but it is mainly due to the fact that, in spite of the facilities for travel afforded by ocean currents, the dangers incidental to a long voyage from one continent to another are rarely surmounted, at any rate by shore-dwelling organisms. We know that many such forms flourish quite as well in some other part of the world as in their original home if they can once overcome the initial difficulty of migration. Thus the artificial introduction of the American oyster into British seas has accidentally brought with it the introduction of the remarkable limpet-like Crepidula, which attaches itself to the oyster shells and runs riot over the oyster beds on the Essex coast. That such occurrences may occasionally take place in a state of nature, and a species thereby be enabled to extend its area of distribution, there can be no reasonable doubt, for even American turtles have occasionally been carried by the Gulf Stream to the shores of Great Britain.

Amongst the higher forms of non-aquatic animals, and especially birds and mammals, their own powers of locomotion constitute the most important means of dispersal. Even these, however, are frequently transported for long distances by those external agencies which are chiefly responsible for the dispersal of less highly organized forms.

Leaving out of account, for the moment, the action of man, which has brought about immense changes in the geographical distribution of the existing fauna, the chief agents to be noticed in this connection are wind and water.

It is to the action of the wind that large numbers of winged animals—insects, birds and bats—owe the wide distribution which they enjoy. All actively flying land animals are liable to be

carried out to sea in storms, and although the great majority of these will inevitably perish a few will occasionally manage to reach some distant haven where they may succeed in establishing a colony and thus extending the range of the species.

During westerly winds American birds not infrequently make their appearance on various parts of the coast of Europe, while north of the 58th parallel of latitude the polar winds trend in the opposite direction and with them we find a transference of European birds, by way of Iceland and Greenland, to the American continent.[1] During storms, again, European birds are cast upon the Azores, about 1,000 miles from the nearest continental coast, and there is strong reason for believing that the little wax-eye (*Zosterops lateralis*) has been transported in this way from Australia to New Zealand, where it has succeeded in establishing itself.

Water currents may play an important part in the dispersal of two groups of terrestrial animals—those which occasionally swim and those which are liable to be carried away on icebergs or on floating masses of vegetation. Most quadrupeds swim well and even if not habitual swimmers may be forced to take to the water in times of flood. In this way they may cross large rivers and even get carried out to sea and perhaps to some neighbouring island, but they cannot cross large stretches of open ocean, and are accordingly never found, except when introduced by man, on islands far remote from any continent.

In polar regions the floating ice affords a means of dispersal to such animals as wolves and polar bears, while within the tropics floating islands or rafts formed of matted vegetation play the same part. Such islands have been observed floating out to sea from the mouths of large rivers like the Ganges, the Amazon, the Congo and the Orinoco. They serve as a means of transport to many different kinds of terrestrial reptiles, birds and mammals, and countless molluscs, worms and insects, to say nothing of plants.

"If," says Sir Charles Lyell, "the surface of the deep be calm, and the rafts are carried along by a current, or wafted by some slight breath of air fanning the foliage of the green trees, it may arrive, after a passage of several weeks, at the bay of an island into which its plants and animals may be poured out as

[1] Heilprin, *op. cit.*, p. 47.

from an ark, and thus a colony of several hundred new species may at once be naturalized." [1]

As a definite example of this kind of dispersal may be mentioned the fact that in 1827 a large boa constrictor, twisted round the trunk of a tree, was carried by ocean currents from South America to the Island of St. Vincent, where it was destroyed after killing a few sheep.

A current flows from the North Island of New Zealand southwards to Chatham Island, four hundred miles distant from the nearest point on the New Zealand coast. This current carries considerable quantities of New Zealand timber to the island and its existence probably accounts for the fact that the planarian worm, *Geoplana exulans*, has been found both in the North Island of New Zealand and on Chatham Island, but, as yet, nowhere else. The land planarians habitually creep into the crevices of decayed timber, and their eggs are enclosed in tough, horny cocoons which may probably occasionally be transported even over wide stretches of sea.

Small terrestrial animals are, of course, often accidentally dispersed by human agency. Rats, mice and cockroaches have been carried nearly all over the world by ships, and snails, worms and other small creatures may be carried about with timber and earth, especially around the roots of plants. When I was in New Zealand I had some plants sent to me from England in a tightly closed tin box. When they arrived, after a voyage of some five or six weeks, I found an earthworm still alive in the tin. Many invertebrates have doubtless been unknowingly dispersed in this manner and great care has to be taken to make due allowance for such possibilities in studying problems of distribution. In exactly the same sort of way the seeds of many plants are accidentally dispersed over the world in ships' ballast, so that the same common European weeds occur in the neighbourhood of the ports along all the great routes of commerce.

The restrictions placed upon the dispersal of fresh water animals are more severe than in the case of either marine or terrestrial forms. One river system or one lake is separated from another by intervening land or sea which fresh water animals cannot as a rule cross by their own exertions. There are of course exceptions, as in the case of the lampreys and eels,

[1] Lyell's "Principles of Geology," Ed. 5, Vol. III., p. 44.

and other fish which go down to the sea periodically, but for the most part the inhabitants of fresh water are largely dependent upon external agencies for their dispersal. Accordingly we find two groups of such animals, widely contrasted with one another as regards their distribution. Those which do not go down to the sea and which are not likely to be carried about by external agencies, such as most of the fishes, have usually restricted areas of specific distribution, and individual mountain lakes sometimes contain peculiar species of fish which are found nowhere else in




FIG. 167.




FIG. 168.

FIG. 167.—Gemmule or Statoblast of a Fresh Water Polyzoon, *Cristatella mucedo*, × 40. (From Sollas.)

FIG. 168.—Two Gemmules of a Fresh Water Sponge, *Ephydatia* (*Spongilla*) *fluviatilis*, × 60. (From a photograph.)

gem., gemmules; *sp.*, spicules of the parent sponge.

the world. *Galaxias nigothoruk*, for example, is a small fish which occurs abundantly in lake Nigothoruk in Victoria (Australia). This lake is in a very isolated position in a mountainous region and the only outlet is by percolation underground. There appears to be no natural means by which the fish could be transferred to any other locality at the present time, and it is not known to occur elsewhere.

On the other hand many fresh water invertebrates, such as the Polyzoa, hydras and sponges, and above all the microscopic Protozoa, are remarkable for their wide distribution. Identical genera if not identical species of these groups occur almost all over the world, and the reason for this is not far to seek, for all

of them have some special character which enables them to be easily dispersed by external agencies. The fresh water Polyzoa and sponges produce minute buds (statoblasts or gemmules) enclosed in hard protective envelopes (Figs. 167, 168), which are likely to be carried about in the mud on the feet of wading birds and mammals. The embryo of Hydra secretes its own protective envelope (Fig. 59, D—G) within which it passes through a period of rest embedded in the mud; while many of the Protista (*e.g.* Hæmatococcus) are capable of being dried up at some period or other of their life-history and carried about by the wind in the form of dust. Thus a sample of mud, taken from a pond and dried up, may, after an interval of many months, if again placed in water, give rise to an abundant fauna, amongst which even such highly organized forms as Crustacea (*e.g.* Apus and Branchipus, which lay specially protected eggs) will frequently appear.

We must remember that the present distribution of animals and plants is the outcome not only of the existing physical conditions of the earth's surface but also of conditions which obtained in past geological periods. From time to time these conditions undergo great changes, which may concern not only the climate of particular regions or of the entire world, but also the relative distribution of land and sea.

The earth has been subject, at various periods of its history, to climatic changes of two chief kinds, (1) cold or even glacial epochs in temperate regions, and (2) mild or warm epochs in arctic or antarctic regions. Probably alternations of these two extremes have been not infrequent, but the case of which we have most complete knowledge occurred in the Pleistocene period and is usually known as the "Glacial Epoch" *par excellence*.

There is clear evidence that during a portion of the Pleistocene period a very large part of the northern hemisphere, which now enjoys a temperate climate, was covered with perpetual ice and snow and reduced to a condition resembling that of Greenland at the present time. Scandinavia and the whole of Northern Europe were buried beneath the ice-sheet, and the same is true of the northern part of North America.

The glacial epoch in the north must have driven the greater number of the northern plants and animals southwards, causing a keen struggle for existence in which many species were exterminated. Its influence was possibly intensified by the

fact that the glaciation was not continuous but alternated with a succession of warm periods. The southern hemisphere also experienced a glacial epoch during which warm and cold periods alternated, and astronomers hold that the warm periods in one hemisphere coincided with cold ones in the other. It has been calculated that each warm or cold period lasted for about 21,000 years.

Other important changes in climate occurred long before the great glacial epoch. Thus the fossil remains of a luxuriant vegetation in Greenland and other northern localities indicate the occurrence of a mild arctic climate in Miocene times. Such a climate must have favoured migration between the old and new worlds by way of what is now Behring Strait, which may very well have been dry land at the time.

Owing to the gradual loss of the earth's heat by radiation and the consequent shrinkage and crumpling of the solid crust, variations in the level of the land are constantly taking place. Areas which are at present separated by sea may have been connected in former times and *vice versâ*, and there can be no doubt that the distribution of plants and animals has been profoundly influenced in this way. Many cases of discontinuity in distribution may be explained by the former existence of land connections which no longer remain. It is necessary, however, to be extremely careful how we invoke the aid of this principle, which, as an easy way out of difficulties, is apt to lead us into all sorts of unjustifiable speculations.

Those remarkable animals the lemurs, as a group, exhibit a very curious discontinuity in their distribution, occurring in Africa (and especially Madagascar) on the one hand and in Southern Asia on the other. To explain this distribution it has been suggested that in former times a continent—Lemuria—existed in the Indian Ocean. Similarly, and with perhaps greater justification, it is believed by many people that the antarctic continent at one time extended much further north than at the present day, so as to afford, possibly with the aid of a chain of islands and with the co-operation of a mild antarctic climate, a route along which migration might take place between South America and Australasia. In this way may be explained certain remarkable points of agreement between the fauna and flora of Australia and New Zealand and those of South America. The genus Fuchsia, for example, is typically South American,

but one or two species occur in New Zealand; and the same is true of Calceolaria. The evergreen beech forests of New Zealand must be extraordinarily like those which Darwin described in Patagonia. Even the same curious genus of fungus (Cyttaria) is found on the beech trees in South America, New Zealand and Tasmania. A fresh water lamprey, Geotria, also occurs both in New Zealand and South America and similar cases could be quoted from the invertebrate fauna.

It is very doubtful, however, whether such an extensive change in the configuration of the earth's surface as the submergence of an entire continent has ever taken place. According to Dr. Wallace, who is recognized as the greatest authority on the subject of geographical distribution, the existing continents and oceans as a whole are permanent features, although their outlines may be greatly affected by oscillations of the earth's crust.

Perhaps the strongest argument against the former existence of continents where we now have oceans lies in the fact that the average depth of the sea is many times greater than the average height of the land, no less than twelve thousand feet as compared with one thousand, for the great depths of the ocean extend over vast areas while the greatest heights of the land are narrow mountain ranges.

In short, we are only justified in postulating the former existence of land in places where the ocean is comparatively shallow[1], but even this limitation leaves abundant opportunity for changes in the relative distribution of land and sea which would profoundly affect the distribution of plants and animals. The actual occurrence of such changes is abundantly proved by geological evidence and they are known to be going on at the present day in many parts of the world.

There is good reason to believe that the principal groups of terrestrial animals originated in the great northern land masses and that the southern peninsular areas of Africa, Australasia (now, of course, represented by detached islands) and South America have been peopled mainly by successive waves of migration from the north. We find in all these southern areas primitive, ancient forms of life. Marsupials at the present day

[1] This statement may require qualification in view of Wegener's recent theory of the separation of the great land masses by meridional splitting and subsequent drift

are found only in Australasia and America, but the fossil remains of such animals are widely distributed over the northern hemisphere. The Onychophora, again, a small group of extremely primitive arthropods, which until recently were all included by zoologists in the single genus Peripatus (Fig. 169), are almost confined to Australasia, South Africa and South America, in all of which regions they are fairly abundant. It is more reasonable to imagine that the ancestors of the Onychophora migrated from the north, where the group has now become almost extinct, than to invent imaginary continents across which they may have wandered, or even to suppose that they have been so widely distributed as we now find them by some external agency such as floating timber.




FIG. 169.—*Peripatus capensis*, from Cape Colony, × ⅓.

The geographical distribution of plants and animals would be quite inexplicable on the supposition that all species had been independently created and deposited where they now live. It is, however, easy enough to explain it on the theory that the earth has been peopled by the descendants of common ancestors which migrated from place to place as occasion permitted and at the same time underwent modification in many different directions. We may now briefly summarize the principal facts of distribution which justify us in holding this view.

(1) The extent of the area of distribution of any group of animals is directly proportional to its means of dispersal. Thus flying vertebrates are much more widely distributed than quadrupeds. Birds occur abundantly on oceanic islands, but the only mammals which occur there in a state of nature are bats and small forms like rats and mice which may be carried on floating timber. Nevertheless we know that when the larger mammals are transported by man to such localities they flourish exceedingly. Many Protozoa, again, which are readily blown about in the form of dust, are almost cosmopolitan even as regards their species.

(2) The degree of peculiarity of the fauna and flora of any

area is proportional to the length of time for which and the extent to which that area has been isolated from other areas. Thus Australia, which has probably been separated from the Asiatic continent ever since the Cretaceous period, has a most peculiar fauna and flora. We have already referred to the numerous different kinds of marsupials—kangaroos, wombats, phalangers, native bears, native cats and so forth—which have not as yet been supplanted by the more recently developed groups of mammals found in other parts of the world. Australia is also still the home of those most primitive and reptile-like of all the mammals, the Monotremata (Figs. 93, 94). The Australasian forests, again, are composed principally of eucalypts of many different species, which are found nowhere else in the world. In New Zealand, which is even more isolated than Australia, we find no less peculiar inhabitants, including the wonderful tuatara (Fig. 115), one of the oldest surviving types of terrestrial vertebrate, together with the kiwi (Fig. 113) and other remarkable flightless birds.

The reasons why the degree of peculiarity of the fauna and flora of any region is proportional to the degree of geographical isolation are not difficult to find. On the one hand ancient types, such as the tuatara, the monotremes and the marsupials, may be preserved from competition with more modern forms long after they have been exterminated elsewhere. On the other hand, individuals accidentally introduced from distant areas at rare intervals will have few opportunities of breeding with others of the same species, and thus whatever variation occurs amongst them will be less liable to be swamped by intercrossing with the parent form. New races and ultimately new species will thus become established more readily in such areas than elsewhere. This principle of geographical isolation as a factor in the production of new species is of great importance and we shall have to refer to it again in a subsequent chapter.

The zoological or botanical affinities of the inhabitants of any given area, not only with one another but also with those of adjacent areas, are exactly what we should expect in accordance with the views which we are advocating. It is impossible to believe that the existing marsupials were (with the exception of the few American species) all specially created in Australasia when we know perfectly well that marsupials used to exist in Europe in past geological times and can still exist in Europe

when transported there by human agency, and it is equally impossible to believe that such animals as sheep and rabbits, to which the Australian climate appears to be pre-eminently suited, were specially created in Europe and Asia but never in Australia. The existing condition of the Australian fauna is, however, easily explained on the supposition that it was originally derived from Asia at the time when marsupials and monotremes flourished in the north, and that the island continent became separated from the mainland before the more recent mammalian types, constituting the Eutheria, had arisen on the latter. Divergent evolution within the limits of this isolated area is then quite sufficient to account for the immense variety of marsupials occurring there at the present day.

It is very instructive in this connection to contrast the condition of the fauna of a comparatively recently separated continental island, such as Great Britain, which is not far removed from its parent continent, with that of the fauna of a typical oceanic island which has never formed part of a continent at all and is very widely separated from any other land. The native or indigenous population of continental islands always exhibits a close relationship with that of the adjacent mainland, from which it was originally derived and with which it is still able to keep up a certain amount of intercourse. Such an island will contain indigenous quadrupeds, and the great majority of the species of plants and animals found in it will be identical with those of the mainland. True oceanic islands, on the other hand, such as St. Helena and the Sandwich Islands, are peopled entirely by waifs and strays which have gained access to them at rare intervals in one or other of the ways discussed in the earlier part of this chapter. They never contain large quadrupeds and, owing to their more or less complete isolation, the animals which do occur almost always belong to peculiar species found nowhere else in the world.

(3) Palæontological investigations have demonstrated that the present animal population of any tolerably isolated area is closely related to the population of the same area in comparatively recent geological periods. Thus in Australia we not only find that at the present day marsupials are by far the most characteristic features of the fauna, but also that the remains of extinct marsupials, many of which belong to genera and species different from any now living, are very abundant in the tertiary deposits

of the same region. Similarly in South America at the present time the edentates (sloths, armadillos and ant-eaters) form the most characteristic mammalian group, and the tertiary deposits of that country have yielded the remains of a great number of extinct forms belonging to the same order. It would be very difficult to explain these facts on any theory of special creation, but we can easily understand how a group of animals, having once gained a footing in any area and finding itself secure and more or less cut off from communication with other parts of the world, would increase and vary, producing new species and ultimately becoming the dominant group in that particular region.

(4) Cases of discontinuous distribution are readily explicable on the theory of evolution and migration. Either individuals of the species in question have occasionally transgressed the barriers to their dispersal and established new and distant colonies, or possibly a large area of distribution has become broken up into a number of smaller ones by geographical or climatic changes rendering portions of it uninhabitable.

"Thus, for instance," says Romanes, "it is easy to understand that during the last cold epoch the mountain hare would have had a continuous range; but that as the arctic climate gradually receded to polar regions, the species would be able to survive in southern latitudes only on mountain ranges, and thus would become broken up into many discontinuous patches, corresponding with these ranges. In the same way we can explain the occurrence of arctic vegetation on the Alps and Pyrenees—namely, as left behind by the retreat of the arctic climate at the close of the glacial period." [1]

[1] "Darwin and after Darwin," Vol. I., p 209.

*

CHAPTER XXII

Adaptation to environment in animals—Deep sea animals—The colouration of animals—Protective and aggressive resemblances—Warning colours —Mimicry—Epigamic ornamentation.

In the last few chapters we have discussed a number of facts selected from that great and ever increasing mass of evidence which leads us to the inevitable conclusion that the present condition of the fauna and flora of the earth, with their almost endless diversity of animals and plants, is the outcome of a long process of organic evolution. It is desirable at this stage of our inquiry to emphasize the fact that this evolution, in the main, has been of a progressive character, and of such a character, moreover, as to maintain a more or less perfect harmony between the organism and its environment.

Adaptation in bodily organization and in corresponding function, whereby each kind of plant or animal is enabled to meet the constant demands made upon it and maintain its existence in the endless warfare of life, is the great outstanding feature of living things. So universal is this adaptation that we are apt to take it for granted, and any want of it is at once recognized as an exception and an anomaly. Anyone, for example, who watches the slow and clumsy movements of a tortoise cannot fail to be struck with the fact that the limbs of this animal are but ill-suited for purposes of locomotion, but even in this case there is compensation in that the tortoise carries its place of refuge about with it and has therefore little need to hurry itself.

We have seen in an earlier chapter how completely the pentadactyl limbs of air-breathing vertebrates may become modified from their primitive condition in correspondence with changes in the mode of life. The fore limbs, adapted in the first instance for locomotion on land, have become changed in the whales, seals and dugongs into paddles; in the pterodactyls, birds and bats into wings, and in man into organs of prehension.

Indeed, given time enough, the power which an organism possesses of altering its bodily structure in accordance with new demands on the part of the environment seems, as we have already pointed out, to be almost without limits.

This plasticity is illustrated in the most striking manner in cases where the organism has been removed from what may be regarded as the normal environment of the group to which it belongs, and to which the great majority of the group are adapted, and come to live under new and very different conditions. Thus it is with the aquatic and aërial mammals, which, in encroaching upon the domains of the fishes and birds, have, by convergent evolution, come to resemble these in bodily form.




FIG. 170. — Two Deep Sea Sponges, exhibiting the Crinorhiza Form. A. *Cladorhiza longipinna;* B, *Axoniderma mirabile;* nat. size. (After Ridley and Dendy in "Challenger" Reports.)

Wherever we turn we find fresh illustrations of the same principle. At great depths of the ocean the conditions of life are very different from those which obtain in shallow water, and we find the animals which inhabit these abysses modified accordingly. Fig. 170 represents two deep sea sponges obtained by the "Challenger" expedition; *Cladorhiza longipinna* from a depth of 3000 fathoms in the North Pacific and *Axoniderma mirabile* from a depth of 2250 fathoms in the South Pacific. It will be seen at once that the form assumed by these sponges is very unusual and quite unlike that exhibited by their shallow water relatives. The great majority of the members of the group of sponges (the Tetraxonida) to which they belong are indeed by no means remarkable for symmetry of shape, but these two are beautifully symmetrical, their form at once suggesting that of a parachute, with a small conical body fringed by long radiating processes surrounding a central root-like projection. This "Crinorhiza form," as it is termed, is obviously an adaptation which serves

to prevent the sponge from sinking into and being smothered by the soft mud or ooze which covers the bottom of the ocean at very great depths, and it is interesting to observe that species of several distinct though related genera have adopted the same device, thus affording a beautiful example of the phenomenon of convergence. Other sessile deep sea animals have found different means of overcoming the same difficulty, especially in many cases by the development of long stalks.

The absence of light at great ocean depths has led to the acquisition on the part of many of the deep sea fishes of brilliant phosphorescent organs, arranged like little lamps on various parts of the body. In some cases at any rate these serve to attract other animals upon which these fishes prey. Some of them, again, develop long and delicate feelers by aid of which they grope their way about in the dark.

In the brilliantly illuminated surface waters of the ocean conditions are very different, and here we find that the most favourite device for preserving life amidst a host of enemies is transparency, but we have already alluded to this in the preceding chapter and need not dwell upon it further. It is a phenomenon which falls under the head of protective colouration, of which we shall find better instances elsewhere.

The significance of the colouration of animals as a means of adaptation to environment is a subject which has in recent years developed into a special branch of biological science, and which already has a copious literature of its own. Professor Poulton, in his well known work on the Colours of Animals,[1] has suggested an elaborate scheme of colour classification from this point of view. He distinguishes, in the first place, between apatetic (deceitful) colours, sematic (warning and signalling) colours, and epigamic colours (displayed in courtship), all of which afford marvellous instances of more or less highly specialized adaptation. We have not space to follow out the details of this classification but we shall presently refer to examples of all the more important types of colouration included therein.

Every observer of nature must have been struck with the general harmony of colouration which exists between animals and their surroundings. So complete is this harmony that our sense of hearing is frequently a better guide to the whereabouts of an insect, bird or mammal than our sense of sight. I

[1] International Scientific Series, Vol. LXVIII.

remember standing with my gun in the midst of a dense patch of scrub in Australia and hearing the pademelons[1] hopping about all around me. For a long time, however, I could see nothing but the trees. My native guide pointed out where I was to aim, but I only fired at a log from the side of which a pademelon hopped away. Again he pointed, and this time at a small white spot which I could just distinguish amongst the trees. I fired once more, aiming at the white spot, and sure enough a pademelon rolled over. It appeared that I had aimed at the white fur which occurs on the breast of the animal and which to the experienced eye of the native told all that he needed to know. It is often supposed that conspicuous patches of this kind serve as recognition marks between individuals of the same species, but it may be questioned how far the advantage of being recognized by a friend compensates for a disturbance of the colour harmony which reveals an animal to its enemies.




FIG. 171.—Larva of the Brimstone Moth (*Rumia crataegata*) resting upon a Hawthorn twig; nat.size. (From Poulton)

The type of colouration which aids in the concealment of an animal is termed, by Professor Poulton, cryptic. It belongs, of course, to the apatetic group. Concealment may be desirable either as a means of escape from enemies or for the purpose of ambuscading prey, or possibly for both. In the former case we may speak of it as protective resemblance (procryptic colouration), in the latter as aggressive resemblance (anticryptic colouration).

Protective resemblance is often of a very highly specialized character, and may be due as much to adaptation in actual form as to adaptation in colour; frequently these two factors unite in producing the result, and a third may be added, viz., adaptation in habit or instinct. In the common stick caterpillars of the geometer moths we see all three factors co-operating. In colour and shape these caterpillars precisely resemble small twigs. They move about with a characteristic looping action amongst the leaves or branches of the bushes which they frequent, but when at rest they stiffen themselves up and stand out from the branch at the exact angle of a twig, and

[1] A small species of kangaroo.

in this condition it is extremely difficult to detect them. Professor Poulton remarks :—

"These caterpillars are extremely common, and between two and three hundred species are found in this country; but the great majority are rarely seen because of their perfect resemblance to the twigs of the plants upon which they feed."

As will be seen from the illustration (Fig. 171), which represents the larva of the brimstone moth upon its food plant, the hawthorn, the caterpillar is enabled to maintain its position for a long period by attaching its head to a twig by means of a silken thread.




FIG. 172.—A Green Leaf Insect (*Pulchriphyllium crurifolium*, ♀), from Ceylon; × ½. (From a photograph.)

Numerous moths so closely resemble in the colour and pattern of the upper surface of their wings the objects upon which they rest in the daytime, such as the bark of trees, that they are almost invisible, but perhaps the most perfect examples of protective resemblance are met with in the wonderful leaf insects. Fig. 172 represents an orthopterous insect, *Pulchriphyllium crurifolium*, from Ceylon. The whole insect is of a bright leaf-green colour,[1] and not only are the wings shaped and veined so as to resemble leaves, but even the body and legs exhibit leaf-like outgrowths.

In the well known Indian leaf butterfly, Kallima (Fig. 173), the resemblance to a leaf is only seen when the insect comes to rest with its wings folded together above the body so as to expose their under surfaces. It is a dry, dead leaf which is imitated this time, and stalk and midrib, veins and colour markings, even down to such minutiæ as rust spots, are perfectly represented.

The Mantidæ or praying insects feed upon flies, &c., which they capture with marvellous dexterity with their serrated claws. In some species the uniform green colouration doubtless serves, not only to protect them from their own enemies, but also to

[1] Sometimes brown, resembling a dead leaf.

prevent them from being seen by their victims before they have come within range. Other species exhibit even more wonderful adaptations both in form and colour. Thus the South African *Harpax tricolor* sits amongst the pink and white flowers of the heath, which are imitated by similarly coloured outgrowths of the insect, and there awaits the approach of its unsuspecting victims; while in Mozambique the terrible *Idolum diabolicum*




FIG. 173.—An Indian Leaf Butterfly (*Kallima inachis*); A., with wings expanded; B., with wings folded; × ⅔. (From a photograph.)

simulates, both in form and colour, a large flower, and thereby deceives and attracts other insects in search of honey.

It is no doubt amongst the almost innumerable species of the great group Insecta that cases of highly specialized adaptation for purposes of concealment or deception are most frequently met with. They also occur, however, and by no means uncommonly, in other groups of the animal kingdom. A familiar instance is afforded by the common British spider crab, now known as *Macropodia rostrata*,[1] of which excellent illustrations (under the name *Cancer Phalangium*) were given by

[1] I am indebted to my friend, the Rev. T. R. R. Stebbing, F.R.S., for information as to the correct nomenclature, &c., of this species.

Dr. Macculloch, in the Transactions of the Linnean Society, as far back as 1801. I am enabled by the courtesy of the Council of the Society to reproduce here, on a reduced scale, Dr. Macculloch's original plate (Fig. 174). The crab actually breaks off fronds of seaweed and attaches them to the long hairs of its body, thus disguising itself so effectually as to be quite unrecognizable except by careful examination. Dr. Macculloch was of opinion




FIG. 174.—Reduced Facsimile of Dr. Macculloch's Plate of *Macropodia rostrata*, in the Transactions of the Linnean Society. On the left is shown a plant of the seaweed in which the crab dresses itself up; on the right the crab without the seaweed, and at the bottom the crab dressed up.

that this dressing up of the crab in seaweed was an artifice which assisted it in capturing its food (anticryptic), but it is much more likely that it is protective (procryptic). The late Professor Bell has told us how the slow and sluggish habits of the crab render it an easy prey to fishes, and the stomach of a thornback ray has been found entirely filled with them, so that there appears to be ample reason for them to seek concealment.

In the case of Macropodia the adaptation for concealment shows itself as an inherited habit or instinct more than in any modification of bodily structure, but such an instinct is probably

itself the effect of some structural modification, however impossible to detect, in nervous tissue. In the Australian *Phyllopteryx eques*, a fish which is closely related to the curious sea-horse (Hippocampus) of our own coasts, we get precisely the same idea, so to speak, carried out in a different manner. Both Hippocampus and Phyllopteryx live amongst seaweed, to which they attach themselves by means of their curious prehensile tails. Hippocampus (Fig. 175) exhibits no special resemblance



FIG. 175.




FIG. 176.

FIG. 175.—A Sea-horse (*Hippocampus antiquorum*), × ⅔. (From a photograph.)

FIG. 176.—*Phyllopteryx eques*, attached to seaweed. (From Günther's "Study of Fishes.")

to its surroundings, but in Phyllopteryx (Fig. 176) the body is covered with cutaneous outgrowths which float out in the water like fronds of seaweed and doubtless effect a most satisfactory disguise. This is certainly a less troublesome plan than that of dressing up in clothing borrowed from the outside world.

The well known colour changes of the chamæleon and of various flat fishes, not to mention numerous other instances which might be cited from different groups of the animal kingdom, are due to a complex apparatus, controlled by the nervous

system, whose function it is to bring about a varying adaptation for concealment under varying conditions of the environment. How perfect the adaptation may be will be realized by all who have ever observed with what marvellous accuracy the colour markings of a turbot in an aquarium are made to match the sand or gravel upon which it is lying.

In striking contrast with the cryptic colouration by which an animal seeks, as it were, to avoid observation, are those numerous cases in which self-advertisement appears to be the main object in view. The British army, which only in recent years has learnt the advantages of khaki clothing when in the field, still exhibits some of the most startling instances of conspicuous colouration met with anywhere in the animal kingdom, though whether these examples should be classed under the head of warning colours, or regarded as belonging to the epigamic category, is perhaps an open question. We must, however, confine our attention in this place to a few examples of warning colours met with amongst the lower animals.

We have seen that both warning and signalling colours, or recognition marks, are spoken of as sematic. The former are further distinguished as aposematic and the latter as episematic. Aposematic colours are exhibited by many animals which possess some special means of defence and find it advantageous to advertize the fact. Wasps and hornets, with their conspicuous orange- and black-banded bodies, are excellent examples. Such animals do not seek to conceal themselves but rely upon their warning colours to remind their enemies that they had better leave them alone. It is not enough that they should possess the power of making themselves disagreeable; the fact must be clearly recognized, otherwise they would be constantly exposed to experimental attack, and suffer injuries for which any damage which they might inflict upon their pursuers would be but a poor consolation. Orange, red and black, owing to their great conspicuousness, especially when associated with one another, are the colours most frequently met with in this connection, and we find them, not only in noxious insects, but in various vertebrates, such as certain poisonous reptiles, fire-toads and salamanders. The Gila monster (*Heloderma suspectum*), of Mexico and Arizona, is the only known poisonous lizard, and is conspicuously coloured in tints of blackish brown, yellow and orange, while other members of the same group are usually

coloured so as to harmonize more or less perfectly with their surroundings.

If it is advantageous for a noxious species to advertize its true character, it is no less so for an innocuous one to advertize a false character, and gain credit for some power of making itself objectionable which it does not really possess. The practice of bluffing is by no means an exclusively human institution. Thus we find many insects, which in themselves are quite inoffensive, taking on the characteristic warning colouration of dangerous species. The drone-fly mimics the bee, and though they belong to widely different orders of insects, the one having only two wings and the other four, the resemblance is so close as to have given rise, as we saw in an earlier chapter, to the ancient belief in the spontaneous generation of bees from the carcases of oxen (on which, of course, drone-flies had deposited their eggs).




FIG. 177. — A., a clear-winged Moth (*Sesia crabroniformis*) mimicking B., a Hornet (*Vespa crabro*); both × ⅔. (From a photograph.)

Most moths, as is well known, have opaque wings, covered with microscopic scales, but in the clear-winged moths (Fig. 177, A) the wings have partially lost their scales and become transparent, and this anomalous feature, combined with the colouration of the body, enables these perfectly harmless insects to mimic the dangerous hornets (Fig. 177, B). Even a harmless snake may mimic the warning colouration of a venomous species, and thus secure for itself the respect which is properly due only to the latter.

It is not necessary that an animal should be capable of inflicting serious injury upon its enemies when attacked for it to secure immunity from pursuit as soon as recognized. Many butterflies and other insects, which are probably merely distasteful or nauseous (or perhaps actually unwholesome) to birds, exhibit aposematic or warning colouration. Amongst these we find curious associations known as synaposematic groups, the members of which, belonging to distinct species and often by no means closely related to one another, seem to have combined

together to share the expenses of a common advertisement and thereby reduce the cost to each. Young birds have to learn by experience which insects are good to eat and which are not. In making their experiments no doubt they themselves suffer, but the subjects of the experiment are probably actually killed. Obviously, then, if one experiment can be made to serve for a number of different species of insects there will be a corresponding reduction in the death-rate, and hence it is that we




FIG. 178.—A Synaposematic Group of South American Lepidoptera, all × ½. (From a photograph.)

A, *Tithorea harmonia*; B, *Heliconius ethilla*; C, *Perrhybris* (*Mylothris*) *malenka*. ♂; D, *Dismorphia praxinöe*, ♀; E, *Pericopis angulosa*.

find these groups of species all adopting the same type of warning colouration, and thus coming to resemble one another very closely, although perhaps belonging to totally distinct families.

We may illustrate this somewhat complex phenomenon by reference to certain South American Lepidoptera which take part in the formation of such a synaposematic group. In Fig. 178 A, B and D represent butterflies belonging to three distinct families, while E is a moth, as may be seen at once by its thick body and the absence of terminal knobs on the antennæ.

All of these, in common with numerous other species which inhabit the same area, have adopted the same characteristic scheme of warning colouration, wherein the prevailing tints are black and orange.

In such a synaposematic group, or mimicry ring, it is usually possible to distinguish between certain species which seem to have led the way in the development of the warning colouration, and others which seem to have followed their example. In the particular case under notice the original "models" belong to the group Ithomiinæ, of which *Tithorea harmonia* (Fig. 178, A) is a representative. These are probably the most distasteful members of the combination to birds. They have been imitated by Heliconinæ, such as *Heliconius ethilla* (Fig. 178, B), Pierinæ ("whites"), such as *Dismorphia praxinöe* (Fig. 178, D), and Hypsidæ (a family of moths), as exemplified by *Pericopis angulosa* (Fig. 178, E), all of which may be regarded as mimics of the Ithomiinæ.


The case of the pierine mimics is particularly instructive, and shows very clearly that these forms really imitate other species, for the female is commonly a far more perfect mimic than the male, which often departs little, if at all, from the typical colouration of the group to which it belongs. Fig. 178, C represents a male pierine, *Perrhybris* (*Mylothris*) *malenka*, which is at once recognizable from its colouration as a "white," although even here, curiously enough, there is a faint trace of the warning colouration on the under surface of the hind wings.[1] The female of the same species has the warning colouration well developed, as it is in both male and female of *Dismorphia praxinöe*.

So different are the males and females of some of these mimicking species that it would be difficult to believe, were it not for breeding experiments, that they are really specifically identical. The explanation of the difference is doubtless to be found in the fact that it is much more important, from the point of view of the species, that the females, heavily laden with the eggs upon which the existence of future generations depends, should be able to warn off the birds, than that the males should do so, for the latter, having once accomplished the fertilization of the eggs, are of no further value to the race.


[1] Doubtless inherited incompletely from female ancestors, as in the case of the vestigial nipples of man.

When an unquestionably harmless species mimics the warning colours of an undoubtedly noxious one, the case is sometimes spoken of as one of "Batesian" mimicry, after the distinguished naturalist, H. W. Bates, who added so much to our knowledge of the subject. In the case of a synaposematic group, or mimicry ring, however, it is often impossible to say whether any particular species is edible or not, and it may very well be that in some cases all are more or less inedible, though undoubtedly some, which are presumably the less objectionable forms, mimic others, which are presumably the more objectionable. This kind of mimicry, resulting in the development of a warning colouration common to a number of species, is sometimes distinguished as "Müllerian" mimicry, after the naturalist Fritz Müller, who first suggested the correct interpretation of the phenomenon.


Perhaps the most remarkable case of mimicry known amongst butterflies is that of certain species of Papilio found in Africa and Madagascar, which have formed the subject of exhaustive study by Trimen, Poulton and others. In Madagascar occurs *Papilio meriones*, a non-mimetic species in which the male and female (Fig. 179, A) closely resemble one another and both possess the "tail" on the hind wing which is such a characteristic feature of the genus. We may take it, then, that this is a primitive form. On the continent of Africa is found the widespread *Papilio dardanus*, with several subspecies. In these subspecies the male (Fig. 179, B_1) retains the ancestral form, but in most of them the female is mimetic; it has lost the Papilio tail and closely mimics, both in shape and colour markings, some one or another of various species of butterflies belonging to different families which occur in the same region. Nor is this all, for the female is likewise polymorphic, and different individuals of the same subspecies resemble widely different models. Thus the subspecies *merope* is known to have three forms of female, a *hippocoon* form (Fig. 179, B_2) which mimics the danaine butterfly *Amauris niavius* (Fig. 179, C), a *trophonius* form (Fig. 179, B_3) which mimics another danaine, *Limnas chrysippus* (Fig. 179, D), and a *planemoides* form which mimics the acræine, *Planema poggei*. Our illustrations, which are reproduced from Mr. Trimen's original memoir, give a good idea of the form and pattern of some of these insects, but they lack the beautiful colouring of the original figures, which is



A. Papilio meriones ♀



B1. Papilio dardanus (*merope*) ♂




C. Amauris niavius



B2. Papilio dardanus (*merope*) ♀
(*hippocoon form*)



D. Limnas chrysippus.



B3. Papilio dardanus (*merope*) ♀
(*trophonius form*)

FIG. 179.—Mimicry in Butterflies. (After Trimen, from coloured plates in the Transactions of the Linnean Society, First Series, Vol. XXVI.)

necessary in order to give a true idea of the close resemblance between mimics and models.

Breeding experiments carried out by Mr. G. F. Leigh with the subspecies *cenea* of *Papilio dardanus* have shown that the eggs laid by one and the same butterfly may give rise to at least




FIG. 180.—Male and Female of an Australian Lyre-Bird (*Menura superba*). (Photographed from specimens in the British Museum, Natural History.)

three different forms of mimetic female, as well as, of course, the male.

It is obvious that we have here the very opposite of a synaposematic group, for, instead of concentrating upon a single warning pattern, different individuals, even of the same species, adopt totally different patterns in imitation of totally different models. This case still requires a great deal of explanation, but concerning the facts there can be no doubt.

Frequenters of any good museum of natural history will be familiar with plenty of examples of epigamic ornamentation. The highly elaborate and gorgeous plumage of many male birds, such as the peacock, the Argus pheasant, the Australian lyre-bird (Fig. 180) and numerous species of humming birds, to say nothing of less conspicuous examples, affords the best illustration of this phenomenon. In all such cases the function of the ornamentation appears to be to gratify the æsthetic sense of the female during the period of courtship, and render her amenable to the attentions of her mate. There is no doubt that in many cases the cock bird deliberately displays himself to the best advantage before the admiring eyes of the hen, who is credited with a no less deliberate choice of the partner who most nearly approaches her ideal standard of beauty. In all these cases the plumage of the female is comparatively sombre and uninteresting. An elaborate and gaudy tail would be a disadvantage during the lengthy period of incubation, when it is desirable, both for her own sake and that of her offspring, that the female should be as inconspicuous as possible. Thus it is the male bird that has had to adapt his clothing to the requirements of the female, and she herself is unable to follow the fashions which she imposes upon her mate.

It is obvious that no theory of evolution can be regarded as satisfactory which does not offer some explanation of the origin of such highly specialized and precise adaptations as those which we have been considering in this chapter, and it was in order to emphasize the need for such explanation that we have laid so much stress upon them. We shall see in our next chapter that no less remarkable and precise adaptations for special purposes are also met with in the vegetable kingdom, and shall then pass on to seek the necessary explanation.

CHAPTER XXIII

Adaptation to the environment in plants—Alpine plants, desert plants and lianes—The modification of flowers in relation to insect-fertilization.

In plants no less than in animals we find adaptation to the conditions under which they have to live to be the most striking feature of their organization. We have already noticed, in dealing with the phenomenon of convergent evolution, the manner in which Alpine plants of many kinds tend to assume the compact cushion-like form which seems best suited to withstand the rigorous climate to which they are exposed. Wherever a plant may be found growing in a state of nature the character of the environment is sure to be reflected more or less obviously in its structure and habit. We see this equally clearly in the water-storing plants of desert regions—the cacti of America or the aloes of Africa—with their succulent stems or leaves and other structural modifications which enable them to withstand the effect of long-continued drought, and in the climbing lianes of tropical forests, whose one object in life appears to be to reach some elevation where they can expose their foliage to the light and air. Just as we find those air-breathing mammals which have taken to an aquatic life adopting the form and habits of fishes as being best suited to their changed conditions, so in the tropical forests of Queensland we find palms, members of a group which elsewhere are types of self-supporting independence, adopting the form and habit of climbing plants as the only means of coping with the exigencies of the situation.

If the adaptation amongst plants usually appears less remarkable than is often the case in animals, it is because the relations of a plant to its environment are usually less complex than those of an animal. The greater activity of animals is associated with the development of highly specialized organs of locomotion, sense-organs and nervous system, all of which are alike subject to adaptation. Plants afford much more restricted opportunities for the effects of the environment to show themselves, and it is in their relations with animals, or to speak more

accurately, in those organs which are immediately concerned with these relations, that adaptation becomes most complex and precise.

Even amongst animals, however, it would be difficult to find better illustrations of accurate adaptation to highly specialized conditions of the environment than those which we see in the wonderful structural modifications whereby the majority of flowers are adapted for pollination by insect agency. This process of pollination is commonly referred to as the "fertilization" of the flower, although, as we have seen in a previous chapter, the real act of fertilization takes place inside the so-called ovule and consists in the conjugation of the male and female gametes, the sperm-cells and egg-cells.

The great majority of flowers produce both pollen and ovules, containing respectively the male and female gametes; in other words they are hermaphrodite. It is obvious that in such cases we have two possibilities with regard to fertilization, for the flower may either be fertilized by its own pollen or by that of some other flower. It may be either "self-fertilized" or "cross-fertilized," and the cross-fertilization may be effected either by pollen from another flower of the same plant or by pollen from a different plant of the same kind, the latter being the more advantageous.

It seems at first sight a strange thing that when a flower is capable of self-fertilization such a roundabout and apparently unnecessary proceeding as cross-fertilization should ever take place at all. It has been shown, however, that cross-fertilization, if not absolutely necessary, is at any rate of very great advantage to the plant, or rather to the species, in which it occurs.

Charles Darwin experimented for eleven years on this subject, and proved conclusively that cross-fertilization yields better results than self-fertilization, both as regards the number of seeds produced and also as regards the quality of the offspring. It would be impossible to give an adequate account of his work in this place, but we may briefly notice one series of experiments and refer for the remainder to his classical volume on the "Cross and Self Fertilization of Plants." He started with the "Convolvulus major" (*Ipomœa purpurea*), the flowers of which are hermaphrodite and may be either cross- or self-fertilized in a state of nature. It is an easy matter, by artificially conveying

the pollen on the tip of a feather, to bring about the fertilization in any way which may be desired. Ten flowers were thus self-fertilized with their own pollen, while ten others were cross-fertilized with pollen from a distinct plant. The crossed and self-fertilized seeds thus obtained were carefully cultivated under exactly the same conditions, and it was found that the plants raised from cross-fertilized seeds were taller than those raised from self-fertilized seeds in the proportion of 100 to 76.

The same experiment was repeated with ten successive generations of the same plants, and always with the same result in favour of the cross-fertilized individuals. Moreover, it was proved at the same time that the fertility of the plants produced by cross-fertilization was greatly superior to that of the self-fertilized plants, a much larger quantity of seed being produced.

These results, taken in conjunction with many others of the same kind, clearly proved the advantages of cross-fertilization. To quote Darwin's own words :—

"It has been shown . . . . . that the offspring from the union of two distinct individuals, especially if their progenitors have been subjected to very different conditions, have an immense advantage in height, weight, constitutional vigour, and fertility over the self-fertilized offspring from one of the same parents."

The theoretical explanation of this advantage is not an easy matter, but is probably to be sought in the admixture of two distinct series of hereditary tendencies in the offspring of a cross.

In a state of nature it is a very rare thing for plants to be exclusively self-fertilized, for, although self-fertilization may take place in some cases to a very large extent, and although some flowers are so constructed that self-fertilization alone is possible, yet there is nearly always at least an occasional cross by the introduction of pollen from a different plant.

Considering the advantages which arise from cross-fertilization, we need not be surprised to find that a very large number of flowers are provided with special adaptations whereby these advantages may be secured to them. We may notice first certain contrivances by means of which self-fertilization is more or less effectually prevented and the injurious effects of perpetual close inbreeding thereby avoided. These contrivances may be classed under three principal heads.

(1) *Separation of the Sexes.*—In many flowers we find that only stamens or pistil are developed, never both, so that we get distinct male and female flowers, which renders self-fertilization absolutely impossible, though it does not necessarily prevent fertilization by pollen from other flowers on the same plant.

(2) *Physiological Self-sterility.*—In some flowers, to quote the words of Darwin, "the ovules absolutely refuse to be fertilized by pollen from the same plant, but can be fertilized by pollen from any other individual of the same species." Again, in a large number of plants, although self-fertilization *may* take place, yet, if the pollen from another individual be brought to the stigma, it takes precedence, so to speak, of the flower's own pollen and renders the latter ineffectual; it is said to be prepotent.

(3) *Dichogamy.*—In a large number of flowers, in which both male and female organs are present, the stamens and pistil become mature at different times, so that self-fertilization cannot possibly take place and, physiologically speaking, the flowers are unisexual. Usually in these cases the pollen ripens and is all shed before the stigma is ready to receive it. The flower is then termed protandrous, as for example in the common pink (Dianthus). More rarely the stigma ripens and withers before the pollen is ripe, and such species are termed protogynous, as in the fig-wort (*Scrophularia nodosa*).

Of course it would be worse than useless to prevent self-fertilization unless some means were provided at the same time for securing cross-fertilization. We saw in Chapter VIII that the principal agents in conveying pollen from one flower to another are wind and insects, and that flowers are accordingly distinguished as anemophilous or wind-fertilized and entomophilous or insect-fertilized. The fact that the former are usually very small and inconspicuous, as for example in the grasses, while the latter are large and brightly coloured, affords strong presumptive evidence that entomophilous flowers have become modified in relation to the insects which visit them in search of food or shelter. A great many different kinds of insects have this habit, bees, flies, butterflies, moths and even beetles; while in South America some of the humming birds in like manner play the part of pollen carriers.

We are in the habit of regarding bees as the most important insects concerned in the cross-fertilization of flowers, and in

countries where they are plentiful this is perhaps the case. They visit the flowers in order to collect both honey and pollen, to be used as food for themselves and their offspring. The honey is usually found at the bottom of a long narrow tube formed by the lower part of the corolla, so that in order to reach it the bee requires a correspondingly long and narrow instrument. This is provided in the shape of a very complicated proboscis (Fig. 181), formed by modification, especially elongation, of certain of the appendages surrounding the mouth, which in more primitive insects, like the cockroach, remain short and simple. When not in use the proboscis is neatly folded away beneath the head, but when a flower is visited it is unfolded and inserted into the tube containing the honey, which is then drawn up into the bee's stomach by means of a special sucking apparatus. In butterflies and moths also a somewhat similar proboscis is used for the same purpose, but it differs so much from that of the bee in details of structure as to indicate that it has been independently evolved from the primitive mouth parts of some remote insect ancestor. In both cases the mouth appendages have become specially adapted for the very special purpose of sucking honey, and the necessity for the fulfilment of the same function has led, as usual, to a superficial resemblance between the two types of proboscis. We have here, of course, another illustration of convergent evolution.




FIG. 181.—Head of a Bee, showing the complex Proboscis formed from modified Mouth Parts. (From Weismann's "Evolution Theory.")

at, antennæ; *Au*, large compound eye; *au*, ocellus; *la.*, labrum or upper lip; *le*, outer division of second maxilla (paraglossa); *li*, ligule or tongue, formed by fusion of inner divisions of second maxillæ; *md*, mandible; mx^1, mx^2, first and second maxillæ; *pl*, labial palp; *p.m.*, maxillary palp.

For collecting pollen the bees make use of their legs, on which special collecting brushes and baskets are formed by the stiff hairs. The pollen is first moistened with honey to make it stick together, and then picked up on the collecting brushes, placed in the baskets on the hind legs and carried to the hive or nest.

Insects commonly visit a large number of flowers of the same kind in rapid succession, and, whether they intentionally collect pollen for their own purposes or not, it is evident that, after each visit to a flower containing ripe pollen grains, they will unintentionally carry away some of these, accidentally attached to various parts of the body. The pollen which is thus unconsciously carried away is equally unconsciously deposited on the stigma of the next flower visited, and thus cross-fertilization is effected. It may, of course, happen sometimes that the pollen is deposited on the wrong kind of flower, but that is of no consequence, for pollen is, with rare exceptions, quite incapable of fertilizing flowers of any but its own particular species.

Under these circumstances it will obviously be advantageous to a plant to make its flowers as attractive to insects as possible, and, just as it is desirable for a nauseous insect to inform the birds by means of warning colours of the fact of its unpalatability, so also is it desirable for flowers which have honey to offer in exchange for the service of pollination to make that fact known to their insect visitors by means of brilliant colours and strong scents. There can be no reasonable doubt that the colours serve to attract the insects and to enable them to recognize the flowers which they prefer, and that the same is true of the scents is very clearly indicated by the fact that certain flowers, such as various species of Arum and related genera, which are fertilized by carrion-loving flies, have managed to perfume themselves in accordance with the tastes of their visitors.

It is also desirable to ensure, by means of mechanical arrangements, that the insects shall not get their honey without paying for it, that is to say, without effecting fertilization, and this end is usually secured by concealing the honey at the bottom of a long tube, in such a manner that the insect must brush against the stamens and stigma before it can reach it. Sometimes, however, the insects become a little too clever for the flower and steal the honey by biting a hole through the bottom of the tube without ever touching the stamens or stigma at all. In this way the red clover flowers are often robbed of their honey by the humble

bee, *Bombus terrestris*, thus affording an example of imperfect adaptation.

We may now consider a few definite examples of the manner in which flowers may be specially adapted in structure so as to secure the advantages of cross-fertilization by insect agency.

If a number of plants of the common primrose, the oxlip, the cowslip or the polyanthus (species of the genus Primula) be examined carefully, it will be seen that in each case two quite different forms of flower occur. In other words the flower is dimorphic. The two forms are known to gardeners as "pin-eyed" and "thrum-eyed" respectively. In the pin-eyed flowers (Fig. 182, A) the style (g) is comparatively long and the stigma (n) appears as a round knob, like the head of a pin, in the centre of the flower, at the entrance to the long tube formed by the lower part of the corolla. The anthers (a) lie much lower down in the tube, so that they are invisible until the flower is cut open. In the thrum-eyed flowers (B) the positions of the stigma and anthers are reversed; the style being much shorter the stigma lies only half way up the tube, while the anthers appear in the centre of the flower, in the mouth of the tube. The two kinds of flower are always found on separate plants, and the long-styled and short-styled plants are said to occur in about equal numbers under natural conditions. The pollen grains also differ in the two kinds of flower, those of the thrum-eyed being larger than those of the pin-eyed and of somewhat different shape. This particular kind of dimorphism, which is sometimes known as heterostylism, is extremely characteristic of the genus Primula, and it has recently been shown that the distinguishing features of the two forms are inherited in a Mendelian fashion.




FIG. 182.—Heterostyled Flowers of the Oxlip (*Primula elatior*) in longitudinal section. (From Vines' "Botany.")

A, long-styled; B, short-styled flower. a, anthers; c, corolla; f, ovary; g, style; k calyx; n, stigma.

The flowers of the primulas are fertilized by the agency of insects such as humble bees, and Darwin found that if insects were carefully excluded by covering the flowers with a net, little

or no seed was produced. In order to reach the honey, which is secreted at the bottom of the long tube of the corolla, the bee thrusts its proboscis down the tube and in so doing brushes past the stigma and the anthers. If a pin-eyed flower be visited the pollen from the anthers is deposited comparatively low down on the proboscis. If a thrum-eyed flower be visited the pollen is deposited much higher up, in accordance with the more elevated position of the anthers. Thus the bees carry about two different kinds of pollen on two different parts of the proboscis, a fact which has been established by microscopic examination of the proboscis itself with the attached pollen.

If it be remembered that in the two different kinds of flower the relative positions of the anthers and stigma are reversed, it will be obvious that when a bee sucks honey from a long-styled flower the stigma will be touched and pollinated by that part of the proboscis which touches the anthers of a short-styled flower, and *vice versâ*. Hence it follows that pin-eyed flowers will be fertilized by pollen from thrum-eyed, and thrum-eyed flowers by pollen from pin-eyed.

Here, then, we have a very precise adaptation for a special kind of cross-fertilization, and Darwin further proved by his experiments that this is the only kind of fertilization which results in complete fertility. Cross-fertilization in these plants is, however, *possible* in no less than four distinct ways:—(1) A pin-eyed flower may be fertilized by pollen from another pin-eyed; (2) a thrum-eyed flower may be fertilized by pollen from another thrum-eyed; (3) a pin-eyed flower may be fertilized by pollen from a thrum-eyed; (4) a thrum-eyed flower may be fertilized by pollen from a pin-eyed. The first two methods have been termed by Darwin "illegitimate unions" and they result in incomplete fertility; the last two have been termed "legitimate" and result in complete fertility.

The benefit derived from the existence of the two kinds of flower lies in the intercrossing, not merely of two distinct flowers, but of two distinct plants, for it will be remembered that each plant bears only one kind of flower. Self-fertilization is not absolutely prevented in this case, for the anthers and stigma are mature at the same time in the same flower, but it is not likely to take place, and if it does it results in incomplete fertility and weakly offspring. But even if pollen should accidentally find its way to a stigma of its own plant it need not necessarily

prevent cross-fertilization, for foreign pollen will be prepotent even if deposited on the stigma some time afterwards.

"To test this belief," Darwin observes, "I placed on several stigmas of a long-styled cowslip plenty of pollen from the same plant, and after twenty-four hours added some from a short-styled dark-red polyanthus, which is a variety of the cowslip. From the flowers thus treated, thirty seedlings were raised, and all these, without exception, bore reddish flowers, so that the effect of pollen from the same form, though placed on the stigmas twenty-four hours previously, was quite destroyed by that of pollen from a plant belonging to the other form."




FIG. 183.—Flower of *Salvia pratensis*. (From Weismann's "Evolution Theory," after H. Müller.)

gr' immature stigma; *gr''*, mature stigma; *st'*, anther-lobe concealed in the "helmet"; *st''*, anther-lobes lowered; *U*, lower lip of corolla.

The flowers of the common sage, and of other species of the genus Salvia (Fig. 183), afford a no less striking example of profound structural modification in adaptation to the visits of insects. These flowers are protandrous, the stamens maturing and shedding their pollen before the stigma is ready to receive it, so that self-fertilization is absolutely prevented. Moreover, the stigma in young flowers (Fig. 183, *gr'*) lies in such a position that it will not be touched by visiting insects, which crawl right under it in order to reach the honey at the bottom of the corolla-tube. In older flowers the style elongates and curves downwards, so that the stigma (Fig. 183, *gr''*) comes to lie in the mouth of the corolla-tube and must be brushed against by insects in search of honey.

The most remarkable feature of the flower, however, is a special mechanical contrivance for placing the pollen on the back of any insect which attempts to suck honey from it in its young or male condition. There are only two fully developed stamens, and these are most curiously modified in structure. Each anther

consists as usual of two anther-lobes united together by a connective; but the connective is very greatly elongated, so that the anther-lobes are widely separated from one another instead of lying close together at the top of the filament. The anther-lobe at one end of each connective is imperfect and produces little or no pollen; the other is fully developed. The connective is attached to the top of the very short filament by a movable joint, so that it can be swung freely up and down in a vertical plane. It has a long limb which curves upwards inside the "helmet" of the corolla and terminates in the perfect anther-lobe, and a short one which bears the imperfect lobe, as shown in the figure. The two stamens lie side by side in the flower and the imperfect anther-lobes are held downwards in the mouth of the corolla-tube, exactly in the path of a visiting insect. The perfect anther-lobes, on the other hand, are, at first, held up well above the level of the insect's back (Fig. 183, *st'*).

When a large insect, such as a bee, visits the flower, it alights upon the large lower lip (*U*), which, as in so many other flowers, affords a convenient platform and has doubtless been specially adapted to that end. The head of the insect is then thrust into the corolla-tube and pushes against the two imperfect anther-lobes. The connectives turn on their pivots like a see-saw and the two ripe anther-lobes (*st''*) are clapped down on the back of the insect and dust it with pollen. This happens when the insect visits a young flower. When an older flower, in the female condition, is visited, the pollen from the back of the insect is deposited on the mature stigma (*gr''*), which now hangs directly in front of the entrance to the corolla-tube.

It is, however, in the highly specialized order Orchidaceæ that we find perhaps the most remarkable contrivances for ensuring cross-fertilization that are to be met with in the vegetable kingdom. Many of these have been described and illustrated by Darwin in his well-known work on the "Fertilization of Orchids."

In the common early orchis of Europe (*Orchis mascula*, Fig. 184) there are three sepals and three petals, and both sepals and petals are brightly coloured. The lower petal is very large and in front forms a tongue-like projection termed the labellum (*v*), which serves as a landing platform, while behind it is produced backwards into a hollow spur or nectary (*sp*, *n*) in which honey is secreted. The reproductive organs lie just above and partly in front of the entrance to the nectary, so that an insect, in

poking its proboscis down to get at the honey, cannot fail to touch them. Both male and female organs are very much modified in structure, and united together to form the column (*C*). There are three stigmas. Of these, however, only two (*B*, *na*) are functional, and they lie at the back of the entrance to the nectary. The third is specially modified to form a remarkable organ known as the rostellum (*B*, *C*, *r*), which projects above the




FIG. 184.—Adaptation in the Flower of *Orchis mascula* in relation to Insect-Fertilization. (From Weismann's "Evolution Theory.")

A, side view of flower; *B*, front view; *C*, vertical section through the column; *D*, pollinia removed on the point of a pencil and still standing erect; *E*, the same later on bent forwards.

ei, entrance to nectary; *n*, nectary; *na*, stigmatic surface; *p*, pollinia; *r*, rostellum *Sm*, honey guide; *sp*, spur; *st*. ovary (twisted); *U*, lower lip of flower (labellum).

other two in front of the mouth of the nectary. This rostellum, or beak, consists of an exceedingly sticky body covered over by a thin, membranous cap. The cap is so delicately adjusted that the slightest touch is sufficient to push it down and expose the sticky mass beneath, and it is so elastic that when the pressure is removed it springs back into its original position and again covers up the sticky substance.

There is only one perfect anther, consisting of two sacs which stand up above and behind the rostellum. Each sac contains a single coherent mass of pollen grains instead of the usual loose,

powdery pollen. Each mass of pollen grains, or pollinium (*B*, *C*, *p*), is a pear-shaped body provided with a short stalk or caudicle. The stalk is continued downwards into the rostellum as shown in *C*, where it ends in a membranous disc attached to the sticky substance. When the pollen is ripe the pollinia are exposed by rupture of the sacs in which they lie, so that in the mature flower they are only attached by means of their stalks or caudicles, loosely fixed by the sticky substance of the rostellum.

If we take any slender object, such as a pencil point, and poke it gently into the mouth of the nectary, we shall find on withdrawing it again that it will bring with it either one or both of the pollinia, attached to it by sticky cement. The pencil has, of course, touched the rostellum and pushed down the little cap which covers it. The sticky substance of the rostellum, thus exposed, has cemented on to the pencil the disc at the lower end of the caudicle, and thus the pollinium itself, or both of them, is pulled bodily out with the pencil. The cement rapidly hardens on exposure to the air.

When first attached to the pencil the pollinium is in a nearly upright position (*D*), so that if the pencil were inserted into another flower it would simply go back into its old place, without touching the stigma and of course, therefore, without effecting fertilization. After being exposed to the air for a short time, however, the disc by which the pollinium is attached to the pencil begins to contract, and in such a manner that the pollinium is pulled down until it comes to project straight forwards (*E*). If *now* the pencil be inserted into a flower it will be found that the pollinium exactly strikes against one of the stigmas and dusts it with pollen.

In the economy of nature the proboscis of some insect takes the place of our experimental pencil. Bees and moths have frequently been observed with the pollinia of various species of Orchis attached to them; indeed Darwin figures one instance in which no less than fourteen pollinia are attached to the proboscis of a moth. Every time such an insect visits a flower in search of honey it will effect cross-fertilization by pushing the pollinia which it brings with it against the stigmas, and may perhaps carry off another pollinium into the bargain.

In this case one can hardly fail to be astonished at the number and complexity of the adaptations which have arisen in the flower for the purpose of ensuring cross-fertilization. There is

the conspicuous colour of the sepals and petals, which serves as an advertisement; the formation of the long spur or nectary, with its secreted honey; the great development of the labellum to serve as a landing place, marked with the "honey-guide" (*Sm*) to point out the way to the visitor; the secretion of sticky cement by the rostellum; the formation of an elastic cap to keep the cement from being dried up before it is wanted; the agglutination of the pollen into solid masses, which serve to fertilize a large number of flowers in succession, losing a few grains at each contact; the remarkable form of these pollinia, with their adhesive discs and their peculiar relation to the sticky substance on the rostellum; and, lastly, the wonderful mechanism by means of which the pollinia become bent downwards after their removal, so as exactly to adjust them for contact with the stigma of another flower!

In some species of plants certain parts of the flower are highly sensitive and respond to the slightest touch by a sudden and vigorous movement, going off, so to speak, like a spring trap or a hair trigger. This is well exemplified in a New Zealand orchid, *Pterostylis trullifolia*, as described by Mr. Cheeseman. In this flower the lower petal, or labellum, is highly sensitive, and when an insect alights upon it springs up and imprisons the visitor in a cage. The parts of the flower are so arranged that the insect can only escape by crawling through a narrow passage, and in such a manner that it must carry away the pollinia and also leave on the stigma some of any pollen which it may chance to bring with it.

A still more remarkable orchid, *Catasetum*, actually throws the pollinia at its insect visitors as soon as they touch the flower, and the tiny projectiles attach themselves to the intruder's head. Darwin has described how, on one occasion, when he experimentally irritated this flower, the pollinium was thrown for a distance of nearly three feet, when it stuck on to a window pane.

The presence of irritable structures which aid in cross-fertilization by insect agency is, however, by no means confined to orchids. *Candollea* (*Stylidium*) *graminifolia* is a common Australian wild flower belonging to a totally different order, the Candolleaceæ. It is found growing on open heaths and sends up tall stems from the midst of a tuft of long, grass-like leaves, each stem bearing a large number of rather small pink flowers

along its length. There are five petals, but only four are fully developed, and these spread themselves out in the form of a cross around the mouth of the tube in which the honey is secreted. The anthers and stigma are borne on the end of a long slender column which springs from the middle of the flower. Close to its base the column is bent downwards at a sharp angle so that it hangs out at one side of the flower, between two of the fully developed petals and resting upon the aborted petal as on a cushion. Near its apex the column is again bent at a sharp angle, this time upwards. The flowers are protandrous, the anthers becoming mature and shedding their pollen before the stigma is fully developed.

An insect, visiting the flower and poking its proboscis down the tube of the corolla in search of honey, must touch the column at the first bend. This is the irritable spot, and no sooner is it touched than the column springs over to the other side of the flower and brings the anthers or stigma, as the case may be, down on the back of its visitor. In this way pollen is deposited upon or removed from the insect's back and cross-fertilization is effected. One of the most curious things about this case is that the column loses its irritability at nightfall and refuses to jump, however much you may tickle it.

The few examples of entomophilous flowers which we have now studied must suffice to give some idea of how wonderfully minute and perfect may be the adaptation of plants to highly specialized environmental conditions. The dominating factor of the environment here is, of course, the presence of insects, which can be pressed into service as pollen carriers, and it is obviously in relation to the requirements and tastes of these insects that the various adaptations which we have been describing have arisen. There can be little doubt that the insects select for their visits those flowers which please them best and which are most readily recognizable as the bearers of the coveted honey.

Although, as we have previously pointed out, some carrion-feeding flies prefer scents which are repulsive to ourselves, yet the vast majority of insect-fertilized flowers have scents and colours which we appreciate perhaps no less than the insects for whose gratification they primarily exist. As we shall see later on, these scents and colours, though now in many cases improved by human selection, doubtless arose in the first instance in response to insect selection. If we pursue this line of thought a

little further, there seems good reason to suspect that man, who appeared upon the scene at a very much later date and whose ideas of what is beautiful are doubtless largely derived from the contemplation of flowers, may owe much of his æsthetic development to the fact that he has been educated by flower-loving insects.

*

PART V.—FACTORS OF ORGANIC EVOLUTION

CHAPTER XXIV

Views of Buffon, Erasmus Darwin and Lamarck.

We shall have occasion to point out in a subsequent chapter that many organisms exhibit characters which it is extremely difficult, if not impossible, to bring into any direct relationship with the environment, but this fact does not invalidate the generalization that the most striking feature of all living things is adaptation to the conditions under which they have to carry on their existence. In seeking for an explanation of the means whereby organic evolution has been effected, this fact must constantly be borne in mind, and, as we have already said, no theory can be considered adequate which does not take fully into account the phenomena of adaptation, and offer some reasonable explanation of the wonderful harmony which exists between living things and their surroundings.

It is well known that the doctrine of organic evolution is no new thing, but can be traced back even to the ancient Greek philosophers. In the middle ages such ideas were thrust into the background, along with other fruits of Greek and Roman intellectual activity, and to a large extent supplanted by the teachings of dogmatic theology. With the revival of scientific inquiry, however, the theory of organic evolution, as opposed to the doctrine of special creation and the immutability of species, again began to occupy a prominent place in the minds of thinking men, and a brief consideration of the views of some of the chief philosophical biologists of the last two centuries will perhaps form the most fitting introduction to this part of our subject.

The celebrated French naturalist, Buffon (1707—1788), who held the post of Superintendent of the Jardin des Plantes and, in conjunction with his colleagues, published a large number of volumes of Natural History, was one of those who had at any

rate strong leanings towards the theory of organic evolution, although, unfortunately, he seems to have found it very difficult to give a frank expression to his views. The following translated extracts will serve to illustrate his position.

Speaking of the arbitrary character of our systems of classification he observes:—

"But Nature proceeds by unrecognized gradations and consequently she cannot lend herself completely to these divisions, since she passes from one species to another species, and often from one genus to another genus, by imperceptible shades: so that we find a great number of intermediate species and objects which we do not know where to place, and which necessarily upset the plan of the general system."[1]

Buffon certainly appears in this passage as no believer in the immutability of species, and amongst the causes which bring about their modification he attributes great importance to the action of climate:—

"If we again consider each species in different climates, we shall find obvious varieties both as regards size and form; all are influenced more or less strongly by the climate. These changes only take place slowly and imperceptibly; the great workman of Nature is Time: he walks always with even strides, uniform and regular, he does nothing by leaps; but by degrees, by gradations, by succession, he does everything; and these changes, at first imperceptible, little by little become evident, and express themselves at length in results about which we cannot be mistaken."[2]

In dealing with the animals of the old and the new worlds, and after speaking of the extinction of the mammoth, he says:—

"This species was certainly the foremost, the largest and the strongest of all the quadrupeds: inasmuch as it has disappeared, how many other smaller ones, weaker and less remarkable, have had to succumb also, without having left us either witness or evidence of their past existence? How many other species, having become modified in their nature, that is to say, perfected or degraded by the great vicissitudes of land and sea, by the neglect or the culture of Nature, by the long influence of a climate become contrary or favourable, are no longer the same that they formerly were? And, moreover, the quadrupeds are, next to man, the beings whose nature is the most fixed and whose form is the most constant: that of the birds and of the fishes varies

[1] Buffon, "Histoire Naturelle," Tom. I, p. 13.
[2] *Op. cit.*, Tom. VI, pp. 59, 60.

more; that of the insects still more, and if we descend to the plants, which we must not exclude from animated nature, we shall be surprised at the promptitude with which the species vary, and at the facility with which they change their nature while taking on new forms.

"It would not be impossible then, that, even without reversing the order of Nature, all these animals of the new world may have been originally the same as those of the old, from which they may have been formerly derived; one might say that having been separated subsequently by immense seas or impassable lands, they would, in the course of time, have received all the impressions, suffered all the effects, of a climate itself altered in character by the same causes which brought about the separation; that in consequence they would in time have become dwarfed, changed their nature, &c. But that should not prevent us from regarding them to-day as animals of different species: whatever may be the cause of this difference, whether it has been produced by time, climate and country, or whether it be of the same date as the creation, it is none the less real. Nature, I admit, is in a continual state of flux; but it is enough for man to seize her as she is in his own time, and to glance backwards and forwards in endeavouring to gain some glimpse of what she may have been in former times and of what she may become in the future."[1]

This passage also seems to be a sufficiently clear declaration in favour of the theory of organic evolution and the action of the environment in modifying species. Buffon, however, by no means confined himself to the consideration of climate as a factor in the production of such modifications. The following quotation shows that he also realized the importance of the principles of use and disuse and the inheritance of acquired characters, which were destined to take such a prominent place in the subsequent writings of Lamarck:—

"The llama, which, like the camel, passes its life in bearing burdens and only rests by lying down upon its breast, has similar callosities which are perpetuated in the same way by generation. The baboons and the apes, whose most usual attitude, whether awake or asleep, is sitting, have also callosities beneath the region of the buttocks, and this callous skin has even become adherent to the bones against which it is continually pressed by the weight of the body; but these callosities of the baboons and apes are dry and healthy, because they do not arise from the constraint of trammels or of the weight of a foreign burden, and because they

[1] *Op. cit.*, Tom. IX, pp. 126, 127.

are merely the effects of the natural habits of the animal, which remains seated more willingly and for a longer time than in any other posture: it is the same with these callosities of the apes as with the double sole of skin which we carry beneath our feet; this sole is a natural callosity which our constant habit of walking or resting upright renders more or less thick, or more or less hard, according to the amount of friction to which the soles of our feet are exposed." [1]

It has been maintained that Buffon not only anticipated Lamarck's views as to the influence of the environment and the principle of use and disuse, but also those of Malthus and Charles Darwin with regard to the importance of the struggle for existence and the process of natural selection. That some such ideas were present in his mind seems sufficiently clear from the following passages. After speaking of the invasions of the Huns and Goths and other peoples he continues:—

"These great events, these conspicuous epochs in the history of the human race, are, however, only trifling vicissitudes in the ordinary course of living nature; it is in general always constant, always the same; its movement, always regular, turns on two fixed pivots, the one the unlimited fecundity given to all species, the other the innumerable obstacles which reduce the product of this fecundity to a fixed quantity and at all times leave only approximately the same number of individuals in each species." [2]

. . . . . .

"The causes of destruction, of annihilation and sterility follow immediately upon those of excessive multiplication; and, independently of contagion, the necessary consequence of too great an accumulation of any living matter in one place, there are in each species special causes of death and destruction, which we shall indicate in the sequel and which alone suffice to compensate for the excess of former generations." [3]

. . . . . .

"The least perfect species, the most delicate, the most heavily burdened, the least active, the least well armed, &c., have already disappeared or will disappear." [4]

Even if, on the strength of this last passage, however, we can claim that Buffon had conceived the idea of the survival of the

[1] *Op. cit.*, Tom. XIV, pp. 325, 326.
[2] *Op. cit.*, Tom. VI, p. 248.
[3] *Ibid.*, p. 251.
[4] I translate this passage, which I have not found in the original, from a quotation given by Osborn in his interesting work "From the Greeks to Darwin" (Columbia University Biological Series). The student should refer to this work for the history of the theory of evolution.

fittest, the mere question of priority is a matter of small moment. As a matter of fact it is now well known that this idea is very much older than Buffon, and can be traced back, as Osborn remarks, "to Empedocles, six centuries before Christ." [1]

Osborn also points out that:—

"Buffon's ideas regarding the physical basis of heredity are very similar to those of Democritus, and certainly contain the basis of the conception of the Pangenesis theory of Darwin, for he supposes that the elements of the germ-cells were gathered from all parts of the body." [2]

So far we have presented the views of Buffon as those of a thoroughgoing evolutionist. He had, however, apparently another side to his mind, which is extremely difficult to understand in the author of the foregoing passages. In the fourth volume of his Natural History, after discussing the possible modification of species, he continues:—

"But no, it is certain, by revelation, that all animals have participated equally in the grace of creation, that the two first of each species and of all the species came forth complete from the hands of the Creator; and we must believe that they were then much the same as they are now represented to us by their descendants." [3]

The doctrine of special creation could hardly be more clearly expressed.

Of course it is possible, as Samuel Butler suggests in his interesting discussion of Buffon in "Evolution Old and New," that such passages as this may be ironical, but it seems more likely that Buffon vacillated between what was then regarded as religious orthodoxy and the more rational views which he knew so well how to express. Indeed, Butler himself remarks, *àpropos* of another passage:—

"This is Buffon's way. Whenever he has shown us clearly what we ought to think, he stops short suddenly on religious grounds." [4]

[1] *Op. cit.*, p. 117.
[2] *Ibid.*, p. 135.
[3] "Histoire Naturelle," Tom. IV, p. 383.
[4] "Evolution Old and New" (New Issue, London, A. & C. Fifield), p. 115. This work contains numerous passages translated from Buffon and Lamarck, and I have found it of great use as a guide to the more salient passages in the voluminous writings of the former. I have, however, in all cases made fresh translations from the French.

Buffon's inability to reconcile the logical consequences of his own inductions with his religious convictions is perhaps nowhere better illustrated than in the attitude which he adopted with regard to the position of man in the animal kingdom. Such an experienced observer as he was could not fail to realize the close agreement in structure between man and the higher apes: —

"We shall see, in the history of the orang utan that, were we to pay attention only to the form, we might equally well look upon this animal either as the highest of the apes or as the lowest of mankind; because, with the exception of the soul, he lacks nothing of all that we possess, and because he differs less from man in bodily structure than he differs from other animals to which the name of ape has been given." [1]

. . . . . .

"I admit that, if one should judge only by form, the ape species might be taken for a variety of the human species: the Creator did not think fit to make for the human body a model absolutely different from that of the animal; He has included his form, like that of all the animals, in one general plan; but at the same time that He bestowed upon him this ape-like material form, He penetrated this animal body with His divine breath." [2]

The ape, on the other hand, is a mere animal, and

"in spite of his resemblance to man, far from being the second in our species, he is not the first in the order of animals, since he is not the most intelligent." [3]

There can be no doubt that the views of Erasmus Darwin (1731—1802) were largely influenced by the writings of Buffon, to which he repeatedly refers. Darwin's "Zoonomia" was published in 1794,[4] but, perhaps because it was mainly a medical work, it received but little attention from professional naturalists. The section dealing with "Generation" contains his views on evolution. A few quotations will suffice to illustrate these:—

"Owing to the imperfection of language the offspring is termed a *new* animal, but is in truth a branch or elongation of the parent; since a part of the embryon-animal is, or was, a part of the parent; and therefore in strict language it cannot be said to

[1] "Histoire Naturelle," Tom. XIV, p. 30. The name "orang utan" was applied by Buffon to the chimpanzee.
[2] *Ibid.*, p. 32.
[3] *Ibid.*, p. 37.
[4] My quotations are taken from an edition published by B. Dugdale at Dublin in 1800.

be entirely *new* at the time of its production; and therefore it may retain some of the habits of the parent-system."

Here we have clearly expressed the idea of continuity which plays such an important part in modern theories of heredity. Erasmus Darwin was, however, a "Spermatist," that is to say he believed

"that the embryon is produced solely by the male, and that the female supplies it with a proper nidus, with sustenance, and with oxygenation; and that the idea of the semen of the male constituting only a stimulus to the egg of the female, exciting it into life, (as held by some philosophers) has no support from experiment or analogy."

It must be remembered that he wrote in the days before the cell theory had shed its illuminating rays over the science of embryology:—

"I conceive," says he, "the primordium, or rudiment of the embryon, as secreted from the blood of the parent, to consist of a simple filament as a muscular fibre,"

but this filament was not necessarily thread-like in form, for he adds:—

"I suppose this living filament, of whatever form it may be, whether sphere, cube, or cylinder, to be endued with the capability of being excited into action by certain kinds of stimulus."

It thus absorbs nutriment and becomes organized by "accretion of parts," and this leads to the development of new kinds of "irritability." According to this view the appearance of a new organ precedes its use:—

"the lungs must be previously formed before their exertions to obtain fresh air can exist."

. . . . . .

"From hence I conclude, that with the acquisition of new parts, new sensations, and new desires, as well as new powers, are produced; and this by accretion to the old ones, and not by distention of them."

But the exercise of these new powers in turn gives rise to the development of more new parts, which

"are formed by the irritations and sensations, and consequent exertions of the parts previously existing, and to which the new parts are to be attached."

. . . . . .

"From this account of reproduction it appears, that all animals have a similar origin, viz. from a single living filament; and

that the difference of their forms and qualities has arisen only from the different irritabilities and sensibilities, or voluntarities, or associabilities, of this original living filament; and perhaps in some degree from the different forms of the particles of the fluids, by which it has been at first stimulated into activity."

. . . . . .

"From their first rudiment, or primordium, to the termination of their lives, all animals undergo perpetual transformations; which are in part produced by their own exertions in consequence of their desires and aversions, of their pleasures and their pains, or of irritations, or of associations; and many of these acquired forms or propensities are transmitted to their posterity."

Dr. Darwin thus passes from the discussion of what is now termed the ontogeny or development of the individual to that of the phylogeny or development of the race. From consideration of the former he endeavoured to gain some insight into the latter, and it may be fairly claimed that he thus anticipated what is known in modern biology as the Recapitulation Hypothesis:—

"From thus meditating on the great similarity of the structure of the warm-blooded animals, and at the same time of the great changes they undergo both before and after their nativity; and by considering in how minute a portion of time many of the changes of animals above described have been produced; would it be too bold to imagine, that in the great length of time, since the earth began to exist, perhaps millions of ages before the commencement of the history of mankind, would it be too bold to imagine, that all warm-blooded animals have arisen from one living filament, which the great First Cause endued with animality, with the power of acquiring new parts, attended with new propensities, directed by irritations, sensations, volitions and associations; and thus possessing the faculty of continuing to improve by its own inherent activity, and of delivering down those improvements by generation to its posterity, world without end!"

Erasmus Darwin was perfectly familiar with the idea of adaptation, as manifested, for example, in the colours of animals:—

"The colours of many animals seem adapted to their purposes of concealing themselves either to avoid danger, or to spring upon their prey. Thus the snake and wild cat, and leopard, are so coloured as to resemble dark leaves and their lighter interstices; birds resemble the colour of the brown ground, or the green

hedges, which they frequent; and moths and butterflies are coloured like the flowers which they rob of their honey."

. . . . . .

"A proboscis of admirable structure has been acquired by the bee, the moth, and the humming bird, for the purpose of plundering the nectaries of flowers. All which seem to have been formed by the original living filament, excited into action by the necessities of the creatures, which possess them, and on which their existence depends."

In the following sentences we have at any rate a very close approach to the idea of natural selection which forms the key-note of the evolutionary theory as advocated by the illustrious grandson of the writer:—

"A great want of one part of the animal world has consisted in the desire of the exclusive possession of the females; and these have acquired weapons to combat each other for this purpose. . . . So the horns of the stag are sharp to offend his adversary, but are branched for the purpose of parrying or receiving the thrusts of horns similar to his own, and have therefore been formed for the purpose of combating other stags for the exclusive possession of the females; who are observed, like the ladies in the times of chivalry, to attend the car of the victor."

. . . . . .

"The final cause[1] of this contest amongst the males seems to be, that the strongest and most active animal should propagate the species, which should thence become improved."

Here the principle of selection seems to be clearly enough recognized, at any rate that form thereof which Charles Darwin afterwards distinguished as sexual selection.

The great French philosophical biologist,[2] Jean Baptiste Pierre Antoine de Monet, Chevalier de Lamarck, was born in 1744 and died in 1829. His most celebrated work, the "Philosophie Zoologique," which contains the fullest expression of his mature views on the theory of organic evolution, was published in 1809, but these views appear to have been first announced to the world in the opening lecture of the Course of Zoology given at the Natural History Museum in Paris in 1800,

[1] *Cf.* Aristotle:—"The final cause, that for the sake of which a thing exists" (De Generatione Animalium, Book I, 715[a], Clarendon Press Trans.).

[2] Lamarck first proposed the term Biology for the Science of Living Things.

and published in the following year in the form of a preface to the "Système des Animaux sans Vertèbres."[1]

It seems impossible to doubt that Lamarck, like Erasmus Darwin, was largely influenced in his views by the writings of his great compatriot Buffon, with whom he was on terms of personal friendship, and to whom he refers in his published work. Whether or not he was acquainted with the works of Erasmus Darwin will probably never be known, but it is evident that both drew part at any rate of their inspiration from the same source. Owing largely to his official position as Professor of Invertebrate Zoology in the National Museum, Lamarck was able to bring forward a very imposing array of facts in support of his opinions, and though these opinions were but the natural development of those enunciated by his predecessors, he was able to place the theory of organic evolution on a much firmer and broader basis than it had previously enjoyed. He also doubtless derived great advantage from the fact that he was an experienced botanist as well as a zoologist, having published many important botanical works before he turned his attention more particularly to the zoological aspect of biology.

During the earlier part of his life Lamarck appears to have accepted the still prevalent doctrine as to the immutability of species, and it is perhaps significant that his conversion to evolutionary views seems to have followed very rapidly upon the extension of his investigations from the vegetable to the animal kingdom.

In the "Philosophie Zoologique" he maintains that the first living things arose by a process of spontaneous generation, which may still take place, and that from the starting points thus provided the entire animal and vegetable kingdoms as they now exist have arisen as the result of orderly and progressive evolution.

He devotes a large amount of space to the question of classification and the conception of species, and arrives at the following conclusions, which are, on the whole, in singularly close agreement with those of modern biologists:—

"But these classifications, of which several have been so happily imagined by naturalists, and the divisions and sub-divisions

[1] *Vide* Packard's "Lamarck, the Founder of Evolution, his Life and Work" (Longmans, Green & Co., 1901). This most interesting work contains translations of portions of Lamarck's writings, and has for the first time made the work of the great French philosopher available to the general reader in England and America. I have, however, thought it desirable to give fresh translations from the original French. An English translation of the "Philosophie Zoologique," by Hugh Elliot, has since been published by Messrs. Macmillan & Co., Ltd. (London, 1914).

which they present, are entirely artificial contrivances. Nothing of all that, I repeat, occurs in nature, in spite of the foundation which appears to be given to them by certain portions of the natural series which are known to us, and which have the appearance of being isolated. We may be certain that amongst her productions, nature has really formed neither classes, nor orders, nor families, nor genera, nor constant species, but only individuals which succeed one another and which resemble those which produced them. Now these individuals belong to infinitely diversified races, which shade off under all forms and in all degrees of organization, and each of which maintains itself without change so long as no cause of change acts upon it."[1]

. . . . . .

"The name *species* has been given to every collection of similar individuals which have been produced by other individuals like themselves.

"This definition is exact; for every individual that enjoys life always resembles very closely that or those from which it sprang. But to this definition has been added the supposition that the individuals which make up a species never vary in their specific character, and that consequently the *species* has an absolute constancy in nature.

"It is exactly this supposition that I propose to combat, because the clear evidence obtained by observation shews that it is unfounded.

"The supposition, almost universally admitted, that living bodies form *species* constantly distinguished by invariable characters, and that the existence of these species is as old as that of nature herself, was established at a time when observations were insufficient, and when the natural sciences were still almost non-existent. It is always contradicted in the eyes of those who have seen much, who have for a long time followed nature, and who have profitably consulted the great and rich collections of our *Museum*."[2]

After speaking of the doctrine of special creation Lamarck continues:—

"Without doubt, nothing exists except by the will of the sublime Author of all things. But can we assign to Him laws in the execution of His will, and fix the method which He has followed in this respect? Has not His infinite power been able to create an *order of things* which should give existence

[1] "Philosophie Zoologique," Tom. I, pp. 21, 22.
[2] *Op. cit.*, Tom. I, pp. 54, 55.

successively to everything that we see, as to everything which exists and which is unknown to us?

"Assuredly, whatever may have been His will, the immensity of His power is always the same; and in whatever manner this supreme will may have been executed, nothing can diminish its grandeur."[1]

Lamarck seems to have been the first to insist upon the branching character of evolutionary series; after speaking of such series he goes on:—

"I do not wish to say thereby that existing animals form a very simple series, everywhere equally graduated; but I say that they form a branching series, irregularly graduated, and which has no discontinuity in its parts, or which, at least, has not always had, if it be true that, in consequence of some species having been lost, such discontinuity occurs anywhere. It results from this that the *species* which terminate each branch of the general series are connected, at least on one side, with other neighbouring species which shade into them."[2]

Like Buffon, he lays great stress upon the action of the environment in modifying organisms:—

"Many facts teach us that in proportion as the individuals of one of our species change their situation, their climate, their manner of living or their habits, they thereby receive influences which little by little change the consistency and the proportions of their parts, their form, their faculties, even their organization; so that everything in them participates, in the course of time, in the transformations which they experience.

"In the same climate, very different situations and exposures at first cause the individuals exposed thereto simply to vary; but, in the course of time, the continual difference in situation of the individuals of which I am speaking, which live and reproduce themselves successively in the same circumstances, causes in them differences which become, in some way, essential to their existence; so that, after many generations have succeeded one another, these individuals, which belonged originally to another *species*, find themselves in the end transformed into a new *species*, distinct from the other.

"For example, if the seeds of a grass, or of any other plant natural to a damp meadow, be transported by any chance, first to the slope of a neighbouring hill, where the soil, although more elevated, is still sufficiently cool to permit of the plant maintaining itself, and if afterwards, after having lived there and

[1] *Op. cit.*, Tom I, pp. 56, 57.
[2] *Ibid.*, p. 59.

reproduced itself many times, it reaches, by slow degrees, the dry and almost arid soil of a mountainous region; if the plant succeeds in living there, and perpetuates itself for a succession of generations, it will then become so changed that the botanists who come across it will make of it a distinct species." [1]

As Lamarck's views have so frequently been misrepresented it is incumbent upon us to make ourselves thoroughly acquainted with what he really meant by the action of the environment, and on this point, fortunately, he is very precise:—

"Here it becomes necessary for me to explain the meaning which I attach to these expressions: *The environment (les circonstances) influences the form and organization of animals*, or in other words, as it becomes very different it changes, in course of time, the form and organization themselves by proportional modifications.

"Certainly, if people took these expressions literally they would attribute to me an error; for, whatever the environment may be, it does not directly effect any modification whatever in the form and organization of animals.

"But great changes in the environment lead, in the case of animals, to great changes in their requirements (besoins), and such changes in their requirements lead necessarily to actions. Now, if the new requirements become constant or very lasting, the animals then adopt new *habits*, which are as lasting as the requirements which have called them forth. . . .

"Now, if a novel environment, having become permanent for a race of animals, has given to these animals new *habits*, or in other words has led them to new actions which have become habitual, there will have resulted therefrom the use of some particular part [of the body] in preference to some other, and in certain cases the complete disuse of some part which has become useless.

"None of these statements should be considered as hypothetical or as the expression of individual opinion; they are, on the contrary, truths which need only attention and the observation of facts to render them evident.

"We shall see immediately, by the citation of known facts which attest it, on the one hand that new requirements having made some part necessary, have really, by a series of efforts, caused this part to arise, and that afterwards its continued employment has little by little strengthened it, developed it, and in the end considerably enlarged it; on the other hand, we shall see that, in certain cases, the novel environment and new requirements having rendered some part quite useless, the

[1] *Op. cit.*, Tom. I, pp. 62, 63.

complete want of employment of this part has caused it to gradually cease from developing like the other parts of the animal; that it has become reduced and attenuated little by little, and that at length, when this want of employment has been complete during a long period, the part in question has in the end disappeared. All this is positive; I propose to give the most convincing proofs of it.

"In plants, where there are no actions, and consequently no *habits* properly so-called, great changes in the environment have none the less led to great differences in the development of their parts; in such a way that these differences have caused certain of them to appear and develop, while they have caused many others to dwindle away and disappear. But here everything is effected by changes which take place in the nutrition of the plant, in its absorptions and transpirations, in the amount of heat, light, air and moisture, which it then habitually receives; finally, in the superiority which certain of the various vital movements may acquire over others."[1]

Like his predecessors, and like those who followed him, Lamarck adduces in support of these views the remarkable modifications which have taken place in animals and plants under the influence of domestication:—

"That which nature does with the aid of much time, we do every day by suddenly changing, in relation to some living plant, the conditions under which it and all the individuals of its species, have existed.

"All botanists know that the plants which they transport from their native place in order to cultivate them in gardens, undergo, little by little, changes which, in the end, make them unrecognizable. . . .

"Is not the cultivated wheat (*Triticum sativum*) a plant brought by man to the condition in which we now actually see it? Who will tell me in what country such a plant occurs naturally, that is to say except as the result of its cultivation in some neighbouring place?

"Where do we find, in a state of nature, our cabbages, our lettuces, &c., as we now possess them in our kitchen gardens? Is it not the same with respect to the many animals which domestication has changed or considerably modified?"[2]

We may next consider two examples of the kind of evidence which Lamarck brings forward in proof of the effects of the

[1] *Op. cit.*, Tom. I, pp. 221—223.
[2] *Ibid.*, pp. 226—227.

environment and of the use and disuse of organs upon plants and animals living in a state of nature :—

"The following fact proves, with regard to plants, how much the alteration of any important factor in the environment modifies the parts of these living bodies.

"So long as *Ranunculus aquatilis* is sunk beneath the surface of the water, its leaves are all finely divided and have their divisions hair-like ; but when the stems of this plant reach the surface of the water, the leaves which develop in the air become broadened, rounded and simply lobed. If some runners of the same plant succeed in pushing their way into a soil which is merely damp, without being inundated, their stems are then short, and none of their leaves are divided into hair-like segments ; thus arises *Ranunculus hederaceus*, which botanists regard as a species when they come across it."[1]

. . . . . .

"With regard to habits, it is curious to observe the result thereof in the remarkable form and in the stature of the giraffe (*Camelo-pardalis*) : we know that this animal, the tallest of the mammals, inhabits the interior of Africa, and that it lives in places where the earth, almost always arid and without herbage, obliges it to browse on the foliage of trees and to make continual efforts to reach it. As a result of this habit, maintained for a long time in all the individuals of its race, the fore limbs have become much longer than the hind ones, and the neck has become so much elongated that the giraffe, without standing up on its hind legs, raises its head and reaches a height of six metres (nearly twenty feet)."[2]

The following passage must suffice to give some idea of Lamarck's views on the inheritance of "acquired" characters, which his theory necessarily implies, though not in the exaggerated sense of some modern writers :—

"These familiar facts are surely well suited to prove what is the result of the habitual use by animals of some particular organ or part ; and if, when we observe, in an animal, an organ specially developed, strong and powerful, anyone pretends that its habitual exercise has caused it to gain nothing, that its continued disuse would cause it to lose nothing, and that, in short, this organ has always been as it is since the creation of the species to which the animal belongs, I would ask why our domestic ducks can no longer fly like wild ducks ; in a word, I would cite a multitude of examples relative to ourselves, which bear witness to the differences which result in our own bodies

[1] *Op. cit.*, Tom. I, p. 230.
[2] *Ibid.*, pp. 256—257.

from the exercise or the want of exercise of any of our organs, although these differences are not maintained in the individuals of the next generation, for then their results would be much more considerable.

"I shall show in the second part that when the will determines an animal to some action, the organs which have to execute this action are forthwith stimulated by the affluence of subtle fluids (the nervous fluid) which become the determining cause of the movements which the action in question requires. A multitude of observations establishes this fact, which should no longer be called in question.

"It results therefrom that numerous repetitions of these acts of organization strengthen, extend, develop and even create the organs which are needed. It is only necessary to observe attentively what is happening everywhere in this respect to convince oneself of the actuality of this cause of organic development and modification.

"Now, every change acquired in an organ by a habit of use sufficient to have produced it, is maintained afterwards by generation, if it is common to the individuals which have united in the act of fecundation for the reproduction of their species. In short, this modification is propagated, and thus passes to all the individuals which follow and which are subjected to the same environment, without their being obliged to acquire it by the means which really created it.

"The mingling in reproductive unions, however, between individuals which have different qualities or forms, is necessarily opposed to the constant propagation of those qualities and forms. This is the reason why in man, who is subjected to so many different modifying circumstances, the accidental qualities or defects which he has chanced to acquire are not preserved and propagated by generation. If, when any peculiarities of form or any defects have been acquired, two individuals in this condition should always unite, they would reproduce the same peculiarities, and successive generations confining themselves to similar unions, a special and distinct race would then be formed. But the perpetual mingling between individuals which have not the same peculiarities of form causes all peculiarities acquired as the result of peculiar circumstances of the environment to disappear. Whence one may be certain that if human beings were not separated by the distances of their habitations, the mixed breeding would cause the general characters which distinguish the different nations to disappear."[1]

In the light of modern knowledge these views on the subject of heredity are, of course, crude and inaccurate enough, but there

[1] *Op. cit.*, Tom. I, pp. 259—262.

is nothing absurd in them, and at the time when Lamarck wrote it would scarcely have been possible to formulate anything better.

It is, however, this assumption of the inheritance of somatogenic characters that has probably done more than anything else to prevent many modern biologists from accepting the so-called Lamarckian factors of evolution. Those who hold with Weismann that there is no possible mechanism by which a somatogenic character can be converted into a blastogenic one are forced to reject Lamarck's teaching, but the Weismannian assumption that there is no such possibility of inheritance of somatogenic characters rests upon no better foundation than the Lamarckian assumption that there is. We have dealt with this question at some length in an earlier chapter and need only now remember that, if there are many modern biologists who reject the Lamarckian factors because they cannot reconcile them with Weismannism, there are perhaps quite as many others who accept them because they appeal irresistibly to their common sense, and because they refuse to believe that Weismann's difficulties are really insurmountable.

It is, of course, easy to ridicule Lamarck's views, and to say, for example, that he maintained that an animal could develop an organ by simply wishing for it, and ridicule of this kind has undoubtedly done much to hinder the due appreciation of his work. Such statements, however, are only made by those who have never paid adequate attention to the writings of the great French biologist.

It is evident from the passage last quoted that Lamarck also did not fail to perceive the importance of isolation as a factor in organic evolution, necessary to prevent the swamping effects of intercrossing upon newly arisen species or varieties.

In another place he discusses the influence of the struggle for existence in counteracting the effects of excessive multiplication, and in so doing just misses the idea of Natural Selection:—

"Animals eat one another, except those which live only upon plants; but the latter are liable to be devoured by carnivores.

"We know that it is the stronger and the better armed which eat the weaker, and that the large species devour the smaller ones. Nevertheless the individuals of one and the same race rarely eat each other; they make war on other races."[1]

[1] *Op. cit.*, Tom. I, p. 99.

Lamarck summed up his views as to the factors which have co-operated in organic evolution, at any rate so far as the animal kingdom is concerned, in a later work, the "Histoire Naturelle des Animaux sans Vertèbres," published in 1815, in the form of four "Laws," which may be taken as replacing the two "Laws" of the "Philosophie Zoologique." They are as follows:—

"First Law: Life, by its own forces, tends continually to increase the volume of every body which possesses it, and to extend the dimensions of its parts, up to a limit which life itself imposes."[1]

. . . . . .

"Second Law: The production of a new organ in an animal body results from a new requirement which continues to make itself felt, and from a new movement which this requirement begets and maintains."[2]

. . . . . .

"Third Law: The development and efficiency of organs are constantly in proportion to the use of these organs."[3]

. . . . . .

"Fourth Law: All that has been acquired, traced out or altered in the organization of individuals during the course of their life, is preserved by generation, and transmitted to the new individuals which originate from those which have experienced these modifications."[4]

With regard to the position of man in the animal kingdom Lamarck, unfortunately, does not seem to have been able, any more than Buffon, to divest himself of the fetters of religious orthodoxy. After pointing out at length the numerous ties by which man, in his bodily organization, is united to the lower animals, and especially his close relationship to the apes, he saves himself, so to speak, in the following paragraph:—

"Such would be the reflections which one might make if man, considered here as the pre-eminent race in question, were only distinguished from the animals by the characters of his organization, and if his origin were not different from theirs."[5]

[1] "Histoire Naturelle des Animaux sans Vertèbres," Tom. I, 1815, p. 182.
[2] *Ibid.*, p. 185.
[3] *Ibid.*, p. 189.
[4] *Ibid.*, p. 199.
[5] "Philosophie Zoologique," Tom. I, p. 357.

CHAPTER XXV

Robert Chambers and the "Vestiges of Creation"—Natural Selection—The Views of Charles Darwin and Alfred Russel Wallace.

For half a century after the appearance of the "Philosophie Zoologique" the theory of organic evolution made but little progress. The gap, however, was to some extent filled by the publication, at first anonymously, of Robert Chambers' celebrated book, "Vestiges of the Natural History of Creation." This work first appeared in the year 1844 and rapidly passed through a large number of editions. Though the views of its author can hardly be said to mark any advance, but on the whole perhaps rather a retrogression, the work, which gave rise to much controversy, undoubtedly played a very important part in preparing the way for the reception of Charles Darwin's "Origin of Species." Chambers presented the evidence of organic evolution in a very convincing manner, laying great stress upon that afforded by the geological record and the facts of comparative anatomy and embryology, and he included mankind in his general scheme of evolution.

His views as to the *modus operandi* of organic evolution are probably expressed as clearly as such views could be in the following paragraphs:—

"The proposition determined on after much consideration is, that the several series of animated beings, from the simplest and oldest up to the highest and most recent, are, under the providence of God, the results, *first*, of an impulse which has been imparted to the forms of life, advancing them, in definite times, by generation, through grades of organization terminating in the highest dicotyledons and vertebrata, these grades being few in number, and generally marked by intervals of organic character which we find to be a practical difficulty in ascertaining affinities; *second*, of another impulse connected with the vital forces, tending, in the course of generations, to modify organic structures in accordance with external circumstances, as food, the nature of the habitat and the meteoric agencies, these being the

"adaptations" of the natural theologian. We may contemplate these phenomena as ordained to take place in every situation, and at every time, where and when the requisite materials and conditions are presented—in other orbs as well as in this—in any geographical area of this globe which may at any time arise—observing only the variations due to difference of materials and of conditions."[1]

. . . . . .

"For the history, then, of organic nature, I embrace, not as a proved fact, but as a rational interpretation of things as far as science has revealed them, the idea of Progressive Development. We contemplate the simplest and most primitive types of being, as giving, under a law to which that of like-production is subordinate, birth to a type superior to it in compositeness of organization and endowment of faculties; this again producing the next higher, and so on to the highest. We contemplate, in short, a universal gestation of nature, analogous to that of the individual being; and attended as little by circumstances of a startling or miraculous kind, as the silent advance of an ordinary mother from one week to another of her pregnancy. We see but the chronicle of one or two great areas, within which the development has reached the highest forms. In some others, as Australia and the islands of the Pacific, development appears to have not yet passed through the whole of its stages, because, owing to the comparatively late uprise of the land, the terrestrial portion of the development was there commenced more recently. It would commence and proceed in any new appropriate area, on this or any other sphere, exactly as it commenced upon our area in the time of the earliest fossiliferous rocks, whichever these are. Nay, it perhaps starts every hour with common infusions, and in similar humble theatres, and might there proceed through all the subsequent stages, granting suitable space and conditions. Thus simple—after ages of marvelling—appears Organic Creation, while yet the whole phenomena are, in another point of view, wonders of the highest kind, being the undoubted results of ordinances arguing the highest attributes of foresight, skill, and goodness on the part of their Divine Author."[2]

Progressive evolution is here clearly attributed to some inherent tendency implanted in the first living things, and apparently the writer imagines that the same or closely similar results may have been arrived at along many different lines of evolution, each commencing at a distinct starting point and at a different time and

[1] "Vestiges of the Natural History of Creation," 12th ed., 1884, pp. 201, 202.
[2] *Ibid.*, pp. 230, 231.

place from all the others. The author of this hypothesis evidently considers it a distinct improvement upon the views of Lamarck, which he very briefly discusses. He thinks that Lamarck attributes too much importance to the principle of use and disuse, which he regards as "obviously insufficient to account for the great grades of organization," though he admits that external conditions may have been "a means of producing the exterior characters." There can be little doubt, however, that, in relying upon a system of more or less definite and continuously operating natural causes as factors of organic evolution, Lamarck took up a far more scientific position than Robert Chambers.

In insisting upon the great importance of Natural Selection as a factor in organic evolution, Charles Darwin and Alfred Russel Wallace made a great advance upon the position of any of their predecessors.

We have seen in the last chapter that this principle had been hinted at by more than one writer about the close of the eighteenth and the commencement of the nineteenth centuries, and that it can even be traced back to the philosophy of ancient Greece. In the historical sketch which prefaces the later editions of the "Origin of Species," Charles Darwin himself quotes a translation from Aristotle which shows sufficiently clearly that the idea was familiar to the great Greek biologist. In the same sketch he also quotes a passage from Dr. W. C. Wells, from a paper read before the Royal Society in 1813, in which the same principle is recognized in the most explicit and unmistakable manner.[1]

It was not, however, until the year 1858 that the part played by natural selection in organic evolution began to be generally understood. In that year Sir Charles Lyell and Dr. J. D. Hooker communicated to the Linnean Society certain papers,[2] written by Darwin and Wallace, which at once called prominent attention to the importance of this factor and contained the essential parts of the theory of natural selection as subsequently developed by both these writers.

Darwin's paper consisted of extracts from his as yet unpublished work, together with an abstract of a letter to

[1] A remarkably clear and concise exposition of the principle of natural selection in the struggle for existence was also given by Patrick Matthew in 1831 in a work "On Naval Timber and Arboriculture," etc., p. 384. (Adam Black, Edinburgh.)

[2] These papers have been reprinted by the Linnean Society in the volume published in connection with the Darwin-Wallace Celebration held on July 1st, 1908, and it is from this volume that the quotations which follow are taken.

Professor Asa Gray. A few quotations will suffice to indicate his views:—

"De Candolle, in an eloquent passage, has declared that all nature is at war, one organism with another, or with external nature. . . . It is the doctrine of Malthus applied in most cases with tenfold force. . . . Even slow-breeding mankind has doubled in twenty-five years; and if he could increase his food with greater ease, he would double in less time. But for animals without artificial means, the amount of food for each species must, *on an average*, be constant, whereas the increase of all organisms tends to be geometrical, and in a vast majority of cases at an enormous ratio. Suppose in a certain spot there are eight pairs of birds, and that *only* four pairs of them annually (including double hatches) rear only four young, and that these go on rearing their young at the same rate, then at the end of seven years (a short life, excluding violent deaths, for any bird) there will be 2048 birds, instead of the original sixteen. As this increase is quite impossible, we must conclude either that birds do not rear nearly half their young, or that the average life of a bird is, from accident, not nearly seven years. Both checks probably concur. The same kind of calculation applied to all plants and animals affords results more or less striking, but in very few instances more striking than in man."

. . . . . .

"Lighten any check in the least degree, and the geometrical powers of increase in every organism will almost instantly increase the average number of the favoured species. . . . Finally, let it be borne in mind that this average number of individuals (the external conditions remaining the same) in each country is kept up by recurrent struggles against other species or against external nature (as on the borders of the Arctic regions, where the cold checks life), and that ordinarily each individual of every species holds its place, either by its own struggle and capacity of acquiring nourishment in some period of its life, from the egg upwards; or by the struggle of its parents (in short-lived organisms, when the main check occurs at longer intervals) with other individuals of the *same* or *different* species.

"But let the external conditions of a country alter. If in a small degree, the relative proportions of the inhabitants will in most cases simply be slightly changed; but let the number of inhabitants be small, as on an island, and free access to it from other countries be circumscribed, and let the change of conditions continue progressing (forming new stations), in such a case the original inhabitants must cease to be as perfectly adapted to the

changed conditions as they were originally. It has been shown in a former part of this work, that such changes of external conditions would, from their acting on the reproductive system, probably cause the organization of those beings which were most affected to become, as under domestication, plastic. Now, can it be doubted, from the struggle each individual has to obtain subsistence, that any minute variation in structure, habits, or instincts, adapting that individual better to the new conditions, would tell upon its vigour and health? In the struggle it would have a better *chance* of surviving; and those of its offspring which inherited the variation, be it ever so slight, would also have a better *chance*. Yearly more are bred than can survive; the smallest grain in the balance, in the long run, must tell on which death shall fall, and which shall survive. Let this work of selection on the one hand, and death on the other, go on for a thousand generations, who will pretend to affirm that it would produce no effect, when we remember what, in a few years, Bakewell effected in cattle, and Western in sheep, by this identical principle of selection?"

. . . . . .

"In nature we have some *slight* variation occasionally in all parts; and I think it can be shewn that changed conditions of existence is the main cause of the child not exactly resembling its parents; and in nature geology shews us what changes have taken place, and are taking place. We have almost unlimited time;"

. . . . . .

"Another principle, which may be called the principle of divergence, plays, I believe, an important part in the origin of species. The same spot will support more life if occupied by very diverse forms. We see this in the many generic forms in a square yard of turf, and in the plants or insects on any little uniform islet, belonging almost invariably to as many genera and families as species. . . . Now, every organic being, by propagating so raqidly, may be said to be striving its utmost to increase in numbers. So it will be with the offspring of any species after it has become diversified into varieties, or subspecies, or true species. And it follows, I think, from the foregoing facts, that the varying offspring of each species will try (only few will succeed) to seize on as many and as diverse places in the economy of nature as possible. Each new variety or species, when formed, will generally take the place of, and thus exterminate its less well-fitted parent. This I believe to be the origin of the classification and affinities of organic beings at all times; for organic beings always *seem* to branch and sub-branch like the limbs of a tree from a common trunk, the flourishing and

diverging twigs destroying the less vigorous—the dead and lost branches rudely representing extinct genera and families."

The same paper also contains a sketch of the supplementary theory of sexual selection, which will be seen to agree very closely with the paragraph from Erasmus Darwin's "Zoonomia" quoted in the last chapter:—

"Besides this natural means of selection, by which those individuals are preserved, whether in their egg, or larval, or mature state, which are best adapted to the place they fill in nature, there is a second agency at work in most unisexual animals, tending to produce the same effect, namely, the struggle of the males for the females. These struggles are generally decided by the law of battle, but in the case of birds, apparently, by the charms of their song, by their beauty or their power of courtship, as in the dancing rock-thrush of Guiana. The most vigorous and healthy males, implying perfect adaptation, must generally gain the victory in their contests. This kind of selection, however, is less rigorous than the other; it does not require the death of the less successful, but gives to them fewer descendants."

The publication from which these quotations are taken itself consists of extracts from Charles Darwin's manuscripts, selected with a view to explaining, as clearly as possible, his theory of natural selection, and is therefore especially suitable for citation. In the following year (1859) the author's classical work, "The Origin of Species by means of Natural Selection," made its appearance, the first of that notable series of volumes on philosophical biology which have made his name so famous. In these works both the general theory of Evolution and the subsidiary theory of Natural Selection are elaborated and supported by an immense body of evidence drawn from published records and personal observations, and so successfully was this done that in a comparatively few years these theories met with general acceptance on the part, not only of scientific men, but also of the educated public. It must not be forgotten, either, that Charles Darwin applied the doctrine of organic evolution in a fearless and uncompromising manner to the origin of the human race.

Dr. Wallace's contribution to the Linnean Society symposium of 1858 was entitled "On the Tendency of Varieties to depart

indefinitely from the Original Type." The following quotations will serve to show that his views on Natural Selection were closely similar to those of Charles Darwin.

"The life of wild animals is a struggle for existence. The full exertion of all their faculties and all their energies is required to preserve their own existence and provide for that of their infant offspring. The possibility of procuring food during the least favourable seasons, and of escaping the attacks of their most dangerous enemies, are the primary conditions which determine the existence both of individuals and of entire species."

. . . . . .

"Even the least prolific of animals would increase rapidly if unchecked, whereas it is evident that the animal population of the globe must be stationary, or perhaps, through the influence of man, decreasing. Fluctuations there may be; but permanent increase, except in restricted localities, is almost impossible. For example, our own observation must convince us that birds do not go on increasing every year in a geometrical ratio, as they would do, were there not some powerful check to their natural increase. Very few birds produce less than two young ones each year, while many have six, eight, or ten; four will certainly be below the average; and if we suppose that each pair produce young only four times in their life, that will also be below the average, supposing them not to die either by violence or want of food. Yet at this rate how tremendous would be the increase in a few years from a single pair! A simple calculation will show that in fifteen years each pair of birds would have increased to nearly ten millions! Whereas we have no reason to believe that the number of the birds of any country increases at all in fifteen or in one hundred and fifty years. With such powers of increase the population must have reached its limits, and have become stationary, in a very few years after the origin of each species. It is evident, therefore, that each year an immense number of birds must perish—as many in fact as are born. . . . It is, as we commenced by remarking, 'a struggle for existence,' in which the weakest and least perfectly organized must always succumb.

"Now it is clear that what takes place among the individuals of a species must also occur among the several allied species of a group,—viz., that those which are best adapted to obtain a regular supply of food, and to defend themselves against the attacks of their enemies and the vicissitudes of the seasons, must necessarily obtain and preserve a superiority in population; while those species which from some defect of power or organization are the least capable of counteracting the vicissitudes of food

supply, &c., must diminish in numbers, and, in extreme cases, become altogether extinct."

. . . . . .

"Most or perhaps all the variations from the typical form of a species must have some definite effect, however slight, on the habits or capacities of the individuals. Even a change of colour might, by rendering them more or less distinguishable, affect their safety; a greater or less development of hair might modify their habits. . . . An antelope with shorter or weaker legs must necessarily suffer more from the attacks of the feline carnivora. . . . If, on the other hand, any species should produce a variety having slightly increased powers of preserving existence, that variety must inevitably in time acquire a superiority in numbers. . . . All varieties will therefore fall into two classes—those which under the same conditions would never reach the population of the parent species, and those which would in time obtain and keep a numerical superiority. Now, let some alteration of physical conditions occur in the district—a long period of drought, a destruction of vegetation by locusts, the irruption of some new carnivorous animal seeking 'pastures new'—any change in fact tending to render existence more difficult to the species in question, and tasking its utmost powers to avoid complete extermination; it is evident that, of all the individuals composing the species, those forming the least numerous and most feebly organized variety would suffer first, and, were the pressure severe, must soon become extinct. The same causes continuing in action, the parent species would next suffer, would gradually diminish in numbers, and with a recurrence of similar unfavourable conditions might also become extinct. The superior variety would then alone remain, and on a return to favourable conditions would rapidly increase in numbers and occupy the place of the extinct species and variety.

"The *variety* would now have replaced the *species*, of which it would be a more perfectly developed and more highly organized form. It would be in all respects better adapted to secure its safety, and to prolong its individual existence and that of the race. Such a variety *could not* return to the original form; for that form is an inferior one, and could never compete with it for existence. . . . But this new, improved, and populous race might itself, in course of time, give rise to new varieties, exhibiting several diverging modifications of form, any of which, tending to increase the facilities for preserving existence, must, by the same general law, in their turn become predominant. Here, then, we have *progression and continued divergence* deduced from the general laws which regulate the existence of animals in

a state of nature, and from the undisputed fact that varieties do frequently occur."

It will be evident from the above sketch of the theory of Natural Selection, which I have thought it desirable to give in the actual words of its chief exponents, that adaptation is explained as the logical consequence of certain facts which can at any time be verified by direct observation. (1) All organisms tend to increase in a high geometrical ratio; (2) there is, partly as a direct result of such increase, a keen struggle for existence, to which all organisms are more or less exposed and in which vast numbers perish without leaving offspring; (3) all organisms tend to vary in many directions; (4) variations, whether favourable or otherwise, tend to be transmitted by heredity from generation to generation; though, as we have already seen, there is at the present time much dispute as to whether variations of a certain kind ought not to be excluded from this generalization.

It follows inevitably from these premisses that in every generation there will be a more or less strongly pronounced tendency towards the elimination of those individuals which are least well adapted to their environment and a corresponding preservation and encouragement of those which are best adapted, or, in Herbert Spencer's celebrated phrase, a "survival of the fittest." This process, continued from generation to generation for count less ages, has resulted in that marvellous perfection of adaptation which we have seen to be such a striking feature of both plants and animals.

Charles Darwin himself, however, was not satisfied with natural selection as the sole factor concerned in bringing about progressive evolution and adaptation. Although, in the historical sketch which he added to the later editions of the "Origin of Species," he remarks:—

"It is curious how largely my grandfather, Dr. Erasmus Darwin, anticipated the views and erroneous grounds of opinion of Lamarck in his 'Zoonomia,'"

and although he himself at first appears to have attached very little importance to Lamarck's opinions, yet we find in the last chapter of the sixth edition of the "Origin of Species" abundant evidence that he was obliged to admit the efficacy of the chief "Lamarckian" factor, the principle of use and disuse, in

modifying species, and also, to some extent, that of the direct action of the environment:—

"Disuse, aided sometimes by natural selection, will often have reduced organs when rendered useless under changed habits or conditions of life; and we can understand on this view the meaning of rudimentary organs.[1] But disuse and selection will generally act on each creature, when it has come to maturity and has to play its full part in the struggle for existence, and will thus have little power on an organ during early life; hence the organ will not be reduced or rendered rudimentary at this early age. The calf, for instance, has inherited teeth, which never cut through the gums of the upper jaw, from an early progenitor having well-developed teeth; and we may believe, that the teeth in the mature animal were formerly reduced by disuse, owing to the tongue and palate, or lips, having become excellently fitted through natural selection to browse without their aid; whereas in the calf, the teeth have been left unaffected, and on the principle of inheritance at corresponding ages have been inherited from a remote period to the present day." [2]

. . . .

"I have now recapitulated the facts and considerations which have thoroughly convinced me that species have been modified, during a long course of descent. This has been effected chiefly through the natural selection of numerous successive, slight, favourable variations; aided in an important manner by the inherited effects of the use and disuse of parts; and in an unimportant manner, that is in relation to adaptive structures, whether past or present, by the direct action of external conditions, and by variations which seem to us in our ignorance to arise spontaneously. It appears that I formerly underrated the frequency and value of these latter forms of variation, as leading to permanent modifications of structure independently of natural selection. But as my conclusions have lately been much misrepresented, and it has been stated that I attribute the modification of species exclusively to natural selection, I may be permitted to remark that in the first edition of this work, and subsequently, I placed in a most conspicuous position—namely, at the close of the Introduction—the following words: 'I am convinced that natural selection has been the main but not the exclusive means of modification.' This has been of no avail. Great is the power of steady misrepresentation; but the history of science shows that fortunately this power does not long endure." [3]

[1] Often now called "vestigial organs."
[2] "Origin of Species," Ed. vi. p. 420.
[3] *Ibid.*, p. 421.

It is of the greatest interest to recognize the fact that Darwin himself saw nothing incompatible between the so-called Lamarckian factors of use and disuse and the direct action of the environment, and the principle of natural selection, but, on the other hand, that the one set of factors might supplement the other.

On the occasion of the unveiling of the statue of Charles Darwin in the Natural History Museum at South Kensington, Professor Huxley found occasion to observe that "science commits suicide when it adopts a creed."[1] This warning, it is to be feared, has not been heeded by all of Darwin's followers. Many of these have departed very far from the moderate and rational position of their leader and, while attributing to natural selection almost every advance which has been made in the evolution of the organic world, are, as we have already seen, obliged to justify their neglect of the "Lamarckian" factors by denying altogether the possibility of the inheritance of acquired characters, which Darwin, of course, freely admitted. Natural selection, in the hands of these enthusiasts, and in spite of Charles Darwin's efforts to maintain a just balance between this and other factors, has indeed become a creed.

Dr. Wallace from the first adopted an uncompromising attitude towards the opinions of Lamarck. In the Linnean Society paper from which we have already quoted he says:—

"The hypothesis of Lamarck—that progressive changes in species have been produced by the attempts of animals to increase the development of their own organs, and thus modify their structure and habits—has been repeatedly and easily refuted by all writers on the subject of varieties and species, and it seems to have been considered that when this was done the whole question has been finally settled; but the view here developed renders such an hypothesis quite unnecessary, by shewing that similar results must be produced by the action of principles constantly at work in nature. The powerful retractile talons of the falcon- and the cat-tribes have not been produced or increased by the volition of those animals;[2] but among the different varieties which occurred in the earlier and less highly organized forms of these groups, *those always survived longest which had the greatest facilities for seizing their prey.*"

[1] *Vide* Herbert Spencer's "Factors of Organic Evolution," p. 75.

[2] Who ever said they had, except in the sense that an animal voluntarily uses its claws on appropriate occasions and that constantly repeated use causes them to

Wallace's views [1] also differ from those of Darwin in that, at any rate in his later years, they became strongly anthropocentric, and he regarded the whole of the organic world as having been designed by the Creator for the ultimate reception and benefit of mankind. He does not, it is true, go back to the old idea that species have been separately and specially created as we now find them, but he holds that the entire scheme of evolution was planned out in the mind of the Creator, and even suggests that the working out of this scheme may have been delegated by the Supreme Being to a body of "organizing spirits":—

"At successive stages of development of the life-world, more and perhaps higher intelligences might be required to direct the main lines of variation in definite directions in accordance with the general design to be worked out, and to guard against a break in the particular line which alone could lead ultimately to the production of the human form." [2]

Such speculations as this would render natural selection and all other natural factors of organic evolution superfluous, but we cannot profitably discuss them in a work like the present. We may point out, however, that they are in essential agreement with the views of the author of the "Vestiges of Creation," to which we have referred in the early part of this chapter, excepting that Robert Chambers did not venture to call in the assistance of subordinate "organizing spirits" to carry out the plans of the Creator.

increase in size and efficiency? Lamarck did not suppose that an animal simply willed organs to sprout out of its body!

[1] For a full exposition of these views the reader should refer to Dr. Wallace's "Darwinism" (London: Macmillan & Co., 1889).

[2] "The World of Life, a Manifestation of Creative Power, Directive Mind and Ultimate Purpose," by Alfred Russel Wallace (London: Chapman and Hall, Ltd., 1910), p. 395.

*

CHAPTER XXVI

Illustrations of the action of natural selection in the struggle for existence — Degeneration — Artificial selection — Mutation and adaptation.

THE operation of natural selection is, obviously, by no means confined to living things. The various bodies which make up the inorganic world owe their actual form and arrangement largely to processes of selection which are constantly going on amongst them. The outline of the sea coast is the result of the selective action of atmospheric and tidal agencies upon the different kinds of rock of which it is composed. The softer parts are destroyed first, leaving the more resistant portions to stand out in the form of bluffs or promontories, and to illustrate in the inanimate world the principle of the survival of the fittest. We might even say that the prominent headlands exhibit adaptation, for if they were not adapted by their peculiar hardness to resist the disintegrating influences of the environment they would not be there, but would have perished with those portions of the land which formerly occupied the bays and inlets.

It is, of course, extremely difficult, if not impossible, to obtain direct evidence of the action of natural selection in modifying species in a state of nature. Human life is all too brief to admit of our making very satisfactory observations concerning processes which extend perhaps over millions of years. Man has, however, in a comparatively short space of time, so changed the conditions of life for many of the lower animals as to lead albeit unintentionally, to the more or less complete extermination of many species, and by studying these cases we may hope to arrive at sound conclusions as to what takes place in a state of nature. After all, mankind is a part of nature and we have no just reason for excluding his influence in our consideration of the factors which have brought about the present condition of the organic world.

It is well known that many of the birds of various remote

islands have lost the power of flight. Such are the kiwi, the kakapo, the weka, the notornis and the already extinct gigantic moas of New Zealand; the dodo of Mauritius, and the solitaire of Rodriguez. Although belonging to several very distinct families of birds, including ratites, parrots, rails and pigeons, all the forms enumerated have undergone the same curious modification, resulting in the most extreme cases (the moas) in the complete loss of the wings, and in others in the reduction of those organs to a more or less vestigial condition.[1]

This convergence is clearly due to the similarity of the conditions under which these birds have had to live. One of the most characteristic features of oceanic islands is the absence from them of predaceous mammals, the natural enemies of birds, which have never been able to cross the great stretches of open ocean which separate such islands from the continental areas on which the Mammalia have been evolved. Birds, however, and even land birds, by virtue of their powers of flight, have been able to reach these islands at more or less frequent intervals and to establish themselves there. Finding abundance of food, which they could obtain near the ground, and finding themselves no longer under the necessity of constantly using their wings in order to escape from their enemies, some of these birds, though by no means all, gradually gave up flying and their wings underwent a slow process of degeneration in accordance with Lamarck's principle of disuse. No doubt such disuse, if continued only through a single lifetime, could scarcely produce a visible effect upon the next generation, but continued under the same conditions throughout thousands of generations it has brought about a permanent deterioration which can no longer be retrieved.

It is to be noted that this degeneration is the result of the removal of the organism, to a certain extent, from the struggle for existence. Natural selection can only act through the struggle for existence and upon those organs which are of value in the struggle. When the struggle ceases, natural selection ceases and degeneration sets in, for there is no longer any reason why a high standard of perfection should be maintained. All degrees of imperfection now have equal opportunities of propagating themselves. The inferior individuals are no longer weeded out, and the average condition of the species consequently deteriorates.

But observe what happens when a degenerate organism is

[1] Compare Chapter XVII, Figs. 113, 114.

once more exposed, by some unfortunate change in its environment, to the old struggle from which it had escaped. This has actually taken place in the case of the flightless birds of New Zealand and other remote islands. With the advent of Europeans, predaceous mammals of many species—dogs, cats, rats, weasels, stoats and ferrets—have been let loose upon their helpless victims. These are once more exposed to a keen struggle for existence, while at the same time they have lost those very organs which are necessary to enable them to maintain themselves in that struggle, and natural selection, having regained her power, is rapidly exterminating them. It is not too much to say that in a few years' time there will be no flightless birds left in New Zealand except in special reserves where they are being protected by man.

It is highly instructive in this connection to contrast the condition of such a bird as the flightless parrot, or kakapo, with that of its relative the kea. The kakapo is a large, heavy bird of nocturnal habits and with practically no means of defence; it haunts the dense forest and is rarely seen except when hunted out by dogs. The kea, on the contrary, is one of the strongest fliers of the parrot tribe. It frequents high and more or less inaccessible mountain regions and since the advent of Europeans has learnt to make use of the sheep which they have introduced as an additional food supply. It is doubtful whether the utmost efforts of the sheep farmers, who annually expend large sums of money for the purpose, will ever enable them to exterminate the kea, and it is equally doubtful whether the efforts of the New Zealand Government to preserve the unique flightless birds will suffice to prevent the complete extermination of the kakapo within the next few years.

The aboriginal human population of remote islands has of course suffered not less than the lower animals from the invasion of their retreats by Europeans, although not always exclusively at the hands of the Europeans themselves. There are, perhaps, few more striking examples of the extermination of a primitive native race than that afforded by the rapid disappearance of the Moriori inhabitants of the Chatham Islands, some four hundred miles to the east of New Zealand, during the nineteenth century.[1] At the time of my visit to these islands, in

[1] Compare Dendy, "The Chatham Islands: A Study in Biology" (Memoirs and Proceedings of the Manchester Literary and Philosophical Society, Vol. XLVI., 1902).

January, 1901, there were only about a dozen pure-blooded individuals left; some of these were of great age, while the youngest was a lad of about 16, and they had all, I think, more or less completely adopted European manners and customs. Under these circumstances we are fortunate in possessing any reliable record of this interesting people, and that we do so is largely due to the energy and enthusiasm of Mr. Alexander Shand, who for more than thirty years lived amongst the Morioris and made a special study both of that race and of their Maori conquerors.

It appears from their language, customs and traditions, as well as from their physical characteristics, that the Morioris are closely related to the New Zealand Maoris. Their ignorance of the art of tattooing, and their very inferior artistic faculties in general, however, point to a very remote separation of the two races.

Like the Maoris they trace their origin to an unknown fatherland called Hawaiki, from which they must have emigrated to Chatham Island in canoes. In their new home they appear to have found the conditions of life remarkably easy, indeed, as the sequel shows, fatally so. With an abundant natural food supply of fruit, shell-fish, &c., and with no enemies to contend with, they multiplied until the islands were thickly populated, while at the same time they doubtless became lazy and effeminate.

The discovery of the islands by the brig "Chatham," in 1790, may be said to have sealed the fate of the unfortunate Moriori, though it is doubtful whether any serious injury ensued until the advent of the whaling and sealing vessels in 1828. These vessels brought with them many undesirable visitors, and probably were the means of introducing a disease which soon played havoc with the native race. On board some of the ships, moreover, were Maoris from New Zealand, who, on their return, painted such a glowing picture of the land of plenty, that a large number of their fellow-countrymen determined to emigrate to the islands *en masse*.

In order to effect this purpose they took possession of the brig "Rodney" at Port Nicholson, in New Zealand, about the beginning of November, 1835. They are said to have seized the crew and compelled the captain to transport them, about 900 in number, to their destination. At the time of the invasion the Morioris are supposed to have numbered about 2000, and had they

attacked the new-comers on their first arrival, they might have exterminated them with little trouble and prolonged for an indefinite period the life of their own race. Unfortunately for themselves, however, they had lost the art of self-defence. Owing to the absence of competition they had, in this respect at any rate, undergone degeneration. Killing was actually forbidden by their laws, and peace had reigned too long and too securely to give place at once to war when the emergency arose.

Just as the flightless birds of New Zealand have more or less completely disappeared since the advent of carnivorous mammals, so the Morioris, their happy isolation once broken, fell an easy prey to the more virile Maoris. The latter proceeded to parcel out the conquered country amongst themselves, claiming not only the land but also the inhabitants thereof, many of whom were massacred under circumstances of unutterable atrocity, while the remnant were speedily reduced to the condition of slaves. Under the changed conditions which had suddenly arisen in their environment the Morioris were no longer fit to survive in the struggle for existence, they had become degenerate in a vital respect, and natural selection, as soon as opportunity arose, stepped in and eliminated them.

It would be easy to multiply illustrations of the great generalization that when removed from the struggle for existence all organisms tend to become degenerate, the organs or faculties which they no longer require atrophying and gradually disappearing for want of employment. We see this very clearly in the case of sedentary animals such as the ascidians (Figs. 131, 132). The young ascidian is a highly organized creature which swims actively about by means of a muscular tail, in the same way as the tadpole of a frog. Like the latter it has nervous system, notochord and sense organs—though the sense organs are of a type peculiar to itself—and is an undoubted chordate. It never, however, progresses further in organization, so as to attain the true vertebrate condition. On the contrary, it gives up its active life and withdraws as far as possible from the struggle for existence by fixing itself to some rock or seaweed and enveloping its entire body in a thick protective envelope, within which it undergoes extensive degeneration. The tail and notochord completely disappear, so do the sense organs, none of these being any longer required under the new conditions of life. The

nervous system dwindles away to a mere ganglion, from which a few nerves come off, and the entire animal is reduced to the condition of a bag, with two openings through which the remaining organs obtain their food supply and communicate with the outside world by means of a stream of water maintained by ciliary action.

Still more conspicuous is the degeneration undergone by the great majority of parasites, whether animals or plants. Sacculina, for example, in the earlier stages of its existence, is an active crustacean which swims vigorously about by means of well developed appendages. It belongs to a group, the barnacles or cirripedes, which are notorious for sedentary habits and consequent degeneration in the adult condition. Sacculina, however, not content with a sedentary life, goes further down hill and becomes parasitic. It attacks crabs, and in the adult state is reduced to the condition of a large, irregularly shaped bag (Fig. 185) fixed to the under surface of the crab's abdomen by root-like processes which penetrate the body of the host and extract nutriment therefrom. With the exception of these root-like processes, which are a special, cænogenetic development, adapted for nutrition under new conditions of life, the only organs which have not undergone degeneration are those of reproduction, for upon these depends the perpetuation of the race and upon these, therefore, natural selection is still able to retain her hold.




FIG. 185.—Lower surface of a Swimming Crab (*Portunus depurator*) with a Sacculina (Sac.) attached to it. (From a photograph.)

It is, indeed, a general rule amongst parasitic animals that the reproductive organs are largely developed and very complicated, for the conditions which have become necessary for the existence of these animals are so complex and highly specialized, while the chances of mating between different individuals for purposes

of sexual reproduction are so remote, that the ova and spermatozoa have to be produced in vast numbers to compensate for the immense mortality which must take place amongst them and amongst the young animals to which they may give rise. Thus




FIG. 186.—The Dodder, *Cuscuta europæa*. Part of a Plant parasitic on a Branch of Willow, with germinating Seedlings on the right and Section of Host and Parasite on the left. (From Strasburger.)

b, vestigial leaves; *Bl*, flowers; *Cus*, stem of parasite in section; *H*, haustoria of parasite in section; *W*, stem of host in section, with vascular bundles (*v*, *c*); *t*, seedlings.

one of the most frequent results, or at any rate concomitants, of parasitism, and one which is well exemplified in the case of Sacculina, is hermaphroditism, which affords many more chances for the fertilization of the eggs than the unisexual condition.

We meet with precisely analogous phenomena in the case of many parasitic plants. In the dodder (Fig. 186) the leaves and

roots have disappeared almost completely and no chlorophyll is produced, but special nutritive organs, the sucker-like haustoria, are developed on the slender, twining stems, and serve to extract the necessary food from the host plant. The flowers, however, upon which the perpetuation of the race depends, still remain in a well developed condition.

Both Sacculina and the dodder have lost the power of independent existence, and if, for any reason, they were to find themselves suddenly confined to an environment where there were no suitable hosts, their races would inevitably become extinct. Nature would treat them just as she is treating the wingless birds, and make them pay the penalty for the degeneration which they have undergone.

It has long been recognized that much light may be thrown upon the problem of the evolution of species by the careful study of the methods which mankind has adopted for the improvement of the various races of cultivated plants and domesticated animals. Many such races have been so greatly modified that, did they occur in what is commonly called a state of nature, we should be obliged to regard them as distinct species. The history of some of these is lost in antiquity and we have no positive knowledge of the methods by which the improvement of wild species was first effected. We may assume, however, with some degree of confidence, that the earliest breeders and cultivators would select for cultivation and propagation those individuals which offered them the most valuable qualities, and that they would reject such as exhibited marked signs of inferiority. This process, repeated from generation to generation through thousands of years, and aided in each generation by the direct effects of cultivation, could not fail to bring about conspicuous results. For an account of what has been effected in this manner the student should consult Charles Darwin's classical work on the "Variation of Animals and Plants under Domestication."

The fact that it is possible, by means of artificial selection, so to guide the course of evolution as to lead to the production of such very distinct types as the numerous breeds of dogs or pigeons, affords strong justification for the view that in a state of nature natural selection has played a similar part. The chief difference

between artificial and natural selection is that man selects for his own purposes and modifies organisms to suit his own ends, while Nature selects to the benefit of the species operated upon, which becomes thereby modified to its own advantage and preservation in the struggle for existence. But we cannot really draw a distinction between the two kinds of selection, for even in a state of nature organisms are often selected and modified to the advantage of other organisms.

As we saw in a previous chapter, the forms, colours and scents of many flowers are probably the result of unconscious selection by insects, extending over countless generations. It may be said that the advantage gained in this case is mutual; the insect gets the honey and the flower gets fertilized. This of course is true, but exactly the same is true of human selection. The sheep gets the pasture and man gets the wool.

The almost unconscious efforts of our ancestors have given place in modern times to deliberate and systematic attempts to discover the principles upon which the improvement of cultivated races, both of plants and animals, should be based.

Perhaps no species of plants have been more improved by man than the various cereals upon which he relies so largely for his food supply. Professor de Vries, in his interesting book on "Plant-Breeding," [1] describes how such improvement has been effected in recent times. In the first place much care and thought have been devoted to carrying out experiments in accordance with the principle of continuous selection:—

"The general custom [in Germany] was to start such experiments from the best local or improved varieties by an initial choice of a certain number of typical heads. Such a group of selected plants was called the élite, and this élite had to be ameliorated according to the prevailing demands or even simply in accordance with some ideal model. Year after year, the best ears of the élite group were chosen for the continuance of the strain or family, and slowly, but gradually, its qualities were seen to improve in the desired direction. After some years, such a family might become decidedly better than the variety from which it had been derived. Then its yearly harvest would be divided into two parts, after having been sufficiently purified by the rejection of accidental ears of minor worth. The best ears were carefully sought out and laid aside for the continuance of the élite strain, but the remainder were sown on a distant field

[1] Kegan Paul, Trench, Trübner & Co., London, 1907.

in order to be multiplied as fast as possible. By this means, after a multiplication during two or three generations, its product could be used as seed grain for the farm or sold to others for the same purpose. Each year the élite would, of course, give a new and better harvest which could be multiplied and sold in the same manner." [1]

By this method improvement may undoubtedly be effected, but the selection has to be constantly repeated, otherwise the improved strain rapidly deteriorates again. Indeed it may be questioned whether it is possible in this way to effect any permanent improvement, at any rate in the case of cereals. We have to bear in mind that we are probably dealing all the time, not with a single pure race, but with a mixture of distinct races. We must also remember that many of the characters which it is desired to perpetuate and increase may be the direct result of the cultural methods employed, and, as we have already seen, we cannot expect such causes to produce visibly heritable effects in the course of a few generations, whatever they might do in the long run.

We have had occasion to point out in an earlier chapter that, according to Professor de Vries, new species arise, in a state of nature, not by the accumulation in particular directions of small, fluctuating variations, but by the sudden appearance of those more conspicuous variations known as mutations. De Vries points out that many of the so-called Linnean species, such as *Draba verna,* are in reality made up of a large number of "elementary species" which have arisen in this manner, and certain results which have been obtained in experiments upon the improvement of cereals appear to afford considerable support to these views.

It has long been known that an ordinary field of wheat contains a larger or smaller number of "types," "mutations," or "elementary species," which can be recognized by the experienced eye, and it has been shown that if a single plant of one of these types be isolated it will produce a "pure line" of offspring like itself [2] and continue to breed true for an indefinite number of generations Of course it is necessary that there should be no crossing with other types, but this is easily avoided, for, although accidental crosses may occur, the cereals, with the exception of rye, are

[1] De Vries, *op cit*, p 58

[2] Subject, however, to ordinary fluctuating variation.

usually self-fertilizing. Upon this knowledge is founded the method of single as opposed to continuous selection, a single selection of a suitable type being enough to establish the desired strain. The method of single selection is, of course, much less valuable in the case of animals (which are very rarely self-fertilizing) on account of the fact that the same mutation is not likely to occur simultaneously in both male and female individuals.

One of the first to make use of the method of single selection was Patrick Shirreff:—

"His first discovery was made in the year 1819. He observed a plant of wheat which surpassed its neighbors by its high degree of branching. It yielded 63 ears with about 2500 kernels. He saved the seeds, sowed them on a separate field and at considerable distances apart so as to induce in all the plants the same rich branching. He contrived to multiply it so rapidly that it took only two generations to get seed enough to bring it advantageously into the trade. He gave it the name of Mungoswell's wheat, and it soon became one of the most profitable varieties of Scotland. It has found its way into England and into France, where it is still considered one of the best sorts of wheat." [1]

The same method has been subjected to severe tests and placed upon a thoroughly scientific footing at the Swedish Agricultural Station of Svalof.

We have seen, in Chapter XIII, that hybridization may sometimes give rise to permanent races or strains exhibiting new combinations of characters, and that this takes place in accordance with Mendelian principles. It cannot be doubted that hybridization occurs occasionally in cultivated cereals, and Professor de Vries is of opinion that the occurrence of the different types or mutations [2] is often the result of hybridization at various periods in the history of the race. Surely, however, the mutation must come first, before hybridization is possible. After they have once been produced, of course, hybrids may, if true breeding, afford as valuable material for selection as mutations. The important results obtained by Professor Biffen and others, already referred to (p. 185), afford conclusive evidence on this point.

De Vries tells us in another work that:—

"According to the theory of mutation species have not arisen

[1] De Vries, *op. cit.*, pp. 34, 35.
[2] *Op. cit.*, p. 322.

gradually as the result of selection operating for hundreds, or thousands, of years but discontinuously by sudden, however small, changes. In contradistinction to fluctuating variations which are merely of a *plus* or *minus* character the changes which we call mutations are given off in almost every manner of new direction. They only appear from time to time, their periodicity being probably due to perfectly definite but hitherto undiscovered causes.

"The theory of the inheritance of acquired characters comes under the heading of fluctuations. Acquired characters have nothing to do with the origin of species." [1]

There is no need to suppose, however, that the theories of mutation and natural selection are mutually exclusive, for, however, new characters may arise, they must be subject to the action of natural selection in the struggle for existence. Selection itself can, of course, originate nothing, and it is perhaps unfortunate that Charles Darwin's great work should have been entitled "The Origin of Species by Means of Natural Selection." The variations with which selection works must be ready at hand and they must be heritable. Given such variations, selection can effect a progressive improvement by eliminating all that fail to fulfil the particular requirements by which their existence is conditioned.

Professor de Vries' objection to small, fluctuating variations as the material upon which natural selection operates in the modification of species appears to be based upon the view that such characters are acquired in the lifetime of the individual and cannot be inherited. If, however, we admit that a somatogenic character may, in the course of many generations and under the continued influence of the same conditions which originally called it forth, become converted into a blastogenic character, this difficulty entirely disappears.

It is extremely hard to believe that mutations, which, apart from a few special cases, seem to occur very rarely and at long intervals, can have afforded sufficient opportunity for the production of all the marvellous adaptations which exist in nature. Take, for example, the mutual adaptations which we see between the length of the nectary in certain flowers and the length of the proboscis in the insects which pollinate them. We cannot suppose that either the elongated nectary or the elongated proboscis arose by sudden mutation for unless these mutations

[1] "The Mutation Theory." English Trans., Vol. I, p. 213.

took place simultaneously in flower and insect, and in the same locality, and in a sufficient number of each, coincidences which, to say the least of it, are wildly improbable, the delicate correlation between the two would be thrown out of gear and the individuals exhibiting the mutations would be eliminated by natural selection because they were no longer sufficiently well adapted to the very special conditions of their environment.

We can only believe that the increase in length of nectary and proboscis took place so slowly that their reciprocal adaptation was never upset. A slight increase in the length of the nectary obliged the insect to poke further into the flower for the honey and thus increased the chances of pollination. A slight increase in the length of the proboscis enabled the insect to get more honey and thus gave it a better chance of existence. After perhaps many thousands of generations, under the influence of natural selection, combined in the case of the insect with the effects of use and disuse, the present enormous lengths of proboscis and nectary have been attained, and no one doubts the fact that they have become inheritable characters.

The same argument applies to other accurate adaptations to special conditions of the environment. How, for example, can the theory of mutation be applied to such cases as that of the flightless birds on oceanic islands? Who can doubt that the reduction of the wings and the loss of the power of flight have been brought about slowly and gradually as a result of disuse? and at the same time who would venture to argue that the flightless birds are not specifically distinct from their actively flying ancestors? If it be urged that mutations may be so small as to be almost imperceptible, then we must ask how do they differ from what Charles Darwin called slow, successive variations? and if we are told that they occur very rarely and are not successive, that very answer is sufficient to show that they are hardly likely to give rise to adaptive modifications, though it is not impossible that they may occasionally have done so by mere accident.

CHAPTER XXVII

Isolation—Physiological selection—Non-adaptive characters - Excessive growth - Synchronism in evolution of organs - Indifferent characters.

One of the most important factors in bringing about divergent evolution is undoubtedly isolation. However a new character may have arisen it is liable to be swamped by the crossing of the individuals which possess it with others which do not possess it unless by some means or other the two groups are prevented from interbreeding. We cannot fail to see the importance of this principle when we study the fauna and flora of remote islands, and their relationships to those of the nearest continental areas or of other islands.

Take, for example, the case of the Chatham Islands, which, as we have already seen, lie some 400 miles to the east of New Zealand. There can be very little doubt that these islands were formerly connected with the New Zealand mainland, and this connection probably continued into Pleistocene times, when a great depression took place which caused the two to be separated by a wide tract of ocean. All who have studied the question are agreed that the fauna and flora of the Chatham Islands are simply isolated detachments of those of New Zealand. Many species, especially of the plants, are identical with New Zealand species, but many others, though closely related to those of New Zealand, are considered by systematists to be specifically distinct, and they occur nowhere else in the world.

We have here an excellent illustration of the effects of geographical isolation, which we shall be able to appreciate better, perhaps, if we confine our attention to a few typical cases. The common New Zealand wood pigeon, *Carpophaga* (*Hemiphaga*) *novæ-zealandiæ*, is represented on the Chathams by a species known as *Carpophaga* (*Hemiphaga*) *chathamensis*, differing but slightly from its New Zealand congener, and the New Zealand

lizard, *Lygosoma moco*, is represented on Pitt Island (one of the Chathams) by a very similar form described by Mr. Boulenger under the name *Lygosoma dendyi*. The remarkable New Zealand lance-woods (*Pseudopanax crassifolium* and *P. ferox*) are represented on Chatham Island by the closely related *Pseudopanax chathamicum*, and the Chatham Island ribbon-wood also differs slightly from the common New Zealand species (*Plagianthus betulinus*).

The explanation of these differences is that the two portions into which each of the species mentioned became divided when the Chatham Islands were separated from New Zealand have diverged from one another and followed somewhat different lines of evolution. Owing, perhaps, to slightly different conditions of the environment, or to other causes which it is impossible to specify, one or both has become modified to a greater or less extent in its own particular direction and, owing to the geographical isolation, there has been no interbreeding between the two sections to keep them both in the same average condition.

The principle of isolation fully explains why the fauna and flora of oceanic islands in general are made up almost entirely of peculiar species found nowhere else in the world. The ancestors of these species were originally derived from some very distant, probably continental area, and their descendants have had few if any opportunities of interbreeding with the parent species, from which they have gradually diverged further and further under their new conditions of life.

Certain writers, such as Mr. Gulick and Dr. Romanes, have maintained that the mere separation of a species into two or more sections which are prevented from interbreeding would suffice to bring about divergent evolution, irrespective of whether or not the separate sections were exposed to different environmental conditions. It would probably be impossible to divide a species into two sections whose average qualities are identical, and :—

"No matter how infinitesimally small the difference may be between the average qualities of an isolated section of a species compared with the average qualities of the restof that species, if the isolation continues sufficiently long, differentiation of specific type is necessarily bound to ensue." [1]

[1] Romanes, "Darwin and after Darwin," Vol. III, "Isolation and Physiological Selection," p. 13.

If isolation is necessary for the establishment of new species by divergent evolution, why, it may be asked, do we find closely related species, which we must suppose to be descended from common ancestors at no very distant period, actually inhabiting the same areas at the present time? The answer is that there are other means by which groups of organisms can be prevented from interbreeding besides *geographical* isolation.

It used to be supposed that one of the best tests of the specific distinctness of any two forms was their incapacity for breeding together and producing fertile offspring.[1] The mule, it is true, is the offspring of parents belonging to two distinct species, the ass and the horse, but the mule is almost always sterile, and most well characterized species[2] are incapable of breeding together at all. This fact has been regarded by many people as a most serious difficulty in the way of comparing the formation of species by natural selection with the results produced amongst domesticated plants and animals by artificial selection, for the products of artificial selection, however much they may differ from one another, if they have been derived from the same parent species will usually remain capable of breeding together, and their offspring, as in the case of mongrel dogs, show no diminution in fertility.

The solution of this difficulty is to be found in the theory of "Physiological Selection," which we owe to Mr. Gulick, Dr. Romanes and others. These writers point out that amongst the endless variations to which plants and animals are subject will be variations in the reproductive system, by which certain individuals will be rendered infertile when crossed with others of the original species, while remaining fertile with individuals which have varied in the same manner as themselves. In this way a species may be as effectively divided into two sections as by any geographical barrier, and under these circumstances divergent evolution may be expected to take place. According to this view the mutual sterility which, to a greater or less extent, undoubtedly does characterize distinct species in a state of nature, is the cause and not the result of their distinctness, and cannot be regarded as a reason for supposing that there is any essential difference between the processes of artificial and natural selection. In artificial selection it is merely another kind of

[1] Although Lamarck pointed out a century ago that this is really no criterion of specific distinction. The idea that it is so is clearly expressed by Buffon ("Histoire Naturelle," Tom. VI, 1756, p. 16).

[2] At any rate amongst the higher animals.

isolation that has been employed to prevent the swamping effects of intercrossing; but it is an isolation that may be broken through at any moment, and if all the different varieties of some domestic plant or animal were turned loose to struggle for existence and interbreed with one another and with the parent species in a state of nature, they would probably in most cases very soon cease to have any separate existence.

The theory of natural selection, combined with that of the gradual inheritance of the effects of use and disuse and of other modifications brought about by the long-continued influence of the environment, affords a satisfactory explanation of the evolution of adaptive characters. Many if not all organisms, however, exhibit characters to which we can assign no adaptive value, which do not seem to be of any particular use to the organism in the struggle for existence, or which apparently might, so far as utility is concerned, be equally well replaced by any one of a number of alternative characters. In illustration of this statement we may first turn our attention to a group of cases which certainly appear to support the view that the factors at work in determining any particular line of evolution are more complex than might at first sight be supposed. It is a fact well known to palæontologists that many widely separated groups of the animal kingdom have, during the course of their evolution, and especially towards the end of that course, shown a strongly marked tendency to enormous increase in size. We see this in the extinct eurypterids (Fig. 139), giants amongst the arthropods; in the huge labyrinthodont amphibians; in many groups of reptiles of the secondary period, some of which attained a length of 80 feet or more, and amongst mammals in the extinct Tinoceras (Fig. 152) and the still surviving elephants and whales. Comparative anatomists are familiar with similar phenomena exhibited by individual organs, such as the extraordinary development of horns and spines in many of the extinct reptiles referred to (Fig. 147), the immense tusks of the babirusa (Fig. 187), and the gigantic and grotesque beak and "helmet" of the hornbill (Fig. 188).

The exuberant development of some organs of this kind may possibly be attributed to the action of sexual selection, and indeed our daily experience of our own species seems to warrant us in

believing that there is no limit to the grotesque results which may ensue from the unrestricted exercise of the æsthetic faculties of either sex, but it seems hardly reasonable to attempt to explain all such bizarre and monstrous productions in this manner.

In all the cases cited, and in many others which could be adduced, either the entire body or some particular organ appears to have acquired some sort of momentum, by virtue of which it continues to grow far beyond the original limits of utility, although




FIG. 187.—Head of *Babirusa alfurus*. (From Flower and Lyddeker's "Mammals Living and Extinct.")

perhaps in some cases a new use may be found which will assist the species in maintaining itself in the struggle for existence. An enormous increase of mere bodily size, however, seems in the long run to be always fatal to the race, whose place will be taken by smaller and presumably more active forms. The gigantic amphibians are all extinct, so are the really gigantic reptiles, and of the gigantic mammals only a couple of species of elephants and a few whales survive, all of which are being rapidly exterminated in competition with man.

There is perhaps some justification in recent developments of physiological science for the belief that a race of animals may acquire a momentum of the kind referred to; that some brake is normally applied to the growth of organisms and organs and that sometimes this brake is removed, leaving the organism to rush onwards to destruction like a car running away down hill.

Modern physiologists hold the view that the growth of the different parts of the animal body is regulated by internal secretions, or hormones, the products of various glands (*cf.* pp. 126, 192). Thus we know that hypertrophy of the pituitary body in man may lead to acromegaly, one of the symptoms of which is great




FIG. 188.—A Hornbill, *Buceros rhinoceros*, from North-West Borneo. (Drawn from a specimen in the British Museum, Natural History.)

enlargement of certain parts. The most dreadful of all the diseases to which human beings are subject, cancer, is essentially due to an unrestrained multiplication of cells, and consequent abnormal growth of tissue, which may very possibly be correlated with the extent to which some specific internal secretion is produced in the body. It also seems not unreasonable to suppose that the growth of the body may be normally inhibited or checked by specific secretions, and that in the absence of these it may continue far beyond the ordinary limits.

It is difficult to see any good reason why we should not apply this principle to the race as well as to the individual, and, paradoxical as it may appear, it even seems possible to explain both the growth of the organism as a whole and that of its various organs, beyond the limits of utility, as an indirect result of natural selection.

When a useful organ, such as the tusk of a wild boar, is first beginning to develop, or to take on some new function for the execution of which an increase in size will be advantageous, natural selection will favour those individuals in which it grows most rapidly and attains the largest size in the individual lifetime. If growth is normally checked and controlled by some specific secretion, or hormone, natural selection will favour those individuals in which the glands which produce this secretion are least developed, or at any rate least active. The process being repeated from generation to generation these glands (whatever may be their nature, and we use the term "gland" for any cell or group of cells which produces a specific secretion, whether recognizable as a distinct organ or not) may ultimately be eliminated, or at any rate cease altogether to produce the particular hormone in question. Moreover, this elimination may take place long before the organ whose growth is being favoured by natural selection has reached the optimum size. When it has reached this optimum it is certainly desirable that it should grow no larger, but is there now any means by which further growth can be checked? The inhibiting hormone is no longer produced; the brake has been removed, and further growth may be supposed to take place irrespective of utility, until, when the size of the organ gets too great to be any longer compatible with the well-being of the race, natural selection again steps in and eliminates the race. The same argument of course applies to the size of the body as a whole as well as to that of its constituent parts.

It may be thought that many of the bizarre and almost monstrous characters under discussion, such, for example, as some of the excrescences of the dermal armature in extinct reptiles (Fig. 147), can never have had any value as adaptations, and that therefore natural selection could never have encouraged them to increase so much in size as to get beyond her control. Here, however, the principle of correlation comes in. Just as many totally different organs are affected by disease of the

pituitary body, so the removal of the gland which controlled the development of some undoubtedly useful organ, such as a frontal horn, might at the same time permit the growth of all sorts of excrescences which have no adaptive significance.

Thus it appears not impossible that, the normal checks to growth being removed along certain lines by the action of natural selection, a definite direction might be given to the course of evolution, which the organism would continue to follow irrespective both of natural selection and of the principle of use and disuse.[1] The principle of the accumulation of surplus energy, discussed in the following chapter, may possibly account for the tendency to increase in size in the absence of any controlling agency.

In the present state of our knowledge, however, the above suggestions can only be regarded as tentative. They are doubtless open to much criticism, and it is unfortunately impossible to subject them to the crucial test of experiment.

The problem of the evolution of bizarre and monstrous organs should, perhaps, be regarded as only a special case of a more general problem, that of what may be termed the synchronism in the evolution of the different organs of the body. It is obvious that neither the individual development nor the phylogenetic evolution of any part of the body can be separately accelerated or retarded without danger of upsetting the necessary correlation between the part in question and other organs. Various facts well known to the zoologist indicate that the synchronism in question is sometimes disturbed. In the case of the New Zealand kiwi, for example (Fig. 113), there is an obvious discrepancy between the size of the egg and that of the bird which lays it. The egg is relatively enormous. It appears that either the egg has increased unduly in size or the bird has grown smaller in the course of evolution. The fact that in recent geological times New Zealand was the home of the gigantic moas seems to point to the latter hypothesis, though, from anatomical considerations, we cannot suppose that the moas were the actual ancestors of the kiwis. A somewhat similar case is afforded by the Graafian follicles in the ovaries of the mammalia, which seem to retain traces of their adaptation to the large, heavily yolked eggs which the ancestors of the mammals undoubtedly laid, and to be far too large for the microscopic eggs which they now produce. In this case the partial retention of the large size of the follicle may be explained by

[1] I have discussed this question at somewhat greater length in a paper read before the British Association for the Advancement of Science (*vide* Report of the Portsmouth Meeting, 1911).

its having assumed another function as a *corpus luteum* (*cf.* p. 126). The diminished egg of the mammal has also an unusually thick membrane, the so-called *zona radiata* (Fig. 71), in striking contrast to the very thin vitelline membrane that surrounds the enormous yolk (the real ovum) in the egg of a bird or reptile (Fig. 70), and it may be suggested that the amount of material secreted for the purpose of forming the egg-membrane has not diminished in proportion to the size of the egg.[1]

It is obvious that loss of synchronism in evolution might easily lead to such serious discrepancies as would result in the extinction of the organisms concerned, and natural selection has probably played an important part in maintaining the synchronism by weeding out all individuals in which such discrepancies became too pronounced.

We now come to a class of non-adaptive characters which seem to have no significance whatever from the point of view of the welfare of the organism, and with which, therefore, natural selection has probably had nothing whatever to do. We may perhaps call them "indifferent characters."

Amongst the microscopic Protozoa species are frequently distinguished from one another by minute differences in the form or ornamentation of the skeleton (compare Figs. 3 and 4). Different species of the genus Lagena (Fig. 4),[2] amongst the Foraminifera, for example, exhibit different sculptured patterns upon their flask-shaped calcareous shells. Are we to suppose that it is of any consequence to the gelatinous, Amœba-like inhabitant of the flask whether its shell be ornamented in one way rather than in another? Does one pattern help a unicellular foraminiferan or radiolarian more than another in the struggle for existence? The same argument applies to the extremely minute siliceous flesh-spicules or microscleres which occur scattered without order through the ground substance of many sponges, and the form of which is regarded by those who have studied the question as by far the most reliable guide, not only in the recognition of species, but also in the grouping of these species in genera and families. Take, for example, the wonderful chelæ (Fig. 189), characteristic of the family Desmacidonidæ. Different genera and species are dis-

[1] Another, and more familiar, instance is seen in the highly injurious overcrowding of the teeth in civilized man, due to the diminution of the size of the jaws out of proportion to the teeth which they contain.

[2] The two figures below the centre figure and two in the bottom right hand corner represent four species of Lagena.

tinguished by differences in the size, shape and number of the teeth of these microscopic and apparently useless structures—useless at any rate so far as their generic and specific characters are concerned, for what can it matter to the sponge whether the number of the teeth be three or more or less, or whether the teeth at the two ends of the spicule be equal or unequal? Yet, in the course of evolution, such characters as these have frequently arisen,




FIG. 189.—Siliceous Spicules (Chelæ) of Sponges. (After Ridley and Dendy, in "Challenger" Report.)

A. A', front and side views of chela of *Esperella lapidiformis*, × 360.
B. B', front and side views of chela of *Esperiopsis pulchella*, × 284.
C. C', front and side views of chela of *Cladorhiza* (?) *tridentata*, × 360.

probably in many cases as mutations which are handed down from generation to generation by heredity.[1]

We pointed out in an earlier chapter that the external form of the entire sponge is, in some cases at any rate, explicable as an adaptation to peculiar conditions of the environment. We saw this is the case of the curious "Crinorhiza" form (Fig. 170) which prevents the sponge from sinking into the soft mud or ooze on which it rests. Let us glance for a moment, however, at another deep sea sponge, *Esperiopsis challengeri*, dredged up by the "Challenger" Expedition from a depth of

[1] The reader should refer back to Fig. 90 for other forms of sponge spicules. See also Dendy, "The Tetraxonid Sponge-Spicule, a Study in Evolution" ("Acta Zoologica," Vol. II, 1921), for a full discussion and a possible mechanical explanation of certain spicule forms.

825 fathoms in the Malay Archipelago. In some respects this is the most remarkable sponge that has ever been discovered. Its form (Fig. 190) is absolutely unique and resembles rather that of some graceful plant than those of other sponges. It belongs to a group of sponges whose members occur mostly in much shallower water and are by no means distinguished by beauty or symmetry of shape. In spiculation, moreover, and other minute anatomical features, it exhibits no striking peculiarities; indeed, so closely does it agree with more ordinary species of Esperiopsis that it has not as yet been considered necessary to separate it generically. How then can we account for this wonderful form? Can we say that it is an adaptation to any special conditions of the environment? It hardly seems likely that this is the case, for we know that the relatives of this sponge get on well enough with all sorts of other forms, for the most part more or less irregular and ill-defined, and we know of nothing in the conditions under which it lives to make such a unique and beautiful form especially advantageous. The "Challenger" obtained no less than thirteen specimens of this sponge at the same place, and the form appears to be quite constant. No doubt the undisturbed condition of the sea at great depths favours symmetry of growth in sessile organisms like sponges, but why this particular and absolutely unique shape, so different from anything else that has ever been met with?




FIG. 190.—*Esperiopsis challengeri*, × ½. (After Ridley and Dendy, in "Challenger" Report.)

These are questions which we cannot answer, and it must suffice to point out that such cases can hardly be explained either as mutations or by the theory of natural selection. Many factors must combine in determining the course of evolution of any particular organism, and some of the characters which result from their interaction may perhaps have no more direct relation to the necessities of the organism in the struggle for existence than has the colour of a pebble to its continued existence on the sea-shore.

CHAPTER XXVIII

The mechanism of organic evolution: Summary and recapitulation—The ancestry of man.

IT is sometimes said that, in spite of all the recent advances in biological science, we are still unable to picture to ourselves the manner in which organic evolution has actually taken place. It may be suspected that those who hold this opinion are people who have occupied themselves too exclusively with some one particular aspect of the subject. We must bear in mind from the outset that in dealing with such a complex problem many factors have to be taken into account, and that widely different views on the question may be merely one-sided and not necessarily antagonistic.[1]

In the present chapter we shall endeavour, chiefly by way of recapitulation and summary, to show that it is quite possible to frame a consistent and intelligible, although still to a large extent hypothetical, account of the *modus operandi* whereby the present condition of the organic world has been attained. It is true that as yet we can only fill in the broad outlines of the picture as a whole, though a surprising amount of detail has already been accumulated with regard to certain portions, and there is little reason to fear for the ultimate result.

Taking for granted the origin of protoplasmic organisms by a gradual process of evolution from inanimate matter, we may say that there are three principal facts, or groups of facts, that have to be accounted for by any theory of organic evolution:—

(1) The fact that, on the whole, evolution has taken place in a progressive manner along definite and divergent lines.

(2) The fact that individual animals and plants are more or less precisely adapted in their organization and in their behaviour to the conditions under which they have to live.

(3) The fact that evolution has resulted in the existence on the earth to-day of a vast number of more or less well-defined groups of animals and plants which we call species.

[1] "To insist on ascribing complex results to single causes is the well-known vice of narrow and untrained minds" (Morley's "Life of Gladstone," Vol. II., p. 68).

To account for the first and most fundamental of these facts, some authorities have called in the aid of the principle of " orthogenesis," in accordance with which living organisms exhibit an innate tendency to undergo evolution in definite and apparently pre-determined directions. This appears, however, to be merely a re-statement of the fact without any sort of explanation.

Let us ask ourselves, first of all, why do organisms progress at all instead of remaining stationary from generation to generation ? To answer this question it is not necessary to go back to the beginning and consider the earliest phases in organic evolution, nor are we obliged to take as illustrations the lowest organisms known to us as existing at the present day. We may attack the problem at any stage of evolution, for at each stage progress is, or may be, still taking place. We may even begin by considering what is usually regarded as the highest stage of all, man himself, and indeed this seems the most natural thing to do, for we certainly know more about the conditions of progress in man than in any other organism. We refer, of course, at the moment, not to progress in bodily organization, but to progress in the ordinary sense of the word, the progress, say, of a family which rises in the course of a few generations from a position of obscure poverty to one of wealth and influence. It may perhaps be said that such a case has no bearing upon the problem of organic evolution in a state of nature, and that we ought to confine our attention to the evolution of bodily structure and function. We have, however, no justification for restricting the scope of our inquiry in this manner ; the contrast between man and nature is purely arbitrary ; man is himself a living organism, and all the improvements that he effects in his own condition are part of the process of evolution in his particular case. We may therefore accept this case as our first illustration of a principle that may be applied to organisms in general.

If we inquire into the cause of the progress of our human family we shall doubtless find that it is due to the accumulation of capital, or, as we should prefer to put it, to the accumulation of potential energy, either in the form of material wealth or of education. What one generation saves is available for the next, and thus each succeeding generation gets a better start in life, and is able to rise a little higher than the preceding one.

Every biologist knows, of course, that there are many analogous cases amongst the lower animals, and also amongst plants. The accumulation of food yolk in the egg has undoubtedly been one of

the chief factors in the progressive evolution of animals, although it has been replaced in the highest forms by a more effective method of supplying potential energy to the developing offspring. It may indeed be laid down as a general law that each generation, whether of animals or of plants, accumulates more energy than it requires for its own maintenance, and uses the surplus to give the next generation a start in life. There is every reason to believe that this has been a progressive process throughout the whole course of evolution, for the higher the degree of organization the more perfect do we find the arrangements for securing the welfare of the offspring.

We have already seen that the very essence of life is the alternate accumulation and dissipation of energy—the constant play of forces between the organism and its environment, and this process had its beginning in the original synthesis of living matter from inorganic constituents. We have no direct knowledge of the earliest living things, but the study of existing unicellular organisms throws some light upon the origin of the habit of accumulating surplus energy and handing it on to succeeding generations.

Professor H. S. Jennings, in his admirable work on the "Behaviour of the Lower Organisms,"[1] has described the experiments which have led him to the conclusion that certain Protozoa, such as Stentor, are able to learn by experience how to make prompt and effective responses to certain stimuli; that after they have been stimulated in the same way a number of times they make the appropriate response at once without having to go through the whole process of trial and error by which it was first attained. In other words, they are able by practice to perform a given action with less expenditure of energy. Some modification of the protoplasm must take place which renders the performance of an act the easier the oftener it has been repeated. The same is, of course, true in the case of the higher animals, and we express the fact most simply by saying that the animal establishes habits. From the mechanistic point of view we might say that the use of the machine renders it more perfect and better adapted for its purpose. In the present state of our knowledge we cannot go beyond this, but must content ourselves with recognizing the power of profiting by experience as a fundamental property of living protoplasm.

It would appear that this power of profiting by experience lies at the root of our problem, and that in it we find a chief cause of progressive evolution. Jennings speaks of the principle involved here

[1] Columbia University Press, 1906.

as the "Law of the readier resolution of physiological states after repetition," and, similarly, we may recognize a "Law of the accumulation of surplus energy" as resulting therefrom. Let us look at the case of the accumulation of food yolk by the egg cell a little more closely from this point of view. Every cell takes in a certain amount of potential energy in the form of food for its own use. If it leads an active life, either as an independent organism or as a constituent part of an organism, it may expend by far the greater part, possibly even the whole, of that energy upon its own requirements, but usually something is left over to be handed down to its immediate descendants. If, on the other hand, the cell exhibits very little activity and expends very little energy, while placed in an environment in which food is abundant, it will tend to accumulate surplus energy in excess of its own needs. Such is the case with the egg cells of the multicellular animals and plants. Moreover, the oftener the process of absorbing food material is repeated the easier does it become; in fact, the egg cell establishes a habit of storing up reserve material or food yolk. Inasmuch as it is a blastogenic character, there can be no objection to supposing that this habit will be inherited by future generations of egg cells. Indeed we are obliged to assume that this will be the case, for we know that the protoplasm of each succeeding generation of egg cells is directly continuous with that of the preceding generation. We thus get at any rate a possibility of the progressive accumulation of potential energy in the germ cells of successive generations of multicellular organisms, and of course the same argument holds good with regard to successive generations of Protista.

It would seem that progressive evolution must follow as a necessary result of the law of the accumulation of surplus energy in all cases where there is nothing to counteract that law, for each generation gets a better start than its predecessor, and is able to carry on a little further its struggle for existence with the environment. It may be said that this argument proves too much, that if it were correct all organisms[1] would by this time have attained to a high degree of organization, and that at any rate we should not expect to find such simple organisms as bacteria and amœbæ still surviving. This objection, which, of course, applies equally to other theories of organic evolution, falls to the ground when we consider that there must be many factors of which we know nothing which may prevent the establishment of progressive habits and render impossible

[1] Unless, of course, new germs of life are constantly being evolved from inorganic matter.

the accumulation of surplus energy. Many of the lower organisms, like many human beings, appear to have an inherent incapacity for progress, though it may be quite impossible for us to say to what that incapacity is due.

In the foregoing remarks attention has been concentrated upon the storing up of reserve material by the egg cells, and in so doing we have avoided the troublesome question of the inheritance of so-called acquired characters. It need not be supposed, however, that this is the only direction in which the law of the accumulation of surplus energy can manifest itself, for the accumulation of surplus energy by the body may be quite as important a factor in progressive evolution as the corresponding process in the germ cells themselves. The parents, in the case of the higher animals, may supply surplus energy, in the form of nutriment or otherwise, to the offspring at all stages of its development, and the more capital the young animal receives the better will be its chances in life, and the better those of its own offspring.

In all these processes, no doubt, natural selection plays an important part, but, in dealing with the accumulation of food material by the egg cells, one of our objects has been to show that progressive evolution would take place even if there were no such thing as natural selection, that the slow successive variations in this case are not chance variations, but due to a fundamental property of living protoplasm and necessarily cumulative.

Moreover, the accumulation of surplus energy in the form of food yolk is only one of many habits which the protoplasm of the germ cells may acquire in a cumulative manner. It may learn by practice to respond with increased promptitude and precision to other stimuli besides that of the presence of nutrient material in its environment. It may learn to secrete a protective membrane, to respond in a particular manner to the presence of a germ cell of the opposite sex, and to divide in a particular manner after fertilization has taken place.

Having thus endeavoured to account for the fact that progressive evolution actually occurs by attributing it primarily to the power possessed by living protoplasm of learning by experience and thus establishing habits by which it is able to respond more quickly to environmental stimuli, we have next to inquire what it is that determines the definite lines along which progress manifests itself.

Let us select one of these lines and investigate it as fully as the space at our disposal will permit, with a view to seeing whether it is

possible to formulate a reasonable hypothesis as to how evolution may have taken place. Let us take the line which we believe has led up to the evolution of air-breathing vertebrates. The only direct evidence at our disposal in such a case is, of course, the evidence of palæontology, but this is of an extremely fragmentary character, and we shall do well to confine ourselves to the ontogenetic evidence, which, although indirect, will be found sufficient for our purpose. One reason for concentrating our attention upon this aspect of the problem is that we may show that the recapitulation of phylogenetic history in individual development is a logical necessity if evolution has really taken place.

We may legitimately take the nucleated protozoon cell as our starting-point, for, whatever may have been the course of evolution that led up to the cell, there can be no question that all the higher organisms actually start life in this condition. We suppose, then, that our ancestral protozoon acquired the habit of taking in food material in excess of its own requirements, and of dividing into two parts whenever it reached a certain maximum size. Here we must, for the sake of simplicity, not only ignore the fact that even a protozoon is by no means a simple organism, but also that its division, usually at any rate, is a very complicated process. Each of the daughter cells presently separates from its sister cell and goes its own way as a complete individual, still a protozoon. It seems not improbable that the separation may be due to the renewed stimulus of hunger, impelling each cell to wander actively in search of food. In some cases, however, the daughter cells remain together and form a colony, and probably this habit has been rendered possible by a sufficient accumulation of surplus energy in the form of food yolk on the part of the parent rendering it unnecessary for the daughter cells to separate in search of food. One of the forms of colony met with amongst existing Protozoa is the hollow sphere, as we see it, for example, in Sphærozoum (Fig. 12) and Volvox (Fig. 11), and it is highly probable that the assumption of this form is due largely, if not entirely, to what are commonly called mechanical causes, though we are hardly in a position to say exactly what these causes may be. The widespread occurrence of the blastosphere or blastula stage in ontogeny is a sufficiently clear indication that the hollow, spherical protozoon colony formed a stage in the evolution of the higher animals.

By the time our ancestral organism has reached this stage, and possibly even before, a new complication has arisen. The cells of

which the colony is composed no longer remain all alike, but become differentiated, primarily into two groups, which we distinguish as somatic cells and germ cells respectively.

From this point onwards evolution ceases to be a really continuous process, but is broken up into a series of ontogenies, or individual life-histories, at the close of each of which the organism has to go back and make a fresh start in the unicellular condition, for the somatic cells sooner or later become exhausted in their conflict with the environment and perish, leaving the germ cells behind to take up the running.

We know that, if placed under suitable conditions, or, in other words, if exposed to the proper environmental stimuli, these germ cells will give rise to new organisms, like that in the body of which they were formerly enclosed. One of the necessary conditions is, with rare exceptions, the union of the germ cells in pairs to form zygotes or fertilized ova; but we may, in the first instance, for the sake of simplicity, leave out of account the existence of the sexual process and the results that follow therefrom, postponing the consideration of these to a later stage of our inquiry. Organic evolution must have taken place even if no such event as amphimixis had ever occurred.

What, then, may the germ cells be expected to do? How are they going to begin their development? In endeavouring to answer this question we must remember that the behaviour of an organism at any moment depends upon two sets of factors—the nature of its own constitution on the one hand, and the nature of its environment on the other. If these factors are identical for any two individual organisms, then the behaviour of these two individuals must be the same. If the germ cells of any generation are identical with those of the preceding generation, and if they develop under identical conditions, then the soma of the one generation must also be identical with that of the other. Inasmuch as they are parts of the same continuous germ plasm—leaving out of account the complications introduced by amphimixis—we may assume that the germ cells of the two generations are indeed identical in nearly every respect; but there will be a slight difference, due to the fact that those of the later generation will have inherited a rather larger supply of initial energy and a slightly greater facility for responding to stimuli of various kinds, for the gradual accumulation of these properties will have gone a stage further. The environment also will be very nearly identical in the two cases, and we know from experiment

that if it were not the organism could not develop at all, or would develop into a monstrosity.

Throughout the whole course of its ontogeny the organism must repeat with approximate accuracy the stages passed through by its ancestors, because at every stage there will be an almost identical organism exposed to almost identical stimuli. We may, however, expect an acceleration of development and a slight additional progress at the end of ontogeny as the result of the operation of the law of the accumulation of surplus energy and of the slightly increased facility in responding to stimuli. The additional progress, of course, will probably be so slight that from one generation to the next we should be quite unable to detect it, and doubtless there will be frequent backslidings due to various causes.

We can thus formulate a perfectly reasonable explanation of how it is that the egg first undergoes segmentation and then gives rise to a blastula resembling a hollow protozoon colony; it does so simply because at every stage it must do what its ancestors did under like conditions. We can also see that progressive evolution must follow from the gradual accumulation of additions at the end of each ontogeny, these additions being rendered possible by the better start which each individual gets at the commencement of its career.

Let us now glance for a moment at the next stage in phylogeny, the conversion of the hollow spherical protozoon colony into the cœlenterate type of organization, represented in ontogeny by the process of gastrulation. Here again it is probable that this process is explicable to a large extent upon mechanical principles. According to Rhumbler, the migration of endoderm cells into the interior of the blastula is partly due to chemotaxis and partly to changes of surface tension, which decreases on the inner side of the so-called vegetative cells owing to chemical changes set up in the blastocœl fluid.

We may at this point profitably ask the question, Is the endoderm thus formed an inherited feature of the organism? The material of which it is composed is of course derived from the egg cell continuously by repeated cell division, but the way in which that material is used by the organism depends upon the environment, and we know from experiment that modifications of the environment actually do produce corresponding modifications in the arrangement of the material. We know, for example, that the addition of salts of lithium to the water in which certain embryos are developing causes the endoderm to be protruded instead of invagi-

nated, so that we get a kind of inside-out gastrula, the well-known lithium larva.

It appears, then, that an organism really inherits from its parents two things: (1) a certain amount of protoplasm loaded with potential energy, with which to begin operations, and (2) an appropriate environment. Obviously the one is useless without the other. An egg cannot develop unless it is provided with the proper environment at every stage. Therefore, when we say that an organism inherits a particular character from its parents all we mean is that it inherits the power to produce that character under the influence of certain environmental stimuli.[1]

From this point of view the distinction between somatogenic and blastogenic characters really disappears, for all the characters of the adult organism are acquired afresh in each generation as a result of response to environmental stimuli during development. This is clearly indicated by the fact that you cannot change the stimuli without changing the result.

We need not discuss the phylogenetic stages through which the cœlenterate passed into the cœlomate type, the cœlomate into the chordate, and the chordate into the primitive vertebrate. We must admit that as yet we know nothing of the particular causes that determined the actual course of evolution at each successive stage. What we do know, however, about the influence of the environment, both upon the developing embryo and upon the adult, is sufficient to justify us in believing that every successive modification must have been due to a response on the part of the organism to some environmental change. Even if the external conditions remained practically identical throughout long periods of time, we must remember that the internal conditions would be different in each generation, because each generation starts with a slightly increased capital and carries on its development a little further under internal conditions modified accordingly, to say nothing of the influence exerted by the so-called "factors" that have accumulated in the germ cells during countless generations.

One of the most remarkable and distinctive features of the lower vertebrates is the presence of gill slits as accessory organs of respiration. These gill slits are clearly an adaptation to aquatic life. When the ancestors of the higher vertebrates left the water and took to life on land the gills disappeared and were replaced by lungs, adapted

[1] Compare Dr. Archdall Reid's suggestive essay on "Biological Terms" (*Bedrock*, January, 1914).

for air-breathing. The change must, of course, have been an extremely gradual one, and we get a very clear indication of how it took place in the surviving dipnoids, which have remained in this respect in an intermediate condition between the fishes and the higher amphibia, possessing and using both gills and lungs.

We also know that even the most highly specialised air-breathing vertebrates, which never live in water and never require gills or gill slits at all, nevertheless possess very distinct vestiges of gill slits during a certain period of their development. This is one of the most familiar illustrations of the law of recapitulation, and our reason for bringing it forward now is that it may serve to introduce a difficulty—perhaps more apparent than real—that arises in connection with such cases.

It might be argued that if gill slits arose in response to the stimuli of aquatic life, and if these stimuli are no longer operative in the case of air-breathing vertebrates, then gill slits ought not to be developed at any stage of their existence. This argument is, perhaps, sufficiently met by the following considerations.

At any given moment of individual development the condition of any organ is merely the last term of a series of morphogenetic stages, that is, stages in the evolution of its form and structure, while its environment at the same moment, which of course includes its relation to all the other parts of the body—is likewise merely the last term of a series of environmental stages. We have thus two parallel series of events to take into consideration in endeavouring to account for the condition of any part of an organism—or of the organism as a whole—at any period of its existence :—

$E_1\ E_2\ E_3\ .\ .\ .\ .$	E_n environmental stages.
$M_1\ M_2\ M_3\ .\ .\ .\ .$	M_n morphogenetic stages.

Ontogeny is absolutely conditioned by the proper correlation of the stages of these two series at every point,[1] and hence it is that any sudden change of environment is usually attended by disastrous consequences. Thus, after the fish-like ancestors of air-breathing vertebrates had left the water and become amphibians, they doubtless still had to go back to the water to lay their eggs, in order that the eggs might have the proper conditions for their development.

Obviously the environment can only be altered with extreme

[1] Compare what has been said in Chapter XXVII. on synchronism in the evolution of organs.

slowness, and one of the first duties of the parent is to provide for the developing offspring conditions as nearly as possible identical with those under which its own development took place. It is, however, inevitable that, as phylogenetic evolution progresses, the conditions under which the young organism develops should change. In the first place, the mere tendency to acceleration of development, to which we have already referred, must tend to dislocate the correlation between the ontogenetic series and the environmental series. Something of this kind seems to have taken place in the life cycle of many Hydrozoa, resulting in the suppression of the free medusoid generation and the gradual degeneration of the gonophore.[1] But it is probably in most cases change in the environment of the adult that is responsible for such dislocation.

To return to the case of the amphibians. At the present day some amphibians, such as the newts and frogs, still lay their eggs in water, while the closely related salamanders retain them in the oviducts until they have developed into highly organised aquatic larvæ, or even into what is practically the adult condition. Kammerer has shown that the period at which the young are born can be varied by changing the environment of the parent. In the absence of water the normally aquatic larvæ of the spotted salamander may be retained in the oviduct until they have lost their gills, and they are then born in the fully developed condition, while, conversely, the alpine salamander, whose young are normally born in the fully developed state, without gills, may be made to deposit them prematurely in water in the larval, gill-bearing condition.

There can be no doubt that the ancestral amphibians laid their eggs in water in a completely undeveloped state. The habit of retaining them in the body during their development must have arisen very gradually in the phylogenetic history of the salamanders, the period for which the young were retained growing gradually longer and longer. It is obvious that this change of habit involves a corresponding change in the environmental conditions under which the young develop, and in cases in which the young are not born until they have reached practically the adult condition this change directly affects practically the whole ontogeny. We may say that the environmental series

$E_1\ E_2\ E_3\ \ldots\ \ldots\ \ldots\ \ldots\ \ldots\ E_n$ has become
$E_1'\ E_2'\ E_3'\ \ldots\ \ldots\ \ldots\ \ldots\ \ldots\ E_n'$,

[1] *Vide* pp. 121—123.

and as the change of environment must produce its effect upon the developing organism the morphogenetic series

$M_1\ M_2\ M_3\ .\ .\ .\ .\ .\ M_n$ will have become
$M_1'\ M_2'\ M_3'\ .\ .\ .\ .\ .\ M_n'$.

We must remember that throughout the whole course of phylogenetic evolution this series is constantly lengthening, so that what was the adult condition at one time becomes an embryonic stage in future generations, and that the series thus represents not only the ontogeny, but also, though in a more or less imperfect manner, the phylogeny of the organism.

The character of each stage in ontogeny must depend upon (1) the morphological and physiological constitution of the preceding stage, and (2) the nature of the environment in which development is taking place. We cannot, however, distinguish sharply between these two sets of factors, for, in a certain sense, the environment gradually becomes incorporated in the organism itself as development proceeds, each part contributing to the environment of all the remainder, and the influence of this internal portion of the environment ever becoming more and more important.

The whole process of evolution depends upon changes of environment taking place so gradually that the necessary self-adjustment of the organism at every stage is possible. In the case of our amphibia the eggs could probably undergo the first stages of development, the preliminary segmentation, within the oviduct of the parent just as well as in the water, for in both cases they would be enclosed in their envelopes, and the morphological differences between the early stages in the two cases might be expected to be quite insignificant. But it must be the same at each term of the series, for each term is built upon the foundation of the preceding one, and the whole process takes place by slow and imperceptible degrees.

It is true that by the time we reach the formation of the vestigial gill slits in the embryo of one of the higher vertebrates the environmental conditions are very different from those under which gill slits were developed in their aquatic ancestors. But what then? Are not the gill slits also very different? The changed environment has had its effect. The gills themselves are never developed, and the gill slits never become functional; moreover, they disappear completely at later stages of development, when the conditions of life become still more different and their presence would be actually

detrimental to their possessor. The embryo with the vestigial gill slits is, as a whole, perfectly well adapted to its environment, though the gill slits themselves have ceased to be adaptive characters. They have not completely disappeared at all stages because they have come to form an integral part of the structure of the developing body, closely correlated with other parts, and can only be removed gradually by re-adaptation to changed conditions of life, as they are. (We need hardly point out that the term gill slit must be taken to include the tissues by which the slit is immediately surrounded and apart from which the slit would have no existence.)

The chief difficulty in forming a mental picture of the manner in which organic evolution has taken place, and especially in accounting for the phenomenon of recapitulation in ontogeny, which is merely another aspect of the same problem, arises from attempting to take in too much at once. There is no difficulty in understanding how any particular stage is related to the corresponding stage in the previous generation, and the whole series of stages, whether looked at from the ontogenetic or from the phylogenetic point of view, can be nothing else but the sum of its successive terms.

It will be convenient, before going further, to sum up the results at which we have so far arrived from the point of view of the theory of heredity. We have as yet seen no reason to distinguish between somatogenic and blastogenic characters. All the characters of the adult animal are acquired during ontogeny as the result of the reaction of the organism to environmental stimuli, both internal and external. All that the organism actually inherits is a certain amount of protoplasm—endowed with a certain amount of energy—and a certain sequence of environmental conditions. In so far as these are identical in any two successive generations the final result must be identical also, the child must resemble the parent; in so far as they are different the child will differ from the parent, but the differences in environment cannot be very great without preventing development altogether.

So far, it is clear, there has been no need to think of the germ cells as the bearers of material factors or determinants that are responsible for the appearance of particular characters in the adult organism; nor yet to suppose that they are, to use the phraseology of the mnemic theory of heredity, charged with the memories of past generations. They have been regarded as simple protoplasmic units, and the entire ontogeny has appeared as the necessary result of the reaction between the organism and its environment at each

successive stage of development. This cannot, however, be a complete explanation of ontogeny, for if it were we should expect all eggs, when allowed to develop under the same conditions from start to finish, to give rise to the same adult form, and this we know is not the case. We know also, from observation and experiment, that the egg is in reality by no means a simple thing, but an extremely complex one, and that different parts of the egg may be definitely correlated with corresponding parts of the adult body. The differentiation of the protoplasmic unit into cytoplasm and nucleus, though not yet definitely accomplished in the Bacteria, must have taken place at a very early stage in evolution, and, thenceforth, the nucleus seems to have played the leading part in cell division and development. Not, however, an exclusive part, for it has been demonstrated in certain cases that the egg contains special "organ-forming" substances definitely located in the cytoplasm, and that if these are removed corresponding parts of the organism into which the egg develops will be missing. We know also that the nucleus of a germ cell of either sex contains, in its chromosomes, factors or determinants which also have been definitely correlated, in certain cases, with special features of the adult organism.

All these differentiations of the germ cells are, no doubt, fundamentally of a chemical nature, and they may be regarded as internal sources of stimuli which play their part in controlling the development of the body; they form, in short, a very important constituent of the internal environment.

Before we can hope to complete our mental picture of the manner in which organic evolution has taken place, if only in outline, it is evident that we must be able to account for the great complexity of structure and chemical composition which the germ cells themselves have managed to acquire, and also to form some idea of the effect of this complication upon the development of both the individual and the race.

We must consider the origin of cytoplasmic and nuclear complications of the germ cells separately. In the first case we have to remember that during oogenesis the egg cell grows to a relatively large size by absorbing nutrient material from the body in which it is enclosed. It is this nutrient material that is used for building up the deutoplasm or food yolk. There is good reason for believing that the character of this nutrient material will change, during the course of evolution, *pari passu* with the changing character of the organism by which it is supplied. Doubtless the change is of a chemical

nature, for we know from precipitin experiments that the body fluids of closely allied species, or even of the two sexes of the same species, do exhibit distinctly recognisable differences in chemical composition. It also appears highly probable, if not certain, from such experiments as those of Agar upon *Simocephalus*,[1] that substances which bring about conspicuous modifications of bodily structure, may, at the same time, be absorbed and stored up by the egg cells so as to bring about corresponding changes in the adults into which the eggs develop.

There seems therefore to be no great difficulty in comprehending, at any rate in a general way, how the cytoplasm of the egg may become the repository of definite chemical substances, possibly to be classed with the hormones and enzymes, which will influence the development in a particular manner as soon as the appropriate conditions arise.

With regard to the complication in nuclear structure we have already said so much in previous chapters that it is needless to dwell upon it in detail in this place. The important thing to remember is that it seems to have arisen mainly through the process of amphimixis, the mingling of the chromatin substance of male and female pronuclei which results from the conjugation of the germ cells. The chromatin must, as a result of this process, become progressively heterogeneous from generation to generation, as Weismann has shown.[2] It would be premature to speculate as to how the separate chromosomes and the individual factors which they contain may have originated. In the course of evolution chemical and physical changes take place in the living protoplasm about which we know no more than we do about the origin of protoplasm itself. These changes have led to the segregation of modified particles of chromatin as distinct units, each exercising its special influence upon the developing organism. The modifications that have arisen along different lines of descent are, within limits, shuffled and recombined in the processes of maturation and fertilization. In view of these facts, it seems desirable to modify our usual conception of organic evolution as simply tree-like, and to conceive of each separate branch of the phylogenetic tree as being composed of a very complicated network, due to the repeated union of male and female lines of descent. The same result would be expressed in human pedigrees if the female as well as the male line of descent were taken into account.

[1] See p. 209.
[2] See p. 169.

The differentiation of the chromatin into discrete factors capable of undergoing new permutations and combinations in the sexual process, and each influencing the developing organism in its own particular way, has given rise to the appearance of separately heritable unit characters and all the well-known Mendelian phenomena attendant upon hybridization. Wonderful as they are, however, the Mendelian results by no means justify us in regarding the organism as being entirely built up of such unit characters, for the characters in question appear to be mere modifications of what might perhaps be regarded as the normal condition. If there were no sexual process the term separately heritable unit characters would have no meaning, but there is no difficulty in conceiving of progressive evolution as having taken place under such circumstances, though of course the results would have been very different.

But evolution is not only progressive, it is also divergent, and we may safely attribute this divergence to differences in the internal and external conditions of life. One of the most remarkable features of organic evolution is that it results in the adaptation of each kind of organism to its own particular environment, and this adaptation, as we have said, is one of the chief phenomena that have to be accounted for. In previous chapters we have shown how Darwin and Wallace met this difficulty by the theory of natural selection. Variation affords the material for selection, and in the struggle for existence all those individuals which are not sufficiently well adapted are eliminated. Favourable variations are handed down by heredity, and thus progress is secured along definitely adaptive lines.

Of course natural selection plays its part, as it must in all cases, even in the inorganic world, and in many cases that part has evidently been an extremely important one. But perhaps even more important than natural selection is what Baldwin [1] has termed "Functional Selection," selection by the organism itself, out of a number of possible reactions, of just those that are required to meet any emergency. As Baldwin puts it, "It is the organism which secures from all its overproduced movements those which are adaptive and beneficial." Natural selection is here replaced by intelligent selection, if, that is to say, we agree with Jennings [2] that we cannot make a distinction between the higher and the lower organisms in this respect, and that all purposive reactions, or adjustments, are essentially intelligent.

[1] "Development and Evolution" (New York, 1902), p. 87.
[2] "Behaviour of the Lower Organisms" (New York, 1906), pp 334, 335.

Surely that much-abused philosopher, Lamarck, was not far from the truth when he said, "The production of a new organ in an animal body results from a new requirement which continues to make itself felt, and from a new movement which this requirement begets and maintains." Is not this merely another way of saying that the individual makes adaptive responses to environmental stimuli? Where so many people fall foul of Lamarck is with regard to his belief in the inheritance of acquired characters. But in speaking of acquired characters Lamarck did not refer to such modifications as mutilations; he was obviously talking of the gradual self-adjustment of the organism to its environment.

We are told, of course, that such adjustments will only be preserved so long as the environmental stimuli by which they were originally called forth continue to exercise their influence. Those who raise this objection are apt to forget that this is exactly what happens in evolution, and that the *sine qua non* of development is the proper maintenance of the appropriate environment, both internal and external. Natural selection sees to it that the proper conditions are maintained within very narrow limits.

We still have to consider the question, How is it that organic evolution has led to the formation of those more or less well-marked groups of organisms which we call species? We have to note in the first place that there is no unanimity of opinion amongst biologists as to what a species is. Lamarck insisted that Nature recognizes no such things as species, and some people at the present day seem to be still of the same opinion. In practice, however, every biologist knows that there are natural groups to which the vast majority of individuals can be assigned without any serious difficulty. Charles Darwin maintained that such groups arise, under the influence of natural selection, through gradual, divergent evolution and the extinction of intermediate forms. To-day we are told by de Vries that species originate as mutations which propagate themselves without alteration for a longer or shorter period, and by Lotsy that they originate by the crossing of more or less distinct forms, though this latter theory leaves quite unsolved the problem of where the original forms that crossed with one another came from.

The origin of species is evidently a different problem from that of progressive evolution. We can hardly doubt, however, that Darwin was right in attributing prime importance to divergence and the disappearance of connecting links. It is obvious that this process must give rise to more or less sharply separated groups of individuals

to which the term species may be applied, and that the differences between these species must be attributed ultimately to differences in the response of the organism to differing conditions of the environment. It may be urged that inasmuch as different species are often found living side by side under identical conditions the differences between them cannot have arisen in this way, but we may be quite certain that if we knew enough of their past history we should find that their ancestors had not always lived under identical conditions.

The case of flightless birds on oceanic islands is particularly instructive in this connection. The only satisfactory way of explaining the existence of such birds is by supposing that their ancestors had well-developed wings by the aid of which they made their way to the islands from some continental area. The conditions of the new environment led to the gradual disuse and consequent degeneration of the wings. It would be absurd to maintain that any of the existing flightless birds are specifically identical with the ancestral flying forms from which they are descended, and it would be difficult to believe that the flightless species arose by mutation or by crossing; indeed, the study of island faunas in general indicates very clearly that the *prevention* of crossing, by isolation, has been one of the chief factors in the divergence of lines of descent and the consequent multiplication of species, and, as we have already seen, even within the same geographical area an identical result may be produced by mutual sterility, which is a cause rather than a result of specific distinction.

Species, then, may clearly arise by divergent evolution under changing conditions of the environment, and may become separated from one another by the extinction of intermediate forms. The environmental stimuli (including, of course, the body as part of its own environment) may, however, act in two different ways: (1) upon the body itself, at any stage of its development, tending to cause adaptation by individual selection of the most appropriate response; and (2) upon the germ plasm, causing mutations or sudden changes, which appear to have no direct relation whatever to the well-being of the organism in which they appear, but to be purely accidental. Such mutations are, of course, inherited, and, inasmuch as the great majority of specific characters appear to have no adaptive significance, it seems likely that mutation has had a great deal to do with the origin of species, though it may have had very little to do with progressive evolution.

Similarly with regard to hybridization, we know that numbers

of distinct forms, that breed true, may be produced in this way, but they are simply due to recombinations of mutational characters in the process of amphimixis, and have very little bearing upon the problem of evolution. If we like to call the new groups of individuals that originate thus " species," well and good, but it only means that we give that name, as a matter of convenience, to any group of closely-related individuals which are distinguished by recognizable characters from the individuals of all other groups, and which hand on those characters to their descendants so long as the conditions remain the same. This, perhaps, is what we should do, and just as we have learnt to regard individuals as the temporary offspring of a continuous stream of germ plasm, so we may regard species as the somewhat more permanent, but, nevertheless, temporary, offshoots of a continuous line of progressive evolution. One species does not arise from another species, but from certain individuals in that species, and when all the individuals become so specialized as to lose their power of adaptation, then changes in the environment may result in the extinction of that line of descent.

It is hardly necessary to point out that no explanation that we are able to give regarding the causes of either phylogenetic or ontogenetic evolution can be complete and exhaustive. Science can never hope to get to the bottom of things in any department of knowledge ; there is always something remaining beyond our reach. If we are asked why an organism chooses the most appropriate response to any particular stimulus, we may suggest that this is the response that relieves it from further stimulation, but we cannot say how it learns to choose that response at once in preference to all others. If we are asked to account for some particular mutation, we may say that it is due to some modification in the constitution or distribution of the chromosomes in the germ cells, but even if we knew exactly what that modification was, and could express it in chemical terms, we could not really say why it produces its particular result and no other, any more than we can say why magnesium chloride produces its remarkable effect on the *Fundulus* larva (Fig. 75), though we may hope to learn more about the matter some day.

There is one group of ontogenetic phenomena in particular that seems to defy all attempts at mechanistic interpretation. We refer to the phenomena of restitution, the power which an organism possesses of restoring the normal condition of the body after it has been violently disturbed by some external agent. The fact that a newt is able to regenerate its limbs over and over again after they

have been removed, or that an echinoderm blastula may be cut in half and each half give rise to a perfect larva, is one of the most surprising things in the domain of biological science. We cannot, at present at any rate, give any satisfactory mechanistic explanation of these facts, and to attribute them to the action of some hypothetical Entelechy, after the manner of Professor Hans Driesch, is simply an admission of our inability to do so. We can only say that in the course of its evolution each organism acquires an individuality or wholeness of its own, and that one of the fundamental properties of living organisms is to maintain that individuality. They are able to do this in a variety of ways, and can sometimes even replace a lost organ out of material different from that from which the organ in question is normally developed, as in the case of the regeneration of the lens of the eye from the iris in the newt. That there must be some mechanism involved in such cases is, of course, self-evident, and we know that that mechanism may sometimes go wrong and produce monstrous and unworkable results ; but it is equally evident that the organism must possess some power of directing the course of events, so as generally to secure the appropriate result ; and it is just this power of directing chemical and physical processes, and thus employing them in its own interests, that distinguishes a living organism from an inanimate object.

The application of the principles of organic evolution to the problem of the origin and progress of the human race cannot be dealt with adequately in the present volume, while at the same time we cannot altogether ignore it, for not only is it in man himself that we find the most remarkable illustration of what has been accomplished by evolution, but the future progress of mankind must depend in large measure upon the correct understanding of the principles in question.

Buffon, more than a century ago, pointed out the close resemblance in anatomical structure between man and the higher apes, and it is clear that both he and Lamarck were only prevented by religious scruples from definitely maintaining the origin of the human species from ape-like ancestors, a view which at the present time is almost universally accepted amongst scientific men.[1] This reluctance to admit the obvious relation-

[1] Professor Wood Jones, however, has brought forward good reasons for believing that the divergence of the human line of evolution took place much earlier than

ship of the human species with the apes was one of the evil results of the intellectual dishonesty and obscurantism of the Middle Ages. If we go back to the days of Carthage, we find that the explorer Hanno did not hesitate to speak of the "gorillas"[1] which he met with in Africa as hairy men and women of the woods, and although this was doubtless going too far in the opposite direction, it shows not only that he recognized the relationship but also that he approached the question with a mind entirely free from prejudice.

Man is one of the latest products of organic evolution, and his appearance upon the scene apparently does not date further back than Pliocene times. It is said that flint flakes of human workmanship have been discovered in early Pliocene deposits of Burmah, but perhaps the earliest actually human fossil so far known is a lower jaw of very massive form which was found in a deposit of probably early Pleistocene age near Heidelberg, and described by Schœtensack in 1908 under the name *Homo heidelbergensis*. This name implies that in the opinion of its author the fossil man of Heidelberg was generically, but not specifically, identical with the human beings which now exist. The question of the distinction of species in the genus Homo, however, is, as in most other genera, a very difficult one, and opinions are divided as to whether only one or several species should be recognized amongst the existing races of mankind.[2]

So close is the anatomical agreement between the genus Homo and the higher apes that there is little room for connecting links between them, the difficulty being rather to find any definite characters by which they can be separated than to discover reasons for bringing them together. Nevertheless, the gap, small as it is, has been filled by the discovery, by Dr. Dubois in 1894, of the remains of a semi-human, ape-like creature, to which the name *Pithecanthropus erectus* has been given. These remains were found in Pliocene strata in the

is generally supposed. He traces the ancestry of man directly back to a lemur-like form related to the existing Tarsius, and believes that the anthropoid apes belong to another branch, so that they are by no means closely related to human beings. See his lecture on "The Origin of Man" in "Animal Life and Human Progress" (London, Constable & Co., 1919), for an interesting discussion of the whole problem.

[1] Probably really chimpanzees.

[2] More recently a possibly human skull from early Pleistocene beds at Piltdown, in Sussex, has been described under the name *Eoanthropus dawsoni*, which implies that the describer, Dr. Smith Woodward, is of opinion that it represents a type generically, as well as specifically, distinct from existing human beings (*Homo sapiens*).

island of Java and consist of a portion of a cranium, a thigh bone and two molar teeth.[1]

In deposits of later Pleistocene age undoubtedly human remains become fairly abundant, and are found associated with the bones of other mammals, of which many, such as the mammoth, the cave bear and the woolly rhinoceros, are now extinct.

The chief factors which contributed towards the gradual transformation of ape-like into human creatures were doubtless the same as those which have operated in the evolution of other branches of the animal kingdom, namely, the efforts which the ancestral forms were obliged to make in order to maintain themselves in the struggle for existence and the natural selection of favourable variations. In no group of the animal kingdom do we see better illustrated the importance of Lamarck's principle of the effect of changed habits upon bodily organization.[2]

The anthropoid ancestors of man were undoubtedly, like the existing Simiidæ, arboreal in habit. Their limbs, whose primitive pentadactyl structure indicates their origin from some little-specialized mammalian type, had ceased to be used exclusively as organs of locomotion on the ground and become adapted for climbing trees. Hence the opposable toe and thumb, which enabled their possessor to obtain a firm grasp of the branches. In the existing apes hand and foot are very similar, and both, as regards function, partake as much of the nature of hand as of foot, whence the name "Quadrumana" applied to the group by the older naturalists. In many of the lower apes or monkeys a long prehensile tail, which can be twisted round the branches, is of great assistance to the animals in their arboreal habits, but in the higher forms, such as the chimpanzee, the gorilla and the orang utan, the tail has already disappeared.

These tailless forms are still mainly arboreal, but when they have occasion to come to the ground they assume a semi-erect posture in locomotion. In walking they usually put their hands to the ground, but generally resting upon the backs of the fingers, instead of upon the palms as in the lower apes.[3] Hence in these

[1] Some authorities regard these remains as truly human. The difference of opinion is itself very instructive.

[2] Darwin, notwithstanding what he says in the sixth edition of the "Origin of Species" about the effects of use and disuse (quoted on p. 403), denies, in the "Descent of Man" (Ed. 2, p. 619), that man has risen through his own exertions. I can see no reason for such a pessimistic view.

[3] *Vide* Beddard, "Mammalia" (Cambridge Natural History, Vol. X), p. 570.

large old-world apes the hands and feet are to some extent differentiated from one another.

The next step in the evolution of man was probably the gradual abandoning of arboreal habits and the assumption of a more completely erect attitude during locomotion. This appears to have been the real starting point of his human career. It was this change of habit which led to those structural modifications required to balance the body properly in its new position, and to the further differentiation between hand and foot, the latter being used to the complete exclusion of the former as an organ of locomotion and at the same time losing its prehensile character, so that one of the chief distinguishing features between man and the higher apes is that in man the great toe has ceased to be opposable.

In this way the hand was completely set at liberty for the purposes of a prehensile organ. It was, however, no longer used, as in the apes, chiefly for laying hold of branches in climbing and for conveying food to the mouth, but more for grasping loose objects and converting them into weapons or tools for different purposes. Hanno observed that the anthropoid apes which he met with in Africa defended themselves with stones, so that we can hardly say that the use of tools or weapons is an exclusively human attribute; but the hand of man is undoubtedly one of his most characteristic features, and by its aid man has been able to make for himself an unlimited number of what are really additional organs, derived not from his own body but from his environment.

To the experience gained by the exercise of the hands in so many different ways must also be attributed in large measure the extraordinary mental and moral development which, more than anything else, separates mankind from the apes. The constant exploitation of the environment stimulated and exercised the brain, which in turn suggested methods of employing the hands and the tools which they had constructed to ever greater advantage; and thus both hand and brain progressed until they attained their present wonderful state of efficiency.

The development of the brain has, however, long since taken the lead in human evolution and, considering the immense difference in intellectual capacity, it is surprising that there should be so little obvious structural difference between the brain of man and that of the higher apes. As Huxley has pointed out :—

"It is only in minor characters, such as the greater excavation of the anterior lobes, the constant presence of fissures usually absent in man, and the different disposition and proportions of some convolutions, that the Chimpanzee's or the Orang's brain can be structurally distinguished from Man's."[1]

Intellectual capacity appears, however, to depend mainly upon the size of the cerebral hemispheres, which is doubtless correlated with the number of nerve cells present, and in this respect the human brain is far in advance of that of any ape.

One of the most important characters which differentiate mankind from the apes is the faculty of articulate speech, but even this undoubtedly had its beginnings in the inarticulate sounds made by ape-like ancestors, either as spontaneous expressions of their emotions or as a means of communicating more or less definite ideas to one another. The development of speech provided a new means for the transmission of experiences from one generation to the next, and as a consequence knowledge began to accumulate in the minds of the human race. When oral tradition gave place to the establishment of written records, and methods were invented for the indefinite multiplication of these, the accumulation of knowledge took place at a much more rapid rate and it became possible for every human being, at any rate in civilized communities, to benefit from the experience of all his fellow men. The acceleration of intellectual and moral progress which has been brought about in this way has led to results which may well have deluded man into the belief that he is the centre of the universe and that between himself and the lower animals there is a great gulf fixed.

Man has indeed acquired a degree of control over his environment and over his own destiny which distinguishes him from any of the lower animals, but at the same time the conditions of his life have become far more complex and the young, at any rate in civilized communities, have to go through a long course of education before they are fit to enter upon the struggle for existence on their own account. Amongst the lower animals all, or almost all, the faculties necessary for existence are directly inherited from the parents, incorporated in the organism itself, but man inherits in this way only a relatively small proportion of the powers which he requires to carry on his life.

[1] Huxley, "Man's Place in Nature," p. 140 (Collected Essays, Vol. VII).

The immense advance which civilized man has made since he parted company with his ape-like progenitors is shown, not only by the fact that he has already to a large extent subjugated the remainder of the organic world and directed the forces of inanimate nature into new channels to serve his own purposes, but also by the intelligent forethought which he exercises for the future welfare of his own race. At the present time this forethought is being exercised in new directions, and a determined effort is being made to apply our knowledge of the principles of organic evolution to the furtherance of human progress. In spite of many differences of opinion, such as that which still prevails with regard to the relative importance of breeding and education, we have undoubtedly arrived already at many results which are of vital significance in this connection, and the intelligent application of scientific principles must here, as always, lead to further progress. We cannot, however, control the future of the human race until we have familiarized ourselves with the past, and learned to recognize the part played by the numerous different factors which have been concerned in the evolution, not only of mankind, but of the whole organic world.

It must always be remembered that the problem before us is one of extreme complexity, and that we cannot afford to neglect any of the factors involved. Above all, we must avoid dogmatizing on an insufficient basis of fact. If, for example, the very modern doctrine of the non-inheritance of acquired characters is allowed to influence the actions of men and women, and if, after all, this doctrine should prove to be erroneous, as seems highly probable at the present time, the attempt to apply biological principles to the welfare of humanity may well end in disaster. The penalty which each generation has to pay, in regard to bodily and mental organization, for the mistakes and misfortunes of its ancestors, may, in most cases, be a very small one; but if there is any penalty at all, and if the mistakes are continued from generation to generation, it will surely be a cumulative one.

In dealing with problems of this kind a rational conservatism, with a mind always open to conviction, seems the only safe attitude to adopt.

*

INDEX

A.

Abbreviation of ontogeny, 284
abiogenesis, 222, 223
Acacia pycnantha, seedling, Fig. 134
acacias, life-history, 291
Acanthodes, 302, Fig. 140
acceleration of development, 437, 440
accessory
  chromosomes, 135
  idioplasm, 166
accretion, 20
accumulation of surplus energy, 426, 431—434
achromatic figure, 74
acquired characters
  and human progress, 454
  Bordage on, 204
  Brewer on, 206, 208
  Buffon on, 203, 378, 379
  Charles Darwin on, 196—198, 404
  de Vries on, 417
  Eigenmann on, 205
  Erasmus Darwin on, 383
  inheritance of, 196—214, 438, 442
  Lamarck on, 196, 390, 391, 393
  meaning of term, 201, 202
  Semon on, 203, 204
  Sumner on, 205
  Weismann on, 196, 201, 202
actinula larva, 122
activity of male, 84, 85
adaptation, 345—375, 445
  and design, 219
  and fluctuating variation, 417, 418
  and mutation, 417, 418
  and natural selection, 402, 418
  average, 214
  embryonic, 278
  Erasmus Darwin on, 383, 384
  in animals, 345—360
  individual, 214
adaptation—*continued*
  in inorganic world, 406
  in leaves of acacias, 291
  in plants, 361—375
  mutual, 417, 418
  resulting from survival of fittest, 402
  Robert Chambers on, 394, 395
adipose tissue, 56, Fig. 19
æsthetic
  development of man influenced by insects, 375
  sense in courtship, 360
affinities, natural, 239, 240
after-effects, 215
Agar, 209, 213, 444
age
  of habitable earth, 296—298
  of ocean, 297
aggregate species, 235
aggressive resemblance, 348
Agnatha, 302
Agnostus princeps, Fig. 136
air-breathing vertebrates, origin, 267
ala spuria, 316
albumin, 23
alcoholism, 157, 165
alimentary canal, 124
allantois, 281
allelomorphs, 180, 186
aloes, 361
Alpine plants, 204, 273, 361
Alps, Arctic vegetation on, 344
alternation of generations, 101
  in aphides, 144
  in cœlenterates, 121
  in ferns, 101—106
  in flowering plants, 106—112
alternative characters, 176
Amauris niavius, 357, Fig. 179
Amblyopsis, 205
ambulatory
  appendages of arthropods, 257, 258
  legs of vertebrates, 246
Ameghino, 264

amitotic nuclear division, 80, Fig. 36
in Copromonas, 83
amnion, 281
Amœba, 12—21, Fig. 2
mitosis in, 79
sensitive to stimuli, 215
Amphibia,
evolution of, 440
geological range, 295
limbs, 246
origin, 303, 304
amphimixis, 146, 169, 170, 444, Fig. 76
and variation, 171
Amphioxus,
adult, 277, 278, Fig. 120
early development, 45—48, 276, Fig. 13
free swimming embryo, 282
ovum, 140
Amphisbænidæ, 261
Amphitherium, 313
anabolism, 9, Fig. 1
analogy, 246, 258
anatomy, evidence afforded by, 243—273
ancestral history, 240
Anchitherium, 321
Ancon sheep, 154
Andalusian fowls, blue, 180, 181
Andrews, C. W., 323
androœcium, 106
anemophilous flowers, 111, 364
Anguis fragilis, 261, Fig. 107
anisogamous conjugation, 84
anisogamy in Fucus, 101
Anomodontia, 307
Antarctic continent, 339
anteaters, 344
Antedon,
hybridization in, 172
recapitulation in development, 284, 286, Figs. 125, 126
antheridia
of Fern, 103, 104, Fig. 51
of Fucus, 100, Fig. 47
antheridial cell of pollen grains, 108, Fig. 54
anthers, 107
antibodies, 210, 211
anticryptic colouration, 348
antiquity of man, 450, 451
antitoxins, 211
antlers, 125
apatetic colours, 347
apes,
Buffon on, 378, 379
and man, Buffon on, 381
Lamarck on, 393
relationship of, 449—453
aphides, parthenogenesis in, 143
Aphrodite, story of, 222
apogamy in ferns, 105
aposematic colouration, 353
Apteryx, 269, Figs. 113, 114
Apus, dispersal of, 338
Archæopteryx, 310, 316—318, Fig. 153
archegonium
of Fern, 103, 104, Fig. 52
of flowering plant, 108
architype, 243
Arctic
climate, retreat of, 344
vegetation on Alps and Pyrenees, 344
areas of distribution, 330, 331, 341
Argus pheasant, 360
Aristotle, 163, 396
arm of man, 248, 249, Fig. 96
armadillos, 344
Arrhenius, 221
Artemia, chromosomes, 73
Arthropoda, limbs, 257, 258
arthropods and vertebrates, 266
artificially produced characters, 156, 157
artificial
parthenogenesis, 144—147
selection, 413—417
and fertility, 421, 422
artiodactyl limbs, 252, Fig. 100
Arum, fertilization, 366
Ascaris,
chromosomes in, 73
fertilization of egg, 131, Fig. 64
mitosis, 79
origin of germ cells, 129
ascidian, 288, Figs. 131, 132
degeneration in, 410
asexual reproduction
in Eudorina, 91
in Hydra, 116
in Obelia, 119
in Pandorina, 89
Aspidium, Figs. 48, 50
assimilation, 10, 16
asters in mitosis, 71
atavism, 272, 273

attraction
of gametes, 143
in Coccidium, 141, 142
in ferns and mosses, 141, 142
in Spirogyra, 142
of sexes, 125–127
sphere, 71
Aucuba, male and female plants, 111
Aurelia, meristic variation in, 149
Australia, fauna and flora of, 261, 339, 340, 342
Australian climate, adaptation to, 291
automatism, 19
Avebury, Lord, 292
average adaptation, 214
axial filament of spermatozoon, 140
Axoniderma mirabile, Fig. 170

B.

Babirusa, tusks, 422, Fig. 187
baboons, Buffon on, 378, 379
Bacillus saccobranchi, 66, Fig. 27
Bacteria, 226, 227, Fig. 85
alleged spontaneous generation, 223
modification of, 212
origin, 228
structure, 66, Fig. 27
Badhamia, Fig. 29
Bakewell, 398
Balæna mysticetus, 256, Fig. 103
Balænidæ, teeth, 271
Baldwin, 445
barnacles, degeneration, 411
barriers to migration, 331
bast, 65
Bates, H. W., 357
Batesian mimicry, 357
Bateson, W., 175, 185, 187, 188
bats, 312
dispersal, 334
wings, 247, 254, Fig. 101
battle.
Charles Darwin on law of, 399
Erasmus Darwin on law of, 384
beech,
evergreen, 340
seedling, 292, Fig. 135
bees,
alleged spontaneous generation, 222, 354
as pollen carriers, 365, 366, &c.
bees—*continued*
organization of, 230
parthenogenesis, 144
proboscis, 365, Fig. 181
beetles, mutation in, 159
Behring Strait,
former land connection, 320
former mild climate, 339
Bell, 351
Biffen, R. H., 185
binomial nomenclature, 237
biogenesis, 223
biogenetic law, 276
biology,
origin of name, 384
science of, 1
Biophoridæ, 227
biophors, 22, 66, 167, 227
birds
compared with reptiles, 316
dispersal, 334, 335
egg, 140, Fig. 70
evolution, 317, 318
geological range, 295
limbs, 246
origin, 310 (*see also* Archæopteryx).
wing, 254, 255, Fig. 101
blackberries, white, 184
blastocœl, 47
blastoderm, 281
blastogenic
characters, 201, 438
inheritance, 199
origin, 159, 160
variations, 149, 157—160
blastomeres, 45, 79
blastopore, 47, 276, 280
blastosphere, 45, 276, 435
blastostyles, 120
blastula, 45, 276, 435
interpretation, 290, 435
of Amphioxus, 45, 47, Fig. 13
of frog, 279, Fig. 121
of Hydra, 118, Fig. 59
blind worm, 261, Fig. 107
blood, 51, Fig. 15
blue Andalusian fowls, 180, 181
boa constrictor, dispersal, 336
Bodo, life-history, 85—87, Fig. 38
body cavity, 48, 124
body wall, 124
Bombus terrestris robbing clover, 366, 367
bone, 57
Bonnet, Charles, 163
bony fishes, 303

Bordage, E., 204
Boveri, T., 129, 146, 172
brachiopods, 299
brain
in evolution of man, 452, 453
of man and apes, 452, 453
branching
classification, Charles Darwin on, 398
evolutionary series, Lamarck on, 387
Branchiosaurus, 304, Fig. 141
Branchipus, dispersal, 338
bread, analogy of baking of, 164, 165
breathing, 8
Brewer, 206, 208
brimstone moth larva, Fig. 171
brittle star, 286, Fig. 128
Brontosaurus, 308, Fig. 146
Buceros rhinoceros, Fig. 188
budding, 274
in Hydra, 116
in Obelia, 119, 120
Buffon
on sterility of species when crossed, 421
views of, 376—381
Burbank, L., 184
Butler, Samuel, 3, 214, 216, 380
Bütschli, O., 19, 21, 22
butterflies, warning colours, 354—358
butterfly,
leaf, 349, Fig. 173
metamorphosis, 275
proboscis, 365

C.

Cacti, 361
thornless, 184
cænogenetic characters, 289—292
Cænolestes, 311
Cæsar's horse, 273
Cainozoic Era, 295, 296
Calceolaria, distribution of, 339
calcium, influence upon segmentation, 45
callosities, 196, 203
Buffon on, 378, 379
calyx, 106
cambium, 76
Cambrian Epoch, 295
camel,
Buffon on, 378
feet, 252, Fig. 100
Camelo-pardalis, Lamarck on, 390
cancer, nature of, 424
Cancer phalangium, 350
candle, analogy of, 2, 5
Candollea graminifolia, fertilization, 373
cane sugar attracting spermatozoa, 141
canine teeth, reversion in, 273
cannon bone, 252
capital, accumulation of, 431, 434
Capsella bursa-pastoris, development, 48, Fig. 14
carbohydrates, 27, 224
carbon, 6, 224
dioxide, 6, 8
Carboniferous Epoch, 295
Carchesium, 40
carnivores, 312
carpals, 248
carpels, 106
Carpophaga
chathamensis, 419
novæ zealandiæ, 419
carrion flies, 366
cartilage, 56, Fig. 20
casein, 23
Castle and Phillips, 209
castration, effect, 125
Catasetum, fertilization, 373
caterpillar,
larval organs, 286
stick, 348, 349
cats, inheritance of mutilation, 206
caudicle, 372
cave-animals, bleaching inherited, 205
cell, 12
body, 13
definition of, 38
division, 69—80
limits of, 81
history of term, 36, 37
membrane, 69
plate, 74
sap, 62
theory, 38
limitations of, 65
typical, 69, 70, Fig. 30
wall, 27, 28, 69
cellular structure, 36
cellulose, 27, 28
centrosome, 71
absence in higher plants, 141
in ovum, 141

centrosome—*continued*
as stimulus to development, 146
in spermatozoon, 139, Fig. 69
in unfertilized egg, 146
origin of, in zygote, 141
centrosphere, 71
Cephalaspis, 301, Fig. 137
Ceratodus (*see* Neoceratodus).
cercariæ, 144
cereals,
fertilization, 415, 416
improvement, 414–416
Mendelian inheritance in, 185
cervical vertebræ
of giraffe, 259, Fig. 106
of whale, 259, 329, Fig. 105
Cetacea,
evolution of, 325—329
limbs, 247
Chætopterus, artificial parthenogenesis, 145
chalk, 26
chamæleon, colour change in, 352
Chambers, Robert, views of, 394—396
change of function, 266, 267, 273
Chara, gametes, 141
characters,
compound, 188
somatogenic and blastogenic, 438
Chatham Islands, 336, 408—410, 419, 420
chelæ of sponges, 428, Fig. 189
Chelonia, 307
chemical
affinity, 6, 7
processes, 9
stimulus to development, 146
chemically modified larvæ, 157
chemotaxis, 141, 143
chick, embryo, 276, Figs. 119, 124
chimpanzee,
brain, 453
Buffon on, 381
Chinese women, small feet, 156
Chironomus, pædogenesis, 144
Chlamydomonas, 40
chlorophyll, 7, 8, 28, 224
cells, 64
corpuscles, 32, 64
chloroplastids, 32, 64
in Spirogyra, 96
Chordata, 288
chordate condition, 277
chromatin, 70, 71
in heredity, 167, 172, 186
chromatophores in Spirogyra, 96
chromomeres, 73, 167, 186
chromosomes, 71, 73, 167, 191, 444
and sex, 135, Fig. 67
differential division, 168
in gametophyte, 138
in sporophyte, 139
integral division, 168
maternal and paternal, 137, 187, Fig. 68
pairing, 133, 137, 186, Figs. 68, 81, 82
reduction, 132, 133, 137, 138, 186, 187, Fig. 68
chrysalis, 275
cilia, 39
Ciona intestinalis, Fig. 131
circumcision, 207, 208
Cirolana, 238
cirripedes, degeneration, 411
Cladocera, parthenogenesis, 144
Cladorhiza
longipinna, Fig. 170
(?) *tridentata*, spicules, Fig. 189
classes, 150, 237
classification, 236—239
and phylogeny, 241, Fig. 89
artificial, 239
Buffon on, 377
Charles Darwin on, 398
Lamarck on, 385, 386
natural, 239, Fig. 88
clavicle, 245, Figs. 91, 92, 95
clear-winged moths, mimicry, 354, Fig. 177
cleavage of ovum, 75
climate,
adaptation to, 291
changes in, 338
influence of,
Buffon on, 377
Lamarck on, 387
Miocene, 339
clover leaf, meristic variation, 149
coal, energy in, 4
Coccidium,
gametes, 87, 88, Fig. 39
maturation of ovum, 139
coccyx in man, 272
cockroaches, dispersal of, 336
Codonella, Fig. 9
Cœciliidæ, 261, Fig. 108
Cœlenterata, 114
cœlenterate and gastrula, 276, 280, 281, 288, 437
cœlom, 48, 124, 277

cœlomate and cœlenterate types, 124, Fig. 62
cœlomic
epithelium, 124
pouches, 277
cold-blooded animals, 6
colloids, 23, 224
colony formation,
cause of, 435
in Hydra, 116
Obelia in, 119
in Protozoa, 40—44
colour changes in animals, 352, 353
colours
of animals, 347, 348
Erasmus Darwin on, 383
of flowers, 366
combustion,
energy liberated by, 4, 6
nature of, 2, 5, 6
compound characters, 188
Condylarthra, 320, 324
congenital variations (characters), 157
Conilera, 238
conjugants in Paramœcium, 92, Fig. 41
conjugation
of chromosomes, 137, 192, Figs. 68, 82
of gametes, 33, 82—85, 131, 141, 186, 187, Fig. 65
in Ascaris, 131, Fig. 64
in Bodo, 87, Fig. 38
in Coccidium, 88, Fig. 39
in Cœlomata, 125
in Copromonas, 83, Fig. 37
in Eudorina, 91, Fig. 40
in ferns, 105
in flowering plants, 109
in Fucus, 101, Fig. 47
in Hæmatococcus, 33, Fig. 5
in Pandorina, 89, Fig. 10
in Paramœcium, 92, 93, Fig. 41
in Spirogyra, 96, 97, 142, Figs. 43, 44
in Zygogonium, 97
of nuclei in zygote, 131, Fig. 64
origin of, 127
results of, 84, 87
(*see also* amphimixis).
connecting links, 243—246, 316—329
destruction of, 233
conodonts, 301
conservatism of germ cells, 214
continental islands, fauna, 343
continents, permanence, 340
continuity
of germ plasm, 165—167, Fig. 83
of life, 67
of parent and offspring, Erasmus Darwin on, 381
of protoplasm, 66
continuous
selection, 414
variations, 148, 150
contractile
tissue (*see* muscle fibres).
vacuole, 14, 18
convergence, 258—266
in Acacia, 291
in flightless birds, 407
in plants, 273
in proboscis of bees and Lepidoptera, 365
"Convolvulus major" fertilization, 362, 363
co-operation, 40
of factors in evolution, 429
Copromonas,
life-history, 83, Fig. 37
nuclear reduction, 139
coracoid, 245, Figs. 91, 95
corals, 114, 276
cork, cellular structure, 37, Fig. 6
corolla, 106
corpora lutea, 126, 427
corpuscles, blood, 51, 52, Fig. 15
correlation, 418, 425, 442
of morphogenetic and environmental stages, 439
cortical tissues, 50
cosmopolitan distribution, 331
Cosmozoa, 221
cotyledons, cænogenetic characters, 291, 292, Figs. 56, 135
cowslip, fertilization, 367
crab,
larva, 287, Fig. 130
swimming, 258, Fig. 104
creation,
Lamarck on, 386, 387
special, 219—221, Fig. 84
Buffon on, 380
Linnæus on, 233
Creodontia, 329
Crepidula, 334
Cretaceous Epoch, 295
Crinoidea, 285

Crinorhiza form, 346, 428, Fig. 170
Cristatella mucedo, statoblast, Fig. 167
Crocodilia, 307
cross-fertilization of flowers, 362—374
crossing (*see* hybridization).
crossing over, 191, 192, Fig. 82
Crustacea,
  fresh water, dispersal, 338
  gills, 266*
cryptic colouration, 348
crystalloids, 23
Cunningham, T. J., 213
currents, dispersal by, 332–336
curve
  of frequency of error, 153
  of variation, 150, 153, Figs. 72, 73
Cuscuta europæa, 412, 413, Fig. 186
cushion plants, 273, 361
Cyathaspis, 301
cyclopean larvæ, 156, 158, 164, 193, Fig. 75
Cyclostomata, 300
cyst, 20, 21, 83
cytology, 67
cytoplasm, 13, 69
  in heredity, 172, 173, 444
cytostome, 83
cytotaxis, 142
cytotropism, 142
  of gametes, 143
Cyttaria, 340
Cyttarocyclis, Fig. 9

D.

Darbishire, A. D., 177
Darwin,
  Charles, views of, 175, 188, 196—200, 208, 233—235, 340, 362—364, 367, 368, 370, 396—399, 402–404, 413, 417, 418, 445, 451
  Erasmus, views of, 381—384
  Francis, 216
Davenport, 209
death, 21, 162
De Candolle, 397
decay, nature of, 4
de-differentiation, 166
deep sea animals, adaptation in, 346, 347
deer, feet, 252, Fig. 100
degeneration, 407—413
degeneration—*continued*
  in ascidians, 410
  in flightless birds, 406, 407
  in Morioris, 408—410
Delage, Y., 146
Delphinus delphis, Figs. 163, 164
Democritus, 380
dendrons, 59
dentition of dog and thylacine, 262—264, Figs. 109, 110
denudation, 297—299
dermatogen, 50
Descartes, 271
descent with modification, 232
design, doctrine of, 219
Desmacidonidæ, spicules, 427, 428, Fig. 189
determinants, 167, 186
deutoplasm, 140, 278, 443
development, 274—292
  and unconscious memory, 216
  Erasmus Darwin on, 382, 383
  of birds and reptiles, 281
  of flowering plants, 48–50, 109, Fig. 14
  of Frog, 279—281, 283, Figs. 121, 123
  of Hydra, 118, Fig. 59
Devonian Epoch, 295
De Vries, Hugo, 154, 184, 235, 414—417, 446
Dianthus, 364
diatoms, 25
dichogamy, 364
Dictyocysta, Fig. 9
Didelphyidæ, 311
differences between plants and animals, 34, 35
differential division of chromosomes, 168
differentiation, 39, 43, 44, 60, 119
  sexual, 85
diffusion of gases, 8, 17
digestion in Amœba, 16
digits, reduction, 250—252
dihybridism, 181—183, Figs. 78, 79
dimorphic flowers, 367
dimorphism of gametes, 139
Dinosauria, 308, Figs. 146—148
Dinotherium, 325, Fig. 162
diœcious, 99, 105
Diplodocus, 308
diploid, 139
Diplosoma crystallinum, larva, Fig. 132
Dipnoi, 266, 302
Diptera, pædogenesis, 144

direct nuclear division, 80, Fig. 36
discontinuity
between species, 233, Fig. 87
in distribution, 330, 331, 344
in evolutionary series, Lamarck on, 387
in organic world, 232
discontinuous variation, 149, 153—156
Dismorphia praxinöe, 356, Fig. 178
dispersal of organisms, 331—338
distribution, geographical, 330—344
disuse (*see* use and disuse).
of wings, effects of, 406—408
divergence
in evolution, 220, 445
A. R. Wallace on, 401
Charles Darwin on, 398
division of labour, 39, 43, 44, 60, 85, 119
between male and female, 127
dodder, 412, 413, Fig. 186
vestigial leaves, 273, Fig. 186
dodo, 269, 407
dog,
skull and dentition, 262—264, Figs. 109, 110
vestigial teeth, 271
dogfish, embryo, 281, Fig. 122
dolphin, 325, Figs. 163, 164
dolphins,
convergence in, 259
shark-toothed, 329
domestication,
Charles Darwin on, 413
Lamarck on, 389
dominant characters, 177, 187
Draba verna, elementary species in, 235, 415
Driesch, H., 449
drone flies
mimicking bees, 354
mistaken for bees, 222
Drosophila, 189—192, Figs. 80—82
Dubois, E., 450
ductless glands, 193
Dujardin, 38

E.

ECHIDNA, 245, 311, Fig. 94
echinoids, larval stage, 287
Echinus,
blastomeres, 45
hybridization in, 172
ectoderm, 47
of cœlomates, 124
of Hydra, 115, 116, 118
edentates, 312, 344
education, 453
eels, dispersal of, 336, 337
egg
cell (*see* ovum).
of Ascaris, mitosis, 79, Fig. 35
of bird, 140, Fig. 70
of frog, 279
eggs,
dispersal of fish, 333
similarity in different organisms, 162
size, 278
Eigenmann, 205
Elasmobranchii, 302
electric
eel, 267
organs, 267
electro-magnetic theory of mitosis, 74, 75
elementary species, 235, 415
elephants,
ancestry, 323—325, Fig. 161
limbs, 250
Elephas, 325
élite, 414
Elodea, evolution of oxygen, 31
embryo,
fixation, 126
of chick, 276, Figs. 119, 124
of Fucus, 101, Fig. 47
of mammals, 281
of rabbit, 276, Fig. 119
embryology,
Erasmus Darwin on, 382, 383
evidence afforded by, 272—292
embryonic cell, 48
embryo-sac, 48, 106, 107, 108
embryos of birds and reptiles, 281
Emily Henderson, sweet pea, 188
Empedocles, 380
encrinites, 285
endocrine glands, 193
endoderm, 47, 437
of cœlomates, 124
of Hydra, 115, 116, 118
endoplasm, 14, 22
endosarc, 14
endosperm, 109
energy,
accumulation of surplus, 426, 431—434
conservation of, 6

energy—*continued*
manifested in life, 4, 5
of chemical affinity, 7
source of, 4, 6, 7, 9
in green plants, 30
engrams, 214
entelechy, 11, 449
enteron, 47, 276
in Hydra, 115
entomophilous flowers, 111, 364
enucleate eggs, fertilization (*see* merogony)
environment,
control of, 453
influence of, 5, 6, 198, 204—206, 436—443
A. R. Wallace on, 401
Buffon on, 377, 378
Charles Darwin on, 398, 403
Lamarck on, 390
upon development, 447
germ plasm, 159, 447
inheritance of, 165, 438
environmental stages, 439—441
Enzymes, 10
Eoanthropus, 450
Eocene Epoch, 295
Eohippus, 320, 321, Fig. 156
Ephydatia fluviatilis, gemmules, Fig. 168
epiblast, 47, 48, 277
of Hydra, 115, 118
epicoracoid, 245, Figs. 91, 95
epidermis, 54, Fig. 17
of plants, 50, 64, Fig. 26
epigamic ornamentation, 347, 360
epigenesis, 163
Epihippus, 321
episematic colouration, 353
Epistylis, 40
epithelium, 54, Figs. 16—18, 28
epochs of earth's history, 294—296
equatorial plate, 72
Equidæ, pedigree of, 318—323
Equus, 320, 322, Fig. 155
eras of earth's history, 294—296
Esperella lapidiformis, spicules, Fig. 189
Esperiopsis
challengeri, 428, 429, Fig. 190
pulchella, spicules, Fig. 189
eucalypts, 342
leaves, 291
Eudendrium, migration of germ cells, 123
Eudorina, 42, 90, Fig. 40
Eurypteridæ, 302, Fig. 139
size of, 422
Eutheria, 312
first appearance of, 313
evolution,
factors of, 376—454
in development, 163
individual, 274
of sex, 81—147
progressive, 217, 345
synchronism in, 426
theory and evidence of, 218—375
versus special creation, 219—221, Fig. 84
ex-conjugants, in Paramœcium, 93
excretion, 9
in Amœba, 17
experience, 432, 434
experiments in heredity, 172 194
explosive character of living molecule, 18
extinction
of groups, 242
of species, Buffon on, 377
extracted
dominants, 178
recessives, 178
eye-colour, -Mendelian inheritance of, 185
eyes, pineal, 269—271

F.

Factors,
co-operation of, 188
in development, 165, 436
in germ plasm, 186, 187, 443
location of, 192
modification of, 213
nature of, 193, 212
of organic evolution, 376—454
permutations and combinations of, 186
fæces, 16
families, in classification, 237
Farmer, J. B., 186
fat, 56, Fig. 19
feather star (*see* Antedon)
feathers, acquisition of, 201
female
characters, 84, 85, 114, 127
dependence on male, 127

femur, 248
ferments, 10
fermentation, 226
fern, life-history, 101—105, Figs. 48 - 52
ferns, dispersal, 332
fertility
and cross-fertilization, 363, 368
test of specific identity, 421
fertilization,
chemical stimulus in, 146
development without, 145
in heredity (*see* amphimixis).
of flowers, 110, 362 374
of ovum, 85, Fig. 65
in Ascaris, 131, Fig. 64
in Cœlomata, 125
in ferns, 105
in Fucus, 101
in Hydra, 118
in medusæ, 121
fibrillar structure of protoplasm, 12
fibula, 248
fig-wort, 364
filter-passers, 227
finger, inheritance of mutilation, 206, 207
First Cause, Erasmus Darwin on, 383
fish eggs, dispersal, 333
fishes,
bony, 303
deep sea, 347
geological range, 295
fish-like stage in ontogeny and evolution, 283, 284, 288—290
fission
in Amœba, 21
in Bodo, 87
in Copromonas, 83
in Hæmatococcus, 29
fixation of embryo in uterus, 126
flagella
in Bodo, 87
in Eudorina, 91
in Hæmatococcus, 29
Flemming, 69
flightless birds, 269, 447
and fluctuating variation, 418
and natural selection, 407, 408, 447
flint, 24
floating islands, dispersal by, 335
flower, structure of, 106, 107, Fig. 53
flowering plants, life-history, 106—112
flowers,
adaptation for fertilization, 362—374
sexual characters, 110, 111
fluctuating variations, 148, 150, 155, Figs. 72, 73
and adaptation, 417, 418
and natural selection, 417
De Vries on, 417
flukes, parthenogenesis in, 144
foam structure of protoplasm, 21
fœtal membranes, 281, 289
fœtus, in Mammalia, 281
food
materials of animals, 16
of green plants, 30—32
nature of, 7
vacuoles, 14
yolk, 278, 289, 431—433, 443
influence of, 279, 282
foot,
artiodactyl, 252
of apes and monkeys, 451
of camel, 252, Fig. 100
of deer, 252, Fig. 100
of elephant, 250
of hippopotamus, 252. Fig. 100
of horse, 252, Fig. 99
atavism in, 273
evolution of, 321—323, Figs. 156—160
of Litopterna, 264—266, Fig. 111
of llama, 252
of man, 249, Fig. 96
of oxen, 252
of pig, 252, Fig. 100
of rhinoceros, 252
of seal, 255, Fig. 102
of sheep, 252
of tapir, 252, Fig. 98
of ungulates, 250 252, 264—266
pentadactyl, 249
perissodactyl, 252
Foraminifera, 26, Fig. 4
fossilization, 298
fowls, Mendelian inheritance in, 180, 181
foxgloves, mutation in, 154
fox terriers, 156
Francotte, 135
Freia, Fig. 9

frequency
of error, curve, 153
polygon, 151, Fig. 72
fresh water animals, dispersal, 336, 337
frog,
early development, 279—281, Fig. 121
life-history, 283, Fig. 123
interpretation of, 290, Fig. 133
pineal eye in, 271, Figs. 117, 118
frogs and toads, 304
fruit trees, propagation, 185
fruits, dispersal, 332
Fuchsia, distribution, 339
Fucus, 99—101, Figs. 45—47
functional selection, 445
functions of organisms, 5
Fundulus, cyclopean larvæ, 156, 164, 193, 448, Fig. 75
Fungi, 34, 332
furze, recapitulation in seedlings, 291

G.

Galaxias nigothoruk, dispersal of, 337
Gallardo, 75
Galton, Francis, 167, 194, 195, 208
Galton's
law of inheritance, 194
polygon, 155
Galtonia, mitosis in, 76, Figs. 33, 34
gametes, 33, 83 (*see also* germ cells).
attraction of, 141, 142, 143
conjugation of, 33, 82—84, 87—93, 96—98, 101, 105, 109, 118, 138, 141—144, 187, Figs. 5, 37—41, 43, 44, 47, 71
evolution of male and female, 84, 85
of Bodo, 87, Fig. 38
of Copromonas, 83, Fig. 37
of Eudorina, 90, 91, Fig. 40
of fern, 104, Figs. 51, 52
of flowering plant, 108, 109, 110, Figs. 54, 55
of Fucus, 100, Fig. 47
of Hæmatococcus, 33, Fig. 5
of Pandorina, 89, Fig. 10
of Spirogyra, 96, 97, 142, 143, Fig. 44
gametes—*continued*
of Volvox, 91, Fig. 11
purity of, 180, 186
sexual dimorphism of, 113, 139
gametic nuclei in Paramœcium, 93
gametogenesis, 132, Fig. 65
gametophyte, 101
chromosomes of, 138
of fern, 103, Fig. 50
of flowering plant, 107, 108
suppression of, 112
gamobium, 121
ganglion, 59
ganoids, 303
gastræa, 288
gastral cavity, 47
in Hydra, 115, 118
in Obelia, 119
gastrula, 47, 276, 288
interpretation of, 276, 290, 437
of Hydra, 118
of Sagitta, 130, Fig. 63
gastrulation
in birds and reptiles, 281
in frog, 280, Fig. 121
Gates, R. R., 157
gemmules, dispersal of, 338
in pangenesis, 197
of fresh water sponge, 338, Fig. 168
genera, 236
generative cells, 108
genes, 173 (*see also* factors).
Genesis, Book of, 219
genital ducts, 125
geographical
distribution, 330—344
summary, 341
isolation, 419, 420
geological
formations, 295
history of the earth, 295, 296
periods, 295
range of animal groups, 295
record, 294, 298—315
geometer moths, caterpillars, 348, 349, Fig. 171
Geoplana erulans, dispersal, 336
Geotria, distribution, 340
germ cells (*see also* gametes).
and somatic cells, 97, 98, 99, 113, 129, 165, 166, 436
conservatism, 214

germ cells—*continued*
immortality, 199
independence, 99
maturation, 138
migration in Hydrozoa, 123
origin
in Ascaris, 129
in Cœlomates, 124, 130
in Hydrozoa, 123
in plants, 130
in Sagitta, 130
potentialities, 163
sensitive to stimuli, 215
germinal
disk, 140
selection, 171
variations, 149, 157—160
germination
of fern spore, 103, Fig. 49
of pollen grain, 108, Fig. 54
of seed, 109, Fig. 56
germ layer theory, 48
plasm, complexity, 167
composition, 167, Fig. 76
constitution, 185, 186, 192, 193
continuity, 165—167, Fig. 83
influenced by environment, 159
gestation of nature, R. Chambers on, 395
gigantic animals, 314, 315, 422—426
Gila monster, 353
gill slits
in Amphioxus, 277
in embryos, 272, 284, Fig. 124
in evolution, 438—442
gills of crustaceans and fishes, 266
giraffe, 259, Fig. 106
Lamarck on, 390
glacial periods, 338, 339
glass snakes, 261
gliadin, 23
glucose, 28, 31
glutinin, 23
Godlewski, 172
gonads, 113
in Cœlomates, 124
in Hydrozoa, 124
in medusæ, 121
gonoducts, 125
gonophores, 122
gonotheca, 120
"gorillas," Hanno on, 450
gorse, recapitulation in seedlings, 291
Graafian follicle, 426
gradation
in nature, Buffon on, 377
in structure, 243
of animals, Lamarck on, 387
Grantia compressa, larva, 333, Fig. 166
grape
hyacinth, curve of variation, 150, Fig. 72
sugar, 28, 31
grasshopper, spermatogenesis, 134, Fig. 66
Gray, Asa, 397
Gray, J. E., 238
grazing mechanism, 320
Great Britain a continental island, 343
Greenland, former mild climate, 339
Grew, Nehemiah, 37
growth, 10, 20
control of, 422—426
in Amœba, 20
in animal tissues, 75
in plants, 76
periodicity of, 215
guard cells, 64, Fig. 26
Gulf Stream, dispersal by, 333, 334
Gulick, 420, 421
Guthrie, 208
Guyer and Smith, 211
Gymnotus, 267
gynœcium, 106

H.

HABIT of plants modified by environment, 204
habitat, 330
habits,
adaptation in, 348
establishment of, 432, 434
influence of, Lamarck on, 388—391
in plants, 216
Haeckel, Ernst, 66, 240, 276, 288
hæmatids, 52, Fig. 15
hæmatochrome, 28
Hæmatococcus, 27—34, Fig. 5
conjugation, 89
dispersal, 338
hæmoglobin, 53
hair, vestigial, 272

hairs of Tradescantia, 61, Fig. 25
hand
of man, 267, 452
of monkeys and apes, 451
Hanno, 450, 452
haploid, 139
harmony in colouration, 347
Harpax tricolor, 350
Hatteria (*see* Sphenodon).
Hawaiki, 409
head, segmentation of, 230
Heape, W., 208
heat in living organisms, 6
Heidelberg, fossil man, 450
Heilprin, A., 330
Heliconinæ, 356
Heliconius ethilla, 356, Fig. 178
helium, 297, 298
Heloderma suspectum, 353
Herbst, 45
heredity, 161—217 (*see also* inheritance).
Buffon on, 380
Charles Darwin's theory, 196—198
common-sense view of, 164
definition of, 165
fertilization experiments, 172, 173
Galton on, 194, 195
hormone theory of, 213
in Protista, 161
Lamarck on, 391, 392
Mendelian experiments, 174 193
mnemic theory, 214—217
nature of problem, 163
Pearson on, 195
Weismann on, 165—172, 198—203, 207, 208
Hering, E., 214
hermaphrodite, 103, 105, 113, 114
hermaphroditism, 93, 116, 125, 412
heterogeny, 144
Heteromita, life-history, 85—87, Fig. 38
heterosporous ferns, 105
heterostyled flowers, 367, Fig. 182
heterozygote, 187
hexadactylism, 154
Hipparion, 322
Hippocampus antiquorum, 352, Fig. 175
Hippopotamus, feet, 252, Fig. 100
histological differentiation, 48
histology, 51
hoatzin, 316
hock of horse, 251, Fig. 97
holophytic nutrition, 34
holozoic nutrition, 34
Homo
heidelbergensis, 450
sapiens, 450
Homo, species of, 450
homologous chromosomes, 137, 186, 187
homology, 246, 258
homoplasy, 246, 258
homosporous ferns, 106
homozygote, 187
honey guide, 373
honey-sucking apparatus, 365
Hooke, Robert, 36
Hooker, J. D., 396
hormones, 126, 193, 213, 424, 425
hornbill, 422, Fig. 188
hornets, colours of, 353, 354
horns, excessive development, 422
horse, evolution of, 318—323, Figs. 155 - 160
horse's skeleton, Fig. 97
horses, Mendelian inheritance in, 185
humble bee robbing clover, 366, 367
humerus, 248
humming birds,
as pollen carriers, 364
distribution, 331
epigamic ornamentation, 360
hunger, stimulus of, 435
hybridization, 174 -193
and evolution, 447, 448
and mutation, 416, 448
in cereals, 416
Hydra, 114—118, 276, Figs. 57—59
dispersal, 338
suppression of medusoid, 123
hydranth, 119
hydrocaulus, 119
hydrotheca, 119
Hydrozoa, 123
hyperphalangy, 255
hypertonic solution inducing parthenogenesis, 145
hypoblast, 47, 48
of Amphioxus, 47, 277
of Frog, 280
of Hydra, 115, 118
hypostome, 116, 119
Hypsidæ, 356
Hyracotherium, 321

I.

ICEBERGS, dispersal by, 335
Ichthyopterygia (Ichthyosauria), 308, Fig. 144
  paddles, 247, 255
Ichthyosaurus communis, Fig. 144
idants, 167, 168
idioplasm, 166
Idolum diabolicum, 350
ids, 167, 168, 186
igneous rocks, 293
Iguanodon, 308, Fig. 145
illegitimate unions in Primula, 368
immortality
  of germ cells, 199
  of Protista, 161
immutability of species,
  Buffon on, 380
  Lamarck on, 385
  Linnæus on, 233
incubation, 164
indifferent characters, 427—429
individual
  adaptation, 214
  characters, transmission of, 173
  variations, 150
individuality, 229—231, 449
  of cells, 68
induction, parallel and somatic, 210
inertia of germ cells, 214
inflorescences, variation in, 150
Infusoria, 40, Fig. 41
inheritance (*see also* heredity)
  of acquired characters, 196—214, 438
  of environment, 165, 438
  of mutilations, 206—208
insect communities as individuals, 231
insectivores, 312
insects
  as pollen carriers, 364—367
  dispersal of, 334
  primordial germ cells, 130
  selection by, 374
  sex determination, 135, 136, Fig. 67
  spermatogenesis, 135
  wings, 258
instincts,
  adaptation in, 348
  origin of, 206
integral division of chromosomes, 168
integration, 44, 229, 230
intelligent reactions, 445
intercellular substance, 57, 123
interclavicle, 245, Figs. 91, 95
intercrossing, swamping effects, 419, 422
interstitial cells, 116
intussusception, 20
invagination, 47
invertebrates,
  dispersal, 336
  geological range, 295
ionium, 297
Ipomœa purpurea, fertilization, 362, 363
irritability, 18
irritable structures in flowers, 373, 374
Isoetes, 105
isogamy, 84, 89, 97
isolation, 342, 419—422
  Lamarck on, 391, 392
Ithomiinæ, 356

J.

JELLY-FISH, 114, 121, 276
Jennings, H. S., 432, 445
Joly, 297
Jones, Wood, 449
Jurassic Epoch, 295

K.

KAKAPO, 407
Kallima inachis, 349, Fig. 173
Kammerer, 209, 440
kangaroos, 311
karyogamy, 128
karyokinesis, 69—79, Figs. 31—35 (*see also* mitosis).
karyoplasm, 14, 69
karyosome, 70, 77
katabolism, 9, Fig. 1
kea, 408
khaki clothing, 353
kidney, effect of removal, 156
kinetic energy, 7
kingdoms, 237
kiwi, 269, 342, 407, Figs. 113, 114
  size of egg, 426

L.

LABELLUM, 370
labyrinthodonts, 254, 422

Lagena, non-adaptive characters, 427
Lamarck, views of, 198, 384—393, 421, 446
Lamarck's four laws, 393
Lamarckian factors,
A. R. Wallace on, 404
Charles Darwin on, 198, 403, 404
neglect of, 404
Robert Chambers on, 396
lampreys,
dispersal, 336, 337
distribution, 340
pineal eye, 269, 271
lance-woods, 420
land
connections, former, 339, 340
planarians, dispersal, 336
larva
of Antedon, 285
of Ascidian, 288, Fig. 132
of crabs, 287, Fig. 130
of echinoids, 287
of frog, 283, Fig. 123
of Grantia, 333, Fig. 166
of ophiuroids, 286, Fig. 129
larvæ, 283
larval
forms, dispersal, 332, 333
organs, 283, 286, 289
Leach, 238
lead, 297, 298
leaf
insects, 349, 350, Figs. 172, 173
structure, 63—65, Fig. 26
leg of man, 248, 249, Fig. 96
legitimate unions in Primula, 368
legumin, 23
Leigh, G. F., 359
Lemuria, 339
lemurs, distribution, 339
lens,
development of, 193
inheritance of defects in, 211
regeneration of, 449
leopard, distribution, 331
Lepidosiren, 266, 302
Leptinotarsa, mutation in, 159, 160
leucocytes, 51, Fig. 15
level, changes of in land, 339
lianes, 361
life-history, 274 (*see also* ontogeny).
life,
nature of, 2, 3, 4, 11, 432
origin of, 224
Lilium, germination of pollen grain, Fig. 54
Lillie, R. S. and F. R., 145
limbs
of arthropods, 257, 258
of vertebrates, 246—257
Limnas chrysippus, 357, Fig. 179
linin network, 70
linkage of characters, 189, 191, 192
Linnæan species, 415
Linnæus, 233, 237, 239
Linnean Society, 351, 396
lithium larvæ, 156, 437
Lithobius, host of Coccidium, 87
Litopterna, 264, Fig. 111
lizards,
pineal eye, 269
shoulder girdle, 245, Fig. 91
llama,
Buffon on, 378
feet, 252
Lock, R. H., 152
locomotion in Amœba, 15
Loeb, J., 145, 146
Lotsy, 446
Lubbock, Sir John, 292
Lull, R. S., 318
luminous organisms, 6
lung-fishes (*see* Dipnoi).
lungs and swim-bladder, 266, 267
Lyell, Sir Charles, 335, 396
Lygosoma
dendyi, 420
moco, 420
lyre bird, 360, Fig. 180

M.

Macculloch, 351
machine, analogy of, 2, 3, 10
Macropodia rostrata, 351, Fig. 174
magnesium larvæ, 156, 164, Fig. 75
maize root, section, 37, Fig. 7
male characters, 84, 85, 114, 127
malic acid attracting spermatozoa, 141
Malthus, 397
Mammalia
compared with Reptilia, 243—246
dispersal, 334
geological history, 295, 311—314
gigantic, 422, 423

Mammalia—*continued*
limbs, 246
nutrition of young, 281
origin, 311
ovum, 140, Fig. 71
mammoth, Buffon on extinction of, 377
man,
æsthetic development influenced by insects, 375
and apes, relations, 449—453
Buffon on, 381
Lamarck on, 393
antiquity, 295, 314, 450, 451
control of environment, 453
evolution, 449—454
Charles Darwin on, 451
influence on other organisms, 406
limbs, 248, Fig. 96
Mendelian inheritance in, 185
races of, 450
reversion in, 273
vestigial
hair, 272
tail, 272
Mantidæ, 349, 350
Maoris and Morioris, 408—410
marine
animals, dispersal, 332
fauna and flora, 334
Marsh, O. C., 273, 318
marsh tit, distribution, 330, 331
Marsilea, 105
marsupial
mole, 264
wolf, 262
Marsupialia, 261, 311, 342
distribution, 340—343
extinct, 313, 343
Mastodon, 325
Mastodonsaurus, 308
maternal
chromosomes, 137, Fig. 68
functions, a handicap, 127
Matthew, Patrick, 396
maturation of germ cells, 132, 137, 138, Figs. 65, 68
in heredity, 168
Mauritius, 269
mechanism, 228, 229, 448
of organic evolution, 430—449
Mediterranean fauna, 334
medusæ, 120, 121, 123, Fig. 60
megagametes, 85, 88, 90
megalecithal, 278
megasporangia, 107
megaspores, 105, 106, 107, 108
Megatherium, 314
meiosis, 132, 186, Figs. 65—68
memory, 214—217
Mendel, G. J., 175
Mendelian
experiments, 174—193
inheritance
in Leptinotarsa, 160
in Primula, 367
phenomena, 445
principles, application of, 185
proportions, 177—183
Menura superba, 360, Fig. 180
meristem, 76
meristic
mutations, 154
variations, 148, 149
merogony, 146, 172
Merychippus, 321, Fig. 155
mesentery, 54
mesoblast, 48, 277
mesoblastic somites, 277
mesoderm, 48, 124
mesogloea, 115, 116
Mesohippus, 321, Figs. 155, 158
mesophyll, 50, 64, Fig. 26
Mesozoic Era, 295, 296
metabolism, 9, Fig. 1
metacarpals, 249
metagenesis, 121
metameric segmentation, 149, 230, 277, 290
metamorphic rocks, 294
metamorphosis, 274
Metaphyta, 44, 95
metapodials, 251, 252
metatarsals, 249
Metatheria, 311—313
Metazoa, 44
mice,
dispersal, 336
experiments in heredity, 205, 207
microgametes, 85, 88, 91
microlecithal, 278
Microlestes, 312, 313
micronucleus, 39, 92
micropyle, 109
microsporangia, 107
microspores, 105, 106, 107
microzooids, 33
migration from north, 340
milk, 282
mimicry, 354—359

mineral salts, 23
Miocene Epoch, 295
Miohippus, 321
mitosis, 69—79, Figs. 31—35
  in heredity, 168
mnemic theory of heredity, 214—217
moas, 269, 407, 426
mode, 152
models and mimics, 356, 359
Mœritherium, 324, Fig. 161
moles, marsupial, 264
Molluscoida, 288
momentum in evolution, 423—426
monads, 83
Monera, 66
monœcious, 103, 105
monohybridism, 181, 190, Figs. 77, 80
monosome, 135
Monotremata, 245, 308, 311, 313, 342
monstrosities, 154, 157
Moore, B., 224
Morgan, T. H., 189, 192
Morioris, extermination, 408—410
morphogenetic stages, 439, 440, 441
mosses, dispersal, 332
moths,
  clear-winged, 354, Fig. 177
  proboscis, 365
  protective resemblance, 349
motion in living organisms, 6
mountain hare, distribution, 344
mud, dispersal in, 338
mud-fishes, 266, 302
Müller, Fritz, 357
Mullerian mimicry, 357
multicellular, 38
  organisms, origin of, 44
multiplication of cells, 21, 69—80
Multituberculata, 313
Mungoswell's wheat, 416
Muscari, variation in, 150
muscle fibres, 57, 58, 116, Figs. 21, 22
music and memory, 216
mutation
  and adaptation, 417, 418
  and evolution, 447
  and hybridization, 416, 448
  and natural selection, 417
  theory, 235
mutations, 149, 153—156, 235
  meristic, 154
mutations—*continued*
  origin, 159, 160
    of species from, 155, 235, 236, 416, 417, 447
  substantive, 154
mutilations, alleged inheritance of, 206—208
mutual adaptation, 417, 418
Mycetozoa (Myxomycetes), 67, Fig. 29

N.

NÄGELI, 166
natural
  affinities, 239, 240
  selection, 406—413, 445
    and mutation, 417
    A. R. Wallace on, 400—402
    Buffon on, 379
    Charles Darwin on, 396—399, 403
    Erasmus Darwin on, 384
    insufficiency of, Charles Darwin on, 403
    summary of theory, 402
  system, 237
nectaries, 370, 371, 417, 418
Neoceratodus, 266, 302, Fig. 112
Neohipparion, 321, Fig. 159
Nepenthes, 273
Nerocila, 238
nerve
  cells, 58, Figs. 23, 24
  fibres, 58
nerves, 59
nervous systems, 18, 121, 277
neurons, 58, 59
newts, 294, 448, 449
New Zealand, fauna and flora, 269, 339, 340, 342
nipples, vestigial, 356
nitrifying bacteria, 226
Nitrobacter, 226
Nitrosomonas, 226, Fig. 86
nomenclature, 237, 238
non-adaptive characters, 422—429
normal
  curve of variation, 153
  variations, 150
notochord, 277
Notornis, 407
Notoryctes, 264
nucellus, 108
nuclear membrane, 69
nucleinic acid, 71

nucleolus, 70, 77
nucleoplasm, 14, 22, 69
nucleus, 13, 69
division (*see* mitosis and amitotic nuclear division).
in heredity, 161, 167, 172, 173, 444
zygote, 83
numerical variations, 149
nutrition, 7 (*see also* food materials).
of embryo in Cœlomata, 125

O.

Obelia, 119, 276, Fig. 60
ocean, age of, 297
oceanic islands, fauna, 341, 343, 407
oceans, permanence, 340
Œnothera, mutation in, 155, 157
oil-foam, 19, 21
Olenus cataractes, Fig. 136
Oligocene Epoch, 295
ontogenetic record, obscuring of, 278, 289
ontogeny, 274, 436, 439–443
abbreviation of, 284
a habit, 216
and phylogeny, 276, 290, Fig. 133
Erasmus Darwin on, 382, 383
interpretation of, 288
Onychophora, distribution, 341
oocytes, 133
oogenesis, 133, Fig. 65
oogonia
of Fucus, 100
in oogenesis, 133
oospheres, 90, 100, 104, 108
ooze, 26, 294
opal, 24, 26
Ophisaurus, 261
Ophiura ciliaris, Fig. 128
ophiuroids, 286, 287
Opisthocomus, 316
opossums, 311
opposable great toe and thumb, 451
optic vesicle, 193
orang, brain, 453
"orang utan," Buffon on, 381
Orchidaceæ, fertilization, 370–373
Orchis mascula, fertilization, 370–373, Fig. 184
orders, 237
Ordovician Epoch, 295
organellæ, 39
organ-forming substances, 443
organic
evolution, doctrine of, 219 (*see also* evolution).
units, 38, 65
organism, 3
organisms,
number and variety of, 218
origin of, 219–228
organizing spirits, A. R. Wallace on, 405
organs, 12, 38
origin
of great groups, 314, 315
of living things, 219–228
of sex, 84, 85, 89, 126–128
of species, 446–448
Ornithorhynchus, 245, 271, 311, Fig. 93
Ornithosauria, 308
Ornithoscelida, 308
Orohippus, 321, Figs. 155, 157
orthogenesis, 431
Osborn, 380
osmosis, 23
osmotic pressure, effect on egg, 145
Ostracodermi, 301, 302, Figs. 137, 138
Otaria hookeri, paddles, Fig. 102
otter sheep, 154
ovary
of animals, 113, 116
of flower, 107
transplantation of, 208
oviducts, 125
ovotestis, 113
ovule, 48, 106, 107, Fig. 55
ovum, 85
interpretation, 290
maturation, 133, Figs. 65, 68
of Amphioxus, 45, Fig. 13
of Ascaris, 131, Fig. 64
of bird, 140, Fig. 70
of Chara, 141
of Coccidium, 88, Fig. 39
of Eudorina, 91, Fig. 40
of fern, 104, Fig. 52
of flowering plant, 108, 109, Fig. 55
of frog, 279, Fig. 121
of Fucus, 100, Fig. 47
of Hydra, 116, Figs. 57, 59
of mammals, 140, 282, Fig. 71
of medusæ, 121
of plants, 141
of rabbit, Fig. 71

ovum– *continued*
of sponges, 113
of Volvox, 91, Fig. 11
segmentation of, 45, 274, 276, 279, Figs. 13, 121
similarity in different organisms, 162
size of, 278
typical, 140, Fig. 69
oxen, feet, 252
oxidation, 5, 145
oxlip, fertilization, 367
oxygen, 5, 6, 8, 31
oyster, American, introduced, 334

P.

Paddles, 247, 255, 258
pademelons, colouration, 348
pædogenesis, 144
pairing of chromosomes, 133, 137, 186, Figs. 65, 66, 68, 82
Palæohatteria, 306
Palæomastodon, 324, Fig. 161
palæontology, evidence afforded by, 298–329
Palæospondylus, 301
Palæozoic Era, 295, 296
palingenetic characters, 288
palms, climbing, 361
Pandorina, 42, 89, Fig. 10
pangenesis, 196—198, 380, Fig. 83
Papilio, mimicry in, 357–359, Fig. 179
parallel induction, 210, 211
Paramœcium, 39, 98, 139, Figs. 8, 41
parasites, peculiarities of, 411—413
parasitism, of gametophyte, 112
Pareiasaurus, 308, Fig. 142
parenchyma, 65
parentage, responsibilities of, 194
parietal
eyes, 269—271, Figs. 116—118
foramen, 271
parthenogenesis, 143, 144, 147
144–147
Parus palustris, distribution, 330—331
passivity of female, 84, 85
Pasteur, 223
Patagonia, beech forests, 340
paternal chromosomes, 137, Fig. 68
peach trees, inheritance of acquired characters, 204
peacock, epigamic ornamentation, 360
Pearson, Karl, 195
pea,
Sicilian, 188
structure and germination of seed, 56
peas, Mendelian experiments on, 176—183
pedigrees, 240, 322, 444
Peebles, Florence, 28
pelagic organisms, 333, 347
pentacrinoid stage of Antedon, 285, 286, Fig. 126
Pentacrinus, 285, Fig. 127
pentadactyl limbs, 248, 304 (*see also* limbs and feet).
periblem, 50
Pericopis angulosa, 356, Fig. 178
Peripatus, Fig. 169
distribution, 341
perisarc, 119
perissodactyl, 252, 264
peristaltic movement, 57
peritoneal epithelium, 54, Fig. 16
Permian Epoch, 295
Perrhybris malenka, 356, Fig. 178
Petalotricha, Fig. 9
petals, 106
phagocytes, phagocytosis, 52
phalangers, 311
phalanges, 249
Phascolotherium, 313, Fig. 151
Phenacodus, 320, Fig. 154
phloem, 65
phosphorescent organs, 347
phosphorus, 22, 71
photosynthesis, 30, 31, 224
phyla, 237
phyllodes, 291
Phyllopteryx eques, 352, Fig. 176
phylogenetic tree, 240, 444
phylogeny, 240
and classification, 241, 242, Fig. 89
and ontogeny, 276, 290, Fig. 133
Erasmus Darwin on, 383
physical
basis of life, 7
conditions of earth, changes in, 338
physiological
selection, 421
unit, the cell, 68

Phytoflagellata,
colony formation, 40, 42
evolution of sex, 89—91
Pierinæ, 356
pig, feet, 252, Fig. 100
Piltdown skull, 450
pineal
eyes, 269—271, Figs. 116—118
gland, 11, 271
pin-eyed flowers, 367
pistil, 106
Pisum sativum, varieties, 176
pitcher plants, 273
Pithecanthropus erectus, 450
pituitary body, 193, 424
placenta, 281
placental mammals, appearance of, 313
Plagianthus betulinus, 420
Plagiaulacidæ, 313
Plagiaulax, 312, Fig. 150
Planema poggei, 357
plankton, 333
plants,
compared with animals, 34, 35
dispersal of, 332
plasma, 51
plasmodia, 67
plasmogamy, 128
plasticity of organisms, 346
plastids, 32
plastogamy, 128
Platypus (*see* Ornithorhynchus)
Pleistocene Epoch, 295
plerome, 50
Plesiosauria, 247, 255, 308
Plesiosaurus macrocephalus, Fig. 143
Pliny, 273
Pliocene Epoch, 295
Pliohippus, 321, 322, Figs. 155, 160
ploughshare bone, 316
plumage of birds, 360
plumcots, 184
pluteus larvæ, 286, 287, Fig. 129
polar bodies, 133, 135, 139, 145, Figs. 35, 65, 68
pole-cell, in insect egg, 130
pollen,
collection of, 366
grains, 106, 107
sacs, 107
tube, 108
pollination, 110, 111
adaptations for, 362—374
pollinia, 372
polyanthus, pollination, 367
polydactylism, 149
polymorphic colony, 119
polymorphism in Papilio, 357, Fig 179
polype, fresh water (*see* Hydra).
Polypodium, archegonium, Fig 52
Polyzoa, dispersal, 338
population,
Buffon on, 379
Charles Darwin on, 397
Lamarck on, 392
Wallace on, 400
porpoises, convergence in, 259
Portunus, 258, Fig. 104
larva, Fig. 130
potential energy, 7
Poulton, E. B., 347, 348, 357
Pre-Cambrian Epoch, 295, 296
precipitin experiments, 444
pre-formation in development, 163
prehension, organs of, 267
prepotency, 364, 369
presence or absence hypothesis, 187
Primary Era, 295, 296
Primates, 312, 315
primordia, in germ plasm, 186
primordial
germ cells, 113 (*see also* germ cells, origin)
utricle, 62, 95
Primula, fertilization, 367—369
Proboscidea, evolution, 323—325, Fig. 161
proboscis,
of bee, 365, Fig. 181
of butterflies and moths, 365
of elephants, 267
of insects, Erasmus Darwin on, 384
procryptic colouration, 348—353
progress, human, 454
progressive
development, R. Chambers on, 395
evolution, 217, 345, 431—434
cause of, 217, 431—434
Wallace on, 401
series, 243, 245
pronuclei, 131, 145, 146, Fig. 64
protandrous, 364, 374
protective resemblance, 348—353
proteids, 7, 22, 224
Proterotherium, 264, Fig. 111

Proteus, 205
prothallus
of fern, 103
of flowering plant, 108
Protista, 38
dispersal of, 338
immortality of, 161
protogynous, 364
Protohippus, 321
Protophyta, 38, 95
sexual differentiation in, 91
protoplasm, 2, 38
chemical composition, 22, 23
controlling power, 23
energy in, 7
physical properties, 21
selective action, 26
sensitive to stimuli, 215
streaming, 62
Protopterus, 266, 302
Protorohippus, 321, Fig. 155
Prototheria, 311, 313
Protozoa, 38, &c., Figs. 3, 4, 9, &c.
non-adaptive characters, 427
nuclear reduction, 139
powers of multiplication, 81
sexual differentiation, 89
Prozeuglodon, 329, Fig. 165
prunes, stoneless, 184
Pseudopanax
chathamicum, 420
crassifolium, 420
ferox, 420
pseudopodia, 15
Pteranodon, 310, Fig. 149
Pteraspis, 301
Pterichthys, 301, Fig. 138
Pterosauria (pterodactyls), 247, 253, 308, 310, Figs. 101, 149
Pterostylis trullifolia fertilization, 373
Pterygotus osiliensis, Fig. 139
Pulchriphyllium crurifolium, 349, Fig. 172
Punnett, R. C., 188
purity of gametes, 180, 186
putrefaction, 226
Pyrenees, arctic vegetation on, 344
pyrenoids, 32, Figs. 5, 42

Q.

QUADRUMANA, 451
quartz, 24

R.

RABBIT,
embryo, 276, Fig. 119
shoulder girdle, 245, Fig. 92
racial characters, transmission, 173
radial canals, 120
radio-active elements, 297
Radiolaria, 25, Fig. 3
radium, 297
radius, 248
rafts, dispersal by, 335
range in time of animal groups, 295
Ranunculus aquatilis and *Ranunculus hederaceus*, Lamarck on, 390
rats, 204, 207, 336
recapitulation hypothesis, 276 292, 435- 442
anticipated by Erasmus Darwin, 383
receptor, 18
recessive characters, 177, 187
recognition marks, 348
red
blood corpuscles, 52, 53, Fig. 15
clover, robbed by humble bee, 366, 367
Red Sea, fauna, 334
red snow, 27
reduction of chromosomes (reducing division), 132 139, 186, 187, Figs. 65—68
regeneration, 66, 448, 449
regression, filial, 195
Reid, Sir Archdall, 438
rejuvenescence, 92
reproduction, 11
Reptilia
compared with Amphibia, 305
with Mammalia, 243, 246
fossil, 305—310
geological range, 295
giant, 423
limbs, 246
origin, 305—307
respiration, 8
in Amœba, 17
in embryos, 281
in plants, 32, 33
response to stimuli, 18
restitution, 448
Réunion, peach trees in, 204
reversion, 272, 273
Mendelian explanation, 188
rhinoceros, feet, 252

Rhumbler, 437
Rhynchocephalia, 270, 307 (*see also* Sphenodon)
ribs, meristic variation, 149
Ritzema Bos, 207
rock-formation, 293
rodents, 312
Rodriguez, 269
Romanes, G. J., 344, 420, 421
root-cap, 50
root, growing point, 76, Figs. 33, 34
Rosenthal, 207
rostellum, 371
rotifers, parthenogenesis, 144
rudimentary organs (*see* vestigial organs)
Charles Darwin on, 403
Rumia cratægata, larva, Fig. 171
rust in wheat, 185
rye, fertilization, 415

S.

SACCULINA, degeneration, 411, Fig. 185
sage (*see* Salvia).
Sagitta, origin of germ cells, 130, Fig. 63
salamanders, 209, 440
Salvia, structure of flower and fertilization, 369, 370, Fig. 183
Salvinia, 105
Sandwich Islands, oceanic, 343
sap, 65
nuclear, 70
saprophytic nutrition, 34
sarcode, 38
Sarracenia, 273
Sauropsida, 310
Sauropterygia, 308, Fig. 143
scapula, 245, Figs. 91, 92, 95
scents, of flowers, 366
Schleicher, 69
Schleiden, 38
Schœtensack, 450
Schwann, 38
Scrophularia nodosa, 364
scurf, 55
sea
anemones, 114
coast, selection in, 406
firs, 114
urchins,
artificial parthenogenesis, 145
sea urchins—*continued.*
blastomeres, 45
hybridization, 172
larvæ, 287
seal, paddles, 255, Fig. 102
Secondary
Era, 295, 296
sexual characters in Cœlomata, 125
secretions, influence of (*see* hormones)
sedimentary rocks, 293, 296
sedimentation, rate of, 296
seed, 109, Fig. 56
coat, 109
leaves (*see* cotyledons).
seedling
of Acacia, 291, Fig. 134
pea, Fig. 56
seeds, dispersal, 332
Seeley, H. G., 308
segmentation, metameric, 149, 277
segmentation of ovum, 45, 274
in Amphioxus, 45, Fig. 13
in birds and reptiles, 281
in frog, 279, Fig. 121
in Hydra, 118
in mammals, 282
interpretation of, 276
segregation of germ cells (*see* germ cells, origin).
selection,
artificial, 413—417
Charles Darwin on, 398
by insects, 374, 414
continuous, 414, 415
functional, 445
germinal, 171
natural (*see* natural selection).
not confined to living things, 406
sexual (*see* sexual selection).
single, 416
self-fertilization, 362—364
sematic colours, 347, 353
Semon, Richard, 203, 214
sensation, 18
sense
cells, stimulation of, 215
organs, 18, 121
sepals, 106
series, progressive, 243, 245
serum experiments, 210, 211
Sesia crabroniformis, Fig. 177
sex determination in insects, 135, Fig. 67

sexes, fundamental distinction between, 127
sexual
characters transferred to asexual generation, 110, 111
differentiation, origin of, 128
phenomena, 84, 85
evolution of, 126, 127
in Bodo, 87, Fig. 38
in Coccidium, 88, Fig. 39
in Cœlomata, 125
in Copromonas, 83, Fig. 37
in Eudorina, 91, Fig. 40
in ferns, 104, 105, Figs. 51, 52
in flowering plants, 108, 109, Figs. 54, 55
in Fucus, 100, 101, Fig. 47
in Hæmatococcus, 33, Fig. 5
in Hydra, 116
in Obelia, 121
in Pandorina, 89, Fig. 10
in Paramœcium, 93, Fig. 41
in Spirogyra, 96, 97, Figs. 43, 44
in Volvox, 91, Fig. 11
in Zygogonium, 97
reproduction, 33
selection, Charles Darwin on, 399
Erasmus Darwin on, 384
Shand, Alexander, 409
sharks, fossil, 302
sheep,
Ancon or otter, 154
feet, 252
shepherd's purse, 48, Fig. 14
Shirreff, Patrick, 416
shoulder girdle,
of mammals, 245, Fig. 92
of Ornithorhynchus, 245, Fig. 95
of reptiles, 244, 245, Fig. 91
Sicilian pea, 188
silica, 23, 24
siliceous skeleton, 25
Silurian Epoch, 295
Simocephalus, 209, 444
single selection, 416
Sirenia, 312
paddles, 247, 255
size, increase of, 320, 422—426
skeleton (*see* feet, limbs, paddles and wings).
of extinct animals, Figs. 141—154
of giraffe, Fig. 106
of horse and man, Fig. 97
of kiwi, Fig. 114
of Obelia, 119
of Protista, 23—26, Figs. 3, 4
of whale, Fig. 102
skulls of dog and thylacine, 262, Figs. 109, 110
slime fungi (*see* Mycetozoa).
sloths, 344
slow worm, 261, Fig. 107
snails, dispersal, 336
snakes, mimicry in, 354
social organizations, 230
Soddy, 298
sodium, in sea water, 297
sole of foot, 203
Buffon on, 379
solitaire, 269, 407
Sollas, W. J., 296, 297, 322
soma and germ cells contrasted (*see* germ cells and somatic cells).
somatic
and germ nuclei in Paramœcium, 98
induction, 210
somatogenic
and blastogenic characters, 442
characters (*see* acquired characters).
variations, 149, 156, 157
somatopleure, 124
somites, 277
South America, fauna and flora, 339, 341, 344
Spalacotherium, 313
special creation, 219—221, 233, Fig. 84
Buffon on, 380
Lamarck on, 386, 387
species,
aggregate, 235
Charles Darwin on, 234, 446
definition of, 234, 448
elementary, 235
Lamarck on, 386
modification of, Buffon on, 377, 378
nature of, 233—235
number of living, 218
origin of, 446–448
from mutations, 236, 446, 447

species—*continued.*
supposed immutability of (*see* immutability of species).
transformation of, Lamarck on, 387, 388
specific characters, non-adaptive, 427—429, 447
speech,
an acquired character, 156, 206
evolution of, 453
Spencer, Herbert, 2, 402
spermary, 113
spermatids, 133, Figs. 65, 66
spermatist (Erasmus Darwin), 382
spermatocytes, 133, Figs. 65, 66
spermatogenesis, 132, 133, 134, 135, Figs. 65, 66
spermatogonia, 133, Figs. 65, 66
spermatozoa, 85, 139, Fig. 69
chemotaxis in, 141
development (*see* spermatogenesis).
of Chara, 141
of Coccidium, 88, 141, Fig. 39
of Eudorina, 91, Fig. 40
of fern, 104, 141, Fig. 51
of Fucus, 100, Fig. 47
of Hydra, 116
of medusæ, 121
of mosses, 141
of sponges, 113
of Volvox, 91, Fig. 11
spermatozoids, 91
Sphærechinus, experiments in hybridization, 172
Sphærella (*see* Hæmatococcus).
Sphærozoum, 43, 276, 435, Fig. 12
Sphenodon punctatus, 270, 271, 295, 331, 342, Figs. 115, 116
spicules (*see* sponges, spicules).
spider crab, 340, 351, Fig. 174
spindle, nuclear, 71
spines, excessive development, 422
spiny anteater (*see* Echidna).
spireme, 71
Spirogyra, 95—97, 142, Figs. 42—44
splanchnopleure, 124
splint bones, 252, 268
sponges,
deep sea, 346
dispersal of fresh water, 338
gemmules of fresh water, 338, Fig. 168
germ cells, 113
sponges—*continued.*
non-adaptive characters, 427—429
spicules, 26, 243, 427, 428, Figs. 90, 189
Spongilla (*Ephydatia*) *fluviatilis*, gemmules, Fig. 168
spontaneous generation, 222, 223, 228
Lamarck on, 385
sporangia
of fern, 101, Fig. 48
of flowering plant, 107, Fig. 53
spores, 21, 101
dispersal, 332
formation, reduction of chromosomes, 138
germination, in fern, 103
of Bodo, 87
of Coccidium, 89
sporophylls, 107
sporophyte, 101
of fern, 105, Fig. 48
of flowering plants, 106
number of chromosomes, 139
sports, 154, 235 (*see also* mutations).
Squalodontidæ, 329
Squamata, 307
stability of organisms, 155, Fig. 74
stag, antlers, 125
staining reactions, 62, 70
stamens, 106
staminodes, 273
starch, 31
star-fish, meristic variation, 149
Starling, E., 193
statoblasts, 338, Fig. 167
stature, variation in human, 152
Staurocephalus murchisoni, Fig. 136
Stebbing, T. R. R., 350
Stegocephalia, 304
Stegosaurus, 308, Fig. 147
Stenobothrus viridulus, spermatogenesis, Fig. 66
Stentor, 432, Fig. 9
Stereognathus, 312
sterility of species when crossed, 421
St. Helena, an oceanic island, 343
stick caterpillars, 348, 349, Fig. 171
Stieda's organ, 271, Figs. 117, 118
stigma, of flower, 107
stimulation of protoplasm and cells, 215

stimuli, 18
to development, 145—147, 202, 436, 442, 443, 447
stimulus, transmission between cells, 143
Stockard, 157
stomata, 64, Fig. 26
storms, dispersal by, 335
stratified
epithelium, 56, Fig. 18
rocks, 293—297
striped muscle, 57, Fig. 22
struggle for existence,
A. R. Wallace on, 400
Buffon on, 379
Charles Darwin on, 397
importance of, 407—410
Lamarck on, 392
Stylidium graminifolia, fertilization, 373
subclasses, 237
subfamilies, 237
subgenera, 236
subkingdoms, 237
suborders, 237
substantive
mutations, 154
variations, 148, 150
succulent plants, 361
Sumner, F. B., 205
sun, dependence of life upon, 5
suprascapula, 245
surface,
relation to volume, 20
tension, 19
surplus energy, accumulation of, 426, 431—434
survival of fittest, 402
Buffon on, 379
Charles Darwin on, 398
in inorganic world, 406
suspensor, 49
Svalöf, 416
sweet peas, reversion in, 188
swim bladder and lungs, 266, 267
synaposematic groups, 354—357, Fig. 178
synapsis, 133, 137, 186, Figs. 65, 66, 68
synaptic mates, 135
synchronism in evolution, 426
syncytia, 66
syncytial epithelium, 67, Fig. 28
syndesis, 137 (*see also* synapsis).
syngamy, 83 (*see also* conjugation).
synthesis of living matter, 224
systematist, work of 237

T.

TADPOLE,
ascidian, 288, Fig. 132
frog, 283, Fig. 123
stage, 289, 290
tail,
in apes, 451
in man, 272, 273
tails, mutilation of, 206, 207
tapir, feet, 252, Fig. 98
tarsals, 248
Tarsius, 450
taxonomic tree, 239, 240, Fig. 88
taxonomy, 237
aims of, 240
teeth
of Cetacea, 328, 329, Figs. 161, 165
of dog and thylacine, 262—264, Figs. 109, 110
of elephants, 325
of horses, 320
vestigial, 271
Teleostei, 303
telescoping of generations, 111, 112, 122
temperature of body, 6
tentacles, 115, 118
Tertiary Era, 295, 296
testis, 113, 116
Tetrabelodon
angustidens, 325, Fig. 161
longirostris, 325, Fig. 161
Tetraxonida, spicules, 243, Figs. 90, 189
Theosodon, 264, Fig. 111
Theromorpha, 307
Thoatherium, 264, Fig. 111
Thomson, J. A., 164
thrum-eyed flowers, 367
thylacines, 311
Thylacinus, 262, Figs. 109, 110
tibia, 248
time,
geological, 294—298
importance in evolution, Buffon on, 377
in evolution of horse, 322
scale, geological, 295
Tinoceras, 314, 422, Fig. 152
Tintinnopsis, Fig. 9
tissue-formation, 45, 50, 51, 75—79
tissues, 37, 51—65
Tithorea harmonia, 356, Fig. 178
tools, use of, 452

torpedo, 267
tortoise, 345
Tower, W. L., 157—160
Tradescantia, histology of, 61—65, Figs. 25, 26
transfusion of blood, 208
transmission of characters, 196
transparency of pelagic animals, 333, 347
transplantation experiments, 208, 209
tree-like
  classification, 239, 240, Fig. 88
  evolution, 232, 444
Trematoda, parthenogenesis, 144
Triassic Epoch, 295
Triceratops, 308, Fig. 118
trichocysts, 39
Triconodon, 313
trilobites, 299, Fig. 136
Trimen, R., 357
Triticum sativum, Lamarck on, 389
Tritylodon, 312, 313
tuatara (*see Sphenodon punctatus*).
Tubularia, 121, Fig. 61
turbellarian, fertilization of polar body, 135
turbot, colour changes, 353
turtles,
  dispersal, 334
  limbs, 247, 255
twins, identical, 171
types, in wheat, 415
Tyndall, 223
Typhlopidæ, 261

U.

Ulna, 248
ultra-microscopic organisms, 227
unconscious memory, 216
ungulates, 312
  limbs of, 250—252
unguligrade, 251
unit characters, 180—186, 444
unstriped muscle, 57, Fig. 21
Urœotyphlus africanus, Fig. 108
uranium, 297, 298
urea, 9
Ursus arctos, systematic position, 240, Fig. 88
use and disuse, effects of, 156, 198
  Buffon on, 378—379
  Charles Darwin on, 402, 403
use and disuse, effects of—*continued*.
  Lamarck on, 388—393
  R. Chambers on, 396
uterus, 125

V.

Vacuoles, contractile, 39, 83
Varanus, shoulder girdle, 245, Fig. 91
variation, 148—160
  cause of, 157—160, 171, 198
  curve of, 150, 153, Figs. 72, 73
  in grape hyacinth, 150, Fig. 72
  in human stature, 152, Fig. 73
variations,
  blastogenic, 149, 157—160
  congenital, 157
  continuous, 148, 150
  discontinuous, 149, 153—156
  fluctuating, 148, 150, 155, Figs. 72, 73
  germinal, 149, 157—160
  individual, 150
  meristic, 148, 149
  normal, 150
  origin, 153, 171
  somatogenic, 149, 156, 157
  substantive, 148, 150
vasa deferentia, 125
vascular
  bundles, 65
  system in plants, 50
vegetable marrow, flowers, 111
vegetative cell in pollen grain, 108
Vergil, 222
vertebræ, meristic variation, 149
Vertebrata,
  evolution of air-breathing, 435
  geological history, 300—329
  origin, 302
Vespa crabro, Fig. 177
vestigial organs, 268—273, 282, 356, 407
  Charles Darwin on, 403
Virchow, 38
vitalism, 19, 228, 229
vitelline membrane, 140, 427, Fig. 70
volume,
  increase of, Lamarck on, 393
  relation to surface, 20

Volvox, 42, 91, 97, 98, 276, 435, Fig. 11
Von Baer, 276
Von Mohl, 38
Vorticella, 40, Fig. 9

W.

Waists, slender, 156
Walker, C. E., 173
Wallace, A. R., views of, 330, 340, 400—402, 404, 405, 445
warm-blooded animals, 6
warning colours, 353—359
wasps, colours, 353
waste products, 8, 9
wattles, life-history, 291
weapons, use of, 452
weeds, dispersal, 336
Wegener, 340
Weismann, views of, 146, 165—172, 186, 198—203, 227
weka, 407
Wells, W. C., 396
Western, 398
whales,
  ancestry, 325—329
  cervical vertebræ, 259, Fig. 105
  convergence in, 259
  paddles, 255, Fig. 103
  size, 314
  systematic position, 312
  vestigial organs in, 268, 271, Fig. 103
wheat,
  improvement of, 185, 414—416
  Lamarck on, 389
wind, dispersal by, 334
winged animals, dispersal of, 334
wings, 247
  convergence in, 259—261
  of bat, 254, Fig. 101
  of bird, 254, 255, Fig. 101
  of insects, 258
  of pterodactyls, 253, Fig. 101
Wolff, C. F., 163
wombats, 311
wood, 65
Woodward, A. S., 264, 305, 307, 312, 313, 450
worms, dispersal, 336

X.

Xylem, 65

Y.

Yolk, 140, 278, 431—433
  corpuscles, 117
  influence on development, 279—281
  sac, 281, 282, Fig. 122

Z.

Zeuglodontidæ, 329
zoæa larva, 287, Fig. 130
zona radiata, 140, 427, Fig. 71
zooids, 43, 119
zoophytes, 34, 119
zoospores, 29
Zoothamnium, 40
Zosterops lateralis, dispersal, 335
Zygogonium, conjugation, 97, 143
zygosis, 83, 131
zygospore, 97
zygote, 33, 83, 87, 88, 91, 97, 101, 105, 109, 118
  conjugation of nuclei in, 131, Fig. 64

PRINTED IN GREAT BRITAIN BY THE WHITEFRIARS PRESS, LTD., LONDON AND TONBRIDGE.

EXTRACTS FROM REVIEWS OF THE FIRST EDITION

Nature.—"It is all admirable, indeed, we do not know how it could be done better. It is packed with interesting material, old and new; the style is clear and vivid, yet the reader is continually being pulled up to think; there is a pleasant absence of dogmatism in regard to debated questions; there are numerous effective illustrations."

The Times.—"It may be doubted whether in the present state of our knowledge a much better book for its purpose could be written to cover the same field. . . . Professor Dendy writes with a good grasp of his subject and excellent sense of proportion. He is moreover lucid and easy to follow, while the illustrations are well chosen to help the reader over difficult places without being so numerous as to obstruct his path."

Cambridge Review.—"Professor Dendy has written a remarkably full and able account of the rapidly accumulating results of biological investigation. . . . We feel we can confidently recommend this book to any one who wishes to know what the leading thinkers in biological science, whether they agree with one another or whether they do not—and they generally do not—are occupying themselves with at the present day."

Times of India.—"Throughout, the book is so clearly and pleasantly written, and the diagrams and photographs so complete, that there is never the least obscurity. It forms delightful reading for any one interested in one of the problems which will last for all time."

Pall Mall Gazette.—"Any one wishing to tackle biology from its right end—which is the beginning—will hardly find a better and more patient guide than Professor Dendy."

Westminster Gazette.—"The main results attained by biological research should be part and parcel of the intellectual equipment not only of our specialising students but of all intelligent people. To supply their requirements, to give a brief presentation of the evidence for organic evolution, to exhibit the factors co-operating in the course of that evolution—this is the task which Professor Dendy has set before himself, and it is one which he has discharged with conspicuous success."

Cape Times.—"An absorbingly interesting portion of the work is where the author enters upon the story of the stratified rocks—the geological periods. . . . It has not been possible to more than glance at the vast mass of material, rich in biological facts, which the late Professor of Zoology in the South African College has accumulated in this distinguished work, and which must make it so valuable a contribution to the science of biology."

Morning Post.—"It will be generally granted that Professor Dendy has done his work well, that he has written a very readable book, and that when he deals with controversial matters he has presented very fairly the views of opposing schools of thought."

Scotsman.—"It provides as competent a survey of the field of biology as the reader is likely to find outside specialised manuals, and students who are taking up the subject for professional reasons will find it helpful as well as the inquirer who is led to investigate the subject through disinterested scientific curiosity."

The Lancet.—"We welcome this interesting, erudite, suggestive, and withal fascinating account of evolutionary biology."

University Extension Bulletin.—"Those who wish to familiarise themselves with the fundamental facts and principles of the science of living things will appreciate the book very highly, and the author is to be congratulated on the success with which he has accomplished a difficult task."

Athenæum.—"The author brings to his task peculiar advantages, inasmuch as he has studied life in many distant parts, having held professorships of biology and zoology in New Zealand and South Africa. . . . Professor Dendy furnishes in this work an excellent summary of the fundamental facts and principles on which the theory of organic evolution is based."

Glasgow Herald.—"This is altogether a most valuable book, that will be of great service to all students of the world of life."

Knowledge.—"The whole subject is treated in a manner which should render the volume acceptable both to the beginner and to the student who has had some previous training; the freedom from unnecessary technicalities being a welcome feature. Among many interesting items, we have been specially enthralled by Professor Dendy's account of a peculiar organ in the head of a frog, which represents the last remnant of an unpaired pineal eye. We confess our own previous ignorance of the existence of such a structure in this well-known animal, but console ourselves by the thought that there are probably others who were in the same boat until they had read the many marvels revealed in Professor Dendy's excellent volume."

Montreal Gazette.—"To the lover of accurate knowledge of the ways and works of nature, this book must be intensely fascinating."

British Medical Journal.—"A book which is likely to be welcomed by a large number of readers. It fills a gap which has long been waiting to be filled, and the author is to be congratulated upon the success he has achieved by this work. It is well and lucidly written."

Oxford Magazine.—"No other single volume in the English language gives such a complete yet condensed account of the vast amount of work done in recent years bearing on the more general principles of the subject. . . . The treatment is throughout clear and systematic, and the illustrations are both good and numerous. This work may safely be recommended as containing a vast amount of accurate information in a small compass."

Eugenics Review.—"Professor Dendy gives a brief but admirable summary of recent evolutionary work upon heredity and the transmission of acquired characters, upon Mendelism and mutation, and on mimicry in insects."—(PROFESSOR POULTON.)

Spectator.—"In this volume Professor Dendy has succeeded in producing an enthrallingly interesting book for the student who is bent on advancing along those long-stretching avenues down which he must travel before he can add even an iota to the sum of scientific knowledge. Professor Dendy is indeed to be congratulated upon so readable, so lucid, and at the same time so profound an exposition of his subject. The illustrations, it may be noted, are numerous and exceedingly clear and adequate."